

Clovis East High School Soccer Stadium- Sewer Improvements Scope of Work

Furnish and install all work necessary for a fully functional sewer system in accordance with the plans and specifications including but not limited to the following items:

Layout and marking of new sewer line path and limits of demolition, excavation and placement of new sewer lines, potholing and identifying existing utilities, relocating existing utilities conflicting with new sewer line, cutting and capping new and existing sewer line, re-channeling manholes, new manholes, point of connection of new sewer line to existing sewer, construction of new manhole on existing RCP line including removal of portion of (e) 48" RCP, installation of all cleanouts, backfill & compaction of trenches, off haul of excess spoils generated by sewer line work.

Note: All Saw cutting, Demolition, Landscape and Irrigation, new Concrete flatwork, Asphalt Patch, Chain link Fencing, reinstallation of salvaged bollards and Construction Staking is not to be included in the bid and will be performed by the owner.