
EUGENE SCHOOL DISTRICT

850 HOWARD EUGENE, OREGON 97404

REVIEW SET 5.21.2014



VICINITY MAP



SITE DETAILS

MISC. DETAILS

MISC. DETAILS

E101 FIELD LIGHTING PLAN

RESOURCE BUILDING

RESOURCE BUILDING

E102 ELEC ROOM PLAN, SCHEDULE

A062

A071

A082

DOUGLAS FIR, DRINKING FOUNTAIN

EQUAL EACH WAY EXTERIOR FLOOR DRAIN FIRE EXTINGUISHER FIRE EXTINGUISHER CABINET FINISH FLOOR FINISH/FINISHED **FLOOR** FACE OF FIBER REINFORCED PANEL

GAUGE **GRAB BAR** GLUE LAM BEAM HANDRAIL HOLLOW METAL INSULATION INTERIOR

ARCHITECTURAL

ABBREVIATIONS

ACOUSTIC

ALUMINUM BUILDING **BOTTOM OF**

CLEAR

COLUMN CONCRETE

DOUBLE

DIAGONAL

DIAMETER DISPENSER

DOWNSPOUT DETAIL

EXPANSION JOINT ELEVATION ELECTRICAL

DRAWING **EXISTING**

CONTINUOUS CARPET

CONTROL JOINT CENTER LINE CEILING

CONCRETE MASONRY UNIT

DEMOLITION/DEMOLISH

ACT

ALUM

CLR CMU COL CONC

CONT CPT

DBL DEMO

DWG

HM

OPP

PTD

PLY

RB

RD

RO ROW RUB

VFY

WA

WD

P LAM

ANCHOR BOLT ASPHALTIC CONCRETE

ACOUSTICAL TILE CEILING SYSTEM

CONTRACTOR FURNISHED/CONTRACTOR INSTALLED

INSUL INT KNOCK DOWN LAVATORY LOC LOCATION MAX MAXIMUM MECH MECHANICAL MFR MANUFACTURER MIN MINIMUM MISC MISCELLANEOUS MTL METAL NTS NOT TO SCALE

ON CENTER OUTSIDE DIMENSION OD OWNER FURNISHED CONTRACTOR INSTALLED OFCI OWNER FURNISHED OWNER INSTALLED OFOI OUTSIDE FACE OF STUD OFS OH OPPOSITE HAND OPNG OPENING

> PLASTIC LAMINATE PAINT SYSTEM PRESSURE TREATED PAINTED PLYWOOD RADIUS RUBBER BASE **ROOF DRAIN** ROOM ROUGH OPENING RIGHT OF WAY RUBBER STORM DRAIN

OPPOSITE

SD SECT SHT SECTION SHEET SIM SIMILAR SPECS **SPECIFICATIONS** SQFT, SF SQUARE FOOT S STL STD STAINLESS STEEL STANDARD STL STEEL STRUC STRUCTURAL T&B TOP & BOTTOM T&G TEMP TONGUE AND GROOVE TEMPERED, TEMPORARY TO TOC TOW TOS TYP UNO TOP OF TOP OF CONCRETE TOP OF WALL

TOP OF STRUCTURE TYPICAL UNLESS NOTED OTHERWISE WALL ASSEMBLY WOOD

WATER PROOF

ARCHITECTURAL SYMBOLS

EXISTING KELLY MS

A201 ■ 3	BUILDING ELEVATION	ROOM NAME	ROOM NAME & NUMBER
1 4 A411 2	INTERIOR ELEVATION	A	WINDOW SYMBOL
3		A	STOREFRONT SYMBOL
1 A301	BUILDING SECTION	101 A	DOOR SYMBOL
1 A301	WALL SECTION	9'-0"	CEILING HEIGHT SYMBOL
		(1-M3-2 06)	WALL ASSEMBLIES
1 A321	DETAIL CALLOUT	05 5000-A ———	SPECIFICATION KEYNOTE
<u></u>		<u></u>	KEYNOTE
TYP A511	DETAIL SECTION	•	VERTICAL ELEVATION

PROJECT TEAM

<u>OWNER</u>

NEW TRACK AND FIELD

EUGENE SCHOOL DISTRICT 715 W. 4th AVENUE EUGENE, OR 97402 PHONE: (541) 790-7417 FAX: (541) 790-7420 CONTACT: DON PHILPOT

ARCHITECT OF RECORD

PIVOT ARCHITECTURE PC 44 WEST BROADWAY, SUITE 300 EUGENE, OR 97401 PHONE: (541) 342-7291 FAX: (541) 342-1535 CONTACT: CURT WILSON

CIVIL ENGINEER

BALZHISER & HUBBARD ENGINEERS 100 W 13TH AVENUE, #100 EUGENE, OR 97401 PHONE: (541) 686-8478 FAX: (541) 345-5303 CONTACT: MONICA ANDERSON

LANDSCAPE ARCHITECT

CAMERON MCCARTHY LANDSCAPE ARCHITECTS 160 EAST BROADWAY EUGENE, OR 97401 PHONE: (541) 485-7385 FAX: (541) 485-7389 CONTACT: MATT SCHEIBE

INDEX OF DRAWINGS

GENERA	AL .	
A000	TITLE SHEET	
G021	TOPOGRAPHICAL SURVEY - WEST	(FOR REFERENCE ONLY)
G022	TOPOGRAPHICAL SURVEY - EAST	(FOR REFERENCE ONLY)
LANDSC	CAPE	
D200	IRRIGATION DEMO PLAN	
L100	IRRIGATION PLAN	
L200	IRRIGATION DETAILS	
CIVIL		
C101	EROSION AND SEDIMENT CONTROL P	LAN
C102	EDOSION AND SEDIMENT CONTROL N	OTES

C102 EROSION AND SEDIMENT CONTROL NOTES **EROSION AND SEDIMENT CONTROL DETAILS** HORIZONTAL CONTROL PLAN C122 HORIZONTAL CONTROL TABLES C131 **GRADING PLAN** C141 STORM DRAIN PLAN

PAVING PLAN CIVIL DETAILS, GENERAL NOTES AND LEGENDS CIVIL DETAILS, GENERAL NOTES AND LEGENDS

DEMOLITION

D100 EXISTING SITE DEMOLITION PLAN

A051 PARTIAL SITE PLAN

ARCHITECTURE A050 OVERALL SITE PLAN

A052 FIELD DIAGRAMS A061 SITE DETAILS

MIDD

TOPOGRAPHICAL SURVEY - WEST (FOR REFERENCE (

BALZHISER & Hubbard

Engineers

MECHANICAL
ELECTRICAL
CIVIL
SURVEYORS

100 WEST 13TH AVENUE EUGENE, OR 97401

/PROFESSIONAL

EXPIRES DECEMBER 31, 2014


4

4J SCHOOL DISTRICT LYING IN SW 1/4 OF SEC. 14 TOWNSHIP 17S, RANGE 4W, W.M.


CITY OF EUGENE LANE COUNTY, OREGON **SEPT 2013**


TOPOGRAPHIC SURVEY

FOR




43 | 122818.47 | 171604.16 | 395.63 | SET BRASS CAF





SCALE: 1"= 40'



- 12"FL= 394.02 ___12"FL= 394.33

RIM= 395.86 8" INV S= 393.74 8" INV W= 393.70

SD MH RIM = 396.68 10" INV N = 390.53

RAMP WITH RAIL -

RIM= 396.99 8" INV E= 392.40

8" I:\V W= 392.41

KELLY MIDDLE SCHOOL

SS MH RIM= 397.31 2-8" INV E= 391.77 10" INV W= 391.91

- OHE OHE OHE OHE OHE OHE OHE

SD AD SQ---

SC #42

BACKSTOP

THE 399

RIM= 395.12 3" INV N= 394.57

- 1. THE BENCHMARK USED FOR THIS SURVEY WAS CITY OF EUGENE BENCHMARK RR0899 WITH A PUBLISHED ELEVATION OF 395.68' (NAVD 88 DATUM).
- THIS SURVEY IS BASED UPON THE OREGON COORDINATE REFERENCE SYSTEM, EUGENE ZONE. ALL DISTANCES ARE GROUND DISTANCES AND ARE EXPRESSED IN INTERNATIONAL FEET. SEE SURVEY METADATA FOR MORE INFORMATION.
- 3. THE EXTERNAL BOUNDARY WAS HELD AS SHOWN ON LANE COUNTY SURVEY NO. 31670.
- UNDERGROUND UTILITIES SHOWN HEREON ARE BASED UPON ABOVE GROUND VISIBLE EVIDENCE ALONG WITH LOCATE MARKS AND RECORD INFORMATION. RECORD INFORMATION IS NOTED AS SUCH ON THE DRAWING. THE ACCURACY OF UNDERGROUND LOCATES AND RECORD INFORMATION MAY VARY. CRITICAL UTILITY LOCATIONS SHOULD BE EXPOSED AND LOCATED FOR HIGHEST ACCURACY.
- THE SUBJECT PROPERTY IS SUBJECT TO THE FOLLOWING DEED MATTERS LISTED IN A TITLE REPORT FROM FIRST AMERICAN TITLE COMPANY OF OREGON, WITH A DATE OF

SCHOOL DISTRICT 4J, LANE COUNTY, OREGON, A MUNICIPAL CORPORATION

AUGUST 2, 2013, ORDER No. 7199-2132015:

A. EASEMENT INCLUDING THE TERMS AND PROVISIONS THEREOF, IN FAVOR OF THE CITY OF EUGENE, AS RECORDED ON JULY 26, 1968, AS RECEPTION No. 33168. THIS EASEMENT IS SHOWN HEREON.

SITE INFO

LANE COUNTY DEED BOOK 291, PAGE 366

KELLEY MIDDLE SCHOOL 850 HOWARD AVE, EUGENE OR 97404 HOWARD ELEMENTARY SCHOOL

SURVEY METADATA

700 HOWARD AVE.

EUGENE OR 97404

INTERNATIONAL FOOT LINEAR UNIT: NORTH AMERICAN DATUM OF 1983 (2011) EPOCH2010 GEODETIC DATUM: OREGON COORDINATE REFERENCE SYSTEM ZONE: PROJECTION: TRANSVERSE MERCATOR 43°45'00" N LATITUDE OF GRID ORIGIN: 123°10'00" W CENTRAL MERIDIAN: FALSE NORTHING: 0.000 m 50000.000 m FALSE EASTING:

CENTRAL MERIDIAN SCALE: 1.000015 (EXACT)

ALL DISTANCES AND BEARINGS SHOWN HEREON ARE GRID VALUES BASED ON THE PROCEEDING PROJECTION DEFINITION. THE BASIS OF BEARINGS IS GEODETIC NORTH. NOTE THAT THE GRID BEARINGS SHOWN HEREON (OR IMPLIED BY GRID COORDINATES) DO NOT EQUAL GEODETIC BEARINGS DUE TO MERIDIAN CONVERGENCE.

FILENAME 3900-02-13 TOPO.dwg SHEET No.

SHEET <u>1</u> OF <u>2</u>

G021

RIM= 394.18 8" INV W = 382.05 8" INV S = 381.92 8" INV N = 381.85

RIM= 394.22 8" INV E= 387.50

HIM= 394.90 8" INV N= 389.88 8" INV S= 390.46

ASPHALT RIM= 397.17

SD CB RIM= 396.81 6" INV W= 394.83 SUMP= 392.81

OVERHANG

SEAT WALL

PLANTERS

APPROX. LOCATION OF

EWEB EASEMENT PER

RECEPTION NO. 33168

KELLY MIDDLE SCHOOL

10" INV S= 391.38 SUMP = 379.77

RIM = 397.06

10" INV SW = 392.71 SUMP = 384.31

RIM = 397.09

TRASH COMPACTOR

10" INV NE = 392.38


SUMP = FULL OF DEBRIS

SD CB RIM= 396.77 4" INV W= 394.79

RIM= 394.81 8" INV SW= 389.86 SUMP = 382.90

RIM= 395.38 8" INV N= 390.36 8" INV S= 390.94 SUMP = 382.09

RIM= 395.48 6" INV N= 393.50 SUMP = 391.48



HAWTHORN PLACE SUBDIVISION BALZHISER PUBLIC SS-8" INV N= 381.07 15" INV E= 381.07 & Hubbard Engineers PUBLIC SD-RIM= 395.36 RIM= 395.16 SD AD SQ RIM= 395.37 12" INV N= 391.42 6" INV S= 389.87 MECHANICAL
ELECTRICAL
CIVIL
SURVEYORS RIM= 394.85 10" INV N= 391.20 12" INV E= 389.72 12" INV W= 390.29 /RIM= 395.79 ₩ 8" INV S= 386.73 12" INV N= 389.67 8" INV S = 381.68 SD AD SQ RIM= 395.52 6" INV E= 394.32 SUMP= 392.52

SD AD SQ RIM= 395.21 6" INV N= 394.01 100 WEST 13TH AVENUE EUGENE, OR 97401 **PLAN SCALE** 6" INV E= 394.14 SUMP= 392.34 SCALE: 1"= 40' PROFESSIONAL SD AD SQ-**SYMBOL LEGEND** ≤ RIM= 395.12 3" INV N= 394.57 SUMP= 392.97 RIM= 395.74 RIM= 396.14 8" INV S= 390.33 8" INV W= 386.96 EXPIRES DECEMBER 31, 2014 8" INV E= 390.25 12 RIM= 395.51 8" INV E= 392.26 FIRE DEPARTMENT CONNECTION **HOWARD ELEMENTARY** 8" INV E= 391.25 8" INV W= 391.23 ADA PARKING AREA DRAIN (SQUARE) COVERED BREEZE WAY STORMDRAIN MANHOLE CONIFEROUS TREE UTILITY POLE HOWARD ELEMENTARY 8" INV W= 393.11 8" INV S= 382.48 **GUY ANCHOR** BROADLEAF TREE AREA LIGHT POLE COMMUNICATIONS → CONCRETE PAD. CORRUGATED METAL PIPE ELECTRIC METER ELECTRIC RISER SANITARY SEWER COVERED ELECTRIC TRANSFORMER ROOF ENTRANCE — — ⊢HANDRAIL **TELEPHONE RISER** HEAT PUMP JUNCTION BOX SEWER MANHOLE ARBORVITAE © CLEANOUT -BASEBALL BACKSTOP METAL POST METAL BASKETBALL HOOP POLE RIM = 396.58 4" INV E = 395.45 WOOD FENCE PLAY AREA & STRUCTURES SET PERMANENT SITE CONTROL (SC) REFER TO DETAIL AND BENCHMARK TABLE WOOD CHIPS & GRASS FOUND CITY BENCHMARK (BM) _____ OUT BUILDING 1 *∟SC #42* GRAVEL TRACK WOODEN WALL HATCH DENOTES BUILDING SC #43 ─\ Bandanaranaranan dalam bandaran bandaran bandaran bandaran bandaran bandaran bandaran bandaran bandaran bandar HATCH DENOTES BUILDING OVERHANG HATCH DENOTES ASPHALT PAVEMENT HATCH DENOTES CONCRETE HATCH DENOTES GRAVEL PAVEMENT PAINT STRIPE CONCRETE PAD-\ ---- w ------ Underground water line ----- UNDERGROUND STORMDRAIN LINE SOCCER GOAL — ss ———— UNDERGROUND SANITY SEWER LINE ---- UNDERGROUND GAS LINE COMM ———— UNDERGROUND COMM LINE OVERHEAD COMBINED UTILITY LINE DATE STORM DRAIN STRUCTURE TABLE BACKSTOP ISSUED: 09/10/2013 FENCE OPENING-\ SD CB 1 SD CB 11 LAST REVISION: 09/18/2013 SD CB 6 RIM = 396.78 RIM = 397.04RIM = 396.926" INV E = 394.93 4" INV S = 396.29 4" INV S = 396.17 SUMP = 393.58 SUMP = 395.99 SUMP = 395.87DRAFTING FIELD GRAVEL TRACK BASEBALL BACKSTOP-SD CB 2 JSM / ASD APD/HDM RIM = 397.00 RIM = 396.66RIM = 397.03FENCE OPENING 4" INV W = 396.25 4" INV S = 395.41 4" INV S = 396.28 SUMP = 395.95 SUMP = 3.46SUMP = 395.98PROJECT SD CB 8 SD CB 13 SD CB 3 3900-002-13 RIM = 397.11RIM = 396.69RIM = 396.57 4" INV N = 396.36 4" INV W = 395.44 4" INV S = 395.32 SUMP = 393.37 SUMP = 396.06SUMP = 393.49FILENAME SD CB 4 SD CB 9 SD CB 14 3900-02-13 TOPO.dwg RIM = 397.08 RIM = 396.98RIM = 396.464" INV N = 396.33 4" INV W = 396.23 4" INV E = 395.21 SUMP = 396.03 SUMP = 395.48 SUMP = 393.26





TOPO

SHEET No.

S

SHEET <u>2</u> OF <u>2</u>

SD CB 5

RIM = 397.17

4" INV W = 396.42 SUMP = 396.12

SD CB 10

RIM = 396.884" INV E = 396.13

SUMP = 395.83

SD CB 15


RIM = 397.13


4" INV S = 395.42


4" INV N = 395.41


TOPOGRAPHICAL SURVEY - EAST (FOR REFERENCE (

G022









DEVELOPER/OWNER

EUGENE SCHOOL DISTRICT 715 W. 4TH AVE. EUGENE, OR 97402 PHONE: 541-790-7417 FAX: 541-790-7420

ENGINEERING/SURVEYING FIRM

BALZHISER & HUBBARD ENGINEERS CONTACT: MONICA ANDERSON

100 W 13TH AVE 1001 SW 5TH AVE., SUITE 1100 EUGENE, OR 97401 PORTLAND, OR 97204 PHONE: 541-686-8478 PHONE: 503-961-6440 FAX: 541-345-5303 FAX: 541-345-5303

NARRATIVE DESCRIPTIONS

SITE CONSISTS OF 23.1 ACRES OF DEVELOPED LAND WITH SLOPES RANGING FROM 0 TO 3 PERCENT. THE EXISTING VEGETATION IS MADE UP OF TREES, SHRUBS, AND VARIOUS GRASSES.

<u>DEVELOPED CONDITIONS</u>
ATHLETIC FIELD AND TRACK WITH VEHICLE AND PEDESTRIAN ACCESS DISTURBING 3.6 ACRES.

(PER SOIL SURVEY OF LANE COUNTY AREA, OREGON) 76 MALABON-URBAN LAND COMPLEX, DEEP AND WELL DRAINED.

A1 CHANNEL VIA LANE COUNTY OWNED PIPED STORM DRAINAGE.

GENERAL EROSION SEDIMENTATION CONTROL (ESC) NOTES

STOCK PILES OF NATIVE SOILS AND/OR FILL MATERIALS SHALL NOT BE EXPOSED TO THE WEATHER WITHOUT PROVISIONS OF SECONDARY CONTAINMENT AND TREATMENT MEASURES AS OUTLINED BELOW.

- 2. SECONDARY CONTAINMENT SHALL CONSIST OF INSTALLED BIO BERM AND/OR CONTAINMENT DITCH AT TOE OF SLOPE AROUND STOCKPILE PERIMETER. BERM AND/OR DITCH SHALL BE OF SUFFICIENT SIZE TO CONTAIN STOCKPILED MATERIALS IN PLACE.
- 3. STOCK PILES ON SITE DURING WET WEATHER SEASON (OCTOBER 15 THROUGH APRIL 30) SHALL BE COVERED WITH 6 MIL (MIN. THICKNESS) POLYETHYLENE PLASTIC SHEETING. SHEETING SHALL BE INSTALLED AND MAINTAINED TIGHTLY IN PLACE USING APPROVED ANCHORING SYSTEM ON A 10' (MAX) GRID SPACING IN ALL DIRECTIONS. ALL SEAMS BETWEEN ADJACENT SHEETS SHALL BE LAPPED 12" (MIN) AND TAPED OR WEIGHTED DOWN FULL LENGTH OF SEAM. FOR SEAMS PARALLEL TO THE SLOPE CONTOUR, THE UPHILL SHEET SHALL OVERLAP THE DOWNHILL SHEET. NO RUNOFF SHALL BE ALLOWED TO RUN UNDER THE PLASTIC COVERING.
- DEMOLITION AND/OR CONSTRUCTION DEBRIS, WASTE AND GARBAGE PILES OR CONSTRUCTION MATERIALS CONTAINING TOXIC CONTAMINANTS SHALL NOT BE PLACED WITHIN 25 FEET OF ANY NATURAL DRAINAGE FEATURE, STORM DRAIN INLET STRUCTURE OR DESIGNATED PROTECTED AREA.
- LOCATION OF CONSTRUCTION MATERIAL STORAGE AREAS AND DEBRIS, WASTE AND GARBAGE PILE AREAS SHALL BE PROVIDED BY THE CONTRACTOR TO THE CITY AT THE TIME OF THE INITIAL ESC CONTROL INSPECTION.

- PROVIDE MINIMUM OF ONE CONCRETE TRUCK WASH AREA FOR USE ON CLEANING OF DEPARTING CONCRETE TRUCKS.
- 2. CONCRETE TRUCK WASH AREAS SHALL BE LOCATED ADJACENT TO ANY CONSTRUCTION ENTRANCE USED BY DEPARTING CONCRETE TRUCKS.
- CONCRETE TRUCK WASH AREAS SHALL BE CONSTRUCTED OF ONE OF THE FOLLOWING: STRAW BALE BARRIER WITH PLASTIC LINER.
- STACKED SAND BAGS OR BIO-BAGS AS A BARRIER WITH PLASTIC LINER.
- C. PORTABLE CONTAINMENT POND.
- 4. SUGGESTED LOCATIONS OF CONCRETE TRUCK WASH AREA(S) ARE SHOWN ON THE EROSION SEDIMENTATION CONTROL PLAN, SHEET C101.
- LOCATION OF CONCRETE TRUCK WASH AREA(S) SHALL BE PROVIDED BY THE CONTRACTOR TO THE CITY AT THE TIME OF THE INITIAL ESC INSPECTION. STABILIZED CONSTRUCTION ENTRANCE

STABILIZED CONSTRUCTION ENTRANCE(S) SHALL BE ESTABLISHED AS SOON AS POSSIBLE AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED FOR THE DURATION OF THE PROJECT IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT INTO PUBLIC RIGHT--OF-WAY. EXISTING PAVED ACCESS MAY BE USED AS CONSTRUCTION ENTRANCE AS NOTED ON SHEET C101,

- 2. ADDITIONAL ROCK SHALL BE ADDED PERIODICALLY, IF NECESSARY, TO MAINTAIN PROPER FUNCTION OF THE PAD.
- INSTALL VEHICLE BARRIERS AT ANY SITE ENTRANCE NOT USED AS STABILIZED CONSTRUCTION ENTRANCE TO RESTRICT SITE ACCESS.
- IF ESTABLISHED ENTRANCES DO NOT ADEQUATELY REMOVE DIRT AND MUD FROM VEHICLE WHEELS SUCH THAT MUD AND DIRT TRACKING IS EVIDENT OFF SITE, ADDITIONAL MEASURES MUST BE TAKEN. SUCH MEASURES MAY INCLUDE WHEEL WASHING BEFORE VEHICLES LEAVE THE SITE OR OTHER CONSTRUCTION TECHNIQUES/WORK OPERATION MODIFICATIONS.
- WHEEL WASHING SHOULD BE DONE ON THE GRAVEL PAD AND WASH WATER SHOULD DRAIN THROUGH A SILT-TRAPPING STRUCTURE PRIOR TO LEAVING THE CONSTRUCTION SITE. REFER TO DETAIL 2/C103, TRUCK
- IT IS THE CONTRACTOR'S RESPONSIBILITY TO CLEAN UP ANY SEDIMENT/MUD TRACKED INTO ADJACENT RIGHT-OF-WAY.

- ILOPE STABILIZATION

 EXPOSED CUT OR FILL AREAS SHALL BE STABILIZED THROUGH THE USE OF TEMPORARY SEEDING AND MULCHING, EROSION CONTROL BLANKETS OR MATS, MID-SLOPE SEDIMENT FENCES OR WATTLES, OR OTHER APPROPRIATE MEASURES. SLOPES EXCEEDING 25% MAY REQUIRE ADDITIONAL EROSION CONTROL MEASURES.
- TEMPORARY SLOPE STABILIZATION MEASURES MAY INCLUDE COVERING EXPOSED SOIL WITH PLASTIC SHEETING. INSTALLATION OF STRAW MULCHING AND/OR WOOD CHIPS, OR OTHER APPROVED MEASURES.
- LONG TERM SLOPE STABILIZATION MEASURES SHALL INCLUDE THE ESTABLISHMENT OF PERMANENT VEGETATIVE COVER VIA SEEDING WITH APPROVED SEED MIX AND APPLICATION RATE.

INSTALL BASIN INSERT BAGS OR CURB INLET SEDIMENT DAMS AT ALL INLET STRUCTURES.

- ALL SAW-CUTTING SLURRY MUST BE VACUUMED IMMEDIATELY AND DISPOSED OF OFF-SITE.
- THE FOLLOWING WERE REVIEWED AND DO NOT PERTAIN TO THIS PROJECT: A. THERE ARE NO NATURAL RESOURCE SITES. B. THERE ARE NO BORROW SITES.
- C. THERE ARE NO CONSERVATION ZONES.
- REFER TO LANDSCAPE PLANS FOR PERMANENT VEGETATION.
- SITE WORK WILL BE COMPLETED IN A SINGLE PHASE.
- EXPECTED TIME PERIOD OF LAND DISTURBING ACTIVITIES IS 4 MONTHS.

ALL ESC MEASURES WILL BE COMPLETED IN A SINGLE PHASE.

SCHEDULE FOR CONSTRUCTION AND IMPLEMENTATION OF ESC CONTROLS

- HOLD THE PRE-CONSTRUCTION MEETING.
- 2. FLAG OR FENCE CLEARING LIMITS (AS STATED ON THE APPROVED PLANS).
- INSTALL ESC MEASURES PRIOR TO CONSTRUCTION.
- CALL TO SCHEDULE AN ON-SITE INSPECTION OF ALL EROSION MEASURES AFTER INSTALLATION AND PRIOR TO COMMENCING SOIL DISTURBANCE OPERATIONS.
- MAINTAIN ESC MEASURES IN ACCORDANCE WITH CITY OF EUGENE STANDARDS AND MANUFACTURER'S
- PERFORM DAILY INSPECTIONS OF THE ESC FACILITIES AND MAINTAIN WRITTEN RECORDS OF INSPECTIONS.
- UPDATE EROSION AND ESC MEASURES TO HANDLE MAJOR CHANGE IN SITE CONDITIONS.
- COVER ALL AREAS THAT WILL BE UNWORKED FOR MORE THAN SEVEN DAYS DURING THE DRY SEASON OR TWO DAYS DURING THE WET SEASON WITH STRAW, WOOD FIBER MULCH, COMPOST, PLASTIC SHEETING, OR EQUIVALENT.
- STABILIZE ALL AREAS WITHIN SEVEN DAYS OF REACHING FINAL GRADE.
- 10. SEED OR SOD ANY AREAS TO REMAIN UNWORKED FOR MORE THAN 30 DAYS.
- SWEEP STREETS ADJACENT TO CONSTRUCTION ENTRANCES A MINIMUM OF ONCE PER WEEK. USE OF WATER TRUCKS TO WASH DOWN STREETS IS NOT ALLOWED AFTER BEGINNING OF PAVEMENT PLACEMENT.
- 12. UPON COMPLETION OF THE PROJECT, STABILIZE ALL DISTURBED AREAS AND REMOVE BMP'S IF APPROPRIATE.

CITY OF EUGENE CONSTRUCTION SITE MANAGEMENT PLAN (CSMP) NOTES

- PRIOR TO ANY GROUND DISTURBANCE ON THE SITE ONE INSPECTION WITH EROSION PREVENTION STAFF IS REQUIRED.
- 2. THE CONSTRUCTION SITE MANAGEMENT PLAN DOES NOT AUTHORIZE CONSTRUCTION ACTIVITIES. GRADING, BUILDING, PEPI, AND OTHER PERMITS MAY BE REQUIRED. ALL OTHER NECESSARY APPROVALS SHALL BE OBTAINED.
- ISSUANCE OF AN EROSION PREVENTION PERMIT APPROVES PROTECTION MEASURES, NOT CONSTRUCTION OR GROUND DISTURBING ACTIVITIES. IT DOES NOT RELIEVE THE PERMIT HOLDER AND/OR THE CONTRACTOR FROM OTHER PERMITTING REQUIREMENTS.
- CONSTRUCTION SHALL CONFORM TO THE CURRENT EDITION OF THE CITY AMENDED OREGON STANDARD SPECIFICATIONS FOR CONSTRUCTION AND CITY STANDARD DRAWINGS* (*REQUIRED FOR PUBLIC IMPROVEMENT PROJECTS ONLY).
- EROSION AND SEDIMENT CONTROL MEASURES, AND OTHER NATURAL RESOURCE PROTECTION FENCING AND BARRIERS, SHOWN ON THE CSMP ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING CONSTRUCTION. MEASURES SHALL BE UPGRADED, AS NEEDED OR AS DIRECTED BY THE CITY INSPECTOR.
- IMPLEMENTATION OF THE CSMP, INCLUDING CONSTRUCTION, MAINTENANCE, REPLACEMENT, AND UPGRADING OF EROSION AND SEDIMENT CONTROL MEASURES AND PROTECTION FENCING, IS THE RESPONSIBILITY OF THE PERMIT HOLDER AND/OR THE CONTRACTOR UNTIL ALL CONSTRUCTION IS COMPLETED AND VEGETATION/LANDSCAPING IS ESTABLISHED AND
- BOUNDARIES OF THE CLEARING AND GRADING LIMITS SHOWN ON THIS PLAN SHALL BE CLEARLY FLAGGED IN THE FIELD PRIOR TO CONSTRUCTION. DURING CONSTRUCTION, NO DISTURBANCE BEYOND THE FLAGGED CLEARING AND GRADING LIMITS SHALL BE PERMITTED. THE FLAGGING SHALL BE MAINTAINED BY THE PERMIT HOLDER AND/OR THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION. IN ADDITION, WETLAND AND RIPARIAN AREAS SHALL BE IDENTIFIED AND PROTECTED WITH APPROPRIATE FENCING AS NOTED ON CSMP PRIOR TO CONSTRUCTION AND SHALL NOT BE DISTURBED UNLESS THE PROPER PERMITS ARE OBTAINED.
- EROSION AND SEDIMENT CONTROL MEASURES SHOWN ON THIS CSMP MUST BE CONSTRUCTED IN CONJUNCTION WITH ALL CLEARING AND GRADING ACTIVITIES, IN SUCH A MANNER AS TO ENSURE THAT SEDIMENT AND SEDIMENT LADEN WATER DOES NOT ENTER THE STORMWATER SYSTEM, ROADWAYS, ADJACENT PROPERTY OR VIOLATE APPLICABLE WATER QUALITY STANDARDS. WHEN DESIGNING AND IMPLEMENTING MEASURES, THE PERMIT HOLDER AND/OR THE CONTRACTOR SHALL CONSIDER THE SEASONAL VARIATION OF RAINFALL, TEMPERATURE, AND OTHER CLIMATIC FACTORS RELATIVE TO THE TIMING OF LAND DISTURBANCE ACTIVITIES.
- EROSION AND SEDIMENT CONTROL MEASURES ON ACTIVE SITES SHALL BE INSPECTED AND MAINTAINED DAILY AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCHES OF RAIN PER 24 HOUR PERIOD. ANY REQUIRED REPAIRS OR ADJUSTMENTS SHALL BE MADE IMMEDIATELY. THE EROSION AND SEDIMENT CONTROL MEASURES ON INACTIVE SITES SHALL BE INSPECTED A MINIMUM OF ONCE EVERY MONTH AND/OR WITHIN 48 HOURS FOLLOWING STORM EVENTS. ADDITIONALLY, SITES COVERED UNDER DEPARTMENT OF ENVIRONMENTAL QUALITY (DEQ) PERMITS (1200-C, 1200-CN) MUST COMPLY WITH THOSE PERMIT MONITORING AND RECORD-KEEPING REQUIREMENTS.
- 10. DURING THE WET WEATHER SEASON (OCTOBER 15 TO APRIL 30), ALL EXPOSED SOIL AND STOCKPILE AREAS SHALL BE COVERED. OR OTHERWISE PROTECTED BY A FACILITY (OR COMBINATION OF FACILITIES) THAT RESULT IN NO STORMWATER RUNOFF LEAVING THE SITE DURING A 5-YEAR STORM EVENT. FOR DEVELOPMENT SITES OVER 40 ACRES, THE DESIGN STORM SHALL BE A 10-YEAR STORM EVENT CONSISTENT WITH AN APPROVED CSMP.
- ALL ADJACENT PROPERTIES, WATER FEATURES, AND RELATED NATURAL RESOURCES ARE TO BE KEPT FREE OF DEPOSITS OR DISCHARGES OF SOIL, SEDIMENT OR CONSTRUCTION-RELATED MATERIAL FROM THE CONSTRUCTION SITE.
- 12. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE PROTECTED FROM DAMAGE AT ALL TIMES. EROSION CONTROL MEASURES SHALL REMAIN IN PLACE UNTIL VEGETATION HAS BEEN ESTABLISHED AND THE SITE IS PERMANENTLY STABILIZED. ANY MEASURES THAT ARE DAMAGED OR DESTROYED SHALL BE REPAIRED OR REPLACED IMMEDIATELY.
- STABILIZE ALL DISTURBED AREAS WITHIN 50 FEET OF WATERWAYS, WETLANDS OR OTHER SENSITIVE AREAS WITHIN 7 DAYS OF EXPOSURE.
- 14. STREETS ADJACENT TO CONSTRUCTION ENTRANCES AND ALONG HAUL ROUTES SHALL BE SWEPT AS NEEDED OR WHEN DIRECTED BY THE CITY INSPECTOR TO ENSURE PUBLIC RIGHTS-OF-WAY ARE KEPT CLEAN AND FREE OF DEBRIS.
- 15. WHEN TRUCKING SATURATED SOILS TO OR FROM THE SITE, EITHER WATER-TIGHT TRUCKS SHALL BE USED OR LOADS SHALL BE DRAINED PRIOR TO TRANSPORT UNTIL DRIPPING HAS BEEN REDUCED TO NO MORE THAN ONE GALLON PER HOUR. SEDIMENT LADEN WATER WILL NOT BE ALLOWED TO ENTER THE STORMWATER SYSTEM.
- 16. EXTRACTED GROUND WATER FROM EXCAVATED TRENCHES SHALL BE DISPOSED OF IN A SUITABLE MANNER WITHOUT DISCHARGING SEDIMENT TO ADJACENT PROPERTIES. THE CITY'S STORMWATER SYSTEM, WATER FEATURES, OR RELATED NATURAL RESOURCES. DEWATERING SYSTEMS SHALL BE DESIGNED AND OPERATED SO AS TO PREVENT REMOVAL OF THE NATURAL SOILS AND SO THAT THE GROUNDWATER LEVEL OUTSIDE THE EXCAVATION IS NOT REDUCED TO THE EXTENT THAT WOULD DAMAGE OR ENDANGER ADJACENT STRUCTURES OR PROPERTY. APPROVAL OF THE DEWATERING SYSTEM DOES NOT GUARANTEE THAT IT WILL MEET THE OUTCOMES OR BE ACCEPTABLE FOR USE IN ALL SITUATIONS. MODIFICATIONS TO THE SYSTEM WILL BE REQUIRED IF THE OUTCOMES CANNOT BE MET. AT NO TIME WILL SEDIMENT LADEN WATER BE ALLOWED TO LEAVE THE CONSTRUCTION SITE.
- 17. A SUPPLY OF MATERIALS NECESSARY TO MEET THE OUTCOMES AND IMPLEMENT THE CSMP OR OTHER EROSION PRACTICES UNDER ALL WEATHER CONDITIONS SHALL BE MAINTAINED AT ALL TIMES ON THE CONSTRUCTION SITE.
- 18. NO HAZARDOUS SUBSTANCES, SUCH AS PAINTS, THINNERS, FUELS AND OTHER CHEMICALS SHALL BE RELEASED ONTO THE SITE, ADJACENT PROPERTIES, OR INTO WATER FEATURES, THE CITY'S STORMWATER SYSTEM, OR RELATED NATURAL RESOURCES.
- 19. NO DISCHARGE INTO THE CITY'S STORMWATER SYSTEM OR RELATED NATURAL RESOURCES OF CONSTRUCTION RELATED CONTAMINANTS RESULTING FROM ACTIVITIES SUCH AS, BUT NOT LIMITED TO, CONCRETE SAWING, CLEANING OR WASHING OF EQUIPMENT, TOOLS, OR VEHICLES, SHALL OCCUR.
- 20. ALL WORK PERFORMED BY UTILITY COMPANIES FOR THIS PROJECT, INCLUDING PLACEMENT OF APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES, FINISHED GRADING, SEEDING, MULCHING AND CLEAN UP IS GOVERNED BY THE CONDITIONS AND REQUIREMENTS OF THIS CSMP. COMPLIANCE WITH THESE REQUIREMENTS IS THE RESPONSIBILITY OF THE PERMIT

DEQ STANDARD EROSION AND SEDIMENT CONTROL PLAN (ESCP) NOTES

- HOLD A PRE-CONSTRUCTION MEETING OF PROJECT CONSTRUCTION PERSONNEL THAT INCLUDES THE INSPECTOR TO DISCUSS EROSION AND SEDIMENT CONTROL MEASURES AND CONSTRUCTION LIMITS. (Schedule A.B.c.i.(3))
- ALL INSPECTIONS MUST BE MADE IN ACCORDANCE WITH DEQ 1200-C PERMIT REQUIREMENTS.
- INSPECTION LOGS MUST BE KEPT IN ACCORDANCE WITH DEQ'S 1200-C PERMIT REQUIREMENTS.
- RETAIN A COPY OF THE ESCP AND ALL REVISIONS ON SITE AND MAKE IT AVAILABLE ON REQUEST TO DEQ, AGENT, OR THE LOCAL MUNICIPALITY. DURING INACTIVE PERIODS OF GREATER THAN SEVEN (7) CONSECUTIVE CALENDAR DAYS, RETAIN THE ESCP AT THE CONSTRUCTION SITE OR AT ANOTHER LOCATION. (Schedule B.2.g).
- 5. ALL PERMIT REGISTRANTS MUST IMPLEMENT THE ESCP. FAILURE TO IMPLEMENT ANY OF THE CONTROL MEASURES OR PRACTICES DESCRIBED IN THE ESCP IS A VIOLATION OF THE PERMIT. (Schedule A.8.a)
- THE ESCP MEASURES SHOWN ON THIS PLAN ARE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, UPGRADE THESE MEASURES AS NEEDED TO COMPLY WITH ALL APPLICABLE LOCAL, STATE, AND FEDERAL EROSION AND SEDIMENT CONTROL REGULATIONS (Schedule A.8.c.ii(1)(c))
- 7. SUBMISSIONS OF ALL ESCP REVISIONS IS NOT REQUIRED. SUBMITTAL OF THE ESCP REVISION IS ONLY UNDER SPECIFIC CONDITIONS. SUBMIT ALL NECESSARY REVISION TO DEQ OR AGENT. (Schedule A.12.c.iii)
- 8. PHASE CLEARING AND GRADING TO THE MAXIMUM EXTENT PRACTICAL TO PREVENT EXPOSED INACTIVE AREAS FROM BECOMING A SOURCE OF EROSION. (Schedule A.8.c.ii(1)(d))
- IDENTIFY, MARK, AND PROTECT (BY FENCING OFF OR OTHER MEANS) CRITICAL RIPARIAN AREAS AND VEGETATION INCLUDING IMPORTANT TREES AND ASSOCIATED ROOTING ZONES, AND VEGETATION AREAS TO BE PRESERVED. IDENTIFY VEGETATIVE BUFFER ZONES BETWEEN THE SITE AND SENSITIVE AREAS (E.G., WETLANDS), AND OTHER AREAS TO BE PRESERVED, ESPECIALLY IN PERIMETER AREAS. (SCHEDULE A.8.c.i(1) & (2))
- 10. PRESERVE EXISTING VEGETATION WHEN PRACTICAL AND RE-VEGETATE OPEN AREAS. RE-VEGETATE OPEN AREAS WHEN PRACTICABLE BEFORE AND AFTER GRADING OR CONSTRUCTION. IDENTIFY THE TYPE OF VEGETATIVE SEED MIX USED. (Schedule A.7.b.iii(1) and A.7.b.iii(3))
- 11. EROSION AND SEDIMENT CONTROL MEASURES INCLUDING PERIMETER SEDIMENT CONTROL MUST BE IN PLACE BEFORE VEGETATION IS DISTURBED AND MUST REMAIN IN PLACE AND BE MAINTAINED, REPAIRED, AND PROMPTLY IMPLEMENTED FOLLOWING PROCEDURES ESTABLISHED FOR THE DURATION OF CONSTRUCTION, INCLUDING PROTECTION FOR ACTIVE STORM DRAIN INLETS AND CATCH BASINS AND APPROPRIATE NON-STORMWATER POLLUTION CONTROLS. (Schedule A.7.d.1 and
- 12. ESTABLISH CONCRETE TRUCK AND OTHER CONCRETE EQUIPMENT WASHOUT AREAS BEFORE BEGINNING CONCRETE WORK. (Schedule A.8.c.i.(6))
- 13. APPLY TEMPORARY AND/OR PERMANENT SOIL STABILIZATION MEASURES IMMEDIATELY ON ALL DISTURBED AREAS AS GRADING PROGRESSES AND FOR ALL ROADWAYS INCLUDING GRAVEL ROADWAYS. (Schedule A.8.c.ii.(2))
- 14. ESTABLISH MATERIAL AND WASTE STORAGE AREAS, AND OTHER NON-STORMWATER CONTROLS. (Schedule A.8.c.i.(7))
- 15. PREVENT TRACKING OF SEDIMENT ONTO PUBLIC OR PRIVATE ROADS USING BMP'S SUCH AS: GRAVELED (OR PAVED) EXITS AND PARKING AREAS, GRAVEL ALL UNPAVED ROADS LOCATED ONSITE, OR USE AN EXIT TIRE WASH. THESE BMP'S MUST BE IN PLACE PRIOR TO LAND-DISTURBING ACTIVITIES. (Schedule A.7.d.ii(1) and A.8.c.i(4))
- 16. WHEN TRUCKING SATURATED SOILS FROM THE SITE, EITHER USE WATER-TIGHT TRUCKS OR DRAIN LOADS ON SITE. (Schedule A.7.d.ii(3))
- 17. USE BMP'S TO PREVENT OR MINIMIZE STORMWATER EXPOSURE TO POLLUTANT FROM SPILLS; VEHICLE AND EQUIPMENT FUELING, MAINTENANCE, AND STORAGE: OTHER CLEANING AND MAINTENANCE ACTIVITIES: AND WASTE HANDLING ACTIVITIES. THESE POLLUTANTS INCLUDE FUEL, HYDRAULIC FLUID, AND OTHER OILS FROM VEHICLES AND MACHINERY, AS WELL AS DEBRIS, LEFTOVER PAINTS, SOLVENTS, AND GLUES FROM CONSTRUCTION OPERATIONS. (Schedule A.7.e.i(2))
- 18. IMPLEMENT THE FOLLOWING BMP'S WHEN APPLICABLE; WRITTEN SPILL PREVENTION AND RESPONSE PROCEDURES, EMPLOYEE TRAINING ON SPILL PREVENTION AND PROPER DISPOSAL PROCEDURES, SPILL KITS IN ALL VEHICLES, REGULAR MAINTENANCE SCHEDULE FOR VEHICLES AND MACHINERY, MATERIAL DELIVERY AND STORAGE CONTROLS, TRAINING AND SIGNAGE, AND COVERED STORAGE AREAS FOR WASTE AND SUPPLIES. (Schedule A.7.e.iii)
- 19. USE WATER, SOIL-BINDING AGENT OR OTHER DUST CONTROL TECHNIQUE AS NEEDED TO AVOID WIND-BLOWN SOIL. (Schedule A.7.b.ii)
- 20. THE APPLICATION RATE OF FERTILIZERS USED TO RE-ESTABLISH VEGETATION MUST FOLLOW MANUFACTURER'S RECOMMENDATIONS TO MINIMIZE NUTRIENT RELEASES TO SURFACE WATERS. EXERCISE CAUTION WHEN USING TIME-RELEASE FERTILIZERS WITHIN ANY WATERWAY RIPARIAN ZONE. (Schedule A.9.b.iii)
- 21. IF A STORMWATER TREATMENT SYSTEM (FORE EXAMPLE, ELECTRO-COAGULATION, FLOCCULATION, FILTRATION, ETC.) FOR SEDIMENT OR OTHER POLLUTANT REMOVAL IS EMPLOYED. SUBMIT AN OPERATION AND MAINTENANCE PLAN (INCLUDING SYSTEM SCHEMATIC, LOCATION OF SYSTEM, LOCATION OF INLET, LOCATION OF DISCHARGE, DISCHARGE DISPERSION DEVICE DESIGN, AND A SAMPLING PLAN AND FREQUENCY) BEFORE OPERATING THE TREATMENT SYSTEM. OBTAIN PLAN APPROVAL BEFORE OPERATING THE TREATMENT SYSTEM. OPERATE AND MAINTAIN THE TREATMENT SYSTEM ACCORDING TO MANUFACTURER'S SPECIFICATIONS. (Schedule A.9.d)
- 22. TEMPORARILY STABILIZE SOILS AT THE END OF THE SHIFT BEFORE HOLIDAYS AND WEEKENDS, IF NEEDED. THE REGISTRANT IS RESPONSIBLE FOR ENSURING THAT SOILS ARE STABLE DURING RAIN EVENTS AT ALL TIMES OF THE YEAR. (Schedule A.7.b)
- 23. AT THE END OF EACH WORKDAY SOIL STOCKPILES MUST BE STABILIZED OR COVERED, OR OTHER BMP'S MUST BE IMPLEMENTED TO PREVENT DISCHARGES TO SURFACE WATERS OR CONVEYANCE SYSTEMS LEASING TO SURFACE WATERS. (Schedule A.7.e.ii(2))
- 24. CONSTRUCTION ACTIVITIES MUST AVOID OR MINIMIZE EXCAVATION AND CREATION OF BARE GROUND DURING WET WEATHER. (Schedule A.7.a.i)
- 25. SEDIMENT FENCE: REMOVE TRAPPED SEDIMENT BEFORE IT REACHES ONE THIRD OF THE ABOVE GROUND FENCE HEIGHT AND BEFORE FENCE REMOVAL. (Schedule A.9.c.i) 26. OTHER SEDIMENT BARRIERS (SUCH AS BIOBAGS): REMOVE SEDIMENT BEFORE IT REACHES TWO INCHES DEPTH ABOVE

GROUND HEIGHT, AND BEFORE BMP REMOVAL. (Schedule A.9.c.ii)

- 27. CATCH BASINS: CLEAN BEFORE RETENTION CAPACITY HAS BEEN REDUCED BY FIFTY PERCENT. SEDIMENT BASINS AND SEDIMENT TRAPS: REMOVE TRAPPED SEDIMENTS BEFORE DESIGN CAPACITY HAS BEEN REDUCED BY FIFTY PERCENT AND AT COMPLETION OF PROJECT. (Schedule A.9.c.iii and iv)
- 28. WITHIN 24 HOURS, SIGNIFICANT SEDIMENT THAT HAS LEFT THE CONSTRUCTION SITE, MUST BE REMEDIATED. INVESTIGATE THE CAUSE OF THE SEDIMENT RELEASE AND IMPLEMENT STEPS TO PREVENT A RECURRENCE OF THE DISCHARGE WITHIN THE SAME 24 HOURS. ANY IN-STREAM CLEAN UP OF SEDIMENT SHALL BE PERFORMED ACCORDING TO THE OREGON DIVISION OF STATE LANDS REQUIRED TIME FRAME. (Schedule A.9.b.i)
- 29. THE INTENTIONAL WASHING OF SEDIMENT INTO STORM SEWERS OR DRAINAGE WAYS MUST NO OCCUR. VACUUMING OR DRY SWEEPING AND MATERIAL PICKUP MUST BE USED TO CLEANUP RELEASED SEDIMENTS. (Schedule A.9.b.ii)
- 30. THE ENTIRE SITE MUST BE TEMPORARILY STABILIZED USING VEGETATION OR A HEAVY MULCH LAYER, TEMPORARY SEEDING, OR OTHER METHOD SHOULD ALL CONSTRUCTION ACTIVITIES CEASE FOR 30 DAYS OR MORE. (Schedule A.7.f.i)
- 31. PROVIDE TEMPORARY STABILIZATION FOR THAT PORTION OF THE SITE WHERE CONSTRUCTION ACTIVITIES CEASE FOR 14 DAYS OR MORE WITH A COVERING OF BLOWN STRAW AND A TACKIFIER, LOOSE STRAW, OR ADEQUATE COVERING OF COMPOST MULCH UNTIL WORK RESUMES ON THAT PORTION OF THE SITE. (Schedule A.7.f.ii)
- 32. PROVIDE PERMANENT EROSION CONTROL MEASURES ON ALL EXPOSED AREAS. DO NOT REMOVE TEMPORARY SEDIMENT CONTROL PRACTICES UNTIL PERMANENT VEGETATION OR OTHER COVER OF EXPOSED AREAS IS ESTABLISHED. HOWEVER, DO REMOVE ALL TEMPORARY EROSION CONTROL MEASURES AS EXPOSED AREAS BECOME STABILIZED, UNLESS DOING SO CONFLICTS WITH LOCAL REQUIREMENTS. PROPERLY DISPOSE OF CONSTRUCTION MATERIALS AND WASTE, INCLUDING SEDIMENT RETAINED BY TEMPORARY BMP'S. (Schedule A.7.b.iii(2) and A.8.c.iii)





CHOOL

Ś

SCHOOL EUGENE, ORI MIDDLI

SEI

AND NOT


PRC ISSI DRA

C102



& HUBBARD ENGINEERS INC. 100 WEST 13TH AVENUE EUGENE, OR 97401 P: 541-686-8478 F: 541-345-5303 1001 SW 5TH AVENUE SUITE 1100 - OFFICE SS PORTLAND, OR 97204

STABILIZED CONSTRUCTION ENTRANCE



NOTES


1. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS IN TO AN APPROVED SEDIMENT TRAP OR BASIN.


2. CONTRACTOR TO REMOVE ACCUMULATED SEDIMENT FROM BOTTOM OF BASIN AND TO ENSURE WASH WATER COLLECTION AND TREATMENT IS FUNCTIONING.

10' EGRESS 16' WASH BASIN

50' RUN OUT AREA

2 TRUCK WHEEL WASH
No Scale






NOTES

1. PRIOR TO 1st PAVEMENT LIFT, REMOVE BIO-BAG/SANDBAG BARRIERS AND INSTALL BASIN INSERT BAG OR CURB INLET SEDIMENT DAM AT ALL INLET STRUCTURES.

DRAINAGE INLET STRUCTURE PROTECTION




SLOPES LESS THAN 5% — 24"—36" WIDE BY 12"—18" HIGH
SLOPES GREATER THAN 5% — 36"—48" WIDE BY 18"—24" HIGH

COMPOST MULCH SHALL BE MEDIUM—GRADE, MIXED YARD DEBRIS.

BARK MULCH SHALL BE STANDARD COMMERCIAL PRODUCT, MEDIUM—COURSE GROUND BARK. BARK SHALL BE GROUND FIR BARK, FREE FROM WEEDS AND SEED.

CONTINUOUS BARK/MULCH BIO BERM
No Scale



- NOTES

 1. MAX GROUND SLOPE (PERPENDICULAR TO FENCE):
 SUPPORTED FENCE 1H: 1V
 UNSUPPORTED FENCE 4H: 1V

 2. SYNTHETIC FILTER FABRIC SHALL CONTAIN ULTRAVIOLET RAY INHIBITORS
 AND STABILIZERS TO PROVIDE A MINIMUM OF 6 MONTHS OF EXPECTED
 USABLE CONSTRUCTION LIFE AT A TEMPERATURE RANGE OF 0°F TO 120°F.

 3. FILTER FABRIC SHALL BE SPLICED TOGETHER ONLY AT SUPPORT POSTS WITH
 A MINIMUM OF 6 INCH OVERLAP AND BOTH ENDS SECURED TO POST.

 4. CONTINUOUS BIO BERM MAY BE INSTALLED AT UPHILL BASE OF FILTER
 FABRIC IN LIEU OF BURYING BOTTOM OF FABRIC.

 5. USE STAPLES OR WIRE RINGS TO ATTACH FILTER FABRIC TO WIRE SUPPORT
 FABRIC.

			IF NO,	YEAR	Γ			2014	1			Г	
BMP'S	YES	NO	RATIONALE		6	7	8	9		11	12		Π
RUNOFF CONTROLS	L							<u> </u>	L	L	<u></u>	<u> </u>	
STABILIZE STREAM BANKS / CONSTRUCT								Г			Γ	T	Т
PRIMARY RUNOFF CONTROL MEASURES		x	SEE BELOW										
ENERGY DISSIPATERS		X	SEE BELOW					 			 	<u> </u>	一
RUN-ON DIVERSION		X	SEE BELOW										T
TEMPORARY DIVERSION DIKES		X	SEE BELOW										T
GRASS-LINED CHANNEL (TURF REINFORCEMENT													T
MATS)		Х	SEE BELOW										
TRENCH DRAINS (COLLECTED RUNOFF TO													
TREATMENT BMP)		X	SEE BELOW										
DROP INLETS		Х	SEE BELOW										
CHECK DAMS		Х	SEE BELOW										
CLEARING & GRUBBING PRACTICES													
TOP-SOILING	T	X	SEE BELOW					Π			Π	Г	Г
TEMPORARY SEEDING & PLANTING		Х	SEE BELOW					l					T
PERMANENT SEEDING & PLANTING	X							X					T
MYCORRHIZAE / BIOFERTILIZERS		X	SEE BELOW										厂
MULCHES		X	SEE BELOW										
COMPOST BLANKETS		X	SEE BELOW										
EROSION CONTROL BLANKETS & MATS		Х	SEE BELOW										
SOIL BINDERS		X	SEE BELOW										
SOIL TACKIFIERS		X	SEE BELOW										
SODDING VEGETATIVE BUFFER STRIPS		Х	SEE BELOW										
PROTECTION OF TREES WITH													
CONSTRUCTION FENCING	X			<u> </u>	X	Х	Х	X				<u> </u>	<u> </u>
VEGETATIVE EROSION CONTROLS													
LIVE STAKING (STABILIZATION PRACTICE)	Т	X	SEE BELOW									Π	П
LIVE FASCINES / BRUSH WATTLES (STABILIZATION)		X	SEE BELOW	l									T
STABILIZATION MATS (STABILIZATION PRACTICE)		X	SEE BELOW										T
POLE PLATING (STREAM BANK STABILIZATION)		X	SEE BELOW										
BRUSH BOX (STREAM BANK STABILIZATION)		X	SEE BELOW										
GRASS-LINED CHANNEL (TURF REINFORCEMENT													
MATS)		X	SEE BELOW									<u> </u>	<u> </u>
FASCINES WITH SUB-DRAINS (STREAM BANK													
STABILIZATION)		X	SEE BELOW									<u> </u>	
LIVE POLE DRAINS (STREAM BANK STABILIZATION)													
(MAY HAVE TO BE REMOVED FOR STABILIZATION)		X							<u> </u>				_
BRUSH PACKING (STREAM BANK STABILIZATION)		X	SEE BELOW					<u> </u>	<u> </u>				
LIVE GULLY FILL REPAIR (STREAM BANK													
STABILIZATION)		X	SEE BELOW		<u> </u>		<u> </u>		<u></u>			<u> </u>	<u></u>
EROSION CONTROL PRACTICES													
SEDIMENT FENCING		X	SEE BELOW										
SAND BAG BARRIER		X	SEE BELOW										
GRAVEL BAG BERM (WITH COMPOST BERM)		X	SEE BELOW										
EARTH DIKES (STABILIZED)		X	SEE BELOW										
DRAINAGE SWALES		Х	SEE BELOW										
SUBSURFACE DRAINS - DAYLIGHT TO SURFACE		Х	SEE BELOW									$oxedsymbol{oxedsymbol{oxed}}$	$oxed{oxed}$
ROCK OUTLET PROTECTION		X	SEE BELOW										
SEDIMENT TRAP		X	SEE BELOW						<u> </u>			<u> </u>	_
ROCK & BUSH FILTERS (STREAM BANK													
STABILIZATION)	<u> </u>	X	SEE BELOW		<u> </u>		<u> </u>	<u> </u>			<u> </u>	<u> </u>	<u> </u>
COMPOST BERM / COMPOST SOCK	X	<u> </u>			X	Х	Х	X				<u> </u>	<u> </u>
FIBER ROLLS / STRAW WATTLES	 	X	SEE BELOW	ļ	ļ.,-			L.		ļ	<u> </u>	 	
EXISTING STORM INLET PROTECTION	X**	 			X	Х	X	X	 	ļ	<u> </u>	 	
MENALOTODIANI ET DOOTECTION	 	X	SEEBELOW	ļ			ļ	ļ	<u> </u>	<u> </u>	<u> </u>	 	
NEW STORM INLET PROTECTION													
TEMPORARY / PERMANENT SEDIMENTATION		X	SEE BELOW	 	ļ		ļ	<u> </u>	_	<u> </u>		 	
TEMPORARY / PERMANENT SEDIMENTATION BASINS	-	1		1									
TEMPORARY / PERMANENT SEDIMENTATION BASINS UNPAVED ROADS GRAVELED OR OTHER BMP ON	 		1	<u> </u>	X	X	X	X	-		-	 	
TEMPORARY / PERMANENT SEDIMENTATION BASINS UNPAVED ROADS GRAVELED OR OTHER BMP ON THE ROAD OR DOWN GRADIENT	Х		000000000000000000000000000000000000000	1	1	1	1	1	<u> </u>		<u> </u>	 	
TEMPORARY / PERMANENT SEDIMENTATION BASINS UNPAVED ROADS GRAVELED OR OTHER BMP ON THE ROAD OR DOWN GRADIENT DEWATERING AND PONDED WATER MANAGEMENT		X	SEE BELOW		├		1/	\ \V				1	
TEMPORARY / PERMANENT SEDIMENTATION BASINS UNPAVED ROADS GRAVELED OR OTHER BMP ON THE ROAD OR DOWN GRADIENT DEWATERING AND PONDED WATER MANAGEMENT PAWNG OPERATIONS CONTROLS	X						X	X	 		 	╂	┼
TEMPORARY / PERMANENT SEDIMENTATION BASINS UNPAVED ROADS GRAVELED OR OTHER BMP ON THE ROAD OR DOWN GRADIENT DEWATERING AND PONDED WATER MANAGEMENT PAMING OPERATIONS CONTROLS TEMPORARY EQUIPMENT BRIDGE		X	SEE BELOW				Х	X					
TEMPORARY / PERMANENT SEDIMENTATION BASINS UNPAVED ROADS GRAVELED OR OTHER BMP ON THE ROAD OR DOWN GRADIENT DEWATERING AND PONDED WATER MANAGEMENT PAVING OPERATIONS CONTROLS TEMPORARY EQUIPMENT BRIDGE BMPs TO PREVENT ILLICIT CONNECTION		X	SEE BELOW				X	X					
TEMPORARY / PERMANENT SEDIMENTATION BASINS UNPAVED ROADS GRAVELED OR OTHER BMP ON THE ROAD OR DOWN GRADIENT DEWATERING AND PONDED WATER MANAGEMENT PAVING OPERATIONS CONTROLS TEMPORARY EQUIPMENT BRIDGE BMPs TO PREVENT ILLICIT CONNECTION BMPs TO PREVENT ILLEGEL DISCHARGE		XXX	SEE BELOW SEE BELOW				X	X					
TEMPORARY / PERMANENT SEDIMENTATION BASINS UNPAVED ROADS GRAVELED OR OTHER BMP ON THE ROAD OR DOWN GRADIENT DEWATERING AND PONDED WATER MANAGEMENT PAVING OPERATIONS CONTROLS TEMPORARY EQUIPMENT BRIDGE BMPs TO PREVENT ILLICIT CONNECTION BMPs TO PREVENT ILLEGEL DISCHARGE REUSE & RECYCLE CONSTRUCTION WASTES	X	XXX	SEE BELOW										
TEMPORARY / PERMANENT SEDIMENTATION BASINS UNPAVED ROADS GRAVELED OR OTHER BMP ON THE ROAD OR DOWN GRADIENT DEWATERING AND PONDED WATER MANAGEMENT PAVING OPERATIONS CONTROLS TEMPORARY EQUIPMENT BRIDGE BMPs TO PREVENT ILLICIT CONNECTION		XXX	SEE BELOW SEE BELOW		X	X	X	X					

X** = MEASURES TO BE INSTALLED PRIOR TO ANY GROUND DISTURBING ACTIVITY

RATIONALE STATEMENT

A COMPREHENSIVE LIST OF AVAILABLE BEST MANAGEMENT PRACTICE (BMP) OPTIONS BASED ON DEQ'S 1200-C PERMIT APPLICATION AND ESCP GUIDANCE DOCUMENT HAS BEEN REVIEWED TO COMPLETE THIS EROSION AND SEDIMENT CONTROL PLAN. SOME OF THE ABOVE LISTED BMPs WERE NOT CHOSEN BECAUSE THEY WERE DETERMINED TO NOT EFFECTIVELY MANAGE EROSION PREVENETION AND SEDIMENT CONTROL FOR THIS PROJECT BASED ON SPECIFIC SITE CONDITIONS, INCLUDING SOIL CONDITIONS, TOPOGRAPHIC CONSTRAINTS, ACCESSIBILITY TO THE SITE, AND OTHER RELATED CONDITIONS. AS THE PROJECT PROGRESSES AND THERE IS A NEED TO REVISE THE ESCP, AN ACTION PLAN WILL BE SUBMITTED.

> & HUBBARD **ENGINEERS INC** 100 WEST 13TH AVENUE EUGENE, OR 97401 P: 541-686-8478 F: 541-345-5303 1001 SW 5TH AVENUE SUITE 1100 - OFFICE SS


PORTLAND, OR 97204 P: 503-961-6440



SCHOOL 'SCHOOL' SCHOOL SEUGENE, OL MIDDL EUGENE 3700 HOWARD I



EROSION AND SEDI CONTROL DETAILS



ARCHITECTURE •



EUGENE SCHOOL DISTRICT
700 HOWARD EUGENE, OREGON
KELLY MIDDLE SCHOOL TRA

TAL CONTROL

HORI PLAN

| PROJECT NO: 1415.00 | REVISIC |
| ISSUE DATE: 05.09.2014 |
| DRAWN JAH |
| CHECKED: MBA |

C121

	HORIZONTAL LAYOUT TABLE							
POINT	NORTHING	EASTING	DESCRIPTION					
129	5205.19	6104.02	TW/ME					
130	5205.19	6092.05	TW					
131	5205.19	6069.62	TW					
132	5077.76	6074.62	TW/PC					
133	5187.28	5467.09	TW					
134	5205.69	5389.79	TW					
135	5072.51	5479.86	TW/PC					
136	5153.47	5512.19	PC/TC					
137	5203.19	5512.19	TC					
138	5203.19	6042.19	TC					
139	5182.19	6042.19	TC					
140	5182.19	6011.54	PC/TC					
141	4952.33	5942.19	PT/TC					
142	4952.33	5612.19	PT/TC					
143	5182.19	5512.19	TC					
144	4973.33	5612.19	PC/TC					
145	5182.19	5612.19	PT/TC					
146	5182.19	5942.19	PC/TC					
147	4973.83	5942.19	PT/TC					
148	5081.86	5486.83	TW/PC					
149	4950.33	5612.19	TW/PT					
150	4950.33	5942.19	TW/PC					
151	5077.76	6069.62	TW/PT					
152	5077.76	5612.19	TC/RAD = 103.9'					
153	5077.76	5942.19	TC/RAD = 103.9					
154	5222.69	5460.21	TW/RAD = 5.0					
155	5222.69	5475.21	TW/RAD = 5.0					
156	5223.72	5606.73	TW/RAD = 5.0					
157	5218.19	5622.72	TW/RAD = 5.0					
158	5285.86	5622.59	TW/RAD = 5.0					

HORIZONTAL LAYOUT TABLE							
POINT	NORTHING	EASTING	DESCRIPTION				
159	5285.55	5725.11	TW/RAD = 5.0				
160	5218.19	5725.02	TW/RAD = 5.0				
161	5218.19	5741.02	TW/RAD = 5.0				
162	5142.76	5970.00	LONG JUMP				
163	5163.76	5970.00	LONG JUMP				
164	5163.76	5982.84	LONG JUMP				
165	5142.76	5982.84	LONG JUMP				
166	5142.76	5974.67	LONG JUMP				
167	5142.76	5978.17	LONG JUMP				
168	5077.77	5974.67	TW				
169	5077.77	5978.17	TW				
170	5032.23	5518.77	TC/TP				
171	5123.29	5518.76	TC/TP				
172	5107.76	5576.72	TP				
173	5047.76	5576.72	TP				
174	4976.57	5588.46	TC				
175	5178.94	5588.46	TC				
176	5178.94	5965.92	TC				
177	4976.57	5965.92	TC				
178	5179.77	5500.28	AD				
179	5012.76	5982.84	LONG JUMP				
180	5012.76	5970.00	LONG JUMP				
181	4991.76	5970.00	LONG JUMP				
182	4991.76	5982.84	LONG JUMP				
183	5182.19	5777.19	PC/PT				
184	4973.33	5777.19	PC/PT				
185	5077.76	5777.19	FIELD CL				
190	4963.99	5501.57	SHOT PUT				
191	4965.99	5502.50	SHOT PUT				
192	4961.76	5511.56	SHOT PUT				

HORIZONTAL LAYOUT TABLE								
POINT	NORTHING	EASTING	DESCRIPTION					
193	4952.70	5507.34	SHOT PUT					
194	4956.93	5498.27	SHOT PUT					
195	4958.93	5499.20	SHOT PUT					
196	4966.76	5440.01	SHOT PUT					
197	5004.30	5457.51	SHOT PUT					
199	5081.31	5457.29	DISCUS					
200	5084.45	5456.45	DISCUS					
201	5087.04	5466.11	DISCUS					
202	5077.38	5468.70	DISCUS					
203	5074.79	5459.04	DISCUS					
204	5077.93	5458.19	DISCUS					
206	5012.76	5978.17	LONG JUMP					
207	5012.76	5974.67	LONG JUMP					
208	5187.76	6074.62	TW					
210	5204.19	5733.02	CL GATE					
211	5204.19	5614.72	CL GATE					
212	5213.00	5485.84	CL GATE					
213	4990.43	5520.89	CL GATE					
214	4951.33	5753.19	CL GATE					
215	5064.99	6067.87	CL GATE					

216 5195.76 6068.62 CL GATE

CONTROL PT #43

CONTROL POINTS
NO SCALE

REFER TO SHEET <u>C201</u> FOR GENERAL NOTES AND SURVEY AND CIVIL SYMBOL LEGENDS.


C122

SHEET NOTES

- REFER TO SHEET C201 FOR GENERAL NOTES AND SURVEY AND CIVIL SYMBOL LEGENDS.
 PROVIDE SMOOTH, UNIFORM GRADE TRANSITIONS TO MATCH EXISTING AT A MAX SLOPE OF 1:20 OR AT LOCATIONS SHOWN.

CONSTRUCTION NOTES

ZONE OF ELEVATED SIDEWALK. REFER TO ARCHITECTURAL DRAWINGS FOR DETAILS.





DISTRICT
REGON
LE SCHOOL

EUGENE SCHOOL 700 HOWARD EUGENE, OR KELLY MIDDL





1001 SW 5TH AVENUE SUITE 1100 - OFFICE 5S PORTLAND, OR 97204 P: 503-961-6440

C131

100 WEST 13TH AVENUE EUGENE, OR 97401 P: 541-686-8478 F: 541-345-5303

& Hubbard **ENGINEERS INC**





GENERAL NOTES:

- 1. <u>EXISTING TOPOGRAPHIC INFORMATION</u>: FROM SURVEY PREPARED BY BALZHISER & HUBBARD ENGINEERS SURVEYORS, TITLED "TOPOGRAPHIC SURVEY FOR 4J SCHOOL DISTRICT: HOWARD MIDDLE & KELLEY ELEMENTARY SCHOOL CAMPUS". DATED 9/18/13.
- 2. <u>BASIS OF BEARING</u>: THIS SURVEY IS BASED UPON THE OREGON COORDINATE REFERENCE SYSTEM, EUGENE ZONE. ALL DISTANCES ARE GROUND DISTANCES AND ARE EXPRESSED IN INTERNATIONAL FEET. SEE SURVEY METADATA FOR MORE INFORMATION.
- 3. COORDINATE SYSTEM TRANSLATION: THE SURVEY FILE HAS BEEN TRANSLATED FROM BHE'S SURVEY CONTROL POINT No. 41 TO A LOCAL DATUM PLAN COORDINATE OF 5000, 5000.
- 4. <u>BASIS OF ELEVATION</u>: THE BENCHMARK USED FOR THIS SURVEY WAS CITY OF EUGENE BENCHMARK RR0899 WITH A PUBLISHED ELEVATION OF 395.68' (NAVD 88 DATUM).
- 5. THE CONTRACTOR SHALL LOCATE AND MARK ALL EXISTING PROPERTY AND STREET MONUMENTS PRIOR TO CONSTRUCTION. ANY MONUMENTS DISTURBED DURING CONSTRUCTION OF THE PROJECT SHALL BE REPLACED BY A REGISTERED LAND SURVEYOR AT THE CONTRACTOR'S EXPENSE. THE MONUMENTS SHALL BE REPLACED WITHIN A MAXIMUM OF 90 DAYS, AND THE COUNTY SURVEYOR SHALL BE NOTIFIED IN WRITING AS REQUIRED BY ORS 209.150.
- 6. LOCATIONS OF EXISTING UTILITIES ARE ASSUMED FROM INFORMATION AVAILABLE AND ARE NOT GUARANTEED TO BE COMPLETE AND ACCURATE. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING THE LOCATION OF EXISTING UTILITIES.
- 7. CONTRACTOR SHALL NOTIFY EACH UNDERGROUND UTILITY PRIOR TO EXCAVATING, BORING, OR POTHOLING. ATTENTION: OREGON LAW REQUIRES THE CONTRACTOR TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THOSE RULES ARE SET FORTH IN O.A.R. 952-001-0010 952-001-0090. THE CONTRACTOR MAY OBTAIN COPIES OF THE RULES BY CALLING THE CENTER. (NOTE: THE TELEPHONE NUMBER FOR THE OREGON UTILITY NOTIFICATION CENTER IS 1-800-332-2344)
- 8. CONTRACTOR SHALL MAKE THE NECESSARY ARRANGEMENTS AND COMPLY WITH REQUIREMENTS AND SPECIFICATIONS OF ANY RESPECTIVE UTILITY COMPANY FOR UTILITIES TO BE CUT, MOVED, RELOCATED, OR RE—CONNECTED TO AN EXISTING FACILITY.
- 9. CONTRACTOR IS RESPONSIBLE FOR COORDINATING WITH ANY SERVING UTILITY COMPANY INSTALLING UTILITIES ON SITE. CONSTRUCTION OF OTHER UTILITIES MAY OCCUR AT SAME TIME ON SITE.
- 10. QUANTITIES SHOWN ARE FOR THE PURPOSE OF IDENTIFYING LENGTHS. ACTUAL QUANTITIES MAY VARY. CONTRACTOR TO PROVIDE QUANTITIES NEEDED FOR LAYOUT OF SYSTEM.
- 11. CONTRACTOR SHALL PROVIDE AND INSTALL FITTINGS AS REQUIRED TO COMPLETE PIPE CONNECTIONS AND TRANSITIONS PER PLAN, AND TO CONFORM TO TRENCHING REQUIREMENTS AND SITE GRADES
- 12. CURB QUANTITIES SHOWN ARE FOR THE PURPOSE OF IDENTIFYING CURB TYPES. ACTUAL QUANTITIES MAY VARY. CONTRACTOR TO PROVIDE QUANTITIES NEEDED FOR LAYOUT SHOWN.
- 13. MANHOLE AND CLEANOUT RIM ELEVATIONS ARE APPROXIMATE. FINAL ELEVATIONS MAY VARY AND SHALL MATCH FINISHED ELEVATIONS OF ADJACENT SURFACES.
- 14. COORDINATE FINAL ROOF DRAIN/DOWNSPOUT LOCATIONS AND ELEVATIONS WITH ARCHITECTURAL/MECHANICAL DRAWINGS. COORDINATE FOOTING DRAIN LOCATIONS AND ELEVATIONS WITH ARCHITECTURAL/STRUCTURAL DRAWINGS AND DETAILS.
- 15. TRACER WIRE SHALL ENTER ALL MANHOLE, CATCH BASIN, INLET, CLEANOUT STRUCTURES. EXTEND TRACER WIRE INTO STRUCTURE FAR ENOUGH TO PROVIDE ADEQUATE FREE WIRE TO EXTEND END OF WIRE 24" ABOVE/OUTSIDE OF STRUCTURE TO FACILITATE TESTING. COIL AND SECURE TRACER WIRE WITHIN EASY REACH OF STRUCTURE OPENING. VERIFY WIRE IS CLEAR OF ALL FILL MATERIAL IN CLEANOUT AND VALVE BOX STRUCTURES.
- 16. CAP AND MARK ALL STORM PIPE ENDS WITH A 2"x4" BOARD STUCK IN GROUND. END OF BOARD SHALL BE PAINTED WHITE AND EXTEND MINIMUM 18" ABOVE GROUND SURFACE.
- 17. WATER PIPES CROSSING SANITARY SEWER AND/OR STORM DRAINAGE PIPING: WATER PIPES CROSSING SEWER OR DRAINAGE PIPING CONSTRUCTED OF CLAY OR MATERIALS THAT ARE NOT APPROVED FOR USE WITHIN A BUILDING SHALL BE LAID A MINIMUM OF 12" ABOVE THE SEWER OR DRAIN PIPE. WHERE MINIMUM SEPARATION CANNOT BE MET, SANITARY SEWER AND/OR STORM DRAIN LINE SHALL BE CONSTRUCTED OF MATERIAL APPROVED FOR USE UNDER BUILDINGS, WITH A FULL LENGTH OF PIPE CENTERED AT THE CROSSING POINT, AND EXTENDING 10' MIN EACH SIDE OF CROSSING.
- 18. REFER TO SHEET <u>C101</u>, EROSION AND SEDIMENT CONTROL PLAN, FOR EROSION SEDIMENT CONTROL MEASURES AND ADDITIONAL CONSTRUCTION REQUIREMENTS.
- 19. CONTRACTOR SHALL INCLUDE DEMOLITION OF EXISTING PRIVATE STORM DRAIN, SANITARY SEWER, AND WATER UTILITIES. REMOVE EXISTING STRUCTURES WHERE ENCOUNTERED. CUT AND CAP EXPOSED ENDS OF EXISTING PIPES ENCOUNTERED. (ABANDON EXISTING PIPE IN PLACE).

CIVIL SYMBOLS AND ABBREVIATIONS LIST									
SYMBOL	ABBR.	DESCRIPTION	SYMBOL	ABBR.	DESCRIPTION	ABBR.	DESCRIPTION	ABBR.	DESCRIPTION
12"SD	SD	STORM DRAIN WITH SIZE		МН	MANHOLE STRUCTURE	AC	ASPHALT CONCRETE	PRC	POINT OF REVERSE CURVATURE
	PERF	STORM DRAIN PERF PIPE WITH SIZE		СВ	SINGLE CHAMBER CATCH BASIN	APPX	APPROXIMATE	PT	POINT OF TANGENCY
FD	FD	BUILDING FOUNDATION DRAIN	AD AD	AD	AREA DRAIN (ROUND OR SQUARE)	BLDG	BUILDING	PTC	POINT OF TANGENT CURVATURE
FRD	FRD	FRENCH DRAIN	DD ⊞	DD	DECK DRAIN	CONC	CONCRETE	PVMT	PAVEMENT
тр	TD	TRENCH DRAIN	œ	TD	TRENCH DRAIN CONNECTION/CATCH BASIN	CONST	CONSTRUCT	R=	RADIUS=
SD	SL	SLOTTED DRAIN	00 O	СО	STANDARD CLEANOUT	DIA	DIAMETER	RD	ROOF DRAIN
200000000000000000000000000000000000000	_	PIPE WITH FLOW DIRECTION ARROW	VCO O	VCO	VERTICAL DROP CLEANOUT	DS	DOWNSPOUT	REQD	REQUIRED
Е	E	ELECTRICAL POWER SERVICE	BW ⋈	BWV	BACKWATER VALVE	ELEV	ELEVATION	RIM	STRUCTURE RIM ELEVATION
IRR	IRR	IRRIGATION LINE		_	PIPE TERMINATION (PLUG & MARK)	EX	EXISTING	S=	SLOPE=
450	_	CONTOUR MAJOR - PROPOSED	10	DET	DETAIL REFERENCE — DETAIL # OVER SHEET #	FFE	FINISHED FLOOR ELEVATION	STD	STANDARD
	_	CONTOUR MINOR - PROPOSED	(10 C-500			FL	FLOWLINE	SW	SIDEWALK
——————————————————————————————————————	R	GRADING RIDGE LINE	12	_	CONSTRUCTION NOTE WITH REFERENCE NUMBER	FS	FINISHED SURFACE ELEVATION (LANDSCAPE AREAS)	TC	TOP OF CURB ELEVATION
	٧	GRADING VALLEY LINE				HORIZ	HORIZONTAL	THK	THICK OR THICKNESS
LMT	LMT	LIMITS OF CONSTRUCTION	A C-500	_	SECTION REFERENCE — SECTION # OVER SHEET #	LF	LINEAR FEET	TP	TOP OF PAVEMENT ELEVATION
scsc	SC	PAVEMENT REMOVAL SAWCUT LINE	L-500		" "	MAX	MAXIMUM	TW	TOP OF WALK ELEVATION
						ME	MATCH EXISTING	TWALL	TOP OF WALL ELEVATION
						MIN	MINIMUM	TYP	TYPICAL
						PC	POINT OF CURVE	UTIL	UTILITY
						PCC	PORTLAND CEMENT CONCRETE/POINT OF COMPOUND CURVATURE	VERT	VERTICAL

VEHICULAR CONCRETE JOINT LEGEND
A CONTRACTION JOINT
B THICKENED EDGE ISOLATION JOINT
C EXPANSION JOINT
JOINT SEALER REINFORCING TYP
CONTRACTION JOINT
EDGE OF BLDG OR UTILITY STRUCTURE B THICKENED EDGE ISOLATION JOINT AT UTILITY STRUCTURES, BUILDINGS AND LANDSCAPING
EXPANSION CAP 1" \(\text{\overline{S}} \) SMOOTH DOWEL. 18" LONG. 12" O.C. PROVIDE DOWELS WHERE INDICATED ON PLAN.

NOTES

1. ALL JOINTS ARE CONTRACTION JOINTS, UNLESS OTHERWISE NOTED.

2. USE THICKENED EDGE JOINT AT PCC PAVEMENT END AND AROUND

- ALL STRUCTURES.

 3. MIX DESIGN AND MATERIALS TO BE APPROVED BY ENGINEER.
- 4. PROVIDE TIED CONSTRUCTION JOINT AT END OF SUCCESSIVE POURS.



MBOL	DESCRIPTION	SYMBOL	DESCRIPTION
₩V ⊠	WATER VALVE	СОММ	COMMUNICATIONS
⊠	WATER METER	CMP	CORRUGATED METAL PIPE
⊠	IRRIGATION VALVE	ELEC	ELECTRIC
₩ <u></u>	WATER VAULT	SS	SANITARY SEWER
<i>BFP</i>	BACK FLOW PREVENTER	AD SQ	SQUARE AREA DRAIN
+∱+	FIRE HYDRANT	SD	STORMWATER
FDC +●+	FIRE DEPARTMENT CONNECTION	<u>©</u>	GAS METER
	AREA DRAIN (SQUARE)	ev ⊠	GAS VALVE
@	STORMDRAIN MANHOLE	©	SEWER MANHOLE
b	UTILITY POLE	©	CLEANOUT
- <	GUY ANCHOR	•	METAL POST
*	LIGHT POLE	A	SET PERMANENT SITE CONTROL (SC) REFER TO DETAIL AND BENCHMARK TABLE
≕ •	LIGHT POLE WITH ARM	4	FOUND CITY BENCHMARK (BM)
EM	ELECTRIC METER		PROPERTY LINE
E	ELECTRIC RISER		DENOTES BUILDING OVERHEAD
屈	ELECTRIC TRANSFORMER		EASEMENT LINE
E	ELECTRIC VAULT		1.0' CONTOUR INTERVAL
120	TELEPHONE RISER		0.5' CONTOUR INTERVAL
团	TELEPHONE VAULT	\$	HATCH DENOTES BUILDING
HV AC	HEAT PUMP		
Œ	JUNCTION BOX		HATCH DENOTES BUILDING OVERHANG
\odot	ARBORVITAE		HATCH DENOTES ASPHALT PAVEMENT
-8-	METAL BASKETBALL HOOP POLE		HATCH DENOTES CONCRETE
•	SIGN		HATCH DENOTES GRAVEL
•	BOLLARD	<u> </u>	PAVEMENT PAINT STRIPE
M	WOOD POST		CHAIN LINK FENCE UNDERGROUND WATER LINE
•	FLAG POLE		UNDERGROUND STORMDRAIN LINE
0	POLE		UNDERGROUND SANITY SEWER LINE
MB	MAIL BOX	G G	UNDERGROUND GAS LINE
Ġ	ada Parking	COMM COMM	UNDERGROUND COMM LINE OVERHEAD COMBINED UTILITY LINE
STANGE STANGE	CONIFEROUS TREE		



PORTLAND, OR 97204 P: 503-961-6440 ARCHITECTURE



EXPIRES 12/31/15

EUGENE SCHOOL DISTRICT 700 HOWARD EUGENE, OREGON KELLY MIDDLE SCHOOL

ETAILS, GENERA AND LEGENDS

15.00 REVISIONS:
2014
JAH
MBA


PROJECT NO: 1415.00 REVIS
ISSUE DATE: 05.09.2014
DRAWN JAH

C201

1. WATER LINES THAT PARALLEL SANITARY SEWER LINES SHALL BE LOCATED A MINIMUM OF 12" ABOVE SEWER LINES, WHERE SERVICES ARE NOT HORIZONTALLY SEPARATED BY 10'.

- WITHIN 5' OF A BUILDING STRUCTURE, BUILDING CODE APPROVED PIPE MATERIAL AND ¾"-0 CRUSHED ROCK BACKFILL SHALL BE USED.
- SAWCUT, REMOVE AND REPAIR EXISTING SURFACES TO MATCH EXISTING ASPHALT, CONCRETE, OR LANDSCAPING IN AREAS WHICH DO NOT RECEIVE NEW IMPROVEMENTS. PROVIDE 4" MIN DEPTH ASPHALT PAVEMENT, 4" MIN DEPTH CONCRETE PAVEMENT, OR MATCH EXISTING PAVEMENT DEPTH, WHICHEVER IS GREATER.
- 4. 36" MINIMUM FOR FIRE SERVICE PIPES UNDER AREAS TRAFFICKED BY VEHICLES. (NFPA 24, 10-4) 5. INSTALL TRACER WIRE ON ANY PIPELINE(S) CONSTRUCTED OF NON-METALLIC PIPE MATERIAL.

TYPICAL TRENCHING & BACKFILL SECTION



1. TRACER WIRE SHALL TERMINATE AT CLEANOUT. PROVIDE ENOUGH FREE WIRE TO EXTEND 24" ABOVE FINISHED GRADE TO FACILITATE TESTING. VERIFY FREE END OF WIRE IS WITHIN EASY REACH OF OPENING IN TOP SECTION.

- 2. LOCATOR PLATE 1/8" THICK STEEL PLATE, 21/2" MINIMUM DIAMETER, PERMANENTLY FASTENED TO EXTERIOR OF CLEANOUT PLUG.
- 3. COORDINATE WITH SYNTHETIC FIELD INSTALLER FOR CLEANOUT ACCESS THROUGHT SYNTHETIC
- 4. RISER PIPE SIZE:

TRENCH DRAIN WITH FRAME

TRACK SURFACE

AND AC PAVING

SECTION PER **PLANS**


SUBGRADE

AND GRATE AS SPECIFIED

TACK COAT

- 4", 6", & 8" DIA MAIN 4" DIA RISER PIPE 10" DIA & LARGER MAIN - 6" RISER PIPE
- 5. ADJUST END OF RISER PIPE TO MAINTAIN 3" MIN. AND 6" MAX. CLEARANCE BETWEEN END PIPE AND BOTTOM OF VALVE BOX LID.

SYNTHETIC FIELD DRAIN CLEANOUT (FCO)




TRACER WIRE SHALL ENTER STRUCTURE WITH RISER PIPE. PROVIDE ENOUGH FREE WIRE TO EXTEND 24" ABOVE FINISHED GRADE TO FACILITATE TESTING. VERIFY FREE END OF WIRE IS WITHIN EASY REACH OF OPENING IN TOP SECTION. 2. RISER PIPE SIZE:

4", 6", AND 8" DIA MAIN — 4" DIA RISER PIPE 10" DIA AND LARGER MAIN - 6" DIA RISER PIPE.

ADJUST END OF RISER PIPE TO MAINTAIN 3" MIN AND 6" MAX CLEARANCE BETWEEN END PIPE AND BOTTOM OF VALVE BOX LID.

STANDARD CLEANOUT (CO)




1. TRACER WIRE SHALL ENTER STRUCTURE AT PIPE INLET OR OUTLET. PROVIDE ADEQUATE FREE WIRE TO EXTEND 24" ABOVE TOP OF GRATE TO FACILITATE TESTING. COIL WIRE AND SECURE WITH NON-CORROSIVE FASTENER 2" UNDER FRAME.

LOCATION SPECIFIED ON PLAN INDICATES CENTER OF GRATED SECTION OF BASIN.

3. BACKFILL AROUND BASIN USING CRUSHED ROCK IN PAVEMENT OR SIDEWALK AREAS OR NATIVE MATERIAL IN LANDSCAPE AREAS.

4. ALL STRUCTURES SHALL BE PROVIDED WITH HEAVY DUTY GRATE WITH BICYCLE BARS

STANDARD AREA DRAIN (AD)



PIPE PENETRATION INTO MANHOLE — SEE NOTE 6 VARIES:
REFER TO ARCHITECTURA REFER TO PAVING PLAN, C151 AND ARCHITECTURAL AND GRADING PLAN FS (AS NOTED ON PLANS) 1"x12" PERFORATED FIELD DRAINAGE PIPE NOTE: REFER TO ARCHITECTURAL PLANS FOR SYNTHETIC TURF CONSTRUCTION FULL DEPTH PERIMETER
CURB, REFER TO ARCHITECTURAL PLANS 10" PERFORATED
PERIMETER DRAIN
REFER TO STORM FASTENER 2" UNDER FRAME. DRAIN PLAN, C141

> FIELD DRAINAGE TERMINATION SECTION

TRACER WIRE: WIRE SHALL ENTER STRUCTURE UNDER RISER AND DIRECTLY ABOVE THE PIPE THAT WIRE IS TRACING. PROVIDE ENOUGH FREE WIRE TO EXTEND 24" ABOVE TOP OF MANHOLE COVER TO FACILITATE TESTING. COIL WIRE AND SECURE WITH NON-CORROSIVE

2. BACKFILL AROUND BASE SECTION USING CRUSHED ROCK IN PAVED OR SIDEWALK AREAS, OR NATIVE MATERIALS IN LANDSCAPE AREAS.

42" OR, AS REQ'D, TO ACCOMMODATE PIPE SIZE AND INSTALLATION LOCATIONS/ANGLES. 4. USE SHALLOW MANHOLE WITH 2' SUMP WHERE DISTANCE BETWEEN RIM AND PIPE CROWN IS

3½' OR LESS. LOCATION SPECIFIED ON PLAN INDICATES CENTER OF BASE SECTION.

INSTALL SEAL OR GROUT, AS SPECIFIED, BETWEEN MANHOLE AND PIPE TO FORM A WATER TIGHT SEAL. PIPES TO BE TRIMMED FLUSH WITH MANHOLE INTERIOR WALL. GROUT BETWEEN TRIMMED PIPE AND MANHOLE INTERIOR WALL, AS REQ'D, TO PROVIDE A SMOOTH TRANSITION.

STANDARD STORM DRAIN MANHOLE



P: 503-961-6440

P: 541-686-8478

F: 541-345-5303 1001 SW 5TH AVENUE

TOPSOIL-12" MIN DEPTH 396.20° DRAIN ROCK NOTE 1 DRAIN ROCK UNDISTURBED EARTH

1. INSTALL GEOTEXILE LINER AT EXTENT OF SOAKAGE TRENCH DRAIN ROCK. OVERLAP SEAM BY ONE 2. FOOT AND STAPLE SEAMS AT ONE FOOT INTERVALS.

2. INSTALL 10" PERF PIPE PER PLAN.

SOAKAGE TRENCH SECTION

NO SCALE

ISOLATION JOINT AND SEALANT.

BOTH SIDES OF ENCASEMENT

PER SPECIFICATION

CRUSHED ROCK BASE 3000 PSI CONCRETE **ENCASEMENT** SEE NOTES 2 & 3 SECTION A-A

TRACER WIRE SHALL ENTER STRUCTURE AT PIPE INLET OR OUTLET. PROVIDE ENOUGH FREE WIRE TO EXTEND 24" ABOVE TOP OF GRATE TO FACILITATE TESTING. COIL WIRE AND SECURE WITH NON-CORROSIVE FASTENER 2" UNDER FRAME. CONSTRUCT CONCRETE ENCASEMENT PER MANUFACTURER RECOMMENDATIONS. PROVIDE TOOLED TRANSVERSE CONTRACTION JOINTS AT TOP AND SIDES OF CONCRETE ENCASEMENT AT CHANNEL JOINT LOCATIONS PER MANUFACTURER RECOMMENDATIONS. REFER TO

INSTALLATION FOR INSTALLATION FOR ASPHALT PAVEMENT | CONCRETE PAVEMENT

JOINTING PLAN FOR CONTRACTION JOINT DETAILS AND SEALANT. 3. CONCRETE ENCASEMENT THICKNESS SHALL BE THE GREATER OF 4" OR THE SURROUNDING PAVEMENT SLAB THICKNESS.

ΓRENCH DRAIN (TD)

SUITE 1100 - OFFICE SS PORTLAND, OR 97204

C202

ARCHITECTURE

DIGITAL SIGNATURE

EXPIRES 12/31/15

CHOOL

∠ Ø

MIDDL

CIVIL DETAILS, GENERANOTES, AND LEGENDS



EUGENE SCHOOL 850 HOWARD EUGENE, OF KELLY MIDDL

DISTRIC EGON 97404 E SCH(


AND


RTIAL SITE PLAN

5.00 REVISIONS:
DAF


ISSUE DATE: 5.21.2014
DRAWN:
CHECKED:

6 DETAIL AT 50 YRD LINE/CENTERLINE






NOTES - FIELD LAYOUTS LINE COLOR 1. SOCCER YELLOW 2. FOOTBALL WHITE **ROYAL BLUE** 3. BOYS LACROSSE 4. GIRLS LACROSS




1 OVERALL FIELD MARKINGS

1" = 50'-0"



2 SOCCER LAYOUT

1" = 50'-0"




3 FOOTBALL LAYOUT

1" = 50'-0"





EUGENE SCHOOL DISTRICT 850 HOWARD EUGENE, OREGON 97404 KELLY MIDDLE SCHO







DISTRIC-EGON 97404 E SCHC SCHOOL EUGENE, ORE

A072

NOTE: OFFSET FENCE POST W/ BALL NET SLEEVE 2'-0" MIN FENCE ASSEMBLY TRACK SURFACING SEE PLAN - AC PAVING, SEE CIVIL BALL NET SLEEVE 0 20' OC BALL NET CONC. FOUNDATION 2' - 6" MIN.

2 DETAIL - EDGE OF PAVEMENT






#5, 30"X30" 'L' AT 32" O.C.

CONTINUOUS, 32" O.C.


#5 VERTICAL,







7 PLAN DETAIL - CORNER
1 1/2" = 1'-0"




INTERSECTIONS

AND ENDS OFF

WALLS

RESOURCE BUILDING WEST ELEVATION



RESOURCE BUILDING IMEDIATE SITE PLAN


AC PAVING - SEE CIVIL

CONC SIDEWALK - SEE 5/A061

FENCE -


TRACK SURFACE

MOW STRIP




8 DOWNSPOUT BRACKET
3" = 1'-0"

5 RESOURCE BUILDING EAST ELEVATION




2 RESOURCE BUILDING PLAN

1/4" = 1'-0"



3 LONGITUDINAL SECTION

SCHOOL EUGENE, OF



2X8 PT PLATE


SHEET METAL FLASHING

3/4" PT PLYWOOD

EA. SIDE


CONTINUOUS CLEAT,

6 CMU WALL SECTION
1" = 1'-0"




4 FOOTING @ CMU WALL


1" = 1'-0"




5 FOUNDATION DETAIL AT OVERHEAD DOOR



HIGH EAVE AND DOOR HEAD 1 1/2" = 1'-0"



2 GUTTER & EAVE
1 1/2" = 1'-0"



3 EAVE @ RAKE

SCHOOI EUGENE, OI


EUGENE 850 HOWARD I

CURIS N. WILSON

SCHOOL EUGENE, OF FIELD LIGHTING PLAN E101 jeffgraper@jlgengineering.com

© JLG Engineering, LLC. 2014. The signature in this document is secured with a


digital certificate. Editing this document is prohibited. (OAR 820).



NOTE: REFER TO ARCHITECTURAL FOR DETAILED SITE PLAN.

E102





— PROVIDE NEW CIRCUIT BREAKER IN EXISTING MAIN SWITCHBOARD

EF I

2

2 E-l2l

2 E-50l



NEW PANEL FLI. SEE ONE-LINE DIAGRAM.

PANEL OVERHEAD.

ROUTE FEEDERS TO SPORTS LIGHTING CONTROL

- NEW SPORTS LIGHTING CONTROL PANEL.


SEE ONE-LINE DIAGRAM. ROUTE FEEDERS UNDER ATS, THEN OUT EAST WALL.

NORTH

- EXISTING ATS (2)

- SEE SHEET EIOI FOR CONTINUATION

- ROUTE FEEDERS TO SPORTS LIGHTING POLES THROUGH WALL. PROVIDE EXTERIOR WP LB FITTINGS, THEN RUN UNDERGROUND TO POLES. SEE SHEET EIOI
- LITHONIA ZL2N-L48-3000LM-MDD-MV0LT 4000K 80CRI WH LENSED STRIP. CONNECT TO LOCAL SWITCHING.



UTILITY BLDG - ELEC PLAN 2

SCALE: 1/4" = 1' 0"

EXISTING PANELS





- PROVIDE NEW 225/3 IN EXISTING SPACE FOR NEW PANEL FLI.
- LITHONIA VGR4C-40LED-41-GL-MVOLT-DDBT-PE-TRS-LPI WALL MOUNT WITH INTEGRAL PC. CONNECT TO 20/I CIRCUIT WITH RECEPTACLES.

PARTIAL ONE-LINE DIAGRAM \E1Ø2 NOT TO SCALE

© JLG Engineering, LLC. 2014. The signature in this document is secured with a digital certificate. Editing this document is prohibited. (OAR 820).

SYMBOLS & ABBREVATIONS

NEW CONCEALED RACEWAY AND WIRE. NUMBER OF

THAN TWO. SIZE OTHER THAN #12 AS NOTED.

(APPLIES TO ALL WIRING SYMBOLS)

PANELBOARD OR ELECTRICAL CABINET

DUPLEX RECEPTACLE - "WP"=WEATHERPROOF,

SPORTS LIGHTING POLE AND LUMINAIRES

"P"= W/PILOT LIGHT, "2"= DOUBLE POLE, "3"=

THREE-WAY, "M"= AUTOMATIC WALL SWITCH, "D"=

DIMMING SWITCH "TS" = DIGITAL TIMER SWITCH

EQUIPMENT IDENTIFIER, EXHAUST FAN I SHOWN

"GFI"=GROUND FAULT INTERRUPTER TYPE, "+n"= MOUNTING HEIGHT, "a"=CIRCUIT a, "ISO"= WITH ISOLATED GROUND, "SRG"= WITH SURGE SUPPRESSION, "TP"= TAMPER PROOF

SWITCH: "a"= CIRCUITS CONTROLLED, "K"= KEY SWITCH,

DISCONNECT SWITCH

COVER, "L"= LOCKING

SHEET REFERENCE NOTE

ROOM NUMBER

PLAN OR DETAIL NUMBER SHEET NUMBER

EXISTING WORK SHOWN LIGHT

NEW WORK SHOWN BOLD

SLASHES INDICATES NUMBER OF CONDUCTORS IF MORE

UNDERGROUND OR UNDERFLOOR WIRING SHOWN DASHED.