

**SOUTH EUGENE HIGH SCHOOL
TENNIS COURT RELOCATION
Eugene Public School District 4J
C.I.P. Project No. 410.566.001**

**Addendum No. 1
September 12, 2014**

Cameron McCarthy Landscape Architecture and Planning
160 East Broadway
Eugene, OR 97401
(541) 485-7385 FAX (541) 485-7389
Contact: Larry Gilbert, ASLA

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents as noted below. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the bidder to disqualification.

GENERAL

1. Pre-bid sign in sheet, attached.

SPECIFICATIONS

2. 01 11 00 – Summary of Work
 - A. Item 1.02(A)1 – Change project location to read “400 E. 19th Ave, Eugene, OR, 97401”.
3. 32 13 13 – Concrete Paving
 - A. Item 2.06(E) – Delete rubber cushion.
 - B. Item 3.09(C)3 – Change finish at tennis courts to read “Medium broom finish”.
 - C. Clarification – At concrete to receive tennis court surfacing no curing compounds shall be used as indicated in Item 2.06(D). Concrete receiving tennis court surfacing shall cure naturally for required duration.
4. 32 31 13 – Chain Link Fences and Gates
 - A. Item 2.02(E) – Change chainlink fence fabric from 2 inch diamond mesh to 1-3/4 inch diamond mesh.

DRAWINGS

5. Sheet L5.0 – Site Details
 - A. Detail 6 Chainlink Fence at Tennis Court: Change maximum spacing of fence posts to “10 feet max – equal spacing”.
 - B. Detail 6 Chainlink Fence at Tennis Court: Change footing depth as follows:
 1. Concrete footings at fence posts behind the ball wall to be 8 feet deep x 1 foot diameter.
 2. Concrete footings at all other fence posts to be 6 feet 4 inches deep x 1 foot diameter.

END OF ADDENDUM

