# ELLIS PARKER SECURITY FENCING AND RETAINING WALL WATERPROOFING 2015

C.I.P. # 420.176.108

**ARCHITECT** 

LOREN BERRY ARCHITECT
41601 MADRONE STREET
SPRINGFIELD, OREGON 97478
(541) 896-3692 FAX (541) 896-0231
LOREN BERRY, AIA
Iberry@berryarch.com

#### **OWNER**


4j SCHOOL DISTRICT 200 NORTH MONROE STREET EUGENE, OREGON 97401 (541) 790-7430 DON PHILPOT

## CIVIL ENGINEERING

BRANCH ENGINEERING INC. 310 5TH STREET SPRINGFIELD, OREGON 97477 (541) 746-0637 FAX: (541) 746-0389 Rick Hernandez, P.E., S.E. rickh@branchengineering.com

# **ELECTRICAL DESIGN**

SYSTEMS WEST ENGINEERS INC.
411 HIGH STREET
EUGENE, OREGON 97401-2427
(541) 342-7210 FAX: (541) 342-7220
JEFF GRAPER
jgraper@systemswestengineers.com



# SITE PLAN - ELLIS PARKER ELEMENTARY

3875 KINCAID STREET EUGENE, OR 97405

# PROJECT DESCRIPTION

METAL SECURITY FENCE
WITH UTILITY & EGRESS GATES
CONCRETE STARE & WATERPROOFING


### **BUILDING DATA - TYPICAL**

CODES: 2014 STRUCTURAL SPECIALTY CODE 2014 OREGON FIRE CODE

FIRE SPRINKLER: OCCUPANT LOAD: NO NO CHANGE

CONSTRUCTION TYPE: OCCUPANCY TYPE: V GROUP F

## DRAWING SYMBOLS




#### **ABBREVIATIONS**

Horizontal


&	And	OC	On Center
&@J ~	At	OFCI	Owner Furnished Contractor Installed
q_	Center Line	OF	Outside Face
~ #	Diameter or Round Pound or Number	DVALT	
		PVMT	Pavement
AB	Anchor Bolt	REINF	Reinforce(d),(ing)
AC	Asphalt Concrete	REQD	Required
AD ADD	Area Drain Addendum	REV	Revision
ALT	Alternate		
ARCH	Architectural	TOC	Top of Concrete
		TOC	Top of Concrete
ВО	By Owner	TOP	Top of Pavement
CJ	Control Joint	TOS	Top of Slab
CLR	Clear	TOW	Top of Wall
CO	Clean out	TYP	Typical
CTR		LINIO	
CIR	Center	UNO	Unless Noted Otherwise
DIA	Diameter	VERT	Vertical
DIM	Dimension	VEY	Verify
DTL	Detail	V.I.F.	Verify In field
DWG	Drawing		
	2	W	West
		W/	With
(E)	Existing	W/O	Without
EA	Each		
EJ	Expansion Joint		
EQ	Equal		
FTG	Footing		
GALV	Galvanized		
GND	Ground		
GR	Grade		

# DRAWING INDEX GENERAL TITLE SHEET T2.0 EGRESS DIAGRAM CSMP COVER SHEET CSMP PLAN SHEET CIVIL PLAN ARCHITECTURAL A1.0 REFERENCE PLAN A2.0 RETAINING WALL & WATERPROOFING PLAN A2.1 RETAINING WALL & WATERPROOFING DETAILS A2.2 ENLARGED PLANS A2.3 ENLARGED PLANS A2.4 ENLARGED PLANS A3.0 | FENCE ELEVATIONS A4.0 DETAILS A4.1 | DETAILS & SCHEDULES ELECTRICAL

ELECTRICAL PLAN SYMBOLS & SCHEDULES



VICINITY MAP



(p) 541-896-3692 (f) 541-896-0231

en Berry Archite

LIS PARKER SECURITY FENCING AND
ETAINING WALL WATERPROOFING 2015
C.I.P. # 420.176.108

PROJECT NUMBER 1504

DRAWN SRN

CHECKED LRB

DATE 5/4/2015

REVISIONS


No. Description Date

T1.0

SHEET NUMBER

Architect

© LorenBerry Architect



#### PROJECT LOCATION

3875 KINCAID STREET EUGENE, OREGON LATITUDE =  $44^{\circ}$  00' 50" N  $LONGITUDE = 124^{\circ} 04' 30'' W$ 

#### PROPERTY DESCRIPTION

LANE COUNTY TAX MAP 18-03-08-43 TAX LOT 7400 TAX ACCOUNT 0660587

#### OWNER/APPLICANT

EUGENE SCHOOL DISTRICT 4J CONTACT: DON PHILPOT PHONE: (541) 790-7430

#### **ENGINEERING**

BRANCH ENGINEERING, INC. CONTACT: LANE BRANCH 310 5TH STREET SPRINGFIELD, OR 97477 PHONE: (541) 746-0637 FAX: (541) 746-0389

#### SCHEDULE

NATURE OF CONSTRUCTION ACTIVITY

- AND ESTIMATED TIME TABLE \* DEMOLITION/CLEARING — SPRING 2015
- \* MASS GRADING SPRING 2015
- \* FINAL STABILIZATION SUMMER 2015

#### **EROSION AND SEDIMENT CONTROL NARRATIVE**

1. PROPOSED CONSTRUCTION ACTIVITY

- THE PROJECT ADDRESSED BY THIS EROSION AND SEDIMENT CONTROL PLAN CONSISTS OF REMOVAL AND REPLACEMENT OF A CONCRETE SIDEWALK AND STAIRWAY AND UNDERLYING FILL TO FACILITATE WATERPROOFING IMPROVEMENTS TO AN EXISTING BASEMENT WALL. NO STRUCTURES ARE PROPOSED TO BE ADDED OR DEMOLISHED.
- 2. SITE TABULATIONS AREA OF DISTURBANCE = 0.38 ACRES
- 3. EXCAVATION AND FILL (ESTIMATE: CONTRACTOR TO VERIFY) FILL: 300 CY±
- **4. SOIL TYPES**THE NRCS SOILS SURVEY INDICATED THIS SOIL TYPE AT THE PROJECT SITE: (127C) HAZELAIR — DIXONVILLE URBAN LAND COMPLEX
- 5. MAINTENANCE OF EROSION CONTROL MEASURES THE EROSION CONTROL MEASURES DESCRIBED ON THIS PLAN ARE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING THE CONSTRUCTION PERIOD, THESE MEASURES SHALL BE UPGRADED AS NEEDED TO 1.) ENSURE THAT SEDIMENT DOES NOT LEAVE THE SITE, AND 2.) ENSURE EXISTING VEGETATION ON SITE SHALL BE PRESERVED UNTIL ALL GRADING IS COMPLETE. THE INSTALLED MEASURES SHALL BE INSPECTED DAILY BY THE CONTRACTOR AND MAINTAINED. ENHANCED AND/OR UPGRADED AS NECESSARY TO ENSURE THEIR CONTINUED FUNCTIONING.
- THE SITE CURRENTLY CONTAINS AN ELEMENTARY SCHOOL BUILDING, PAVED PARKING LOT AND
- A WRITTEN RECORD OF INSPECTIONS FOR AN ACTIVE SITE SHALL BE KEPT ON SITE AND MADE AVAILABLE UPON REQUEST TO D.E.Q., ITS AGENT, OR LOCAL MUNICIPALITY.

#### CITY OF EUGENE SPECIFIC ESP NOTES


THE PERSON RESPONSIBLE FOR IMPLEMENTATION OF THE CSMP AND MAINTENANCE OF THE

2. THE PERSON RESPONSIBLE FOR IMPLEMENTATION OF THE BMPS AND PROVIDING FOR ANY NEEDED SITE STABILIZATION DURING THE PERIODS OF NO CONSTRUCTION:

#### (TO BE DETERMINED)

- 3. THE CONTRACTOR SHALL PROVIDE THE FOLLOWING: A. CONSTRUCTION SCHEDULE B. STAGING INFORMATION C. ADDITIONAL BMP AS NEEDED
- 4. A CONSTRUCTION SCHEDULE WILL BE PROVIDED BY THE CONTRACTOR
- 5. ADDITIONAL BMP TO BE IMPLEMENTED DURING WET WEATHER.

PER CITY OF EUGENE STANDARDS.




#### CITY OF EUGENE CONSTRUCTION SITE MANAGEMENT PLAN (CSMP) GENERAL NOTES


- PRIOR TO ANY GROUND DISTURBANCE ON THE SITE ONE INSPECTION WITH EROSION PREVENTION STAFF IS REQUIRED.
- 2. THE CONSTRUCTION SITE MANAGEMENT PLAN DOES NOT AUTHORIZE CONSTRUCTION ACTIVITIES. GRADING, BUILDING, PEPI, AND OTHER PERMITS MAY BE REQUIRED. ALL OTHER NECESSARY
- 3. ISSUANCE OF AN EROSION PREVENTION PERMIT APPROVES PROTECTION MEASURES, NOT CONSTRUCTION OR GROUND DISTURBING ACTIVITIES. IT DOES NOT RELIEVE THE PERMIT HOLDER AND/OR THE CONTRACTOR FROM OTHER PERMITTING REQUIREMENTS.
- 4. CONSTRUCTION SHALL CONFORM TO THE CURRENT EDITION OF THE CITY AMENDED OREGON STANDARD SPECIFICATIONS FOR CONSTRUCTION AND CITY STANDARD DRAWINGS \* (\*REQUIRED FOR PUBLIC IMPROVEMENT PROJECTS ONLY).
- 5. EROSION AND SEDIMENT CONTROL MEASURES, AND OTHER NATURAL RESOURCE PROTECTION FENCING AND BARRIERS, SHOWN ON THE CSMP ARE THE MINIMUM REQUIREMENTS FOR ANTICIPATED SITE CONDITIONS. DURING CONSTRUCTION, MEASURES SHALL BE UPGRADED, AS NEEDED OR AS DIRECTED BY THE CITY INSPECTOR.
- IMPLEMENTATION OF THE CSMP, INCLUDING CONSTRUCTION, MAINTENANCE, REPLACEMENT, AND UPGRADING OF EROSION AND SEDIMENT CONTROL MEASURES AND PROTECTION FENCING, IS THE RESPONSIBILITY OF THE PERMIT HOLDER AND/OR THE CONTRACTOR UNTIL ALL CONSTRUCTION IS COMPLETED AND VEGETATION/LANDSCAPING IS ESTABLISHED AND APPROVED.
- BOUNDARIES OF THE CLEARING AND GRADING LIMITS SHOWN ON THIS PLAN SHALL BE CLEARLY FLAGGED IN THE FIELD PRIOR TO CONSTRUCTION, DURING CONSTRUCTION, NO DISTURBANCE BEYOND THE FLAGGED CLEARING AND GRADING LIMITS SHALL BE PERMITTED. THE FLAGGING SHALL BE MAINTAINED BY THE PERMIT HOLDER AND/OR THE CONTRACTOR FOR THE DURATION OF CONSTRUCTION. IN ADDITION, WETLAND AND RIPARIAN AREAS SHALL BE IDENTIFIED AND PROTECTED WITH APPROPRIATE FENCING AS NOTED ON CSMP PRIOR TO CONSTRUCTION AND SHALL NOT BE DISTURBED UNLESS THE PROPER PERMITS ARE OBTAINED.
- 8. EROSION AND SEDIMENT CONTROL MEASURES SHOWN ON THIS CSMP MUST BE CONSTRUCTED IN CONJUNCTION WITH ALL CLEARING AND GRADING ACTIVITIES, IN SUCH A MANNER AS TO ENSURE THAT SEDIMENT AND SEDIMENT LADEN WATER DOES NOT ENTER THE STORMWATER SYSTEM, ROADWAYS, ADJACENT PROPERTY OR VIOLATE APPLICABLE WATER QUALITY STANDARDS. WHEN DESIGNING AND IMPLEMENTING MEASURES, THE PERMIT HOLDER AND/OR THE CONTRACTOR SHALL CONSIDER THE SEASONAL VARIATION OF RAINFALL, TEMPERATURE, AND OTHER CLIMATIC FACTORS RELATIVE TO THE TIMING OF LAND DISTURBANCE ACTIVITIES.
- EROSION AND SEDIMENT CONTROL MEASURES ON ACTIVE SITES SHALL BE INSPECTED AND MAINTAINED DAILY AND WITHIN 24 HOURS AFTER ANY STORM EVENT GREATER THAN 0.5 INCHES OF RAIN PER 24 HOUR PERIOD. ANY REQUIRED REPAIRS OR ADJUSTMENTS SHALL BE MADE IMMEDIATELY. THE EROSION AND SEDIMENT CONTROL MEASURES ON INACTIVE SITES SHALL BE INSPECTED A MINIMUM OF ONCE EVERY MONTH AND/OR WITHIN 48 HOURS FOLLOWING STORM EVENTS. ADDITIONALLY, SITES COVERED UNDER DEPARTMENT OF ENVIRONMENTAL QUALITY (DEQ) PERMITS (1200-C, 1200-CN) MUST COMPLY WITH THOSE PERMIT MONITORING AND RECORD-KEEPING REQUIREMENTS.
- 10. During the wet weather season (october 15 to april 30), all exposed soil and stockpile areas shall be covered, or otherwise protected by a facility (or COMBINATION OF FACILITIES) THAT RESULT IN NO STORMWATER RUNOFF LEAVING THE SITE DURING A 5-YEAR STORM EVENT. FOR DEVELOPMENT SITES OVER 40 ACRES, THE DESIGN STORM SHALL BE A 10-YEAR STORM EVENT CONSISTENT WITH AN APPROVED CSMP
- 11. ALL ADJACENT PROPERTIES, WATER FEATURES, AND RELATED NATURAL RESOURCES ARE TO BE KEPT FREE OF DEPOSITS OR DISCHARGES OF SOIL, SEDIMENT OR CONSTRUCTION—RELATED MATERIAL FROM THE CONSTRUCTION SITE.
- 12. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE PROTECTED FROM DAMAGE AT ALL TIMES. EROSION CONTROL MEASURES SHALL REMAIN IN PLACE UNTIL VEGETATION HAS BEEN ESTABLISHED AND THE SITE IS PERMANENTLY STABILIZED. ANY MEASURES THAT ARE DAMAGED OR DESTROYED SHALL BE REPAIRED OR REPLACED IMMEDIATELY.
- 13. STABILIZE ALL DISTURBED AREAS WITHIN 50 FEET OF WATERWAYS, WETLANDS OR OTHER SENSITIVE AREAS WITHIN 7 DAYS OF EXPOSURE.
- 14. STREETS ADJACENT TO CONSTRUCTION ENTRANCES AND ALONG HAUL ROUTES SHALL BE SWEPT AS NEEDED OR WHEN DIRECTED BY THE CITY INSPECTOR TO ENSURE PUBLIC RIGHTS-OF-WAY ARE KEPT CLEAN AND FREE OF DEBRIS.
- 15. WHEN TRUCKING SATURATED SOILS TO OR FROM THE SITE, EITHER WATER-TIGHT TRUCKS SHALL BE USED OR LOADS SHALL BE DRAINED PRIOR TO TRANSPORT UNTIL DRIPPING HAS BEEN REDUCED TO NO MORE THAN ONE GALLON PER HOUR. SEDIMENT LADEN WATER WILL NOT BE ALLOWED TO ENTER THE STORMWATER SYSTEM.
- 16. EXTRACTED GROUND WATER FROM EXCAVATED TRENCHES SHALL BE DISPOSED OF IN A SUITABLE MANNER WITHOUT DISCHARGING SEDIMENT TO ADJACENT PROPERTIES, THE CITY'S STORMWATER SYSTEM, WATER FEATURES, OR RELATED NATURAL RESOURCES. DEWATERING SYSTEMS SHALL BE DESIGNED AND OPERATED SO AS TO PREVENT REMOVAL OF THE NATURAL SOILS AND SO THAT THE GROUNDWATER LEVEL OUTSIDE THE EXCAVATION IS NOT REDUCED TO THE EXTENT THAT WOULD DAMAGE OR ENDANGER ADJACENT STRUCTURES OR PROPERTY. APPROVAL OF THE DEWATERING SYSTEM DOES NOT GUARANTEE THAT IT WILL MEET THE OUTCOMES OR BE ACCEPTABLE FOR USE IN ALL SITUATIONS. MODIFICATIONS TO THE SYSTEM WILL BE REQUIRED IF THE OUTCOMES CANNOT BE MET. AT NO TIME WILL SEDIMENT LADEN WATER BE ALLOWED TO LEAVE THE CONSTRUCTION SITE.
- 17. A SUPPLY OF MATERIALS NECESSARY TO MEET THE OUTCOMES AND IMPLEMENT THE CSMP OR OTHER EROSION PRACTICES UNDER ALL WEATHER CONDITIONS SHALL BE MAINTAINED AT ALL TIMES ON THE CONSTRUCTION SITE.
- NO HAZARDOUS SUBSTANCES, SUCH AS PAINTS, THINNERS, FUELS AND OTHER CHEMICALS SHALL BE RELEASED ONTO THE SITE, ADJACENT PROPERTIES, OR INTO WATER FEATURES, THE CITY'S STORMWATER SYSTEM, OR RELATED NATURAL RESOURCES.
- 19. NO DISCHARGE INTO THE CITY'S STORMWATER SYSTEM OR RELATED NATURAL RESOURCES OF CONSTRUCTION RELATED CONTAMINANTS RESULTING FROM ACTIVITIES SUCH AS, BUT NOT LIMITED TO, CONCRETE SAWING, CLEANING OR WASHING OF EQUIPMENT, TOOLS, OR VEHICLES, SHALL OCCUR.
- 20. ALL WORK PERFORMED BY UTILITY COMPANIES FOR THIS PROJECT, INCLUDING PLACEMENT OF APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES, FINISHED GRADING, SEEDING. MULCHING AND CLEAN UP IS GOVERNED BY THE CONDITIONS AND REQUIREMENTS OF THIS CSMP. COMPLIANCE WITH THESE REQUIREMENTS IS THE RESPONSIBILITY OF THE PERMIT HOLDER.

#### RATIONAL STATEMENT


A COMPREHENSIVE LIST OF AVAILABLE BEST MANAGEMENT PRACTICES (BMP) OPTIONS BASED ON DEQ'S GUIDANCE MANUAL HAS BEEN REVIEWED TO COMPLETE THIS EROSION AND SEDIMENT CONTROL PLAN. SOME OF THE ABOVE LISTED BMPs WERE NOT CHOSEN BECAUSE THEY WERE DETERMINED TO NOT EFFECTIVELY MANAGE EROSION PREVENTION AND SEDIMENT CONTROL FOR THIS PROJECT BASED ON SPECIFIC SITE CONDITIONS INCLUDING SOIL CONDITIONS, TOPOGRAPHIC CONSTRAINTS, ACCESSIBILITY TO THE SITE, AND OTHER RELATED CONDITIONS. AS THE PROJECT PROGRESSES AND THERE IS A NEED TO REVISE THE ESC PLAN. AN ACTION PLAN WILL BE SUBMITTED.



NOT TO SCALE



NOT TO SCALE



ME H Erevisions:

E

civil • transportation

structural • geotechnical

SURVEYING

310 5th Street

Springfield, OR 97477

p: 541.746.0637 f: 541.746.0389

www.BranchEngineering.com

Springfield OR | Salem OR

EXPIRES: DECEMBER 31, 2015


project title:


MAY 1, 2015 drawn by: designer:

15-075 project no: **CSMP** 

**COVER SHEEET** 

copyright © 2015 Branch Engineering, Inc.





#### CONSTRUCTION NOTES

- PROVIDE CATCH BASIN DROP-IN SEDIMENTATION INSERT IN STORM DRAIN FACILITY PER DETAIL, SHEET EC-I. CONTRACTOR TO VERIFY LOCATIONS OF INDICATED DRAINS.

copyright © 2015 Branch Engineering, Inc.

- 181) TEMPORARY CONSTRUCTION ACCESS ROUTE.
- (182) CONSTRUCT GRAVEL ENTRANCE & EXIT, PER DETAIL, SHEET EC-I
- 183 CONSTRUCT WASHOUT AREA, PER DETAIL, SHEET EC-I
- CONSTRUCT SEDIMENTATION BARRIER AROUND STOCKPILE PER DETAIL, SHEET EC-I.
  PROVIDE TEMPORARY GRADE TO DIVERT UNCONTAMINATED FLOWS AROUND STOCKPILE

civil • transportation structural • geotechnical S U R V E Y I N G

310 5th Street Springfield, OR 97477 p: 541.746.0637 f: 541.746.0389 www.BranchEngineering.com Springfield OR | Salem OR EXPIRES: DECEMBER 31, 2015

project title:

revisions:

MAY 1, 2015


15-075


**CSMP** 

(CAID OREG


PLAN SHEEET

EC2







PROJECT NUMBER 1504 5/4/2015 No. Description Date





PROJECT NUMBER 1312 No. Description Date





LOREN R. BERRY
EUGENE, DREGON
FOR OF ORKERS

(p) 541-896-3692 (f) 541-896-0231

orenBerryArchi

ELLIS PARKER SECURITY FENCING AND
RETAINING WALL WATERPROOFING 2015
C.I.P. # 420.176.108

PROJECT NUMBER 1504

DRAWN SRN

CHECKED LRB


DATE 5/4/2015


REVISIONS


No. Description Date

SHEET NUMBER


A2.2







PROJECT NUMBER 1312 5/4/2015 No. Description Date






PROJECT NUMBER 1504

5/4/2015 No. Description Date

SHEET NUMBER


A3.0



PROJECT NUMBER 1504 SRN LRB 5/4/2015 REVISIONS No. Description Date

SHEET NUMBER

A4.0



SCALE: 3'' = 1'-0''

SCALE: 3'' = 1'-0''

0

9 9 PARKER SECURITY FENCIN

SCHEDULES

DETAILS &


PROJECT NUMBER 1504 DRAWN 5/4/2015

CHECKED DATE REVISIONS No. Description Date

SHEET NUMBER

SCALE: 3'' = 1'-0''

A4.1



PROJECT NUMBER 1504 JLG JLG 5/1/2015