

Date: May 11, 2018
To: Plan Holders

Company: Eugene School District 4J
Project: **Awbrey Park & Spring Creek ES Concrete Walk & SD Replacement
C.I.P. 420.109.108**

Subject: Addendum #2

From: Roberts Consulting & Engineering
3220 Tilden Street, Suite A
Eugene, OR 97404

The following deletions and additions are
hereby made a part of Quotations and Contract Documents, effective this date.

CLARIFICATIONS AND ANSWERS TO QUESTIONS:

Items:

1. Per paving notes and jointing detail 6/C1.1 all new concrete work are to be doweled to adjacent concrete flatwork.

DRAWINGS

Items:

1. Drawing Sheet C2.1 and C5.0, Paving Plans:

New concrete flat work to be reinforced. Replace PAVING LEGEND concrete walk section with:

CONCRETE PAVEMENT SECTION

6" THICK - 3,000 PSI CONCRETE OVER

3" 3/4"-0 MIN CRUSHED ROCK BASE OVER

PROOF-ROLLED SUBGRADE

TRANSVERSE REINFORCEMENT : #4 BARS 16" OC

LONGITUDINAL REINFORCEMENT: #4 BARS 16" OC

MIN 3" CONCRETE COVER SURROUNDING ALL REINFORCING

ATTACHMENTS:

Email:

*Owner
Oregon Plan Centers & Exchanges (8)
City of Eugene Permit & Information Center*