FULLER MIDDLE SCHOOL FEASIBILITY STUDY

City Council Meeting February 6, 2018



Agenda

- 1. Introductions
- 2. Feasibility Study Scope
- 3. MSBA Process and Schedule
- 4. Existing School Conditions
- 5. Educational Programming
- 6. Pre-Concept Options
- 7. Next Steps
- 8. Questions



Introductions



School Building Committee Members

Charlie Sisitsky Co-Chair, Board of Selectmen Dr. Edward Gotgart Co-Chair, Chief Operating Officer, FPS Chris Walsh State Representative **Town Manager** Robert Halpin Superintendent of Schools Dr. Robert Tremblay Heather Connolly School Committee Chair **Richard Finlay** School Committee Member and Convenor **David Miles** Finance Committee Member Mary Ellen Kelley **Chief Financial Officer** Jennifer Pratt **Chief Procurement Officer** Dr. Sonia Diaz Chief Academic Officer FPS Matt Torti Director of Buildings and Grounds, FPS



School Building Committee Members (continued)

Jose Duarte Principal, Fuller Middle School Teacher, Fuller School Middle Caitlin Stempleski Patrick Johnson Principal, Walsh Middle School Principal, Woodrow Wilson School John Haidemenos **Michael Tusino Building Commissioner** Member **Richard Weader II** Michael Grilli Member Dr. Jennifer Krusinger Martin Member Donald Taggart III Member **David Panich** Member **Thomas Barbieri** Member Dr. Dale Hamel Member

Jonathan Levi Architects

Architect

Jonathan Levi Architects

Owner's Project Manager (OPM)

Symmes Maini and McKee Associates



Feasibility Study Scope, Process and Schedule



Massachusetts School Building Authority

- MSBA is an independent public authority that administers and funds a program for grants to eligible cities, towns, and regional school districts for school construction and renovation projects.
- MSBA mandates a multi-step rigorous study and approval process
- **MSBA** will fund **57.05%** plus incentives of eligible project cost for an approved project if accepted by the voters of Framingham

JLA Jonathan Levi Architect

PROJECT MANAGEMENT

Feasibility Study Scope


The MSBA has agreed to participate with Framingham in a feasibility study for a 630 Student Middle School for Grades 6-8. Scope items include:

- Program of Architectural Spaces to be included
- Existing Conditions Review
- Design Alternatives
 - Renovation
 - Renovation / Addition
 - All New Construction
- Cost Estimates

JAA Jonathan Levi Architect:

PROJECT MANAGEMENT

MSBA Feasibility Study Process and Schedule





PROJECT MANAGEMENT

Completed Project Milestones

November 2011	Framingham Submits Proposal to MSBA
February 2013	Pre-Feasibility Study Completed
<u>April 2016</u>	Historic Enrollments Study Completed
June 2016	K-8 Educational Visioning Completed
October 2016	Framingham Town Meeting approves Feasibility Study Funding
December 2016	Framingham and MSBA Agree on
	Student Design Enrollment
February 2017	MSBA Invites Framingham to Feasibility Study
June 2017	Framingham Retains Owner's Project Manager
September 2017	Framingham Retains Architect
November 13, 20	17 Community Forum No. 1
November 27, 20	17 Community Forum No. 2
December 20, 20	17 Preliminary Design Program Submitted



Defining the Need



The Need:

- Need a long-term solution to resolve deteriorating school building
- Provide educational spaces to meet MSBA standards
- Update the layout to meet 21st century Visioning Session goals

The Goal

 Cost Effective, Safe, Code-Compliant School Framingham can be proud of



EXISTING FULLER SCHOOL ROOM SIZES





Existing School Conditions



A 2013 Pre-Feasibility Study by Bargmann Hendrie + Archetype Inc concluded that "Fuller Middle School, constructed as Framingham High School in 1958, while well maintained, has reached the end of its useful life."

More recently, JLA and their team of consulting engineers have provided additional inspection to determine what work would be required to bring the Fuller up to current building codes and standards.



PROJECT MANAGEMENT

EXISTING CONDITIONS AT FULLER SCHOOL

Energy Code:

The building was designed and built with almost no insulation on the floors, walls, or roof. The windows are typically single glazed. New work would need to comply with current codes, which would save substantial \$\$ in ongoing annual energy costs.



Jonathan Levi Architects

PROJECT MANAGEMENT

<u>Accessibility</u>

Most entries from the outside are noncompliant. The Auditorium floor is too steep, lacks landings, and has no accessible route from the seats to the stage.





PROJECT MANAGEMENT

EXISTING CONDITIONS AT FULLER SCHOOL

Structural:

Much of the structural concrete floor and gypsum roof deck is degrading and would need to be replaced. To meet current earthquake code, the entire roof would need to be replaced with steel deck and steel brace frames installed at the walls.



PROJECT MANAGEMENT

EXISTING CONDITIONS AT FULLER SCHOOL

<u>Mechanical Electrical,</u> <u>Plumbing,Fire</u> <u>Protection</u>

Systems typically have outlived their intended useful life. Boilers were installed in 2003, so have been used for over half of their expected useful service life. The building is not sprinklered. To comply with current code, it would need to be fully sprinklered and have a new fire alarm



PROJECT MANAGEMENT

Hazardous Materials

Typical of older buildings, there are concealed hazmats. While these materials do not pose a problem as long as they are undisturbed, they will need to be identified and disposed of properly as part of a renovation project.






PROJECT MANAGEMENT

Educational Programming



Programming



Jonathan Levi Architects

PROJECT MANAGEMENT

Landscape Analysis





Urban Analysis



Campus Analysis





Construction Phase Swing Space Options

Assumption: 530 students, Approx. 80,000sf Minimum

- A Move students to TBD School or Town Property
- B Move students to either all or portion of Farley
- C Move students to temporary modular facility on site
- D Retain students in reduced footprint portion of Fuller with temporary renovation
- E Retain students in Fuller as is (new building between Fuller and Farley)




Fuller Swing Space Test Fit






Farley Swing Space Test Fit











PROJECT MANAGEMENT






PROJECT MANAGEMENT






PROJECT MANAGEMENT






PROJECT MANAGEMENT





PROJECT MANAGEMENT






PROJECT MANAGEMENT





PROJECT MANAGEMENT





PROJECT MANAGEMENT

Pre-Concept Options Evaluation Matrix

Voted to be Removed from Consideration by School Building Committee

-o- Neutral

RATINGS:

+

- Disadvantageous

Advantageous


Very Disadvantageous

	<u>Option 0.0</u> Repair to Code Baseline	<u>Option 0.1</u> Renovation	<u>Option A</u> Add / Reno	<u>Option B.1</u> Tree Branch Add / Reno	<u>Option B.2</u> Tree Branch New Constr.	<u>Option C.1</u> Folded Hands Add / Reno	<u>Option C.2</u> Folded Hands New Constr.	<u>Option D</u> Butterfly New Constr.	<u>Comments</u>
Project Criterion									
Total Project Cost	-		-	-	-0-	-	+	+	See costs below
Schedule			-	-	+	÷	+		Renovation options will require phasing and additional construction time. Swing space requires additional time
Swing Space or Occupied Construction			-	-	+	Ŧ	+	+	New school outside existing footprint requires no swing space
Construction Impact to Education			-	-	+	-0-	+	+	Swing space will be disruptive and smaller than current Fuller use
Construction Impact to Campus and Neighbors	-0-	-0-	-0-	-0-	-0-	-0-	-0-	-0-	Swing space / trailers will be disruptive to neighbors. New Construction on east will require temporary parking
Educational Program Accommodation		-	-0-	+	+	+	+	+	Options vary on ability to provide 3 appropriate cohort locations and identity
Flexibility		-	-	+	+	÷	+		New construction would be designed for flexible use and improved MEP accessibility
Open Space /Building Massing / Footprint		÷	-	-0-	+	-0-	+		Options built on east parking would open very large and flexible open area on existing Fuller footprint
Academic Campus Coordination	-	Ŧ	-	+	+	÷	+	+	Locating Fuller closer to Farley and McCarthy improves ability to create identifiable campus
Natural Light and Views			-0-	-0-	+	÷	+	+	"Pancake" massing creates interior rooms with limited access to windows
Risk		Ъ.	-	-	+	-0-	+	+	Options requiring renovation and/or swing space have more inherent risk due to unforeseen conditions
Community Use	-0-	÷	+	÷	+	+	+	+	All alternatives allow community use. New Construction options allow increased access to playfields.
Total GSF	195,000	163,000	160,000	164,000	155,000	149,000	145,000	145,000	
Swing Space Cost (\$Million)	\$6	\$6	\$6	\$6	\$0	\$0	\$0	\$0	Option 0 and 0.1 would require swing space at Farley. Options A and B.1 could have swing space in Fuller. Other options require no swing space.
Order of Magnitude Project Cost (\$Million)	\$133	\$123	\$114	\$116	\$95	\$107	\$89	\$89	This existing building is particularly expensive to renovate due to its construction assembly and degree of deterioration
MSBA Share	\$0	\$54	\$49	\$50	\$43	\$45	\$41	\$41	
Framingham Share	\$139	\$75	\$71	\$72	\$52	\$62	\$48	\$48	



PROJECT MANAGEMENT

Alternatives in Development




OPTION 0.0 - EXISTING

0.0 'Repair Existing': Minimum required repairs and code upgrades to the existing structure




OPTION A - ADD/RENO

A 'Addition/Renovation': Retention and Upgrade of existing auditorium, gymnasium/locker and cafeteria areas. Conversion of existing calleria to multi-use dining and learning. Addition of new attached two story classroom and administration wing at front and east of existing cafeteria. Swing space required.




OPTION C.1 - FOLDED HANDS ADD/RENO

C.1 'Folded Hands Addition/Renovation: Retention and renovation of existing gymnasium/locker room only. Remaining scope to be attached new Inree story split level entry construction with stepped convertible commons/jouditorium/cateteria and balconyaccessed classrooms. Occupied phased construction required.




OPTION 0.1 - ADD/RENOVATION

0.1 'Addition/Renovation : Partial demolition of surplus floor areas and complete gut renovation and reconstruction of remaining areas to meet code and to address, as best as possible, the educational program. The later includes conversion of the existing cafeteria into a multi-use dining and learning space. Swing space required.




B.1 'Iree Branches Addition/Renovation': Retention and renovation of existing auditorium and gymasium/locker room, Remaining scope to be attached new two stary construction with central learning commons/cafeteria spine and branching academic wings and courtyards. Swing space required.




OPTION B.2 - TREE BRANCHES

B.2 Tree Branches New Construction': New two story construction with central learning commons/cratteria spine, new replacement sloped-floor auditarium and branching academic wings and courtyards. New construction located in existing parking. No swing space required.



OPTION C.2 - FOLDED HANDS

C.2 'Folded Hands New Construction : New three story split level entry construction with stopped convertible commons/auditorium/cafeteria and balcony-accessed classrooms. New construction located in existing parking. No swing space or occupied construction required.



OPTION D - BUTTERFLY

D 'Butterfly: New two story construction with classroom wings radiating off stepped convertible commons/auditorium/cofeterio/gymnasium. New construction located in existing parking. No swing space or occupied construction required.

Jonathan Levi Architects

PROJECT MANAGEMENT

Fuller Middle School Feasibility Study City Council Meeting February 6, 2018

Jonathan Levi Archited

NEXT STEPS

School Building Committee meetings are every two weeks. Meetings and agendas are posted on the FPS website.

- February 12, 2018 Community Forum #3
- April 2, 2018 Community Forum #4
- May 9, 2018 Submit Preferred Schematic Report (PSR) to MSBA
- September 12, 2018 Submit Schematic Report (SD) to MSBA
- October 31, 2018 MSBA board meeting to approve project
- Late Fall 2018 City appropriation voting



PROJECT MANAGEMENT

Community Resources

Project Website: <u>www.Framingham.k12.ma.us/Page/2997</u>



PROJECT MANAGEMENT

Questions and Comments



PROJECT MANAGEMENT