

October 18, 2019

Mr. Brian Lynch  
Project Coordinator  
Massachusetts School Building Authority  
40 Broad Street, Suite 500  
Boston, Massachusetts 02109

**Re: Fuller Middle School**

**Framingham, Massachusetts**

*90% Construction Documents Submission to the MSBA*

*SMMA No. 17050*

Dear Brian:

Attached please find the Module 6 90% Construction Documents submission to the MSBA. The team has followed the guidelines set forth in Module 6 to develop this submission. We look forward to reviewing the information contained in this submission with you and your team.

SMMA certifies that (1) we have reviewed and coordinated the materials, (2) the submittal is complete, (3) the Proposed Project as documented within the submittal is within the District's Budget, and (4) the District has approved the materials for submission to the MSBA.

Please contact me at 617-520-9403 if you have any questions, comments, or would like to schedule a meeting.

Thank you.

Very truly yours,

**SMMA | Symmes Maini & McKee Associates**



Joel G. Seeley  
Project Director

cc: Framingham School Building Committee; Philip Gray, Jonathan Levi Architects (MF)

enclosures: 90% Construction Documents Submission

JGS/sat /P:\2017\17050\03-DESIGN\3.4  
Submissions\5-60% CD  
Submission\OPM  
Deliverables\Northbridge  
Sample\0\_OPM Cover Transmittal  
Letter\L\_Blynch@MSBA\_60%  
Construction  
Documents\_9August2019.Docx

1000 Massachusetts Avenue  
Cambridge, MA 02138  
617.547.5400

[www.smma.com](http://www.smma.com)



# FULLER

## Construction Documents - 90%

Fuller Middle School, Framingham, Massachusetts

### Owner

City of Framingham, Massachusetts

### Client

City of Framingham, Massachusetts

### Architect

Jonathan Levi Architects LLC

### Owner's Project Manager

SMMA

### Construction Manager at Risk

Consigli Construction Company

October 18, 2019



<b>6C.1 Summary Comments</b>	
1.1 Basic Project Information	5
<b>6C.2 OPM Deliverables</b>	
<b>2.1 Submittal Review and Coordination</b>	
2.1.1 Submission Review	7
2.1.2 Commissioning Agent Review	87
2.1.3 MSBA CD-60% Review and District Response	97
<b>2.2 Project Schedule</b>	127
<b>2.3 Scope and Budget</b>	139
2.3.1 Project Budget	139
2.3.2 Total Project Budget	145
2.3.3 Construction Estimate Comparison	151
2.3.4 Reconciled Cost Estimate - CMR	155
2.3.5 Reconciled Cost Estimate - Designer	287
2.3.6 Reconciled Cost Estimate - OPM	341
2.3.7 Prequalification Requirements	431
<b>6C.3 Designer Deliverables</b>	
<b>3.1 General Requirements</b>	443
3.1.1 Work Plan	443
3.1.2 Basis of Design Narratives	449
3.1.3 Building Code Analysis	501
3.1.4 Proprietary Items	629
3.1.5 Color Theory Statement	647
3.1.6 Independent Structure Review	651
3.1.7 Quality Control Documents	659
3.1.8 Security and Visual Access Requirements	661
<b>3.2 Space Summary</b>	665
3.2.1 Space Summary	665
3.2.2 Space Summary - Education Program Comparison	671
<b>3.3 Project Approvals</b>	673
3.3.1 Approval Status	673
3.3.2 Approval Letter	679
3.3.3 Utility Certifications	683
<b>Appendices</b>	
1 Energy Calculations	
2 Life Cycle Cost Analysis	
3 Heat Gain and Loss Calculations HVAC	
4 Draft Cost Estimates	



## 6C.1 Summary Comments

### 1.1 Basic Project Information

#### *Introduction*

The Fuller Middle School project is anticipated to serve 630 students in grades 6-8. When the new school is complete, the students will move out of the adjacent existing middle school, which will then be demolished. The proposed building program based on Framingham's Educational Program and the Project Funding Agreement comprises 137,100 GSF. The project will be constructed under the Construction Management at Risk methodology in accordance with M.G.L. Chapter 149A. Consigli Construction Company has been formally selected as the CMR for the project.

Construction on the Phase 1 site enabling package began when the students finished their school year in June 2019 and was completed in time for the new school year starting August 28 on time and on budget. This work includes temporary parking, new permanent parking, utility work, geotechnical ground improvement, and geoenvironmental soil abatement.



### ***Schedule Summary***

The project's scheduled milestones are as follows:

#### ***Design***

Site enabling 100%: 5/10/19

60% CD, 100% Early Concrete and Steel Package: 8/9/19

100% Masonry Package 10/18/19

90% CD: 10/18/19

100% CD: 11/22/19

GMP approval 1/3/20

#### ***Construction***

The project will have 3 construction phases

Phase 1 site enabling substantial completion 8/20/19

Phase 2 building substantial completion 6/15/2021

FF&E technology installation 6/15/2021 - 7/30/2021

Phase 3 Demo and site work substantial completion 12/20/2021



## 6C.2 OPM Deliverables

### 2.1 Submittal Review and Coordination

#### 2.1.1 Submission Review

The OPM has reviewed the Designer's 90% Construction Documents Submission and recommends the Owner approve the submission.

#### *OPM REVIEW*

The OPM performed a review of the Progress 90% Construction Documents, dated September 9, 2019. The OPM comments are documented in the OPM Design Review, dated September 23, 2019 and appended to the end of this section.

1. Technical Accuracy, Coordination and Clarity – The design documents at this 90% Construction Documents Phase contain the typically expected level of technical accuracy. Areas of the building are laid out in plan, elevation, and section, and are generally consistent with the space summary and design requirements of the MSBA and DESE. The sitework, concrete and steel documents are developed to a more complete level due to the Early Site Package and Early Concrete and Steel Package development. The 90% Construction Documents drawing set includes detail and schedule development appropriate to this level and reflects the complexities of the project design, systems and site constraints. The design documents at this 90% Construction Documents phase contain the expected level of coordination and clarity.
2. Efficiency and Cost Effectiveness – The project as designed represents a very efficient and compact floor plan that allows the existing building to remain operational for the duration of construction. The location of the mechanical room and electrical room maximizes the efficiency of the system, while also allowing for an efficient piping distribution. The building layout is a cost-effective solution. The materials and equipment included in the design represent generally accepted materials for school construction projects. The District's Buildings and Grounds Staff has participated in the material and equipment selections.
3. Operability – The project is designed for ease of operation. The location of support spaces are within appropriate distances to the spaces they serve. Access to equipment for preventative maintenance is thoughtful. Lastly, the easy segregation of the public spaces from the instructional spaces, facilitates community use in an efficient and easily maintained manner.
4. Constructability – Several meetings between the Construction Manager, the OPM and the Designer on constructability and logistics have occurred. The OPM review of the progress 90% Construction Documents set did not surface any significant constructability issues.

5. Phasing – The new school is located on the site to allow for the continued operation of the existing school. Once the new school is completed, it can operate unimpeded while the existing is demolished and the parking lot and fields are completed.
6. Bid-ability – The MEP elements of the progress 90% Construction Documents drawing set have been coordinated to the level of 90% Construction Documents set. The general layout of the building, floor to floor construction height and the relationship between spaces will facilitate further coordination. The OPM review did not surface any significant bid-ability issues.
7. Site Access During Construction – As noted in the Phasing section above, the project has been designed to allow for site access to the operational school during both Phase I and Phase II construction.

#### ***CM REVIEW***

The CM performed a review of the Progress 90% Construction Documents, dated September 9, 2019. The CM comments are documented in the CM Design Review, dated October 7, 2019 and appended to the end of this section.



## OPM Design Review Comments

<b>Project Name:</b>	Fuller Middle School, Framingham, Massachusetts	<b>Project Phase:</b>	90% Construction Documents
<b>Project Number:</b>	17050	<b>Reviewed Date:</b>	September 23, 2019
<b>Document Reviewer:</b>	Mariana Hernandez, Robert Smith, John Hart, Paul Livernois, Christopher Davis, Robert Marshall, Rafael Gurevich, Stella Drizin, Patrick Weygint, and Joshua Delaplain-Zook	<b>Discipline</b>	All Disciplines

### DESIGN REVIEW NOTES

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
1.	Architecture	LS101-103	Define the fire and smoke separation required for the 3-story atrium.	MSBC Section 404.6 required atrium spaces to be separated from adjacent spaces by 1-hour fire barriers in accordance with Section 707. A fire barrier is not required for this project as the building will include a smoke control system, which is currently being modelled by Howe Engineers using FDS. Refer to the Atrium Design section of the Fire Protection and Life Safety Code Compliance Strategy report drafted by Howe Engineers.	A code compliance drawing should be included. Showing rated walls, separations construction type for ISP review. The Code Report is not typically submitted with Permit documents.	LS drawings include rated walls. A Life Safety Code Summary sheet will be included in the CD-90 submission.	Closed	
2.	Architecture	LS101-103	No reference shown to type of construction, allowable areas, etc.	The building is currently designed to be Type IB construction as noted on page 7 of the code report.	A code compliance drawing should be included. Showing rated walls, separations construction type for	LS drawings include rated walls. A Life Safety Code Summary sheet will be included in the CD-90 submission.	Closed	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
3.	Architecture	LS101	Exit 6 is from a storage room, should not be counted towards egress totals.	The exit tag will be changed and updated in future submissions to indicate "Direct Exit" from the storage room. The exit will be called out on the Life Safety sheet, but will not be counted towards the overall egress totals.	Closed			
4.	Architecture	LS103	Some areas between corridor and atrium seem to be missing a railing	Railings will be provided on upper levels of the building.	Still appears to have missing railing at locations near breakout rooms.	Railings have since been provided.	Closed	
5.	Architecture	A101-A103C	Provide overall dimensions, angles and working points	Dimensions will continue to be added	Open item	Dimensions will continue to be provided. A lot of the dimensioning will rely on a grid dimension layout plan.	Open	
6.	Architecture	A101-A103C	Indicate partition types on plans	Tags will be added	Partially done, wall tags still missing. Ex 3134,3130,2160	Tags will continue to be added.	Open	
7.	Architecture	A101-A103C	Some structural grid lines are not appearing on the floor plans	Will continue to be coordinated	Open	Will continue to be coordinated.	Open	
8.	Architecture	A101-A103C	Coordinate brace locations w/ openings, plumbing and HVAC ductwork	Will continue to be coordinated	Open	Will continue to be coordinated.	Open	
9.	Architecture	A101-A103C	Reference enlarged toilet rooms back to floor plans.	Will continue to be developed	Open	Call outs to enlarged plans are included.	Closed	
10.	Architecture	A101-A103C	Indicate ramp and stair direction	Will continue to be developed	Partially done, still needs additional direction arrows.	Notations will continue to be added.	Open	
11.	Architecture	A101	The interior finish notes mention a bubble skylight on the Auditorium ceiling, this skylight doesn't show on RCP or on Roof plans	Will be revised	Closed			
12.	Architecture	A101	Top right corner of Auditorium was cropped out from view	Will be revised	Closed			
13.	Architecture	A101A	Exterior HM single egress door from Corridor 1020	Door is now double door	Closed			

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
			may need to be widened to accommodate reach required on a thick wall					
14.	Architecture	A101B and A101C	Cohort Common and Learning Common are each 1'-0" off from the main floor elevation, provide cane detection per Code.	Measures have been added to meet code.	Closed			
15.	Architecture	A101D	Room name missing from room facing exterior between Gym and Aud.	Will be added	Closed			
16.	Architecture	A102A	Four apparent flues showing next to Closet 2017 seem in conflict w/ the walls and structure	Will continue to be coordinated in upcoming submissions.	Open	Will continue to be coordinated.	Open	
17.	Architecture	A102B	Indicate HVAC elliptical duct risers and connection detail.	Will continue to be developed in upcoming submissions.	Open	Duct risers are now rectangular and enclosed in GWB partition. Details will be developed in upcoming submissions.	Open	
18.	Architecture	A102B	Railing missing near Breakout room	Railings will be provided	Open, needs more refinement	Railings indicated, details in process.	Open	
19.	Architecture	A1022B	East stair not showing	Will be fixed	Stair shown provide direction.	Tags will continue to be added.	Open	
20.	Architecture	A102C	Ensure required door reach clearance at TP rooms typ.	Will continue to be refined to meet code.	Do you have 18" clearance on pull side of breakout 2068	Required clearance provided.	Closed	
21.	Architecture	A102D	How is the roof between Classroom 2224 and Auditorium drained?	With tapered insulation and roof drains.	Closed			
22.	Architecture	A103A	Sunscreen image is confusing should be higher or not shown	Has been clarified	Closed			
23.	Architecture	A103A	Roof south of Classroom 3144 shows as flat on the framing plans, coordinate with Structural drawings	Roof steel intended to be flat, insulation will be sloped.	Closed			
24.	Architecture	A103B	Coordinate hanging post locations with bridge, indicate railing	Will continue to be coordinated in upcoming submissions.	Closed			

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
25.	Architecture	A104	Indicate tapered insulation and how drain slopes will be achieved. Roof framing plans don't show sloping steel	Main drainage will be shown on the 100% DD set.	Open	Main drainage is shown on the roof plans. Main roofs use tapered insulation. Auditorium and gym roofs have sloped steel.	Additional drain slopes needed on A104 for lower roofs.	
26.	Architecture	A104	Indicate different roof levels and how different roof levels are accessed	Minor roof access will not be fully resolved for 100% DD set.	Open	Minor roof access at gym & auditorium will have access ladders.	Open, how do you access lower roofs.	
27.	Architecture	A104	Any roof ladders required to access the different roof levels?	An access ladder will be provided from the main roof level to the raised roof area at the skylights.	Open - not shown	Access ladders has been added to high roof	Closed	
28.	Architecture	A104	Indicate amount and layout of roof walk way pads	Walk Way pads will be indicated on the roof plan in the 100% set.	Partially done, consider all mechanical equipment needing servicing should have walkway pads	Additional walkway pads will be added	Open	
29.	Architecture	A104	Include view for stair and elevator roof.	Will be provided in the 60% DD set.	Closed			
30.	Architecture	A-104	Smoke vent hatches not shown on roof plans	Smoke vents will be shown at the auditorium only.	Open	Ongoing, smoke vents will be added.	Open	
31.	Architecture	A104	Indicate roof types, canopy construction	Roof types will be indicated in the 100% DD set.	Open	Roof Types have been added.	Open, Canopy construction needs further refinement	
32.	Architecture	A104	Show openings in Mechanical screen to allow access	Roof screen will allow for access at the line of the raised roof area 4'-0" clear.	Closed			
33.	Architecture	A141A-A143C	Consider consolidating room finishes to one location. They are shown/ listed as a note on the A101 series, scheduled on these sheets and with room tags as well	Roof finishes will be consolidated to the A14 series	Closed			
34.	Architecture	A141A-A143C	Show floor transitions for detailing	Floor transition details are indicated on door schedule	Partially done, show transition details where occur other than door locations.	Tags will continue to be added.		
35.	Architecture	A161A-A163C	Coordinate furniture locations with architecture. Ensure clearance around furniture and doors, walls, equip, etc.	Will be further developed in upcoming submissions	Partially done, charging carts, mobile furniture or makerspace equipment that are not yet shown on plans.	Additional furnishings will be included. Mobile Cabinetry is included in base project, ref. A622.	Open	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
36.	Architecture	A181-A183C	Show HVAC diffusers, return grills and exposed ductwork	Will be further developed in upcoming submissions	Partially developed	Continues to be added to drawings.	Open	
37.	Architecture	A181-A183C	Show light fixtures, sprinkler heads, smoke detectors, motion detectors, etc.	Will be further developed in upcoming submissions	Partially developed	Continues to be added to drawings.	Open	
38.	Architecture	A181-A183C	Indicate ceiling elevations	Will be further developed in upcoming submissions	Needs further development, ceiling elevations missing or incorrect. Ex. Classroom 1244	Tagging included.	Needs further refinement so tagging does not cover fixtures or symbols	Open
39.	Architecture	A181-A183C	Show ceilings legend on all ceiling plans.	Will be further developed in upcoming submissions	Legends are shown but not all symbols are shown on ceiling plan legend. Ex. Smoke detector, motion detector.	Continues to be developed	Open	
40.	Architecture	A181-A183C	In some areas exposed deck is shown with a line pattern, in other areas is shown blank show one consistent way.	Line pattern is meant to indicate a painted deck, will be clarified in upcoming submissions.	Has been clarified. Confirm classroom closet ceiling will have no finish.	Confirmed	Closed	
41.	Architecture	A201	Drawing is very hard to read. Consider highlighting cut areas and fading out planes behind	JLA will review. This drawing will be refined for 60% DD.	Drawing is easier to read but needs further refinement and detailing.	Will continue to refine	Open	
42.	Architecture	A211-A217	More detailed information and notes required, consider graphic refinement of patterns to provide more clarity Windows, CW and storefront need to be tagged, brick control joints need to be indicated. Applicable structural gridlines should show on the partial elevations. A key plan for the partial elevations may help in locating them.	JLA will review. A key plan will not be provided for the 100% DD set.	More refinement needed including brick control joints.	Drawings are being updated and modified per VM requirements and OPM/CMR review comments.	Open	
43.	Architecture	A300 and A301	Hard to read what is cut and what is beyond. Work w/ line weights. Label spaces,	JLA will review. This drawing will be refined for 60% CD set.	Partially refined, will cut rooms have room #'s to identify the space.	We will add room numbers	Open	
44.	Architecture	A311- A320	Wall sections not developed, need to show dimensions, exterior wall	Wall Section drawings will be further	Open, including additional drawings from A311-A326	Drawings are being updated and modified per VM	Open	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
			and roof types, indicate insulation and AVB continuity, roof edge treatments, flashing conditions, sun screen structure, overhang structure and insulation criteria, how ceilings meet with exterior walls, windows	developed for 100% DD.	needing further development.	requirements and OPM/CMR review comments.		
45.	Architecture	Floor plans	Confirm door reach clearance on both pull and push side, on the Break Out spaces	Will continue to be refined to meet code.	Open	Door clearances provided.	Closed	
46.	Architecture	Specs	Specs indicate precast concrete and none shown on drawings.	There is no precast concrete in the project. This section will be removed.	Drawings call for a precast planter on drawing A102A. As well as precast stair treads.	These planters are now cast in place	Drawing A102A still indicates precast planters.	
47.	Architecture	Specs	Specs call for mineral wool insulation, drawings show Polyiso	The intent is to use both types of insulation Pending confirmation of final detailing for masonry walls. Polyiso is preferred for masonry veneer walls.	Open	The intent is to use both types of insulation Pending confirmation of final detailing for masonry walls. Polyiso is preferred for masonry veneer walls.	Drawings indicate mineral wool in some masonry walls between windows.	
48.	Architecture	Specs	Drawing A501 shows Concrete Unit Masonry block w/ insulated cores. There is no mention of it in the specs	Insulated CMU has been removed from the project based on CM cost analysis.	Closed			
49.	Architecture	Drawing Index			A001 drawing not present.	Will be included	Closed	
50.	Architecture	Drawing Index			Add drawing to indicate toilet fixture and accessories mounting heights.	Will be included	Closed	
51.	Architecture	LS101			Does the number of seats in the Gymnasium take into consideration ADA seating? Non shown.	Yes	Closed	
52.	Architecture	LS101			If gymnasium and auditorium both have after hours permits for events are there a sufficient number of toilet fixtures to	Yes	Closed	



Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
					accommodate all occupants.			
53.	Architecture	A101A			No door number tag on doors to room 1134.	Tag has been added	Closed	
54.	Architecture	A101A			Kitchen serving countertop indicates PLAM on drawings. Specifications indicate Quartz stone countertop	Will be coordinated in upcoming submissions.	Closed	
55.	Architecture	A101C			Is there a separate plan for the loading dock?	No	Will details be provided for loading dock bumper pads?	
56.	Architecture	A102A			Provide additional detail and dimensioning of precast planter and railing connection.	Will be further developed	Open	
57.	Architecture	A102A			Provide additional detail and dimensioning of wood slat seating.	Will be provided in upcoming submissions	Open	
58.	Architecture	A102A			Provide additional detail and dimensioning for phenolic bench with slopped back.	Will be provided in upcoming submissions	Open	
59.	Architecture	A101-A103			Classroom dividing walls indicate both a wall type F6 and a folding partition.	That is correct	Closed	
60.	Architecture	A102A			No door tag on closet 2017.	Will be provided	Closed	
61.	Architecture	A102A			Should the flues in chase behind closet 2017 be in a rated shaft.	Yes, we will revise.	Partition type not called out.	
62.	Architecture	A103A			Room # missing from A3134.	Will be provided	Open	
63.	Architecture	A104			Provide additional drawings indicating roof and edge details.	These are included on exterior wall sections	Included but need further refinement and detailing.	
64.	Architecture	A11A-A113C			EOS Legend does not match hatched out areas on floor plans.	EOS Legend updated in Early Concrete & Steel Package 8/9/19	Closed	
65.	Architecture	A11A-A113C			Include EOS legend on all pages.	EOS Legend updated in Early Concrete & Steel Package 8/9/19	Closed	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
66.	Architecture	A141A-A143C			Not all abbreviations are included on legend. Needs further refinement.	Will be further refined in upcoming submissions	Open, example floor finish "LP" not indicated.	
67.	Architecture	A141A-A143C			Legend indicates power troweled concrete-should that be polished concrete to coincide with specifications.	Specs will be revised to power troweled concrete	Closed	
68.	Architecture	A201			Remove curtainwall from elevations.	Notes will be deleted	Closed	
69.	Architecture	A221			Is there a window type D2?	Not at this time	Closed	
70.	Architecture	A311-A326			Need further refinement and detailing. Ex. Drawing refer to a details on drawing A511 that has not been developed.	Drawings are being updated and modified per 60% VM requirements	Open, drawing need further refinement, labeling and detailing.	
71.	Architecture	A400			Call out glazed partition with gradated pattern on details 4&5.	Additional notation included.	Closed	
72.	Architecture	A400			Elevation #7 needs further refinement and labeling.	Additional information included.	Closed	
73.	Architecture	A403			Elevation #12 needs further refinement and labeling.	Additional information to be provided	Open	
74.	Architecture	A404			Elevation #7 needs further refinement and labeling.	Additional information to be provided	Open	
75.	Architecture	A404			Call out plumbing fixtures on elevation #5.	Drinking Fountains are keynoted	Closed	
76.	Architecture	A405			Elevations #2&7 need further refinement and labeling.	Additional information to be provided	Open	
77.	Architecture	A406			Elevations need further refinement and labeling.	Additional information to be provided	Open	
78.	Architecture	A400-A406			Drawings should include keynotes and legends.	Legends to be included, Elevations are keynoted.	Open	
79.	Architecture	A410			Elevations need further refinement Elevation#6 calls out paint on door glass, elevation #5 has	Tagging to be refined.	Open	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
					exterior glazing arrow pointed to nothing.			
80.	Architecture	A410-A416			Is there a detail on supporting sink counter if cabinet bases are mobile on casters?	Additional information to be provided	Open	
81.	Architecture	A420-A442			It might be beneficial to have a plumbing legend on these drawings.	Additional information to be provided	Open	
82.	Architecture	A425			Detail for PLAM work Counter in center of admin office 2010.	Additional information to be provided	Partially done needs refinement	
83.	Architecture	A430			Detail #2 railing does not connect to breakout room.	Railings included; Additional information to be provided	Partially done needs refinement	
84.	Architecture	A431			Details #2&#3 Locker/railing detail unclear at connection to breakout room	Additional information to be provided	Partially done needs refinement	
85.	Architecture	A430-A433			Breakout elevations need further labeling and dimensioning.	Additional information to be provided	Open	
86.	Architecture	A450			Indicate duct risers in gymnasium and connection details.	Additional information to be provided	Open	
87.	Architecture	A450			Is there enough space for a timekeepers table for basketball and volleyball games?	Yes, First row of bleachers retractable to accommodate scoring table.	Closed	
88.	Architecture	A450			Gymnasium game lines need dimensioning. Will any graphics be included (school mascot or name of school).	Additional information to be provided	Open	
89.	Architecture	A451			All tag callouts are not indicated on keynote legend.	Additional information to be provided	Open	
90.	Architecture	A452,A453			Should basketball shot clocks be shown above main court backboards.	This is a spec item	Closed	
91.	Architecture	A460-A463			Callout auditorium stage curtains. Also mounting between stage curtains b	Note will be added	Open	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
92.	Architecture	A461			Will standard sprinkler connection with concealed plate apply to clouds or is sprinkler head exposed?	Sprinkler heads will be exposed	Closed	
93.	Architecture	A470			Show arrows with stair direction.	Additional information to be provided	Open	
94.	Architecture	A470			Indicate finishes example handrails are they painted?	Additional information to be provided	Closed	
95.	Architecture	A470			Indicate large details and connection details. Example railing at top landing looks unfinished.	Additional information to be provided	Open	
96.	Architecture	A470			Reference all details on A652	References have been added	Closed	
97.	Architecture	A471			Are metal risers and side stops indicated to be painted?	Additional information to be provided	Closed	
98.	Architecture	A471-A473			Will matching wall base be applied to GWB below stairs	Yes, will be added to drawings	Open	
99.	Architecture	A471-A473			Will additional dimensioning be added for posts between perforated panels.	Yes, dimensions will be added.	Open	
100.	Architecture	A480			Layout of elevator equipment should be included in elevator mechanical room.	Reference VT01 for elevator and elevator mechanical room layout.	Closed	
101.	Architecture	A480			Will an elevator sill detail be provided?	Additional information to be provided	Open	
102.	Architecture	A480			Should corridor floor finish be identified on elevator sections?	Sill detail to be provided.	Open	
103.	Architecture	A502			Provide additional roofing details.	Additional roofing details will be provided at 90%.	Open	
104.	Architecture	A540			Will a skylight end detail be provided?	End detail will be provided at 90%.	Open	
105.	Architecture	A540			Provide additional detail and description to skylight edge section detail.	Additional details will be provided	Open	
106.	Architecture	A570			Canopy details need more refinement to	Drawings are being updated and	Open	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
					show connections, dimensions and materials.	modified per 60% VM requirements		
107.	Architecture	A600-A625			Need additional refinement indicating reference details, dimensioning and details.	Additional information to be provided.	Open	
108.	Architecture	A621			Should show a dimensioned plan view of bench in corridors	Refer to 10/A600	Closed	
109.	Architecture	A650			Detail 7, Section - Guardrail locker. Is additional metal framing necessary to install GWB soffit?	No	What does ACT wall trim anchor into? Detail appears trim is floating	
110.	Architecture	A651			Stair detail indicates both precast stair tread and metal pan with concrete fill.	This note has been revised in PR 12.	Closed	
111.	Architecture	A651			Details need further refinement and coordination to	Details have been further developed.	Open-Detail 1 angle iron at top rail shows recessed into 1/2"x3" steel plate. Should sit on top of flat plate to match bottom steel angle.	
112.	Architecture	A652			Stair detail indicates both precast stair tread and metal pan with concrete fill. Detail #7&12.	This note has been revised in PR 12.	Closed	
113.	Architecture	A652			Interior stair details with 1/2"x3" steel stanchion. Is this within reach of students and should it be rounded instead of square edge	Square edges will be eased	Closed	
114.	Architecture	A690			Some details need further refinement	Ongoing	Open	
115.	Architecture	A690			Is there a mounting detail for the chain of the roller shade?	This is a spec item, it will be mounted to the wall with a holder.	Closed	
116.	Architecture	A690			Is addition vertical metal framing required for sloped ACT to GWB Soffit at Corridor.	No, slope is within range for standard ACT ceiling application.	Closed	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
117.	Architecture	A691			Should a ceiling legend be included on this drawing for reference.	We do not typically do this.	Closed	
118.	Architecture	A691			The wood trim piece covering the anchor for the cloud, is this piece a custom turned piece or supplied from manufacturer. If custom provide additional details.	Wood trim would be custom millwork piece. Detail 5/A691 shows dimensions.	Closed	
119.	Architecture	A700			Partition type "D6" indicates a 7 1/4" wall thickness with a 3 5/5" stud.	Has been revised	Closed	
120.	Architecture	A700			Partition type "H6" indicates a 7 1/4" wall thickness with a 3 5/5" stud.	Has been revised	Closed	
121.	Architecture	A715			Is there any exterior signage details?	Will be provided in upcoming submissions	Open	
122.	Architecture	Drawings			Provide mechanical enclosure on roof elevations and details.	Detail Section has been added, elevations will be provided.	Open	
123.	Architecture	Drawings			Show calculations and counts of toilet fixtures.	Plumbing fixture requirements included in Code Report and will be included on Code Summary sheet in upcoming submissions.	Closed	
124.	Architecture	Drawings			Details are hard to follow without callbacks or reference to locations on plans where they apply.	Additional tagging in progress.	Open	
125.	Architecture	Plumbing P101A			Indicates to refer to P202 for enlarged kitchen plan.	These are plumbing comments with an Architectural discipline designation	Agreed, want to make sure they are coordinated.	
126.	Architecture	Plumbing P002			Detail 7 indicates a 6" water service please verify with site utilities changes.	These are plumbing comments with an Architectural discipline designation	Agreed, want to make sure they are coordinated.	
127.	Architecture	Spec Section 03.35.10			Show the application include the procedure	Polished concrete is no longer on the job.	Closed	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
128.	Architecture	Spec Section 06 40 00			to repair any hairline cracks in concrete surface to receive polished concrete. Subsection 3.4 Installation -casework and countertops. Should you include after installation applying a continuous bead of specified sealant to all joint which abut walls or partitions. Page 2 Subsection 1.2.H has Question (?) marks for all listed drawing numbers. Section 1.7 Quality Assurance. Roofing manufacturer's representative should be onsite during roofing installation and not just provide a final inspection. Section 2.3.A.2.a. 1) Wood Species and cut indicated as "xxx". Please indicated species and cut. Should you indicate wider width of top and bottom rails that have closers and lock blocks at door stiles with exit devices. Can more than 1 manufacturer be specified. Can more than 1 manufacturer be specified. Can more than 1 manufacturer be specified. Should joint sealants be specified at locations were GWB	Limited areas of exposed concrete are power troweled and sealed. See 064000 pg 19 3.4F. Section 079200 will provide these sealants.	Closed	
129.	Architecture	Spec Section 07 00 02				Drawings will be finalized for 100% CDs or any related early bid package. Agreed, will revise.	Open	
130.	Architecture	Spec Section 07 54 19					Closed	
131.	Architecture	Spec Section 08 14 16				Will be provided as white maple	Open	
132.	Architecture	Spec Section 08 14 16				Stiles are indicated on drawings.	Closed	
133.	Architecture	Spec Section 08 34 57				Yes, will add	Closed	
134.	Architecture	Spec Section 08 35 15				Section has been removed	Closed	
135.	Architecture	Spec Section 08 45 13				Yes, this has been added	Closed	
136.	Architecture	Spec Section 09 91 00				This is covered in section 079200	Yes, concern with interior metal door frame and floor	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
					comes in contact with metal frames, sills, countertops, casework. Or at locations where metal frames come in contact with flooring but has a gap from shimming frame.		when door frame has floor spacers for shimming due to floor unevenness.	
137.	Architecture	Spec Section 09 91 00			Will exterior doors be numbered and painted with stencils?	We will use an applied film. Numbering system will need to be reviewed at upcoming Fire Department meeting. Will be revised.	Open	
138.	Architecture	Spec Section 11 53 00			Has wrong page numbering and section at bottom of pages	Will be revised.	Open	
139.	Architecture	Spec Section 11 53 13			Has wrong page numbering and section at bottom of pages	Will be revised.	Open	
140.	Architecture	Spec Section 12 35 53			Has wrong page numbering and section at bottom of pages	Will be revised.	Open	
141.	Architecture	Spec Section 12 36 53			Has wrong page numbering and section at bottom of pages	Will be revised.	Open	
142.	Architecture	Spec Section 12 61 00			Section 12 61 00 subsection 2.2 B. refers to City of Boston Fire Prevention Code.	Will be revised.	Open	
143.	Architecture	Spec Section 12 61 00			Section 12 61 00 subsection 2.3 D.1. refers to City of Boston Fire Marshal.	Will be revised.	Closed	
144.	Architecture	Drawing G101					Indicates location of 2 exterior Acid Neutralization tanks that have been eliminated.	
145.	Architecture	A101A					Should there be a notation/callout on this plan indicating see FS-001 plans.	
146.	Architecture	A101A					Is their an automatic H.C. door release/hold open for entering and exiting main entrance.	



Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
147.	Architecture	Drawing A102D					Needs key plan	
148.	Architecture	Drawing A104					Keynote legend for Roof.	
149.	Architecture	Drawing A104					What type of roof finish is located at roof by Chimney flues.	
150.	Architecture	Drawing A104					Scupper note indicated on Gridline N12 but not drawn into edge of roof.	
151.	Architecture	Drawings A113A, A113D, A114C ,A114B					Should roof drains cut outs be shown on EOS roof Drawings. Roof Drain Bowls should be set to prevent chipping concrete out to recess bowls.	
152.	Architecture	Drawing A141A					Finish Schedule indicates -/PTD is that symbol different than PTD symbol.	
153.	Architecture	Drawing A141A					Roof finish schedule indicates corridor 1000A and Kitchen Scramble 1001 but not shown on floor plans.	
154.	Architecture	Drawing A141C					Lockers outside of Art room indicate dimension of 4'-8" and a locker quantity of 5 cannot be achieved.	
155.	Architecture	Drawing A142B					Lockers outside of Room 2038 indicate dimension of 1'-7" and a locker quantity of 5 cannot be achieved.	
156.	Architecture	Drawing A142B					Lockers outside of Room 2120 indicate dimension of 1'-7"	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents		
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response	
157.	Architecture	Drawing A181A						203/256" and a locker quantity of 2 cannot be achieved.	
158.	Architecture	Drawing A181A-A183C						1134 has (3) locations with B\$ indicated below Acoustical panel Ceiling?	
159.	Architecture	Drawing A200 and A201						Coordinated lighting, O.S. and PS with sprinkler head layout.	
160.	Architecture	Drawing A400						Note#5 indicates Curtainwall system. Drawings need further refinement. See detail 12, doors are cut off. Detail #2 has section cuts on top of each other.	
161.	Architecture	Drawing A400						Detail 10 has section cut indicating see detail 1 on Drawing A514. Drawing A514 does not exist.	
162.	Architecture	Drawing A480						Should proximity card locations on corridor side be dimensioned on plan for location.	
163.	Architecture	Drawing A480						Should proximity card reader be located on detail 10 inside cab.	
164.	Architecture	Drawing A490						Detail #7, Drawings indicate 1/8" sawcut joint in stair treads. How do you make this cut without damaging riser with saw.	
165.	Architecture	Drawing A491						Has lintel detail on drawing that should be removed	
166.	Architecture	Drawing A491						Detail 1, needs further refinement. Unfinished.	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents		
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response	
167.	Architecture	Drawing A510						Detail 8 & 9 does the 3/8" joint get caulked between WT8 and WT10.	
168.	Architecture	Drawing A510						General note Wall types to not fit in call out boxes. Drawing needs refinement	
169.	Architecture	Drawing A511						Detail #6 metal stud on outside corner beyond concrete slab. How is it attached.	
170.	Architecture	Drawing A511						Detail 6 how does wood blocking for attach to metal studs.	
171.	Architecture	Drawing A511-A513						Details need further refinement.	
172.	Architecture	Drawing A513						Detail #2, After metal framing corner appears to need addition reinforcement or blocking to anchor board and masonry anchors.	
173.	Architecture	Drawing A520, A521, A531, A542						Roof edge metal facia should lay flat on top of roof with flashing strip hot-air welded over seam.	
174.	Architecture	Drawing A520						Detail #12 indicates wood "SundHade" should this be wood grilles.	
175.	Architecture	Drawing A520, A521, A522						Needs further refinement and detailing.	
176.	Architecture	Drawings A520-A522 and A542						Shows rim board. Specs indicate that sizes are indicated on drawings. Provide dimensions or rim board schedule.	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents		
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response	
177.	Architecture	Drawing A531						More refinement is needed on edge details.	
178.	Architecture	Drawing A540						Provide skylight panel spacing dimensions.	
179.	Architecture	Drawing A541						Detail #2 GWB does not appear to be continuous and cuts off fire proofing from I-Beam.	
180.	Architecture	Drawing A541						Detail #3 does sprinkler pipe being attached to skylight structure affect manufacturer warrantee.	
181.	Architecture	Drawing A541						Detail 1 - Elastomeric flashing arrow points towards rigid insulation.	
182.	Architecture	Drawing A541						Additional labeling of roofing materials, PPT plywood, cants, ect.==	
183.	Architecture	Drawing A542						Details 1&3 PLAM extends beyond metal flashing.	
184.	Architecture	Drawing A542						Additional refinement and dimensioning of edge facia metal	
185.	Architecture	Drawing A544						Details 12&13 indicates prefab curb section 23 00 00. They are to be poured by concrete subcontractor.	
186.	Architecture	Drawing A544						Detail 13 has a ? for a description.	
187.	Architecture	Drawing A544						Detail 7 should have a minimum dimension for the location of Thru wall flashing in case coursing if off.	
188.	Architecture	Drawing A600						Detail 10, at the intersection of the	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
189.	Architecture	Drawing A623						glazed partition with the wrapped beam the interior joint appears to be approx. 1". Provide larger detail of how it is anchored and finished on the interior side.
								Media center and Admin desks, will they require any additional leg stanchions or brackets to support countertop.
190.	Architecture	Drawing A625						Detail 5 concerns that concealed alum. Glazing shoe is recessed to far into receiver and glass will rest on blocking.
191.	Architecture	Drawing A625						Detail 5 Linoleum base molding arrow points to GWB
192.	Architecture	Drawing A625						Detail 5 Consider additional blocking to anchor GMW at angle into.
193.	Architecture	Drawing A625						Details need further refinement.
194.	Architecture	Drawing A650						Details 2, 3,4,8&9 have a section cut 2/A300 thru detail that should be removed.
195.	Architecture	Drawing A650						Details 4&5 blocking for phenolic lockers should be continuous horizontally at a predetermined height for installation.
196.	Architecture	Drawing A651						Details refer to Atrium stair and Cohort Stairs-

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents		
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response	
197.	Architecture	Drawing A651						Should you refer to stairs by number so there is less chance for discrepancies. Detail 1&2 indicates precast concrete stairs treads but shows poured in place.	
198.	Architecture	Drawing A651						Detail 1 top of c-channel has dashed circle with not indication or call out.	
199.	Architecture	Drawing A652						Detail 12 depicts precast concrete stair treads, but call outs indicate both precast and concrete filled.	
200.	Architecture	Drawing A652						Detail 2 indicates precast stair treads.	
201.	Architecture	Drawing A652						Detail 6 has arrow indicating GWB, PTD but pointed to space.	
202.	Architecture	Drawing A652						Detail 3 correct spelling of stair / Floor side.	
203.	Architecture	Drawing A652						Detail 7 indicates precast concrete tread but depicts concrete filled.	
204.	Architecture	Drawing A690						Detail 6, How is the bottom of the GWB being attached and what are you anchoring the corner bead into.	
205.	Architecture	Drawing A690						Detail 5, at intersection into T-1 ¾" wall molding what supports wall molding. Tie wire?	
206.	Architecture	Drawing A691						Detail 8 needs further refinement. Has ? for 2 of the callouts.	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents		
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response	
207.	Architecture	Drawing A700						Partition D6- has 6" stud should have 5 1/2" batt insulation	
208.	Architecture	Drawing A700						Partition H6- has 6" stud should have 5 1/2" batt insulation	
209.	Architecture	Drawing A700						Partition C6- has 6" stud should have 5 1/2" batt insulation	
210.	Architecture	Drawing A700						Partition details D&M have large dashed line going thru detail.	
211.	Architecture	Drawing A710						Door 1065A exterior door from stair 2 should that have security film as well as all other exterior storefront glazing.	
212.	Architecture	Drawing A710						Door Schedule Comment "EL" is not on door abbreviations.	
213.	Architecture	Drawing A710						Only details SF3 & SF4 indicate security glazing. Should be on all exterior doors with glazing.	
214.	Architecture	Drawings						Drawing E300 shows plywood on electrical and IDF rooms by G.C. - Should be a note on Architectural drawings or it should refer you to the electrical drawings.	
215.	Architecture	Drawings						Where are the interior wood grilles located? Locate on floor plans or provide schedule.	
216.	Architecture	Drawings						Will you be providing standard masonry details indicating joint	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents		
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response	
217.	Architecture	Drawings						finish. Flush, concave, etc....	
218.	Architecture	Drawings						Show location and dimensions of any exterior Knox box and card reader locations around perimeter of school in masonry.	
219.	Architecture	Drawings						Masonry should provide detail of end dams or specify turn up dimensions.	
220.	Architecture	Drawings						Will Defibrillators and cabinets be located on plans.	
221.	Architecture	Drawings						Will there be Theater drawings issued note on drawing A460 references Theater Drawings.	
222.	Architecture	Spec. Section 072100						Will there be an exterior Mock up detail drawing issued.	
223.	Architecture	Spec Section 072100						Page 1 indicates curtainwall but not in current project.	
224.	Architecture	Spec Section 1248132						Rigid insulation at perimeter of foundation walls and under slab is by Concrete subcontractor.	
225.	Architecture	Specs						Has wrong page numbering.	
226.	Civil	All	Include Legends for all series of plans.	Legends will be included in 100% DD	Abbreviations are provided, but not comprehensive legends.	Additional legends were added to C4.0, C5.0 and C.6.0		Spec has numerous section that refers to Curtain wall system including Masonry, Cold Metal Framing, Rough Framing	Closed.



Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
227.	Civil	All	Include detail references.	Detail references will be included in 100% DD	No detail callouts are provided on Civil Plans.	Detail references added	Closed.	
228.	Civil	C-0.1 & 0.2	Include parking stripes for clarity	Existing spaces were not surveyed	Closed			
229.	Civil	C-1.0, 2.0 & 3.0	Phase 1 Notes: Note 1 – Clarify? Note 2 – Fence Limits are unclear & not in legend., Note 4 – Nothing shown as bold	Items to be demo are shown in bold (darker than other existing items). Fence is called out on plan.	Closed			
230.	Civil	C-1.0, 2.0 & 3.0	Clarify the disposition of utilities within demo areas. Remain, remove, abandon, cut/cap, etc.	Items in bold are to be demo'd.	Closed			
231.	Civil	C-1.0, 2.0 & 3.0	Identify salvage items.	No items have been identified to be salvaged.	Closed			
232.	Civil / LA	C-1.1 & L1.2	Civil and LA indicate different parking layouts, curbing, striping and sidewalk materials	Will coordinate Civil / LA	Closed			
233.	Civil	C-1.1	Does Phase 1 construction include both binder and wearing course? If just binder, striping will be done twice, & structures reset, this needs to be noted.	Pavement detail calls for only binder on temp parking areas. Temp striping and structure reset, will be based on CM's paving schedule.	Closed			
234.	Civil	C-1.1	Reconsider using SGC directly against sidewalk on west side of parking lot. Coordinate Phase 3 Fire Access Road with sidewalk and curbing.	Revisions have eliminated SGC, and most of the curb.	Closed			
235.	Civil	C-1.2	DMH3 indicates a stub for Phase "4", not Phase 3	Revised to indicated P3.	Closed			
236.	Civil	C-1.2	Consider a filter strip or stone apron at north edge of parking with no curb.	A grass and gravel filter strip was shown	Closed			
237.	Civil	C-1.3 & 2.3	No utility text/callouts are indicated. Pipe sizes etc.	Proposed sizes are shown, see MEP plans for additional info & sizing not called out.	Closed			

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
238.	Civil	C-1.4	Clarify limits of pavement, binder or full depth asphalt.	Pavement detail calls for only binder on temp parking areas.	Closed			
239.	Civil	C-2.x	Clarify limits of Phase 1 and Phase 2 work on Phase 2 drawings.	Phasing plans were updated based on Consigli's phasing.	Closed			
240.	Civil	C-2.3 & C-6.x	Clarify if utilities are in Phase 2 or Phase 3, no roof drains shown.	C-2.3 shows the utilities to be installed for P2. Roof drains are shown.	No further comment, see new comments.			
241.	Civil	C-2.3	Has City Fire and Water Depts approved a 600'+ dead end water pipe for the hydrant to the north?	Its been reviewed, CDW is not aware of a requirement to loop the main.	Closed			
242.	Civil	C-2.3 & C-6.1	Coordinate building utilities and roof drains	Roof drains are shown. Bldg. utilities will continue to be coordinated.	See new comments, coordination not complete.	Building utilities and roof drains have been further coordinated.	Closed.	
243.	Civil	C-3.0	Is entrance drive constructed at the end of Phase 2 or in Phase 3.	The construction entrance is for P2.	Not shown on Civil Phase 2 plans	A construction entrance is shown on P2 C2.0	Closed.	
244.	Civil	C-3.0	Define Phase 3 enabling and/or temporary work.	P3 is the demolition of the exist bldg	Closed			
245.	Civil / LA	C-4.X & L	Coordinate sidewalk locations, curbing and striping.	Plans have been revised.	Closed			
246.	Civil	C-4.1	Are gates proposed for the Fire Access Road?	Gates are shown.	Closed			
247.	Civil	C-4.1	Review loading geometry with truck turning movements	Loading area revised.	Closed			
248.	Civil	C-5.X	Has it been Closed that no stormwater recharge is required for the project?	Recharge is required, plans have been updated.	Closed			
249.	Arch/Plumb/ Civil	C-6.1	Is the FDC located in the raised main entrance plaza? Is this acceptable.	Yes, and a hydrant is shown within 100-ft of the entrance.	Closed			
250.	Civil	C-7.2 & 7.3	Repeated and conflicting details on these 2 sheets.	Has been revised	Closed			
251.	Landscape		Building Footprint does not match Arch or Civil dwgs.	Will be coordinated	Closed			
252.	Landscape		Coordinate drainage system structures with civil.	Will be coordinated	Closed			
253.	Landscape		Show light poles on all enlargements and Planting Plans for coordinating design.	Light Poles will be shown.	See new comments to coordinate locations with Electrical	OK	Closed.	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
254.	Architecture	Specifications	TOC is missing 320000 & 329000, headers are not consistent throughout. Check that cross-referenced sections are included.	Will be revised.	No further comment			
255.	Civil	Specifications		Will review and revise as necessary.	No further comment			
256.	Civil	Specifications	Storm Drainage piping materials do not match what is on plans.	Piping on plans and specs is a mix of HDPE, PVC, and RCP.	No further comment			
257.	Civil				No Detail callouts are provided.	Detail callouts have been added	Closed.	
258.	Civil	C-4.1			No details for retaining walls either side on building entrance.	A generic detail is provided, final detail to be by wall manufacturer	Closed.	
259.	Civil	C-4.1			Provide concrete pads at building exterior doors, and walkways where needed.	Concrete pads shown	Closed.	
260.	Civil	C-4.1			Building doors at rear center are not coordinated with Architecture	Building doors updated	The door out of the Art Room appears to be shown in differing locations.	
261.	Civil	C-4.1			Is there a solution to the fire access road being so close to the building in 2 locations due to the 50' wetland setback and the width of the road?	The building wall has shifted further south	Closed.	
262.	Civil	C-4-x			Additional layout & dimensioning needed	Has been further developed	Closed.	
263.	Civil	C-5.1			An enlarged grading plan with spot elevations for the entire front entry loop would be very helpful.	Grading of the amphitheater and loop area is still ongoing. Specifically, the amphitheater area was layout and graded by the LA	Further detail and spot elevations will clarify critical areas like entry, ramps, walls, intersections, etc. A 165 contour is missing north of amphitheater.	
264.	Civil				Add Generator, adjust Transformer	Generator and transformer pads added	Clarify grading & dimensions/location	
265.	Civil / FP / Plumbing	C-6.1 / FP101A / P101A			Coordinate size and location of Fire Protection Service.	Size and locations coordinated	Closed.	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
266.	Civil / Plumbing	C-6.1 / P100A-C			Coordinate size, location and inverts of roof drains, water service and gas service	Size, locations, inverts coordinated	Plumbing exits perpendicular, site is angled, coord & show as intended and add cleanouts where needed.	
267.	Civil / Plumbing	C-6.1 / P100A			Show size, detail and invert information for grease trap & SMH between GT & building. Indicate contract limits as done for Acid NT between Plumbing & Civil.	Grease trap and the SMH between GT and the build will be detailed by plumbing at it falls under plumbing code.	Plumbing did not show on 90%, and their drawing say by Div. 33 after 10'. Info previously shown for SMH-1,2 & 3 on C-6.1 and C-6.2 is missing on 90%	
268.	Landscape	L1.1			Dimension & locate fields and BB Court.	Dimensions will be added at 90%CD	Closed.	
269.	Landscape	L1.1			What is 2' wide strip at north edges of pavement in loading area?	This should be part of the planting bed. Drawing will be corrected.	Closed.	
270.	Landscape / Civil / Architecture / Electric	L1.3			Coordination of items referenced in other disciplines: Entrance Plaza, Guard Rail, Concrete Ramps, Concrete Pavers, CIP & Unit Block Retaining walls, Pavilion, and lighting.	The landscape materials plan does call out items and reference the other disciplines. We will continue to coordinate.	Closed.	
271.	Landscape	L1.3			Provide Detailed Layout information and dimensioning.	Dimensions will be added at 90%CD	Closed.	
272.	Civil	C-1.1					Site lighting poles should be shown for coordination, as they are for the other phases.	
273.	Civil	C-1.4					Label headwalls (HW-1 & HW-2) to correspond with details 2/C-7.2 and 10/C-7.3.	
274.	Civil	C-5.1					Is there an outlet detail for the roof drains as they discharge into the stormwater basins?	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
275.	Civil	C-2.3					The sewer connection reference to C-4.0 should be C-6.1??	
276.	Civil	C-6.1					Indicate clear routing of utilities east of main entrance. Many utility crossings.	
277.	Civil	C-7.1					Detail 5 indicates 3 feet of "soil Media" for bio-cell & trees and shrubs. Only 2 trees appear to be in bottom of basins. Does this 3 feet cover the entire bottom of the basins? Define limits or correct detail.	
278.	Civil / Architecture	C-7.6 / A490					Detail 2 on C-7.6 indicates a different top of wall treatment than 3/A490	
279.	Landscape / Architecture	L1.6					Landscape drawing says the exterior Plaza and planter east of the Makerspace room is on Architectural drawings. I could not find it.	
280.	Landscape	L2.2					The civil drawings indicate a 10 x 35 concrete pad at the loading area, the landscape plan shows 4 squares in this area, clarify.	
281.	Landscape / Architecture	L3.0					Landscape drawings indicate that the site stair railings are on Architectural drawings. Where are these located?	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents		
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response	
282.	Structural & Architecture	S401 / A490 & A491						Coordinate the top of walls on S401 and A490 & 491..	
283.	Architecture	A490						#7 Plan indicates 12" diameter footings, #3 section does not. What are these footings for? Closed.	
284.	Structural	S-000	Some additional design load information for the structure should be provided. Refer to IBC Section 1603.1	A design load schedule is provided in the 60% CD drawings.	Noted. Still missing the snow drift surcharge loading and extent. This is usually indicated on the roof plans where the snow drifting applies.			A dedicated snow drift plan has been included: S002	
285.	Structural	S-101A	Indicate slab on grade size and reinforcing.	Comment addressed in 60%CD drawings	OK. However, slab not indicated on drawing 1-101A. Closed.			This has since been corrected.	
286.	Structural	S-101A, S-101B, S-101C, S101D	Indicate slab on grade sawcut control joint locations.	In exposed concrete areas joints are to be shown on architectural drawings. At non-exposed areas, the typical detail showing control joint layout can be used.					
287.	Structural	S-101A, S-101B, S-101C, S101D	Column sizes should be shown.	Comment addressed in 60%CD drawings where there is a column schedule.	Ongoing. Columns schedule in Closed, base plate sizes, elev. and anchors not shown.			Drawings S202 and S203 now include base plate and anchor bolt designs	
288.	Structural	S-101A, S-101B, S-101C, S101D	Pricing notes are vague and should be more specific for DD level. Typical wall and pier sections with reinforcing should be shown	Pricing notes have been removed and reinforcement is shown in section.	Ongoing. Limited foundation details provided in 60% set.			More details have since been provided.	
289.	Structural	S-101A, S-101B, S-101C, S101D	MSBA requires footing elevations to be shown on the plan along each section and not just in a note.	Bottom of footing elevations will be shown in the next set of drawings.	Ongoing. Elevations not shown,			Bottom of footing elevations have since been provided.	
290.	Structural	S-101A, S-101B, S-101C, S101D	Gridlines and dimensions should be shown.	A geometry layout plan will be generated to define the complex geometry of the grid system.	Closed.				

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
291.	Structural	S-101A, S-101B, S-101C, S101D	More info is required on the extent and depth of the Geo Piers under the footings and the slab-on-grade.	This information is described elsewhere as part of the ESP.	Closed.			
292.	Structural	S-102A, S-102B, S102C, S102D	Typical grid and general framing dimensions should be shown at DD level submission.	Comment addressed in 60%CD drawings	Ongoing: There are no grid dimensions shown on any of the foundation or framing planes.	A dedicated grid dimension drawing has since been provided: S001	Closed.	
293.	Structural	S-102A, S-102B, S102C, S102D	Typical member sizes for beams and girders should be shown for DD Level submission.	Comment addressed in 60%CD drawings	Closed.			
294.	Structural	S-102A, S-102B, S102C, S102D	What is the fire rating of the floor assembly? Are the framing members fireproofed?	Floor rating and steel members are rated 2HR, refer to code report.	Noted. There should however, be some reference to the code drawing on the structural drawings. Are all members fireproofed, or do some get other treatments such as Intumescent paint, etc.	A fireproofing diagram has been included in the set, see A002, added in PR 12.	Closed.	
295.	Structural	S-102A, S-102B, S102C, S102D	Typical framing details should be shown at DD Level, including typical exterior wall support details	Comment addressed in 60%CD drawings	Ongoing: Limited detailing has been provided in 60% set. Coordination with Arch. Details is required throughout.	Details have since been provided.	Closed.	
296.	Structural	S-102A, S-102B, S102C, S102D	What is the Top of Steel Elevation?	Comment addressed in 60%CD drawings	Closed.			
297.	Structural	S-102A, S-102B, S102C, S102D	Will there be any expansion joints at this level?	No expansion joints at this level.	Closed.			
298.	Structural	S-103A, S-103B, S103C, S103D	Typical grid and general framing dimensions should be shown at DD level submission.	Framing dimensions will be added and grid geometry will be defined.	Ongoing: There are no grid dimensions shown on any of the framing planes.	A dedicated grid dimension drawing has since been provided: S001	Closed.	
299.	Structural	S-103A, S-103B, S103C, S103D	Typical member sizes for beams and girders should be shown for DD Level submission.	Comment addressed in 60%CD drawings	Closed.			
300.	Structural	S-103A,	Typical member sizes for beams and girders should	Comment addressed in 60%CD drawings	Closed.			

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
			be shown for DD Level submission,					
301.	Structural	S-103B, S103C, S103D S-103A, S-103B, S103C, S103D	What is the Top of Steel Elevation?	Comment addressed in 60%CD drawings	Closed.			
302.	Structural	S-103A, S-103B, S103C, S103D	Will there be any expansion joints at this level?	No expansion joints at this level.	Closed.			
303.	Structural	S-103A, S-103B, S103C, S103D	Typical braced frame member sizes should be shown.	Comment addressed in 60%CD drawings	Ongoing: Member sizes shown, but required connection forces and typical details not shown. (Per Mass. Code the connections require a 2E multiplier for seismic loading when using R=3.	Design forces have since been shown on the braced frame elevations for delegated connection design and have been doubled per code.	Closed: However, note that the only the seismic forces need to be doubled in any particular load combination, and not the whole combination load. Thus, some of your forces may be a bit on the high side.	
304.	Structural	S-103D	Should the roof deck over the Gym be acoustical deck?	This has been updated. And the gym roof is now acoustical deck in 60% CD drawings	Closed.			
305.	Structural	S-104-B, S104C	Typical braced frame member sizes should be shown.	Comment addressed in 60%CD drawings	Ongoing: Member sizes shown, but the required connection forces and typical details are not indicated.	Design forces have since been shown on the braced frame elevations for delegated connection design and have been doubled per code.	Closed.	
306.	Structural	S-104B, S-104C	Typical grid and general framing dimensions should be shown at DD level submission.	Framing dimensions will be added and grid geometry will be defined.	Ongoing: There are no grid dimensions shown on any of the framing plans.	A dedicated grid dimension drawing has since been provided: S001	Closed.	
307.	Structural	S-104B, S-104C	Typical member sizes for beams and girders should be shown for DD Level submission,	Comment addressed in 60%CD drawings	Closed.			
308.	Structural	S-104B, S-104C	Typical member sizes for beams and girders should be shown for DD Level submission,	Comment addressed in 60%CD drawings	Closed.			



Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
309.	Structural	S-104B, S-104C	What is the Top of Steel elevation at this level?	Comment addressed in 60%CD drawings	Closed.			
310.	Structural	S-104B, S-104C	Will there be any expansion joints at this level?	No expansion joints at this level.	Closed.			
311.	Structural	S-105B, S-105C	Typical Sections at roof screen and top of steel elevations should be shown.	Comment addressed in 60%CD drawings	Ongoing.		Details have since been provided	Closed.
312.	Structural	S-200, S-201	Is there any special finish required on the exposed steel?	These clerestory trusses have since been eliminated from the project	Closed.			
313.	Structural	S-300	Detail 10: Diamond isolation joints should be avoided as the joints in diamonds will telegraph thru the floor finishes.	Project team will review detail and potentially change to pinwheel isolation joint detail.	Closed.			
314.	Structural	S-300, S-301, S-302, S-303	Typical concrete and steel details should be provided for the DD set.	Comment addressed in 60%CD drawings	Noted. Continued detailing should be Ongoing. For CD set.		Details have since been provided	Closed.
315.	Structural	S-000	Include an allowance for partition loading in the floor Live Loads.	A design load schedule is provided in the 60% CD drawings. Classrooms include 15psf partition loads.	Closed.			
316.	Structural	S-000	Include Design Live Loads for atypical spaces.: Gym, Auditorium, Cafeteria, Media Center/Library, Lecture Halls, etc.	A design load schedule is provided in the 60% CD drawings.	Closed.			
317.	Structural	S101A, S1001B, S101C, S101D			The grade beams between footings appear to be sitting on the footing. Is this the case, or should they stop outside the footing as both the grade beam and footing are indicated to be 1.2" below slab.		Grade beams geometry has since been updated but in general grade beams match bottoms of footings.	Closed.
318.	Structural	S101A, S1001B, S101C, S101D			Given the need for Preconsolidation/ Surcharge of the soils under the SOG, is a 5"		Yes, it is sufficient.	Closed.

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
319.	Structural	S101A, S1001B, S101C, S101D			All top of interior footings are indicated to be 12" below slab. Some may need to be dropped at roof drain leaders and at underground piping runs. Coordinate top of interior and exterior footings with the Below-Slab Plumbing drawings, P-100A, B, C, and D.	This needs to be coordinated.	Ok. Ongoing.	
320.	Structural	S101A			How are the lateral earth forces being resolved into the Floor 2 framing? Shouldn't this wall be designed as a cantilevered retaining wall and not a typical foundation wall. Review Sections 1- S300 and 3- S400.	The wall on grid M is designed as a basement wall with some of the earth forces going into the 2 <sup>nd</sup> floor diaphragm	Please clarify. Has the wall been designed for at-rest loading from the soil? Also, how is the reaction at the top being resolved? Thru the braced frames? There is over 2000 lbs /ft reaction at the top of the wall. This leads to very large forces in the braces and very high lateral forces in the footing. How is that being handled? Closed.	
321.	Structural	S101A, B, C, and D.			Are there any special floor Ft and FI requirements for wood flooring or Floor tiles, etc. Review requirements with flooring specs. (typ.).	Concrete spec lists special requirements for wood floor & tile.		
322.	Structural	All framing plans.			Where are the edge of slab dimensions indicated? Not shown on EOS Architectural Plans or Structural Drawings. Will the edge of slab be on a radius	Edge of slab dimensions are shown on Architectural drawings. Edge of atrium is segmented.	Closed.	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
323.	Structural	S102A, S103A			Line S5.7. Check beams supporting posts. They appear to be undersized. See also item 40 below. At Floor 3 the HSS post should be tied back to the concrete deck and not just to underside of beam.	Beam sizes have since been updated and posts go to deck underside	We are still seeing W12x16's under the posts up. Impossible to get a good bolted connection for the post's base plate on a 4" beam flange. Please review.	
324.	Structural	S502			Review design of canopy roof, especially cantilevered members south of Line M at the connection to column Line M.	The canopy is in the process of being redesigned for a new architectural approach	Ongoing.	
325.	Structural	S102B			Check design and deflections of W12x19 and W12x16 spandrel beam on Line R3.8 and just off Line R3.	There is no longer a W12x16 in this area.	We are still seeing the W12x16's in some places. Check the W12x16 on Line R3 between N7 and N8. Appears undersized. Also check the W12x16 supporting the W21x62 between N8 and N8.1, north on line R3.	
326.	Structural	S102B			Check sizes of all HSS columns with HSS beams framing into them. Ex. Cols.B/ N7 and B/N8 where there is an HSS 5x5 column supporting a HSS 20x 8" girt.	Column sizes are not an issue. Connections will be reviewed.	On-Going: You should seriously consider increasing the width of the columns to match the horizontal girts.	
327.	Structural	All framing plans.			There are many HSS beam to Column moment Connections. These need to be detailed in order to show how these connections are to be fabricated. And if any special stiffeners are required.	More connection design details have since been shown on drawings.	Closed.	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
328.	Structural	S102C			Check design of girders supporting coped W21x111 beams between S1 and S3 lines.	The W16 and W18 girders have been checked.	Closed.	
329.	Structural	All framing plans,			Check allowable spans for 3'x18ga composite deck accounting for skewed sections that may dictate single span vs multiple span layout.	This has been checked.	Closed.	
330.	Structural	S103B			Check design of girders supporting coped W21x111 beams between S8 and S10 lines.	The W16 and W18 girders have been checked.	Closed.	
331.	Structural	S103B			Review hanger details at Breakout Bridge and Space. May want to Beef up W12x16's at Hangers. See ASCE-7 for hanger connection multiplier requirements.	Beam sizes have since been increased at the high roof. Hanger connection details are being finalized.	Closed.	
332.	Structural	S103B			Is any sway bracing required at the Breakout Bridge or Space?	The bridge has in-plan truss action from added angles to provide stability.	Closed.	
333.	Structural	S104B, and S104C.			Coordinate proposed size and location of mechanical rooftop units. Frame out openings as required.	This has since been coordinated.	Closed.	
334.	Structural	All framing plans all levels.			Coordination with MEP drawings for all floor penetrations, duct shafts and openings etc. is required.	This has since been coordinated.	Closed.	
335.	Structural	S103D			Review stage rigging supports with theatrical drawings. Are there any lateral loads from the thrust and head blocks etc.	Rigging support steel has since been shown. Loads provided by theatre consultant have been incorporated.	Closed.	
336.	Structural	S102A			How are the wall fins attached to the building on Line M, and other similar areas.	Ongoing	Ongoing.	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
337.	Structural	S102A, S102B and S102C			Has the weight of the brick and snow drifting been account for on the low roofs?	Yes, these loads have been accounted for.	Closed.	
338.	Structural	S103D			The masonry bearing wall on the west side of the gym is not continuous to roof. Please review. See A213.	It should be. This has been corrected.	Closed.	
339.	Structural	All framing plans			Coordinate all loose and hung lintel requirements with Architectural drawings. Roof joists over the gym where required should be designated as (SP) or special loaded joists. Mechanical unit weights with snow drifting, wind and seismic loading as well as gym equipment loads need to be identified in order to properly design the joist.	Structural exterior elevations showing loose lintel extent has since been included. A dedicated drawing S003 - STEEL JOIST LOAD DIAGRAMS has since been included which contains all the necessary information. All joists on the projects are SP joists.	Closed.	
340.	Structural	S103D						
341.	Structural	S-000						Please review future PV loading noted as 10psf. The loads are dependent on the angle of the PV panels. The localized loading needs to be taken into account where the ballast loads locally are several hundreds of pounds, which can overload the decking. Recommend a minimum of 20 psf for ballast PV's and racking system.
342.	Structural							With a structure this complex it would be beneficial to

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
343.	Structural	S-503 Details 2,3,4,5 and 6.						review all members in plan one more time to make sure that nothing has been mislabeled. Check the joist seats depths as drawn. Typical DLH joists have a 7.5" seat not 6.5" or 5". Is it possible to align all of the cantilevered WT beams with the columns. This would lead to a cleaner stronger frame.
344.	Structural	S-502, Canopy Section 5.						Review connection for adequacy at HSS14x10 to Column at M/S5.7 Check deflection of 32' +/- Cantilever
345.	Structural	S-502 Entrance Canopy Framing plan.						
346.	Structural	S-502 Entrance Canopy Framing Plan.						
347.	Fire Protection	General	Are intermediate fire department connections required?	Will review with AHJ. Standpipe connections are currently 360' +/- apart. Intermediate standpipe may be requested.	Open	Added a FDV for the middle open stairs in the atrium.		Item still open – has it been verified with Fire dept no additional roof manifolds are required? Open
348.	Fire Protection	FP1.01	Coordinate exact scope of Division 21 work with Civil. Exact scope of work is missing. Suggest site utility dwg as part of FP set, including details.	Agree. FP will reference site utility spec. Fire service from water main into building will be installed by Division 21.	Open. Suggest this scope be located on the FP drawings and not just reference to Civil documents to avoid public bid issues.	Will include Civil site utility drawings as part of the FP Scope		Open
349.	Fire Protection	General – floor plans	Typical room sprinkler layouts missing	Will provide sprinkler head layouts.	Open. MSBA requires sizes and branch piping as well at this submission. Open	Branch Piping and sizes will be shown in the 90% MSBA Submission		Closed.
350.	Fire Protection	General – floor plans	Verify height of floor control assemblies is in accord with Fire Dept requirements. Height may not be allowed over 7 ft.	Will review with AHJ	Open	Will review with AHJ		Open

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
351.	Fire Protection	FP1.03	Fire Dept Valves may not be allowed to be installed in dressing rooms behind stage; especially if rooms are lockable.	Fire department valves would be accessed from the corridor, not located in dressing rooms. Will coordinate with AHJ on preferred location of valve cabinets.	Open	Will review with AHJ	Closed.	
352.	Fire Protection	General - roof	Are roof manifolds required or desired by Fire Dept?	Roof manifolds are required. Will review with AHJ on preferred location.	Open	Will review with AHJ	Open	
353.	Fire Protection	FP101A			Loading dock area (outside) will require dry sprinkler protection/dry sidewall protection.	Will review with AHJ. Sprinklers are not required for non-combustible canopies with no storage below.	Open	
354.	Fire Protection	FP101A			Exterior fire protection to include fire mains, hydrants, tapping sleeves, curb stops, etc. No documentation seen.	Civil site utilities drawing will be included as part of the FP Drawings	Open	
355.	Fire Protection	FP101A			Why is water tight sleeve provided for fire main through foundation wall?	Will be removed	Open	
356.	Fire Protection	General			Sprinkler system branches missing. Sprinkler protection missing from scattered areas/rooms throughout. Sprinklers missing below stairs.	All areas will be sprinkler protected. Branch pipes will be shown in the 90% MSBA Submission	Closed.	
357.	Fire Protection	FP101A			Sprinklers missing in areas such as Breakout room 1054 and low ceiling space at left of it.	All areas will be sprinkler protected.	Closed.	
358.	Fire Protection	FP102A			Is only one Storz FDC required or additional locations required by local Fire Dept?	Will review size and location with AHJ	Open	
359.	Fire Protection	General					Suggest including RCP in background for coordination. Also, room names	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents		
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response	
360.	Fire Protection	FP001						and soffits missing from background at times. Water service entrance detail shows grade beam. No grade beams seen	
361.	Fire Protection	FP001						Double check backflow preventer diagram shows incorrect elevation for assembly. Required to be 48" max to top of device per Mass. DEP, not 53".	
362.	Fire Protection	FP001						Flow test data is now out of date. (6 months max)	
363.	Fire Protection	General						Verify wet sprinklers are desired in emergency electric rooms as indicated. If 1 hr enclosure provided, they aren't required except if mandated by local AHJ	
364.	Fire Protection	General						Many floor plans show sprinkler heads but no piping to them (example, dwg FP101A, shop #1134)	
365.	Fire Protection	FP101B						Sprinkler protection missing from Breakout room which is also not labelled.	
366.	Fire Protection	FP101C						Verify heat is provided in plenum above entry vestibule 1045 to avoid Winter sprinkler pipe freezing	
367.	Fire Protection	FP102B						Dry sprinkler heads - piping missing	



Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents		
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response	
368.	Fire Protection	FP102C						3 sprinkler heads adjacent to each other in/at classroom walls – suggest a section be developed for clarity.	
369.	Fire Protection	FP104B						Inadequate sprinkler protection in stair	
370.	Fire Protection	FP104C						Suggest section to clarify where sprinkler is located and how piping is routed	
371.	Plumbing	P0.01	Water heater and pump schedules missing	Schedules are not provided on drawings. Equipment will be indicated in specifications.	Closed			Closed.	
372.	Plumbing	P0.01	Backflow preventer detail – dimension to floor is to be from bottom of device to floor per Code.	Agree	Open			Closed.	
373.	Plumbing	P0.02	Detail 1 – Is redundancy required for water heater?	Will review with Owner	Open			Closed.	
374.	Plumbing	P0.02	Detail 1 – Valve and pump not allowed between heater and expansion tank. Also, check valve upstream of heater on CW supply not allowed without inspector permission. Mixing valve should be installed below top of heater.	Detail to be corrected.	Open			Closed.	
375.	Plumbing	P0.02	Detail 3 – No valve allowed between heater and expansion tank. Also, check valve upstream of heater on CW supply not allowed without inspector permission. Swing check valve installed in vertical position may not function.	Detail will be corrected.	Open			Open. Shut-off valves between expansion tank and heaters are still present.	
376.	Plumbing	P0.02	Detail 4 – Verify chip tank is sufficient for chemicals used. pH adjustment system required? Depth of	Will review once chemical list is provided.	Open			Open. Review new MSBA direction on acid neutralization. The direction is to	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
			vault structure may not be deep enough.				tank will be sized per Table 10.13 (7)	eliminate these systems, but must be coordinated with faculty
377.	Plumbing	General – below slab plans	Verify no footings bearing on piping below slab. Also, wall footings to be dropped at pipe exits and entrances to building.	Will coordinate with structural engineer.	Open	Coordination is ongoing.		Open
378.	Plumbing	General – sanitary venting	Some venting indicated appears to not meet Code.	Please specify location.	Water service room, for instance. Open	All vents will be shown.		Open
379.	Plumbing	General – Plumbing chases	Plumbing chases should be verified for adequate depth to accommodate fixture carriers/piping. Some look shallow.	Will be coordinated with Architect.	Open	Coordination is ongoing.		Open
380.	Plumbing	General – structural/architectural/plumbing coordination	There appear to be many instances of plumbing chases and walls with plumbing risers being located directly over beams. Requires coordination.	Will coordinate with Architect.	Open	Coordination is ongoing		Open
381.	Plumbing	General	Recommend hot water be recirculated directly behind all lavatories to ensure timely hot water with low flow faucets.	Will review.	Open	Will be shown near lavatories.		Open
382.	Plumbing	General	No natural gas indicated on plans	Natural gas will be shown for boiler, water heater, kitchen science classrooms on first level, and generator	Open	Will be shown on 90%CD		Open. Not complete
383.	Plumbing	General	Exterior wall hydrants missing throughout	Will provide	Open	Will be shown on 90%CD		Open. Not complete
384.	Plumbing	P2.01	Emergency shower/eyewash required in boiler room at water treatment – corrosives used	Will be provided in mech room.	Open	Will be shown on 90%CD		Open
385.	Plumbing	P2.02	Hot water expansion loops missing	Expansion fittings are required by specifications. Will review drawings for required locations.	Open	Will be shown on 90%CD		Closed

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
386.	Plumbing	P2.02	Suggest hot water recirc. loop with small elec heater for non-potable hot water system to Science classroom sinks.	Agree.	Open	Will be electrical heat trace for temperature maintenance	Closed	
387.	Plumbing	General - Science rooms	No emergency shower- Eyewash stations seen in Science Classrooms.	Emergency fixture will be provided in Science rooms.	Closed			
388.	Plumbing	P2.03	Toilet/Shower room 1310 - Recommend floor drain outside shower.	Agree. Will provide	Closed			
389.	Plumbing	General	Roof drainage seems to be missing from most of the set. Is secondary roof drainage required?	Primary roof drains now shown. Secondary system not required.	Closed			
390.	Plumbing	P3.03	Floor drain required for water heater and backflow preventer.	Agree. Will add.	Closed			
391.	Plumbing	P3.03 & P3.04	Emergency showers/eyewashes missing in Science classrooms	Emergency fixture will be provided in Science rooms	Closed			
392.	Plumbing	General - Acid waste/vent			Polypropylene piping is not plenum rated. Need to specify PVDF or plenum rated wrap for piping in return air plenums	Noted. Acid waste / vent will not be running inside the air plenum.	Open. This assumes there is no horizontal acid waste or vent piping, although it is shown on plans.	
393.	Plumbing	P001			RP-1 indicated on water heater diagram is not piped	RP-1 is a prepackaged with Tempering valve assembly. See detail 6 on Dwg P004 for pipe connection	Open. How is RP-1 piped; where connected?	
394.	Plumbing	P002			Detail 7 - water meter to be specified & sized, state pressure settings on PRV's. Pipe sizes missing.	Pressure and size has been addressed on detail 7	Closed	
395.	Plumbing	P002			Detail 11 - Verify if this a seismic category B or C building. If B, no seismic bracing required.	Seismic bracing is not required.	Closed	
396.	Plumbing	P002			Detail 14 - Sizes missing.	Gas pipe to building has been shown on the plan	Closed	
397.	Plumbing	P003			Detail 2 - Verify clearance for plaster	Will coordinate	Item open	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
398.	Plumbing	P003			Detail 8 – If this is for storm drainage tie-in, suggest a backwater valve be added.	Trap with float backwater valve has been specified.	Backwater float valve may "spit" (during rain deluge)	
399.	Plumbing	P004			Detail 1 – Specify frame/cover and "box" if any, for grease trap.	The grease trap is floor recessed type.	Closed	
400.	Plumbing	P004			Detail 5 – locate CO detectors on plans.	Has been shown on the plan	Item open – not seen	
401.	Plumbing	P004			Detail 1 – verify whether heat is required in vault.	The detail is for the interior grease interceptor.	Closed	
402.	Plumbing	P004			Detail 2 – Locate mixing valves on plans/ coordination with architecture.	The detail 2 is for the lab sink faucet pipe connection. The casework will be coordinated with architect.	Closed	
403.	Plumbing	P005			Detail 4 – Dual check valve/VB shown. Verify reduced pressure backflow preventer is provided. Only a dual check valve/VB does not meet Code.	The lab cold water is protected through reduced pressure backflow preventer.	Closed	
404.	Plumbing	P001					Shock absorber schedule – Verify pressure doesn't exceed 60 psi; if it does, shock absorbers need to be over-sized	
405.	Plumbing	General – acid neutralization					Review new MSBA direction on acid neutralization. The direction is to eliminate these systems, but must be coordinated with faculty	
406.	Plumbing	P001					Expansion tank schedule – size looks very small for the water heater inputs.	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents		
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response	
407.	Plumbing	P001						Water heater diagram – Sub meter (SM-1) should be on the cold water feed to the water heaters. The arrangement shown will register every time the circulating pumps are on as well as when hot water being used... Not an accurate reading.	
408.	Plumbing	P002						Detail 3 – Insulation shield not sized, based on pipe size, etc.	
409.	Plumbing	P002						Detail 5 – which sinks require mixing valves?	
410.	Plumbing	P003						Detail 1 – where is access panel owned? (typical throughout – all systems)	
411.	Plumbing	P005						Recessed emergency shower/eyewash detail – verify a piped waste connection is not desired by school for testing. Suggest providing a emergency shower testing unit	
412.	Plumbing	General – Below slab plans						Not complete – sizes/notes/crossing pipe inverts missing	
413.	Plumbing	P100B						8" RL shown in the building but 10" outside. 10" is correct unless sloped at ¼" per ft	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents		
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response	
414.	Plumbing	General – below slab plans						Floor cleanouts missing per Code. (every 50' or 100' based on size) Architect will want these located for coordination	
415.	Plumbing	P101A, P200, P201						Kitchen plans are not complete – lacking information and clarity.	
416.	Plumbing	General; plans						Pipe sizes missing at times, valves missing, vent piping missing, pipe notes missing.	
417.	Plumbing	P101A						Verify adequate clearance between gas meter and building opening (door)	
418.	Plumbing	General – plumbing chases						Verify adequate chase dimensions throughout – Many look too shallow; especially behind water closets, such as on dwgs P101B, P101C (near Fab Lab), P102B, P102C, etc. Also, there appear to be conflicts with cross-bracing and beams below “wet” walls and chases.	
419.	Plumbing	P102B						Horizontal AW piping in plenum ceilings not allowed to be Polypropylene unless fire/plenum wrap used. (typical throughout)	
420.	Plumbing	General – trap primers						Trap primers generally not indicated on plans. Suggest locating and specifying	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents		
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response	
421.	Plumbing	General – Electric water coolers						which type is to be used and where. Verify adequate clearance behind all units for recessed chillers or specify only non-recessed type (could be a problem for situations such as on P102C, at Toilet 2152)	
422.	Plumbing	General						Plans at times appear to be incomplete and not cohesive with missing information, such as on P102C – where are P-10 emergency showers fed from?	
423.	Plumbing	P104						Verify all VTR's are no closer than 25' to fresh air intakes	
424.	Plumbing	P200						FS-1 at walk-in cooler/freezer for condensate drainage. Verify 300 gal/day is not exceeded. Also, verify with local plumbing inspector this drain can run to exterior grease trap (typical comment for kitchen hand sinks also)	
425.	Plumbing	P200 and 201						Plans incomplete. Also, kitchen and Custodian toilets scope is missing	
426.	Plumbing	P101A						Custodial area/receiving normally includes a clothes washer/dryer. None seen. Is this in scope?	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents		
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response	
427.	Plumbing	P300						Plans incomplete. Also, what is the oil/water separator for? Not seen on plans – it appears this might be acid waste? If this is a true oil separator, might need a DEP approved unit	
428.	Plumbing	P400-402						Riser diagrams – sizes missing	
429.	HVAC	GENERAL	Add key plan to all drawings	Key plan has been added to the drawings.	Closed				
430.	HVAC	M104	Suggest heat to be added in the mechanical pump house	Agreed. A unit heater has been added to the pump house.	Closed				
431.	HVAC	M104	Consider double doors into the pump house	Agree, double doors can be provided in lieu of (2) single doors. plans updated.	Open		Double doors will be included on the 90% drawing submission.	Closed	
432.	HVAC	M104	Add floor drains to pump house	We will review with manufacturer and plumbing to provide floor drains in the pump house.	Open		Floor drains will be provided on the 90% drawing submission.	Not located on M104. There is no pump house detail to confirm.	
433.	HVAC	M104	What is the makeup air for SEF-1 through SEF-4. Where is it shown?	Make up air for the smoke exhaust system will be provided by the architect via mostly louvers and potential for south entrance doors.	Not clear on life safety plans LS101-LS103. Suggest an airflow riser indicating locations/sizes.		We will coordinate with the architect to provide a more accurate diagram on the life safety plans. HVAC drawings will also indicate these make-up locations.	Closed	
434.	HVAC	M103C M102B	Please indicate why two dampers are shown normally closed and one shown normally opened?	The motorized dampers are provided to isolate RTU-1 & 2 from RTU-3 & 4 in the ring duct system, but maintain redundancy. This has since been eliminated via VM.	Can you please explain redundancy of this? It is not identified in the OPR or HVAC system description. Closed.		If any of the four RTU's were to have a failure, the other three rooftop units would be able to supply conditioned air to the spaces that would normally be conditioned by the now out-of-service RTU. The dampers were provided to isolate the various RTU systems during	Closed	



Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
435.	HVAC	M305	All motorized dampers shown on the rooftop unit airflow diagram are tagged normally opened. See note above.	Half of the motorized are indicated as normally open, and half are normally closed. Thru VM, these dampers have been eliminated, see item 145 response.	Can you please explain redundancy of this? It is not identified in the OPR or HVAC system description. Closed.	Closed	normal operation, and in the event of a system failure, the dampers could be opened to create a single duct system. As indicated in DD designer response, these dampers and ring ducts have been eliminated per VE. See item 297 response.	
436.	HVAC	M305 M306	Chilled water flow diagram needs to be shown with air cooled chillers (2) and pump house on the roof. Coordinate these two diagrams please.	Thru VM, the quantity of chillers has been reduced to 1. The flow diagrams will be updated to reflect this.	Closed.	Closed.		
437.	HVAC	Fire Protection Chapter 9 Smoke Control (909)	Provide document that shows the firefighters smoke control panel.	This will be indicated within the controls series drawings in future submissions.	Open.	Open	This will be coordinated with Electrical/Fire alarm included in the 90% submission.	
438.	HVAC	Schematic Design HVAC Narrative Part O	The new BMS is indicated as proprietary by Advanced Energy Management Systems. Please confirm if correct.	BMS narrative and specification updated to be non-proprietary BACnet controls with Tridium JACE.	Closed.	Closed.		
439.	HVAC	Narrative / M101A	Narrative outlines Boiler Plant in the Pump House. Drawings show Boilers in Boiler Room 101B.	The narrative will be updated to reflect floor plans.	Not Closed.	Closed	The narrative has been updated to reflect the plans.	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
440.	HVAC	GENERAL	Are fire smoke dampers required in the duct leaving the shafts?	Fire smoke dampers are required only where shafts that serve more than 2 stories are penetrated by ductwork. The only location so far that this applies to is the gang bathroom exhaust ducts.	Closed.			
441.	HVAC	M104	Is smoke or fire protection required in the Mechanical Penthouse?	Smoke protection is not required within the pump house. We will review for the fire protection requirements.	What are your findings on FP?	Sprinkler head will be shown in the pump penthouse	Not shown on FP104C	
442.	HVAC	M104	Provide makeup water piping to the Penthouse	Make up water to the penthouse will be provided under the plumbing scope of work. Refer to M306.	Did not locate on plumbing drawings.	We will coordinate with plumbing engineer to ensure that this is included.	Not shown on P103D and cold and hot water riser diagrams.	
443.	HVAC	M104	Review ventilation requirements for Pump House	We will further review with manufacturer.	Open	We will review and revise the ventilation requirements and include the necessary provisions on the 90% submission.	Status confirmation?	
444.	HVAC	M104	How is Pump House installed on Roof? Is it on damage like the chillers?	Pump house shall be mounted on roof curb. Drawings updated.	Please show a detail.	A detail of the pump house curb will be included on the 90% submission.	Open	
445.	HVAC	M104	Review internal and external powered convenience outlets for the Pump House.	We will review with electrical for convenience outlets and add for future drawing submission.	Open	Convenience outlets will be coordinated and included on the 90% submission.	Open	
446.	HVAC	Fire Alarm Fire Protection	Include a fire alarm input/output matrix for the Smoke Control System.	This will be indicated within the controls series drawings in future submissions.	Closed.			
447.	HVAC	GENERAL	What discipline or drawing/specification identifies all the requirements for the fire alarm smoke control panel?	Will review and advise.	Is there a fire protection narrative?	Division 260000 will be responsible for this scope of work.	Is there a fire protection narrative?	
448.	HVAC	GENERAL	What discipline is covering the scope of the special inspector testing	We will review the special inspector testing requirements	What are your findings?	The independent Third-party review shall be provided by	Closed.	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
			consultant? Will this be in Division 1? Please refer to Section 909 Smoke Control.	to determine the correct discipline.		the owner. IBC 909.2		
449.	HVAC	E400			Show makeup air on the fire alarm riser.	The make up air interface with fire alarm is shown on detail 5/E307	Not complete. Detail 5 on sheet is kitchen emergency power off wiring diagram.	
450.	HVAC	M404			Show makeup air on controls for smoke evacuation.	This will be included for 90% submission	Confirmed on M408	
451.	HVAC	GENERAL			Are the two VFDs for the smoke fans being installed in 2-hr rooms? Which rooms?	We will review and indicate on future drawing submissions.	Not shown on E300	
452.	HVAC	GENERAL			Recommend UPS Power for all makeup air provisions, Reference 909.11.1	ATC contractor to wire components subject to 909.11.2 to a UPS backed up panel on the legally required distribution system.	Closed.	
453.	HVAC	GENERAL			Add to ATC notes on control drawings that the system must comply with UL864.	This will be included on the 90% submission.	Not seen in 230000	
454.	HVAC	GENERAL			Specify that all ducts part of the smoke system are leak tested to 1.5 times the max design pressure	This will be included in the 90% submission.	Not seen in 230000	
455.	HVAC	GENERAL			SEF-1, SEF-2, SEF-3 and SEF-4: Confirm 1.5 times number of belts shall be specified. Confirm minimum service factor of 1.15.	This will be included in the specifications in the 90% submission.	Open.	
456.	HVAC	GENERAL			SEF: Provide fan installation details on HVAC Detail Sheets. None shown.	We will include this on the 90% submission.	Open.	
457.	HVAC	GENERAL			RTU=112 has an install issue with a 6" RO on P104C.	We will review and coordinate with plumbing for this conflict.	Open.	
458.	HVAC	GENERAL			Show EPO (Emergency Power Off) switch on	This will be shown on the electrical	Not complete on E300	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
459.	HVAC	M201A			M201A Boiler Room Plan. Do not recommend running hot water pipes over VFD devices. Please review.	drawings for the 90% submission. We will revise the pipe routing to avoid the VFD's.	Complete.	
460.	HVAC	Piping Plans			Indicate anchors and guides on the thermal expansion HW loops	We will provide expansion loops with anchors and guides as required on the 90% submission.	Open.	
461.	HVAC	RTU Unit Penthouses			Are there piping vestibules in the RTU penthouses?	Piping will be located up through service vestibule for connection to AHU HW/CHW coils separate piping vestibule not required.	Open. Not clear.	
462.	HVAC	HVAC Details			Recommend a RTU penthouse detail to indicate devices, sensor, clearances.	We will provide a detail on the 90% submission.	Open. Not clear.	
463.	HVAC	M202D			Pipe runouts to units are not labeled. Not clear where the HWS&R piping is routed on this plan leaving the Auditorium.	Pipe runouts have been revised. Additional noting has been added to clarify the routing.	Closed	
464.	HVAC	M403/M201A			Show the low flow bypass valve location on the piping plans. Size the valve and pipe.	Bypass valve location and size will be indicated on piping plans in 100% CD documents	Open.	
465.	HVAC	M201A			Piping not sized. Only in Boiler Room.	Pipe sizes have been added to the drawings.	Closed	
466.	HVAC	M201B			Have you considered exhausting the electric rooms rather than provide ductless splits? Review Room 1127.	We found that ductless split systems are more suitable for the project as space for duct chases is limited and significant ductwork runs would be required.	Understood. Closed.	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
467.	HVAC	M101C			Electric Room 1165: What is design approach?	Electric room 1165 at this time does not indicate a required cooling or heating load, and per code, does not require ventilation. We will review the equipment within the space in future submissions to determine is a ductless split system is required.	Understood. Closed	
468.	HVAC	Details			Need/recommend cooling and heating coil hookup details. Identify popping connections, gauges, and hydronic specialties to the one or two high coils for each RTU.	We will include these details on future drawing submissions.	Closed	
469.	HVAC	M104			Suggest a piping vestibule for RTU-7.	Full service vestibule will be provided.	Did not locate on plans, schedule or specifications.	
470.	HVAC	M104			Suggest a piping vestibule for MAU-1.	Will be specified on 90% CD documents.	Did not locate on plans, schedule or specifications.	
471.	HVAC	M102C			Electric Room 2167: What is design approach?	Electric room 2167 at this time does not indicate a required cooling or heating load, and per code, does not require ventilation. We will review the equipment within the space in future submissions to determine is a ductless split system is required.	Understood. Closed	
472.	HVAC						SMMA did not locate a division 23 specification as it relates to the pump house.	
473.	HVAC						Review if a motorized damper is required to be	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents		
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response	
474.	HVAC							installed at the inlet of each SEF fan. It may need to be installed in the ductwork on the roof, or bought with the fan?	
475.	HVAC							Detail and call out the size of the sheet metal plenum (if required) behind each make-up air louver.	
476.	HVAC ELECTRICAL	M301 E303						Draw the 8" HWS pipe to scale in the mechanical room.	
477.	HVAC	GENERAL						There is not scheduled equipment on generator power.	
								There is no HVAC Legend with the current drawing set.	
478.	HVAC	M407 P004						Coordinate with kitchen master gas valve control diagram for BMS status and control of a CO event (alarm, exhaust fan and MAU SOO)	
479.	HVAC	M407 P003						Recommend ATC status (ALM) on the elevator sump pump system.	
480.	HVAC	M407 P001						Recommend ATC temperature on the hot water storage tank.	
481.	HVAC	M407 M408						Coordinate the two plans and show the makeup air motorized damper locations on the floor plans.	
482.	HVAC	M407						Fix notes as they correspond to the unit numbers. For example, leak	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents		
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response	
483.	HVAC	GENERAL						detection and note #3.	
484.	HVAC	RTU-1/2 RTU-3/4						There are no fire/smoke dampers shown on the supply air risers. Based on the plans is there a concern in regards to the unit clearances with all the SEF weather hoods and fan roof curbs?	
485.	HVAC	M104						Not clear to SMMA the outside air (intake) and exhaust air section of all the units.	
486.	HVAC	M104 M305 RTU UNITS						With a 36" roof curb; How do you get into these units? Has a stair/platform been designed with structural?	
487.	HVAC							Review if there is enough makeup air in the adjacent corridor to the trash room when EF-3 is running.	
488.	HVAC	M408 A104 A543						Exhaust air coordination at top of wall is unclear for the SEF fan ducts penetrating the building structure.	
489.	HVAC	M104 A104						SEF-2 and DCU-7 appear to be in conflict roof access door.	
490.	HVAC	M104 A104						HVAC roof equipment plan and arch roof plan are not fully coordinated. Condensing units and kitchen freezer	

**Design Review Comments**

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
491.	HVAC	M104					units need to be shown.	
492.	HVAC STRUCTURAL						KEF-1 fan and pump house maintenance doors should be coordinated. Appears to be a conflict.	
493.	HVAC						How is the pump house being installed on the roof? There is no dunnage detail for the pump house.	
494.	HVAC						Chiller curb/dunnage. How high off the roof is the pump house? You will need steps to get in and out.	
495.	HVAC	M104					Add blind flanges and isolation valves to come with each pump house's pipe outlets. Quantity of four (4).	
496.	HVAC	E204 E301					Suggest ventilation or a Dx Cooling Unit for the pump house.	
497.	HVAC	M401					Who is installing the two (2) electrical panels. Not shown on electrical plans. An additional MERV 14 filters may need to be installed. Show it/them and own additional DP switches.	
498.	HVAC	M401					Who controls the speed of the energy wheel?	
499.	HVAC	M401					Show/clarify ATC devices and sensor and unit provided devices and sensors.	



Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents		
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response	
500.	HVAC	M401						Add high limit switches add if there is an event, disable unit, open the HW valve 100% and alarm the BMS manual reset.	
501.	HVAC	M401						Coordinate with Owner recommendation of a manual reset freeze protection device.	
502.	HVAC	M401 M301						Schedule a low limit minimum OA CFM for the demand control units with CO2.	
503.	Electrical	C-2.1, E-PH-1	Locations of the site lights don't match electrical site plan. Coordinate	Civil notes state to see MEP plans for locations.	Dwg. E-PH-1 is not included in the package. Review can't be done.	The work on E-PH-1 is currently under construction and will not be part of the bid documents.		Current notes for site light locations: -Dwg L1.2 "Parking lot lights, see Electrical drawings" -Dwg C-2.1 Note 2 "Refer to MEP plans for locations" - Dwg E-PH-1 Note 2 "Refer to Landscape drawings for location of site fixtures" Please assign a discipline who will be in charge of locations. Recommendation to add a note on Dwg E-PH-1 stating "Scope of work shown on this drawing is NIC. Drawing is provided for reference and coordination purposes."	
504.	Electrical	C-2.3, E003-1	Electrical manhole is not shown on the civil plan. Location of the power,	Locations of power, communication and FA services are	No coordination has been done. Also, show location of the	Has been added.		Closed	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
505.	Electrical	C-2.1, E003-1	communication and FA services are not coordinated.  Location of the electric car charging stations is not shown on the civil plan.	shown and coordinated.  This item is still being discussed with owner.	generator and an emergency power duct bank on the civil plan.  Open	There are no electric car charging stations on project, will be removed from the project.	Drawings C-4.1 and E003-1 show (3) symbols noted "EV charging stations". Please clarify scope of work (Power? Communications? Provisions for "future"? Or will be deleted from drawings entirely?)	
506.	Electrical	C-2.1, E003-1	Locations of the site lights, security camera poles are not shown on the civil plan.	Civil notes state to see MEP plans for locations.	Electrical plans are diagrammatic. Note 10 doesn't allow to coordinate location of the all utilities	Detail references and electrical items have been added to drawings	Coordinate security pole locations, please see comment for item 1 above.	
507.	Electrical	C-2.1, E003-1	Generator set location is not shown on the civil plan. Coordinate. Show natural gas line to the generator.	Generator continues to be coordinated.	No coordination has been done yet.	Has been coordinated	Closed	
508.	Electrical	C-4.2, E003-2	Show location of the site lights, refer to electrical plan.	Civil notes state to see MEP plans for locations.	Electrical plans are diagrammatic. Note 10 doesn't allow to coordinate location of the all utilities	Detail references and electrical items have been added to drawings	Current notes for site light locations: -Dwg L1.3 "Bollard light, see Electrical drawings". -Dwg C-4.0 Note 2 "Refer to MEP plans for locations" - Dwg E-003-2 Note 2 "Refer to Landscape drawings for location of site fixtures". Please assign a discipline who will be in-charge of locations.	
509.	Electrical	E003-1, P0.02/4, C2.1	Wiring of the (2) acid neutralization tanks is not shown on the electrical plan	This will be picked up on next submission.	Not included. Plumbing details have been moved to P005	Updated plumbing drawings received the wiring for the tanks will be coordinated and shown for the 90% CDs	Closed	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
510.	Electrical	C-7.4	Add a base detail for a site lighting pole. Coordinate with detail on dwg. E004	Detail will be shown on electrical sheet.	Not coordinated. Details on dwg.E004 indicate the bases be provided by site contractor.	This is correct and work is ongoing on site.	Detail E004/3 states that concrete base is by Site Contractor. Civil drawings don't show the acceptance of this scope. Please clarify.	
511.	Electrical	A001	No info shown on the dwg.	Will continue to develop	Symbols drawing is not in the package	Unclear what this is referring to. There should only be architectural items on A001, not electrical	Closed	
512.	Electrical	A101, A102	Location of a toilet room (at principle office) above main electrical room is not recommended	Appropriate protection is required by architect where plumbing is installed over electrical panels.	Plumbing shaft with hot and cold water and sewer piping above main electrical room is not recommended.	Will provide proper protection	Please note that the "proper protection" method (such as dripping pan) will require a formal approval by Electrical Inspector.	
513.	Electrical	E300, E301	Confirm the transformers (located remote from the primary side panels) will be with the primary side disconnect switches or lockable devices will be used per MEC 450.14	All remote transformers will conform to NEC 450.14	Closed		Closed	
514.	Electrical	E301, E302	Panel PP2B is power fed from panel MP1B. Panel MP1B shall be 400A bus/250A main breaker.	This will be revised	PP2B is fed from new panel 2DP1B. Revise panel schedule 2DP1A and add schedule for 2DP1B per one-line diagram E-301	This will be completed for the 90%CD set	Closed	
515.	Electrical	E301, E302	Panel MP1B shall be 400A bus/250A main breaker. Is it single or double tub panel?	This will be revised.	Revised diagram for panel MP1B is acceptable.	Ok	Closed	
516.	Electrical	260000.2.23A, E301	Per spec- 200kW diesel generator set, but per dwg.- 250kW natural gas generator set.	A calculation was Closed since the previous set and the generator will be 300KW and edited so that drawings match the specifications.	Closed		New comments: Correct below to match the design intent: - 260010.1.3.B.4 - ".diesel..." - 260010.2.23 - "300KW ..gas" - Dwg E003-1 "250KW generator with 10ft stack".	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
517.	Electrical	E301	is a generator set with a natural gas engine approved by local AHJ to support life safety loads?	A request has been issued to the AHJ. The facility directors have stated that existing emergency stand-by generators in the city are currently natural gas so the design team has followed that precedence.	Closed		- Dwg E301-350KW. Reconfirm stack height for upsized generator. Closed	
518.	Electrical	260000.2.23K	Per spec- "load bank for indoor mounting adjacent to a generator in series with engine radiator"? Clarify and revise type of housing if required.	There will be no load bank if the generator remains natural gas fired.	Closed		Closed	
519.	Electrical	260000.2.23M, E201A, E301	Show a manual transfer switch location and wiring for connection of roll-up generator set	Will show on next submission.	Wiring for life safety loads transfer to temporary generator is not shown		Closed	Manual transfer switch is shown wiring not complete. This will be complete for the 90%CDs
520.	Electrical	E302	Panel MP3C is fed from 75kVA transformer, it shall be 400A bus/250A main breaker	Will correct.	Closed		Closed	
521.	Electrical	E301, E302	Is panel 2DP1C power fed from T-6 or T-7 size transformer? Coordinate a schedule and one-line diagram.	Will revise in next submission.	Closed		Closed	
522.	Electrical	E301, TL111	TL dwg. requires 200A power feed to a dimmer rack and also an emergency power feed. Dwg. E301 shall be revised accordingly.	Will add emergency power feed as required.	Closed		Closed	
523.	Electrical	260000.2.14D	Main switchboard short circuit rating of 100kA is too high (add'l cost). Rating should not exceed 65kA.	Will reduce to 65KAIC	Closed		Closed	
524.	Electrical	260000.2.14H and 2.17E, E301	Coordinate location of the utility metering CTs and PTs between the spec pars.	Will coordinate with utility.	Spec and drawing are not coordinated.		Closed	Specification has been edited to cold sequence metering.

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
			revise a diagram accordingly.				CT's and PTS installed in the CT section of the switchboard.	
525.	Electrical	All plans	Add a key plan on each dwg.	Will do	Closed	Closed		Closed
526.	Electrical	A102, E300	Rm. 2254 is not emergency electrical closet. Change a room name.	Will coordinate with architect.	Not coordinated yet.	Closed	Will be revised.	Closed
527.	Electrical	FP1.01	FP service piping is shown in the main electrical room, it should be relocated.	Will be coordinated.	Closed	Closed		Closed
528.	Electrical	E401A	Show FP tamper and water flow switches in Rm.1023	Will be coordinated as drawings develop.	Open Room has been re-numbered to 1022.	Closed	Updated FP plans have been issued this will be coordinated for the 90%CD's	Closed
529.	Electrical	E401B, FP1.02	Show FP tamper and water flow switches, refer to FP plan	Will be coordinated as drawings develop.	Open	Closed		Closed
530.	Electrical	E401C, FP1.03	Show FP tamper and water flow switches, refer to FP plan	Will be coordinated as drawings develop.	Open The FP plan has been re-numbered to FP1.01C	Closed	Updated FP plans have been issued this will be coordinated for the 90%CD's	Closed
531.	Electrical	FP plans	Add building key plan on each dwg.	Will add.	Closed	Closed		Closed
532.	Electrical	E401D	Quantity of the FA speaker/strobes in Gym is not sufficient for 15dB above ambient noise. Consider high output and overhead mounted devices.	Will be corrected.	Open	Open	In process of being addressed.	Open
533.	Electrical	260000 par.2.18Z	FA 1 watt output speakers are not sufficient for public areas such as Gym, atrium, etc.	Will be corrected.	Open	Closed	Speaker strobes are adjustable to 2 W high output will be provided in the gym	Closed
534.	Electrical	E402B E402C E403B E403C	Show FP tamper and water flow switches, refer to FP plans	Will be coordinated as drawings develop.	Open	Open	In process of being completed.	Open
535.	Electrical	E202.A, FP2.01	Show location of the FP electric bell on electrical plan	Will be coordinated as drawings develop.	Open. Coordinate location with FP102A	Open	In process of being completed.	Open
536.	Electrical	P2.01	Multiple piping runs in the main electrical room. Coordinate with electrical/relocate	Will be coordinated as drawings develop.	Closed.	Closed		Closed

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents		
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response	
537.	Electrical	E201A, M101A, A101A	Pumps P-1 and P-2 are located in custodian toilet rm. 1016. Coordinate.	Will be coordinated as drawings develop.	Closed			Closed	
538.	Electrical	E303, M301	Circuit breakers for the all RTUs 1 to 8 are oversized. Refer to mechanical schedule.	Will be coordinated as drawings develop.	Closed			Closed	
539.	Electrical	E302, E303	Equipment schedule indicates all RTUs are wired from main switchboard MSB. MSB schedule does not reflect the same.	The schedule will be corrected as the drawings develop.	Open. RTUs are wired from 4DPXX panels.	In process of being worked on schedules will be updated once wiring is complete.		Closed	
540.	Electrical	E303, M301	Circuit breakers for the both chillers are oversized, 600Amp vs. 400Amp in M301 schedule.	Will be coordinated as drawings develop.	Closed			Closed	
541.	Electrical	E302, E303	Equipment schedule indicates two chillers are wired from main switchboard MSB. MSB schedule does not reflect the same.	Will be coordinated as drawings develop.	Open. Add 800Amp chiller breaker in MSB1A schedule.	Will correct.		Closed	
542.	Electrical	E303, M301	Pumps P1 to P4 are 25HP on electrical plans, but they are not sized yet in schedule on M301. Coordinate.	Will be coordinated as drawings develop.	No pumps size selection has been made by mechanical. Wiring to be completed.	Ongoing.		M301 schedule indicates P-1 & P-2 as 25HP. Closed.	
543.	Electrical	E204ABCD	Change roof plan number to E204, to be consistent with all other disciplines	Ok will revise.	Closed			Closed	
544.	Electrical	E204, M104, A104	Architectural roof plan does not match the engineering plans. Pump house is missing, the chillers location to be changed.	Will update model and coordinate mechanical equipment locations.	Pump house plan is missing on E204.	Ongoing.		Open	
545.	Electrical	E303, M301	There are (11) ductless cooling units in electrical schedule, and (7)- in mechanical schedule. No electrical data is shown in the mechanical schedule	Will be coordinated as drawings develop.	Quantity has been coordinated. Electrical data is still not shown in the mechanical schedule. Electrical schedule update is pending.	Ongoing.		Electrical data (MCA, MOCF) is still not shown in the mechanical schedule. Electrical schedule update is pending.	
546.	Electrical	E303, M301	Exhaust and supply fans data is missing in the mechanical schedule, but electrical schedule on E303 includes the fans HP, voltage and wiring. Quantity	Will be coordinated as drawings develop.	Electrical data is still not shown in the mechanical schedule. Electrical schedule update is pending.	Ongoing.		Open	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
			is also different. Coordinate.					
547.	Electrical	260000.2.24, E204, E205	Drawings and spec show a different type of a lightning protection system. Coordinate	A lightning preventor system will be provided. Drawings will be edited to match	Details on E205 needs to be revised.	Will correct the details to preventor style.	Open	
548.	Electrical	E302, 260000.2.14 and 2.15	Note 1 for MSB and 4DP1B schedules allows the breakers be series rated. Spec does not state anything. Confirm design intent and coordinate.	Will be coordinated as drawings develop.	MSB note 1 and spec should be coordinated	Will coordinate.	Open	
549.	Electrical	Electrical power plans, spec 12 24 14	Spec for motorized shades is included. No wiring is shown on electrical plans. Coordinate.	Will be coordinated as drawings develop.	Open	Ongoing.	Open	
550.	Electrical	E303, P0.01	Plumbing equipment schedule is missing on P0.01, although it is shown on E303 with HP, voltage and wiring data. Coordinate.	Will be coordinated as drawings develop.	Open	Ongoing.	Dwg P001 has electrical data. Closed	
551.	Electrical	E102B, A182B	Typical for all classrooms. Ceiling soffits on architectural and electrical plans are not matching. Verify length and installation of the LC3 fixtures	Will be coordinated as drawings develop.	Closed.		Closed	
552.	Electrical	E102B (typical for lighting plans)	Typical for all classrooms. Are (2) LC3 fixtures sufficient for classroom seating area illumination? Verify lighting calculations.	Lighting calcs will be Closed to ensure IESS illumination levels are met.	Open. Include opposite walls vertical illumination levels.	Ongoing.	Open	
553.	Electrical	E102D, GA005	Is auditorium lighting layout coordinated with the performance lighting pipes?	Needs further coordination.	Coordinate location of stage PC1 lights with stage pipe 4	Ongoing.	Open	
554.	Electrical	A101D, GA001	Theatrical electrical room 1347 size and layout are not matching on these plans	Will continue to coordinate.	Open. Room has been re-numbered 1348 on A101D	Will complete coordination for the 90%CD's	Open	
555.	Electrical	E300/6, GA111/1	Conflict in Room 1347 size and layout of the electrical and theatrical lighting control equipment	Will continue to coordinate.	Open. Room has been re-numbered 1348.	Will complete coordination for the 90%CD's	Open	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
556.	Electrical	260000.1.30, 230000.1.32	Electrical spec requires VFDs for fans/pumps be furnished and installed by Div.23. Mechanical spec requires the same be done by Div.26. VFD spec is not included in either Div.23 or Div.26 specs.	Will coordinate responsibilities matrix.	Open.	Responsibility coordination matrix will be completed for the 90%CD's	Suggesting VFD's to be provided by Div.23, and installed/wired by Div.26. Open.	
557.	Electrical	260000.1.31	Par. refers to spec 012300 for Gym Walking Track alternate 3. Section 012300 is missing.	This alternate is incorrect. Will coordinate alternates with architect.	Coordination is required.	Will revise	Closed	
558.	Electrical	E-301			Is transformer feeding panel 2DP1B K-rated?	yes	Closed	
559.	Electrical	E-302			Panels 2DP1A, 2DP1B and 2DP1C shall be with 200% neutral	yes	Closed	
560.	Electrical	E-302			Add panel 2DP1B (via a transformer) in the main switchboard schedule	Will add	Open	
561.	Electrical	260000.2.14D E302			Change MSB short circuit rating in spec to 65kA to match the schedule	done	Closed	
562.	Electrical	260000.2.14			Add an energy reduction maintenance switch (ARMS) for MSB main circuit breaker	done	Closed	
563.	Electrical	260000.2.14			It is recommended the MSB feeder breakers 400Amp and larger be with electronic trip for coordination purpose	Done 250Amps or larger will be electronic trip.	Closed	
564.	Electrical	M301; E303			RTU1/2 and RTU3/4 schedule on M301 shall state that a separate power ckt is required for each of 4 units	Will be added.	Open	
565.	Electrical	E204; M104			Split system condensing units #s 2,3,4,6 and 7 are not shown on the electrical plan. Also, M104 shows a unit#8 that is not scheduled. Coordinate.	In process of being coordinated.	Open	



Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
566.	Electrical	E201D			Should the aisle lights be provided in the auditorium seating area?	No, overhead aisle lighting will be provided	Closed	
567.	Electrical	E201D; GA111/1			Coordinate quantity of the devices and circuits in auditorium/stage area	Will coordinate.	Open	
568.	Electrical	E102D			Identify emergency lights in Gym and Auditorium	Will do	Open	
569.	Electrical	E301; E300/1; E005/3			Why MI cable is shown on E301 from ATS-LS to a generator? The feeder is installed underground in a duct bank.	MI is not required will edit	Closed	
570.	Electrical	E301			Utility metering CTs are in the switchboard and a meter is on the transformer enclosure. Distance between CTs and meter is a limiting factor. Coordinate w/utility metering department	Will coordinate with the utility and architect to show meter on the outside of the electric room.	Clarify status of review with Utility provider	
571.	Electrical	E305; E200 power plans			Identify plug load controlled receptacles on the plans. There are no controlled receptacles shown in the office areas.	This will be added to meet energy code.	Add "controlled" receptacle symbol to Legend. Per detail E305/1 only the top outlet in duplex receptacle is expected to be "controlled" – please clarify the intent. The current layout in typical admin office shows (2) duplex receptacles to be "controlled" (half in each duplex)– such approach may not meet the 50% minimum requirement. Please review/modify design.	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
572.	Electrical	E801; E302			Kitchen transformer – 45kVA, panel KPP1A – 400Amp. Revise. Provide panel schedule and load data. Kitchen panel should not be w/200% neutral.	Will be corrected.	Kitchen panel is wired to panel 2DP1A. There is no transformer. Closed.	
573.	Electrical	E306			Note 19: Provide GF breakers in panel KPP1A or show GFI type receptacles per the kitchen equipment schedule	Note 19 will be edited to say kitchen and not culinary arts.	Open	
574.	Electrical	E003.1					Site lighting: complete wiring/circuiting.	
575.	Electrical	E003.1					"WP" receptacles noted "P" – please clarify the "P" intent here. Per Legend, "P" denotes "pedestal-mounted on casework". Complete wiring/circuiting.	
576.	Electrical	E003.1; E004					Duct bank details have names "A-A", "B-B", etc. – not tagged on site plans yet.	
577.	Electrical	E001					Lighting control symbols "L", "Lk", "Lv" make a reference to the ALCS one-line diagram – suggest to add Dwg number where it can be found in set, E306.	
578.	Electrical	E001; E306					Lighting control stations in various combinations such as "on/off", "dimming", "multi-station dimming", etc. are not on Legend – suggesting to either add them to	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents		
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response	
579.	Electrical	E101A						Legend or make a reference to drawing E306 with explanation/model for each type used in this project. Symbols that are not used in this project can be removed from One-Line.	
580.	Electrical	E101A						Lighting control concept in the Head End and Main Electric differ from other spaces – a line voltage toggle switch vs. networked control station L – please clarify/correct.	
581.	Electrical	E101A						Building-mounted lights: complete wiring/circuiting and controls concept.	
582.	Electrical	E101A						Exit sign in Receiving – is it ceiling-mounted or wall-mounted above the door installation method?	
583.	Electrical	E101B; E101C; E101D; E102A; E102B; E102C; E102D; E103A; E103B;						Receiving/Workshop/Storage/Corridor area – if there are no occupancy sensors, what is the automatic control concept?	Wiring/circuiting is in progress

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
584.	Electrical	E103C; E103D  Lighting System: General Comment					Are there any interior time-controlled areas or all spaces are controlled by occupancy sensors only? Will there be any "NL" (Uncontrolled "Night Lights")?	
585.	Electrical	Lighting System: General Comment					Lighting in typical corridors- please clarify controlling method - time-controlled? Occupancy sensors? Uncontrolled? If "time-controlled" - is there a manual override system for "emergency" lights during "unoccupied" time? Suggesting to provide manual override stations at the main/secondary entrance vestibules, to be used by police, FD or authorized people during afterhours/night.	
586.	Electrical	General: Lighting in Typical Classrooms					Quantity of occupancy sensors - will the current amount provide a full "hand motion" coverage?	
587.	Electrical	E101B					Toilet 1252: is there sufficient illumination level?	
588.	Electrical	E101C					Lockers 1231,1234 - where switches "Lab" are located?	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
589.	Electrical	E101C					Learning Common and adjacent corridors need "emergency" lighting.	
590.	Electrical	E101D					Toilet/shower 1323 needs lighting control station	
591.	Electrical	E101D					Offices 1213,1214 need lighting control stations	
592.	Electrical	General: Occupancy sensors in student toilet rooms					Clarify type (technology) of occupancy sensors - ultrasonic?	
593.	Electrical	E101D					Dressing rooms 1343,1347 - control switches shall be moved from behind the door.	
594.	Electrical	E101D					Vestibules 1342,1346 need some type of controls.	
595.	Electrical	E102A					Office Principal 2014 - clarify controls concept - switching? No manual dimming? Also, add occupancy and daylight sensors.	
596.	Electrical	E102A					Conference room 2016 add control station (switching or dimming).	
597.	Electrical	E102D					Gym 1320 needs "emergency" lighting and controls.	
598.	Electrical	E102D					Auditorium 1340 needs "emergency" lighting at stage and adjacent area. Also, needs controls.	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
599.	Electrical	E103B; E103C					Common area lights "Sp1" - circuiting and controls are in progress.	
600.	Electrical	E103C					Breakout 3058 needs controls.	
601.	Electrical	E201A					Makerspace/shop 1134 - complete cord reals and welder wiring. Any power required above two tables in the middle?	
602.	Electrical	E201A E201B; E201C; E201D; E202A; E202B; E202C; E202D; E203A; E203B; E203C; E203D					Wiring is mostly completed, except for a few rooms and spaces. Complete wiring/circuiting.	
603.	Electrical	E202D					Stage equipment and "performance lighting" connector strips (assumed, no tag is present) - complete wiring.	
604.	Electrical	E302					A few 120/208v panels (PPTC, TEP1D, EP3C, etc.) are provided with shunt trip on MCB's - what is the purpose? What is the "tripping" concept (not shown on Power One-Line)?	
605.	Electrical	E302					120/208v and 277/480v panel schedules - complete selection/quantity of circuit breakers.	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
606.	Electrical	E302						Distribution panels 2DP1A, 4DP1B, 2DP1B, 4DP1C show 2-3 "spaces" – is this sufficient?
607.	Electrical	General: FA						Symbol speaker/strobe + "A" circle – add to Legend or provide clarifications.
608.								
609.								
610.	Security	E500	TS not called out under security system.	This is an electrical component and shown on the electrical plans we will add this symbol to the security symbol list for clarity.	Closed			
611.	Security	General	Missing key plan for all sheets.	Will add	Closed			
612.	Security	501A	Floating door contacts.	Will fix	Closed			
613.	Security	E501A	IC not called out on E500. Is AI meant to be IC?	corrected	Closed			
614.	Security	E501C	Door contact in wall in chair storage room 1164.	Will fix	Closed			
615.	Security	E501D	Missing door hardware and card reader for AV room 1347.	Will add	Closed			
616.	Security	E502A	Motion detector should be moved out of closet 2017 into conference-Ig 2016.	Will fix	Closed			
617.	Security	E502B	Missing motion detector, door hardware and card reader at stair 2005.	Will add	Closed			
618.	Security	E502C	Missing card reader and door hardware at stair 2065.	Will add	Closed			
619.	Security	E503B	Missing motion detector at stair-2 3005.	Will add	Closed			
620.	Security	General	Door contacts at roof access hatches?	Will be provided	Closed			
621.	Security	E501A	Missing card reader and door hardware for head end room 1026.	Will add	Closed			

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
622.	Technology	General	Wall phone outlets in classrooms are not on the wall.	Has been corrected	Closed			
623.	Technology	General	Speakers in classrooms are not in center of room.	Speaker is located at 8'-0" ceiling before it angles up to exposed deck	Open	Will coordinate further.		
624.	Technology	General	Missing key plan for all sheets.	Will add	Closed			
625.	Technology	General	Head End Room is the MDF?	Correct.	Open	yes		
626.	Technology	T101A	Missing annotation for tel/data outlet in main electric room 1024.	Will fix	Closed			
627.	Technology	T101B	Consider adding second flush mounted ceiling speaker in media room 1240.	ok	Closed			
628.	Technology	T102B	Missing speaker in stair 2005.	Will add	Closed			
629.	Technology	T102B	Missing speakers in SPED-Classrooms 2260 and 2264.	Will add	Closed			
630.	Technology	T102C	Missing "W" annotation for outlet next to clock in SPED-Reading room 2168B.	Will fix	Closed			
631.	Technology	T102A	Missing hallway speakers.	Will add	Closed			
632.	Technology	T102B	Missing hallway speakers.	Will add	Closed			
633.	Technology	T102C	Missing hallway speakers.	Will add	Closed			
634.	Technology	T102C	Missing speaker in stair 2065.	Will add	Open	Will add	Incomplete	
635.	Technology	T103B	Missing speaker in stair-2 3005.	Will add	Open	Will add	Incomplete	
636.	Technology	T103C	Missing speaker in stair-1 3065.	Will add	Open	Will add	Complete	
637.	AV Systems	General	Missing key plan for all sheets.	On bottom of each plan sheet	Closed			
638.	AV Systems	AV000	"BP" not called out under AV Junction Box Symbols.	To be defined on following sets	Closed			
639.	AV Systems	AV101A	AV System in media room 1240?	Added on east wall	Closed			
640.	AV Systems	AV102B	AV system in classroom next to classroom 2224?	From Band Room 1220. On wrong layer	Closed			



Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
641.	Security	E501A			"IMS" floating in middle of custodian office / break room 1207.	This is a desk mounted device	Response Accepted.	
642.	Security	E501B			Far right bottom corner of building, missing camera. Tags are there but missing device.	Will fix.	Complete.	
643.	Security	E501C			DC in wall in Art room 1234.	Will fix.	Complete.	
644.	Security	E501C			Camera in locker room 1321?	Will remove	Complete.	
645.	Security	E502B			Door leading to STAIR-1 2005 not shown.	Will fix.	Complete.	
646.	Security	E503B			Door leading to STAIR-1 3005 not shown.	Will fix	Complete.	
647.	Security	E503C			Move CR and Camera out of storage room 3066.	Will correct.	Complete.	
648.	Security	E503C			Add "E" tag om CR for Elevator 3162.	Will add E tag and add E designation on symbol list.	Complete.	
649.	Technology	General			Add "WP" tags for all outside speakers	Will add	Complete.	
650.	Technology	T102A			"F" tag for tel/data outlet in copy room 2010A not called out on T001	Will add to T001	Complete.	
651.	Technology	T102B			Review IDF 2255 part plan. Room seems to have shrunk.	Will review with architect.	Complete.	
652.	Technology	T102C			Review IDF 2155 part plan. Room seems to have shrunk.	Will review with architect.	Complete.	
653.	Technology	General			Consider changing "Head End" to "MDF" on floor plans. Details on T201, T202 & T300 all reference a MDF not a Head End Room.	Will make consistent.	Incomplete	
654.	Technology	T101A			Consider adding a wireless access node in Makerspace / shop 1134.	Will add.	Complete.	
655.	AV Systems	General			Digital Signage?	Provided as part of FF&E technology buy out will coordinate	No devises located, confirm they will be in the 100% set	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents		
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response	
656.	Security	General				locations with architect.		Card reader "LD" tag not defined	
657.	Security	General						Consider tagging doors (With hardware) on floorplans with door numbers and listing each door number under their corresponding typical door elevation on E500. Cross reference with door schedule.	
658.	Security	E501B						No "LB" or "DB" tag on button devices in "Guidance office 1126" or "Guidance office 1125".	
659.	Security	E501A						No "LB" or "DB" tag on button device in "custodian office / break 1027".	
660.	Security	E502A						No "LB" or "DB" tag on button devices in "copy 2010A" or "Office - Principal 2014".	
661.	Security	General						Consider adding cameras in all IDF and MDF rooms.	
662.	Technology	T101C						Add speaker in "Art Workroom 1233".	
663.	Technology	General						Is plywood backboard needed for IDF and MDF rooms?	
664.	Technology	General						Create BDA riser diagram.	
665.	Technology	T102C						Add wireless access node in	

Item	Discipline	DWG/Spec	Design Development		60% Construction Documents		90% Construction Documents	
			OPM Comment	Designer Response	OPM Comment	Designer Response	OPM Comment	Designer Response
666.	Technology	T300						
667.	Technology	T102D						
668.	Technology	T102D						
669.	Technology	T102D						



# Fuller Middle School

## Constructability and Drawing Review Log, 90% CDs

As of: 10/7/2019

Revision:



ITEM #	DATE OPENED	DWG NO/DTL OR SPEC SECTION	DESCRIPTION	B/C	DATE RESOLVED	COMMENTS
<b>THEATER DRAWING REVIEW</b>						
<b>ARCHITECTURAL DRAWING REVIEW</b>						
1	snapshot	9/26/19	A001			
2	snapshot	9/26/19	A316			Call out Ceiling Layout Plan on RCP's / Relocate to RCP Series
3	snapshot	9/26/19	A102C			Confirm Glass Types (Typical), Type "Q1" does not appear in Spec 084313
4	snapshot	9/26/19	2/A419			Show blowup detail of required furring. Wall Type D6 does not indicate furring
5	snapshot	9/26/19	A181D			Clarify ceiling types - appears multiple layers cross-hatching over one another
6	snapshot	9/26/19	A182			Confirm Light Fixture Types in IT/AV Rooms; LR2 indicated on Legend on Right of Sheet as Recessed, but areas are exposed to deck above
7	snapshot	9/26/19	A182B			Review Corridor LR2 layout; Not currently aligned with ceiling grid
8	snapshot	9/26/19	A183B			Detail 6 on Sheet A690 does not account for spray fireproofing on beams with respect to soffit framing
9	snapshot	9/26/19	A183C			Remove Note 7.18 for Intumescent paint at Commons/Breakout areas (Intumescent only where exposed through skylights per Early Release Steel Package)
10	snapshot	9/26/19	A211			Remove Note 7.18 for Intumescent paint at Commons/Breakout areas (Intumescent only where exposed through skylights per Early Release Steel Package)
11	snapshot	9/26/19	A300			Confirm Relieving Angles shown per Structural Set (depicted here as continuous vs. individuals shown on Early Release Steel package).
12	snapshot	9/26/19	A314			A300-Series Sections/Details incomplete; Need to review waterproofing/flashing details fully developed
13	snapshot	9/26/19	A403			Provide Key/Legend for Storefront Types tying back to Sheet A221
14	snapshot	9/26/19	6/A410			Typical P-4 Drinking Fountain not scheduled to include bottle filler; OK with City?
15	snapshot	9/26/19	3/A410			Provide blow-up dimensioned detail for typical device layout for clocks/switches/etc. next to door
16	snapshot	9/26/19	5/A411			Provide blowup dimensioned layout plan for devices/outlets at typical Teaching Wall
17	snapshot	9/26/19	1/A413			Provide blowup of typical Emergency Shower / Eye Wash Station. Allow to confirm ADA compliance
18	snapshot	9/26/19	A413			Confirm door(s) to Chorus Room 1224 don't need to be oversized to allow access for intended Plano
19	snapshot	9/26/19	A414			Details 2 & 11 - Soffit construction required at Chorus / Band Rooms (potential VM Items)?
20	snapshot	9/26/19	A426			Possible to use Acoustic Fabric Panel in lieu of Cementitious (Possible VM Item, just use different color)?
21	snapshot	9/26/19	A431			Provide typical ceiling grid detail at light fixtures; to identify what is required by ACT bidders to support lights (typ).
22	snapshot	9/26/19	A440			Eliminate angled/hourglass shape of breakout space as potential VM Item
23	snapshot	9/30/19	A460			Provide blowup detail for layout/blocking of various toilet accessories with respect to toilet
24	snapshot	9/30/19	A461			No ceilings here; confirm if a specialty height of plywood is required (i.e. 8' AFF).
25	snapshot	9/30/19	A462			Provide indication of whether wall is flat or sloped with concrete on 6/A602.
26	snapshot	9/30/19	A470			VE opportunity: VE down from perforated metal at egress stairs #1 and #2.
27	snapshot	9/30/19	A490			Will the Fuller Middle School lettering be visible behind the railings?#
28	snapshot	9/30/19	A502			Trade Bidder must carry temporary roof (boiler room is below)
29	snapshot	9/30/19	A520			Potential soffit / framing conflict.
30	snapshot	9/30/19	A521			Provide information on frequency of attachments. These hang from blocking above.
31	snapshot	9/30/19	A522			Incomplete details.
32	snapshot	9/30/19	A523			Provide details / sections.
33	snapshot	9/30/19	A530			AVB Support?
34	snapshot	9/30/19	snapshot			Provide direction as to whether this joint is to be caulked.
35	snapshot	9/30/19	A530			Provide layout plans for wall logs; degrees are not reliable for masons.
36	snapshot	9/30/19	A531			Provide detail as to how AVB gets supported. Is there a gap in insulation?
37	snapshot	9/30/19	A532			Confirm wood blocking, Z-furring, AVB scope.
38	snapshot	9/30/19	A541			Is blocking required or as drawn?
39	snapshot	9/30/19	A541			Is this acceptable per the skylight manufacturer?
40	snapshot	9/30/19	A541			Confirm 1/2" vs. 5/8" required (typ.)
41	snapshot	9/30/19	A541			Clarify scope required.
42	snapshot	9/30/19	A541			Adjust dimensions to allow soffit past soffit.
43	snapshot	9/30/19	A542			Confirm this firestopping design is okay.
44	snapshot	9/30/19	A543			Confirm that this duct will be accessible.
45	snapshot	9/30/19	A544			N/A inside HSS Post.
46	snapshot	9/30/19	A544			Confirm whether this is HVAC or Roofer scope. I.E. Final seal performed by whom?
47	snapshot	9/30/19	A570			Confirm this material. (Glass?)
48	snapshot	9/30/19	A602			Review this detail; this insulation condition does not work.
49	snapshot	9/30/19	A602			How will the fin tube be accessed for maintenance
50	snapshot	9/30/19	A640			Rough surface for hands
51	snapshot	9/30/19	A651			Confirm height of toe kick is adequate.
52	snapshot	9/30/19	A652			Confirm where this applies: Gate with magnetic hold open is not shown on fire alarm plans.
53	snapshot	9/30/19	A690			No SOPP shown. Is the soffit sized to accommodate?
54	snapshot	9/30/19	A690			Confirm light fixture throw is okay with soffit.
55	snapshot	9/30/19	A690			Revise to include SOPP.
56	snapshot	9/30/19	A700			How is this blocking supported? Potential elimination as VE opportunity.
57	snapshot	9/30/19	VT01			UIL designs are needed for fire-rated partitions in order to comply with building code fire-stopping requirements.
58	snapshot	9/30/19	FS100			GGD: Need HVAC design for ventilation of hoistway for current elevator code.
59	snapshot	9/30/19	FS101			Show location on HVAC and Roof Plans.
60	snapshot	9/30/19	FS101			Show this on HVAC & Roof Plans.
61	snapshot	9/30/19	FS101			Should be by roofer.
62	snapshot	10/1/19	1/A690			Custom angle not adjusted to standard 45 degree per 60% CD comments.

# Fuller Middle School

## Constructability and Drawing Review Log, 90% CDs

10/7/2019

As of:

Revision:



ITEM #	DATE OPENED	DWG NO/DTL OR SPEC SECTION	DESCRIPTION	B/C	DATE RESOLVED	COMMENTS
63	snapshot	10/2/19	Snapshot			Review 36" service clearance requirements for electrical.
1	snapshot	9/25/19	S503			Architect confirm dimension from top of structural steel to top of damage steel to account for roof insulation thickness / snow drifting.
<b>STRUCTURAL DRAWING REVIEW</b>						
<b>FIRE PROTECTION DRAWING REVIEW</b>						
1	snapshot	9/25/19	FP001			Note #6 - What flow data was used to complete current design?
2	snapshot	9/25/19	FP101A			Wet Sprinkler system OK in Main Electric / Emergency Elec / Head End Rooms?
3	snapshot	9/25/19	FP101B			Note for Window Sprinklers - Where does "typical" apply? All required locations must be shown, with associated piping
4	snapshot	9/25/19	FP101C			Sprinkler Heads under balconies / walkways / breakout spaces should identify required piping
5	snapshot	9/25/19	FP101D			Confirm no sprinkler coverage required under Stage / Extension
6	snapshot	9/25/19	FP101E			Confirm Sprinkler location vs. Fin tube under windows
7	snapshot	9/25/19	FP102A			Confirm auxiliary drain necessary? Are others required, as this is only location shown in set; if needed for this pipe run, is Exam Room acceptable location?
8	snapshot	9/25/19	FP102A - detail			FP Piping passes thru CMU bearing wall in two locations this area, Confirm acceptable with Structural Engineer, provide sleeving detail
9	snapshot	9/25/19	FP104C			Sprinkler Head shown in Elevator Roof Vestibule; Confirm Wet vs. Dry System; HVAC Plans do not currently show means to heat this space
10	snapshot	9/25/19	FP101C			Confirm no special FP requirements for Klin in Art Workroom 1233
<b>PLUMBING DRAWING REVIEW</b>						
1	snapshot	9/25/19	2/P005			Confirm HVAC Plans to be updated to show required BMS tie-ins
2	snapshot	9/25/19	P101A			Bollards Required at Gas Meter? None shown on Arch/Landscape Plans
3	snapshot	9/25/19	P101A			Rain Leader Cleanup OK in Dry Storage Room?
4	snapshot	9/25/19	P101D			Rain Leader thru CMU Bearing Wall acceptable to Structural? Provide sleeving/intel information if required
5	snapshot	9/25/19	P102A			Additional Steel support required at TD-1 S?
6	snapshot	9/25/19	P102D			Review Rain Leader Cleanup Access Acceptable
7	snapshot	9/25/19	P102D			Confirm Rain Leader across backstage area OK with theatre rigging / productions
8	snapshot	9/25/19	P103B			Review Rain Leader riser location for possible conflict with Architectural
9	snapshot	9/25/19	P103B			Confirm riser stack core spacing requirements with Structural
10	snapshot	9/25/19	P103C			Vent Sizing does not appear to fit inside stud cavity; Confirm partition types don't need to change
11	snapshot	9/25/19	P104			No overflow drains required on roof?
<b>HVAC DRAWING REVIEW</b>						
1	snapshot	9/25/19	M101B			Specify any different requirement for look of visible ducts where passing into Breakout Spaces (type of finish, insulation, etc.)
2	snapshot	9/25/19	M101B			Confirm Free Area SF total vs. per louver
3	snapshot	9/25/19	M101B			Specify "DG" for grilles on doors, if to be provided by HVAC vs. door supplier
4	snapshot	9/25/19	M101C			Confirm HVAC requirements for Klin to be installed in Art Workroom 1233
5	snapshot	9/25/19	M302			DD-7 Diffusers are radius-style in rounded corner of typical classroom; Notes in schedule / drawing sheet graphics do not indicate custom nature of grille
6	snapshot	9/25/19	M302			Does minimum CFM column need to be completed in the VAV Schedule?
7	snapshot	9/25/19	M104			Confirm no access required within "Enclosure"; Duct will be very difficult to access (if not inaccessible) from 3rd Floor corridor
8	snapshot	9/25/19	M201B			Why does Note #6 exist? T-stats and/or CO2 sensors should be shown wherever required
9	snapshot	9/25/19	M201B			What is interaction between soffits, lights, radiant panels in room like this where no ACT ceiling exists?
10	snapshot	9/25/19	M301			Clarify specifications for factory painted items (standard range vs. custom colors)
11	snapshot	10/2/19	M101A			Review finished ceiling elevation vs. cavity space. Duct may not fit tapping off the top or bottom. Typical in multiple areas in main corridor
12	snapshot	10/2/19	M101B			Service access appear to be blocked on both sides.
13	snapshot	10/2/19	M101B			VAV 1-16 appears to have the controls on top of the equipment. Is this the contract intent? If so, 36" from the deck will be required for access by code.
14	snapshot	10/2/19	M101B			No FD or FSD shown on the floor or exiting the shaft. Please confirm that rating does not have to be maintained.
15	snapshot	10/2/19	M101B			FSD not shown on 8"x4" Hood Duct as it exits shaft.
16	snapshot	10/2/19	M101C			VAV 6-1 may have service/controls access issues. 36" min. required by electrical code.
17	snapshot	10/2/19	M101C			VAV 1-7 seems to have access/min. clearance issues.
18	snapshot	10/2/19	M101C			VAV 6-3 is showing controls to wall side. Need 36" clearance by code.
19	snapshot	10/2/19	M101C			Please review if S.A. & R.A. ducts require FD or FSD as they enter the space or the bathrooms further down stream.
20	snapshot	10/2/19	M101C			VAV 1-16 shows controls on top of the equipment. 36" min. clearance is required by code.
21	snapshot	10/2/19	M102B			Controls access shown to wall side. Need 36" min. by code.
22	snapshot	10/2/19	M102B			VAV 2-25 may not have minimum require clearance for controls on either side.
23	snapshot	10/2/19	M102B			VAV 2-19 controls location may have to be flipped.
24	snapshot	10/2/19	M102B			What is the intent of this vertical ductwork (Toilet 2150). Seems to be out of place.

# Fuller Middle School

## Constructability and Drawing Review Log, 90% CDs

10/7/2019

As of:

Revision:



ITEM #	DATE OPENED	DWG NO/DTL OR SPEC SECTION	DESCRIPTION	BIC	DATE RESOLVED	COMMENTS
25	snapshot	10/2/19	M102B	IDF 2155 is not showing any type of temperature contro or ventilation. Confirm that it is not required.		
26	snapshot	10/2/19	M102B	VAV 2-13 is straddling a wall. Walls are full deck height.		
27	snapshot	10/2/19	M102B	VAV 2-17 may not comply with minimum required clearance for electrical.		
28	snapshot	10/2/19	M102B	VAV 2-11 may not have the min. required clearance for electrical as drawn.		
29	snapshot	10/2/19	M102B	VAV 2-18 may not have the required min. clearance for electrical.		
30	snapshot	10/2/19	M102C	No liner shown between SA and unit connection on return side for noise purposes. Confirm not required.		
31	snapshot	10/2/19	M102C	Branch ductwork not shown.		
32	snapshot	10/2/19	M102D	34-X18 will be in conflict with toilet and toilet partition if the path is to continue down as shown on note.		
33	snapshot	10/2/19	M102D	No FSD shown on return on 20x12 duct exiting shaft.		
34	snapshot	10/2/19	M102D	VAV 2-34 may not have the min. required clearance for electrical.		
35	snapshot	10/2/19	M102D	No FSD shown as exhaust ducts exit shaft. Confirm that it is not required.		
36	snapshot	10/2/19	M102D	No FSD shown as exhaust ducts exit shaft. Confirm that it is not required.		
37	snapshot	10/2/19	M102D	VAV 4-36 will not have the min. required clearance for electrical as drawn. Wall on controls side; access door thru wall would be required.		
38	snapshot	10/2/19	M103A	No FSD shown. Confirm not required.		
39	snapshot	10/2/19	M103A	VAV 3-16 is straddling wall. All walls go to the deck.		
40	snapshot	10/2/19	M103A	VAV 3-17 may not comply with min. electrical clearance requirements as shown.		
41	snapshot	10/2/19	M103A	VAV 3-18 may have an electrical access issue as shown.		
42	snapshot	10/2/19	M103A	VAV 3-19 may have an electrical access issue as shown.		
43	snapshot	10/2/19	M103A	3x14 duct will have to be shifted to not run above wall.		
44	snapshot	10/2/19	M103A	VAV 3-27 & VAV 3-22 will have electrical access issues as shown.		
45	snapshot	10/2/19	M103B	VAV 2-35 is straddling the wall. Walls to be deck height.		
46	snapshot	10/2/19	M103B	VAV 4-36 is straddling a full height wall and will have electrical access issues as shown.		
47	snapshot	10/2/19	M103B	No FSD shown as duct enters shafts or as it enters the building from the roof. Confirm that they are not required.		
48	snapshot	10/2/19	M103B	VAV 4-39 is straddling a full height wall.		
49	snapshot	10/2/19	M103B	VAV 4-43 is straddling a full height wall and controls does not have the min. required electrical access as drawn.		
50	snapshot	10/2/19	M103B	Duct SMOKE Detectors not shown. Confirm that they are not required. (Typical with all rooftop equipment).		
51	snapshot	10/2/19	M103B	Louvers for smoke indicate approximate free face area required, but do not indicate dimension (Typical thru job).		
52	snapshot	10/2/19	M103C	No FSD or FD's shown at roof or shaft penetration. Confirm this is not required.		
53	snapshot	10/2/19	M103C	VAV 1-29 is straddling a full height wall and may pose electrical access issues.		
54	snapshot	10/2/19	M103C	VAV 1-33 may pose an electrical access issue   elevation is same as 24x14 duct.		
55	snapshot	10/2/19	M103C	VAV 1-35 is straddling a full height wall.		
56	snapshot	10/2/19	M103C	Detail needed to show how to run duct and connect the diffusers in the Breakout 3068 and Breakout 3058. It needs to show interiors work associated to the rooms.		
57	snapshot	10/2/19	M103C	VAV 2-33 appears to have electrical access issues as shown.		
58	snapshot	10/2/19	M103C	No FSD shown as 20x12 duct exits shaft. Duct is shown going down, which appears to be in conflict with door.		
59	snapshot	10/2/19	M103C	34x18 S.A. Duct DN. This appears to be conflict with toilet and partitions below.		
60	snapshot	10/2/19	M103C	VAV 2-35 is straddling full height wall.		
61	snapshot	10/2/19	M103C	Ductwork does not show FSD as it exits shaft. Confirm none are required.		
62	snapshot	10/2/19	M103D	No FSD shown on duct exiting shaft. Confirm that it is not required.		
63	snapshot	10/2/19	M103D	No duct smoke detector shown on drawings. Confirm that they are not required.		
64	snapshot	10/2/19	M104	A detail for the dog house will be required for pricing purposes for RTU-5/6. Not something usually provided by mechanical contractor.		
<b>ELECTRICAL DRAWING REVIEW</b>						
1	snapshot	9/25/19	E101D	Confirm no lighting required for ends of aisles/seating in Auditorium		
2	snapshot	9/25/19	E102D	Are this many occupancy sensors necessary in Gymnasium?		
3	snapshot	9/25/19	E103B	Is this quantity of 5p1 light fixtures required? What is detail at lockers vs. railings locations around atrium?		
4	snapshot	9/25/19	E103D	Lighting Plans stop at 3rd Floor; Confirm no lighting required at Roof Level		
5	snapshot	9/25/19	E201A	Review outlet locations vs. Borrowed Lite / Furniture adjacent to Boiler Room		
6	snapshot	9/25/19	E201A	Overhead door at Maker Space by not at Loading Dock; Confirm acceptable to school		
7	snapshot	9/25/19	E201D	Specify height AFF to avoid confusion		
8	snapshot	9/25/19	E201D	No power required for Auditorium Seating / Aisle lighting?		
9	snapshot	9/25/19	E202A	Are these switched receptacles? Is this OK with school?		
10	snapshot	9/25/19	E203A	Architecturals should include typical elevation view of teaching wall referenced for electrical outlet layout		
11	snapshot	9/25/19	E208A	Architecturals should include typical elevation view of classroom entry door/wall referenced for electrical outlet layout		
12	snapshot	9/25/19	6/E300	Check clearance at panel vs. door swing. Review if wall behind panel ELPID should be frame parallel to door to improve clearances		
13	snapshot	9/25/19	E300	Review plywood backboard requirements at electrical/IDF Rooms; 8-ft tall plywood OK in lieu of floor-to-ceiling?		
14	snapshot	9/25/19	E401A	No Carbon Monoxide Detector required in Boiler Room 1018?		
15	snapshot	9/25/19	E401B	Are this many fire alarm horns/strobes actually required in the corridors surrounding the Atrium?		
16	snapshot	9/25/19	E403D	Fire Alarm Plans stop at 3rd Floor; Confirm no Fire Alarm devices required at Roof Level.		
17	snapshot	9/26/19	E400	No BDA System shown; Confirm not required by Framingham Fire Dept		
18	snapshot	9/26/19	E400	Confirm Framingham Fire Dept requirements for Master Box and/or Knox box		
19	snapshot	9/26/19	LS001	Information missing RE: Interior Wall & Ceiling Finishes		
20	snapshot	9/26/19	LS001	Confirm Stage Exhaust requirements captured in HVAC plans		
21	snapshot	9/26/19	E003-1	Dumpster Pad shown on Sheet C-4.1. Confirm no power required for compactor-style dumpster		

**Fuller Middle School**

Constructability and Drawing Review Log, 90% CDs

10/7/2019

As of:

Revision:



ITEM #	DATE OPENED	DWG NO/DTL OR SPECSECTION	DESCRIPTION	B/C	DATE RESOLVED	COMMENTS
<b>LANDSCAPE DRAWING REVIEW</b>						
<b>SPECIFICATIONS</b>						



### **2.1.2 Commissioning Agent Review**

The Commissioning Agent, Jacobs, performed a review of the Progress 90% Construction Documents, dated September 9, 2019.

The Commissioning Agent's comments are documented in the Commissioning Agent Review, dated October 14, 2019 and appended to the end of this section.

The Commissioning Agent's recommendations will be incorporated into the 100% Construction Documents submission.



Item	Initials	Reference	100% DD Comments	100% DD Response	Action	60% CD Comments	60% CD Response	90% CD Comment	90% CD Response
<b>SPECIFICATIONS</b>									
<b>DIVISION 01</b>									
S-1	JAH	011000	Section 1.2.: Several spec sentences indicate a value by listing "xxx". Please review and add required values.	Specs will be further refined for 100% DD Set	CLOSED	To be verified as design progresses	Refer to 100% DD response – no change in response comment.		
S-2	JAH	011000	Section 1.3.A.c: A reference is made to spec 018113. This spec did not appear to be included with the design package (ref. Vol. 1). Please review and reconcile.	This section will be included in 100% DD Set	CLOSED	To be verified as design progresses	Refer to 100% DD response – no change in response comment.		
S-3	JAH	011000	Section 1.3.A.: LEED is indicated, however the level of LEED compliance did not appear to be indicated. Please review and reconcile.	Will be defined in 100% DD Set	CLOSED	To be verified as design progresses	Refer to 100% DD response – no change in response comment.		
S-4	JAH	Div 1 specs	It is suggested that several Div. 1 specs, not currently listed in the TOC, should be added to the design package (ref. Vol. 1). As a minimum, suggest adding specs: 013100 Project Management and Coordination; 013300 Submittal Procedures; 017300 Execution; 017700 Closeout Procedures; 017836 Warranties; and 018113 Sustainable Design requirements. If contents of above-noted additions do not adequately cover Operation and Maintenance manuals and Training requirements, it is also suggested that specs for these be provided.	Additional sections will be included in 100% DD Set	CLOSED	To be verified as design progresses	Refer to 100% DD response – no change in response comment.		
S-5	JRC	General Comment	Many spec sections reviewed has an incorrect section number for Part 3 - Execution. Many sections reviewed start with either 3.2 or 3.3. Suggest reviewing and correcting as required.	Specs will be further refined for 100% DD Set	CLOSED	To be verified as design progresses	Refer to 100% DD response – no change in response comment.		
S-6	JRC	General Comment	Please define where requirements are for submitting shop drawings. These are not provided for in the volume 1 specification sections reviewed.	Will be defined in 100% DD Set	CLOSED	To be verified as design progresses	Refer to 100% DD response – no change in response comment.		
<b>DIVISION 04</b>									
S-7	JRC	04 20 00	Confirm if wetting brick based on IRA testing will be allowed	For veneer layout it is not anticipated that wetting brick will be required as the specifications require an IRA of less than 30. Fully grouted brick areas at the base of the building are to be wetted prior to grout installation.	CLOSED		Refer to 100% DD response – no change in response comment.		
S-8	JRC	04 20 00-4	Special shapes - confirm number of shapes and confirm that cutting is not allowed.	Special shapes are documented on sheet A501. Additional shapes may be added during CD's if warranted (stair towers). Bricks may be cut where required with approval of architect.	CLOSED				
S-9	JRC	04 20 00-18	Consider using the proper term for masonry joints - Masonry Institute states that Brick Expansion Joints (BEJ) is the proper term for clay masonry products.	JLA to review.	CLOSED		It has been JLAs experience that "control joint" is the common use terminology for this type of masonry joint and distinguishes itself separately from the more substantial building structural "expansion joint".		
<b>DIVISION 07</b>									
S-10	JRC	072100-2	Specification notes that the thickness of the insulation is as noted on the drawings. Please confirm that the designed system will provide minimum continuous R value as required by the energy code.	The DD energy models based on the R values indicated in the drawings. Glazed areas have been reduced significantly and mid level shading has been removed to satisfy value engineering requirements. The energy model will be re-run at 60% CD to confirm compliance with the energy code.	CLOSED		The insulation will be continuous and the energy model will meet code and project requirements.		
S-11	JRC	074254	Suggest that coordination guidelines for phenolic wall panels and intersection with other materials such as the aluminum curtainwall and the face brick construction be included in Part 3 - Execution, as they apply.	This will be reviewed and provided in the 60% DD set. The design elevations are being finalized for DD based on value management requirements (the phenolic panels have been reduced significantly).	CLOSED		Relevant instructions will be included in the specifications		
<b>DIVISION 08</b>									
S-12	JRC	084313	Basis of design is the Kawneer Trifab 451UT system, Center glazed. Note that this does not match the system description of flush or outside glazed system. Please confirm intent. Please review drawing comments regarding integration of framing system with exterior wall materials.	Storefront is intended for use in the interior vestibules only. The exterior wall line will be curtain wall.	CLOSED		The basis of design has been modified to Oldcastle 6000 XT as curtain wall has been removed from the project.		
<b>DIVISION 22</b>									
S-13	WGH	22 00 00	Section 2.28 Elevator Sump Pump: Consider specifying the required oil minder control panel's ancillary components	Will comply.	CLOSED	Sump Pump specification section appears removed. Is this still in scope?	Elevator sump pump is included in 90% specification		
S-14	WGH	22 00 00	Section 2.28 Elevator Sump Pump: Consider specifying the required oil minder control panel's ancillary components	Will comply.	CLOSED	Redundant Comment.			
S-15	WGH	22 00 00	Section 2.28 Elevator Sump Pump: Consider integrating the control panel alarms with the building management system.	Agree. Panel will be integrated in BMS.	OPEN	Sump Pump specification section appears removed. Is this still in scope?	Elevator sump pump is included in 90% specification. Control panel will integrate with BMS	Elevator sump pump control panel integration with BMS not indicated in specs section.	
S-16	WGH	22 00 00	2.31 Acid Neutralization System: Consider integrating the control panel alarms with the building management system.	Control panel alarm will be connected to BMS.	OPEN	Control panel interface is not included in specifications. Comment is still OPEN.	Control panel alarm interface will be included in the 90% specification	Control panel interface is not included in specifications.	
<b>DIVISION 23</b>									
S-17	KML	23 00 00 TOC	Table of Contents does not indicate various spec sections (listed as single section "23 00 00 - HVAC"). Suggest updating TOC with specific sections.	Will review and revise table of contents.	CLOSED	Division 23 TOC included at the beginning of section.			

Item	Initials	Reference	100% DD Comments	100% DD Response	Action	60% CD Comments	60% CD Response	90% CD Comment	90% CD Response
S-18	KML	23 00 00 Part 2.12.J.7.99	Chiller controls section indicates "Optional" features. Included in this section is line item 1, which is BMS interface with BACnet or LonTalk. Please verify if this is an optional feature from the chiller manufacturer that is required for the project, or optional for the project. If optional for the project, consider making this a requirement for consolidate system monitoring and operation.	This feature is an optional feature from the manufacturer. Will clarify specifications.	CLOSED				
S-19	KML	23 00 00 Part 2.12	Chiller startup requirements call for two working days to ensure proper operation of equipment and owner training. Suggest including coordination with control contractor for integration with BMS during manufacturer's startup.	Will review and revise start-up requirements to coordinate with controls contractor.	CLOSED	Comment still OPEN.	GGD: This has been added to the 90% set.		
S-20	KML	23 00 00 Part 2.13.B.2	Roof Top Air Handling Unit General Description calls for the units to be provided with "e. Modulating direct expansion cooling coil section" and "h. Chilled water cooling coil." Please confirm number of chilled water coils required and remove redundant items.	Will review and remove redundant items.	CLOSED	Comment still OPEN.	GGD: This has been added to the 90% set.		
S-21	KML	23 00 00 Part 2.13.Q	Roof Top Air Handling Unit controls sections calls for "All sensors, actuators, controls shall be provided by the ATC/DDC controls subcontractor. AHU General Description section calls for units to be factory assembled and tested. Please verify if controls will be packaged with unit or field-installed custom controls and associated scope of the controls subcontractor.	Will review and revise provisions of controls.	CLOSED	Comment still OPEN.	GGD: ATC subcontractor shall coordinate with HVAC contractor to provide any controls items that RTU manufacturer cannot provide.		
S-22	WGH	23 00 00 Part 2.13P			CLOSED	This specification section refers to 23 00 00 Part 2.3 for Roof Curb requirements. Part 2.3 specifies Meters and Gages. CxA suggests rooftop unit roof curb requirements be included with the specifications and coordinated with the drawing notes and details. Refer to comments #89a and #93.	GGD: Specification reference will be updated to specification 23 05 48 paragraph 2.2.A.22 - Roof Curb specification & drawing details.		
S-23	KML	23 00 00 Part 2.14	Hydronic Terminal Heating Units controls not specified for all types of equipment (devices, setpoints, integration with BMS, etc.). Suggesting noting if equipment is to be provided with packaged controls and no BMS interface.	Will review to see if this is needed.	CLOSED	Comment still OPEN.	GGD: A general note has been added to refer to control drawings for all terminal heating units.		
S-24	KML	23 00 00 Part 2.16	Power and Gravity Ventilators section does not indicate motor/drive integration with BMS. Consider including integration requirement for fans equipped with variable frequency drives (status, speed, alarms, etc.).	Will review to see if this is needed.	CLOSED	Comment still OPEN.	GGD: A general note has been added to refer to control drawings for all fans equipped with VFD's.		
S-25	KML	23 00 00 Part 2.24	Please confirm if Ductless Cooling Units will have any interface with the BMS (space temperature, unit status, alarms, etc.)	Ductless cooling units will interface with BMS. We will review the specifications to ensure this is indicated.	OPEN	Updated ductless split specifications does not include BMS interface. This is a common gap in coordination. CxA suggest this is clarified.	GGD: Specification notes will be revised to refer to control drawings for ductless cooling units interface with BMS.	Ductless cooling units integration with BMS not specified.	
S-26	KML	23 00 00 Part 3.14 & 3.15	Sections appear to be redundant ("Installation of HVAC Rooftop Units" vs. "Installation of Rooftop Air Handling Units")	Will review and revise/remove redundant information.	OPEN	Comment still OPEN.	GGD: This has been corrected on the 90% set.	Section removed, but still included in Table of Contents so subsequent section numbering is off.	
S-27	KML	23 00 00	Sequence of operation not provided for all equipment and systems. To be reviewed once complete.	Sequence of operations are underway.	CLOSED				
S-28	WGH	28 00 00 Part 1.3D			CLOSED	Related sections include Division 23 "HVAC Instrumentation and Controls. Section 23 00 00 Part 2.29 includes Automatic Temperature Controls. CxA suggests these sections be coordinated for clarity.	GGD: Reference has been updated.		
<b>DIVISION 26</b>									
S-29	JAH	260000	Section 1.2.C.: A reference is made to spec 012300. This spec did not appear to be included with the design package. Please review and reconcile	Division 012300 is typically for alternates. We will review and edit as required.	OPEN	To be verified as design progresses	GGD: We have removed all references to 01 23 00 as there is no such section on the project.	Reference still exists in spec section 26 00 00 1.2C.	
S-30	JAH	260000	Section 1.3.B: Suggest adding text....."Provide all necessary coordination with other trades and the architect."	Done	CLOSED				
S-31	JAH	260000	Section 1.3.B.10: Suggest adding text....."Provide and coordinate required electrical manufacturer's site testing and installation verifications. Identify and coordinate any Factory testing and make provisions for necessary site personnel (e.g., maintenance personnel, client, Cx agent, and engineer of record) to attend FAT execution.	Done	CLOSED				
S-32	JAH	260000	Section 1.3.B.26: Suggest adding text....."Provide all necessary technical and material support for the commissioning of the project's electrical components and systems.	Done	CLOSED				
S-33	JAH	260000	Sections 1.3.B.25 & 1.7: A reference is made to spec 018113. This spec did not appear to be included with the design package. Please review and reconcile.	We will review this reference and correct as required.	CLOSED	To be verified as design progresses	GGD: 01 81 13 refers to sustainable design requirements		
S-34	JAH	260000	Section 1.3.B.14: A reference is made to specs 116133, 116191, and 266111. These specs did not appear to be included with the design package. Please review and reconcile.	We will review these references and correct as required.	CLOSED	To be verified as design progresses	GGD: 11 61 33 refers to Theatrical Rigging, 11 61 91 refers to Theatrical lighting instruments and accessories, 26 61 11 refers to Theatrical Lighting controls		
S-35	JAH	260000	Section 1.8: A reference is made to spec 018111. This spec did not appear to be included with the design package. Please review and reconcile.	We will review this reference and correct as required.	OPEN	To be verified as design progresses	GGD: There is no such section all references to this section will be removed.	Reference still exists in spec section 26 00 00 1.8A.3.	

Item	Initials	Reference	100% DD Comments	100% DD Response	Action	60% CD Comments	60% CD Response	90% CD Comment	90% CD Response
S-36	JAH	260000	Section 1.3. B. 30: Add line item indicating "...Work required for Lightning protection and building grounding, including grounding tests and lightning protection certification."	Lightning preventor system has been added. The project will not have a lightning protection system.	OPEN	Please clarify what is provided for a Lightning Preventor System - UL master label only refers to Ltng Protection sys.	GGD: Lighting preventor system manufacturer provides upon completion of installation and required inspection and tests that the system meets HPB-21, Levels 1&2 a certificate of Guarantee catastrophe umbrella policy that guarantees the preventor lighting protection system with an insurance policy of \$10,000,000.00. The guarantee is limited to the structural building and also excludes surge transient protection for services.	Lightning preventor system has been added to Section 1.3 "Description of Work" as a line item, but no associated section has been included or requirements identified.	
S-37	JAH	260000	Section 1.3. B. 20: A reference is made to spec 0150003. This spec did not appear to be included with the design package. Please review and reconcile.	We will review this reference and correct as required.	CLOSED				
S-38	JAH	260000	Section 1.8: A reference is made to spec 013100. This spec did not appear to be included with the design package. Please review and reconcile.	We will review this reference and correct as required.	CLOSED	To be verified as design progresses	GGD: 01 31 00 refers to project management and coordination.		
S-39	JAH	260000	Section 1.13: It is suggested "NETA, National Electrical Testing Association" be added to the list of Codes, Ordinances, and Permits	Done	CLOSED				
S-40	JAH	260000	Section 1.16. D. It is suggested to add a new item: ... "Electrical Contractor is responsible to provide and/or install the correct designated equipment, components, and materials. Submittal approval by the engineer does not relieve the contractor from any contractual requirement to provide a complete and fully working system."	Done	CLOSED				
S-41	JAH	260000	Section 1.15: A reference is made to spec 013300. This spec did not appear to be included with the design package. Please review and reconcile.	We will review this reference and correct as required.	CLOSED	To be verified as design progresses	GGD: 01 33 00 refers to submittal procedures		
S-42	JAH	260000	Section 1.3 B: It is suggested to add a line item ... "Electrical Subcontractor shall conduct a light level review in the field to ensure luminaires and their footcandle readings are in accordance with project criteria and the IESNA."	Done	CLOSED				
S-43	JAH	260000	Section 1.19. A. : Division number to be provided.	Division number will be coordinated and edited.	OPEN	To be verified as design progresses	GGD: 01 50 00 temporary facilities and controls section has been referenced.	Division number not specified.	
S-44	JAH	260000	Section 1.20.C: Add text...."Provide and coordinate required electrical manufacturer's site testing and installation verifications. Site testing protocols shall be submitted by the applicable vendor PRIOR to commencement of site tests. All completed site testing is to be properly documented with test reports submitted as a Cx pre-requisite. Identify any Factory testing and make provisions for necessary site personnel (e.g., maintenance personnel, client, Cx agent, and engineer of record) to attend FAT execution.	Done	CLOSED				
S-45	JAH	260000	Section 1.20. D: At add item...."Provide all necessary technical and material support for the commissioning of the project's electrical components and systems. After establishing a general project schedule, add pertinent details of the commissioning workplan, incorporating necessary Cx predecessors, successors, and durations. Obtain/execute/submit all required documentation necessary for Cx to commence".	Done	CLOSED				
S-46	JAH	260000	Section 1.23: A reference is made to spec 017700. This spec did not appear to be included with the design package. Please review and reconcile.	We will review this reference and correct as required.	CLOSED	To be verified as design progresses	GGD: 01 77 00 refers to closeout procedures.		
S-47	JAH	260000	Section 2.24: Suggest label indicate "Lightning Protection System", <b>not</b> "Lightning Preventer System"	A lightning protection system will not be provided. The project will include a lightning preventor system. No change necessary.	OPEN	Please clarify what is provided for a Lightning Preventor System - UL master label only refers to Ltng Protection sys.	GGD: Lighting preventor system manufacturer provides upon completion of installation and required inspection and tests that the system meets HPB-21, Levels 1&2 a certificate of Guarantee catastrophe umbrella policy that guarantees the preventor lighting protection system with an insurance policy of \$10,000,000.00. The guarantee is limited to the structural building and also excludes surge transient protection for services.	Reconcile "Lightning Preventor" and "Lightning Protection" nomenclature as required.	
S-48	JAH	260000	Section 3.4: Add text or additional item: "Ensure that equipment nameplate include date of manufacture".	Done	CLOSED				
S-49	JAH	260000	Section 3.16.H.: Clarify/describe NFPA 110 testing requirements for the generator	This is described in Part 2 of the specifications.	CLOSED	To be verified as design progresses	GGD: NFPA 110 test requirement has been added.	Included in Section 2.23.O.	
S-50	JAH	260000	Suggest that all control points/alarms that are to be indicated at the BMS system which are derived from the generator, generator annunciator, and ATS switches be identified.	Done	CLOSED				
S-51	JAH	260000	Section 3.16.H.: Add requirement and references for NFPA 3 & 4 testing (Integrated Life Safety tests)	We will review these standards further before editing the specifications.	CLOSED	To be verified as design progresses	GGD: This would fall under commissioning		
S-52	JAH	260000	Suggest that all control points/alarms that are to be indicated at the BMS system which are derived from the FACP be identified.	This will be identified in the ATC control drawings point list if required.	CLOSED	To be verified as design progresses	GGD: The fire alarm system will output a single Analog out for alarm to BMS system		
S-53	JAH	260000	Add requirement for electrical subcontractor to provide "in process" panel schedule sheet while loads are being connected. Electrical subcontractor to review phase loading at panelboards at the end of work and prior to closeout to ensure balanced loading. Provide a final typed panel schedule at completion of work.	Done	CLOSED				
S-54	JAH	260000	Add requirement for Arc Flash study to provide required PPE/Arc Flash equipment ID labels	Already included in 3.17, we will add to this section to provide more detail.	CLOSED				
S-55	JAH	260000	Add requirement for "ring out" of all starters, controllers, circuits and sensors in coordination with BMS checkout to ensure all components properly connected and operable.	Requirement will be added.	CLOSED	To be verified as design progresses	GGD: added requirement		

Item	Initials	Reference	100% DD Comments	100% DD Response	Action	60% CD Comments	60% CD Response	90% CD Comment	90% CD Response
S-56	JAH	260000	It is suggested to add text to distribution gear nameplates (panels, switchboards, ATS units, etc.) to provide info of the gear/branch circuit that supplies it and/or which it powers. In addition, the distribution gear nameplates shall identify the year of their manufacture (required for future life cycle reviews)	Done	CLOSED				
S-57	JAH	260000	It is suggested to add text to the wiring device nameplates to include info of the panel/branch circuit that supplies it.	Done	CLOSED				
<b>Drawings</b>									
<b>Architectural</b>									
D-1	JRC	A-104	As the documents continue through the CD phase please consider the layout of the roof drains, high and low points of the roof, as they relate to the roof skylights. The high point(s) and framing for the skylights will have an impact on the roof sill condition and the method of waterproofing / flashing, as well as the unusual connection at the ends of the skylights	The major roof drainage strategy will be shown in the 100% DD set.	CLOSED		The drainage has been refined in the 60% documents. Final scupper elevations will be determined, but the overall roof edge has been held to 6" above the low point of the drain low point line.		
D-2	JRC	General Exterior Comment	As the documents continue through the CD phase please consider the number of differing plan and vertical details required due to specific material / Design considerations. Note that there are a number of air barrier details required for the maintenance of air, thermal and water separation, and proper detailing must support what appears to be a Rain Screen application with the phenolic panels. (Sheet A-501)	JLA agrees with comment. The brick and phenolic panel systems are open joint systems.	OPEN		Refer to 100% DD response – no change in response comment.		
D-3	JRC	General Exterior Comment	It is recognized that the Design Development sections noted are raw cut from the building model. As the documents continue through the CD phase please consider the need for integration and coordination of exterior elements and structural framing. In these cases tolerances of material and construction are often overlooked.	JLA agrees with the comment.	OPEN		Refer to 100% DD response – no change in response comment.		
D-4	JRC	A-211/A213	A number of elevations indicate phenolic panels with aluminum curtainwall on either or both sides. Consider how the connection is designed for maintaining the air barrier and how the glass panel may be removed in the event of breakage.	The curtain wall utilizes a pressure plate which will facilitate any necessary glass replacement. The phenolic panels will not be set into the glazing pocket.	CLOSED		The parameters are the same in terms of a rain screen wall system, however, the openings have been changed to a storefront system and a sealant-based tie in with the AVB.		
D-5	JRC	A-211/A212	A number of elevations indicate phenolic panels with face brick panels on either or both sides. Consider how the connection is designed for maintaining the air barrier.	The AVB will always run continuous behind the systems. There will be no break or transition in the AVB where the veneer material changes from brick to panel.	CLOSED		Refer to 100% DD response – no change in response comment.		
D-6	JRC	A-211/A212	Brick panels, suggest study on BEJ (Brick Expansion Joint) and position of random pattern brick joints as well as masonry openings and their associated lintel design.	Generally where the brick rises more than one story there will be a continuous relieving angle bracketed from the floor edge. Localized loose lintels will employed as necessary.	CLOSED		Refer to 100% DD response – no change in response comment.		
D-7	JRC	A-213	As the design continues - please consider the offset configuration of the sun shade framing indicated on several of the elevations. The curtainwall specified may not be able to achieve the offset positioning as have been indicated. Primary issue will be structural loading on the horizontal mullions as well as the potential interference with the specified weep designation for each glass panel.	It is anticipated that the horizontal will be structural in this configuraion. Openings are being adjusted accordingly. This will maintain the integrity of the separate panels to allow for zone drainage. The current design is under review by manufacturers.	CLOSED		Sunshades have been deleted from the project and the curtain wall has been changed to storefront.		
D-8	JRC	A-214	As the design continues - please consider the location of the horizontal masonry joint and its final location. Confirm that the expansion or contraction limits are maintained.	Refer to item 61. The only locations where veneer will bear directly from foundation to roof are at the auditorium and gymnasium.	CLOSED		Refer to 100% DD response – no change in response comment.		
D-9	JRC	A-215 - A 217	Please see comments noted above as similar	Refer to responses above.	CLOSED		Refer to 100% DD response – no change in response comment.		
D-10	JRC	A-311-A-320	The following comments apply generally to all wall sections. Please consider these as suggestions as the construction document phase continues.	Refer to responses above.	CLOSED		Refer to 100% DD response – no change in response comment.		
D-11	JRC	A Series	Typical head and sill details at curtainwall - consider minimizing potential thermal bridging with structural slab.	Thermal bridging will be considered.	CLOSED		Details have been modified for storefront framing at the openings.		
D-12	JRC	A Series	Typical head and sill details at curtainwall - consider the method of flashing and how potential movement may impact it.	Flashing and movement will be considered. As details develop JLA would be pleased to do a sit down review of BEX comments.	OPEN		Refer to 100% DD response – no change in response comment.		
D-13	JRC	A Series	Typical brick details - the specifications call for special shapes. As the design continues note that the potential cost and detail consideration increases with the number of special shapes intended for the project.	Specials will be detailed as required to meet the design intent.	CLOSED				
D-14	JRC	A Series	Roof / parapet details - provide the masonry walls to expand, minimizing potential water infiltration	Details will be provided for review.	CLOSED				
D-15	JRC	A Series	Typical air barrier details - primarily at the intersection of differing materials. Allow for thermal expansion and movement.	Details will be provided for review.	OPEN		Refer to 100% DD response – no change in response comment.		
D-16	JRC	A Series	Glazing at offset panels - Standard frames as specified may not achieve the required thermal barrier and subject the framing to condensation, sections 2 and 3 on sheet A318	JLA to reiew. The intent here is not clear to the reviewer due to incomplete drafting.	CLOSED		These wall sections have been modified with the deletion of the curtain wall.		
D-17	JRC	A Series	Exterior sun shade details - as they develop please consider the limitations on weight and wind loading that could contribute to the limits of the aluminum curtainwall system. In addition, the connections for the sun shades could impact thermal separation, (bridging), and failure of the air barrier cavity seals at the line of insulation.	JLA understands comment.	CLOSED		Sunshades have been deleted from the project.		

Item	Initials	Reference	100% DD Comments	100% DD Response	Action	60% CD Comments	60% CD Response	90% CD Comment	90% CD Response
D-18	JRC	A Series	Details for skylight will be reviewed with next package. Several items to consider are the thermal barrier between the framing and roof deck as well as the height of the skylight curb, primarily for winter snow depth and potential water infiltration.	Skylight details are under development. A section at the curb will be provided for review by the commissioning agent.	CLOSED				
D-19	PW	A104			CLOSED	As the design process continues, be sure proper drainage of all roof areas is provided including bays, projections, stairwells, etc. (ie, no drainage shown at the bay along the south elevation between S2 and S3.)	Small bays will direct drain off of the edge. Stair roofs will drain onto the main roof.		
D-20	PW	dwg 1/A314			CLOSED	At the interface of the roof assembly and the exterior wall, be sure to provide continuity of the air barrier from the wall to the roof. Discontinuities of the air barrier provide pathways for air exfiltration and air infiltration and the large volumes of moisture vapor that travel in them. This moisture vapor can condense on cold surfaces creating moisture problems.	The roof vapor retarder and AVB will be overlapped and sealed along the roof edge.		
D-21	PW				CLOSED	As brick and concrete masonry units are porous and absorb water, be sure to provide expansion joints vertically and horizontally to accommodate expansion/contraction due to moisture absorption. Frequency of expansion joints can be found in The Brick Industry Association and The International Masonry Institute.	Expansion joints will be provided at the top of the masonry walls and will also have multiple vertical control joints in the façade. CMU back up walls at gym and auditorium are restrained by bond beams and do not require expansion joints.		
D-22	PW	dwg 4/A322			CLOSED	As the design proceeds, be sure to include proper drainage of the wall cavity at the cavity's bottom.	Proper drainage will be provided at the base of walls.		
D-23	PW	dwg 4/A322			OPEN	Consider including ventilation openings in the mortar joints at the top of the typical wall cavity (for brick and concrete masonry unit walls) for enhanced ventilation and drying out of the wall cavity and exterior masonry cladding. This will also reduce the risk of inward driven moisture vapor.	JLA will review – the top of the wall will have a brick expansion joint. This is typically open for good ventilation.		
D-24	PW	dwg 1,2/A316			CLOSED	As the design progresses, be sure to seal the air barrier when penetrated by the canopy/sunshade structure.	The AVB will be sealed at all penetrations.		
D-25	PW	A501			CLOSED	Confirm R-value project requirements can be met with continuous insulation within the wall cavity. (Confirm insulation is not needed within the typical stud cavity)	The insulation will be continuous and the energy model will meet code and project requirements.		
D-26	PW	dwg 10/A501			OPEN	Due to the open joint configuration of the composite metal panel cladding, drainage of the wall cavity should be carefully considered. The horizontal configuration of the Z-furring supporting the composite metal panels will impede good drainage of the cavity. Consider orienting the Z-furring vertically if possible.	JLA will review. The Z furring is designed to drain at edges.		
D-27	PW	dwg 9/A501			OPEN	Similar to comment on 10/A501	JLA will review. The Z furring is designed to drain at edges.		
D-28	PW	dwg 2/A501			CLOSED	We recommend a soft joint between the underside of the relieving angle and the brick/CMU below to allow for expansion due to moisture absorption.	This is an open joint that will allow for expansion of the masonry.		
D-29	PW	dwg 5/A540			OPEN	Consider including an enlarged detail describing the flashing, counterflashing and roof flashing termination in greater detail.	JLA will review.		
D-30	PW	dwg 5/A540			CLOSED	Will the skylights have gutters to capture condensation?	Yes.		
D-31	PW	dwg 1/A104			OPEN		Consider providing an overflow roof drain near every roof drain to create a secondary means of drainage should the main become clogged from leaves, dirt, debris, etc.		
D-32	PW	dwg 1/A104			OPEN		Slopes of the roof membrane should be provided. Recommend a minimum of 1/4" per foot to allow for deflection the roof structure.		
D-33	PW	dwg 1/A104			OPEN		Along the south elevation there are several "bays" with low-slope membrane roofs separated from the main roof. It is not clear how these roof areas are being drained; with a scupper or with a roof drain?		
D-34	PW	07.54.19			OPEN		Roofing insulation: a high compressive strength rigid insulation may be needed under the precast conc. pavers of Roof System 4. The polyiso foam board insulation currently in the spec has a capacity of 20 psi, which may not be sufficient.		
D-35	PW	A213			OPEN		As brick and concrete masonry units are porous and absorb water, be sure to provide expansion joints vertically and horizontally to accommodate expansion/contraction due to moisture absorption. Frequency of expansion joints can be found in The Brick Industry Association and The International Masonry Institute.		

Item	Initials	Reference	100% DD Comments	100% DD Response	Action	60% CD Comments	60% CD Response	90% CD Comment	90% CD Response
D-36	PW	A501			OPEN			As currently designed, the fluid applied AVB (07 27 26) is vapor impermeable and will function as a vapor barrier (water vapor permeance is currently specified to be 0.08 perms). These exterior wall systems should be designed to dry to the interior and exterior of the AVB. As the design is completed, Jacobs strongly recommends not including any interior finishes with a water vapor permeance of less than 2 perms as this would act as a second vapor barrier effectively trapping moisture vapor within. Vinyl wallcovering and some paint coatings are vapor impermeable and should be avoided.	
D-37	PW	A501			OPEN			Wall Types 4, 5, 6, 7, 8, 9: As the wall sections for these wall types are completed, consider including voids in the mortar joints at the top of the masonry cladding to allow for ventilation of the wall cavities. (Ventilation of the wall cavities will allow the water vapor to be circulated to the exterior via convection. Dryer wall cavities will reduce the risk of moisture damage within the exterior wall system in two ways; 1) mitigate the risk of inward driven moisture vapor drive in the spring and fall, and 2) reduce corrosion of the steel masonry anchors, fasteners, etc.	
D-38	PW	3, 12, 13, 17/A520			OPEN			As these parapet details are finalized, Jacobs strongly recommends joining the air barrier of the roof assembly with the air barrier of the wall assembly. There should be no discontinuities of the air barrier, and the wall-roof interface is a common failure mode. (Small defects or gaps in the air barrier can result in substantial moisture problems within the wall/roof. For example, in the cold climate of Massachusetts, approximately 50 pints of water can enter a wall assembly through a hole only 1/2" in diameter during the course of a single heating season.)	
D-39	PW	10, 11/A521			OPEN			We recommend a soft joint between the underside of the relieving angle and the brick/CMU cladding below to allow for expansion due to moisture absorption.	
D-40	PW	4,6/A521			OPEN			Recommend including pan flashing with end dams below the aluminum sill to collect and drain to the exterior incidental water which will enter the window assembly as it ages. (Gaskets, seals, etc become brittle and inelastic over time and fail to expand/contract.) Pan flashing with an interior upturned leg is a best practice and will prevent moisture from entering the wall system.	
<b>Plumbing</b>									
D-41	WGH	P0.02	Schematic H.W. Heater / Storage Tank Piping Detail 1 includes a hot water return recirculation pump connected to the BMS for the potable domestic hot water system. Non-Potable Water Heater Piping Detail includes a hot water return recirculation pump controlled by a (7) programmable time clock. Is this recirc pump and time clock connected to the BMS?	Detail to be revised with circ pump connected to BMS.	CLOSED	This schematic has been relocated to sheet P001. The control notes call for the water heater controller to interface with the BMS. DD response notes circ pump to connect to BMS. Please clarify.	The detail and specification revised to monitor the status of water heater and recirculating system through BMS		
D-42	WGH	P0.02	Detail 7 calls for an oil minder control panel. Does this control panel integrate with the BMS? The specified unit includes this option.	Yes. Will connect panel to BMS.	OPEN	Sump detail appears removed from detail sheets. Is this still in scope?	Detail shown on dwg P003	Elevator sump pump detail calls for panel to have additional contact for remote alarm location. Suggest specifying in notes if this alarm is to be monitored at BMS (and ATC contractor scope).	
D-43	WGH	P0.02	Detail 7 shows a single float switch. The specifications indicates a stainless steel probe. The specified unit includes additional floats and sensors. Cx suggest coordinating the detail and specifications.	Agree Will coordinate and update detail.	OPEN	Sump detail appears removed from detail sheets. Is this still in scope?	Detail shown on dwg P003	Detail indicates float switch while specifications still call for stainless steel sensor probe.	
<b>Mechanical</b>									
D-44	KML	General	Drawing set does not include a symbol/abbreviation legend.	Symbol/abbreviation legend is included on drawing M302.	CLOSED	CxA suggest alphabetizing the abbreviations list.	GGD: Will comply.		
D-45	KML	M Series	All terminal heating/cooling equipment locations not yet indicated. Several occupied spaces are not outfitted with ventilation or tempering.	Terminal equipment locations will be indicated.	CLOSED	Comment still OPEN.	GGD: This has been corrected on the 90% set.		
D-46	KML	M Series	Mechanical equipment nomenclature/tags not yet indicated.	Equipment tags/nomenclature will be indicated.	CLOSED				
D-47	KML	M101A	No exhaust indicated for Recycling/Trash Room 1014.	Exhaust will be indicated.	CLOSED				
D-48	KML	M101A	Kitchen makeup and exhaust air equipment and ductwork not indicated on mechanical floor plans.	Kitchen make up and exhaust equipment and ductwork will be indicated.	CLOSED	Comment still OPEN.	GGD: This has been corrected on the 90% set.		
D-49	KML	M101A	Enlarged Boiler Room Plan appears to indicate the boiler plant is not confined to the designated space (pumps and expansion tank shown in Custodian Toilet 1016.	Boiler room plan has been updated.	CLOSED				
D-50	KML	M101A-103D	Ductwork plans do not indicate supply/return designations.	Ductwork plans will indicate supply/return designations.	CLOSED	Comment still OPEN.	GGD: This has been corrected on the 90% set.		
D-51	KML	M101A-103D	Ductwork plans do not yet show duct routes and connections to all terminal units.	Duct routes and connections to all terminal units will be indicated.	CLOSED	Comment still OPEN.	GGD: This has been corrected on the 90% set.		
D-52	KML	M101A-103D	Ductwork plans do not indicate min/max airflow values utilized for basis of design and energy modeling.	Ductwork plans will indicate max design airflow values for equipment. The VAV schedule will indicate minimum airflow values.	CLOSED				
D-53	KML	M201A-203D	Mechanical piping plans do not indicate system or supply/return designations (CHWS/R, HHWS/R).	Piping plans will be updated to indicate supply/return designations.	CLOSED	Heating Hot Water piping labels added in places. CxA suggest piping identification be clearly provided with flow arrows.	GGD: This has been corrected on the 90% set.		



Item	Initials	Reference	100% DD Comments	100% DD Response	Action	60% CD Comments	60% CD Response	90% CD Comment	90% CD Response
D-54	KML	M201A-203D	Mechanical piping plans do not yet show supply and return CHW/HW piping and connections to all terminal units.	Piping plans will be updated to indicate connections to terminal units.	OPEN	Comment still OPEN.	GGD: This has been corrected on the 90% set.	Piping plans do not show routes/connections to rooftop equipment.	
D-55	KML	M201A-203D	Mechanical piping plans do not indicate min/max flow rates or differential pressures utilized for basis of design and energy modeling.	Hydronic flow rates of equipment will be indicated in future submissions on the piping plans and schedules.	OPEN	Comment still OPEN.	GGD: This will be finalized and addressed on final CD piping flow diagrams and hot & chilled water controls drawings.		
D-56	KML	M201A-203D	Mechanical piping plans do not include roof level and connections to Rooftop Air Handling Units equipped with chilled water and heating hot water coils.	Drawing M104 indicates both ductwork and piping layout at the roof level.	OPEN			Roof piping layout not indicated on Drawing M104 (ductwork only).	
D-57	KML	M104			OPEN	Sheet M104 includes the note "Factory fabricated rooftop plenum curbs to be provided by RTU manufacturer. Typical". This note is at variance with the Rooftop unit / Makeup air unit detail on sheet M304. Refer to comment D-63. Please coordinate these sheets.	GGD: Details will be revised for RTU curb requirements.	Please confirm if rooftop plenum curbs will be provided by RTU manufacturer or HVAC contractor.	
D-58	KML	M104			OPEN	Rooftop unit RTU-5/6 includes supply and return mains dropping into the building within a roof level duct enclosure. CxA suggest roof level duct enclosures be detailed for construction, duct access (if necessary), etc.	GGD: A detail will be provided.	Detail not included in 90% CD set.	
D-59	KML	M104			OPEN	Enlarged Pump House Plan is shown at 1/4" scale. CxA suggest this enlarged plan be increased for better clarity.	GGD: Will comply.	Still shown at 1/4" scale.	
D-60	KML	M301	RTU schedule notes call for variable frequency drives for energy recovery wheels. Specifications call for fixed plate heat exchangers or enthalpy plate heat exchangers for energy recovery. Please verify what type of energy recovery, if any, is required.	The basis of design rooftop units will be equipped with fixed plate heat exchangers. We will review and revise the RTU schedule notes.	OPEN	Comment still OPEN.	GGD: Schedule notes will be revised.	RTU schedule notes still include VFD for energy recovery wheel.	
D-61	KML	M301	Air-Cooled Liquid Chiller schedule notes call for 30% propylene glycol solution for heating hot water system freeze protection. Please verify if this note is applicable for the chilled water system or should be relocated.	Schedule note has been updated to indicate chilled water.	CLOSED				
D-62	KML	M301	Equipment schedules in development. To be further reviewed once complete.	Equipment schedules will continue to develop.	OPEN	Comment still OPEN.	GGD: Schedules will continue to develop.	Equipment schedules are not complete, including but not limited to expansion tanks, glycol make-up systems, ductless splits, condensate pumps.	
D-63	KML	M Series	Roof Top Unit Detail/Layout not included. To be reviewed once complete.	Make up air unit detail on drawing M304 will be updated to apply to all rooftop units.	CLOSED	This Rooftop unit / Makeup air unit detail is at variance with the drawing notes on sheet M104. Refer to comment D-57.	GGD: Detail will be revised for RTU curb requirements.		
D-64	KML	M Series	Control diagrams not provided for all equipment and systems. To be reviewed once complete.	Control diagrams will be provided in future submissions.	CLOSED				
D-65	KML	M Series	Because of the size of the building and the numerous systems, CxA suggest including single line flow diagrams for the mechanical systems including: heating hot water piping systems, chilled water piping systems, condensate piping, and air distribution systems.	Drawing M305 includes flow diagrams for ductwork, heating hot water and chilled water piping systems.	CLOSED				
D-66	KML	M401			OPEN			RTU-1-4 are noted as 100% outdoor air units. The flow diagram indicates recirc dampers that the sequence of operation states shall modulate in sequence with the outdoor air and exhaust air dampers to maintain space CO2 and temperature. The schedule indicates the units are only capable of 12,500 CFM of outdoor air with a total supply airflow of 20,000 CFM. Please clarify.	
D-67	KML	M401			OPEN			RTU-1-4 points list includes reference to energy recovery wheel. Basis of design is for energy and sensible heat plate exchangers.	
D-68	KML	M402			OPEN			RTU-5 points list includes reference to energy recovery wheel. Basis of design is for energy and sensible heat plate exchangers.	
D-69	KML	M402			OPEN			RTU-5 serves the gymnasium. Sequence of operation states the chilled water coil control valve will modulate to dehumidify the incoming air. Consider specifying space relative humidity setpoints to control unit operation in order to protect gymnasium floor and avoid voiding warranty.	
D-70	KML	M403			OPEN			RTU-6 is noted as 100% outdoor air unit. The flow diagram indicates recirc dampers that the sequence of operation states shall modulate in sequence with the outdoor air and exhaust air dampers to maintain space CO2 and temperature. The schedule indicates the units are only capable of 11,250 CFM of outdoor air with a total supply airflow of 12,000 CFM. Please clarify.	
D-71	KML	M403			OPEN			RTU-6 points list includes reference to energy recovery wheel. Basis of design is for energy and sensible heat plate exchangers.	
D-72	KML	M404			OPEN			RTU-6 points list includes reference to energy recovery wheel. Basis of design is for energy and sensible heat plate exchangers.	
D-73	KML	M405			OPEN			The VAV details show a connection to the lighting controls and associated motion sensor. Please clarify if the lighting controls motion sensor shall be used to index the VAV between occupied and unoccupied modes.	
D-74	KML	M406			OPEN			Boiler sequence of operation reference rotating boilers #1, 2 and 3. There are only 2 boilers indicated in the schedule.	

Item	Initials	Reference	100% DD Comments	100% DD Response	Action	60% CD Comments	60% CD Response	90% CD Comment	90% CD Response
D-75	KML	M407			OPEN			Chilled water system sequence of operation reference primary and secondary loop pumps. System appears to be variable primary with a single set of chilled water pumps. Please clarify.	
<b>Electrical</b>									
D-76	JAH	E001	Suggest modifying "Electrical Symbols " with respect to raceways and panels data - a similar symbol is used for both. Drawing is not listed on drawing table of contents. In addition, if drawing is to be utilized with or is to complement drawing E003-1, there should be a note or reference between the two.	Ok	OPEN	Comment still OPEN.	GGD: the symbol is not the same it is a printing issue that we will correct.		
D-77	JAH	E-PH-1	Drawing E-PH-1 lists two fixtures that do not appear on the lighting fixture drawing (E002) - namely, SL1A & SL2. If these fixture types are correct, and all lighting fixture info is to be found on E002, these fixtures should be added to drawing E002. If incorrect, remove/correct the fixtures on drawing E-PH-1.	This is an early bid package not to be issued with final set.	CLOSED	Please clarify how dwg will be issued	GGD: the work is done and it will not be part of the final bid set.		
D-78	JAH	E-PH-1 & E002	Drawing E-PH-1 lists two fixtures that do not appear on the lighting fixture drawing (E002) - namely, SL1A & SL2. If these fixture types are correct, and all lighting fixture info is to be found on E002, these fixtures should be added to drawing E002. If incorrect, remove/correct the fixtures on drawing E-PH-1.	E-PH-1 is an early bid package not to be issued with the final set.	CLOSED	Please clarify how dwg will be issued	GGD: the work is done and it will not be part of the final bid set.		
D-79	JAH	E-PH-1	Add circuit info for the lights as design is finalized	This has been completed.	CLOSE				
D-80	JAH	E002	Complete lighting fixture table . Of the dozen or so fixtures utilized on the lighting drawings, the "mgr. column" (2nd from right) and the "schedule column" (farthest right column) do not contain all required references. Also, for many fixtures, a single alpha character is designated for a manufacturer, however, this is at variance with the fixture manufacturer chart.	This will be completed as the drawings develop.	OPEN	To be verified as design progresses	GGD: This will be completed as the drawings develop.	Schedule data not complete.	
D-81	JAH	E002	The drawing indicates lighting fixture schedule notes. However, they appear to be a mixed set - some Notes are applicable for ALL fixtures yet some are only applicable to just a few fixtures. Please clarify general from specific notes or ADD notes that apply to all utilized fixtures in the appropriate fixture schedule column.	This will be completed as the drawings develop.	OPEN	To be verified as design progresses	GGD: This will be completed as the drawings develop.	Schedule notes still unclear as to what notes apply.	
D-82	JAH	E002	Drawing title & contents focus on lighting and lighting fixtures. It is recommended that the ELECTRICAL GENERAL NOTES be moved to a separate drawing.	Ok	OPEN	Comment still OPEN.	GGD: we will move the electrical general notes to the symbol list	Electrical general notes still included with lighting schedules and notes.	
D-83	JAH	E003-1	Add circuit info for the lights as design is finalized	Ok	CLOSED	To be verified as design progresses	GGD: this will be completed as the drawings develop		
D-84	JAH	E003-2	Add circuit info for the lights as design is finalized	Ok	CLOSED	To be verified as design progresses	GGD: this will be completed as the drawings develop		
D-85	JAH	E002-E005 (typ)	Suggest removing north arrow from non-plan drawings	Will remove.	CLOSED				
D-86	JAH	E101A (typical for all power and lighting plan drawings)	Instead of just showing a north arrow, it is suggested to show a keyplan for these drawings (would apply to mechanical and plumbing drawings, as well).	Ok	CLOSED				
D-87	JAH	E101A (typical for all power and lighting plan drawings)	Add circuit info for all equipment/lights as design progresses.	Ok	CLOSED	To be verified as design progresses	GGD: this will be completed as the drawings develop		
D-88	JAH	E201A (typical for all power plan drawings)	Identify all components	Ok	CLOSED				
D-89	JAH	E204ABCD	Note 1 indicates a lightning protection system is shown but drawing does not provide this. Review and reconcile.	We will revise to what will be a lightning preventor system.	OPEN	Please clarify what is provided for a Lightning Preventor System - UL master label only refers to Ltng Protection sys.	GGD: Lighting preventor system manufacturer provides upon completion of installation and required inspection and tests that the system meets HPB-21, Levels 1&2 a certificate of Guarantee catastrophe umbrella policy that guarantees the preventor lighting protection system with an insurance policy of \$10,000,000.00. The guarantee is limited to the structural building and also excludes surge transient protection for services.	Reconcile "Lightning Preventor" and "Lightning Protection" nomenclature as required.	
D-90	JAH	E300	Suggest indicating code/manufacturer clearance for electrical equipment on drawing.	Will add to the drawings.	OPEN	To be verified as design progresses	GGD: we will add to the drawings.	Several clearances not indicated.	
D-91	JAH	E301	ATS-OC connection to panel EHP3C is not indicated at ATS end. Please add info.	Will correct.	CLOSED	Comment still OPEN.	GGD: EPH3C is fed from EHP1A		
D-92	JAH	E301	Load Bank not indicated at generator. Please add info.	Ok	CLOSED	Comment still OPEN.	GGD: Generator is natural gas therefore no load bank will be provided.		
D-93	JAH	E301	MSB connections to panels LP3C, MHP3C, LP3B and at transformers for panels MP3B and MP3C are not indicated at MSB end. Please add info.	Ok	CLOSED	Comment still OPEN.	GGD: LP3C is fed from 4DP1C, MHP3C is fed from 4DP1C, LP3B is fed from 4DP1B, MP3B and MP3C are fed from 120/208V distribution panels.		
D-94	JAH	E301	There is an emergency LS panel installed on floors 1 and 2 - suggest adding a similar panel at floor 2	Will review to see if this is needed.	CLOSED	To be verified as design progresses	GGD: not needed.		
D-95	JAH	E301 and E302	Panel schedule lists panel 4DP1B - Riser does not. Add panel to riser or remove from schedule? Please reconcile.	Will correct.	CLOSED				
D-96	JAH	E301 and E302	Verify Main switchboard ID - MSB or MSB-1 ?	MSB, this will be corrected.	CLOSED	Comment still OPEN.	GGD: MSB1A		
D-97	JAH	E302 +	Need to add several more panel schedules to detail all the panels shown on riser (add add'l drawings, as required).	Will be added as the drawings progress.	OPEN	To be verified as design progresses	GGD: this will be completed as the drawings develop	Incomplete.	
D-98	JAH	E302+	Complete panel schedules with circuit numbers, AIC rating, and MLO/MCB indication (add add'l drawings, as required).	Will be completed as the drawings progress.	OPEN	To be verified as design progresses	GGD: this will be completed as the drawings develop	Incomplete.	
D-99	JAH	E304	Det. 12: Please verify is AHJ requires generator to have local EPO	This is a code requirement, we will review with AHJ.	CLOSED	To be verified as design progresses	GGD: this is a code requirement		
D-100	JAH	E304	Det. 12: Provide connection detail to load bank at generator	Will add to the drawings.	CLOSED	No change for 60%CD set.	GGD: no load bank		
D-101	JAH	E305	Suggest Automated Lighting Control one-line be presented on a separate drawing for clarity and ease of review	Ok	CLOSED	To be verified as design progresses	GGD: done it is on E306		
D-102	JAH	E400	Suggest Smoke Seq of OPs and fire alarm matrix be moved to a separate drawing for clarity and ease of review	Ok	OPEN	To be verified as design progresses	GGD: suggestion considered.		
D-103	JAH	E401A (typical for all FA plan drawings)	Instead of just showing a north arrow, it is suggested to show a keyplan for these drawings (would apply to mechanical and plumbing drawings, as well).	Ok	CLOSED				

### **2.1.3 MSBA CD-60% Review and District Response**

The OPM has reviewed the District's response to the MSBA 60% Construction Documents Comments and confirms that the comments have been addressed with the 90% Construction Documents submission.

The District's response to the MSBA 60% Construction Documents Comments is appended to the end of this section.



City of Framingham  
Fuller Middle School  
**60% CD**  
**MSBA Review Comment Responses**  
**9/13/19**

**APPENDIX 6B**  
**MODULE 6 – 60% CONSTRUCTION DOCUMENTS REVIEW COMMENTS**

**District:** City of Framingham  
**School:** Fuller Middle School  
**Owner’s Project Manager:** Symmes Maini Mckee Associates  
**Designer Firm:** Jonathan Levi Architects  
**Submittal Received Date:** August 9, 2019  
**Review Date:** August 13-29, 2019  
**Reviewed by:** Gienapp Architects, K. Brown, K. Sullivan, R. Hudson

---

**MSBA REVIEW COMMENTS**

The following comments<sup>1</sup> on the 60% construction documents submittal are issued pursuant to a review of the project submittal document for the new construction of the proposed project and presented as a 60% construction documents submission in accordance with the MSBA Module 6 Guidelines.

**6B.1 Summary Comments**

- Basic Project Information:
  - *630 students*
  - *137,100 GSF*
  - *New construction*
  - *Construction Manager at Risk: Consigli Construction*
- Comments here:

---

<sup>1</sup> The written comments provided by the MSBA are solely for purposes of determining whether the submittal documents, analysis process, proposed planning concept and any other design documents submitted for MSBA review appear consistent with the MSBA’s guidelines and requirements, and are not for the purpose of determining whether the proposed design and its process may meet any legal requirements imposed by federal, state or local law, including, but not limited to, zoning ordinances and by-laws, environmental regulations, building codes, sanitary codes, safety codes and public procurement laws or for the purpose of determining whether the proposed design and process meet any applicable professional standard of care or any other standard of care. Project designers are obligated to implement detailed planning and technical review procedures to effect coordination of design criteria, buildability, and technical adequacy of project concepts. Each city, town and regional school district shall be solely responsible for ensuring that its project development concepts comply with all applicable provisions of federal, state, and local law. The MSBA recommends that each city, town and regional school district have its legal counsel review its development process and subsequent bid documents to ensure that it is in compliance with all provisions of federal, state and local law, prior to bidding. The MSBA shall not be responsible for any legal fees or costs of any kind that may be incurred by a city, town or regional school district in relation to MSBA requirements or the preparation and review of the project’s planning process or plans and specifications.

- *The Total Project Budget per the PFA is \$98,276,878, and the information provided confirms it is still on budget.*
- *The construction cost estimates are \$77,752,185 (CMR's estimate by Consigli Construction Co.), \$77,544,171 (Designer's estimate by A.M. Fogarty) and \$77,247,346 (OPM's estimate by Miyakoda Consulting).*
- *The construction budget per the PFA is \$77,935,429, and the information provided confirms that the reconciled construction cost of \$77,752,185 is still within budget.*
- *While some items of work (i.e. joints in the floor tile) are well beyond 60% CD development, other core building issues (i.e. wall sections, details) appear to be behind. With the response to these comments, indicate if this is intentional, and if so, provide an explanation for why.*

Response: The items JLA has developed beyond 60% CD development typically fall into 2 categories: Those for which we have submitted early 100% construction packages (i.e. sitework, structure and concrete) and those in which the District has a particular interest in regard to appearance and/or maintenance. It is JLA's intent to have other core building issues to be at not less than 60% CD level, and believe this is reflected in the documents. JLA's approach to notating wall sections and details is to refer to typical wall and window types so as to not duplicate notes and dimensions which may be modified over time. As a result, for example, many of the 76 wall sections included have more information than may appear upon initial inspection.

**6B.2 OPM Deliverables:** *Unless specifically stated otherwise, the OPM deliverables are included in the submission with no response from MSBA required.*

#### **6B.2.1 Submittal Review & Coordination**

- Review designer submissions; make recommendations to Owner. Address each of the following items individually, and describe how each was evaluated.
  - *Approve submission.*
- Coordinate design; include written recommendations to the Owner.
  - Technical accuracy, coordination & clarity.
  - Efficiency & cost effectiveness.
  - Operability.
  - Constructability.
  - Phasing.
  - Bid-ability.
  - Site access during construction.
- Coordinate the commissioning consultant's review.
  - Include Cx review & District response.
  - Incorporate Cx recommendations.
- Coordinate the District response to MSBA comments of previous submittal.
  - Include MSBA review & District response.

- Comments addressed / comment resolution outstanding.

**6B.2.2 Project Schedule:** All schedules should be presented in calendar days.

Update project schedule: As a minimum, the schedule update should provide the same level of detail as was included in Exhibit C of the Project Funding Agreement, expanded and updated to include milestones for Design Development, Bidding, Construction, and Closeout. The updated schedule should include proposed critical path and construction milestone information. In addition to the construction milestones, the schedule must also include the following information as listed in MSBA Module 7, Schedule Activities:

- Punch list start and end dates.
- Date of Project Registration with the US Green Building Council ("USGBC") or Collaboration for High Performance Schools ("CHPS").
- Provisional/Design package submittal date to USGBC or CHPS.
- Submittal date of 50% DCAMM Notification and 100% DCAMM Notification.
- General Contractor/Construction Manager request for final payment.
- Commissioning Consultant inspection (substantial completion plus approximately 10 months).
- Submittal date of Final Commissioning Report to MSBA.
- Submittal date of Final Construction package including but not limited to Final Commissioning Report to USGBC or CHPS.
- Anticipated issuance date of final Green School Program Certification letter from USGBC or CHPS.
- Submittal date to MSBA of Commissioning Certificate of Completion.
- Submittal date to MSBA of final reimbursement request.
- Indicate submission dates for the following approvals. In addition, provide dates for any other state or federal approval not listed below (the following list is not a comprehensive itemization of required state approvals; other requirements may apply, and some of the items listed below may not be applicable to this project). Indicate "Not Applicable" where appropriate: *The items listed below are not addressed or included in main project schedule, but they are listed in a separate sheet. These items should be added to the main project schedule for clarity (provide a revised project schedule in the response to this review).*

Response: Please see updated project schedule attached. (Attachment 6B.2.2.1)

- DESE - Special Education approval by Department of Elementary and Secondary Education.
- MHC – Project Notification Form and approvals by MA Historical Commission.
- OIG - Construction Manager at Risk approval by the Office of Inspector General.
- Executive Office of Energy and Environmental Affairs / EEA:
  - MEPA - MA Environmental Policy Act by Energy & Environmental Affairs:

- ENF - Environmental Notification Form.
- EIR - Environmental Impact Report.
- Article 97 Land Disposition Policy approval by Energy & Environmental Affairs.
- MA DEP - Massachusetts Department of Environmental Protection.
- MA DOT - Massachusetts Department of Transportation. *The submission indicates this as not applicable.*
- MA DPH - Massachusetts Department of Public Health. *The submission indicates this as not applicable.*
- EPA –NPDES National Pollutant Discharge Elimination System Notice of Intent approval by the US Environmental Protection Agency.
- MAAB - Accessibility variances by MA Architectural Access Board. *The submission indicates this as not applicable.*
- Indicate all required state reviews or permits on the milestone schedule including actual or planned dates of approval which are required in order to maintain the planned bidding and construction schedule and milestones indicated therein. For required state reviews or permit approvals which have not been obtained on schedule, provide a separate (sub network) schedule depicting recovery actions to obtain required approvals in order to maintain the bidding and construction schedule.
- A letter on District letterhead confirming that the Project has undergone review and obtained all necessary state reviews and approvals by any departments or agencies of the Commonwealth required by law to review the Project, including but not limited to the approvals listed above. Attach such letter of documentation evidencing such state reviews and approvals: *The submission does not contain a letter from the School District confirming the Project's status overall. Confirm this will be provided in the next submission.*

Response: Please see letter from District attached. (Attachment 6B.2.2.2)

- Identify any state reviews or permits for which approval has not been obtained as of the 60% Construction Documents submission date, and include in the District letter a status update including actions taken to date and actions planned to obtain the required approval(s) in order to comply with Project Funding Agreement (the "PFA") Section 4.12. and maintain the projected schedule milestones listed in OPM Deliverables.
- Section 4.12 of the PFA, executed between the District and the MSBA, requires that each project successfully undergo review and obtain all necessary approvals "prior to the solicitation of construction bids, by any departments or agencies of the Commonwealth required by law to review such projects..." As part of the response to these 60% CD submission review comments, MSBA requires documentation



that the District is in compliance with this requirement of the PFA.

- The schedule is to be updated and submitted to MSBA as often as is required to reflect any changes, including any changes to milestone dates, but must be submitted with each design submittal (DD, 60% CD, 90% CD).
- Indicate the date for submission to MSBA of the 60% and proposed dates for 90% Construction Documents submittals. The schedule is to incorporate 21 calendar day required duration for MSBA review of each submission, and a minimum of 14 calendar days for project team incorporation of MSBA review comments as well as all others into the project documents prior to the due date of the next submission or finalizing project documents for bidding. 35 calendar days for each submission is the minimum acceptable duration; if the project team believes additional time is required for any or all of the submissions the durations for these activities are to be increased accordingly.

### **6B.2.3 Scope and Budget**

- Update project scope and budget:
  - Reconciled construction cost estimate including Designer/OPM comparison chart:
    - Prepare independent construction cost estimates pursuant to Section 8.1.2.2 of the Contract for Project Management Services, with escalation to the mid-point of construction, for comparison with the Designer's cost estimate, based upon design development progress documents.
  - CMR (if applicable):
    - If Owner has not yet contracted with a Construction Manager (CM), the OPM must develop a construction cost estimate for comparison with the Designer's cost estimate.
    - If the Owner has given the CM a Notice to Proceed, the OPM must review cost estimates provided by the Designer and CM and provide a detailed line by line reconciliation of the Designer's and CM's construction cost estimates.
  - Updated project budget in the total project budget format, based on the reconciled construction cost estimate. If the reconciled estimate is not used for the updated project budget, provide an explanation.
  - Value Engineering recommendations.
    - For any Value Engineering recommendations which have been accepted, provide a copy of the Committee vote.

**6B.3 Designer Deliverables:** *Unless specifically stated otherwise, the Designer deliverables are included in the submission with no response from MSBA required.*

### **6B.3.1 General Requirements**

- Submit updated work plan.
- Updated and expanded Basis of Design narrative description for all disciplines.
- Updated building code analysis.
- Provide a list identifying all proposed proprietary items (if any) with an affidavit which shall indicate that an elected body of the district (school committee, city or town council, or selectmen, -but not ad-hoc building committee) has been presented with proposals for proprietary requirements approval action, has had an opportunity to investigate, or to require staff or consultant investigation upon each item so proposed, and has majority voted in an open public session that it is in the public interest to do so. Provide MSBA with a certified copy of the vote of the elected body. *The submission provides a list and the minutes of the Town Meeting wherein the items were approved; however, it does not appear to be an official certified copy of the vote. This should be reviewed and provided with the next submission.*

Response: Agreed. To be provided in the next submission

- Updated interior color theory statement describing proposed paint and material selections and colors for typical and special spaces, why they have been selected and how these selections relate to exterior materials and colors. Confirm that color and material selections have been presented to and approved by the District. *Included, the range of color choices and materials have been approved by the School Building Committee. However, the finalization of color values by the Committee is set to be concluded during construction. Confirm that any future color and/or materials selection will not affect the materials and colors included in the cost estimates.*

Response: Confirmed

- Updated structural narrative including methods of lateral bracing and how requirements of earthquake code will be met.
- Updated structural calculations and required floor loads.
- Independent structural design review in compliance with the current edition of The Massachusetts State Building Code (an MSBA requirement for all projects with new construction over 10,000 sf). MSBA requires submission of a structural engineering peer review as part of the Final (100%) Construction Documents submission, to include documentation of resolution of any issues identified by the Peer Reviewer. Actions are to be advanced well prior to the 90% CD submission to engage the peer reviewer, and that scheduling be arranged to allow final structural design drawings and calculations to be submitted to the peer reviewer at the time of completion of the 90% Construction Documents submittal, in order to incorporate comments and response action reporting in the final construction documents and avoid delays. Confirm this process has been initiated.
- Updated energy calculations. *Not included, please include in next submission.*

Response: Agreed. To be provided in the next submission

- Updated Life Cycle cost analysis for energy and water consuming devices. *The Life Cycle Cost Analysis is included for water consuming devices, but not for energy consuming devices. Please include in next submission.*

Response: Agreed. To be provided in the next submission.

- Updated heat gain and loss calculations for Heating, Ventilating and Air Conditioning systems. *The submission indicates these calculations are included with the Basis-of-Design Narrative; however, they do not appear to be included. This should be reviewed and provided in the next submission.*

Response: Agreed. To be provided in the next submission.

- Updated calculations showing total electrical load. *Calculations are included for generator sizing, but it does not appear to be complete. For example, it contains line items for life safety lighting and shelter lighting, but not other lighting. Confirm this will be reviewed and complete updated calculations provided in the next submission.*

Response: Please see attached. (Attachment 6B.3.1)

- Updated security and visual access requirements:
  - Confirmation that the persons responsible for implementation of the District's emergency procedures, and responding emergency medical, fire protection, and police agency representatives have been consulted in the planning process and any associated requirements have been included in the project. *No reference is made to emergency medical responders being consulted. Please clarify in next submission.*

Response: To be clarified in the next submission.

- Identification of any other security related items particular to the District and/or the proposed project.
- Verification that the following safety and security related issues have been reviewed and are in accordance with the District's procedures as noted above:
  - Main entrance design – describe District protocol for visitor entry and check-in related to the current design for visitors to remain in the vestibule versus a side sub-vestibule.
  - Classroom lockset hardware - confirm hardware functions are compatible with the District's protocols related to lockdown.
  - Classroom / Instructional spaces visibility - confirm that the inclusion of sidelights at entrance locations is compatible with the District's current standards related to visibility from corridors and whether any related vision control option measures are to be incorporated.
  - Alternative entry locations - confirm project includes site and building signage, as may be required by District's emergency

procedures, to identify locations where first responders may more directly reach a person needing medical attention; Knox Boxes; and provisions for building plans to be delivered to local fire and response agencies.

- Updated quality Control documents demonstrating:
  - Ceiling clearances.
  - Mechanical room and shaft sizes.
  - Coordinate specifications and drawings.
  - Filed sub-bid work.
  - Scheduling.
  - Equipment and power.
  - Existing and new construction.
  - Phasing.

**6B.3.2 Space Summary**

- Updated space summary and signed certification that reflects the current design. *Based on the space summary provided, the MSBA notes the following:*

<u>Spaces</u>	<u>PFA Space Summary</u>	<u>DD Space Summary</u>	<u>60% CD Space Summary</u>	<u>90% CD Space Summary</u>	<u>Difference to PFA</u>	<u>Comments</u>
Core Academic Spaces	36,000	35,600	35,530		(470)	This category has decreased by 70 nsf since the last submittal.
Special Education	9,150	9,075	9,150		-	This category has increased by 75 nsf since the last submittal and is now in compliance with the original DESE approval dated September 27, 2018.
Art and Music	3,675	3,640	3,640		(35)	This category remains unchanged since the last submittal.
Vocations & Technology	3,170	3,185	3,150		(20)	This category has decreased by 35 nsf since the last submittal.
Health and Physical Education	9,985	9,795	9,765		(220)	This category has decreased by 30 nsf since the last submittal.
Media Center	6,280	6,250	6,250		(30)	This category remains unchanged since the last submittal.

Dining and Food Service	8,960	8,690	8,840		(120)	This category has increased by 150 nsf since the last submittal.
Medical	610	620	620		10	This category remains unchanged since the last submittal.
Administration and Guidance	5,250	5,245	5,235		(15)	This category has decreased by 10 nsf since the last submittal.
Custodial and Maintenance	2,140	2,630	2,555		415	This category has decreased by 75 nsf since the last submittal.
Other	6,700	6,755	6,630		(70)	This category has decreased by 125 nsf since the last submittal.
<b>Total Building Net</b>	<b>91,920</b>	<b>91,485</b>	<b>91,365</b>	-	(555)	<b>This category has decreased by 120 nsf since the last submittal.</b>
<b>Non Programmed</b>						
Other Occupied Rooms						
Unoccupied MEP/FP	1,685	1,415	1,400			
Unoccupied Closets, Supply Rooms & Storage	235	280	350			
Toilet Rooms	3,560	3,325	2,970			
Circulation	34,175	25,970	26,350			
Remaining	5,215	14,285	14,665			
<b>Total Gross</b>	<b>136,790</b>	<b>136,760</b>	<b>137,100</b>		<b>310</b>	
<b>Grossing Factor</b>	<b>1.49</b>	<b>1.49</b>	<b>1.50</b>		<b>0</b>	

- Comparison of the current design with the final educational program, and confirmation that there are no variations. If there are variations, the written summary must address the following:
  - Explanation of deviations within the space summary from the Project Funding Agreement.
  - *The MSBA will continue to monitor these ineligible square footage amounts through Module 6, and to continue to consider them ineligible at PFA Bid. Please note the following:*
    - *The Medical category did not exceed guidelines at the time of PFA (610 nsf); however as outlined above, as part of the 60% submission the category has increased by 10 nsf, therefore 10 nsf would now be considered ineligible for reimbursement.*

Response: So noted.

- *Custodial and Maintenance exceeded guidelines by 35 nsf at PFA, and 35 nsf was considered ineligible. This category has increased by 415 nsf in the 60% submission. This additional area will be considered ineligible.*

Response: So noted.

- *Please note that an additional elevator was added to the building following Schematic Design. As a result, the gross square footage has increased by 310 sf and the grossing factor has increased from 1.49 to 1.50. Any additional gross square footage added to the original PFA approved gross square footage will be deemed ineligible by the MSBA at the PFA Bid Amendment.*

Response: It is understood that any additional gross square footage added to the original PFA approved gross square footage will be deemed ineligible by the MSBA at the PFA Bid Amendment. It should be noted that an additional elevator has not been added following Schematic Design.

- The MSBA considers that deviations include changes in the size of a specific space, the total nsf of a program area (e.g. general classrooms, voc tech, dining etc.), the location of a space, the surrounding adjacencies of a space and or the intended purpose of the room.
- The submittal must clearly call out deviations to location and surrounding adjacencies through the use of redlines or “clouding.”
- The explanation should clearly identify the basis of the change identifying both architectural and/or programmatic reasons.
- If the basis of the change is programmatic, the submittal should include a red-lined version of the educational plan included in the Project Funding Agreement.
- Regarding DESE approved SPED spaces:
  - If the District wishes to submit a change to its DESE approved submittal, it must a) confirm that all changes to SPED spaces are final; b) provide a new submittal utilizing the format of the original submittal requirements and clearly noting any changes through use of clouded floor plans and red-lined narratives and tables; and c) indicate how the project schedule can accommodate a potential resubmittal and approval by DESE. Please provide a separate package for changes to DESE approved SPED spaces. *The submission indicates that the proposed SPED spaces have been brought back into the configuration approved by DESE following the PS&B submittal. As part of the response to these review comments, confirm no further changes to SPED spaces will be considered.*

Response: Confirmed. No further changes to SPED spaces will be considered.

- If the District chooses not to change from the DESE approved submittal it should confirm that the spaces are the same or explain when and how the spaces will be returned to the approved size, configuration and location.
- Regarding DESE approved Public Day Education spaces; *Not applicable.*
- Regarding DESE pre-approved Chapter 74 Program spaces; *Not applicable.*

### **6B.3.3 Project Approvals**

- Describe the status of the following approvals. In addition, provide the status of any other state or federal approval not listed below (the following list is not a comprehensive itemization of required state approvals; other requirements may apply, and some of the items listed below may not be applicable to this project). Provide a copy of the appropriate application forms and/or approval letters where applicable. Indicate “Not Applicable” where appropriate. For each agency approval required for this project, indicate the date when approval was received. All required approvals should have an associated approval date indicated as part of the 90% CD submission and prior to advertising for bids.
  - DESE - Special Education approval by Department of Elementary and Secondary Education.
  - MHC – Project Notification Form and approvals by MA Historical Commission.
  - OIG - Construction Manager at Risk approval by the Office of Inspector General.
  - Executive Office of Energy and Environmental Affairs / EEA:
    - MEPA - MA Environmental Policy Act by Energy & Environmental Affairs:
      - ENF - Environmental Notification Form.
      - EIR - Environmental Impact Report.
    - Article 97 Land Disposition Policy approval by Energy & Environmental Affairs.
  - MA DEP - Massachusetts Department of Environmental Protection. *The submission indicates that approval is currently pending. In the response to this review, indicate the date when approval is anticipated. As noted above, all required approvals should have an associated approval date indicated as part of the 90% CD submission and prior to advertising for bids. Provide a status update including actions taken to date and actions planned to obtain the required state reviews and permit approval(s) in order to comply with PFA Section 4.12 and maintain the projected schedule milestones listed in OPM Deliverables.*

DEP-related work is limited to reportable conditions associated with the precharacterization of soil to be removed from the site (as part of the site enabling package currently in construction). Initial release notification was filed with the DEP and a Release Abatement Measure (RAM) Plan was also filed, as required, with DEP prior to commencement of remedial excavation as part ongoing work. No other DEP approvals are currently required to perform or complete this work. If additional reportable soil conditions are discovered during performance of the work, appropriate DEP notifications will be made, but in no case is anticipated to adversely affect the overall schedule. Upon completion of the excavation and assessment work, a Permanent Solution Statement will be filed with the DEP closing out the release condition.

- MA DOT - Massachusetts Department of Transportation. *The submission indicates this as not applicable.*
- MA DPH - Massachusetts Department of Public Health. *The submission indicates this as not applicable.*
- EPA –NPDES National Pollutant Discharge Elimination System Notice of Intent approval by the US Environmental Protection Agency.
- MAAB - Accessibility variances by MA Architectural Access Board. *The submission indicates this as not applicable.*
- Confirmation that the Project has undergone review and obtained all necessary approvals by any departments or agencies of the Commonwealth required by law to review the Project, including but not limited to the approvals listed above. Attach such letter of documentation evidencing such reviews and approvals. In accordance with Section 4.12 of the Project Funding Agreement (the "PFA"), the District must obtain such reviews or approvals prior to the solicitation of construction bids.
- For any required state reviews or permits for which approval has not been obtained as of the 60% Construction Documents submission date, provide a status update including actions taken to date and actions planned to obtain the required state reviews and permit approval(s) in order to comply with PFA Section 4.12 and maintain the projected schedule milestones listed in OPM Deliverables.
- List and target dates for all local zoning approvals, testing and permits.
- Provide a certification that all applicable utility officials have been contacted by the designer regarding each basic design, and utility connections.

#### **6B.3.4 Cost Estimate**

- Provide a construction cost estimate based on the 60% Construction Documents, including cost estimates for general conditions, overhead and profit, insurance, bonds, and all other items; and allowances expressed as percentage rates for construction contingencies and escalation to the mid-point of the construction period; and other mutually agreed upon contingencies. Prepare the construction cost estimate in the CSI MasterSpec format to Level 3 and M.G.L. c.149, §44F (filed sub-bid) format including a



single line outline specification description for each item with the detailed unit rate or item cost buildup provided as a backup in each case.

- The date of the estimate should be no earlier than the date of 60% Construction Documents.
- Provide a summary sheet including the following:
  - Date that the estimate was prepared (value date).
  - Anticipated bid date. *Not included and should be included in the next submission.*

Response: Acknowledged and agreed. To be provided in the next submission.

- Project and contract number. *The project name is included in the summary, but the contract number is not. This should be included in the next submission.*

Response: Acknowledged and agreed. To be provided in the next submission.

- Title and location of the project.
- Name of the Designer.
- Name of the Estimator.
- Site cost (including all utilities).
- Building cost (including fixed equipment).
- Estimated construction cost of each Phase of the work, totaled. *Not included and should be included in the next submission.*

Response: Acknowledged and agreed. To be provided in the next submission.

- Costs of Item 1 and Item 2 work, as distinguished in the General Contractor's bid forms, individually totaled. *Not included and should be included in the next submission.*

Response: Acknowledged and agreed. To be provided in the next submission.

### **6B.3.5 Drawings** (developed to 60% CD progress level)

- Cover sheet showing a list of all drawings, symbols, abbreviations, notes, locations map (the project title should be visible when the drawings are rolled). *Neither the drawing list, symbols, nor abbreviations are included on the cover sheet; however, it appears this information is included elsewhere in the set. Please confirm as part of the response to these review comments.*

Response: Confirmed. This information is included elsewhere in the set and noted in the drawing list directly after the cover page.

- Site drawings showing the following: *The submission did not include site drawings, which may be part of an early bid package. Therefore, compliance for the following items could not be confirmed. Consider providing these in the next submission for clarity.*

Response: Agreed. Site drawings from the early bid package currently under construction will be provided for reference in the next submission.

- Layout and location of all proposed work with details.
- Existing and proposed contours including floor elevations at all entrances/exits showing drainage away from the building.
- Bench marks and boring locations.
- Landscaping and planting.
- All utility service lines, systems and structures for electricity, gas, oil, water, steam, telephone, CATV, fire alarm, sanitary and storm drainage.
- Contract limit line and storage area for construction materials.
- Site survey which includes, but is not limited to, all existing foundations, obstructions and other physical characteristics of the site.
- Demolition drawings and temporary work required. *There are no demolition drawings included in the submission. This was noted in the previous review, and the District indicated they would be included. This should be reviewed and as part of the response to these review comments confirm this will be provided in the next submission.*

Response: Agreed. Drawings of the existing building and site demolition drawings from the early bid package currently under construction will be provided for reference in the next submission.

- Architectural drawings showing the following:
  - Floor plans of each floor, with dimensions, column locations, floor elevations, door and window designations, partition types, built in furniture and equipment, keyed to other architectural drawings and coordinated with exterior grade elevations at all interior/exterior transitions. *The floor elevations are not included. Please include them in the next submission. Window designations are not included on the floor plan, but appear to be included on the elevations; confirm as part of the response to these review comments.*

Response: Agreed. Floor elevations will be included in the next submission. Window designations are included in the elevations.

- Large scale floor plans where required.
- Roof plans including equipment.
- Key plans / overall plans where required.
- Building Sections updated and coordinated with plans and elevations.
- Building elevations. All building elevations, including hidden elevations, fully developed, showing context and relation to exterior sloping grade around the building.
- Wall sections indicating dimensions, flashing, anchorage, reinforcing, coursing, cladding, and all other conditions at wall, roof, foundation, interior floors.
- Exterior details, for roofing, flashing and other details showing all major conditions.

- Door, window, entrance, curtain wall and storefront, schedules, and details.
- Vertical circulation plans, sections and details including ramps, stairs, lifts and elevators.
- Guardrails and handrails including details.
- Interior elevations of all significant and typical spaces.
- Interior details including casework, paneling surfacing and acoustical treatment.
- Reflected ceiling plans coordinated with fire protection, mechanical and electrical drawings.
- Ceiling details.
- Schedules (clearly define new or existing):
  - Doors.
  - Equipment, e.g. for services.
  - Partitions.
  - Finishes.
- Structural drawings showing the following: *Structural drawings are not included in the submission, and based on the schedule, may have been included in an early bid package. Therefore, compliance with the following could not be confirmed. Consider providing these drawings in the next submission for clarity.*

Response: Agreed. Structural drawings from the early bid package currently in the bidding process will be provided for reference in the next submission.

- Legend and/or graphical symbols on the first sheet of the structural drawings.
- Foundation plans with bottom grades showing layout of all footings, walls, slabs on grade including reinforcing, grade beams, and columns; include design soil bearing pressures and live loads for each area.
- Floor and roof plans of structural systems including framing, grades of finished floors and depressed areas, with locations and dimensions for all openings, coordinated with the architectural drawings.
- Complete foundation wall elevation and typical sections, with reinforcing indicating location, dimensions and grades for all footings, steps and wall openings.
- Complete details and section with dimensions for all construction including expansion and construction joints, reinforcing and other embedded items. Coordinate construction and expansion joint details with specified materials including caulking and sealant.
- Schedules (with dimensions) for all lintels, beams, joists, and columns. Coordinate dimensions of all elements listed in the schedules with dimensions depicted on the plans.
- Structural supports required for mechanical equipment.
- General notes including the following information: class and 28-day strength of concrete for each portion, structural steel and concrete

reinforcing design stresses for each type of structural member, concrete cover for each type of structural member, shrinkage and temperature steel requirements, reinforcing laps for main reinforcing and temperature steel; bend point, cutoff, and hook locations for all members, minimum beam and lintel bearing.

- MSBA requires submission of a structural engineering peer review as part of the Final (100%) Construction Documents submission, to include documentation of resolution of any issues identified by the Peer Reviewer. Actions are to be advanced well prior to the 90% CD submission to engage the peer reviewer, and that scheduling be arranged to allow final structural design drawings and calculations to be submitted to the peer reviewer at the time of completion of the 90% Construction Documents submittal, in order to incorporate comments and response action reporting in the final construction documents and avoid delays. *As part of the response to these review comments, confirm compliance with this requirement.*
- Fire protection drawings showing the following:
  - Legend and/or graphical symbols on the first sheet of the fire protection drawings.
  - Standpipe systems, sprinkler systems, suppression systems, fire pump where required, accessories, and piping.
  - All piping, equipment, fixtures, valves and devices. *Most of the piping is not included in the Fire Protection plans. Confirm that all piping will be included in the next submission.*

Response: Agreed. To be provided in the next submission.

- Design criteria shall be provided on the drawings in accordance with NFPA requirements.
- Plumbing drawings showing the following:
  - Legend and/or graphical symbols on the first sheet of the plumbing drawings.
  - All work done by the Plumbing Subcontractor, which includes all water, gas, air, vacuum, medical gases, sanitary and storm wastes, and accessories.
  - Trapping and venting of all plumbing fixtures including floor drains. Provide location dimensions for floor drains in coordination with the structural plans.
  - Water and gas supply sources, storm and sanitary discharge mains.
  - All piping sizes shall be indicated on drawings and riser diagrams. Indicate all directions of flow and pitch on piping.
  - All accessories, valves, fixtures including all drinking fountains and grease traps for kitchen waste.
  - All piping and connections required for other trades (e.g., kitchen equipment, HVAC make-up water, etc.).
  - Acid waste (where required), vents and neutralization systems for laboratories.

- Plumbing riser diagrams.
- Domestic water booster pumps, boiler feed water, meter location, hose bibs.
- Domestic hot water: storage tanks, piping material, hanger details.
- Backflow preventers, and cleanouts.
- Heating, Ventilating and Air Conditioning Drawings showing the following:
  - Legend and/or graphical symbols on the first sheet of the mechanical drawings. *The legend is not included on the first sheet of the mechanical drawings; however, they are included on a later sheet. Consider including them on the first sheet for clarity.*

Response: Agreed. To be considered for the next submission.

- Large scale plans of all mechanical & electrical spaces showing equipment to scale. *The large-scale plan of the electrical room is not included. Confirm it will be included in the next submission.*

Response: Agreed. To be provided in the next submission.

- All piping and ductwork systems shall be located and sized. All ductwork shall be shown double line and drawn to scale.
- All systems shall be sized at all reductions and riser diagrams of piping and duct systems shall be indicated. *The riser diagram for the duct system is not included. Confirm it will be included in the next submission.*

Response: Agreed. To be provided in the next submission.

- All directions of flow and pitch on piping, and direction of flow and volumes for duct systems shall be indicated.
- All equipment shall have sufficient servicing and/or replacement space indicated on drawings. *Service and replacement spaces are not indicated in the plans. Please include them in the next submission.*

Response: Agreed. To be provided in the next submission.

- All equipment, accessories, valves and dampers identified as to type and size.
- Cooling system pumps, chillers, cooling towers, air handling units, ductwork system and dampers, fan details, temperature control system, air and hydronic balancing equipment, and schedules shall be indicated.
- Cooling tower (where required) shall be indicated on the drawings showing site location, elevations and floor plan of equipment layout and typical flow diagram as related to the total HVAC system. *Not applicable.*
- All fire and smoke dampers, access panels and doors. *Access panels are not included. Please include them in the next submission.*

Response: Agreed. To be provided in the next submission.

- Mechanical room designs:

- Vent pipes for safety valves, relief valves, back pressure valves and tanks shall be extended above flat roofs in accordance with all governing authorities.
- In all designs for boiler and refrigeration plants, include a complete floor plan indicating location of all major mechanical equipment and sufficient service space. *The service space for the mechanical equipment is not indicated on the plan. Confirm these spaces will be identified in the next submission.*

Response: Agreed. To be identified in the next submission.

- In designs of new and/or replacement boiler and refrigeration plants, provide a flow diagram detailing steam or hot water distribution systems, return systems, including all existing equipment and their function, as well as any proposed expansions with all necessary instrumentation and controls.
- Electrical Drawings showing the following:
  - Legend and/or graphical symbols on the first sheet of the electrical drawings.
  - General arrangement: Outline layout of each floor.
  - Indicate interface with other systems. Identify any work by general contractor or other trades.
  - Interior lighting system: Light fixture schedules, circuiting location and mounting heights of all fixtures, receptacle and switch outlets, sizes and types of all lamps, conduits, all other accessories and riser diagrams shall be indicated on drawings. Designer shall specify that all electrical lighting fixtures be supported from the building structure, and shall be independent of ducts, pipes, ceilings and their supporting members. Comply with seismic design criteria. *The mounting heights for fixtures and a riser diagram for the lighting are not included. Please include them in the next submission.*

Response: Agreed. To be provided in the next submission.

- Power system: Locations, types and method of control for all motors, heaters, appliances, controllers, starters, branch circuits, feeder conductors and conduits. Indicate riser diagrams. Show details and indicate method of supporting electrical conduit. For larger projects, thermostats and control wiring are normally covered under the HVAC sub-contract, assure coordination.
- Fire Alarm, Data, Communications, CATV/CCTV Systems: Locations and types of all devices, outlets and equipment, service connections, wiring diagrams, all other essential details.
- Services: Location and details of all services, whether overhead or underground, feeder sizes, plans and elevations of switchgear and transformers, metering and service switchboard arrangements, wiring and ground fault diagram and bus ducts.

- General and sub-stations: Location, size, method of connection and protection of all generators, transformers, exciters, motor generators, switch gear, and associated equipment, current characteristics and equipment capacities. Indicate equipment connections by means of one line and/or wiring diagrams and schedule all major items of equipment and all instruments.
- Underground work: The size and locations of manholes and types of cables, number, size, and location of ducts, locations, sizes and types of cable supports, fireproofing, duct line profile, and one-line diagram of connections.
- Pole line work: Location, length, treatment and class of poles, guying, cross arms, insulators, circuiting, transformers, protective and switching devices, lightning arresters, special structures, diagrams, current characteristics and grounding.
- Exterior lighting: Location, size, and type of transformers, luminary, poles, light standards, cables, ducts, and manholes, details of control equipment and connection diagrams.
- Emergency system (where provided) details including transfer switch, type of fuel.
- One-line diagram indicating load KVA, and available short circuit amperes at each transformer, switchboard, distribution panel board, branch circuit panel board, and at major pieces of equipment.
- Riser diagrams for all system.

#### **6B.3.6 Project Manual** (developed to 60% CD progress level)

- The format for the technical specifications shall be CSI Master format (current version) with separate sections for each of class of work required by M.G.L. c. 149 §44F.
- For each item of material or equipment, the specifications shall provide for a minimum of three named brands of material or equipment and the words "or equal" or a description of material or equipment which can be met by a minimum of three manufacturers or producers, and the words "or equal". Proprietary products shall not be specified except as provided by M.G.L. c. 30, § 39M; however, when they are specified, proprietary specifications are subject to the "or equal" provisions of c. 30, § 39M.
- Do not specify that a product or system shall require prequalification for use prior to bidding.
- Include a copy of the geotechnical report, including locations and dates of test boring holes and results of soil investigation, including water levels, allowable solid bearing pressure and bottom grades of footing and slabs.
- List all required filed sub-bids specification sections.
- Each filed sub-bid section shall detail all labor and materials required by the particular sub-trade. *It does not appear that the list of relevant drawings is included in all the filed sub-bid sections. For example, they are missing from*

*Section 07 00 01 and Section 08 00 08. This should be included prior to the next submission.*

Response: Agreed. To be provided in the next submission.

- Staging, scaffolding cutting and patching, refuse collection and disposal, demolition work and cleaning task, allocation policy and proposed language shall be carefully assigned to avoid duplication or omission. *It does not appear this is fully coordinated. For example, Section 26 00 10 Electrical states that all staging and scaffolding over eight feet shall be furnished, installed and maintained by the General Contractor and all staging up to eight feet provided by the non-trade and trade contractor. This language is not coordinated with Section 01 50 00 Temporary Facilities. This should be reviewed and coordinated in the next submission.*

Response: Agreed. To be coordinated in the next submission.

- Describe the extent of the work, the materials and workmanship, and include the work under the proper section. If any portion of the work included in a section of the specifications is to be performed by a trade covered by another section, there shall be clear and distinct cross-referencing between the sections. Merely to state "by others" is not acceptable.
- All "Work by Others" specification references are coordinated.
- Specify work in appropriate Sections according to local trade jurisdiction.
- In sections for which filed sub-bids are required, refrain from using such terms as "the Contractor," the "Heating Contractor," or "the Plumbing Contractor," but where necessary for clarity refer to the "HVAC Subcontractor," the "General Contractor" and so on. *The term "the Contractor" is used throughout the Project Manual. For clarity, this term should be replaced with the term "General Contractor" prior to the next submission.*

Response: Agreed. To be clarified in the next submission.

- Alternates, if approved in writing by the owner, shall be properly described and cross-referenced in the project manual and drawings. *Alternate 1 is defined in the Project Manual; however, it is not clearly shown in the drawings. This should be coordinated and shown on the drawings prior to the next submission.*

Response: Agreed. To be coordinated in the next submission.

- Allowances are prohibited pursuant to M.G.L. c. 149, § 44G(A)
- Unit price items, if permitted or ordered by the owner, shall be properly described in the specifications. *Section 01 22 00 Unit Prices refers to Document 00 54 22 – Bid Attachment Unit Prices Schedule. This schedule is not included in the submission. This should be review and provided in the next submission.*

Response: Agreed. To be provided in the next submission if applicable.



- Do not use general clauses intended to be all-inclusive in lieu of complete descriptions.
- Do not duplicate standard requirements that are contained in the contract form.
- Use consistency throughout. The word "will" shall be used to designate what the owner, authority, owner's project manager, or the designer can be expected to do, and the word "shall" shall be used to designate what is mandatory for the contractor or subcontractors to do. *The words "will" and "shall" are used interchangeably throughout the Project Manual. This should be reviewed and coordinated prior to the next submission.*

Response: Agreed. To be coordinated in the next submission.

- Use the same term throughout for the same subject and the term shall be the same as that used on the drawings. *Many of the section drawings and details are not fully developed and are missing notes, as is typical at 60% CDs; therefore, similar term usage could not be fully confirmed. This should be reviewed and provided in the next submission.*

Response: Agreed. To be coordinated in the next submission.

- Do not use the term "etc." *There are several instances throughout the Project Manual that use the word "etc." This should be reviewed and revised prior to the next submission.*

Response: Agreed. To be revised in the next submission.

- Avoid such terms as "to the satisfaction of the designer", "as directed by the designer", "as approved" and "as required." *"As approved by Architect", "to the satisfaction of the Designer/Architect", "as directed by Architect" and "as required" is used throughout the project manual. This should be reviewed and revised in the next submission.*

Response: Agreed. To be revised in the next submission.

- Avoid the use of symbols.
- Do not give numbers both in words and figures. Numbers less than 10 shall be written in words, 10 and higher numbers shall be written in figures. In expressing dimensions, figures such as 2 in., 16 in., 7 ft., 6 in., shall be used. *Numbers are written in both words and figures. This should be reviewed and revised in the next submission.*

Response: Agreed. To be revised in the next submission.

- Specify materials mined or manufactured in Massachusetts first and the United States of America second whenever possible.

### **6B.3.7 Project Coordination**

- Verify all details are accurately cross-referenced to the correct plan sheet. *Details are not cross referenced to the plans. This should be reviewed and coordinated in the next submission.*

Response: Agreed. To be coordinated in the next submission.

- Verify that the structural, mechanical, or other disciplines, do not conflict with architectural plans or specifications.
- Structural dimensions match architectural drawings. *No structural drawings were included in the set for review; therefore, coordination could not be reviewed. See other note regarding structural drawings in section 6B.3.5 of this review.*

Response: Agreed. Structural drawings from the early bid package currently in the bidding process will be provided for reference in the next submission.

- Column orientation matches architectural drawings. *The columns are not included in the fire protection, plumbing and mechanical plans. Please include them in the next submission.*

Response: Agreed. To be provided in the next submission.

- Column grid lines match architectural drawings. *The columns grid lines are not included in the fire protection, plumbing and mechanical plans. Please include them in the next submission.*

Response: Agreed. To be provided in the next submission.

- Column and bearing wall locations match architectural drawings. *No structural drawings were included in the set for review; therefore, coordination could not be reviewed. See other note regarding structural drawings in section 6B.3.5 of this review.*

Response: Agreed. Structural drawings from the early bid package currently in the bidding process will be provided for reference in the next submission.

- Column locations coordinated with all other disciplines. *The columns are not included in the fire protection, plumbing and mechanical plans. Please include them in the next submission.*

Response: Agreed. To be provided in the next submission.

- Seismic detailing coordinates with architectural drawings. *No structural drawings were included in the set for review; therefore, coordination could not be reviewed. See other note regarding structural drawings in section 6B.3.5 of this review.*

Response: Agreed. Structural drawings from the early bid package currently in the bidding process will be provided for reference in the next submission.

- Beams and columns protruding horizontally and vertically into stairwells, and other interior spaces. *No structural drawings were included in the set*

*for review; therefore, coordination could not be reviewed. See other note regarding structural drawings in section 6B.3.5 of this review.*

Response: Agreed. Structural drawings from the early bid package currently in the bidding process will be provided for reference in the next submission.

- The finish grade elevations coordinated between all disciplines. *The finish floor elevations are not included in the architectural plans and there are no site drawings in the set. Please coordinate in the next submission.*
- Response: Agreed. Finish floor elevations will be included and Site drawings from the early bid package currently in construction will be provided for reference in the next submission.

- Mechanical equipment power requirements and physical locations, including special information as to who mounts, connects, tests, etc.
- Verification of potential spatial conflicts in mechanical equipment.
- Room wall/floor/ceiling construction coordinated with the finish schedule. *There are no partition types included with ceramic tile or backer board. Please coordinate in the next submission.*

Response: Agreed. To be coordinated in the next submission.

- Civil earthwork grading and excavation plans are coordinated with architectural and landscape plans. *The civil plans are not included in the set; therefore, coordination could not be confirmed. Consider providing civil drawings in the next submission.*

Response: Agreed. Site drawings from the early bid package currently in construction will be provided for reference in the next submission.


- All room numbers are coordinated between all disciplines. *The room numbers are missing from the fire protection and plumbing plans, and they are illegible on the mechanical and electrical plans. Please include them in the next submission.*


Response: Agreed. To be provided and clarified in the next submission.

- Equipment plan coordinates with architectural plans.
- All kitchen equipment connected to utility.




City of Framingham  
New Fuller Middle School  
Project Schedule





ID	Task Name	Duration	Start	Finish	2017	2018	2019	2020	2021	2022	2023
118	Interview Shortlisted CM Firms	11 days	2/6/2019	2/6/2019			2/6/2019				
119	Negotiate and Award	0 days	2/6/2019	2/20/2019			2/20/2019				
120	CM Notice to Proceed	0 days	2/20/2019	2/20/2019			2/20/2019				
121	<b>Trade Contractors Prequalification - Package No. 1</b>	<b>36 days</b>	<b>3/18/2019</b>	<b>5/7/2019</b>			3/18/2019				
122	Draft RFO	13 days	3/18/2019	4/3/2019			3/18/2019				
123	Submit to Advertisement to Central Register and Local Newspaper	0 days	3/28/2019	3/28/2019			3/28/2019				
124	Notice in Central Register	0 days	4/3/2019	4/3/2019			4/3/2019				
125	Prepare SOO	11 days	4/3/2019	4/17/2019			4/17/2019				
126	Submit SOQs	0 days	4/17/2019	4/17/2019			4/17/2019				
127	Review SOQs	9 days	4/17/2019	4/29/2019			4/29/2019				
128	Recommend Prequalified Trade Contractors to SBC	0 days	5/6/2019	5/6/2019			5/6/2019				
129	Issue Notification Letters to Prequalified Trade Contractors	0 days	5/7/2019	5/7/2019			5/7/2019				
130	<b>Trade Contractors Prequalification - Package No. 2</b>	<b>69 days</b>	<b>5/1/2019</b>	<b>8/6/2019</b>			5/1/2019				
131	Develop Draft RFOs	41 days	5/1/2019	6/26/2019			5/1/2019				
132	Submit Advertisement to Central Register and Local Newspaper	0 days	6/25/2019	6/25/2019			6/25/2019				
133	Notice in Central Register	0 days	7/3/2019	7/3/2019			7/3/2019				
134	Prepare SOO	10 days	7/3/2019	7/17/2019			7/17/2019				
135	Submit SOQs	0 days	7/17/2019	7/17/2019			7/17/2019				
136	Review SOQs	14 days	7/17/2019	8/5/2019			8/5/2019				
137	Recommend Prequalified Trade Contractors to SBC	0 days	8/6/2019	8/6/2019			8/6/2019				
138	Issue Notification Letters to Prequalified Trade Contractors	0 days	8/6/2019	8/6/2019			8/6/2019				
139	<b>Trade Contractors Prequalification - Package No. 3</b>	<b>55 days</b>	<b>7/1/2019</b>	<b>9/17/2019</b>			7/1/2019				
140	Develop Draft RFOs	21 days	7/1/2019	7/30/2019			7/30/2019				
141	Submit Advertisement to Central Register and Local Newspaper	0 days	7/30/2019	7/30/2019			7/30/2019				
142	Notice in Central Register	0 days	8/7/2019	8/7/2019			8/7/2019				
143	Prepare SOO	11 days	8/7/2019	8/21/2019			8/21/2019				
144	Submit SOQs	0 days	8/21/2019	8/21/2019			8/21/2019				
145	Review SOQs	13 days	8/21/2019	9/9/2019			9/9/2019				
146	Recommend Prequalified Trade Contractors to SBC	0 days	9/16/2019	9/16/2019			9/16/2019				
147	Issue Notification Letters to Prequalified Trade Contractors	0 days	9/17/2019	9/17/2019			9/17/2019				
148	<b>Trade Contractors Prequalification - Package No. 4</b>	<b>60 days</b>	<b>8/20/2019</b>	<b>11/12/2019</b>			8/20/2019				
149	Develop Draft RFOs	15 days	8/20/2019	9/10/2019			9/10/2019				
150	Submit Advertisement to Central Register and Local Newspaper	0 days	9/10/2019	9/10/2019			9/10/2019				
151	Notice in Central Register	0 days	9/18/2019	9/18/2019			9/18/2019				
152	Prepare SOO	11 days	9/18/2019	10/2/2019			10/2/2019				
153	Submit SOQs	0 days	10/2/2019	10/2/2019			10/2/2019				
154	Review SOQs	24 days	10/2/2019	11/4/2019			11/4/2019				
155	Recommend Prequalified Trade Contractors to SBC	0 days	11/11/2019	11/11/2019			11/11/2019				
156	Issue Notification Letters to Prequalified Trade Contractors	0 days	11/12/2019	11/12/2019			11/12/2019				
157	<b>100% Construction Document Package No. 4</b>	<b>46 days</b>	<b>10/29/2019</b>	<b>1/3/2020</b>			10/29/2019				
158	Submit Advertisement to Central Register and Newspaper	0 days	10/29/2019	10/29/2019			10/29/2019				
159	Notice in Central Register	0 days	11/6/2019	11/6/2019			11/6/2019				
160	Trade Contractor Bid Package	15 days	11/15/2019	12/6/2019			12/6/2019				
161	Pre-Bid Meeting	0 days	11/22/2019	11/22/2019			11/22/2019				
162	Trade Contractor Bid Due	0 days	12/6/2019	12/6/2019			12/6/2019				
163	CM Develop GMP	19 days	12/6/2019	1/3/2020			1/3/2020				
164	GMP Approval	0 days	1/3/2020	1/3/2020			1/3/2020				
165	<b>EARLY PACKAGES PROCUREMENT</b>	<b>122 days</b>	<b>5/7/2019</b>	<b>10/28/2019</b>			5/7/2019				
166	<b>Early Site Package No. 1</b>	<b>30 days</b>	<b>5/7/2019</b>	<b>6/17/2019</b>			5/7/2019				
167	Submit Advertisement to Central Register and Newspaper	0 days	5/7/2019	5/7/2019			5/7/2019				
168	Notice in Central Register	0 days	5/15/2019	5/15/2019			5/15/2019				
169	Issue Early Site Package Bid Documents	0 days	5/10/2019	5/10/2019			5/10/2019				
170	PreBid Meeting	0 days	5/20/2019	5/20/2019			5/20/2019				
171	Trade Contractor Bids Due	0 days	5/24/2019	5/24/2019			5/24/2019				
172	Site Contractor Bids Due	0 days	5/31/2019	5/31/2019			5/31/2019				
173	Escoping and Development of GMP Amendment	12 days	5/31/2019	6/17/2019			6/17/2019				
174	Award Early Site Package GMP	0 days	6/17/2019	6/17/2019			6/17/2019				
175	<b>Early Foundation and Structural Package No. 2</b>	<b>33 days</b>	<b>7/30/2019</b>	<b>9/16/2019</b>			7/30/2019				
176	Submit Advertisement to Central Register and Newspaper	0 days	7/30/2019	7/30/2019			7/30/2019				

ID	Task Name	Duration	Start	Finish
177	Notice in Central Register	0 days	8/7/2019	8/7/2019
178	Issue Early Foundation and Structural Package Bid Documents	0 days	8/9/2019	8/9/2019
179	PreBid Meeting	0 days	8/19/2019	8/19/2019
180	Trade Contractor Bids Due	0 days	8/26/2019	8/26/2019
181	Concrete and Steel Contractor Bids Due	0 days	8/30/2019	8/30/2019
182	Decoping and Development of GMP Amendment	10 days	8/30/2019	9/13/2019
183	Award Early Foundation and Structural Package GMP	0 days	9/16/2019	9/16/2019
184	<b>Early Masonry Package No. 3</b>	<b>29 days</b>	<b>9/17/2019</b>	<b>10/26/2019</b>
185	Submit Advertisement to Central Register and Newspaper	0 days	9/17/2019	9/17/2019
186	Notice in Central Register	0 days	9/25/2019	9/25/2019
187	Issue Early Masonry Package Bid Documents	0 days	10/2/2019	10/2/2019
188	PreBid Meeting	0 days	10/9/2019	10/9/2019
189	Trade Contractor Bids Due	0 days	10/23/2019	10/23/2019
190	Award Early Masonry Package GMP	0 days	10/28/2019	10/28/2019
191	<b>CONSTRUCTION</b>	<b>737 days</b>	<b>6/10/2019</b>	<b>4/21/2022</b>
192	Notice to Proceed	0 days	6/18/2019	6/18/2019
193	EPA NPDES Submitted	0 days	6/10/2019	6/10/2019
194	EPA NPDES Approved	0 days	6/24/2019	6/24/2019
195	Site Mobilization	0 days	6/20/2019	6/20/2019
196	MA DEP RAM Plan Submitted	0 days	7/17/2019	7/17/2019
197	<b>Substantial Completion - Phase 1 "Enabling Work"</b>	<b>0 days</b>	<b>8/20/2019</b>	<b>8/20/2019</b>
198	50% DCAMM Evaluation	0 days	8/15/2020	8/15/2020
199	Punch List Start	0 days	4/15/2021	4/15/2021
200	Punch List Complete	0 days	6/15/2021	6/15/2021
201	<b>Substantial Completion - Phase 2 "Building Construction"</b>	<b>0 days</b>	<b>6/15/2021</b>	<b>6/15/2021</b>
202	Final Completion, Closeout and Commissioning	34 days	6/15/2021	7/30/2021
203	FFE/Technology Installation	34 days	6/15/2021	7/30/2021
204	Teacher/Staff Move-In	21 days	8/2/2021	8/30/2021
205	<b>Occupancy</b>	<b>0 days</b>	<b>8/30/2021</b>	<b>8/30/2021</b>
206	Abate and Demolish Existing School	67 days	7/3/2021	10/5/2021
207	Parking Lot and Playfield Construction	55 days	10/4/2021	12/20/2021
208	CM Request for Final Payment	0 days	12/20/2021	12/20/2021
209	<b>Substantial Completion - Phase 3 "Demolition and Site Work"</b>	<b>0 days</b>	<b>12/20/2021</b>	<b>12/20/2021</b>
210	Closeout	46 days	12/20/2021	2/1/2022
211	Final Completion	46 days	12/20/2021	2/1/2022
212	100% DCAMM Evaluation	0 days	2/21/2022	2/21/2022
213	LEED-S Construction Submission	46 days	12/20/2021	2/21/2022
214	MSBA Final Payment Reimbursement Request	0 days	3/1/2022	3/1/2022
215	Commissioning Agent 10-month Inspection	0 days	4/15/2022	4/15/2022
216	Commissioning Agent Final Report Submission to MSBA	0 days	4/15/2022	4/15/2022
217	Commissioning Agent Submission of Certification	0 days	4/15/2022	4/15/2022
218	USGC Issuance of Certification	0 days	4/21/2022	4/21/2022





## 2.2 Project Schedule

The project schedule anticipates submission of the 90% Construction Documents on October 18, 2019. The submission dates incorporate the MSBA review periods for each submission.

The schedule anticipates early packages for sitework, foundations, steel and masonry. The Early Site Work Contract Documents were released for bid on May 10, 2019. The Early Foundation and Steel Contract Documents were released for bid on August 9, 2019. The Early Masonry Package will be released October 18, 2019.

The main package will be released on November 22, 2019 with the GMP expected in January 27, 2020. Substantial Completion of the building is scheduled for June 2021 and occupancy in August 2021. Thereafter, demolition of the existing building and construction of the playfields and parking lots will be completed by December 2021.

The following is the status of project approvals:

- DESE – Special Education approval by Department of Elementary and Secondary Education – Approved September 27, 2018
- MHC – Project Notification Form and approvals by MA Historical Commission – Approved January 2, 2018
- OIG – Construction Manager at Risk approval by the Office of Inspector General – Approved December 21, 2018
- Executive Office of Energy and Environmental Affairs / EEA:
  - MEPA – MA Environmental Policy Act by Energy & Environmental Affairs:
    - ENF – Environmental Notification Form – Not Applicable, an ENF is not required.
    - EIR – Environmental Impact Report – Not Applicable, an EIR is not required.
  - Article 97 Land Disposition Policy approval by Energy & Environmental Affairs – Not Applicable to this project.
- MA DEP – Massachusetts Department of Environmental Protection – Release Abatement Measure submitted July 17, 2019.
- MA DOT – Massachusetts Department of Transportation – Not Applicable
- MA DPH – Massachusetts Department of Public Health – Not Applicable
- EPA – NPDES National Pollutant Discharge Elimination System

Notice of Intent approval by the US Environmental Protection Agency – Submitted by CM on June 10, 2019 and approval received on June 24, 2019.

- MAAB – Accessibility variances by MA Architectural Access Board – Not Applicable as no variances are required.
- Framingham Planning Board – Site Plan Approval received on May 2, 2019.
- Framingham Conservation Commission – NOI approved on July 1, 2019

The Project Schedule is appended to the end of this section.

ID	Task Name	Duration	Start	Finish	2014	2019	2024
1	<b>MSBA PREREQUISITES</b>	496 days	3/13/2015	2/15/2017			
2	Original Statement of Interest (SOI) Submission	0 days	3/13/2015	3/13/2015	◆ 3/13/2015		
3	MSBA Invite into Eligibility	0 days	5/25/2016	5/25/2016		◆ 5/25/2016	
4	Execute Feasibility Study Agreement (FSA)	0 days	2/15/2017	2/15/2017		◆ 2/15/2017	
5	<b>RETAIN OPM</b>	43 days	4/19/2017	6/19/2017		◆ 4/19/2017	
6	Submit OPM Proposals	0 days	4/19/2017	4/19/2017		◆ 4/19/2017	
7	OPM Interview	1 day	5/3/2017	5/3/2017		◆ 5/3/2017	
8	Negotiate OPM Contract	12 days	5/8/2017	5/23/2017		◆ 5/8/2017	
9	Submit Documents to MSBA OPM Panel	0 days	5/10/2017	5/10/2017		◆ 5/10/2017	
10	<b>MSBA OPM Panel Meeting</b>	0 days	6/19/2017	6/19/2017		● 6/19/2017 MSBA OPM Panel Meeting	
11	<b>RETAIN DESIGNER</b>	93 days	5/11/2017	9/20/2017		◆ 5/11/2017	
12	Draft Designer RFS and Submit to MSBA	21 days	5/11/2017	6/8/2017		◆ 6/8/2017	
13	MSBA Approve Draft RFS	11 days	6/8/2017	6/22/2017		◆ 6/22/2017	
14	Submit to Central Register	0 days	6/22/2017	6/22/2017		◆ 6/22/2017	
15	Notice in Central Register	0 days	6/28/2017	6/28/2017		◆ 6/28/2017	
16	Briefing Session	0 days	7/6/2017	7/6/2017		◆ 7/6/2017	
17	Submit Designer Proposals	0 days	7/20/2017	7/20/2017		◆ 7/20/2017	
18	<b>MSBA DSP Proposal Review Meeting</b>	0 days	8/22/2017	8/22/2017		● 8/22/2017 MSBA DSP Proposal Review Meeting	
19	<b>MSBA DSP Interview Meeting</b>	0 days	9/12/2017	9/12/2017		● 9/12/2017 MSBA DSP Interview Meeting	
20	Negotiate Designer Contract	6 days	9/13/2017	9/20/2017		◆ 9/13/2017	
21	<b>FEASIBILITY STUDY (FS)</b>	198 days	9/19/2017	6/27/2018		◆ 9/19/2017	
22	Develop Preliminary Design Program (PDP)	67 days	9/19/2017	12/21/2017		◆ 9/19/2017	
23	Submit PNF to MHC	23 days	11/5/2017	12/6/2017		◆ 11/5/2017	
24	Community Presentations	44 days	10/19/2017	12/20/2017		◆ 10/19/2017	
25	Town Council Presentations	22 days	11/20/2017	12/20/2017		◆ 11/20/2017	
26	School Committee Presentations	22 days	11/20/2017	12/20/2017		◆ 11/20/2017	
27	<b>Submit PDP to MSBA Staff</b>	0 days	12/20/2017	12/20/2017		● 12/20/2017 Submit PDP to MSBA Staff	
28	Develop Preferred Schematic Report (PSR)	99 days	12/20/2017	5/9/2018		◆ 12/20/2017	
29	Receive MHC Clearance	0 days	1/2/2018	1/2/2018		◆ 1/2/2018 Receive MHC Clearance	
30	Community Presentations	78 days	1/22/2018	5/9/2018		◆ 1/22/2018	
31	City Council Presentations	78 days	1/22/2018	5/9/2018		◆ 1/22/2018	
32	School Committee Presentations	78 days	1/22/2018	5/9/2018		◆ 1/22/2018	
33	<b>Submit PSR to MSBA FAS</b>	0 days	5/9/2018	5/9/2018		● 5/9/2018 Submit PSR to MSBA FAS	
34	<b>FAS Presentation</b>	0 days	5/23/2018	5/23/2018		◆ 5/23/2018	
35	<b>MSBA Board Meeting</b>	0 days	6/27/2018	6/27/2018		● 6/27/2018 MSBA Board Meeting	
36	<b>SCHEMATIC DESIGN (SD)</b>	114 days	5/9/2018	10/17/2018		◆ 5/9/2018	
37	Develop Schematic Design	89 days	5/9/2018	9/12/2018		◆ 5/9/2018	
38	Community Presentations	67 days	6/8/2018	9/12/2018		◆ 6/8/2018	
39	City Council Presentations	67 days	6/8/2018	9/12/2018		◆ 6/8/2018	
40	School Committee Presentations	67 days	6/8/2018	9/12/2018		◆ 6/8/2018	
41	Submit Total Project Cost to MSBA	0 days	8/29/2018	8/29/2018		◆ 8/29/2018 Submit Total Project Cost to MSBA	
42	<b>Submit Schematic Design to MSBA</b>	0 days	9/12/2018	9/12/2018		● 9/12/2018 Submit Schematic Design to MSBA	
43	MSBA Review Schematic Design (SD) Submission	16 days	9/12/2018	10/3/2018		◆ 9/12/2018	
44	DESE Review	23 days	9/12/2018	10/12/2018		◆ 9/12/2018	
45	DESE Approval	0 days	9/27/2018	9/27/2018		◆ 9/27/2018	
46	Respond to MSBA Comments	11 days	10/3/2018	10/17/2018		◆ 10/3/2018	



City of Framingham  
New Fuller Middle School  
Project Schedule

ID	Task Name	Duration	Start	Finish	2014	2019	2024
47	<b>PROJECT SCOPE AND BUDGET</b>	75 days	10/2/2018	1/17/2019			
48	Project Scope and Budget Conference	0 days	10/3/2018	10/3/2018		10/3/2018 ♦ Project Scope and Budget Conference	
49	Execute Scope and Budget Agreement	11 days	10/3/2018	10/17/2018			
50	<b>MSBA Board Meeting</b>	0 days	10/31/2018	10/31/2018		10/31/2018 ♦ MSBA Board Meeting	
51	City Council Meeting to Vote Funds for Total Project Budget	18 days	10/2/2018	10/25/2018			
52	Proposition 2 1/2 Ballot Vote	0 days	12/11/2018	12/11/2018		12/11/2018 ♦ Proposition 2 1/2 Ballot Vote	
53	Execute Project Funding Agreement	26 days	12/11/2018	1/17/2019			
54	<b>DESIGN DEVELOPMENT</b>	122 days	12/11/2018	5/31/2019			
55	Develop Design Development Documents to Estimator	82 days	12/12/2018	4/8/2019			
56	LEED-S Registration	11 days	12/11/2018	12/26/2018			
57	Design Development Cost Estimate	15 days	4/8/2019	4/26/2019			
58	Value Engineering	7 days	4/26/2019	5/6/2019			
59	Design Development Submission for OPM and Cx Review	0 days	4/8/2019	4/8/2019		4/8/2019 ♦ Design Development Submission for OPM and Cx Review	
60	OPM and Cx Review	15 days	4/8/2019	4/26/2019			
61	<b>Design Development Submission to MSBA</b>	0 days	5/10/2019	5/10/2019		5/10/2019 ♦ Design Development Submission to MSBA	
62	MSBA Comments	16 days	5/10/2019	5/31/2019			
63	<b>SITE PERMITTING</b>	303 days	5/15/2018	7/19/2019			
64	<b>Framingham Conservation Commission - ANRAD</b>	7 days	12/12/2018	12/20/2018			
65	Separate ANRAD not required; Delineation reviewed by Staff	7 days	12/12/2018	12/20/2018			
66	<b>Framingham Conservation Commission - NOI</b>	155 days	12/12/2018	7/19/2019			
67	Prepare Application Documents	89 days	12/12/2018	4/17/2019			
68	File Application	0 days	4/17/2019	4/17/2019		4/17/2019 ♦ File Application	
69	Hearing No. 1	0 days	5/1/2019	5/1/2019		5/1/2019 ♦ Hearing No. 1	
70	Hearing No. 2	0 days	5/15/2019	5/15/2019		5/15/2019 ♦ Hearing No. 2	
71	Hearing No. 3	0 days	6/5/2019	6/5/2019		6/5/2019 ♦ Hearing No. 3	
72	Hearing No. 4	0 days	6/19/2019	6/19/2019		6/19/2019 ♦ Hearing No. 4	
73	Conservation Commission Issue Order of Conditions	0 days	6/26/2019	6/26/2019		6/26/2019 ♦ Conservation Commission Issue Order of Conditions	
74	Appeal Period	10 days	6/26/2019	7/10/2019			
75	File at Registry	5 days	7/15/2019	7/19/2019			
76	<b>Framingham Planning Board - Limited Site Plan Review - Dover Amend.</b>	118 days	12/12/2018	5/28/2019			
77	Prepare Application Documents	82 days	12/12/2018	4/8/2019			
78	File Application	0 days	4/8/2019	4/8/2019		4/8/2019 ♦ File Application	
79	TRT Meeting	0 days	4/17/2019	4/17/2019		4/17/2019 ♦ TRT Meeting	
80	Hearing No. 1	0 days	4/25/2019	4/25/2019		4/25/2019 ♦ Hearing No. 1	
81	Hearing No. 2	0 days	5/2/2019	5/2/2019		5/2/2019 ♦ Hearing No. 2	
82	Planning Board Issues Site Plan Approval	0 days	5/2/2019	5/2/2019		5/2/2019 ♦ Planning Board Issues Site Plan Approval	
83	Appeal Period	10 days	5/2/2019	5/15/2019			
84	File at Registry	5 days	5/22/2019	5/28/2019			
85	<b>Framingham Zoning Board of Appeals</b>	0 days	5/15/2018	5/15/2018			
86	Height Variance Granted and Appeal Period Expired	0 days	5/15/2018	5/15/2018		5/15/2018 ♦ Height Variance Granted and Appeal Period Expired	
87	<b>BUILDING PERMITTING</b>	153 days	5/10/2019	12/15/2019			
88	Site Enabling and Preparation Package Permit	29 days	5/10/2019	6/19/2019			
89	Foundation Permit	21 days	8/9/2019	9/9/2019			
90	Structure Permit	21 days	8/9/2019	9/9/2019			
91	Building Permit	21 days	11/15/2019	12/15/2019			



ID	Task Name	Duration	Start	Finish	2014	2019	2024
92	<b>CONSTRUCTION DOCUMENTS</b>	263 days	12/12/2018	12/20/2019			
93	<b>Early Site Enabling and Foundation Packages (Nos. 1 &amp; 2)</b>	170 days	12/12/2018	8/9/2019			
94	<b>Early Site Enabling, and Preparation Package No. 1</b>	106 days	12/12/2018	5/10/2019			
95	Incorporate MSBA DD Comments	11 days	5/31/2019	6/14/2019			
96	Develop 60% Contract Documents to Estimator	41 days	5/10/2019	7/8/2019			
97	OPM and Cx Review	15 days	7/8/2019	7/26/2019			
98	Structural Peer Review of Early Foundation and Structural Package	15 days	7/8/2019	7/26/2019			
99	60% Construction Documents Cost Estimate	15 days	7/8/2019	7/26/2019			
100	Value Engineering	7 days	7/26/2019	8/5/2019			
101	<b>Early Foundation and Structural Package No. 2</b>	65 days	5/10/2019	8/9/2019			
102	<b>60% Construction Documents Submission to MSBA</b>	0 days	8/9/2019	8/9/2019		8/9/2019	60% Construction Documents Submission to MSBA
103	MSBA Review of 60% CD Submission	16 days	8/9/2019	8/30/2019			
104	Incorporate MSBA 60% CD Comments	10 days	8/30/2019	9/13/2019			
105	Develop 90% Contract Documents to Estimator	21 days	8/9/2019	9/9/2019			
106	90% Construction Documents Cost Estimate	15 days	9/9/2019	9/27/2019			
107	<b>Early Masonry Package No. 3</b>	114 days	5/10/2019	10/18/2019			
108	<b>90% Construction Documents Submission to MSBA</b>	0 days	10/18/2019	10/18/2019		10/18/2019	90% Construction Documents Submission to MSBA
109	MSBA Review of 90% CD Submission	16 days	10/18/2019	11/8/2019			
110	Incorporate MSBA 90% CD Comments	11 days	11/8/2019	11/22/2019			
111	<b>Construction Documents Complete Package No. 4</b>	0 days	11/22/2019	11/22/2019		11/22/2019	Construction Documents Complete Package No. 4
112	LEED-S Design Submission	20 days	11/22/2019	12/20/2019			
113	<b>PROCUREMENT</b>	340 days	9/26/2018	1/27/2020			
114	<b>CM Selection</b>	103 days	9/26/2018	2/20/2019			
115	Develop Application to Inspector General Office	11 days	9/26/2018	10/10/2018			
116	<b>Submit CM Application to IG Office</b>	0 days	10/10/2018	10/10/2018		10/10/2018	Submit CM Application to IG Office
117	IG Approval of CM Application	0 days	12/21/2018	12/21/2018		12/21/2018	IG Approval of CM Application
118	RFQ/RFP Process	39 days	12/12/2018	2/6/2019		2/6/2019	RFQ/RFP Process
119	Interview Shortlisted CM Firms	0 days	2/6/2019	2/6/2019		2/6/2019	Interview Shortlisted CM Firms
120	Negotiate and Award	11 days	2/6/2019	2/20/2019			
121	CM Notice to Proceed	0 days	2/20/2019	2/20/2019		2/20/2019	CM Notice to Proceed
122	<b>Trade Contractors Prequalification - Package No. 1</b>	36 days	3/18/2019	5/7/2019			
123	Draft RFQ	13 days	3/18/2019	4/3/2019			
124	Submit to Advertisement to Central Register and Local Newspaper	0 days	3/28/2019	3/28/2019		3/28/2019	Submit to Advertisement to Central Register and Local Newspaper
125	Notice in Central Register	0 days	4/3/2019	4/3/2019		4/3/2019	Notice in Central Register
126	Prepare SOQ	11 days	4/3/2019	4/17/2019			
127	Submit SOQs	0 days	4/17/2019	4/17/2019		4/17/2019	Submit SOQs
128	Review SOQs	9 days	4/17/2019	4/29/2019			
129	Recommend Prequalified Trade Contractors to SBC	0 days	5/6/2019	5/6/2019		5/6/2019	Recommend Prequalified Trade Contractors to SBC
130	Issue Notification Letters to Prequalified Trade Contractors	0 days	5/7/2019	5/7/2019		5/7/2019	Issue Notification Letters to Prequalified Trade Contractors
131	<b>Trade Contractors Prequalification - Package No. 2</b>	69 days	5/1/2019	8/6/2019			
132	Develop Draft RFQs	41 days	5/1/2019	6/26/2019			
133	Submit Advertisement to Central Register and Local Newspaper	0 days	6/25/2019	6/25/2019		6/25/2019	Submit Advertisement to Central Register and Local Newspaper
134	Notice in Central Register	0 days	7/3/2019	7/3/2019		7/3/2019	Notice in Central Register
135	Prepare SOQ	10 days	7/3/2019	7/17/2019			
136	Submit SOQs	0 days	7/17/2019	7/17/2019		7/17/2019	Submit SOQs
137	Review SOQs	14 days	7/17/2019	8/5/2019			
138	Recommend Prequalified Trade Contractors to SBC	0 days	8/5/2019	8/5/2019		8/5/2019	Recommend Prequalified Trade Contractors to SBC





City of Framingham  
New Fuller Middle School  
Project Schedule

ID	Task Name	Duration	Start	Finish	2014		2019		2024
139	Issue Notification Letters to Prequalified Trade Contractors	0 days	8/6/2019	8/6/2019			8/6/2019	◆ Issue Notification Letters to Prequalified Trade Contractors	
140	<b>Trade Contractors Prequalification - Package No. 3</b>	<b>55 days</b>	<b>7/1/2019</b>	<b>9/17/2019</b>				┌	
141	Develop Draft RFQs	21 days	7/1/2019	7/30/2019				■	
142	Submit Advertisement to Central Register and Local Newspaper	0 days	7/30/2019	7/30/2019			7/30/2019	◆ Submit Advertisement to Central Register and Local Newspaper	
143	Notice in Central Register	0 days	8/7/2019	8/7/2019			8/7/2019	◆ Notice in Central Register	
144	Prepare SOQ	11 days	8/7/2019	8/21/2019				■	
145	Submit SOQs	0 days	8/21/2019	8/21/2019			8/21/2019	◆ Submit SOQs	
146	Review SOQs	13 days	8/21/2019	9/9/2019				■	
147	Recommend Prequalified Trade Contractors to SBC	0 days	9/16/2019	9/16/2019			9/16/2019	◆ Recommend Prequalified Trade Contractors to SBC	
148	Issue Notification Letters to Prequalified Trade Contractors	0 days	9/17/2019	9/17/2019			9/17/2019	◆ Issue Notification Letters to Prequalified Trade Contractors	
149	<b>Trade Contractors Prequalification - Package No. 4</b>	<b>60 days</b>	<b>8/20/2019</b>	<b>11/12/2019</b>				┌	
150	Develop Draft RFQs	15 days	8/20/2019	9/10/2019				■	
151	Submit Advertisement to Central Register and Local Newspaper	0 days	9/10/2019	9/10/2019			9/10/2019	◆ Submit Advertisement to Central Register and Local Newspaper	
152	Notice in Central Register	0 days	9/18/2019	9/18/2019			9/18/2019	◆ Notice in Central Register	
153	Prepare SOQ	11 days	9/18/2019	10/2/2019				■	
154	Submit SOQs	0 days	10/2/2019	10/2/2019			10/2/2019	◆ Submit SOQs	
155	Review SOQs	24 days	10/2/2019	11/4/2019				■	
156	Recommend Prequalified Trade Contractors to SBC	0 days	11/11/2019	11/11/2019			11/11/2019	◆ Recommend Prequalified Trade Contractors to SBC	
157	Issue Notification Letters to Prequalified Trade Contractors	0 days	11/12/2019	11/12/2019			11/12/2019	◆ Issue Notification Letters to Prequalified Trade Contractors	
158	<b>100% Construction Document Package No. 4</b>	<b>51 days</b>	<b>11/12/2019</b>	<b>1/27/2020</b>				┌	
159	Submit Advertisement to Central Register and Newspaper	0 days	11/12/2019	11/12/2019			11/12/2019	◆ Submit Advertisement to Central Register and Newspaper	
160	Notice in Central Register	0 days	11/20/2019	11/20/2019			11/20/2019	◆ Notice in Central Register	
161	Trade Contractor Bid Package	20 days	11/22/2019	12/20/2019				■	
162	Pre-Bid Meeting	0 days	12/3/2019	12/3/2019			12/3/2019	◆ Pre-Bid Meeting	
163	Trade Contractor Bid Due	0 days	12/20/2019	12/20/2019			12/20/2019	◆ Trade Contractor Bid Due	
164	CM Develop GMP	24 days	12/20/2019	1/24/2020				■	
165	GMP Approval	0 days	1/27/2020	1/27/2020			1/27/2020	◆ GMP Approval	
166	<b>EARLY PACKAGES PROCUREMENT</b>	<b>133 days</b>	<b>5/7/2019</b>	<b>11/12/2019</b>				┌	
167	<b>Early Site Package No. 1</b>	<b>30 days</b>	<b>5/7/2019</b>	<b>6/17/2019</b>				┌	
168	Submit Advertisement to Central Register and Newspaper	0 days	5/7/2019	5/7/2019			5/7/2019	◆ Submit Advertisement to Central Register and Newspaper	
169	Notice in Central Register	0 days	5/15/2019	5/15/2019			5/15/2019	◆ Notice in Central Register	
170	Issue Early Site Package Bid Documents	0 days	5/10/2019	5/10/2019			5/10/2019	◆ Issue Early Site Package Bid Documents	
171	PreBid Meeting	0 days	5/20/2019	5/20/2019			5/20/2019	◆ PreBid Meeting	
172	Trade Contractor Bids Due	0 days	5/24/2019	5/24/2019			5/24/2019	◆ Trade Contractor Bids Due	
173	Site Contractor Bids Due	0 days	5/31/2019	5/31/2019			5/31/2019	◆ Site Contractor Bids Due	
174	Descoping and Development of GMP Amendment	12 days	5/31/2019	6/17/2019				■	
175	Award Early Site Package GMP	0 days	6/17/2019	6/17/2019			6/17/2019	◆ Award Early Site Package GMP	
176	<b>Early Foundation and Structural Package No. 2</b>	<b>33 days</b>	<b>7/30/2019</b>	<b>9/16/2019</b>				┌	
177	Submit Advertisement to Central Register and Newspaper	0 days	7/30/2019	7/30/2019			7/30/2019	◆ Submit Advertisement to Central Register and Newspaper	
178	Notice in Central Register	0 days	8/7/2019	8/7/2019			8/7/2019	◆ Notice in Central Register	
179	Issue Early Foundation and Structural Package Bid Documents	0 days	8/9/2019	8/9/2019			8/9/2019	◆ Issue Early Foundation and Structural Package Bid Documents	
180	PreBid Meeting	0 days	8/19/2019	8/19/2019			8/19/2019	◆ PreBid Meeting	
181	Trade Contractor Bids Due	0 days	8/26/2019	8/26/2019			8/26/2019	◆ Trade Contractor Bids Due	
182	Concrete and Steel Contractor Bids Due	0 days	8/30/2019	8/30/2019			8/30/2019	◆ Concrete and Steel Contractor Bids Due	
183	Descoping and Development of GMP Amendment	10 days	8/30/2019	9/13/2019				■	
184	Award Early Foundation and Structural Package GMP	0 days	9/16/2019	9/16/2019			9/16/2019	◆ Award Early Foundation and Structural Package GMP	



City of Framingham  
New Fuller Middle School  
Project Schedule

ID	Task Name	Duration	Start	Finish	2014		2019		2024
185	<b>Early Masonry Package No. 3</b>	25 days	10/8/2019	11/12/2019			11/12/2019	□ Early Masonry Package No. 3	
186	Submit Advertisement to Central Register and Newspaper	0 days	10/8/2019	10/8/2019			10/8/2019	◆ Submit Advertisement to Central Register and Newspaper	
187	Notice in Central Register	0 days	10/16/2019	10/16/2019			10/16/2019	◆ Notice in Central Register	
188	Issue Early Masonry Package Bid Documents	0 days	10/18/2019	10/18/2019			10/18/2019	◆ Issue Early Masonry Package Bid Documents	
189	PreBid Meeting	0 days	10/22/2019	10/22/2019			10/22/2019	◆ PreBid Meeting	
190	Trade Contractor Bids Due	0 days	11/8/2019	11/8/2019			11/8/2019	◆ Trade Contractor Bids Due	
191	Award Early Masonry Package GMP	0 days	11/12/2019	11/12/2019			11/12/2019	◆ Award Early Masonry Package GMP	
192	<b>CONSTRUCTION</b>	737 days	6/10/2019	4/21/2022					
193	Notice to Proceed	0 days	6/18/2019	6/18/2019			6/18/2019	◆ Notice to Proceed	
194	EPA NPDES Submitted	0 days	6/10/2019	6/10/2019			6/10/2019	◆ EPA NPDES Submitted	
195	EPA NPDES Approved	0 days	6/24/2019	6/24/2019			6/24/2019	◆ EPA NPDES Approved	
196	Site Mobilization	0 days	6/20/2019	6/20/2019			6/20/2019	◆ Site Mobilization	
197	MA DEP RAM Plan Submitted	0 days	7/17/2019	7/17/2019			7/17/2019	◆ MA DEP RAM Plan Submitted	
198	<b>Substantial Completion - Phase 1 "Enabling Work"</b>	0 days	8/20/2019	8/20/2019			8/20/2019	◆ Substantial Completion - Phase 1 "Enabling Work"	
199	50% DCAMM Evaluation	0 days	8/15/2020	8/15/2020			8/15/2020	◆ 8/15/2020	
200	Punch List Start	0 days	4/15/2021	4/15/2021			4/15/2021	◆ 4/15/2021	
201	Punch List Complete	0 days	6/15/2021	6/15/2021			6/15/2021	◆ 6/15/2021	
202	<b>Substantial Completion - Phase 2 "Building Construction"</b>	0 days	6/15/2021	6/15/2021			6/15/2021	◆ Substantial Completion - Phase 2 "Building Construction"	
203	Final Completion, Closeout and Commissioning	34 days	6/15/2021	7/30/2021					
204	FFE/Technology Installation	34 days	6/15/2021	7/30/2021					
205	Teacher/Staff Move-In	21 days	8/2/2021	8/30/2021					
206	<b>Occupancy</b>	0 days	8/30/2021	8/30/2021			8/30/2021	◆ Occupancy	
207	Abate and Demolish Existing School	67 days	7/3/2021	10/5/2021					
208	Parking Lot and Playfield Construction	55 days	10/4/2021	12/20/2021					
209	CM Request for Final Payment	0 days	12/20/2021	12/20/2021			12/20/2021	◆ 12/20/2021	
210	<b>Substantial Completion - Phase 3 "Demolition and Site Work"</b>	0 days	12/20/2021	12/20/2021			12/20/2021	◆ Substantial Completion - Phase 3 "Demolition and Site Work"	
211	Closeout	46 days	12/20/2021	2/21/2022					
212	Final Completion	46 days	12/20/2021	2/21/2022					
213	100% DCAMM Evaluation	0 days	2/21/2022	2/21/2022			2/21/2022	◆ 2/21/2022	
214	LEED-S Construction Submission	46 days	12/20/2021	2/21/2022					
215	MSBA Final Payment Reimbursement Request	0 days	3/1/2022	3/1/2022			3/1/2022	◆ 3/1/2022	
216	Commissioning Agent 10-month Inspection	0 days	4/15/2022	4/15/2022			4/15/2022	◆ 4/15/2022	
217	Commissioning Agent Final Report Submission to MSBA	0 days	4/15/2022	4/15/2022			4/15/2022	◆ 4/15/2022	
218	Commissioning Agent Submission of Certification	0 days	4/15/2022	4/15/2022			4/15/2022	◆ 4/15/2022	
219	USGBC Issuance of Certification	0 days	4/21/2022	4/21/2022			4/21/2022	◆ 4/21/2022	



## 2.3 Scope and Budget

### 2.3.1 Project Budget

The Project Budget for the New Fuller Middle School is \$98,276,878 as defined in the Project Funding Agreement. The project is on budget, as shown on the Total Project Budget Form, inclusive of the Reconciled Construction Cost Estimate, appended at the end of this section.

The Construction Budget is \$77,935,429. The 90% Construction Documents Estimate provided by Consigli Construction Co., Inc., dated October 7, 2019, is currently tracking on budget at \$77,393,464 and as defined by the Cost Estimate Comparison Spreadsheet appended at the end of this section.

Three independent 90% Construction Documents Estimates were prepared. The estimates, prepared by A.M. Fogarty, dated September 26, 2019; Miyakoda Consulting, dated September 30, 2019 and Consigli Construct Co., Inc., dated September 27, 2019, were reconciled with each other through an intensive series of review meetings with the entire design team, the OPM and the estimators. The estimates and the Draft Cost Estimate Comparison Spreadsheet are appended at the end of this section.

Value Engineering was performed with the School Building Committee (SBC) on October 7, 2019, meeting minutes attached. The following Value Engineering items were approved:

1. Change Learning Commons Porcelain Tile to Linoleum – Deduct \$112,000

The approved value engineering item will be incorporated into the 100% Construction Documents and Estimate.



## Project Minutes

Project: New Fuller Middle School  
 Prepared by: Joel Seeley  
 Re: School Building Committee Meeting  
 Location: Fuller Middle School Library  
 Distribution: Attendees (MF)

Project No.: 17050  
 Meeting Date: 10/7/19  
 Time: 7:00pm  
 Meeting No: 49

### Attendees

PRESENT	NAME	AFFILIATION	VOTING MEMBER
✓	David Miles	Co-Chair, City Resident with Experience in Finance	<b>Voting Member</b>
	Dr. Edward Gotgart	Co-Chair	Non-Voting Member
	Mayor Spicer	Mayor, Chief Executive Officer	Non-Voting Member
	Thatcher Kezer III	Chief Operating Officer	Non-Voting Member
✓	Richard Finlay	School Committee Member and Convener	<b>Voting Member</b>
✓	Adam Freudberg	Chair, School Committee	<b>Voting Member</b>
	Charlie Sisitsky	City Council Member	<b>Voting Member</b>
✓	Richard Weader II	Member of community with arch., eng., and/or const. experience	<b>Voting Member</b>
✓	Michael Grilli	Member of community with arch., eng., and/or const. experience	<b>Voting Member</b>
✓	Cynthia Blackwell	School Building Committee Member	<b>Voting Member</b>
✓	Dr. Jennifer Krusinger Martin	School Building Committee Member	<b>Voting Member</b>
✓	Donald C. Taggart III	City Resident/Retired Teacher	<b>Voting Member</b>
	Jennifer Pratt	Assistant Chief Financial Officer and SBC Member who is MCPPO certified	Non-Voting Member
	Dr. Robert Tremblay	Superintendent of Schools	Non-Voting Member
✓	Matt Torti	Director of Buildings and Grounds	Non-Voting Member
	Kerry Wood	Principal, Fuller Middle School	Non-Voting Member
✓	Anne Ludes	Director of Secondary Education	Non-Voting Member
	Mary Ellen Kelley	Chief Financial Officer and Local Budget official or member of Finance Committee	Non-Voting Member
	Michael Tusino	Certified Building Official	Non-Voting Member
	Patrick Johnson	Principal, Walsh Middle School	Non-Voting Member
✓	David Panich	School Building Committee Member	Non-Voting Member
	Thomas Barbieri	School Building Committee Member	Non-Voting Member
	Noval Alexander	School Committee Member	Non-Voting Member
	Heather Connolly	Former Chair of the School Committee	Non-Voting Member
✓	Scott Wadland	School Committee Member	
✓	Michael Stevens	Assistant Principal, Fuller Middle School	
✓	Jonathan Levi	JLA, Architect	
✓	Philip Gray	JLA, Architect	
	Elizabeth Bugbee	JLA, Architect	
	Christian Riordan	Consigli Construction Company (CCC), CM	
✓	Matteo Batista	Consigli Construction Company (CCC), CM	
	Kristy Lyons	Consigli Construction Company (CCC), CM	
✓	Robert Smith	SMMA, OPM	
✓	Joel Seeley	SMMA, OPM	

Item #	Action	Discussion
49.1	Record	Call to Order, 7:00 PM, meeting opened.
49.2	Record	D. Miles indicated S. Wadland will be voting for A. Freudberg upon his departure as the School Committee representative.
49.3	Record	Public Comments - none
49.4	Record	A motion was made by R. Finlay and seconded by M. Grilli to approve the 9/16/19 School Building Committee meeting minutes, attached. No discussion, motion passed unanimous by those attending.
49.5	Record	J. Seeley distributed and reviewed the Budget Tracking Form thru 9/30/19, attached, for the Total Project Budget
49.6	Record	J. Seeley distributed and reviewed Warrant No. 23, attached.  A motion was made by R. Finlay and seconded by M. Grilli to approve Warrant No. 23. No discussion, motion passed unanimous.
49.7	Record	P. Gray distributed and reviewed Change Order No. 3, dated 10/1/19 in the amount of \$291.12, Change Order Description Form and Change Order Contingency Summary Form, all attached.  A motion was made by R. Finlay and seconded by M. Grilli to approve Change Order No. 3, dated 10/1/19 in the amount of \$291.12 and recommend signature by T. Kezer III. No discussion, motion passed unanimous.
49.8	Record	J. Seeley distributed and reviewed the updated 90% Construction Document Phase Meetings and Agenda Schedule, the updated 100% Construction Document Phase Meetings and Agenda Schedule, and the updated Project Schedule, attached.
49.9	J. Levi	J. Levi to coordinate with the Principal on a presentation of the project to the Fuller teachers and staff, targeted for September or October. <i>(Item from Prior Meeting)</i>
49.10	E. Gotgart	E. Gotgart to be the SBC liaison to the Facilities Subcommittee relative to the School Department and Parks and Recreation joint-sponsored appropriation request, for FY 2022, to the City for upgrading one or both of the Fuller playing fields, or other fields in the City, to synthetic turf fields. <i>(Item from Prior Meeting)</i>
49.11	A. Freudberg	A. Freudberg will follow-up with the School Committee for approval of the supplemental list of Recommended Proprietary Specifications to be included in the project. <i>(Item from Prior Meeting)</i>
49.12	Record	J. Seeley indicated the Public Information Working Group met on 10/7/19 to coordinate community information releases.
49.13	Record	P. Gray distributed and reviewed the 9/19/19 Door Hardware Meeting minutes, attached.
49.14	Record	P. Gray provided an overview of the 10/5/19 Neighborhood Meeting, attached. Future neighborhood meetings to be determined.
49.15	Record	J. Levi presented updated Interior Renderings with three options for the interior painted color accent bands, attached.



		After discussion, a motion was made by M. Grilli and seconded by A. Freudberg to approve Option A for the Atrium Corridors and Option B for the Classrooms. No discussion, motion passed unanimous.
49.16	Record	M. Batista presented and reviewed the 90% Construction Documents Construction Cost Estimates, attached. The Consigli estimate reflects a construction cost of \$77.4M against a budget of \$77.9M. The OPM and Designer estimates were reflecting a lower construction cost.
49.17	Record	<p>P. Gray presented and reviewed a Bidding Alternate strategy and a bidding alternate to change the Learning Commons porcelain tile flooring to linoleum flooring with an estimated deductive value of \$112,000, attached</p> <p>Committee Discussion:</p> <ol style="list-style-type: none"> <li>1. D. Miles indicated there is good reason to include bidding alternates, avoiding a project delay in an over budget bid situation</li> <li>2. S. Wadland asked how does the bidder bid on the alternate? <i>J. Levi indicated the Bid Form will have two separate lines, one for the base bid and a second for the alternate.</i></li> <li>3. C. Blackwell indicated it may be prudent to include additional bidding alternates for bid and market risk. <i>J. Levi indicated if there are any additional alternates, they will need to be decided by the next Committee meeting to provide JLA sufficient time to include in the contract documents.</i></li> <li>4. R. Finlay indicated he would like Building and Grounds to provide an opinion on the alternate. <i>M. Torti indicated if there is a risk of not installing the porcelain tile, then Building and Grounds would not recommend the alternate.</i></li> </ol> <p>A motion was made by S. Wadland and seconded by D. Taggart III to incorporate the following Bidding Alternate into the 100% Construction Documents: 1) change the Learning Commons porcelain tile flooring to linoleum flooring. No discussion, motion passed 7 in favor and 1 against (R. Finlay).</p>
49.18	Record	A Motion was made by M. Grilli and seconded by R. Finlay to approve the 90% Construction Documents Submittal and authorize submission to the MSBA. No discussion, motion passed unanimous.
49.19	Record	M. Batista provided a Construction Update, attached.
49.20	Record	Old or New Business - none
49.21	Record	Next <b>SBC Meeting: October 28, 2019 at 7:00 PM</b> at Fuller Middle School Library.
49.22	Record	A Motion was made by R. Finlay and seconded by M. Grilli to adjourn the meeting. No discussion, motion passed unanimous.

Attachments: Agenda, Budget Tracking Form, Warrant No. 23, Change Order No. 3, Description Form and Contingency Summary Form, Updated 90% Construction Document Phase Meetings and Agenda Schedule,

Project: New Fuller Middle School  
Meeting Date: 10/7/19  
Meeting No.: 49  
Page No: 4

---

Updated 100% Construction Document Phase Meetings and Agenda Schedule, Updated Project Schedule  
Construction Update, 9/19/19 Door Hardware Meeting minutes, Powerpoint

The information herein reflects the understanding reached. Please contact the author if you have any questions or are not in agreement with these Project Minutes.

---

1000 Massachusetts Avenue  
Cambridge, MA 02138  
617.547.5400

[www.smma.com](http://www.smma.com)

---

### 2.3.2 Total Project Budget

Attached is the updated Total Project Budget.



**Total Project Budget**

**City of Framingham  
Fuller Middle School  
Updated for 90% Construction Documents Cost  
Estimate**

**School Building Committee Reviewed on:**

**8/27/2018**

<b>Total Project Budget: All costs associated with the project are subject to 963 CMR 2.16(5)</b>	<b>Estimated Budget</b>	<b>Scope Items Excluded from the Estimated Basis of Maximum Facilities Grant or Otherwise Ineligible</b>	<b>Estimated Basis of Maximum Total Facilities Grant<sup>1</sup></b>	<b>Estimated Maximum Total Facilities Grant<sup>1</sup></b>
<b>Feasibility Study Agreement</b>				
OPM Feasibility Study	\$175,000	\$0	\$175,000	
A&E Feasibility Study	\$545,000	\$0	\$545,000	
Environmental & Site	\$145,000	\$0	\$145,000	
Other	\$135,000	\$0	\$135,000	
<b>Feasibility Study Agreement Subtotal</b>	<b>\$1,000,000</b>	<b>\$0</b>	<b>\$1,000,000</b>	<b>\$623,100</b>
<b>Administration</b>				
Legal Fees	\$80,000	\$80,000	\$0	\$0
<b>Owner's Project Manager</b>				
Design Development	\$175,445	\$284,370	-\$108,925	
Construction Contract Documents	\$242,886	\$0	\$242,886	
Bidding	\$115,789	\$0	\$115,789	
Construction Contract Administration	\$1,727,876	\$0	\$1,727,876	
Closeout	\$95,905	\$0	\$95,905	
Extra Services	\$40,000	\$0	\$40,000	
Reimbursable & Other Services	\$40,000	\$0	\$40,000	
Cost Estimates	\$80,000	\$0	\$80,000	
Advertising	\$20,000	\$0	\$20,000	
Permitting	\$50,000	\$0	\$50,000	
Owner's Insurance	\$120,000	\$0	\$120,000	
Other Administrative Costs	\$100,000	\$0	\$100,000	
<b>Administration Subtotal</b>	<b>\$2,887,901</b>	<b>\$364,370</b>	<b>\$2,523,531</b>	<b>\$1,572,412</b>
<b>Architecture and Engineering</b>				
<b>Basic Services</b>				
Design Development	\$2,059,998	\$832,109	\$1,227,889	
Construction Contract Documents	\$2,746,664	\$0	\$2,746,664	
Bidding	\$137,334	\$0	\$137,334	
Construction Contract Administration	\$1,833,398	\$0	\$1,833,398	
Closeout	\$89,265	\$0	\$89,265	
Other Basic Services	\$0	\$0	\$0	
<b>Basic Services Subtotal</b>	<b>\$6,866,659</b>	<b>\$832,109</b>	<b>\$6,034,550</b>	
<b>Reimbursable Services</b>				
Construction Testing	\$30,000	\$0	\$30,000	
Printing (over minimum)	\$20,000	\$0	\$20,000	
Other Reimbursable Costs	\$180,000	\$0	\$180,000	
Hazardous Materials	\$170,984	\$0	\$170,984	
Geotechnical & Geo-Environmental	\$155,925	\$0	\$155,925	
Site Survey	\$44,000	\$0	\$44,000	
Wetlands	\$44,000	\$0	\$44,000	
Traffic Studies	\$38,500	\$0	\$38,500	
<b>Architectural/Engineering Subtotal</b>	<b>\$7,550,068</b>	<b>\$832,109</b>	<b>\$6,717,959</b>	<b>\$4,185,960</b>
<b>CM at Risk Preconstruction Services</b>				
Pre-Construction Services	\$400,000	\$0	\$400,000	\$249,240
Site Acquisition				
Land / Building Purchase	\$0	\$0	\$0	
Appraisal Fees	\$0	\$0	\$0	
Recording fees	\$0	\$0	\$0	
<b>Site Acquisition Subtotal</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>

**Total Project Budget**

**City of Framingham  
Fuller Middle School  
Updated for 90% Construction Documents Cost  
Estimate**

**School Building Committee Reviewed on:**

**8/27/2018**

<b>Total Project Budget: All costs associated with the project are subject to 963 CMR 2.16(5)</b>	<b>Estimated Budget</b>	<b>Scope Items Excluded from the Estimated Basis of Maximum Facilities Grant or Otherwise Ineligible</b>	<b>Estimated Basis of Maximum Total Facilities Grant<sup>1</sup></b>	<b>Estimated Maximum Total Facilities Grant<sup>1</sup></b>
<b>Construction Costs</b>				
<b>SUBSTRUCTURE</b>				
Foundations	\$1,634,809	\$0		
Basement Construction	\$0	\$0		
<b>SHELL</b>				
SuperStructure	\$6,055,836	\$0		
Exterior Closure	\$0	\$0		
Exterior Walls	\$5,081,958	\$0		
Exterior Windows	\$1,676,839	\$0		
Exterior Doors	\$167,968	\$0		
Roofing	\$2,375,388	\$0		
<b>INTERIORS</b>				
Interior Construction	\$7,235,868	\$0		
Staircases	\$408,160	\$0		
Interior Finishes	\$5,102,211	\$0		
<b>SERVICES</b>				
Conveying Systems	\$220,450	\$0		
Plumbing	\$2,094,999	\$0		
HVAC	\$8,064,951	\$0		
Fire Protection	\$873,859	\$0		
Electrical	\$5,196,978	\$0		
<b>EQUIPMENT &amp; FURNISHINGS</b>				
Equipment	\$1,671,288	\$0		
Furnishings	\$1,533,465	\$0		
<b>SPECIAL CONSTRUCTION &amp; DEMOLITION</b>				
Special Construction	\$0	\$0		
Existing Building Demolition	\$1,367,800	\$0		
In-Building Hazardous Material Abatement	\$1,213,480			
Asbestos Containing Floor Material Abatement	\$388,800	\$388,800		
Other Hazardous Material Abatement	\$0	\$0		
<b>BUILDING SITEWORK</b>				
Site Preparation	\$4,746,798	\$6,674,478		
Site Improvements	\$4,201,267	\$0		
Site Civil / Mechanical Utilities	\$1,025,389	\$0		
Site Electrical Utilities	\$652,626	\$0		
Other Site Construction	\$0	\$0		
Scope Excluded Site Cost		\$0		
<b>Construction Trades Subtotal</b>	<b>\$62,991,187</b>	<b>\$7,063,278</b>		
Contingencies (Design and Pricing)	\$1,416,139	\$158,793		
General Conditions	\$3,988,224	\$447,204		
General Requirements	\$3,084,502	\$345,869		
Insurance	\$895,218	\$100,382		
Bonds	\$1,320,945	\$148,119		
GMP Fee	\$1,560,000	\$174,925		
not used		\$0		
GMP Contingency	\$1,651,041	\$185,133		
Escalation to Mid-Point of Construction	\$486,208	\$54,519		
Ineligible Auditorium & PE Areas beyond Guidelines		\$7,213,734		
Overall Excluded Construction Cost		\$13,683,070		
<b>Construction Budget</b>	<b>\$77,393,464</b>	<b>\$29,575,027</b>	<b>\$47,818,437</b>	<b>\$29,795,668</b>
<b>Alternates</b>				
Alternates	\$0		\$0	
Alternates Included in the Total Project Budget	\$0	\$0		
Alternates Excluded from the Total Project Budget	\$0		\$0	
<b>Subtotal to be Included in Total Project Budget</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>
<b>Miscellaneous Project Costs</b>				
Utility Company Fees	\$280,000	\$0	\$280,000	
Testing Services	\$300,000	\$0	\$300,000	
Swing Space / Modularity	\$0	\$0	\$0	
Other Project Costs (Mailing & Moving)	\$200,000	\$200,000	\$0	
<b>Misc. Project Costs Subtotal</b>	<b>\$780,000</b>	<b>\$200,000</b>	<b>\$580,000</b>	<b>\$361,398</b>
<b>Furnishings and Equipment</b>				
Furniture, Fixtures, and Equipment	\$1,134,000	\$378,000	\$756,000	
Technology	\$1,134,000	\$378,000	\$756,000	
<b>FF&amp;E Subtotal</b>	<b>\$2,268,000</b>	<b>\$756,000</b>	<b>\$1,512,000</b>	<b>\$942,127</b>
Soft Costs that exceed 20% of Construction Cost		\$0		

**Total Project Budget**

**City of Framingham  
Fuller Middle School  
Updated for 90% Construction Documents Cost  
Estimate**

**School Building Committee Reviewed on:**

**8/27/2018**

Total Project Budget: All costs associated with the project are subject to 963 CMR 2.16(5)	Estimated Budget	Scope Items Excluded from the Estimated Basis of Maximum Facilities Grant or Otherwise Ineligible	Estimated Basis of Maximum Total Facilities Grant <sup>1</sup>	Estimated Maximum Total Facilities Grant <sup>1</sup>
<b>Project Budget</b>	<b>\$92,279,433</b>	<b>\$31,727,506</b>	<b>\$60,551,927</b>	<b>\$37,729,906</b>

<b>Board Authorization</b>	
Design Enrollment	630
Total Building Gross Floor Area (GSF)	136,790
Total Project Budget (excluding Contingencies)	\$92,279,433
Scope Items Excluded or Otherwise Ineligible	\$31,727,506
Third Party Funding (Ineligible)	\$0
Estimated Basis of Maximum Total Facilities Grant <sup>1</sup>	\$60,551,927
Reimbursement Rate <sup>3,4</sup>	62.31%
Est. Max. Total Facilities Grant (before recovery) <sup>1</sup>	\$37,729,906
Cost Recovery <sup>5</sup>	\$0
Estimated Maximum Total Facilities Grant <sup>1</sup>	\$37,729,906

57.83 Reimbursement Rate Before Incentive Points  
4.48 Total Incentive Points<sup>3,4</sup>  
62.31% MSBA Reimbursement Rate

**NOTES**

This template was prepared by the MSBA as a tool to assist Districts and consultants in understanding MSBA policies and practices regarding potential impact on the MSBA's calculation of a potential Basis of Total Facilities Grant and potential Total Maximum Facilities Grant. This template does not contain a final, exhaustive list of all evaluations which the MSBA may use in determining whether items are eligible for reimbursement by the MSBA. The MSBA will perform an independent analysis based on a review of information and estimates provided by the District for the proposed school project that may or may not agree with the estimates generated by the District using this template.

- Does not include any potentially eligible contingency funds and is subject to review and audit by the MSBA.
- The proposed demolition of the \_\_\_\_\_ School is expected to result in the MSBA recovering a portion of state funds previously paid to the District for the \_\_\_\_\_ project at the existing facilities completed in \_\_\_\_\_. The MSBA will perform an independent analysis based on a review of information and estimates provided by the District for the proposed school project that may or may not agree with the estimated cost recovery generated by the District and its consultants using this template.
- Pursuant to Section 3.20 of the Project Funding Agreement and the applicable policies and guidelines of the Authority, any project costs associated with the reallocation or transfer of funds from either the Owner's contingency or the Construction contingency to other budget line items shall be subject to review by the Authority to determine whether any such costs are eligible for reimbursement by the Authority. All costs are subject to review and audit by the MSBA.

Construction Contingency <sup>2</sup>	\$4,438,736
Ineligible Construction Contingency <sup>2</sup>	\$3,664,801
"Potentially Eligible" Construction Contingency <sup>2</sup>	\$773,935
Owner's Contingency <sup>2</sup>	\$1,558,709
Ineligible Owner's Contingency <sup>2</sup>	\$0
"Potentially Eligible" Owner's Contingency <sup>2</sup>	\$1,558,709
Total Potentially Eligible Contingency <sup>2</sup>	\$2,332,644
Reimbursement Rate <sup>3,4</sup>	62.31%
Potential Additional Contingency Grant Funds <sup>2</sup>	\$1,453,470
Maximum Total Facilities Grant	\$39,183,376
Total Project Budget	\$98,276,878

By signing this Total Project Budget, I hereby certify that I have read and understand the form and further certify, to the best of my knowledge and belief, that the information supplied by the District in the table above is true, accurate, and complete.

By signing this Total Project Budget, I hereby certify that I have read and understand the form and further certify, to the best of my knowledge and belief, that the information supplied by the District in the table above is true, accurate, and complete.

By signing this Total Project Budget, I hereby certify that I have read and understand the form and further certify, to the best of my knowledge and belief, that the information supplied by the District in the table above is true, accurate, and complete.

By signing this Total Project Budget, I hereby certify that I have read and understand the form and further certify, to the best of my knowledge and belief, that the information supplied by the District in the table above is true, accurate, and complete.

By: \_\_\_\_\_  
Title: Chair of School Building Committee

By: \_\_\_\_\_  
Title: Chief Executive Officer

By: \_\_\_\_\_  
Title: Superintendent of Schools

By: \_\_\_\_\_  
Title: Chair of School Committee

Date: \_\_\_\_\_

Date: \_\_\_\_\_

Date: \_\_\_\_\_

Date: \_\_\_\_\_





### 2.3.3 Construction Estimate Comparison

Attached is the updated Construction Cost Comparison.



Dated 10/9/19

	Consigli Final 60% CD Estimate 8/5/19	Consigli Final 90% CD Estimate 10/7/19	Delta from Final 60% Estimate	Myakoda Final 90% CD Estimate 10/9/19	Delta from Final 60% Estimate	Fogarty Draft 90% CD Estimate 10/9/19	Delta from Final 60% Estimate
SF	136,790	136,790		136,790		136,790	
Division 1 - General Requirements	\$ 75,000	\$ 75,000	\$ -	\$ -	\$ (75,000)	\$ 75,000	\$ -
Division 2 - Existing Conditions	\$ 2,872,380	\$ 2,970,080	\$ 97,700	\$ 2,759,990	\$ (112,390)	\$ 2,970,080	\$ 97,700
Division 3 - Concrete	\$ 2,772,478	\$ 2,772,478	\$ (2,772,478)	\$ 45,648	\$ (2,726,830)	\$ -	\$ (2,772,478)
Division 4 - Masonry	\$ 2,015,845	\$ 2,290,785	\$ 274,940	\$ 2,338,257	\$ 322,412	\$ 2,296,962	\$ 281,117
Division 5 - Metals	\$ 5,438,115	\$ 1,112,650	\$ (4,325,465)	\$ 836,941	\$ (4,601,174)	\$ 1,152,710	\$ (4,275,405)
Division 6 - Wood, Plastics and Composites	\$ 2,101,375	\$ 1,929,625	\$ (171,750)	\$ 1,781,230	\$ (320,145)	\$ 2,078,706	\$ (22,669)
Division 7 - Thermal and Moisture Protection	\$ 3,789,139	\$ 3,839,458	\$ 50,319	\$ 3,738,916	\$ (50,223)	\$ 3,905,896	\$ 116,757
Division 8 - Openings	\$ 4,382,132	\$ 4,265,650	\$ (116,482)	\$ 4,302,558	\$ (79,574)	\$ 4,024,611	\$ (357,521)
Division 9 - Finishes	\$ 7,991,673	\$ 9,107,876	\$ 1,116,203	\$ 8,912,813	\$ 1,195,063	\$ 8,645,689	\$ 266,324
Division 10 - Specialties	\$ 1,087,728	\$ 1,170,442	\$ 82,714	\$ 1,286,280	\$ 1,103,562	\$ 1,083,401	\$ (4,377)
Division 11 - Equipment	\$ 1,431,329	\$ 1,428,829	\$ (2,500)	\$ 1,683,448	\$ 252,119	\$ 1,492,662	\$ 61,333
Division 12 - Furnishings	\$ 668,465	\$ 642,675	\$ (25,790)	\$ 540,232	\$ (128,233)	\$ 654,764	\$ (13,701)
Division 13 - Special Construction	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Division 14 - Conveying Equipment	\$ 220,000	\$ 220,000	\$ -	\$ 215,000	\$ (5,000)	\$ 212,000	\$ (8,000)
Division 21 - Fire Suppression	\$ 791,653	\$ 873,859	\$ 82,206	\$ 962,994	\$ 89,135	\$ 893,565	\$ 7
Division 22 - Plumbing	\$ 2,195,545	\$ 2,033,274	\$ (162,271)	\$ 2,126,673	\$ (88,872)	\$ 2,150,852	\$ 16
Division 23 - HVAC	\$ 7,967,908	\$ 8,126,676	\$ 158,768	\$ 7,879,869	\$ (88,039)	\$ 8,247,841	\$ 279,933
Division 26 - Electrical	\$ 5,663,400	\$ 5,773,794	\$ 110,394	\$ 5,893,015	\$ 129,615	\$ 6,000,049	\$ 336,649
Division 31 - Earthwork	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Division 32 - Exterior Improvements	\$ 1,605,665	\$ 1,340,457	\$ (265,208)	\$ 1,401,720	\$ (203,945)	\$ 1,353,932	\$ (51,733)
Division 33 - Utilities	\$ -	\$ 3,500	\$ 3,500	\$ -	\$ -	\$ -	\$ -
	\$ 53,069,830	\$ 47,204,630	\$ -5,865,200	\$ 46,705,584	\$ -6,364,246	\$ 47,248,720	\$ -5,821,110
Total Trade Cost	\$ 53,069,830	\$ 47,204,630	\$ -5,865,200	\$ 46,705,584	\$ -6,364,246	\$ 47,248,720	\$ -5,821,110
General Conditions	\$ 3,401,447	\$ 2,931,033	\$ -470,414	\$ 2,931,033	\$ -470,414	\$ 2,931,033	\$ -470,414
General Requirements	\$ 2,652,482	\$ 2,289,380	\$ -363,102	\$ 2,289,380	\$ -363,102	\$ 2,289,380	\$ -363,102
Insurance	\$ 668,571	\$ 576,109	\$ -92,462	\$ 576,109	\$ -92,462	\$ 576,109	\$ -92,462
Bonds	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Sub Bonds	\$ 742,977	\$ 660,865	\$ -82,112	\$ 672,892	\$ -70,085	\$ 265,000	\$ -477,977
Builders Risk	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Permit	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Fee	\$ 1,337,143	\$ 1,152,218	\$ -184,925	\$ 1,152,218	\$ -184,925	\$ 1,152,218	\$ -184,925
Design Contingency	\$ 2,653,491	\$ 1,416,139	\$ -1,237,352	\$ 1,401,168	\$ -1,252,323	\$ 1,417,462	\$ -214,861
GMP Contingency	\$ 1,432,554	\$ 1,244,196	\$ -188,358	\$ 1,376,431	\$ -56,123	\$ 1,216,655	\$ -215,899
Escalation	\$ 835,850	\$ 485,208	\$ -350,642	\$ 481,068	\$ -354,782	\$ 498,828	\$ -337,022
	\$ 13,724,515	\$ 10,756,148	\$ -2,968,367	\$ 10,880,299	\$ -2,844,216	\$ 10,346,685	\$ -3,377,830
Early Site Package	\$ 10,957,843	\$ 10,957,843	\$ 0	\$ 10,957,843	\$ 0	\$ 10,957,843	\$ 0
Early Concrete and Steel Package	\$ 8,738,800	\$ 8,738,800	\$ 8,738,800	\$ 8,738,800	\$ 8,738,800	\$ 8,738,800	\$ 8,738,800
Buy Savings	\$ (487,000)	\$ (50,755)	\$ -50,755	\$ (50,755)	\$ -50,755	\$ (50,755)	\$ -50,755
Total Construction Cost	\$ 77,752,188	\$ 77,606,666	\$ 567	\$ 77,231,771	\$ -520,417	\$ 77,241,293	\$ -510,895
Post 60% VE **	\$ (487,000)	\$ (213,200)	\$ -273,800	\$ (213,200)	\$ -273,800	\$ (213,200)	\$ -273,800
Adjusted Cost	\$ 77,265,188	\$ 77,393,466	\$ 128,278	\$ 77,018,571	\$ -246,617	\$ 76,928,093	\$ -337,495
Construction Cost Budget	\$ 77,935,429	\$ 77,935,429	\$ -	\$ 77,935,429	\$ -	\$ 77,935,429	\$ -
Delta	\$ (670,241)	\$ (541,963)	\$ -128,278	\$ (703,658)	\$ -520,417	\$ (694,136)	\$ -173,723

\*\*

Remove the raised traffic table on Flagg Drive - Deduct \$247,000  
Remove the stepped terraces on the amphitheater - Deduct \$139,000  
Change the Centralized pH Neutralization System to a point of use system - Deduct \$101,000



**2.3.4 Reconciled Cost Estimate - CMR**  
Attached is the reconciled CMR Cost Estimate.



# 90% CD Reconciled Estimate



## **Town of Framingham**

Fuller Middle School

Framingham, MA

October 7, 2019

## **SUBMITTED BY:**

Consigli Construction Co., Inc.

72 Sumner Street

Milford, MA 01757







CONSIGLI  
*Est. 1905*

# TABLE OF CONTENTS

Fuller Middle School



## The Right Choice

Consigli Construction Co., Inc. is a fourth-generation family owned organization that can offer the resources and experience of one of the strongest construction management firms in the Northeast with the creativity and flexibility of a start-up.

1. Uniformat Summary
2. Uniformat Detail
3. CSI Summary
4. CSI Detail
5. General Requirements
6. Assumptions & Qualifications





**CONSIGLI**  
*Est. 1905*





Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>A Substructure</b>			
<b>A10 Foundations</b>			
A1010 Standard Foundations	136,600 sf	/sf	
A1030 Slab on Grade	136,600 sf	/sf	
<b>A10 Foundations</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>A Substructure</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>B Shell</b>			
<b>B10 Superstructure</b>			
B1010 Floor Construction	136,600 sf	1.55 /sf	211,720
B1020 Roof Construction	136,600 sf	1.39 /sf	190,225
<b>B10 Superstructure</b>	<b>136,600 sf</b>	<b>2.94 /sf</b>	<b>401,945</b>
<b>B20 Exterior Enclosure</b>			
B2010 Exterior Walls	136,600 sf	37.20 /sf	5,081,958
B2020 Exterior Windows	136,600 sf	12.28 /sf	1,676,839
B2030 Exterior Doors	136,600 sf	1.23 /sf	167,968
<b>B20 Exterior Enclosure</b>	<b>136,600 sf</b>	<b>50.71 /sf</b>	<b>6,926,765</b>
<b>B30 Roofing</b>			
B3010 Roof Coverings	136,600 sf	12.32 /sf	1,682,388
B3020 Roof Openings	136,600 sf	5.07 /sf	693,000
<b>B30 Roofing</b>	<b>136,600 sf</b>	<b>17.39 /sf</b>	<b>2,375,388</b>
<b>B Shell</b>	<b>136,600 sf</b>	<b>71.04 /sf</b>	<b>9,704,098</b>
<b>C Interiors</b>			
<b>C10 Interior Construction</b>			
C1010 Partitions	136,600 sf	38.28 /sf	5,228,988
C1020 Interior Doors	136,600 sf	7.23 /sf	987,898
C1030 Specialties/Millwork	136,600 sf	7.46 /sf	1,018,982
<b>C10 Interior Construction</b>	<b>136,600 sf</b>	<b>52.97 /sf</b>	<b>7,235,868</b>
<b>C20 Stairs</b>			
C2010 Stair Construction	136,600 sf	2.87 /sf	392,000



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>C2020 Stair Finishes</b>	<b>136,600 sf</b>	<b>0.12 /sf</b>	<b>16,160</b>
<b>C20 Stairs</b>	<b>136,600 sf</b>	<b>2.99 /sf</b>	<b>408,160</b>
<b>C30 Interior Finishes</b>			
<b>C3010 Wall Finishes</b>	<b>136,600 sf</b>	<b>11.51 /sf</b>	<b>1,571,556</b>
<b>C3020 Floor Finishes</b>	<b>136,600 sf</b>	<b>8.76 /sf</b>	<b>1,196,940</b>
<b>C3030 Ceiling Finishes</b>	<b>136,600 sf</b>	<b>17.08 /sf</b>	<b>2,333,715</b>
<b>C30 Interior Finishes</b>	<b>136,600 sf</b>	<b>37.35 /sf</b>	<b>5,102,210</b>
<b>C Interiors</b>	<b>136,600 sf</b>	<b>93.31 /sf</b>	<b>12,746,238</b>
<b>D Services</b>			
<b>D10 Conveying Systems</b>			
<b>D1010 Elevators &amp; Lifts</b>	<b>136,600 sf</b>	<b>1.61 /sf</b>	<b>220,450</b>
<b>D10 Conveying Systems</b>	<b>136,600 sf</b>	<b>1.61 /sf</b>	<b>220,450</b>
<b>D20 Plumbing</b>			
<b>D2010 Plumbing</b>	<b>136,600 sf</b>	<b>3.62 /sf</b>	<b>494,156</b>
<b>D2020 Domestic Water Distribution</b>	<b>136,600 sf</b>	<b>3.96 /sf</b>	<b>540,525</b>
<b>D2030 Sanitary Waste</b>	<b>136,600 sf</b>	<b>2.51 /sf</b>	<b>343,448</b>
<b>D2040 Rain Water Drainage</b>	<b>136,600 sf</b>	<b>1.62 /sf</b>	<b>221,676</b>
<b>D2090 Other Plumbing Systems</b>	<b>136,600 sf</b>	<b>3.63 /sf</b>	<b>495,194</b>
<b>D20 Plumbing</b>	<b>136,600 sf</b>	<b>15.34 /sf</b>	<b>2,094,999</b>
<b>D30 Heating, Ventilating, and Air Conditioning (HVAC)</b>			
<b>D3010 Energy Supply</b>	<b>136,600 sf</b>	<b>9.29 /sf</b>	<b>1,268,916</b>
<b>D3020 HVAC</b>	<b>136,600 sf</b>	<b>1.20 /sf</b>	<b>163,945</b>
<b>D3030 Cooling Generating Systems</b>	<b>136,600 sf</b>	<b>2.85 /sf</b>	<b>389,905</b>
<b>D3040 HVAC Distribution</b>	<b>136,600 sf</b>	<b>18.38 /sf</b>	<b>2,510,378</b>
<b>D3050 Terminal &amp; Package Units</b>	<b>136,600 sf</b>	<b>17.52 /sf</b>	<b>2,393,325</b>
<b>D3060 HVAC Instrumentation &amp; Controls</b>	<b>136,600 sf</b>	<b>5.49 /sf</b>	<b>749,864</b>
<b>D3070 Testing, Adjusting &amp; Balancing</b>	<b>136,600 sf</b>	<b>0.65 /sf</b>	<b>88,790</b>
<b>D3090 Other HVAC Systems &amp; Equipment</b>	<b>136,600 sf</b>	<b>3.66 /sf</b>	<b>499,829</b>
<b>D30 Heating, Ventilating, and Air Conditioning (HVAC)</b>	<b>136,600 sf</b>	<b>59.04 /sf</b>	<b>8,064,951</b>
<b>D40 Fire Protection Systems</b>			
<b>D4010 Sprinklers</b>	<b>136,600 sf</b>	<b>6.02 /sf</b>	<b>822,286</b>



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D4020 Standpipes</b>	136,600 sf	0.17 /sf	22,839
<b>D4030 Fire Protection Specialties</b>	136,600 sf	0.08 /sf	10,734
<b>D4090 Other Fire Protection Systems</b>	136,600 sf	0.13 /sf	18,000
<b>D40 Fire Protection Systems</b>	136,600 sf	6.40 /sf	873,859
<b>D50 Electrical Systems</b>			
<b>D5010 Gear &amp; Distribution</b>	136,600 sf	8.18 /sf	1,117,861
<b>D5020 Lighting &amp; Branch Wiring</b>	136,600 sf	13.46 /sf	1,838,194
<b>D5030 Communications &amp; Security</b>	136,600 sf	12.46 /sf	1,702,074
<b>D5090 Other Electrical Systems</b>	136,600 sf	3.95 /sf	538,839
<b>D50 Electrical Systems</b>	136,600 sf	38.05 /sf	5,196,968
<b>D Services</b>	136,600 sf	120.43 /sf	16,451,226
<b>E Equipment &amp; Furnishings</b>			
<b>E10 Equipment</b>			
<b>E1020 Institutional Equipment</b>	136,600 sf	12.06 /sf	1,646,689
<b>E1090 Other Equipment</b>	136,600 sf	0.18 /sf	24,600
<b>E10 Equipment</b>	136,600 sf	12.24 /sf	1,671,288
<b>E20 Furnishings</b>			
<b>E2010 Fixed Furnishings</b>	136,600 sf	11.23 /sf	1,533,465
<b>E20 Furnishings</b>	136,600 sf	11.23 /sf	1,533,465
<b>E Equipment &amp; Furnishings</b>	136,600 sf	23.46 /sf	3,204,754
<b>F Special Construction &amp; Demolition</b>			
<b>F20 Demolition</b>			
<b>F2010 Building Elements Demolition</b>	194,500 sf	7.03 /sf	1,367,800
<b>F2020 Hazardous Component Abatement</b>	194,500 sf	8.24 /sf	1,602,280
<b>F20 Demolition</b>	194,500 sf	15.27 /sf	2,970,080
<b>F Special Construction &amp; Demolition</b>	194,500 sf	15.27 /sf	2,970,080
<b>G Sitework</b>			
<b>G10 Site Preparation</b>			



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
G1010 Site Clearing	136,600 sf	/sf	
G1020 Site Demolition & Relocations	136,600 sf	0.07 /sf	9,000
G1030 Site Earthwork	136,600 sf	3.01 /sf	410,790
<b>G10 Site Preparation</b>	<b>136,600 sf</b>	<b>3.07 /sf</b>	<b>419,790</b>
<b>G20 Site Improvements</b>			
G2010 Roadways	136,600 sf	/sf	
G2020 Parking Lots	136,600 sf	/sf	
G2030 Pedestrian Paving	136,600 sf	0.14 /sf	19,265
G2040 Site Development	136,600 sf	3.15 /sf	430,650
G2050 Landscaping	136,600 sf	4.99 /sf	681,702
<b>G20 Site Improvements</b>	<b>136,600 sf</b>	<b>8.28 /sf</b>	<b>1,131,617</b>
<b>G30 Site Civil/Mechanical Utilites</b>			
G3010 Water Supply	136,600 sf	/sf	
G3020 Sanitary Sewer	136,600 sf	/sf	
G3030 Storm Drainage	136,600 sf	/sf	
G3060 Fuel Distribution	136,600 sf	/sf	
<b>G30 Site Civil/Mechanical Utilites</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>G40 Site Electrical Utilities</b>			
G4010 Electrical Distribution	136,600 sf	1.22 /sf	166,498
G4020 Site Lighting	136,600 sf	2.57 /sf	350,530
G4030 Site Communications & Security	136,600 sf	0.44 /sf	59,799
<b>G40 Site Electrical Utilities</b>	<b>136,600 sf</b>	<b>4.22 /sf</b>	<b>576,826</b>
<b>G Sitework</b>	<b>136,600 sf</b>	<b>15.58 /sf</b>	<b>2,128,233</b>





**Estimate Totals**

Description	Amount	Totals	Rate	Cost per Unit
Subtotal	<b>47,204,628</b>	<b>47,204,628</b>		<b>345.57 /sf</b>
Design/Estimate Contingency	1,416,139		3.000 %	10.37 /sf
Escalation	486,208		1.000 %	3.56 /sf
<b>Subtotal</b>	<b>1,902,347</b>	<b>49,106,975</b>		<b>359.49 /sf</b>
SDI (Non-Trade Contracts)	260,633		1.400 %	1.91 /sf
Sub Bonds (Trade Contracts)	400,232		1.400 %	2.93 /sf
Contractor's Contingency	1,244,196		2.500 %	9.11 /sf
General Conditions	2,931,033			21.46 /sf
General Requirements	2,289,380			16.76 /sf
<b>Subtotal</b>	<b>7,125,474</b>	<b>56,232,449</b>		<b>411.66 /sf</b>
Builder's Risk Insurance - BP1				
General Liability Insurance	576,109			4.22 /sf
Building Permit - NIC				
Performance & Payment Bond				
<b>Subtotal</b>	<b>576,109</b>	<b>56,808,558</b>		<b>415.88 /sf</b>
Fee	1,152,218			8.43 /sf
Amendment #1 - Sitework	10,957,843			80.22 /sf
- Addendum #3: Delete Traffic Table	(195,200)			(1.43) /sf
- Addendum #3: Reduced Fill at Amphitheater	(18,000)			(0.13) /sf
Amendment #2 - Concrete & Steel	8,738,800			63.97 /sf
Amendment #2 - Buy Savings	(50,755)			(0.37) /sf
<b>Total</b>		<b>77,393,464</b>		<b>566.57 /sf</b>





CONSIGLI  
*Est. 1905*





Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>A Substructure</b>			
<b>A10 Foundations</b>			
<b>A1010 Standard Foundations</b>			
Lull, laborer for cleanup by Consigli (Concrete)	(1) ls	116,000.00 /ls	(116,000)
Trade support - lull, laborer for cleanup (Concrete)	1 ls	116,000.00 /ls	116,000
<i>Elevator pit</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>F3 spread footings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>F4 spread footings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>F5 spread footings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>F6 spread footings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>F7 spread footings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>F8 spread footings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>F9 spread footings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>F10 spread footings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>F11 spread footings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>F12 spread footings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Continuous footings - 3'x12"</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Continuous footings - 4'x12"</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Continuous footings - 5'x12" @ Bandshell</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Foundation walls - 16"</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Foundation walls - 16" @ Bandshell</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Foundation walls - 21"</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Retaining walls - 16"</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Concrete walls @ Auditorium</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Piers - 24"x24"</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Grade beam 1</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Grade beam 2</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Foundation wall insulation</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Dampproofing at foundation wall</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Foundation wall waterproofing - membrane w/ drainage board</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Elevator pit waterproofing - cementitious</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Site cuts to site fills</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Excavation @ foundations</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Fill to subgrade @ building footprint - import (structural fill)</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Crushed stone base beneath column &amp; wall footings</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Excavate for elevator pits</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Dewatering</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Additional dewatering</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Site surcharge/rigid inclusion</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Rammed aggregate piers</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Rigid inclusions Gym and Auditorium</i>	<i>BP#1</i>	<i>/BP#1</i>	



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>A1010 Standard Foundations</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>A1030 Slab on Grade</b>			
<i>Slab depressions</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Slab on grade - 5"</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Power trowel/seal concrete @ Auditorium</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Underslab insulation (perimeter only)</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Crushed stone base beneath S.O.G</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Fine grade under building</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Excavate/backfill utilities under SOG by machine</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>A1030 Slab on Grade</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>A10 Foundations</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>A Substructure</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>B Shell</b>			
<b>B10 Superstructure</b>			
<b>B1010 Floor Construction</b>			
<i>Place &amp; finish slabs - 3-1/4" on 3" deck @ floor (LW)</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Topping slab @ Breakout LGMF floors</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Moment connections @ floor</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Steel @ floors</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Steel hangers - AEES</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Steel @ floors</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Steel @ Canopy - AEES</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Relieving angles @ brick veneer</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Shoring @ Learning Commons</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Metal floor decking - galvanized (3" 18g)</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Metal floor decking @ Breakout room LGMF floors</i>	<i>BP#2</i>	<i>/BP#2</i>	
Sprayed fireproofing - steel beams and columns @ floor structure	64,740 sf	3.00 /sf	194,220
Patch Sprayed fireproofing - floor structure	5 days	3,500.00 /days	17,500
<b>B1010 Floor Construction</b>	<b>136,600 sf</b>	<b>1.55 /sf</b>	<b>211,720</b>
<b>B1020 Roof Construction</b>			
<i>Place &amp; finish slabs - 2-1/2" on 3" deck @ roof</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Place &amp; finish slabs - 3-1/4" on 3" deck @ roof</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Moment connections @ roof</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Steel @ screen wall - galvanized</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Steel @ roof</i>	<i>BP#2</i>	<i>/BP#2</i>	



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>B1020 Roof Construction</b>			
<i>Steel dunnage - RTU &amp; chiller</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Open web joists, bridging</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Metal roof decking - acoustical (3" 18/16g)</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Metal roof decking - galvanized (1-1/2" 20g)</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Metal roof decking - acoustical (1-1/2" 20g)</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Metal roof decking - galvanized (3" 18g)</i>	<i>BP#2</i>	<i>/BP#2</i>	
Sprayed fireproofing - steel beams and columns @ roof structure below 20'	33,575 sf	3.00 /sf	100,725
Patch Sprayed fireproofing - roof structure	5 days	3,500.00 /days	17,500
Intumescent fireproofing @ Learning Commons	1 ls	72,000.00 /ls	72,000
<b>B1020 Roof Construction</b>	<b>136,600 sf</b>	<b>1.39 /sf</b>	<b>190,225</b>
<b>B10 Superstructure</b>	<b>136,600 sf</b>	<b>2.94 /sf</b>	<b>401,945</b>
<b>B20 Exterior Enclosure</b>			
<b>B2010 Exterior Walls</b>			
Exterior wall mockup - Masonry, Allowance	1 allw	7,500.00 /allw	7,500
<i>Exterior wall mockup - Steel, Allowance</i>	<i>BP#2</i>	<i>/BP#2</i>	
Exterior wall mockup - Siding, Allowance	1 allw	10,000.00 /allw	10,000
Exterior wall mockup - Waterproofing, Allowance	1 allw	5,000.00 /allw	5,000
Exterior wall mockup - Roofing, Allowance	1 allw	2,500.00 /allw	2,500
Exterior wall mockup - Drywall, Allowance	1 allw	10,000.00 /allw	10,000
Temporary bracing of CMU @ Gym and Auditorium	1 ls	100,000.00 /ls	100,000
Exterior staging	40,145 sf	2.50 /sf	100,363
Masonry winter conditions/heat	12 wks	5,000.00 /wks	60,000
Lull, laborer for cleanup by Consigli (Masonry)	(1) ls	77,000.00 /ls	(77,000)
Lull, laborer for cleanup by Consigli (Waterproofing)	(1) ls	29,000.00 /ls	(29,000)
Lull, laborer for cleanup by Consigli (Siding)	(1) ls	48,000.00 /ls	(48,000)
Trade support - lull, laborer for cleanup (Masonry)	1 ls	77,000.00 /ls	77,000
Trade support - lull, laborer for cleanup (Waterproofing)	1 ls	29,000.00 /ls	29,000
Trade support - lull, laborer for cleanup (Siding)	1 ls	48,000.00 /ls	48,000
<b>Precast planters - N/A</b>	-	/-	
Install loose lintels (< 8")	14 ea	150.00 /ea	2,100
4x4x12 iron spot brick veneer, scored	6,105 sf	36.00 /sf	219,780
4x8x8 iron spot brick veneer, scored	6,750 sf	36.00 /sf	243,000
Brick veneer, precast cap @ entry wall per A102A	25 lf	285.00 /lf	7,125
Sill brick/lip brick - Premium	12,885 sf	2.00 /sf	25,770
4x4x12 scored ground faced CMU veneer	3,680 sf	27.00 /sf	99,360
4x8x16 scored ground faced CMU veneer	23,615 sf	29.00 /sf	684,835
Sill brick/lip brick - Premium	27,295 sf	2.00 /sf	54,590



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>B2010 Exterior Walls</b>			
CMU - 12" exterior wall	15,795 sf	25.00 /sf	394,875
Loose lintels - Furnish	95 lf	25.00 /lf	2,375
Guardrails - 42" galvanized perforated @ exterior	105 lf	500.00 /lf	52,500
Guardrails - 42" galvanized perforated @ terrace	30 lf	500.00 /lf	15,000
Misc. caulking & sealants @ exterior	73,210 sf	0.75 /sf	54,908
Mineral wool insulation at brick/CMU veneer	40,145 sf	3.50 /sf	140,508
Air and vapor barrier @ exterior walls	56,650 sf	7.50 /sf	424,875
Air and vapor barrier @ soffits	1,245 sf	7.50 /sf	9,338
Air and vapor barrier @ phenolic fins per A102A, A315	380 sf	7.50 /sf	2,850
Corrugated, perforated metal siding @ screen walls	1,105 sf	45.00 /sf	49,725
Exposed fastener metal panel	6,065 sf	48.00 /sf	291,120
Composite metal panel siding	3,120 sf	75.00 /sf	234,000
Phenolic panel siding	7,705 sf	80.00 /sf	616,400
Metal louver	625 sf	85.00 /sf	53,125
Exterior walls - 10" studs, 1/2" sheathing, 5/8" GWB, insulation	44,220 sf	23.50 /sf	1,039,170
Framing @ phenolic fins per A102A, A315	380 sf	7.65 /sf	2,907
Exterior soffit framing, sheathing, insulation	1,245 sf	23.90 /sf	29,756
Misc. exterior painting	73,210 sf	0.50 /sf	36,605
<b>B2010 Exterior Walls</b>	<b>136,600 sf</b>	<b>37.20 /sf</b>	<b>5,081,958</b>
<b>B2020 Exterior Windows</b>			
Exterior wall mockup - Windows, Allowance	1 allw	20,000.00 /allw	20,000
Lull, laborer for cleanup by Consigli (Windows)	(1) ls	73,000.00 /ls	(73,000)
Trade support - lull, laborer for cleanup (Windows)	1 ls	73,000.00 /ls	73,000
Window blocking	7,425 lf	12.75 /lf	94,669
Door blocking - exterior	265 lf	13.85 /lf	3,671
Caulking @ storefront/curtainwall	7,425 lf	4.00 /lf	29,700
Window transitions	7,425 lf	10.00 /lf	74,250
Aluminum storefront/windows	11,555 sf	100.00 /sf	1,155,500
Aluminum storefront - School Guard	545 sf	140.00 /sf	76,300
Extruded aluminum perimeter angles	7,425 lf	30.00 /lf	222,750
<b>B2020 Exterior Windows</b>	<b>136,600 sf</b>	<b>12.28 /sf</b>	<b>1,676,839</b>
<b>B2030 Exterior Doors</b>			
Install exterior door, HW	14 ea	300.00 /ea	4,200
HM doors - exterior flush	23 lvs	625.00 /lvs	14,375
HM frames - exterior single	5 ea	255.00 /ea	1,275
HM frames - exterior double	9 ea	440.00 /ea	3,960
Overhead coiling door	1 ea	7,500.00 /ea	7,500
Aluminum entrance doors, HW - exterior	4 lvs	6,000.00 /lvs	24,000





# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>B2030 Exterior Doors</b>			
Aluminum entrance doors, HW - exterior, School Guard	11 lvs	7,000.00 /lvs	77,000
Hardware sets - exterior door/panic	14 set	1,920.01 /set	26,880
Hardware sets - auto operators	1 set	4,500.00 /set	4,500
Install HM door frames - exterior single	5 ea	73.00 /ea	365
Install HM door frames - exterior double	9 ea	117.00 /ea	1,053
Paint HM doors - exterior	23 lvs	90.00 /lvs	2,070
Paint HM frames - exterior, single	5 ea	50.00 /ea	250
Paint HM frames - exterior, double	9 ea	60.00 /ea	540
<b>B2030 Exterior Doors</b>	<b>136,600 sf</b>	<b>1.23 /sf</b>	<b>167,968</b>
<b>B20 Exterior Enclosure</b>	<b>136,600 sf</b>	<b>50.71 /sf</b>	<b>6,926,765</b>
<b>B30 Roofing</b>			
<b>B3010 Roof Coverings</b>			
Roof blocking	5,390 lf	32.00 /lf	172,480
PVC membrane roof w/insulation, underlayment, cover board, vapor barrier	63,155 sf	19.00 /sf	1,199,945
Additional layer of protection board	7,565 sf	3.00 /sf	22,695
PVC membrane @ walls	2,740 sf	20.25 /sf	55,485
Reinforced walkway pads	715 sf	7.50 /sf	5,363
Pavers - terrace	295 sf	35.00 /sf	10,325
Pavers - main entrance	780 sf	35.00 /sf	27,300
Roof accessories	63,155 sf	0.35 /sf	22,104
Roof vents & hatches	1 ls	25,000.00 /ls	25,000
Metal roof fascia	2,695 lf	35.00 /lf	94,325
Additional flashing, scuppers	63,155 sf	0.75 /sf	47,366
Polycarbonate glazing @ canopy	440 sf	150.00 /sf	66,000
Polycarbonate glazing @ canopy - VM E01	(440) sf	150.00 /sf	(66,000)
<b>B3010 Roof Coverings</b>	<b>136,600 sf</b>	<b>12.32 /sf</b>	<b>1,682,388</b>
<b>B3020 Roof Openings</b>			
Metal-framed skylights (8:12)	4,130 sf	150.00 /sf	619,500
Metal-framed skylights gable ends	490 sf	150.00 /sf	73,500
<b>B3020 Roof Openings</b>	<b>136,600 sf</b>	<b>5.07 /sf</b>	<b>693,000</b>
<b>B30 Roofing</b>	<b>136,600 sf</b>	<b>17.39 /sf</b>	<b>2,375,388</b>
<b>B Shell</b>	<b>136,600 sf</b>	<b>71.04 /sf</b>	<b>9,704,098</b>



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>C Interiors</b>			
<b>C10 Interior Construction</b>			
<b>C1010 Partitions</b>			
Lull, laborer for cleanup by Consigli (Drywall)	(1) ls	188,000.00 /ls	(188,000)
Trade support - lull, laborer for cleanup (Drywall)	1 ls	188,000.00 /ls	188,000
CMU - 12" interior wall	6,890 sf	25.00 /sf	172,250
CMU - acoustical block, premium	1,000 sf	7.50 /sf	7,500
White CMU - Premium	1 ls	75,000.00 /ls	75,000
White CMU - Premium - VM E02	(1) ls	75,000.00 /ls	(75,000)
White CMU - Premium - VM E02	41,220 sf	2.00 /sf	82,440
CMU - ground face block @ exterior, premium - VM E02	(27,295) sf	6.00 /sf	(163,770)
CMU - ground face block @ interior, premium	1 ls	35,000.00 /ls	35,000
CMU - ground face block @ interior, premium - VM E02	(1) ls	35,000.00 /ls	(35,000)
CMU - ground face block @ Auditorium, premium - VM E02	8,760 sf	6.00 /sf	52,560
Light gage metal framing @ Breakout floors	1,440 sf	60.00 /sf	86,400
Light gage metal framing @ Breakout walls	16,820 sf	25.00 /sf	420,500
Misc. metal fabrications	136,600 sf	1.50 /sf	204,900
Seismic clips - 4' OC, each side	270 ea	60.00 /ea	16,200
Support for HVAC enclosure	1 ls	40,000.00 /ls	40,000
<b>Steel angles/stantions @ locker guardrail</b>	<b>BP#2</b>	<b>/BP#2</b>	
Handrail @ steps/ramps	55 lf	295.00 /lf	16,225
Cane rails	120 lf	200.00 /lf	24,000
In-wall blocking	12,160 lf	12.75 /lf	155,040
Miscellaneous rough carpentry - Allowance	136,600 sf	0.50 /sf	68,300
Caulking & sealants @ interior	136,600 sf	0.90 /sf	122,940
Firestopping @ rated walls	5,630 lf	16.20 /lf	91,206
Miscellaneous firestopping	136,600 sf	0.10 /sf	13,660
Aluminum storefront - interior, School Guard	340 sf	140.00 /sf	47,600
Aluminum windows - interior, School Guard	2 ea	12,000.00 /ea	24,000
Misc. interior glass & glazing	136,600 sf	0.25 /sf	34,150
Glazed partition	4,700 sf	60.00 /sf	282,000
Glazed partition - double acoustic	625 sf	110.00 /sf	68,750
Glazed partition @ sidelights	1,165 sf	75.00 /sf	87,375
Glass walls @ Breakout	2,323 sf	100.00 /sf	232,300
<b>Glass roof @ Breakout - N/A</b>	-	/-	
Glass roof @ canopy - VM E01	82 sf	150.00 /sf	12,300
Graduated glass film	3,675 sf	5.00 /sf	18,375
3M Safety and Security Window Film @ glass walls	4,090 sf	15.00 /sf	61,350
3M Safety and Security Window Film @ doors	67 lvs	450.00 /lvs	30,150
Level 5 finish - Allowance	25,000 sf	2.55 /sf	63,750
Interior wall framing - 2-1/2"	3,370 sf	5.75 /sf	19,378



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>C1010 Partitions</b>			
Interior wall framing - 3-5/8"/4"	96,355 sf	5.75 /sf	554,041
Interior wall framing - 6"	7,050 sf	7.65 /sf	53,933
Interior wall framing - 8"	21,965 sf	10.15 /sf	222,945
Interior wall framing - 10"	555 sf	12.10 /sf	6,716
GWB - 5/8", level 4	229,230 sf	4.15 /sf	951,305
GWB - 5/8", additional layer	96,320 sf	3.50 /sf	336,627
GWB - high impact	1 ls	50,000.00 /ls	50,000
Shaft liner - 1"	2,420 sf	4.15 /sf	10,043
Sound batt insulation	137,275 sf	1.60 /sf	219,640
Half height walls @ Auditorium	400 sf	22.90 /sf	9,160
LGMF framing @ locker guardrail	4,095 sf	5.10 /sf	20,885
GWB - 5/8", level 5 @ locker guardrail	4,095 sf	6.70 /sf	27,437
Curved walls - premium	5,205 sf	6.35 /sf	33,074
Patch GWB	136,600 sf	0.35 /sf	47,810
Operable partitions w/writeable surface on one side	325 sf	77.00 /sf	25,025
Operable partitions w/writeable surface on both sides	2,740 sf	98.00 /sf	268,520
<b>C1010 Partitions</b>	<b>136,600 sf</b>	<b>38.28 /sf</b>	<b>5,228,988</b>
<b>C1020 Interior Doors</b>			
Door blocking - interior	4,965 lf	13.85 /lf	68,772
Install interior door, HW	300 ea	300.00 /ea	90,000
HM doors - interior - flush	45 lvs	310.00 /lvs	13,950
HM frames - interior single	258 ea	310.00 /ea	79,980
HM frames - interior single, tandem	13 ea	360.00 /ea	4,680
HM frames - interior double	29 ea	385.00 /ea	11,165
Wood door - interior flush	297 lvs	390.00 /lvs	115,830
Fire rated wood doors - premium	44 lvs	390.00 /lvs	17,160
Acoustical doors (STC 45) - premium	1 ls	15,000.00 /ls	15,000
Access panels	1 ls	15,000.00 /ls	15,000
Coiling security screen - 4' high, manual	85 sf	70.00 /sf	5,950
Coiling security screen - 8' high, manual	690 sf	70.00 /sf	48,300
Custom security gate @ Learning Commons	2 lvs	6,000.00 /lvs	12,000
Aluminum entrance doors, HW - interior	1 lvs	6,000.00 /lvs	6,000
Aluminum entrance doors, HW - interior, School Guard	8 lvs	7,000.00 /lvs	56,000
Hardware sets - standard interior	287 set	1,015.00 /set	291,305
Hardware sets - interior, tandem	13 set	1,330.00 /set	17,290
Automatic operators	3 pair	4,400.00 /pair	13,200
Door glazing - full	159 ea	400.00 /ea	63,600
Door glazing - narrow	2 ea	100.00 /ea	200
Install HM door frames - interior single	271 ea	73.00 /ea	19,783



### 90% CD Reconciled Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>C1020 Interior Doors</b>			
Install HM door frames - interior double	29 ea	117.00 /ea	3,393
Paint HM doors - interior	45 lvs	90.00 /lvs	4,050
Paint HM frames - interior, single	271 ea	50.00 /ea	13,550
Paint HM frames - interior, double	29 ea	60.00 /ea	1,740
<b>C1020 Interior Doors</b>	<b>136,600 sf</b>	<b>7.23 /sf</b>	<b>987,898</b>
<b>C1030 Specialties/Millwork</b>			
Guardrails @ Atrium	380 lf	500.00 /lf	190,000
Perforated architectural grille @ stage front	120 sf	200.00 /sf	24,000
Perforated architectural ceiling grille	210 sf	200.00 /sf	42,000
Window sills - P-lam	1,100 lf	25.00 /lf	27,500
Wood louvered shades - Rulon panel grille	450 lf	150.00 /lf	67,500
Mirrors - unframed restroom	1,145 sf	35.00 /sf	40,075
Interior signage	136,600 sf	0.35 /sf	47,810
Toilet partition	23 ea	1,020.00 /ea	23,460
Toilet partition - handicap	16 ea	1,650.00 /ea	26,400
Urinal screens - wall-hung	15 ea	433.00 /ea	6,495
Cubicle curtains	45 lf	40.00 /lf	1,800
Cubicle curtain track	45 lf	11.50 /lf	518
Corner guards	1 ls	20,000.00 /ls	20,000
Toilet paper dispenser	54 ea	105.17 /ea	5,679
Grab bar	62 ea	141.38 /ea	8,765
Soap dispenser - surface mounted	59 ea	87.64 /ea	5,171
Paper towel dispenser - recessed	32 ea	136.79 /ea	4,377
Framed mirrors	15 ea	171.00 /ea	2,565
Sanitary napkin disposal	46 ea	274.00 /ea	12,604
Shower curtains, hooks & rod	3 ea	125.00 /ea	375
Shower seat	2 ea	668.00 /ea	1,336
Mop rack	3 ea	230.67 /ea	692
Fire extinguisher cabinet - fully recessed	27 ea	350.00 /ea	9,450
Student lockers - phenolic	660 ea	580.00 /ea	382,800
Athletic lockers	80 ea	350.00 /ea	28,000
Staff lockers	12 ea	400.00 /ea	4,800
Locker benches	12 lf	55.00 /lf	660
Misc. specialties - Allowance	136,600 sf	0.25 /sf	34,150
<b>C1030 Specialties/Millwork</b>	<b>136,600 sf</b>	<b>7.46 /sf</b>	<b>1,018,982</b>
<b>C10 Interior Construction</b>	<b>136,600 sf</b>	<b>52.97 /sf</b>	<b>7,235,868</b>

### C20 Stairs



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>C2010 Stair Construction</b>			
<i>Place &amp; finish stair treads/landings</i>	<i>BP#2</i>	<i>/BP#2</i>	
Ornamental stairs 3 and 6 - excluding rails	2 flt	60,000.00 /flt	120,000
Egress stair	5 flt	30,000.00 /flt	150,000
<i>Ornamental stairs 4 and 5 - excluding rails</i>	<i>BP#2</i>	<i>/BP#2</i>	
Roof ladders	3 ea	1,500.00 /ea	4,500
Guardrails @ Atrium stairs	235 lf	500.00 /lf	117,500
<b>C2010 Stair Construction</b>	<b>136,600 sf</b>	<b>2.87 /sf</b>	<b>392,000</b>
<b>C2020 Stair Finishes</b>			
Rubber flooring @ ornamental stairs	770 sf	8.00 /sf	6,160
Paint egress stairs	5 flt	2,000.00 /flt	10,000
<b>C2020 Stair Finishes</b>	<b>136,600 sf</b>	<b>0.12 /sf</b>	<b>16,160</b>
<b>C20 Stairs</b>	<b>136,600 sf</b>	<b>2.99 /sf</b>	<b>408,160</b>
<b>C30 Interior Finishes</b>			
<b>C3010 Wall Finishes</b>			
Lull, laborer for cleanup by Consigli (Tile)	(1) ls	7,000.00 /ls	(7,000)
Trade support - lull, laborer for cleanup (Tile)	1 ls	7,000.00 /ls	7,000
<b>Brick veneer - interior - N/A</b>	-	-	
1/4" steel plate @ tile	1 ls	15,000.00 /ls	15,000
Miscellaneous wood base/trim	136,600 sf	0.50 /sf	68,300
Trim @ Breakout D glass lights	320 sf	25.00 /sf	8,000
Head and sill MDF trim per 1,2/A620	1,700 lf	25.00 /lf	42,500
P-lam panel	1,440 sf	45.00 /sf	64,800
P-lam panel backsplash	120 sf	45.00 /sf	5,400
Marker tray - bamboo	2,485 lf	30.00 /lf	74,550
MDF bumper rail	3,715 lf	25.00 /lf	92,875
P-lam wall panels - sound reflecting @ Auditorium	2,925 sf	45.00 /sf	131,625
P-lam wall panels - vestibules	400 sf	45.00 /sf	18,000
P-lam projector enclosure @ Auditorium	1 ea	2,500.00 /ea	2,500
Ceramic wall tile	2,295 sf	18.00 /sf	41,310
Quarry tile base	280 lf	20.00 /lf	5,600
Linoleum tile base w/trim	19,260 lf	9.00 /lf	173,340
Linoleum tile base w/trim - VM I10	(15,545) lf	9.00 /lf	(139,905)
Linoleum tile base - VM I10	15,545 lf	7.00 /lf	108,815
Rubber base	2,175 lf	3.50 /lf	7,613
Vented base @ Gym	370 lf	8.00 /lf	2,960
Fiberglass reinforced panels (FRP) - wall panels	2,240 sf	8.00 /sf	17,920
Fabric wrapped acoustical panels	12,275 sf	20.00 /sf	245,500



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>C3010 Wall Finishes</b>			
Tectum wall panels	5,535 sf	18.00 /sf	99,630
<b>Mural panorama wall covering - By Others</b>	-	/-	
Paint GWB partitions	227,710 sf	0.80 /sf	182,168
<b>Paint CMU - N/A</b>	-	/-	
Epoxy wall paint	15,550 sf	2.30 /sf	35,765
Touchup	136,600 sf	0.50 /sf	68,300
Magnetic writeable wall covering	9,045 sf	22.00 /sf	198,990
<b>C3010 Wall Finishes</b>	<b>136,600 sf</b>	<b>11.51 /sf</b>	<b>1,571,556</b>
<b>C3020 Floor Finishes</b>			
Lull, laborer for cleanup by Consigli (Resilient)	(1) ls	48,000.00 /ls	(48,000)
Trade support - lull, laborer for cleanup (Resilient)	1 ls	48,000.00 /ls	48,000
<b>Polished concrete @ Auditorium - N/A</b>	-	/-	
<b>Wood base - N/A</b>	-	/-	
Porcelain floor tile	5,475 sf	25.00 /sf	136,875
Quarry floor tile	1,770 sf	20.00 /sf	35,400
Underlayment at 2nd and 3rd floor linoleum - Forbo NR99, exclude corridors	36,505 sf	4.00 /sf	146,020
<b>Moisture mitigation - Excluded</b>	-	/-	
Hardwood stage assembly	1,610 sf	25.00 /sf	40,250
Wood athletic flooring	8,570 sf	20.00 /sf	171,400
Linoleum tile	90,135 sf	6.00 /sf	540,810
Epoxy flooring/base	5,780 sf	14.00 /sf	80,920
Carpet @ Auditorium	135 sy	45.00 /sy	6,075
Seal concrete floor	7,245 sf	2.00 /sf	14,490
Seal concrete floor @ Auditorium	3,650 sf	2.00 /sf	7,300
Entry mats - recessed	435 sf	40.00 /sf	17,400
<b>C3020 Floor Finishes</b>	<b>136,600 sf</b>	<b>8.76 /sf</b>	<b>1,196,940</b>
<b>C3030 Ceiling Finishes</b>			
Dance floor at auditorium - multi-trade	1 ls	75,000.00 /ls	75,000
Lull, laborer for cleanup by Consigli (Finish Carpentry)	(1) ls	72,000.00 /ls	(72,000)
Lull, laborer for cleanup by Consigli (Ceilings)	(1) ls	49,000.00 /ls	(49,000)
Trade support - lull, laborer for cleanup (Finish Carpentry)	1 ls	72,000.00 /ls	72,000
Trade support - lull, laborer for cleanup (Ceilings)	1 ls	49,000.00 /ls	49,000
P-lam panel on Z-clips @ Breakout	325 sf	45.00 /sf	14,625
Suspended P-lam clouds @ Auditorium	100 ea	2,000.00 /ea	200,000
Gypsum board ceilings	21,010 sf	15.25 /sf	320,411
Gypsum board ceilings - 1 hr	655 sf	19.10 /sf	12,511
Gypsum board ceilings - 2 hr	80 sf	22.90 /sf	1,832



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>C3030 Ceiling Finishes</b>			
Gypsum board ceilings - resilient	5,350 sf	31.75 /sf	169,863
Stucco soffit	1,245 sf	11.35 /sf	14,131
Gypsum board soffits	28,335 sf	25.45 /sf	721,126
Gypsum board soffits - VM I11	(2,250) sf	25.45 /sf	(57,263)
Gypsum board soffits @ Learning Commons	4,920 sf	25.45 /sf	125,214
Gypsum board soffits @ Skylights	1,915 sf	25.45 /sf	48,737
A1 - Armstrong Ultima #1911, random running bond pattern	21,400 sf	9.00 /sf	192,600
A1 - Armstrong Ultima #1911 @ Learning Commons corridors	9,980 sf	9.00 /sf	89,820
A2 - Armstrong Calla #2824	20,985 sf	8.00 /sf	167,880
A2 - Armstrong Calla #2824 - VM I03	1,393 sf	8.00 /sf	11,144
A3 - USG Geometrix 3 Dimensional	3,815 sf	35.00 /sf	133,525
A3 - USG Geometrix 3 Dimensional - VM I03	(1,393) sf	35.00 /sf	(48,755)
A4 - Armstrong Healthzone Ultima	1,760 sf	7.00 /sf	12,320
Paint GWB ceilings	21,735 sf	1.00 /sf	21,735
Paint GWB soffits	35,170 sf	1.00 /sf	35,170
Paint exposed ceilings	24,085 sf	1.50 /sf	36,128
Paint exposed ceilings @ Gym and Auditorium	14,385 sf	2.50 /sf	35,963
<b>C3030 Ceiling Finishes</b>	<b>136,600 sf</b>	<b>17.08 /sf</b>	<b>2,333,715</b>
<b>C30 Interior Finishes</b>	<b>136,600 sf</b>	<b>37.35 /sf</b>	<b>5,102,210</b>
<b>C Interiors</b>	<b>136,600 sf</b>	<b>93.31 /sf</b>	<b>12,746,238</b>
<b>D Services</b>			
<b>D10 Conveying Systems</b>			
<b>D1010 Elevators &amp; Lifts</b>			
Elevator pit ladders	1 ea	450.00 /ea	450
Passenger elevators - cab, equipment	1 ls	40,000.00 /ls	40,000
Passenger elevators - stops	4 stop	45,000.00 /stop	180,000
<b>D1010 Elevators &amp; Lifts</b>	<b>136,600 sf</b>	<b>1.61 /sf</b>	<b>220,450</b>
<b>D10 Conveying Systems</b>	<b>136,600 sf</b>	<b>1.61 /sf</b>	<b>220,450</b>
<b>D20 Plumbing</b>			
<b>D2010 Plumbing</b>			
Lull, laborer for cleanup by Consigli (Plumbing)	(1) ls	83,000.00 /ls	(83,000)
Trade support - lull, laborer for cleanup (Plumbing)	1 ls	83,000.00 /ls	83,000
Water closet/wall mnt./carrier/flush valve	22 ea	1,330.12 /ea	29,263



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D2010 Plumbing</b>			
Water closet/wall mnt./carrier/flush valve/ADA	32 ea	1,367.52 /ea	43,761
Urinal/wall mnt./carrier/flush valve	18 ea	1,202.85 /ea	21,651
Urinal/wall mnt./carrier/flush valve/ADA	5 ea	1,241.35 /ea	6,207
Lavatory/undermount/std 1-lever faucet	54 ea	523.24 /ea	28,255
Lavatory/undermount/std 1-lever faucet/ADA	10 ea	586.41 /ea	5,864
Lavatory/wall hung/std 1-lever faucet/carrier/ADA	15 ea	1,147.55 /ea	17,213
Sensor faucets/flush	1 ls	78,000.00 /ls	78,000
Mixing valve/single lav. (Leonard #170)	85 ea	348.84 /ea	29,651
P15 Sink/lay-in/1-bowl 20"x22"/std faucet/ADA	2 ea	1,560.75 /ea	3,121
P14 Sink/lay-in/1-bowl 20"x22"/std faucet/ADA Maker Space	2 ea	1,610.75 /ea	3,221
P7 Sink/lay-in/1-bowl 21"x15"/std faucet	36 ea	1,584.98 /ea	57,059
P9 Sink/lay-in/1-bowl 21"x15"/std faucet Art Room	3 ea	1,384.98 /ea	4,155
P9A Sink/lay-in/1-bowl 21"x15"/std faucet/ADA Art Room	1 ea	1,455.75 /ea	1,456
P7A Sink/lay-in/1-bowl 21"x15"/std faucet/ADA	3 ea	1,860.75 /ea	5,582
P8 Sink/lay-in/1-bowl/22"x16"/bubbler	5 ea	1,715.35 /ea	8,577
P-13 Sink/acid waste/undermount/std 2-lever faucet/ss - 21"x15"x10"D	3 ea	1,508.82 /ea	4,526
- Solids interceptors (Art Room sinks)	4 ea	552.64 /ea	2,211
Mop sink/floor mnt - 24"x24"	5 ea	1,349.01 /ea	6,745
P6 Shower stall/std valve & access./3'x3' fiberglass	1 ea	2,704.96 /ea	2,705
P6-A Shower stall/std valve & access./5'x3' fiberglass/ADA	2 ea	3,701.67 /ea	7,403
P13 Emergency eye wash station/mixing valve/sink mount	3 ea	1,106.71 /ea	3,320
Emergency shower/eye wash sta./mixing valve/cabinet mount	7 ea	3,540.35 /ea	24,782
Water cooler/bi-level/ADA	10 ea	4,418.42 /ea	44,184
- Plumbing fixtures offload & distribution	239 ea	103.07 /ea	24,634
- Plumbing fixtures rough-in	239 ea	128.07 /ea	30,609
<b>D2010 Plumbing</b>	<b>136,600 sf</b>	<b>3.62 /sf</b>	<b>494,156</b>
<b>D2020 Domestic Water Distribution</b>			
Insulation/copper pipe/fiberglass	7,975 lf	8.44 /lf	67,307
Water meter w/remote readout - 4"	1 ea	2,285.75 /ea	2,286
Water sub-meter - avg. size	1 ea	1,561.84 /ea	1,562
Water sub-meter - 1.5 Circ	1 ea	1,261.84 /ea	1,262
Water sub-meter - 2" Domestic WH	1 ea	1,277.30 /ea	1,277
Backflow preventer/RPZ-BFP - dishwasher	1 ea	1,809.21 /ea	1,809
Backflow preventer/RPZ-BFP - 2" LW	2 ea	1,657.68 /ea	3,315
Backflow preventer/RPZ-BFP - 4"	1 ea	1,960.75 /ea	1,961
Pressure reducing valve/PRV - 1"	1 ea	1,159.21 /ea	1,159
Pressure reducing valve - 4"	1 ea	2,210.75 /ea	2,211
Recirculation pump/bronze/6.5 gpm - 1/8 hp (B&G Ecocirc)	1 ea	1,806.14 /ea	1,806





# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D2020 Domestic Water Distribution</b>			
Recirculation pump/bronze/10 gpm - 1/6 hp (B&G #SSF-22)	2 ea	709.14 /ea	1,418
Expansion tank/ASME/potable - 9 gal (B&G #PTA-30V)	1 ea	1,250.61 /ea	1,251
TMV/master/hi-lo temp.	1 ea	2,759.21 /ea	2,759
Hose bibbs w/vac. breaker/encased - interior	19 ea	382.50 /ea	7,268
Hose bibbs/exterior/encased (Zurn #Z1320)	3 ea	452.07 /ea	1,356
Trap primers/electronic - 8 outlet (PPP #PT-8)	8 ea	1,359.91 /ea	10,879
Shock absorbers/12 - 33 fixture units (Shoktrol #200)	3 ea	269.77 /ea	809
Valve box/washing machine	1 ea	226.54 /ea	227
Valve box/ice machine	3 ea	176.54 /ea	530
Domestic water entrance UG/ductile iron - 4"	20 lf	306.14 /lf	6,123
Domestic water AG/type "L" copper/press fit ftgs. - avg. size	525 lf	23.31 /lf	12,235
Domestic water AG/type "L" copper/press fit - 1/2" TP	1,120 lf	13.02 /lf	14,577
Domestic water AG/type "L" copper/press fit - 1/2" NP	800 lf	13.02 /lf	10,412
Domestic water AG/type "L" copper/press fit - 1/2"	1,460 lf	13.02 /lf	19,002
Domestic water AG/type "L" copper/press fit - 3/4" NP	450 lf	15.76 /lf	7,091
Domestic water AG/type "L" copper/press fit - 3/4"	1,240 lf	15.76 /lf	19,539
Domestic water AG/type "L" copper/press fit - 1" NP	100 lf	20.56 /lf	2,056
Domestic water AG/type "L" copper/press fit - 1"	50 lf	20.57 /lf	1,028
Domestic water AG/type "L" copper/press fit - 1-1/4" NP	100 lf	25.23 /lf	2,523
Domestic water AG/type "L" copper/press fit - 1-1/4"	115 lf	25.23 /lf	2,902
Domestic water AG/type "L" copper/press fit - 1-1/2"	400 lf	30.31 /lf	12,125
Domestic water AG/type "L" copper/press fit - 2" NP	450 lf	41.16 /lf	18,523
Domestic water AG/type "L" copper/press fit - 2"	300 lf	41.16 /lf	12,349
Domestic water AG/type "L" copper/press fit - 2-1/2"	285 lf	66.38 /lf	18,919
Domestic water AG/type "L" copper/press fit - 3"	480 lf	84.91 /lf	40,759
Domestic water AG/type "L" copper/press fit - 4"	100 lf	116.00 /lf	11,600
Non-potable water AG/type "L" copper/solder - Hood Tie In	60 lf	22.94 /lf	1,377
- Domestic water piping accessories DOM	6,095 lf	2.78 /lf	16,917
- Domestic water piping accessories NP	1,900 lf	2.78 /lf	5,274
- Domestic water heat tracing/small bore piping All LHW	1,900 lf	25.97 /lf	49,340
- Domestic water pipe & equipment I.D. DOM	6,095 lf	1.61 /lf	9,817
- Domestic water pipe & equipment I.D. NP	1,900 lf	1.52 /lf	2,881
- Domestic water pressure gauges & thermometers	12 ea	120.61 /ea	1,447
- Domestic water support steel/additional to hangers & clamps	1 ls	1,074.56 /ls	1,075
- Layout Mech Room	1 ls	20,000.00 /ls	20,000
- Domestic water storage tank	1 ls	3.52 /ls	4
Domestic Boilers/gas fired/399 mbh (AO Smith #BTH-300A)	2 ea	15,618.42 /ea	31,237
Boiler Flues	1 ls	45,525.00 /ls	45,525
Water Heater Flues	1 ls	24,000.00 /ls	24,000
HWH/indirect fed - 300 gal	1 ea	7,418.42 /ea	7,418



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D2020 Domestic Water Distribution</b>	<b>136,600 sf</b>	<b>3.96 /sf</b>	<b>540,525</b>
<b>D2030 Sanitary Waste</b>			
Floor drain - 3" (#ZN415-6B)	16 ea	294.07 /ea	4,705
Floor drain - 4" (#ZN415-8B)	4 ea	353.07 /ea	1,412
Floor sink/12x12 - 4" (#Z1900)	8 ea	2,581.14 /ea	20,649
Floor cleanouts - 4" (#ZN1400)	37 ea	291.07 /ea	10,770
Wall cleanouts - 4" (#Z1468)	10 ea	101.08 /ea	1,011
Grease interceptor/interior/size 800/75 gpm/150 gal.	2 ea	4,291.56 /ea	8,583
8000 Gallon Concrete Grease Trap	1 ea	17,649.12 /ea	17,649
Elevator sump pump/oil minder	1 ea	3,812.28 /ea	3,812
Grease interceptor flow control	1 ea	417.14 /ea	417
Sanitary UG/cast iron single hub pipe & ftgs. - 2"	220 lf	31.98 /lf	7,036
Sanitary UG/cast iron single hub pipe & ftgs. - 3"	236 lf	36.45 /lf	8,602
Sanitary UG/cast iron single hub pipe & ftgs. - 4"	610 lf	44.78 /lf	27,315
Sanitary UG/cast iron single hub pipe & ftgs. - 6"	275 lf	74.82 /lf	20,576
Sanitary AG/cast iron no hub pipe & ftgs. - avg. size Fixture Runouts	1,560 lf	47.33 /lf	73,828
Sanitary AG/cast iron no hub pipe & ftgs. - 1-1/2"	30 lf	33.82 /lf	1,015
Sanitary AG/cast iron no hub pipe & ftgs. - 2"	750 lf	34.83 /lf	26,119
Sanitary AG/cast iron no hub pipe & ftgs. - 3"	980 lf	44.36 /lf	43,468
Sanitary AG/cast iron no hub pipe & ftgs. - 4"	495 lf	52.52 /lf	25,999
Grease waste UG/cast iron single hub pipe & ftgs. - 2"	40 lf	31.98 /lf	1,279
Grease waste UG/cast iron single hub pipe & ftgs. - 3"	20 lf	36.45 /lf	729
Grease waste UG/cast iron single hub pipe & ftgs. - 4"	220 lf	44.78 /lf	9,851
Grease waste AG/cast iron no hub pipe & ftgs. - 2"	55 lf	34.83 /lf	1,915
Grease waste AG/cast iron no hub pipe & ftgs. - 3"	65 lf	44.36 /lf	2,883
Grease waste AG/cast iron no hub pipe & ftgs. - 4"	70 lf	52.52 /lf	3,677
- Sanitary waste & vent piping accessories	5,626 lf	1.77 /lf	9,976
- Sanitary piping & equipment I.D.	5,626 lf	1.81 /lf	10,171
<b>D2030 Sanitary Waste</b>	<b>136,600 sf</b>	<b>2.51 /sf</b>	<b>343,448</b>
<b>D2040 Rain Water Drainage</b>			
Insulation/rainleader pipe/fiberglass/PVC jacketed/horiz. & vert.	1,200 lf	40.61 /lf	48,737
Roof drain/#ZC100 - 4"	9 ea	298.07 /ea	2,683
Roof drain/#ZC100 - 5"	2 ea	387.84 /ea	776
Roof drain/#ZC100 - 6"	14 ea	387.84 /ea	5,430
Floor cleanouts - 4" (#ZN1400)	6 ea	291.07 /ea	1,746
Wall cleanouts - 4" (#Z1468)	12 ea	101.07 /ea	1,213
Rainleader UG/cast iron single hub pipe & ftgs. - 4"	90 lf	44.77 /lf	4,030
Rainleader UG/cast iron single hub pipe & ftgs. - 6"	90 lf	74.82 /lf	6,734
Rainleader UG/cast iron single hub pipe & ftgs. - 8"	70 lf	103.25 /lf	7,228



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D2040 Rain Water Drainage</b>			
Rainleader UG/cast iron single hub pipe & ftgs. - 10"	160 lf	141.04 /lf	22,566
Rainleader UG/cast iron single hub pipe & ftgs. - 12"	25 lf	186.99 /lf	4,675
Rainleader AG/cast iron no hub pipe & ftgs. - 4"	265 lf	52.53 /lf	13,919
Rainleader AG/cast iron no hub pipe & ftgs. - 6"	410 lf	81.16 /lf	33,274
Rainleader AG/cast iron no hub pipe & ftgs. - 8"	460 lf	133.84 /lf	61,565
Rainleader AG/cast iron no hub pipe & ftgs. - 10"	10 lf	198.47 /lf	1,985
- Rainleader piping accessories	1,580 lf	1.77 /lf	2,802
- Rainleader piping & equipment I.D.	1,580 lf	1.46 /lf	2,314
<b>D2040 Rain Water Drainage</b>	<b>136,600 sf</b>	<b>1.62 /sf</b>	<b>221,676</b>
<b>D2090 Other Plumbing Systems</b>			
General requirements (management, permits, as-builts, coring, fire stopping)	136,600 sf	0.75 /sf	102,450
3D/BIM coordination	1 ls	12,000.00 /ls	12,000
Core drilling	1 ls	10,000.00 /ls	10,000
Project management	1 ls	50,000.00 /ls	50,000
Kitchen Equipment Tie ins	1 ls	12,000.00 /ls	12,000
Commissioning support/day	5 day	824.56 /day	4,123
Gas Flow Meter - avg. size	1 ea	1,857.68 /ea	1,858
Emergency gas shut off/cabinet w/1" solenoid & UL ball valve 1114, 1111A	2 ea	3,968.42 /ea	7,937
Emergency gas shut off/cabinet w/1-1/2" solenoid & UL ball valve KIT	1 ea	5,093.42 /ea	5,093
- Remote panic buttons	2 ea	828.07 /ea	1,656
Gas turret/single	5 ea	212.07 /ea	1,060
Gas turret/double	5 ea	320.54 /ea	1,603
Gas piping/sch 40 black steel CW t&c - 1"	240 lf	28.68 /lf	6,882
Gas piping/sch 40 black steel CW t&c - 1-1/4"	120 lf	34.14 /lf	4,097
Gas piping/sch 40 black steel CW t&c - 1-1/2"	65 lf	37.25 /lf	2,421
Gas piping/sch 40 black steel CW t&c - 2"	10 lf	42.28 /lf	423
Gas piping/sch 40 blk stl ERW weld - 2-1/2"	30 lf	45.73 /lf	1,372
Gas piping/sch 40 blk stl ERW weld - 3"	75 lf	54.12 /lf	4,059
Gas piping/sch 40 blk stl ERW weld - 4"	60 lf	87.71 /lf	5,263
Gas piping for generator	250 lf	80.00 /lf	20,000
Gas piping/sch 40 blk stl ERW weld - 8"	25 lf	180.43 /lf	4,511
- Gas piping accessories	625 lf	2.52 /lf	1,577
- Gas piping link seals	1 ea	404.61 /ea	405
- Gas piping & equipment I.D.	625 lf	28.95 /lf	18,094
Acid neut. Tank/5 gallon - 1-sink (Orion style 5)	1 ea	622.14 /ea	622
Acid neut. tank/15 gallon - 3-sinks (Orion style 5)	3 ea	911.21 /ea	2,734



90% CD Reconciled Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D2090 Other Plumbing Systems</b>			
Acid neut. tank/55 gallon -	2 ea	1,912.28 /ea	3,825
- Limestone chips/50 lb. bag	24 ea	43.77 /ea	1,050
PH Monitoring (2) locations	2 ea	6,612.28 /ea	13,225
Floor drain - 6" (#ZN415-AA-8B)	3 ea	480.84 /ea	1,443
Floor cleanout/heavy duty - 4" (#ZN1400-K-AR)	5 ea	424.84 /ea	2,124
Wall cleanouts/#Z1468 - 4"	5 ea	101.07 /ea	505
Acid waste UG/sch 40 polypropylene fuseal & ftgs. - 3"	20 lf	58.29 /lf	1,166
Acid waste UG/sch 40 polypropylene fuseal & ftgs. - 4"	230 lf	68.91 /lf	15,849
Tie-ins to Lab Hoods acid waste & vent - A/G	3 ea	815.35 /ea	2,446
Acid waste AG/sch 40 polypropylene fuseal & ftgs. - 2"	800 lf	51.44 /lf	41,154
Acid waste AG/sch 40 polypropylene fuseal & ftgs. - 3"	400 lf	65.67 /lf	26,269
Acid waste AG/sch 40 polypropylene fuseal & ftgs. - 4"	360 lf	77.44 /lf	27,877
- Acid waste & vent piping accessories	1,810 lf	2.02 /lf	3,662
- Acid waste piping & equipment I.D.	1,810 lf	2.56 /lf	4,636
Wiring PH Monitor and Misc Control	1 ls	6,000.00 /ls	6,000
SM - Flue piping/double wall/stainless steel/6" pipe - linear foot DWH	600 lf	97.98 /lf	58,786
SM - Flue piping/double wall/stainless steel/6" fittings - each DWH	16 ea	122.47 /ea	1,960
SM - Flue piping/double wall/stainless steel/6" fittings - each DWH	8 lf	122.47 /lf	980
<b>D2090 Other Plumbing Systems</b>	<b>136,600 sf</b>	<b>3.63 /sf</b>	<b>495,194</b>
<b>D20 Plumbing</b>	<b>136,600 sf</b>	<b>15.34 /sf</b>	<b>2,094,999</b>
<b>D30 Heating, Ventilating, and Air Conditioning (HVAC)</b>			
<b>D3010 Energy Supply</b>			
Insulation/pipe/copper	14,483 lf	7.09 /lf	102,715
Insulation/pipe/weld	3,838 lf	12.50 /lf	47,975
Hot water s&r/type "L" copper solder - 3/4"	8,970 lf	20.16 /lf	180,835
Hot water s&r/type "L" copper solder - 1"	1,760 lf	25.01 /lf	44,018
Hot water s&r/type "L" copper solder - 1-1/4"	1,260 lf	28.57 /lf	35,998
Hot water s&r/type "L" copper solder - 1-1/2"	890 lf	32.82 /lf	29,210
Hot water s&r/type "L" copper solder - 2"	1,550 lf	41.25 /lf	63,937
Hot water s&r/sch 40 blk stl ERW weld - 2-1/2"	605 lf	50.55 /lf	30,583
Hot water s&r/sch 40 blk stl ERW weld - 3"	475 lf	59.42 /lf	28,225
Hot water s&r/sch 40 blk stl ERW weld - 4"	756 lf	82.30 /lf	62,219
Hot water s&r/sch 40 blk stl ERW weld - 6"	520 lf	134.07 /lf	69,716
Hot water s&r/sch 40 blk stl ERW weld - 8"	220 lf	167.74 /lf	36,903
Glycol water s&r/type "L" copper solder - 2"	53 lf	41.25 /lf	2,186
Glycol water s&r/sch 40 blk stl ERW weld - 2-1/2"	47 lf	50.55 /lf	2,376
Glycol water s&r/sch 40 blk stl ERW weld - 3"	90 lf	59.42 /lf	5,348



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D3010 Energy Supply</b>			
Glycol water s&r/sch 40 blk stl ERW weld - 4"	152 lf	82.30 /lf	12,510
Glycol water s&r/sch 40 blk stl ERW weld - 6"	910 lf	134.07 /lf	122,004
Glycol water s&r/sch 40 blk stl ERW weld - 8"	110 lf	167.74 /lf	18,451
- Hydronic piping accessories	18,368 lf	2.53 /lf	46,506
Pump/base mount/790 gpm (HW)	2 ea	8,167.68 /ea	16,335
Chilled water pump house (pumps & accesories, enclosure, piping, unit heater	1 ls	226,667.68 /ls	226,668
- Suction diffusers	2 ea	1,460.58 /ea	2,921
- Flex connector/HVAC pumps	4 ea	556.35 /ea	2,225
- Triple duty valves	2 ea	2,312.69 /ea	4,625
Air separators	1 ea	4,333.84 /ea	4,334
Expansion tanks/ASME	2 ea	7,167.68 /ea	14,335
Chemical treatment (lump sum)	1 ls	20,000.00 /ls	20,000
Glycol feed/50 gal. tank w/pump (Neptune #G-50-1)	2 ea	5,272.92 /ea	10,546
- Glycol solution/40% propylene	1,000 gal	25.21 /gal	25,212
<b>D3010 Energy Supply</b>	<b>136,600 sf</b>	<b>9.29 /sf</b>	<b>1,268,916</b>
<b>D3020 HVAC</b>			
Boiler/HW/gas/high eff. cond. - 4,000 mbh Riello AR 4000	2 ea	57,501.52 /ea	115,003
Boiler circulator pump	2 ea	1,708.46 /ea	3,417
Boiler combustion air/galvanized steel 10"	200 lf	38.00 /lf	7,600
Flue piping/double wall/stainless steel 10"	205 lf	185.00 /lf	37,925
<b>D3020 HVAC</b>	<b>136,600 sf</b>	<b>1.20 /sf</b>	<b>163,945</b>
<b>D3030 Cooling Generating Systems</b>			
Chiller/air cooled - 370 tons	1 ea	381,153.80 /ea	381,154
Buffer tanks/Lochinvar - 300 gals.	1 ea	8,750.76 /ea	8,751
<b>D3030 Cooling Generating Systems</b>	<b>136,600 sf</b>	<b>2.85 /sf</b>	<b>389,905</b>
<b>D3040 HVAC Distribution</b>			
Lull, laborer for cleanup by Consigli (HVAC)	(1) ls	343,000.00 /ls	(343,000)
Trade support - lull, laborer for cleanup (HVAC)	1 ls	343,000.00 /ls	343,000
Insulation/ductwork/blanket wrap	83,500 sf	3.55 /sf	296,088
Insulation/ductwork/weatherproof exposed	4,500 sf	12.89 /sf	57,986
Sheetmetal & accessories/galvanized	111,320 lb	11.04 /lb	1,228,973
Sheetmetal & accessories/galvanized (perforated)	869 lb	14.49 /lb	12,592
Sheetmetal & accessories/galvanized (smoke exhasut)	9,735 lb	11.04 /lb	107,474
Sheetmetal & accessories/galvanized (perforated liner)	4,000 lb	14.49 /lb	57,960
Sheetmetal & accessories/stainless steel (dishwasher)	350 lb	22.28 /lb	7,798
Sheetmetal & accessories/welded stainless steel (kitchen exhaust)	1,060 lb	29.78 /lb	31,567



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D3040 HVAC Distribution</b>			
Sheetmetal & accessories/welded stainless steel (kiln exhaust)	500 lb	29.78 /lb	14,890
Sheetmetal & accessories/welded stainless steel (3 - fume hoods)	2,700 lb	29.78 /lb	80,406
Sheetmetal & accessories/fabric/1-row cable (DuctSox) - 20"	405 lf	76.50 /lf	30,982
Sheetmetal & accessories/fabric/1-row cable (DuctSox) - 24"	305 lf	81.29 /lf	24,792
Duct enclosure (roof)	1 ea	5,424.10 /ea	5,424
SM - Diffusers, registers & grilles	136,600 sf	0.20 /sf	27,320
SM - Linear slot diffusers (supply)	6 ea	465.39 /ea	2,792
<b>SM - Linear slot diffusers (exhaust) - architectural</b>	<b>lf</b>	<b>/lf</b>	
SM - Displ. Diffuser/Floor Mnt.	156 ea	1,289.88 /ea	201,221
SM - Combination fire/smoke dampers/louver type/UL	20 ea	776.53 /ea	15,530
SM - Motorized damper	14 ea	1,107.92 /ea	15,511
SM - Smoke detectors/duct mount	40 ea	747.47 /ea	29,899
SM - Sound attenuators/in-line/std. gauge	239,000 cfm	0.55 /cfm	131,341
SM - Kitchen exhaust hood/st. steel/install only (by KES)	1 ea	2,339.28 /ea	2,339
SM - Dishwasher exhaust hood/st. steel/install only (by KES)	1 ea	1,559.52 /ea	1,560
SEF-1-4	4 ea	17,339.28 /ea	69,357
EF-3&4 /centrifugal downblast/roof/direct drive - 500 cfm	2 ea	1,069.31 /ea	2,139
EF-1&2 /centrifugal downblast/roof/direct drive - 2,500 cfm	2 ea	1,771.24 /ea	3,542
KEF-1&2/centrifugal upblast/roof	2 ea	2,734.82 /ea	5,470
FEF-1,2,3,4,5 Lab exhaust fan/roof - 1,200 cfm	5 ea	9,084.82 /ea	45,424
<b>D3040 HVAC Distribution</b>	<b>136,600 sf</b>	<b>18.38 /sf</b>	<b>2,510,378</b>
<b>D3050 Terminal &amp; Package Units</b>			
Variable air volume box - small	12 ea	533.15 /ea	6,398
Variable air volume box - medium	143 ea	668.62 /ea	95,612
RTU-1-4 Classrooms (service enclosure, HW&CHW coils, energy recovery)	80,000 cfm	15.75 /cfm	1,260,000
RTU-5 Gymnasium (service enclosure, HW&CHW coils, energy recovery)	15,000 cfm	16.25 /cfm	243,750
RTU-6 Auditorium (service enclosure, HW&CHW coils, energy recovery)	12,000 cfm	16.25 /cfm	195,000
RTU-7 Lockers (service enclosure, HW&CHW coils, energy recovery)	2,000 cfm	18.25 /cfm	36,500
MAU-1 Make-up air unit/HW&CHW coil/	5,000 cfm	7.25 /cfm	36,250
Mini-split AC system/1-zone/wall mnt./cool only - 12 mbh	1 ea	2,072.92 /ea	2,073
Mini-split AC system/1-zone/wall mnt./cool only - 18 mbh	5 ea	2,681.66 /ea	13,408
Mini-split AC system/1-zone/wall mnt./cool only - 24 mbh	2 ea	2,956.03 /ea	5,912
Mini-split refrigeration line set/6-12 mbh - 50'	2 ea	584.88 /ea	1,170
Mini-split refrigeration line set/15-18 mbh - 50'	10 ea	599.88 /ea	5,999
Mini-split refrigeration line set/24-30 mbh - 50'	4 ea	614.88 /ea	2,460
Mini-split condensate drains/type"L" copper	450 lf	19.43 /lf	8,744



90% CD Reconciled Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D3050 Terminal &amp; Package Units</b>			
A/C cond. pump	8 ea	253.74 /ea	2,030
INS - Mini-split Insulation/copper pipe	450 lf	6.87 /lf	3,090
ATC - Mini-split condensing units (w/factory controls)	8 ea	879.76 /ea	7,038
ATC - Mini-split indoor units (w/factory controls)	8 ea	587.35 /ea	4,699
Radiant ceiling panels/24" wide - ft.	1,450 lf	120.00 /lf	174,000
FTR-2 Finned-tube radiation w/enclosure - 1 row	260 lf	194.24 /lf	50,502
FTR-1 Finned-tube radiation w/enclosure - 2 row	570 lf	259.37 /lf	147,841
FTR-3 Finned-tube radiation w/enclosure - 2 row	40 lf	297.49 /lf	11,900
Fin-tube radiation/electric - 2 kW	8 ea	739.88 /ea	5,919
Cabinet unit heater/hot water/wall mount/recessed - avg. size	4 ea	1,573.62 /ea	6,294
Cabinet unit heater/hot water/ceiling mount - avg. size	10 ea	1,749.51 /ea	17,495
Unit heater/hot water/horiz./propeller - avg. size	2 ea	1,092.41 /ea	2,185
Misc. VFD's	1 ls	35,000.00 /ls	35,000
VFD w/keypad/disconnect/bypass/NEMA 1 - HW pumps	2 ea	6,028.47 /ea	12,057
<b>VFD w/keypad/disconnect/bypass/NEMA 1 - CHW pumps w/ pump house</b>	<b>ea</b>	<b>/ea</b>	
<b>D3050 Terminal &amp; Package Units</b>	<b>136,600 sf</b>	<b>17.52 /sf</b>	<b>2,393,325</b>
<b>D3060 HVAC Instrumentation &amp; Controls</b>			
Automatic temperature controls/cost per sq. ft.	136,600 sf	0.25 /sf	34,150
ATC - Air valve/hood exhaust/HEX	3 ea	4,194.32 /ea	12,583
ATC - Air valves/no coil control wiring - 3 pts./fume hood	9 pnt	437.00 /pnt	3,933
ATC - RTU's/custom - 30 pts.	240 pnt	1,303.18 /pnt	312,763
ATC - MUA units - 10 pts.	10 pnt	759.44 /pnt	7,594
ATC - Exhaust fans - 3 pts.	18 pnt	711.10 /pnt	12,800
ATC - Life safty fans - 8 pts.	32 pnt	766.15 /pnt	24,517
ATC - Lab exhaust fans - 5 pts./fan	25 pnt	766.15 /pnt	19,154
ATC - Boilers/modular - 10 pts.	20 pnt	821.19 /pnt	16,424
ATC - Pumps - 4 pts.	16 pnt	766.15 /pnt	12,258
ATC - VFD wiring for pumps (remote mount) - 4 pts.	16 pnt	763.91 /pnt	12,223
ATC - Circulators - 2 pts.	4 pnt	488.68 /pnt	1,955
ATC - Chillers - 15 pts.	15 pnt	1,303.18 /pnt	19,548
ATC - VAV box/no coil (ATC furn./factory install controls) 2 pts.	310 pnt	408.36 /pnt	126,592
ATC - Fintube radiation zones - 2 pts.	20 pnt	381.96 /pnt	7,639
ATC - electric fintube radiation zones - 2 pts.	4 pnt	381.95 /pnt	1,528
ATC - Cabinet unit heaters - 3 pts.	42 pnt	381.96 /pnt	16,042
ATC - Unit heaters - 3 pts.	6 pnt	381.95 /pnt	2,292
ATC - Radiant ceiling panel zones - 2 pts.	246 pnt	381.96 /pnt	93,961
ATC - Plumbing points - 10 pts.	10 pnt	595.50 /pnt	5,955
ATC - Elctrical points - 10 pts.	10 pnt	595.50 /pnt	5,955



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D3060 HVAC Instrumentation &amp; Controls</b>	<b>136,600 sf</b>	<b>5.49 /sf</b>	<b>749,864</b>
<b>D3070 Testing, Adjusting &amp; Balancing</b>			
Testing & balancing/cost per sq. ft.	136,600 sf	0.65 /sf	88,790
<b>D3070 Testing, Adjusting &amp; Balancing</b>	<b>136,600 sf</b>	<b>0.65 /sf</b>	<b>88,790</b>
<b>D3090 Other HVAC Systems &amp; Equipment</b>			
General requirements (sq. ft.)	136,600 sf	1.15 /sf	157,090
3D/BIM coordination	1 ls	100,000.00 /ls	100,000
Commissioning support/lump sum	1 ls	15,000.00 /ls	15,000
Dust collection system	1 ea	17,339.28 /ea	17,339
Kiln exhaust	1 ls	5,500.00 /ls	5,500
Equipment hoisting/rigging/setting/start-up	136,600 sf	1.50 /sf	204,900
<b>D3090 Other HVAC Systems &amp; Equipment</b>	<b>136,600 sf</b>	<b>3.66 /sf</b>	<b>499,829</b>
<b>D30 Heating, Ventilating, and Air Conditioning (HVAC)</b>	<b>136,600 sf</b>	<b>59.04 /sf</b>	<b>8,064,951</b>
<b>D40 Fire Protection Systems</b>			
<b>D4010 Sprinklers</b>			
Lull, laborer for cleanup by Consigli (Fire Protection)	(1) ls	31,000.00 /ls	(31,000)
Trade support - lull, laborer for cleanup (Fire Protection)	1 ls	31,000.00 /ls	31,000
General requirements (management/design, permits, as-builts, coring, fire stopping)	136,600 sf	0.50 /sf	68,300
Fire dept. inlet connection - 2-1/2" polished brass - 3-way	1 ea	1,863.93 /ea	1,864
Sprinkler head - wet - recessed pendant	903 ea	125.42 /ea	113,250
Sprinkler head - wet - pendant or upright	522 ea	77.23 /ea	40,313
Sprinkler head - wet - sidewall	151 ea	87.51 /ea	13,213
Sprinkler head - wet - window	34 ea	87.51 /ea	2,975
Sprinkler head - extended coverage pendant or upright	120 ea	127.23 /ea	15,267
Sprinkler head - dry - sidewall (wet system)	22 ea	293.06 /ea	6,447
Sprinkler branch piping black steel sch. 40 w/ fittings 1"	3,465 lf	23.99 /lf	83,116
Sprinkler branch piping black steel sch. 40 w/ fittings 1-1/4"	600 lf	27.93 /lf	16,757
Sprinkler branch piping black steel sch. 40 w/ fittings 1-1/2"	5,200 lf	30.66 /lf	159,417
Sprinkler branch piping black steel sch. 40 w/ fittings 2"	650 lf	34.57 /lf	22,468
Sprinkler main piping black steel sch. 40 w/ fittings (avg. size)	1,000 lf	62.18 /lf	62,184
Sprinkler main piping black steel sch. 10 w/ fittings 3"	450 lf	36.32 /lf	16,345
Sprinkler main piping black steel sch. 10 w/ fittings 4"	3,180 lf	39.66 /lf	126,127
Sprinkler main piping black steel sch. 10 w/ fittings 6"	500 lf	69.39 /lf	34,695
Wet alarm valve - 6"	1 ea	3,656.71 /ea	3,657
Double check valve (BFP) assembly - 6"	1 ea	8,244.56 /ea	8,245
Butterfly valve - 6"	2 ea	1,566.71 /ea	3,133





# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D4010 Sprinklers</b>			
Zone flow control valve - 4"	7 ea	2,521.71 /ea	17,652
Waterflow switch	8 ea	421.96 /ea	3,376
Tamper switch	8 ea	356.96 /ea	2,856
Water motor gong bell	1 ea	628.36 /ea	628
<b>D4010 Sprinklers</b>	<b>136,600 sf</b>	<b>6.02 /sf</b>	<b>822,286</b>
<b>D4020 Standpipes</b>			
Standpipe - sch 40 black steel piping w/ fittings - 6"	125 lf	99.13 /lf	12,391
Drain riser - sch 40 black steel piping w/ fittings - 3"	125 lf	49.66 /lf	6,208
Fire hose valve - 2-1/2"	12 ea	353.36 /ea	4,240
<b>D4020 Standpipes</b>	<b>136,600 sf</b>	<b>0.17 /sf</b>	<b>22,839</b>
<b>D4030 Fire Protection Specialties</b>			
Fire valve cabinet - steel - recessed	12 ea	894.50 /ea	10,734
<b>D4030 Fire Protection Specialties</b>	<b>136,600 sf</b>	<b>0.08 /sf</b>	<b>10,734</b>
<b>D4090 Other Fire Protection Systems</b>			
Hydraulic calculation & shop drawings	1 ls	8,000.00 /ls	8,000
3D/BIM coordination	1 ls	10,000.00 /ls	10,000
<b>D4090 Other Fire Protection Systems</b>	<b>136,600 sf</b>	<b>0.13 /sf</b>	<b>18,000</b>
<b>D40 Fire Protection Systems</b>	<b>136,600 sf</b>	<b>6.40 /sf</b>	<b>873,859</b>
<b>D50 Electrical Systems</b>			
<b>D5010 Gear &amp; Distribution</b>			
Feeder (MC) - 20A (kitchen equipment - x42)	3,150 lf	5.75 /lf	18,111
Feeder (MC) - 30A (kitchen equipment - x2)	200 lf	5.87 /lf	1,173
1" PVC - 30A (3#8 & #10G)	250 lf	10.29 /lf	2,573
Feeder (MC) - 40A (kitchen equipment - x1)	100 lf	7.01 /lf	701
Feeder (MC) - 60A (kitchen equipment - x2)	200 lf	10.55 /lf	2,110
Power for automatic temperature control panels (BMS)	12 ea	460.91 /ea	5,531
Electric heat trace power (cables, sensors, controllers by Div. 21 / 22)	1,900 lf	3.50 /lf	6,650
Service switch: 20A/3P, NEMA-1	1 ea	107.43 /ea	107
Fused Disco: 20A/3P, NEMA-1	7 ea	323.22 /ea	2,263
Fused Disco: 100A/3P, NEMA-1	2 ea	1,185.41 /ea	2,371
Fused Disco: 200A/3P, NEMA-1	3 ea	1,555.38 /ea	4,666
Fused Disco: 1000A/3P, NEMA-1	2 ea	7,290.94 /ea	14,582
Wire gymnasium equipment SMC control stations (furnished by others)	8 ea	1,058.23 /ea	8,466



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5010 Gear &amp; Distribution</b>			
Wire motors and controllers	15 ea	821.28 /ea	12,319
Kitchen equipment final connections (includes flexible whip)	47 ea	72.36 /ea	3,401
Mount & wire VFD's (furnished by Div. 23)	8 ea	646.55 /ea	5,172
MAU (5000cfm) - circuit / disconnect (3R) / connection	1 ea	2,503.41 /ea	2,503
RTU's - circuit / disconnect (3R) / connection (small)	3 ea	4,736.19 /ea	14,209
RTU's - circuit / disconnect (3R) / connection (large)	4 ea	7,010.29 /ea	28,041
Mini-split systems (indoor/outdoor) - circuits / disconnects (3R) / connections	8 ea	3,225.23 /ea	25,802
Chiller (370T) - circuit / disconnect (3R) / connection	1 ea	25,825.56 /ea	25,826
Smoke exhaust fans - circuit / disconnect / connection (100A)	4 ea	2,400.01 /ea	9,600
Kitchen exhaust fans - circuit / disconnect / connection	2 ea	1,420.91 /ea	2,842
Kiln exhaust system - circuit / disconnect / connection	1 ea	2,655.30 /ea	2,655
Dust collection system - circuit / disconnect / connection	1 ea	3,579.00 /ea	3,579
Fume hood exhaust fans - circuit / disconnect / connection	5 ea	1,214.10 /ea	6,071
Exhaust fans - circuit / disconnect / connection	4 ea	1,214.11 /ea	4,856
Power to electronic trap primers - 120V	8 ea	100.19 /ea	801
Hot water pumps - circuit / disconnect / connection	2 ea	1,673.87 /ea	3,348
Boilers - circuit / disconnect / connection	2 ea	1,204.71 /ea	2,409
Chilled water pump house pumps & heaters - circuits / disconnects / connections	1 ls	6,158.00 /ls	6,158
Hot water heater - circuit / service switch / connection	1 ea	591.53 /ea	592
Cabinet unit heaters - circuit / service switch / connection	14 ea	868.28 /ea	12,156
Unit heaters - circuit / service switch / connection	2 ea	868.28 /ea	1,737
Elevator sump pump - circuit / disconnect (3R) / connection	1 ea	1,247.28 /ea	1,247
Domestic boilers - circuit / disconnect (3R) / connection	2 ea	1,247.28 /ea	2,495
Recirculation pumps - circuit / disconnect / connection	3 ea	997.87 /ea	2,994
Glycol feed pumps - circuit / disconnect / connection	2 ea	997.87 /ea	1,996
Boiler circulation pumps - circuit / disconnect / connection	2 ea	997.87 /ea	1,996
Fin-tube radiators (2kW) - circuit / disconnect / connection	8 ea	1,847.40 /ea	14,779
VAV's - circuit / disconnect / connection	155 ea	298.83 /ea	46,318
Acid neutralization tanks / PH monitoring - circuit / connection	2 ea	965.80 /ea	1,932
Circuit breaker - 20A/1P (panel)	1 ea	149.86 /ea	150
Switchboard: 3000A bus, 2500A rated MCB (100%), 480/277V, 3PH, 65kAIC	1 ea	45,417.04 /ea	45,417
Panelboard: 100A, 42-circuit	14 ea	2,550.41 /ea	35,706
Panelboard: 225A, 42-circuit	9 ea	3,420.66 /ea	30,786
Panelboard: 225A, 84-circuit	9 ea	4,338.66 /ea	39,048
Panelboard: 400A, 42-circuit	3 ea	5,435.74 /ea	16,307
Panelboard: 400A, 84-circuit	1 ea	10,724.46 /ea	10,724
Distribution panel: 600A	2 ea	9,886.92 /ea	19,774



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5010 Gear &amp; Distribution</b>			
Distribution panel: 800A	3 ea	12,443.25 /ea	37,330
Transformer: floor/wall - 75kVA, 480V:208V	1 ea	4,384.00 /ea	4,384
K-13 Transformer: floor - 225kVA, 480V:208V	3 ea	12,168.50 /ea	36,506
Engineered Services - Training (Manufacturer)	1 ea	4,165.70 /ea	4,166
Engineered Services - Start-Up Assistance (Manufacturer)	1 ea	3,519.08 /ea	3,519
Feeder (EMT/CU) - 20A [BMS to utility meter]	200 lf	7.43 /lf	1,486
Feeder (EMT/CU) - 20A [EP1A to Elevator Controller]	125 lf	7.43 /lf	929
Feeder (EMT/CU) - 60A [MSB to SPD]	50 lf	14.69 /lf	735
Feeder (EMT/CU) - 60A [2DP1A to SPD]	50 lf	14.69 /lf	735
Feeder (EMT/CU) - 60A [2DP1B to SPD]	50 lf	14.69 /lf	735
Feeder (EMT/CU) - 60A [2DP1C to SPD]	50 lf	14.69 /lf	735
Feeder (EMT/CU) - 60A [4DP1B to SPD]	50 lf	14.69 /lf	735
Feeder (EMT/CU) - 90A [2DP1A to KPP1A]	42 lf	15.96 /lf	670
Feeder (EMT/CU) - 100A [MSB to LP1A]	40 lf	20.74 /lf	830
Feeder (EMT/CU) - 100A [4DP1B to LP1B]	50 lf	20.74 /lf	1,037
Feeder (EMT/CU) - 100A [4DP1C to LP1C]	27 lf	20.74 /lf	560
Feeder (EMT/CU) - 100A [4DP1B to LP2B]	50 lf	20.74 /lf	1,037
Feeder (EMT/CU) - 100A [2DP1A to LP2C]	190 lf	20.74 /lf	3,940
Feeder (EMT/CU) - 100A [4DP1B to LP3B]	150 lf	20.74 /lf	3,111
Feeder (EMT/CU) - 100A [4DP1C to LP3C]	165 lf	20.74 /lf	3,422
Feeder (EMT/CU) - 100A [MSB to LP1D]	150 lf	20.74 /lf	3,111
Feeder (EMT/CU) - 100A [EHP1A to Elevator Controller]	125 lf	20.74 /lf	2,592
Feeder (EMT/CU) - 100A [TEP1A to TEP2B]	200 lf	20.74 /lf	4,148
Feeder (EMT/CU) - 100A [TEP1A to TEP2C]	200 lf	20.74 /lf	4,148
Feeder (EMT/CU) - 100A [TEP1A to TEP1D]	200 lf	20.74 /lf	4,148
Feeder (EMT/CU) - 100A [TEP1A to UPS]	50 lf	20.74 /lf	1,037
Feeder (EMT/CU) - 100A [2DP1A to MP1A]	410 lf	20.74 /lf	8,503
Feeder (EMT/CU) - 125A [UPS to EP1A]	150 lf	20.99 /lf	3,149
Feeder (EMT/CU) - 150A [2DP1B to MP1B]	50 lf	26.82 /lf	1,341
Feeder (EMT/CU) - 150A [2DP1C to MSB]	200 lf	26.82 /lf	5,365
Feeder (EMT/CU) - 150A [2DP1C to MP3C]	250 lf	26.82 /lf	6,706
Feeder (EMT/CU) - 150A [2DP1B to PP2B]	60 lf	26.82 /lf	1,609
Feeder (EMT/CU) - 150A [2DP1C to PP2C]	100 lf	26.82 /lf	2,682
Feeder (EMT/CU) - 150A [2DP1B to PP1B]	50 lf	26.82 /lf	1,341
Feeder (EMT/CU) - 150A [2DP1C to MP1C]	40 lf	26.83 /lf	1,073
Feeder (EMT/CU) - 150A [2DP1C to PP2C]	125 lf	26.82 /lf	3,353
Feeder (EMT/CU) - 150A [2DP1C to PP3C]	150 lf	26.82 /lf	4,024
Feeder (EMT/CU) - 150A [4DP1C to PP3B]	165 lf	26.82 /lf	4,426
Feeder (EMT/CU) - 150A [2DP1C to PP1C]	50 lf	26.82 /lf	1,341
Feeder (EMT/CU) - 150A [2DP1A to PP1D]	100 lf	26.82 /lf	2,682



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5010 Gear &amp; Distribution</b>			
Feeder (EMT/CU) - 200A [MSB to ATS-LS]	100 lf	32.13 /lf	3,213
Feeder (EMT/CU) - 200A [ATS-LS to ELP1A]	40 lf	32.13 /lf	1,285
Feeder (EMT/CU) - 200A [2DP1A to PP1A]	50 lf	32.13 /lf	1,607
Feeder (EMT/CU) - 200A [Cam Lock Box to ATS-LS]	60 lf	32.13 /lf	1,928
Feeder (EMT/CU) - 225A [MSB to Dimming Rack HDP]	250 lf	46.72 /lf	11,679
Feeder (EMT/CU) - 225A [2DP1A to Dimming Rack SDP]	200 lf	46.72 /lf	9,344
Feeder (EMT/CU) - 225A [EHP1A to EHP3C]	250 lf	46.72 /lf	11,679
Feeder (EMT/CU) - 225A [MP3C to PP3C]	45 lf	46.72 /lf	2,102
Feeder (EMT/CU) - 225A [2DP1B to MP3B]	100 lf	46.72 /lf	4,672
Feeder (EMT/CU) - 225A [4DP1C to MHP3C]	165 lf	49.70 /lf	8,200
Feeder (EMT/CU) - 225A [ATS-OS to EHP1A]	200 lf	49.70 /lf	9,940
Feeder (EMT/CU) - 225A [MSB to ATS-OS]	75 lf	49.70 /lf	3,727
Feeder (EMT/CU) - 400A [MSB to MHP1A]	50 lf	73.75 /lf	3,688
Feeder (EMT/CU) - 400A [EHP1C to EHP1A]	100 lf	73.75 /lf	7,375
Feeder (EMT/CU) - 400A [Generator to ATS-LR] (interior)	430 lf	73.75 /lf	31,713
Feeder (EMT/CU) - 400A [MSB to ATS-LR]	375 lf	78.46 /lf	29,422
Feeder (EMT/CU) - 400A [MHP-LR to ATS-LR]	10 lf	78.46 /lf	785
Feeder (EMT/CU) - 400A [ATS-LR to MHP-LR]	50 lf	73.75 /lf	3,688
Feeder (EMT/CU) - 600A [MSB to 4DP1B]	200 lf	108.91 /lf	21,782
Feeder (EMT/CU) - 600A [MSB to 2DP1A]	70 lf	108.91 /lf	7,624
Feeder (EMT/CU) - 800A [MSB to 2DP1C]	125 lf	138.78 /lf	17,348
Feeder (EMT/CU) - 800A [MSB to 4DP1C]	200 lf	138.78 /lf	27,757
Empty conduit (EMT) - 3/4" [utility meter to switchboard]	75 lf	6.28 /lf	471
Feeder (MC) - 125A [75kVA]	30 lf	12.82 /lf	385
Feeder (MC) - 225A [75kVA]	30 lf	35.43 /lf	1,063
Feeder (MC) - 400A [225kVA]	90 lf	59.32 /lf	5,339
Feeder (MC) - 800A [225kVA]	90 lf	111.65 /lf	10,048
M.I. Cable - 4-1/c #6 [ELP1B to ELP3B]	150 lf	36.15 /lf	5,422
M.I. Cable - 4-1/c #3 [EHP1A to EP3C]	165 lf	65.42 /lf	10,794
M.I. Cable - 4-1/c #3 [ELP1A to EDP]	125 lf	65.42 /lf	8,178
M.I. Cable - 4-1/c #3 [ELP1A to EP1C]	125 lf	65.42 /lf	8,178
M.I. Cable - 4-1/c #2 [EPL1A to ELP1B]	150 lf	72.60 /lf	10,890
M.I. Cable - 4-1/c #2 [ELP1A to ELP1D]	417 lf	77.24 /lf	32,208
Quick term kit - #6 4-1/c	2 ea	359.96 /ea	720
Quick term kit - #3 4-1/c	6 ea	710.21 /ea	4,261
Quick term kit - #2 4-1/c	4 ea	734.64 /ea	2,939
Brass plate (per hole)	12 ea	92.10 /ea	1,105
Empty conduit - sch 40 PVC: 1 x 2" [future Canopy PV]	280 lf	26.88 /lf	7,526
Empty conduit - sch 40 PVC: 2 x 2" [future PV]	1,250 lf	35.04 /lf	43,800
Empty conduit - sch 40 PVC: 2 x 4" [future Canopy PV]	160 lf	45.14 /lf	7,222



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5010 Gear &amp; Distribution</b>			
ATS-OS: 225A, 277/480V, 4P, no iso by-pass - open transition	1 ea	6,752.90 /ea	6,753
ATS-LS: 150A, 277/480V, 4P, w/ iso by-pass - open transition	1 ea	11,058.30 /ea	11,058
ATS-LR: 400A, 277/480V, 4P, w/ iso by-pass - open transition	1 ea	19,961.43 /ea	19,961
Power junction w/feed (EMT) - 20A	1 ea	337.91 /ea	338
Empty conduit (EMT) - 3/4"	2,000 lf	5.11 /lf	10,218
<b>D5010 Gear &amp; Distribution</b>	<b>136,600 sf</b>	<b>8.18 /sf</b>	<b>1,117,861</b>
<b>D5020 Lighting &amp; Branch Wiring</b>			
Lull, laborer for cleanup by Consigli (Electrical)	(1) ls	230,000.00 /ls	(230,000)
Trade support - lull, laborer for cleanup (Electrical)	1 ls	230,000.00 /ls	230,000
Science Classrooms - CO system solenoid shutdown- 120V power & control wiring	2 ea	5,326.40 /ea	10,653
Kitchen - Ansul system - 120V power & control wiring	1 ea	10,237.00 /ea	10,237
Gym scoreboards and shot clocks - wiring only, F&I by Div. 11	2 ea	5,344.80 /ea	10,690
On-site programming & startup (manufacturer)	1 ls	3,913.41 /ls	3,913
Single pole switch (120/277V)	13 ea	65.04 /ea	845
Key op switch (120/277V)	2 ea	72.44 /ea	145
Three position momentary contact switch	1 ea	226.42 /ea	226
Ceiling PIR occupancy sensor (24VDC)	323 ea	247.23 /ea	79,854
Occupancy sensor power packs (120V)	200 ea	82.04 /ea	16,408
Wall dimmer switch (0-10V)	227 ea	131.04 /ea	29,746
Photocells (daylight harvesting)	84 ea	265.06 /ea	22,265
Universal dimming room controller, 1-channel	50 ea	536.88 /ea	26,844
ALCS master switching / dimming station	1 ea	821.83 /ea	822
Plug load controllers (20A/120V)	50 ea	300.80 /ea	15,040
Emergency lighting transfer (bypass relay) - non-dimming	30 ea	236.81 /ea	7,104
Astronomical time clock	1 ea	919.97 /ea	920
Rough in for Theater Lighting - Allowance	1 allw	9,400.01 /allw	9,400
Power for Theater Lighting - Allowance	1 allw	28,199.87 /allw	28,200
Sub lighting control panels	3 ea	2,394.56 /ea	7,184
Master lighting control panel	1 ea	4,383.41 /ea	4,383
Energy control unit	1 ea	2,157.58 /ea	2,158
System server unit	1 ea	1,316.75 /ea	1,317
Network Ethernet switch	1 ea	2,270.85 /ea	2,271
MC Cable (12/2) - 20A	12,500 lf	3.45 /lf	43,126
MC Cable (12/3) - 20A	3,500 lf	3.87 /lf	13,541
EMT (12/2) - 20A	2,000 lf	6.70 /lf	13,404
EMT (12/2) - 20A	50 lf	7.13 /lf	356
RJ45 Cable, 25LF (plenum-rated)	407 ea	72.10 /ea	29,344
RJ45 Cable, 50LF (plenum rated)	228 ea	111.05 /ea	25,318



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5020 Lighting &amp; Branch Wiring</b>			
MC Cable (12/2) - 20A	11,370 lf	3.45 /lf	39,227
MC Cable (10/2) - 20A [homeruns - x372]	24,180 lf	4.36 /lf	105,516
EMT (12/2) - 20A	2,000 lf	6.70 /lf	13,404
PVC (10/2) - 20A	450 lf	6.68 /lf	3,007
Duplex receptacle - 20A - tamper resistant	497 ea	78.60 /ea	39,065
Duplex receptacle - 20A - switched with IO module	14 ea	67.78 /ea	949
Simplex receptacle - 20A [scoreboard control]	2 ea	70.18 /ea	140
Duplex receptacle - 20A - GFCI	187 ea	92.44 /ea	17,286
Duplex receptacle - 20A - GFCI - W.P.	29 ea	129.27 /ea	3,749
Duplex receptacle - 20A [kitchen equipment] - circuitry in Equipment Wiring]	33 ea	67.79 /ea	2,237
Duplex receptacle - 20A [A/V]	9 ea	67.79 /ea	610
Duplex receptacle - 20A [CR]	8 ea	67.80 /ea	542
Exterior pedestal receptacle, GFI type, Wayne Tyler, Inc. #CB-BOX	5 ea	1,292.26 /ea	6,461
Quadruplex receptacle - 20A	325 ea	93.78 /ea	30,479
Quadruplex receptacle - 20A - switched with IO module	18 ea	93.79 /ea	1,688
Duplex receptacle - 20A - USB	14 ea	99.44 /ea	1,392
Specialty receptacle - 20A - L5-20R	11 ea	101.01 /ea	1,111
Specialty receptacle - 20A - L14-20R	1 ea	104.81 /ea	105
Specialty receptacle - 30A - L5-30R	23 ea	111.69 /ea	2,569
Quadruplex receptacle - 20A - GFCI	5 ea	143.12 /ea	716
Hardwired A/C junction (MC) - 20A [A/V]	2 ea	318.93 /ea	638
Hardwired A/C junction (MC) - 20A [fume hoods]	4 ea	318.93 /ea	1,276
Power junction w/feed (MC) - 20A [water coolers/bottle fillers]	11 ea	221.21 /ea	2,433
Power junction w/feed (MC) - 20A	28 ea	221.21 /ea	6,194
Trash compactor feed & connection	2 ea	2,243.92 /ea	4,488
Overhead door power & connection	3 ea	1,223.50 /ea	3,671
Dock leveler feed & connection	1 ea	3,532.90 /ea	3,533
Emergency power offs (EPO)	10 ea	295.11 /ea	2,951
Wiremold receptacles - G4	110 ea	31.05 /ea	3,416
G4000 dual-channel wiremold - 24" spacing	220 lf	63.39 /lf	13,945
Reduce lighting by \$1.50/sf - VM E01	(136,600) sf	1.50 /sf	(204,900)
LK24: 2'x2' lay-in fixture [O]	24 ea	198.57 /ea	4,766
SPFL: LED flood light [C]	20 ea	682.90 /ea	13,658
SPNF: LED flood light, narrow [C]	20 ea	682.90 /ea	13,658
LR2 (emerg): 2' linear 2" aperature recessed luminaire [O]	183 ea	300.48 /ea	54,987
LR2: 2' linear 2" aperature recessed luminaire [O]	912 ea	300.48 /ea	274,033
G4: 4' linear rugged low profile 360 deg adjustable flood luminaire [O]	80 ea	1,160.93 /ea	92,874
LS4: 4' utility fixtre with frosted acrylic diffuser [O]	20 ea	246.16 /ea	4,923



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5020 Lighting &amp; Branch Wiring</b>			
LS4 (emerg): 4' utility fixture with frosted acrylic diffuser [O]	14 ea	246.16 /ea	3,446
LS8: 8' utility fixture with frosted acrylic diffuser [O]	11 ea	411.94 /ea	4,531
LS4A (emerg): 4' utility fixture with frosted acrylic diffuser [O]	12 ea	494.94 /ea	5,939
LS4A: 4' utility fixture with frosted acrylic diffuser [O]	12 ea	494.94 /ea	5,939
LP8 (emerg): Axis 8' LED fixture [O]	9 ea	1,027.94 /ea	9,251
LS8 (emerg): 8' utility fixture with frosted acrylic diffuser [O]	10 ea	411.94 /ea	4,119
JB: utility fixture with frosted tempered glass globe & guard [O]	4 ea	245.95 /ea	984
PC3: 6" down light fixture with dead-front gasketed trim [O]	1 ea	298.16 /ea	298
LRW (emerg): 6" aperture LED linear recessed fixture / qty. of 18 [C]	114 lf	146.99 /lf	16,757
PC1: 4" down light fixture, 0-10V dimming capable [O]	24 ea	298.16 /ea	7,156
RC1: 6" down light fixture [O]	45 ea	271.54 /ea	12,219
RC1 (emerg): 6" down light fixture [O]	18 ea	271.54 /ea	4,888
LS2 (emerg): 2' utility fixture [O]	2 ea	177.98 /ea	356
LSV4: 4' linear utility fixture with prismatic polycarbonate lens [C]	4 ea	675.93 /ea	2,704
RC2: 4" down light fixture, 0-10V dimming [O]	8 ea	230.56 /ea	1,844
LR4: 4' linear 2" aperture recessed luminaire with frosted lens [O]	1 ea	410.45 /ea	410
LUL: LED tape light with AL channel [C]	1,840 lf	88.49 /lf	162,829
LC3: linear cove Xeleum lighting / qty. of 96 [O]	1,925 lf	121.99 /lf	234,826
LWW: LED tape light with AL channel [C]	1,408 lf	88.49 /lf	124,599
RSH: 6" down light fixture with dead-front gasketed trim [O]	1 ea	306.54 /ea	307
LC2: linear cove fixture with frosted diffuser / qty. of 10 [O]	76 lf	148.23 /lf	11,265
PC2: 6" down light fixture with dead-front gasketed trim [O]	28 ea	298.16 /ea	8,348
LCL: LED tape light with AL channel [C]	3,051 lf	88.49 /lf	269,994
LSL: LED strip mounted on edge of stage / qty. of 1	59 lf	305.95 /lf	18,051
Exit sign, ceiling mounted, double sided [O]	34 ea	196.16 /ea	6,669
Exit sign, ceiling mounted, single sided [O]	16 ea	183.16 /ea	2,931
Exit sign, wall mounted	18 ea	313.16 /ea	5,637
Exit sign, ceiling mounted, single sided - handicap [O]	2 ea	433.16 /ea	866
LRC (emerg): 6" aperture LED linear recessed fixture / qty. of 46 [C]	596 lf	161.70 /lf	96,373
Revised lighting package from Omni-Lite	(1) ls	271,965.00 /ls	(271,965)
MC Cable (12/2) - 20A (concealed branch)	12,068 lf	3.67 /lf	44,291
MC Cable (10/2) - 20A (concealed homeruns)	2,400 lf	4.64 /lf	11,142
EMT (12/2) - 20A (exposed branch)	4,023 lf	7.13 /lf	28,679
EMT (10/2) - 20A (exposed homeruns)	500 lf	8.58 /lf	4,290
SL4: LED egress / perimeter lighting fixture - custom color/finish [O]	20 ea	565.36 /ea	11,307
MC Cable (12/2) - 20A	1,200 lf	3.67 /lf	4,404
<b>D5020 Lighting &amp; Branch Wiring</b>	<b>136,600 sf</b>	<b>13.46 /sf</b>	<b>1,838,194</b>

**D5030 Communications & Security**



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5030 Communications &amp; Security</b>			
Externally mounted SPD's	6 ea	3,131.70 /ea	18,790
Tel/data J-hook system (plenum)	136,600 sf	0.19 /sf	25,681
Cable tray - 18"W (IDF/MDF only)	200 lf	75.55 /lf	15,109
Empty conduit (EMT) - 2"	650 lf	11.19 /lf	7,271
Copper ground bar w/isolators - 2"x1/4"	4 ea	280.03 /ea	1,120
Conduit sleeve w/ fireproofing - 4"	20 ea	201.11 /ea	4,022
Data outlet - (1) CAT-6A cable	20 ea	264.84 /ea	5,297
Data outlet - (1) CAT-6A cable [audio-visual]	12 ea	264.84 /ea	3,178
Data outlet - (2) CAT-6A cables	131 ea	466.16 /ea	61,067
Tel/data outlet - (3) CAT-6A cables	91 ea	652.82 /ea	59,407
Floor box tel/data outlet - (3) CAT-6A cables	2 ea	652.83 /ea	1,306
Voice outlet - (1) CAT-6A cable (WAP's by Owner)	79 ea	263.70 /ea	20,832
Wireless access point - (1) CAT-6A cable (WAP's by Owner)	138 ea	263.70 /ea	36,390
TVE - Video outlet	56 ea	838.75 /ea	46,970
TVC - Video outlet	2 ea	838.77 /ea	1,678
Double gang junction box with (4) 1" C	54 ea	482.68 /ea	26,065
FO - 12 strand SM	1,750 lf	5.27 /lf	9,225
FO - 12 strand MM	1,500 lf	7.10 /lf	10,642
4-Post Full Height Rack	10 ea	1,170.17 /ea	11,702
Vertical cable wire manager	20 ea	314.09 /ea	6,282
Horizontal cable wire manager	10 ea	80.25 /ea	803
Copper patch panel - 96 port	15 ea	1,244.28 /ea	18,664
Fiber optic patch panel - 24 port	6 ea	570.06 /ea	3,420
Fiber enclosure (rack mtd.)	6 ea	485.85 /ea	2,915
Network switch - 24 port	2 ea	5,390.24 /ea	10,780
S1: wall mounted loudspeaker - 1 gang metal box w/ cover	2 ea	228.33 /ea	457
S2: ceiling loud speaker - custom backbox	6 ea	308.23 /ea	1,849
S3: ceiling loud speaker - 4" SQ metal box w/ cover	16 ea	179.94 /ea	2,879
S4: ceiling loud speaker - 4" SQ metal box w/ cover	2 ea	251.94 /ea	504
S5: ceiling loud speaker - 4" SQ metal box w/ cover (New)	2 ea	245.27 /ea	491
D1: display back box, Chief PAC-526	3 ea	371.35 /ea	1,114
F1: floor box, FSR FL-500P-6 floor box w/ finished cover	1 ea	469.58 /ea	470
V1: wall mounted video projector - 1 gang metal box w/ cover	1 ea	179.47 /ea	179
R1: receptacle panel - 2 gang metal box w/ cover	3 ea	242.43 /ea	727
R2: receptacle panel - 12"x12"x4" NEMA-1 enclosure w/ oversized flush	2 ea	242.43 /ea	485
R3: receptacle panel - 3 gang metal box w/ cover	4 ea	311.69 /ea	1,247
R5: receptacle panel - 3 gang metal box w/ cover	1 ea	242.43 /ea	242
R6: receptacle panel - 12"x12"x4" NEMA-1 enclosure w/ oversized flush	2 ea	405.94 /ea	812





# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5030 Communications &amp; Security</b>			
BP: wall mounted button panel - 1 gang metal box w/ cover	3 ea	221.77 /ea	665
J1: junction box - type 1 - 12"x12"x4" NEMA-1 enclosure w/ oversized flush	2 ea	723.57 /ea	1,447
J2: junction box - type 2 - 18"x18"x4" NEMA-1 enclosure w/ oversized flush	1 ea	844.78 /ea	845
J3: junction box - type 3 - same as Type 2	3 ea	844.78 /ea	2,534
A1: Wall mounted antenna - 1 gang deep metal box w/ cover	2 ea	159.74 /ea	319
A2: Wall mounted antenna - 1 gang deep metal box w/ cover	1 ea	159.74 /ea	160
A3: Ceiling mounted antenna - 4" SQ metal box w/ cover	2 ea	138.32 /ea	277
A4: Ceiling mounted antenna - 4" SQ metal box w/ cover	1 ea	138.31 /ea	138
PS: Production communication speaker station - 4 gang deep metal box w/ cov	5 ea	385.28 /ea	1,926
PC: Production communication - 1 gang deep metal box w/ cover	1 ea	134.38 /ea	134
T1: Wall mounted touch panel - 3 gang metal box w/ cover	2 ea	249.04 /ea	498
VC: Wall mounted audio volume control - 1 gang deep metal box	2 ea	134.39 /ea	269
MC: Motor controller - 4" SQ metal box w/ cover	3 ea	86.46 /ea	259
C1: Wall mounted camera - 2 gang deep metal box w/ cover	1 ea	193.57 /ea	194
A/V Equipment Rack	2 ea	1,001.85 /ea	2,004
M1: Ceiling mounted microphone - 1 gang deep metal box w/ cover	1 ea	134.38 /ea	134
Intercom sub-stations	6 ea	1,009.28 /ea	6,056
Intercom master-stations	5 ea	3,327.13 /ea	16,636
Speaker - ceiling mouted	269 ea	405.93 /ea	109,194
Speaker - wall mounted	32 ea	611.85 /ea	19,579
Volume control	24 ea	177.96 /ea	4,271
Power supply (80) units - speakers 24V DC	4 ea	2,661.71 /ea	10,647
PA console	1 ea	14,251.90 /ea	14,252
PA equipment power connection - 120V	1 ea	256.53 /ea	257
AM/FM/CD/DVD tuner	1 ea	694.40 /ea	694
Speaker system testing	1 ea	1,986.71 /ea	1,987
Two way communication call box (recessed)	20 ea	799.75 /ea	15,995
Power supply w/battery back up	1 ea	1,714.28 /ea	1,714
Two way communication base station (28 zone)	1 ea	5,980.66 /ea	5,981
Tel/data outlet - (1) CAT-6A cable	20 ea	264.84 /ea	5,297
Tel/data outlet - (2) CAT-6A cables	1 ea	466.16 /ea	466
System testing	1 ea	1,016.70 /ea	1,017
Clock, wall mounted - 12" round	126 ea	283.06 /ea	35,665
Master clock w/ roof mounted antenna	1 ea	3,778.57 /ea	3,779
Wireless clock repeater	1 ea	647.06 /ea	647
Wireless clock transciever	1 ea	647.06 /ea	647
Program unit	1 ea	991.96 /ea	992



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5030 Communications &amp; Security</b>			
Speaker baffle, clock back box	74 ea	202.78 /ea	15,006
Wire guard	20 ea	57.70 /ea	1,154
Clock wiring (EMT)	700 lf	7.03 /lf	4,923
Clock wiring (RS-485 plenum)	500 lf	3.08 /lf	1,540
System testing	1 ls	33.83 /ls	34
Card readers	22 ea	1,163.83 /ea	25,604
Card readers - W.P.	3 ea	1,967.78 /ea	5,903
Electro-magnetic lock	6 ea	657.91 /ea	3,947
Request to exit motion sensor	26 ea	322.33 /ea	8,380
Electric strike	40 ea	400.49 /ea	16,020
Thermal disconnecting means	20 ea	427.58 /ea	8,552
24V power supply	20 ea	295.11 /ea	5,902
Junction box - 6"x6"x4"	20 ea	130.61 /ea	2,612
Power transfer hinge	20 ea	377.68 /ea	7,554
Intrusion digital keypads	4 ea	984.97 /ea	3,940
Dual tech motion detectors	77 ea	595.80 /ea	45,876
Door contacts	63 ea	465.74 /ea	29,342
Access control panel	1 ea	8,222.56 /ea	8,223
Tie in to lighting control system	1 ea	402.23 /ea	402
Security wiring - cable	7,500 lf	3.80 /lf	28,527
Security wiring (EMT)	2,250 lf	8.53 /lf	19,181
Power junctions - 120V/20A	2 ea	193.20 /ea	386
Connect to CCTV system	1 ea	665.43 /ea	665
Proximity cards	250 ea	2.35 /ea	588
Software / licenses, programming, testing, startup (manufacturer)	1 ea	13,308.52 /ea	13,309
CCTV color monitors	2 ea	815.52 /ea	1,631
360-degree multi-sensor interior cameras	28 ea	1,659.85 /ea	46,476
Dome I.P. camera - exterior	19 ea	1,996.28 /ea	37,929
Dome I.P. camera - interior - fixed	27 ea	1,471.85 /ea	39,740
Camera monitoring station	1 ea	1,330.85 /ea	1,331
Video recorders	2 ea	3,131.71 /ea	6,263
Video switchers	2 ea	1,627.71 /ea	3,255
Camera wiring (EMT)	2,500 lf	8.76 /lf	21,899
Camera wiring - cable	7,400 lf	4.04 /lf	29,885
Power junction - 120V/20A	2 ea	193.20 /ea	386
Software / licenses, programming, testing, startup (manufacturer)	1 ea	13,308.52 /ea	13,309
<b>Temporary fire alarm heat detection coverage / stairwell pull stations / temp notification - N/A</b>	-	/-	
Fire alarm impairment plan (NFPA-101)	1 ls	10,000.00 /ls	10,000
Elevator fire alarm interfacing	1 ls	5,000.00 /ls	5,000



90% CD Reconciled Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5030 Communications &amp; Security</b>			
Manual pull stations	25 ea	202.12 /ea	5,053
Mass notification	1 ls	49,999.98 /ls	50,000
Smoke detectors	82 ea	220.39 /ea	18,072
Smoke detector w/ elevator recall	3 ea	373.26 /ea	1,120
Smoke detectors (for Atrium)	89 ea	220.39 /ea	19,615
Smoke detectors w/ elevator recall (for Atrium)	3 ea	373.25 /ea	1,120
Carbon monoxide detector (w/ monitor module)	5 ea	367.16 /ea	1,836
Beam detector (receiver & transmitter)	5 ea	416.88 /ea	2,084
Duct smoke detector (furnish & wire)	40 ea	838.91 /ea	33,556
Remote test switch w/ indicating light	40 ea	194.88 /ea	7,795
Control modules	20 ea	265.75 /ea	5,315
Addressable monitor modules	30 ea	160.83 /ea	4,825
Tamper switch connection (via monitor module)	8 ea	560.06 /ea	4,480
Flow switch connection (via monitor module)	8 ea	403.67 /ea	3,229
Door hold device (magnetic)	5 ea	388.88 /ea	1,944
Wire motorized dampers (120V)	14 ea	407.48 /ea	5,705
Wire combination fire/smoke damper (120V & SLC)	20 ea	608.50 /ea	12,170
Strobe only	48 ea	175.36 /ea	8,417
Speaker/strobes	150 ea	246.56 /ea	36,983
Speaker/strobe - W.P.	1 ea	309.72 /ea	310
Horn/visual - wall mounted	52 ea	222.79 /ea	11,585
Exterior beacons (weatherproof)	4 ea	388.83 /ea	1,555
Fire alarm transponder panels	6 ea	928.51 /ea	5,571
Fire alarm annunciators w/ microphones	3 ea	2,107.39 /ea	6,322
FACP w/ 60-minute battery backup (Notifier NFS640)	1 ea	6,999.66 /ea	7,000
Masterbox (local energy)	1 ea	4,212.70 /ea	4,213
Key (Knox) box	2 ea	806.43 /ea	1,613
Smoke control panel	1 ea	19,502.56 /ea	19,503
Generator monitoring control panel	1 ea	571.80 /ea	572
Fire pump/jockey pump connection	1 ea	402.23 /ea	402
Fire alarm graphic maps	3 ea	1,454.56 /ea	4,364
Fire alarm comissioning	1 ea	6,158.00 /ea	6,158
Fire alarm testing (manufacturer)	6 ea	1,338.28 /ea	8,030
Fire alarm system programming	397 ea	20.79 /ea	8,254
FPLP cable (red) - #14-4/c	11,475 lf	2.23 /lf	25,589
FPLP cable (red) - #16-2/c	12,330 lf	1.83 /lf	22,564
EMT (red) - 3/4"C w/ #16-2/c (exposed)	2,500 lf	7.19 /lf	17,981
EMT (red) - 3/4"C w/ #14-4/c (exposed)	1,200 lf	7.95 /lf	9,535
Circuit integrity cabling (CIC)	1,500 lf	18.31 /lf	27,465
BDA system - parts & smarts (dual-frequency)	136,600 sf	0.47 /sf	64,202



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5030 Communications &amp; Security</b>			
BDA system - installation & minor material (dual-frequency)	136,600 sf	0.19 /sf	25,681
Directional couplers	20 ea	1,150.35 /ea	23,007
In-Line connectors	20 ea	249.01 /ea	4,980
Lightning protection units	5 ea	1,995.53 /ea	9,978
<b>D5030 Communications &amp; Security</b>	<b>136,600 sf</b>	<b>12.46 /sf</b>	<b>1,702,074</b>
<b>D5090 Other Electrical Systems</b>			
LEED Silver - premium (T.B.D.)	1 ls	9,400.00 /ls	9,400
Temp light stringers & GFCI power	136,600 sf	0.35 /sf	47,810
Temp 480Y/277V electrical service (400A)	3 ea	18,226.22 /ea	54,679
Material handling / project mgmt.	250 mh	97.71 /mh	24,428
3D/BIM coordination	500 mh	97.71 /mh	48,856
Record drawings / as-builts	1 ea	5,318.52 /ea	5,319
Seismic & testing (panels, generator, lighting control, fire alarm)	1 ls	18,800.00 /ls	18,800
Coring - patching - firestopping	136,600 sf	0.09 /sf	12,840
Project phasing (re-mobilization)	1 ls	9,400.00 /ls	9,400
Hoisting & rigging (generator & switchboard)	2 ls	7,050.00 /ls	14,100
Building grounding & bonding	136,600 sf	0.11 /sf	15,408
SPD grounding (internal and external)	47 ea	120.29 /ea	5,653
Dry-type transformer grounding	4 ea	213.22 /ea	853
Copper ground bar - 2"x1/4" (ea.)	5 ea	280.03 /ea	1,400
Natural gas generator: 350kW / 437.5kVA	1 ea	133,322.25 /ea	133,322
Generator testing & start-up	1 ea	1,863.20 /ea	1,863
Generator annunciator panel	1 ea	1,447.40 /ea	1,447
Battery charger circuit (4#10 & 1#10G in 1"C)	140 lf	20.94 /lf	2,932
Jacket heater circuit	140 lf	34.49 /lf	4,828
Oil heater circuit	140 lf	53.66 /lf	7,512
Exterior W.P. sound attenuating enclosure (350kW)	1 ea	19,478.75 /ea	19,479
Remote status panel circuit	140 lf	9.64 /lf	1,349
Starting circuits - 2#14 MI cable	140 lf	12.76 /lf	1,787
Remote annunciator panel - 16#14 (EMT)	100 lf	15.81 /lf	1,581
Quick connect switch, ESL Storm Switch 3020	1 ea	3,668.10 /ea	3,668
UPS: 480-208/120V, 24kW (static ts, manual by-pass, 8min batt.BU)	2 ea	30,061.40 /ea	60,123
Lightning prevention system subcontractor	1 ls	30,000.00 /ls	30,000
<b>D5090 Other Electrical Systems</b>	<b>136,600 sf</b>	<b>3.95 /sf</b>	<b>538,839</b>
<b>D50 Electrical Systems</b>	<b>136,600 sf</b>	<b>38.05 /sf</b>	<b>5,196,968</b>
<b>D Services</b>	<b>136,600 sf</b>	<b>120.43 /sf</b>	<b>16,451,226</b>



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>E Equipment &amp; Furnishings</b>			
<b>E10 Equipment</b>			
<b>E1020 Institutional Equipment</b>			
Loading dock equipment	1 ls	1,000.00 /ls	1,000
Food service equipment - Allowance	1 ls	415,270.00 /ls	415,270
Vocational shop equipment	1 ls	25,000.00 /ls	25,000
- <b>Welding booths - In Above</b>	-	/-	
- <b>Portable welding fumes extractor - In Above</b>	-	/-	
- <b>Paint spray hoods - In Above</b>	-	/-	
- <b>Portable wood working equipment dust collector - In HVAC</b>	-	/-	
Kiln	1 ls	12,000.00 /ls	12,000
Sound systems @ Auditorium - Allowance	1 allw	200,000.00 /allw	200,000
Sound systems @ Gym - Allowance	1 allw	120,000.00 /allw	120,000
Sound systems @ Cafeteria - Allowance	1 allw	50,000.00 /allw	50,000
Sound systems @ Band/Chorus - Allowance	2 allw	30,000.00 /allw	60,000
Sound systems @ Drama - Allowance	1 allw	20,000.00 /allw	20,000
Projection screen @ Gym, Cafeteria	2 ea	10,000.00 /ea	20,000
Projection screen	1 ea	5,000.00 /ea	5,000
<b>Orchestra enclosures - FFE</b>	-	/-	
Theatrical rigging - Allowance	1 ls	158,300.00 /ls	158,300
Theatrical draperies - Allowance	1 ls	33,854.00 /ls	33,854
Theatrical lighting instruments & accessories - Allowance	1 ls	129,018.00 /ls	129,018
Theatrical lighting controls - Allowance	1 ls	95,749.00 /ls	95,749
Basketball backstop - ceiling-hung	6 ea	6,500.00 /ea	39,000
Gym divider curtain - electric roll up	1,530 sf	20.00 /sf	30,600
Athletic wall padding	835 sf	12.50 /sf	10,438
Volleyball system	1 ls	5,000.00 /ls	5,000
Fixed audience seating	406 ea	285.00 /ea	115,710
Retractable Bleachers at Gym	650 seat	155.00 /seat	100,750
<b>E1020 Institutional Equipment</b>	<b>136,600 sf</b>	<b>12.06 /sf</b>	<b>1,646,689</b>
<b>E1090 Other Equipment</b>			
Refrigerator	7 ea	1,200.00 /ea	8,400
<b>Ice maker - None shown</b>	-	/-	
<b>Undercounter refrigerator - None shown</b>	-	/-	
Microwave oven	1 ea	450.00 /ea	450
Range hood	1 ea	650.00 /ea	650
Range	1 ea	900.00 /ea	900
Dishwasher	4 ea	925.00 /ea	3,700
Washer/dryer - stackable	2 ea	1,500.00 /ea	3,000
Scoreboards - basketball	1 ea	7,500.00 /ea	7,500



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>E1090 Other Equipment</b>	<b>136,600 sf</b>	<b>0.18 /sf</b>	<b>24,600</b>
<b>E10 Equipment</b>	<b>136,600 sf</b>	<b>12.24 /sf</b>	<b>1,671,288</b>
<b>E20 Furnishings</b>			
<b>E2010 Fixed Furnishings</b>			
Hardwood trim @ locker guardrail per A650	3,300 lf	15.00 /lf	49,500
P-lam top panels @ locker guardrail per A650	1,025 lf	50.00 /lf	51,250
P-lam side panels @ locker guardrail per A650	450 lf	50.00 /lf	22,500
Casework for lockers (bank of 5) - including base	1,025 lf	250.00 /lf	256,250
P-lam base cabinet w/top	40 lf	450.00 /lf	18,000
P-lam workstation w/top	770 lf	250.00 /lf	192,500
Mobile storage	172 ea	1,000.00 /ea	172,000
Mobile storage - VM I05	(172) ea	1,000.00 /ea	(172,000)
P-lam valance for fin tube	570 lf	45.00 /lf	25,650
P-lam 3/4" lip at counter for fin tube	570 lf	4.00 /lf	2,280
P-lam wall cabinet	40 lf	325.00 /lf	13,000
P-lam full height cabinet	50 lf	700.00 /lf	35,000
Bathroom vanity w/top	210 lf	250.00 /lf	52,500
Reception cabinet	20 lf	1,000.00 /lf	20,000
P-lam circulation desk	10 lf	750.00 /lf	7,500
P-lam work counter @ Admin	10 lf	1,500.00 /lf	15,000
<b>P-lam counter @ Servery - In Food Service</b>	-	/-	
P-lam end/filler panels @ Admin	10 lf	135.00 /lf	1,350
Mailboxes	18 lf	415.00 /lf	7,470
Storage shelving	380 lf	150.00 /lf	57,000
Storage shelving w/MDF	470 lf	200.00 /lf	94,000
P-lam bookcases	40 lf	500.00 /lf	20,000
Built-in benches	205 lf	600.00 /lf	123,000
Free-standing benches	35 lf	600.00 /lf	21,000
Display cases	5 ea	4,500.00 /ea	22,500
<b>Misc. casework - N/A</b>	-	/-	
Misc. lab equipment - Allowance	1 ls	25,000.00 /ls	25,000
Fume hoods	3 ea	11,000.00 /ea	33,000
Fume hoods - 2-sided	1 ea	15,000.00 /ea	15,000
Roller shades	10,235 sf	8.00 /sf	81,880
Roller shades - motorized	970 sf	18.00 /sf	17,460
Roller shades - interior	3,300 sf	8.00 /sf	26,400
Roller shades - doors	50 ea	150.00 /ea	7,500
Base cabinet w/epoxy top	30 lf	600.00 /lf	18,000
Epoxy countertop - open below	325 lf	375.00 /lf	121,875



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>E2010 Fixed Furnishings</b>			
Epoxy backsplash	635 lf	60.00 /lf	38,100
Wall cabinets	105 lf	400.00 /lf	42,000
<b>E2010 Fixed Furnishings</b>	<b>136,600 sf</b>	<b>11.23 /sf</b>	<b>1,533,465</b>
<b>E20 Furnishings</b>	<b>136,600 sf</b>	<b>11.23 /sf</b>	<b>1,533,465</b>
<b>E Equipment &amp; Furnishings</b>	<b>136,600 sf</b>	<b>23.46 /sf</b>	<b>3,204,754</b>
<b>F Special Construction &amp; Demolition</b>			
<b>F20 Demolition</b>			
<b>F2010 Building Elements Demolition</b>			
Building demolition	195,400 sf	7.00 /sf	1,367,800
<b>F2010 Building Elements Demolition</b>	<b>194,500 sf</b>	<b>7.03 /sf</b>	<b>1,367,800</b>
<b>F2020 Hazardous Component Abatement</b>			
Asbestos abatement	195,400 sf	8.20 /sf	1,602,280
<b>F2020 Hazardous Component Abatement</b>	<b>194,500 sf</b>	<b>8.24 /sf</b>	<b>1,602,280</b>
<b>F20 Demolition</b>	<b>194,500 sf</b>	<b>15.27 /sf</b>	<b>2,970,080</b>
<b>F Special Construction &amp; Demolition</b>	<b>194,500 sf</b>	<b>15.27 /sf</b>	<b>2,970,080</b>
<b>G Sitework</b>			
<b>G10 Site Preparation</b>			
<b>G1010 Site Clearing</b>			
<i>Mobilizations</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Survey/layout</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Police details</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Precast Concrete Jersey Barriers for Temp. Parking Lot</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Temporary site signage</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>As-built plan preparation</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Localized dewatering</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Clear &amp; grub, vegetation removal</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Strip &amp; stockpile topsoil/loam</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Construct Phase 2 Temp. Sediment Basins</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>SWPPP (Prep of SWPPP by civil engineer)</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>12" diameter Straw Wattles</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Silt sacks at catch basin</i>	<i>BP#1</i>	<i>/BP#1</i>	



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>G1010 Site Clearing</b>			
<i>Construction entrance</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Street sweeping</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Inspect / repair silt barrier weekly</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Remove erosion control measure at project completion</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Asphalt paving - Temp. Parking Layout</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Temporary roads and maintenance required during construction</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>G1010 Site Clearing</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>G1020 Site Demolition &amp; Relocations</b>			
<i>Demo hydrants</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo bituminous concrete paving</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo bituminous walk</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo Temporary Bituminous Parking &amp; Access Pavement</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo concrete sidewalks/pads/ramps</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo curbing</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Cut &amp; cap site utilities - water</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Cut &amp; cap site utilities - sewer</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo utility piping - water</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo utility piping - sewer</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo utility piping - electrical</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo utility piping - drain</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo utility piping - gas</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo drain structures</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo grease trap</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo fencing/guardrail</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Misc. site demolition</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo utility poles</i>	<i>BP#1</i>	<i>/BP#1</i>	
Flag pole	1 ea	9,000.00 /ea	9,000
<b>G1020 Site Demolition &amp; Relocations</b>	<b>136,600 sf</b>	<b>0.07 /sf</b>	<b>9,000</b>
<b>G1030 Site Earthwork</b>			
<i>Preconstruction survey and vibration monitoring &amp; compliance</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Rough grading</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Fine grading - building SOG</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Fine grading - paving</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Fine grading - conc walks &amp; site pads</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Fine grading - bituminous walks</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Cut to subgrade @ site</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Fill to subgrade from cut @ site</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Grind foundations for fill - In Demolition</i>	-	/-	





# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>G1030 Site Earthwork</b>			
<i>Fill to subgrade @ site - import</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Site cuts to stockpile for temporary parking &amp; access layout</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Site surcharge</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Contaminated soil removal - unlined landfill</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Rock removal - NIC</i>	-	/-	
Import loam & spread (6") at Lawns, Athletic Fields & Native Meadows	5,594 cy	40.00 /cy	223,760
Ammend & spread (6") at Lawns, Athletic Fields & Native Meadows	6,030 cy	12.00 /cy	72,360
Import loam & spread (6") at Detention Basins	802 cy	40.00 /cy	32,080
Import loam & spread (12") at Plant Beds	375 cy	40.00 /cy	15,000
Landscape Metal Edging at Building Mow Strip	2,330 lf	15.00 /lf	34,950
Building Mowing Strip- (Peastone)	100 tn	50.00 /tn	5,000
Import loam & spread (6") at Sodded Amphlitheather Lawns	691 cy	40.00 /cy	27,640
<b>G1030 Site Earthwork</b>	<b>136,600 sf</b>	<b>3.01 /sf</b>	<b>410,790</b>
<b>G10 Site Preparation</b>	<b>136,600 sf</b>	<b>3.07 /sf</b>	<b>419,790</b>
<b>G20 Site Improvements</b>			
<b>G2010 Roadways</b>			
<i>Street plates for protection</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>G2010 Roadways</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>G2020 Parking Lots</b>			
<i>Gravel base course @ asphalt pavements</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Gravel base course @ Raised Stamped asphalt pavement at Flag Drive</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>1 1/2" crushed stone base course - concrete walks &amp; site pads</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Asphalt paving - (Parking Lots &amp; Site Drives)</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Asphalt paving - top course @ temporary to permanent</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Precast concrete curbs</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Vertical granite curbs</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Handicapped ramps at curbing</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Detectable Warning Plates at Handicapped Ramps</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Speed bumps - bituminous</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Pavement markings</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Parking signage</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>G2020 Parking Lots</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>G2030 Pedestrian Paving</b>			
<i>Processed Aggregate base course - bituminous walks</i>	<i>BP#1</i>	<i>/BP#1</i>	



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>G2030 Pedestrian Paving</b>			
<i>Concrete pavement</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Steps - premium</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Dumpster pad</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Concrete pavement with sawcut joints</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Stamped pavement at Flagg Drive</i>	<i>BP#1</i>	<i>/BP#1</i>	
Pavers - plaza paving	745 sf	25.00 /sf	18,625
Stone Dust at Raised Planter	32 sf	20.00 /sf	640
<i>Bituminous sidewalks</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>G2030 Pedestrian Paving</b>	<b>136,600 sf</b>	<b>0.14 /sf</b>	<b>19,265</b>
<b>G2040 Site Development</b>			
<i>Retaining footing</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Retaining wall</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Concrete bench/seat wall</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Steel @ Bandshell - AESS</i>	<i>BP#2</i>	<i>/BP#2</i>	
Guardrails - exterior, colorgalv	240 lf	325.00 /lf	78,000
Phenolic bench per A102A	1 ea	4,200.00 /ea	4,200
Glass @ Bandshell (vertical) - 9/16" tempered, laminated	235 sf	150.00 /sf	35,250
Glass @ Bandshell (roof) - 9/16" tempered, laminated	300 sf	150.00 /sf	45,000
Prep/paint Bandshell	1 ls	10,000.00 /ls	10,000
Prep/paint main and West Admin egress canopies	1 ls	10,000.00 /ls	10,000
Exterior signage	1 ls	25,000.00 /ls	25,000
Wood benches	20 lf	750.00 /lf	15,000
Bicycle Racks	20 ea	785.00 /ea	15,700
Basketball Poles & Hoops	2 ea	8,000.00 /ea	16,000
Miscellaneous site furnishings - Allowance	1 ls	30,000.00 /ls	30,000
<i>Gravel base course - misc site amenities- (i.e.- curbing, swales,etc.)</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Basketball Court Pavement- (3 1/2" Total Paving w/ Gravel Base)</i>	<i>sf</i>	<i>/sf</i>	
<i>- BP#1</i>			
Basketball Court Pavement Markings	1 ls	2,000.00 /ls	2,000
<i>Wooden Guardrailing</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Fencing - N/A</i>	<i>-</i>	<i>/-</i>	
24' wide Single Arm Gate	1 ea	3,500.00 /ea	3,500
<i>Wooden Guardrailing - BP#1</i>	<i>lf</i>	<i>/lf</i>	
<i>Bollards - 6" steel w/concrete - BP#1</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Bollards - 6" steel w/concrete - BP#1</i>	<i>ea</i>	<i>/ea</i>	
<i>Bollards - architectural</i>	<i>0 ea</i>	<i>/ea</i>	
Segmental retaining wall	2,600 sf	50.00 /sf	130,000
Additional segmental retaining wall per PR #12	220 sf	50.00 /sf	11,000



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>G2040 Site Development</b>	<b>136,600 sf</b>	<b>3.15 /sf</b>	<b>430,650</b>
<b>G2050 Landscaping</b>			
Landscaping maintenance	1 yr	8,000.00 /yr	8,000
<i>Irrigation system @ south sports field - by others</i>	-	/-	
Irrigation @ ampitheater - Allowance	23,435 sf	2.00 /sf	46,870
Irrigation system @ north sports field - Allowance	81,000 sf	2.00 /sf	162,000
Mulch at trees and planting beds (3")	240 cy	105.00 /cy	25,200
Fine grade & hydroseed lawn areas	119,420 sf	0.30 /sf	35,826
Fine grade & seed (Native Wildflower Meadow)	104,005 sf	0.25 /sf	26,001
Fine grade & seed (Detention Basin Mix- Hydroseed)	33,330 sf	0.25 /sf	8,333
Fine grade & seed (Natural Turf Fields)	259,269 sf	0.25 /sf	64,817
Sod (Amphiltheather Lawns)	28,719 sf	1.50 /sf	43,079
Sod (100'x170') - Temporary	17,000 sf	1.50 /sf	25,500
Sod northeast - Phase 3 play area, temporary	5,000 sf	1.50 /sf	7,500
Watering for sod areas - Fields	1 ls	7,500.00 /ls	7,500
Watering for sod areas - Amphitheater	1 ls	7,500.00 /ls	7,500
Trees	118 ea	750.00 /ea	88,500
Shrubs (478 Total)	7,736 sf	8.50 /sf	65,756
Groundcover/perennials	1,966 ea	20.00 /ea	39,320
Plantings @ planter beds	1 ls	20,000.00 /ls	20,000
<i>Rain garden - N/A</i>	-	/-	
<b>G2050 Landscaping</b>	<b>136,600 sf</b>	<b>4.99 /sf</b>	<b>681,702</b>
<b>G20 Site Improvements</b>	<b>136,600 sf</b>	<b>8.28 /sf</b>	<b>1,131,617</b>
<b>G30 Site Civil/Mechanical Utilites</b>			
<b>G3010 Water Supply</b>			
<i>Fire hydrants</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Fire hydrant - relocate existing</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Gate valves, tees, bends, thrust blocks, restraints</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Water distribution connections to existing</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Water line - domestic</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Water line - hydrant &amp; fire services</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Pressure test &amp; chlorinate</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>G3010 Water Supply</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>G3020 Sanitary Sewer</b>			
<i>Sanitary sewer piping</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Sanitary sewer manholes</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Connect to existing structures</i>	<i>BP#1</i>	<i>/BP#1</i>	



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>G3020 Sanitary Sewer</b>			
<i>Utility and sewer tie-in at trailer</i>	<b>BP#1</b>	<b>/BP#1</b>	
<i>Sanitary sewer testing - piping</i>	<b>BP#1</b>	<b>/BP#1</b>	
<i>Video inspect incoming sewer, etc.</i>	<b>BP#1</b>	<b>/BP#1</b>	
<i>Sanitary sewer testing - structures</i>	<b>BP#1</b>	<b>/BP#1</b>	
<i>Grease interceptor - In Plumbing</i>	-	/-	
<i>Acid Neutralization - In Plumbing</i>	-	/-	
<b>G3020 Sanitary Sewer</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>G3030 Storm Drainage</b>			
<i>Catch basins</i>	<b>BP#1</b>	<b>/BP#1</b>	
<i>Granite Curb Inlets</i>	<b>BP#1</b>	<b>/BP#1</b>	
<i>Storm drainage manholes</i>	<b>BP#1</b>	<b>/BP#1</b>	
<i>Outlet control structures</i>	<b>BP#1</b>	<b>/BP#1</b>	
<i>Storm headwalls</i>	<b>BP#1</b>	<b>/BP#1</b>	
<i>Stormceptors</i>	<b>BP#1</b>	<b>/BP#1</b>	
<i>Storm drainage piping</i>	<b>BP#1</b>	<b>/BP#1</b>	
<i>Rip Rap Splash Pads</i>	<b>BP#1</b>	<b>/BP#1</b>	
<i>Weir Overflows</i>	<b>BP#1</b>	<b>/BP#1</b>	
<i>Check dams</i>	<b>BP#1</b>	<b>/BP#1</b>	
<i>Foundation drainage piping</i>	<b>BP#1</b>	<b>/BP#1</b>	
<i>Infiltration system</i>	<b>BP#1</b>	<b>/BP#1</b>	
<b>G3030 Storm Drainage</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>G3060 Fuel Distribution</b>			
<i>Excavation / backfill for gas line</i>	<b>BP#1</b>	<b>/BP#1</b>	
<b>G3060 Fuel Distribution</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>G30 Site Civil/Mechanical Utilites</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>G40 Site Electrical Utilities</b>			
<b>G4010 Electrical Distribution</b>			
Temp power for welders	2 ea	2,398.27 /ea	4,797
Temp power for trailers	4 ea	1,302.42 /ea	5,210
Temp internet connection for trailers	4 ea	1,854.17 /ea	7,417
Feeder (PVC/CU) - 150A [generator / LS]	135 lf	22.18 /lf	2,994
Feeder (PVC/CU) - 225A [generator / OS]	135 lf	33.46 /lf	4,517
Feeder (PVC/CU) - 400A [generator / LR] (exterior)	135 lf	56.93 /lf	7,685
Feeder (PVC/CU) - 2500A [secondary]	105 lf	414.00 /lf	43,470
Empty conduit - sch 40 PVC: 1 x 4" [generator]	135 lf	9.86 /lf	1,330
Empty conduit - sch 40 PVC: 1 x 4" [secondary / spare]	105 lf	9.86 /lf	1,035



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>G4010 Electrical Distribution</b>			
Empty conduit - sch 40 PVC: 2 x 4" [primary]	250 lf	17.66 /lf	4,415
Magnetic warning tape - 1/8"	875 lf	4.37 /lf	3,826
Pole riser (GRC - 4"C)	2 ea	2,343.85 /ea	4,688
Electric manhole - 6'x12x7'	1 ea	6,773.56 /ea	6,774
Cast iron manhole frame/cover, 32"D x 6'H grade rings	1 ea	1,140.93 /ea	1,141
12" x 12" x 12"D ground mounted pullbox (Quazite #PC1212HG00 w/ Cover)	2 ea	752.15 /ea	1,504
Hand hole & cover - 4'x4'x4'	6 ea	1,937.11 /ea	11,623
17"x30"x12"D ground pullbox (Quazite #PC1730BA12 w/ cover)	11 ea	1,078.60 /ea	11,865
24" x 36" x 24"D ground mounted pullbox (Quazite #Pg2436BC-24 w/ Cover)	1 ea	1,718.39 /ea	1,718
Manhole / racking grounding & bonding	1 ea	701.05 /ea	701
Exterior (utility) transformer grounding & bonding	1 ea	1,066.05 /ea	1,066
Generator grounding & bonding	1 ea	1,066.05 /ea	1,066
Bare copper wire - #4/0 [duct bank]	875 lf	4.99 /lf	4,368
Electric vehicle charging station / dual pedestal / cable mgmt.	3 ea	10,512.40 /ea	31,537
Utility meter socket (meter by Util. Co.)	1 ea	289.66 /ea	290
CT meter enclosure for switchboard	1 ea	1,462.26 /ea	1,462
<b>Excavation/backfill for Emergency Generator ductbank</b>	<b>BP#1</b>	<b>/BP#1</b>	
<b>Excavation/backfill for Primary Electric ductbank</b>	<b>BP#1</b>	<b>/BP#1</b>	
<b>Excavation/backfill for Fire Alarm ductbank</b>	<b>BP#1</b>	<b>/BP#1</b>	
<b>Excavation/backfill for Telcom ductbank</b>	<b>BP#1</b>	<b>/BP#1</b>	
<b>Excavation/backfill for U.G. ductbank</b>	<b>BP#1</b>	<b>/BP#1</b>	
<b>Excavation/backfill for 2"C Power Data ductbank (Amphitheater)</b>	<b>BP#1</b>	<b>/BP#1</b>	
<b>Excavation/backfill for 2"C to IDF ductbank</b>	<b>BP#1</b>	<b>/BP#1</b>	
<b>Concrete and rebar for electrical/telcom ductbanks</b>	<b>BP#1</b>	<b>/BP#1</b>	
<b>6" Concrete Filled Steel Pipe Bollards at Generator &amp; Transformer Pads</b>	<b>BP#1</b>	<b>/BP#1</b>	
<b>G4010 Electrical Distribution</b>	<b>136,600 sf</b>	<b>1.22 /sf</b>	<b>166,498</b>
<b>G4020 Site Lighting</b>			
Remove existing exterior site light fixture	11 ea	672.85 /ea	7,401
Lighting contactor - 12 pole (exterior lighting)	1 ea	1,899.98 /ea	1,900
SL5: exterior amphitheater RGB projector, DMX capable, IP65 rated [O]	8 ea	3,626.85 /ea	29,015
SLS: LED recessed step light, 0-10V dimming capable [C]	7 ea	732.90 /ea	5,130
SL1: LED pole mounted luminaires mounted on a 20' pole [O]	35 ea	2,891.40 /ea	101,199
SL2A: exterior post top fixture with 15' round tapered alum pole [O]	13 ea	5,492.50 /ea	71,403
SL3: exterior bollard 43.3 cast illuminium [O]	9 ea	1,929.78 /ea	17,368



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>G4020 Site Lighting</b>			
SL10: LED mini in-ground flood fixture capable of 0-10V dimming [O]	12 ea	978.60 /ea	11,743
EMT (12/2) - 20A	1,400 lf	7.13 /lf	9,981
1" PVC - 30A (3#8 & #10G)	6,900 lf	10.95 /lf	75,528
1" GRC - 90 Deg Sweep	114 ea	174.22 /ea	19,861
<b>Emergency Call Box base</b>	<b>BP#1</b>	<b>/BP#1</b>	
<b>EV Parking Station bases</b>	<b>BP#1</b>	<b>/BP#1</b>	
<b>Light pole bases</b>	<b>BP#1</b>	<b>/BP#1</b>	
<b>G4020 Site Lighting</b>	<b>136,600 sf</b>	<b>2.57 /sf</b>	<b>350,530</b>
<b>G4030 Site Communications &amp; Security</b>			
Relocate existing emergency call box (provide new concrete base)	1 ea	2,994.80 /ea	2,995
Empty conduit (PVC) - 1"	250 lf	8.07 /lf	2,016
Empty conduit (PVC) - 2"	700 lf	6.03 /lf	4,223
Empty conduit (sch 40 PVC) (4) 4"C (CATV, Telephone, Fiber, Spare)	220 lf	32.32 /lf	7,110
Three (3) 1.25" inner ducts for fiber	220 lf	15.50 /lf	3,411
Communications utility pole conduit riser (GRC - 4"C)	4 ea	2,343.84 /ea	9,375
Telecom manhole & cover - 4'x6'x7'	1 ea	3,920.36 /ea	3,920
360-degree multi-sensor exterior cameras mounted on poles	3 ea	4,509.56 /ea	13,529
Camera wiring (PVC)	600 lf	13.34 /lf	8,003
Ductbank w/ IMSA cable - 2" PVC	320 lf	16.30 /lf	5,217
<b>Excavation/backfill for site lighting</b>	<b>BP#1</b>	<b>/BP#1</b>	
<b>G4030 Site Communications &amp; Security</b>	<b>136,600 sf</b>	<b>0.44 /sf</b>	<b>59,799</b>
<b>G40 Site Electrical Utilities</b>	<b>136,600 sf</b>	<b>4.22 /sf</b>	<b>576,826</b>
<b>G Sitework</b>	<b>136,600 sf</b>	<b>15.58 /sf</b>	<b>2,128,233</b>



**CONSIGLI**  
*Est. 1905*







**Fuller Middle School**  
**90% CD Reconciled Estimate**

10/7/2019

**CONSIGLI**  
*Est. 1905*

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
01-54 SCAFFOLDING	136,600 sf	0.55 /sf	75,000
02-20 SELECTIVE DEMOLITION	136,600 sf	10.01 /sf	1,367,800
02-82 HAZARDOUS MATERIAL ABATEMENT	136,600 sf	11.73 /sf	1,602,280
03-30 CONCRETE	136,600 sf	/sf	
03-45 POLISHED CONCRETE	136,600 sf	/sf	
04-20 MASONRY (TS)	136,600 sf	16.77 /sf	2,290,785
05-12 STRUCTURAL STEEL	136,600 sf	/sf	
05-50 MISCELLANEOUS METALS (TS)	136,600 sf	8.15 /sf	1,112,650
06-25 FINISH CARPENTRY	136,600 sf	14.13 /sf	1,929,625
07-10 WATERPROOFING & JOINT SEALANTS (TS)	136,600 sf	5.30 /sf	723,860
07-42 METAL/COMPOSITE PANELS & SIDING	136,600 sf	8.79 /sf	1,201,245
07-50 MEMBRANE ROOFING (TS)	136,600 sf	11.07 /sf	1,512,408
07-81 FIREPROOFING	136,600 sf	2.94 /sf	401,945
08-10 DOORS, FRAMES & HARDWARE	136,600 sf	5.21 /sf	711,550
08-34 OVERHEAD DOORS & GRILLES	136,600 sf	0.55 /sf	74,750
08-41 ALUMINUM STOREFRONT & WINDOWS (TS)	136,600 sf	17.68 /sf	2,415,350
08-45 TRANSLUCENT PANEL SYSTEMS	136,600 sf	/sf	
08-80 GLASS & GLAZING (TS)	136,600 sf	7.40 /sf	1,010,875
08-90 LOUVERS	136,600 sf	0.39 /sf	53,125
09-21 DRYWALL	136,600 sf	46.10 /sf	6,297,346
09-30 TILE (TS)	136,600 sf	1.61 /sf	219,185
09-51 ACOUSTICAL CEILINGS (TS)	136,600 sf	6.62 /sf	903,664
09-64 WOOD FLOORING	136,600 sf	1.55 /sf	211,650
09-65 RESILIENT FLOORING (TS)	136,600 sf	6.19 /sf	845,813
09-67 RESINOUS FLOORING	136,600 sf	0.59 /sf	80,920
09-68 CARPET	136,600 sf	0.17 /sf	23,475
09-90 PAINTING (TS)	136,600 sf	3.85 /sf	525,823
10-14 SIGNAGE	136,600 sf	0.53 /sf	72,810
10-24 OPERABLE PARTITIONS	136,600 sf	2.15 /sf	293,545
10-51 LOCKERS	136,600 sf	3.05 /sf	416,260
10-95 MISCELLANEOUS SPECIALTIES	136,600 sf	2.84 /sf	387,827
11-31 RESIDENTIAL APPLIANCES	136,600 sf	0.13 /sf	17,100





Description	Takeoff Quantity	Total Cost/Unit	Total Amount
11-40 FOOD SERVICE EQUIPMENT	136,600 sf	3.04 /sf	415,270
11-51 AUDIO-VISUAL EQUIPMENT	136,600 sf	3.29 /sf	450,000
11-61 THEATER & STAGE EQUIPMENT	136,600 sf	3.05 /sf	416,921
11-65 ATHLETIC/RECREATIONAL EQUIPMENT	136,600 sf	0.68 /sf	92,538
11-95 VOCATIONAL SHOP EQUIPMENT	136,600 sf	0.27 /sf	37,000
12-20 WINDOW TREATMENTS	136,600 sf	0.98 /sf	133,240
12-35 LAB CASEWORK	136,600 sf	2.15 /sf	292,975
12-60 FIXED AUDITORIUM SEATING	136,600 sf	0.85 /sf	115,710
12-62 BLEACHERS	136,600 sf	0.74 /sf	100,750
14-20 ELEVATORS (TS)	136,600 sf	1.61 /sf	220,000
21-01 FIRE PROTECTION (TS)	136,600 sf	6.40 /sf	873,859
22-01 PLUMBING (TS)	136,600 sf	14.89 /sf	2,033,274
23-01 HVAC (TS)	136,600 sf	59.49 /sf	8,126,676
26-01 ELECTRICAL (TS)	136,600 sf	42.27 /sf	5,773,794
31-23 SITEWORK	136,600 sf	/sf	
32-10 LANDSCAPING & SITE IMPROVEMENTS	136,600 sf	9.81 /sf	1,340,457
32-31 FENCING	136,600 sf	0.03 /sf	3,500



**Estimate Totals**

Description	Amount	Totals	Rate	Cost per Unit
Subtotal	<b>47,204,628</b>	<b>47,204,628</b>		<b>345.57 /sf</b>
Design/Estimate Contingency	1,416,139		3.000 %	10.37 /sf
Escalation	486,208		1.000 %	3.56 /sf
<b>Subtotal</b>	<b>1,902,347</b>	<b>49,106,975</b>		<b>359.49 /sf</b>
SDI (Non-Trade Contracts)	260,633		1.400 %	1.91 /sf
Sub Bonds (Trade Contracts)	400,232		1.400 %	2.93 /sf
Contractor's Contingency	1,244,196		2.500 %	9.11 /sf
General Conditions	2,931,033			21.46 /sf
General Requirements	2,289,380			16.76 /sf
<b>Subtotal</b>	<b>7,125,474</b>	<b>56,232,449</b>		<b>411.66 /sf</b>
Builder's Risk Insurance - BP1				
General Liability Insurance	576,109			4.22 /sf
Building Permit - NIC				
Performance & Payment Bond				
<b>Subtotal</b>	<b>576,109</b>	<b>56,808,558</b>		<b>415.88 /sf</b>
Fee	1,152,218			8.43 /sf
Amendment #1 - Sitework	10,957,843			80.22 /sf
- Addendum #3: Delete Traffic Table	(195,200)			(1.43) /sf
- Addendum #3: Reduced Fill at Amphitheater	(18,000)			(0.13) /sf
Amendment #2 - Concrete & Steel	8,738,800			63.97 /sf
Amendment #2 - Buy Savings	(50,755)			(0.37) /sf
<b>Total</b>		<b>77,393,464</b>		<b>566.57 /sf</b>





**CONSIGLI**  
*Est. 1905*





Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>01-54 SCAFFOLDING</b>			
<b>01.54.23 Temporary Scaffolding &amp; Platforms</b>			
Dance floor at auditorium - multi-trade	1 ls	75,000.00 /ls	75,000
<b>Temporary Scaffolding &amp; Platforms</b>	<b>136,600 sf</b>	<b>0.55 /sf</b>	<b>75,000</b>
<b>01-54 SCAFFOLDING</b>	<b>136,600 sf</b>	<b>0.55 /sf</b>	<b>75,000</b>
<b>02-20 SELECTIVE DEMOLITION</b>			
<b>02.41.01 Demolition - General</b>			
Building demolition	195,400 sf	7.00 /sf	1,367,800
<b>Demolition - General</b>	<b>136,600 sf</b>	<b>10.01 /sf</b>	<b>1,367,800</b>
<b>02-20 SELECTIVE DEMOLITION</b>	<b>136,600 sf</b>	<b>10.01 /sf</b>	<b>1,367,800</b>
<b>02-82 HAZARDOUS MATERIAL ABATEMENT</b>			
<b>02.82.00 Asbestos Remediation</b>			
Asbestos abatement	195,400 sf	8.20 /sf	1,602,280
<b>Asbestos Remediation</b>	<b>136,600 sf</b>	<b>11.73 /sf</b>	<b>1,602,280</b>
<b>02-82 HAZARDOUS MATERIAL ABATEMENT</b>	<b>136,600 sf</b>	<b>11.73 /sf</b>	<b>1,602,280</b>
<b>03-30 CONCRETE</b>			
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Concrete)	(1) ls	116,000.00 /ls	(116,000)
Trade support - lull, laborer for cleanup (Concrete)	1 ls	116,000.00 /ls	116,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>03.11.50 Concrete Forming - Flatwork</b>			
<b>Slab depressions</b>	<b>BP#2</b>	<b>/BP#2</b>	
<b>Concrete Forming - Flatwork</b>	<b>135,589 sf</b>	<b>/sf</b>	
<b>03.11.75 Concrete Forming - Pits</b>			
<b>Elevator pit</b>	<b>BP#2</b>	<b>/BP#2</b>	
<b>Concrete Forming - Pits</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>03.31.10 Concrete Ready Mix - Site</b>			
<b>Retaining footing</b>	<b>BP#2</b>	<b>/BP#2</b>	
<b>Retaining wall</b>	<b>BP#2</b>	<b>/BP#2</b>	



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>03.31.10 Concrete Ready Mix - Site</b>			
Concrete bench/seat wall		BP#2	/BP#2
Concrete Ready Mix - Site	136,600 sf		/sf
<b>03.31.20 Concrete Ready Mix - Foundations</b>			
F3 spread footings		BP#2	/BP#2
F4 spread footings		BP#2	/BP#2
F5 spread footings		BP#2	/BP#2
F6 spread footings		BP#2	/BP#2
F7 spread footings		BP#2	/BP#2
F8 spread footings		BP#2	/BP#2
F9 spread footings		BP#2	/BP#2
F10 spread footings		BP#2	/BP#2
F11 spread footings		BP#2	/BP#2
F12 spread footings		BP#2	/BP#2
Continuous footings - 3'x12"		BP#2	/BP#2
Continuous footings - 4'x12"		BP#2	/BP#2
Continuous footings - 5'x12" @ Bandshell		BP#2	/BP#2
Foundation walls - 16"		BP#2	/BP#2
Foundation walls - 16" @ Bandshell		BP#2	/BP#2
Foundation walls - 21"		BP#2	/BP#2
Retaining walls - 16"		BP#2	/BP#2
Concrete walls @ Auditorium		BP#2	/BP#2
Piers - 24"x24"		BP#2	/BP#2
Grade beam 1		BP#2	/BP#2
Grade beam 2		BP#2	/BP#2
Concrete Ready Mix - Foundations	136,600 sf		/sf
<b>03.31.50 Concrete Ready Mix - Flatwork</b>			
Slab on grade - 5"		BP#2	/BP#2
Concrete Ready Mix - Flatwork	136,600 sf		/sf
<b>03.35.55 Concrete Finishing - Slabs-on-Grades</b>			
Power trowel/seal concrete @ Auditorium		BP#2	/BP#2
Concrete Finishing - Slabs-on-Grades	136,600 sf		/sf
<b>03.35.60 Concrete Finishing - Slabs-on-Decking</b>			
Place & finish slabs - 2-1/2" on 3" deck @ roof		BP#2	/BP#2
Place & finish slabs - 3-1/4" on 3" deck @ floor (LW)		BP#2	/BP#2
Topping slab @ Breakout LGMF floors		BP#2	/BP#2
Place & finish slabs - 3-1/4" on 3" deck @ roof		BP#2	/BP#2





Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Concrete Finishing - Slabs-on-Decking</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>03.35.90 Concrete Finishing - Miscellaneous</b>			
<i>Place &amp; finish stair treads/landings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<b>Concrete Finishing - Miscellaneous</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>03.36.00 Miscellaneous Concrete Items</b>			
<i>Underslab insulation (perimeter only)</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Foundation wall insulation</i>	<i>BP#2</i>	<i>/BP#2</i>	
<b>Miscellaneous Concrete Items</b>	<b>135,589 sf</b>	<b>/sf</b>	
<b>32.13.00 Rigid Paving</b>			
<i>Concrete pavement</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Steps - premium</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Dumpster pad</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Concrete pavement with sawcut joints</i>	<i>BP#2</i>	<i>/BP#2</i>	
<b>Rigid Paving</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>03-30 CONCRETE</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>03-45 POLISHED CONCRETE</b>			
<b>03.36.00 Miscellaneous Concrete Items</b>			
<i>Polished concrete @ Auditorium - N/A</i>	<i>-</i>	<i>/-</i>	
<b>Miscellaneous Concrete Items</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>03-45 POLISHED CONCRETE</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>04-20 MASONRY (TS)</b>			
<b>01.43.00 Quality Assurance</b>			
Exterior wall mockup - Masonry, Allowance	1 allw	7,500.00 /allw	7,500
<b>Quality Assurance</b>	<b>136,600 sf</b>	<b>0.06 /sf</b>	<b>7,500</b>
<b>01.54.23 Temporary Scaffolding &amp; Platforms</b>			
Temporary bracing of CMU @ Gym and Auditorium	1 ls	100,000.00 /ls	100,000
Exterior staging	40,145 sf	2.50 /sf	100,363
<b>Temporary Scaffolding &amp; Platforms</b>	<b>136,600 sf</b>	<b>1.47 /sf</b>	<b>200,363</b>
<b>01.56.50 Winter Conditions</b>			
Masonry winter conditions/heat	12 wks	5,000.00 /wks	60,000



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Winter Conditions</b>	<b>136,600 sf</b>	<b>0.44 /sf</b>	<b>60,000</b>
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Masonry)	(1) ls	77,000.00 /ls	(77,000)
Trade support - lull, laborer for cleanup (Masonry)	1 ls	77,000.00 /ls	77,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>03.45.00 Precast Architectural Concrete</b>			
<b>Precast planters - N/A</b>	-	-	
<b>Precast Architectural Concrete</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>04.05.23 Masonry Accessories</b>			
Install loose lintels (< 8")	14 ea	150.00 /ea	2,100
<b>Masonry Accessories</b>	<b>136,600 sf</b>	<b>0.02 /sf</b>	<b>2,100</b>
<b>04.21.13 Brick Masonry - Veneer</b>			
4x4x12 iron spot brick veneer, scored	6,105 sf	36.00 /sf	219,780
4x8x8 iron spot brick veneer, scored	6,750 sf	36.00 /sf	243,000
<b>Brick veneer - interior - N/A</b>	-	-	
Brick veneer, precast cap @ entry wall per A102A	25 lf	285.00 /lf	7,125
Sill brick/lip brick - Premium	12,885 sf	2.00 /sf	25,770
<b>Brick Masonry - Veneer</b>	<b>136,600 sf</b>	<b>3.63 /sf</b>	<b>495,675</b>
<b>04.22.00 Concrete Unit Masonry</b>			
4x4x12 scored ground faced CMU veneer	3,680 sf	27.00 /sf	99,360
4x8x16 scored ground faced CMU veneer	23,615 sf	29.00 /sf	684,835
Sill brick/lip brick - Premium	27,295 sf	2.00 /sf	54,590
CMU - 12" exterior wall	15,795 sf	25.00 /sf	394,875
CMU - 12" interior wall	6,890 sf	25.00 /sf	172,250
CMU - acoustical block, premium	1,000 sf	7.50 /sf	7,500
White CMU - Premium	1 ls	75,000.00 /ls	75,000
White CMU - Premium - VM E02	(1) ls	75,000.00 /ls	(75,000)
White CMU - Premium - VM E02	41,220 sf	2.00 /sf	82,440
CMU - ground face block @ exterior, premium - VM E02	(27,295) sf	6.00 /sf	(163,770)
CMU - ground face block @ interior, premium	1 ls	35,000.00 /ls	35,000
CMU - ground face block @ interior, premium - VM E02	(1) ls	35,000.00 /ls	(35,000)
CMU - ground face block @ Auditorium, premium - VM E02	8,760 sf	6.00 /sf	52,560
<b>Concrete Unit Masonry</b>	<b>136,600 sf</b>	<b>10.14 /sf</b>	<b>1,384,640</b>
<b>07.21.00 Thermal Insulation</b>			
Mineral wool insulation at brick/CMU veneer	40,145 sf	3.50 /sf	140,508



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Thermal Insulation</b>	<b>136,600 sf</b>	<b>1.03 /sf</b>	<b>140,508</b>
<b>04-20 MASONRY (TS)</b>	<b>136,600 sf</b>	<b>16.77 /sf</b>	<b>2,290,785</b>
<b>05-12 STRUCTURAL STEEL</b>			
<b>01.43.00 Quality Assurance</b>			
<i>Exterior wall mockup - Steel, Allowance</i>	<i>BP#2</i>	<i>/BP#2</i>	
<b>Quality Assurance</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>05.05.23 Metal Fastenings</b>			
<i>Moment connections @ floor</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Moment connections @ roof</i>	<i>BP#2</i>	<i>/BP#2</i>	
<b>Metal Fastenings</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>05.12.00 Structural Steel Framing</b>			
<i>Steel @ floors</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Steel hangers - AESS</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Steel @ floors</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Steel @ screen wall - galvanized</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Steel @ Bandshell - AESS</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Steel @ Canopy - AESS</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Steel @ roof</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Steel dunnage - RTU &amp; chiller</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Relieving angles @ brick veneer</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Shoring @ Learning Commons</i>	<i>BP#2</i>	<i>/BP#2</i>	
<b>Structural Steel Framing</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>05.20.00 Metal Joists</b>			
<i>Open web joists, bridging</i>	<i>BP#2</i>	<i>/BP#2</i>	
<b>Metal Joists</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>05.30.00 Metal Decking</b>			
<i>Metal floor decking - galvanized (3" 18g)</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Metal roof decking - acoustical (3" 18/16g)</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Metal floor decking @ Breakout room LGMF floors</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Metal roof decking - galvanized (1-1/2" 20g)</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Metal roof decking - acoustical (1-1/2" 20g)</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Metal roof decking - galvanized (3" 18g)</i>	<i>BP#2</i>	<i>/BP#2</i>	
<b>Metal Decking</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>05.51.00 Metal Stairs</b>			
<i>Ornamental stairs 4 and 5 - excluding rails</i>	<i>BP#2</i>	<i>/BP#2</i>	



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Metal Stairs</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>05.52.00 Metal Railings</b>			
<i>Steel angles/stantions @ locker guardrail</i>	<i>BP#2</i>	<i>/BP#2</i>	
<b>Metal Railings</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>05-12 STRUCTURAL STEEL</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>05-50 MISCELLANEOUS METALS (TS)</b>			
<b>05.50.00 Metal Fabrications</b>			
Misc. metal fabrications	136,600 sf	1.50 /sf	204,900
Seismic clips - 4' OC, each side	270 ea	60.00 /ea	16,200
Support for HVAC enclosure	1 ls	40,000.00 /ls	40,000
1/4" steel plate @ tile	1 ls	15,000.00 /ls	15,000
Loose lintels - Furnish	95 lf	25.00 /lf	2,375
<b>Metal Fabrications</b>	<b>136,600 sf</b>	<b>2.04 /sf</b>	<b>278,475</b>
<b>05.51.00 Metal Stairs</b>			
Ornamental stairs 3 and 6 - excluding rails	2 ft	60,000.00 /ft	120,000
Egress stair	5 ft	30,000.00 /ft	150,000
Roof ladders	3 ea	1,500.00 /ea	4,500
Elevator pit ladders	1 ea	450.00 /ea	450
<b>Metal Stairs</b>	<b>136,600 sf</b>	<b>2.01 /sf</b>	<b>274,950</b>
<b>05.52.00 Metal Railings</b>			
Handrail @ steps/ramps	55 lf	295.00 /lf	16,225
Cane rails	120 lf	200.00 /lf	24,000
Guardrails @ Atrium	380 lf	500.00 /lf	190,000
Guardrails @ Atrium stairs	235 lf	500.00 /lf	117,500
Guardrails - 42" galvanized perforated @ exterior	105 lf	500.00 /lf	52,500
Guardrails - 42" galvanized perforated @ terrace	30 lf	500.00 /lf	15,000
Guardrails - exterior, colorgalv	240 lf	325.00 /lf	78,000
<b>Metal Railings</b>	<b>136,600 sf</b>	<b>3.61 /sf</b>	<b>493,225</b>
<b>05.70.00 Decorative Metal</b>			
Perforated architectural grille @ stage front	120 sf	200.00 /sf	24,000
Perforated architectural ceiling grille	210 sf	200.00 /sf	42,000
<b>Decorative Metal</b>	<b>136,600 sf</b>	<b>0.48 /sf</b>	<b>66,000</b>
<b>05-50 MISCELLANEOUS METALS (TS)</b>	<b>136,600 sf</b>	<b>8.15 /sf</b>	<b>1,112,650</b>



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>06-25 FINISH CARPENTRY</b>			
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Finish Carpentry)	(1) ls	72,000.00 /ls	(72,000)
Trade support - lull, laborer for cleanup (Finish Carpentry)	1 ls	72,000.00 /ls	72,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>06.20.23 Interior Finish Carpentry</b>			
<b>Wood base - N/A</b>	-	-	
Miscellaneous wood base/trim	136,600 sf	0.50 /sf	68,300
Trim @ Breakout D glass lights	320 sf	25.00 /sf	8,000
Head and sill MDF trim per 1,2/A620	1,700 lf	25.00 /lf	42,500
Window sills - P-lam	1,100 lf	25.00 /lf	27,500
Hardwood trim @ locker guardrail per A650	3,300 lf	15.00 /lf	49,500
<b>Interior Finish Carpentry</b>	<b>136,600 sf</b>	<b>1.43 /sf</b>	<b>195,800</b>
<b>06.25.00 Prefinished Paneling</b>			
P-lam panel	1,440 sf	45.00 /sf	64,800
P-lam panel on Z-clips @ Breakout	325 sf	45.00 /sf	14,625
Suspended P-lam clouds @ Auditorium	100 ea	2,000.00 /ea	200,000
P-lam top panels @ locker guardrail per A650	1,025 lf	50.00 /lf	51,250
P-lam side panels @ locker guardrail per A650	450 lf	50.00 /lf	22,500
P-lam panel backsplash	120 sf	45.00 /sf	5,400
Marker tray - bamboo	2,485 lf	30.00 /lf	74,550
Casework for lockers (bank of 5) - including base	1,025 lf	250.00 /lf	256,250
MDF bumper rail	3,715 lf	25.00 /lf	92,875
P-lam wall panels - sound reflecting @ Auditorium	2,925 sf	45.00 /sf	131,625
P-lam wall panels - vestibules	400 sf	45.00 /sf	18,000
P-lam projector enclosure @ Auditorium	1 ea	2,500.00 /ea	2,500
<b>Prefinished Paneling</b>	<b>136,600 sf</b>	<b>6.84 /sf</b>	<b>934,375</b>
<b>06.41.00 Architectural Wood Casework</b>			
P-lam base cabinet w/top	40 lf	450.00 /lf	18,000
P-lam workstation w/top	770 lf	250.00 /lf	192,500
Mobile storage	172 ea	1,000.00 /ea	172,000
Mobile storage - VM I05	(172) ea	1,000.00 /ea	(172,000)
P-lam valance for fin tube	570 lf	45.00 /lf	25,650
P-lam 3/4" lip at counter for fin tube	570 lf	4.00 /lf	2,280
P-lam wall cabinet	40 lf	325.00 /lf	13,000
P-lam full height cabinet	50 lf	700.00 /lf	35,000
Bathroom vanity w/top	210 lf	250.00 /lf	52,500
Reception cabinet	20 lf	1,000.00 /lf	20,000



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>06.41.00 Architectural Wood Casework</b>			
P-lam circulation desk	10 lf	750.00 /lf	7,500
P-lam work counter @ Admin	10 lf	1,500.00 /lf	15,000
<b>P-lam counter @ Servery - In Food Service</b>	-	/-	
P-lam end/filler panels @ Admin	10 lf	135.00 /lf	1,350
Mailboxes	18 lf	415.00 /lf	7,470
Storage shelving	380 lf	150.00 /lf	57,000
Storage shelving w/MDF	470 lf	200.00 /lf	94,000
P-lam bookcases	40 lf	500.00 /lf	20,000
Built-in benches	205 lf	600.00 /lf	123,000
Free-standing benches	35 lf	600.00 /lf	21,000
Display cases	5 ea	4,500.00 /ea	22,500
<b>Misc. casework - N/A</b>	-	/-	
Phenolic bench per A102A	1 ea	4,200.00 /ea	4,200
Wood louvered shades - Rulon panel grille	450 lf	150.00 /lf	67,500
<b>Architectural Wood Casework</b>	<b>136,600 sf</b>	<b>5.85 /sf</b>	<b>799,450</b>
<b>06-25 FINISH CARPENTRY</b>	<b>136,600 sf</b>	<b>14.13 /sf</b>	<b>1,929,625</b>
<b>07-10 WATERPROOFING &amp; JOINT SEALANTS (TS)</b>			
<b>01.43.00 Quality Assurance</b>			
Exterior wall mockup - Waterproofing, Allowance	1 allw	5,000.00 /allw	5,000
<b>Quality Assurance</b>	<b>136,600 sf</b>	<b>0.04 /sf</b>	<b>5,000</b>
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Waterproofing)	(1) ls	29,000.00 /ls	(29,000)
Trade support - lull, laborer for cleanup (Waterproofing)	1 ls	29,000.00 /ls	29,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>07.10.00 Dampproofing &amp; Waterproofing</b>			
Caulking @ storefront/curtainwall	7,425 lf	4.00 /lf	29,700
Caulking & sealants @ interior	136,600 sf	0.90 /sf	122,940
<b>Dampproofing at foundation wall</b>	<b>BP#2</b>	<b>/BP#2</b>	
Misc. caulking & sealants @ exterior	73,210 sf	0.75 /sf	54,908
<b>Foundation wall waterproofing - membrane w/ drainage board</b>	<b>BP#2</b>	<b>/BP#2</b>	
<b>Elevator pit waterproofing - cementitious</b>	<b>BP#2</b>	<b>/BP#2</b>	
<b>Dampproofing &amp; Waterproofing</b>	<b>136,600 sf</b>	<b>1.52 /sf</b>	<b>207,548</b>
<b>07.26.00 Vapor Retarders</b>			
Air and vapor barrier @ exterior walls	56,650 sf	7.50 /sf	424,875



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>07.26.00 Vapor Retarders</b>			
Air and vapor barrier @ soffits	1,245 sf	7.50 /sf	9,338
Air and vapor barrier @ phenolic fins per A102A, A315	380 sf	7.50 /sf	2,850
Window transitions	7,425 lf	10.00 /lf	74,250
<b>Vapor Retarders</b>	<b>136,600 sf</b>	<b>3.74 /sf</b>	<b>511,313</b>
<b>07-10 WATERPROOFING &amp; JOINT SEALANTS (TS)</b>	<b>136,600 sf</b>	<b>5.30 /sf</b>	<b>723,860</b>
<b>07-42 METAL/COMPOSITE PANELS &amp; SIDING</b>			
<b>01.43.00 Quality Assurance</b>			
Exterior wall mockup - Siding, Allowance	1 allw	10,000.00 /allw	10,000
<b>Quality Assurance</b>	<b>136,600 sf</b>	<b>0.07 /sf</b>	<b>10,000</b>
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Siding)	(1) ls	48,000.00 /ls	(48,000)
Trade support - lull, laborer for cleanup (Siding)	1 ls	48,000.00 /ls	48,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>07.42.00 Wall Panels</b>			
Corrugated, perforated metal siding @ screen walls	1,105 sf	45.00 /sf	49,725
Exposed fastener metal panel	6,065 sf	48.00 /sf	291,120
Composite metal panel siding	3,120 sf	75.00 /sf	234,000
Phenolic panel siding	7,705 sf	80.00 /sf	616,400
<b>Wall Panels</b>	<b>136,600 sf</b>	<b>8.72 /sf</b>	<b>1,191,245</b>
<b>07-42 METAL/COMPOSITE PANELS &amp; SIDING</b>	<b>136,600 sf</b>	<b>8.79 /sf</b>	<b>1,201,245</b>
<b>07-50 MEMBRANE ROOFING (TS)</b>			
<b>01.43.00 Quality Assurance</b>			
Exterior wall mockup - Roofing, Allowance	1 allw	2,500.00 /allw	2,500
<b>Quality Assurance</b>	<b>136,600 sf</b>	<b>0.02 /sf</b>	<b>2,500</b>
<b>07.50.00 Membrane Roofing</b>			
PVC membrane roof w/insulation, underlayment, cover board, vapor barrier	63,155 sf	19.00 /sf	1,199,945
Additional layer of protection board	7,565 sf	3.00 /sf	22,695
PVC membrane @ walls	2,740 sf	20.25 /sf	55,485
Reinforced walkway pads	715 sf	7.50 /sf	5,363
Pavers - terrace	295 sf	35.00 /sf	10,325



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>07.50.00 Membrane Roofing</b>			
Pavers - main entrance	780 sf	35.00 /sf	27,300
<b>Membrane Roofing</b>	<b>136,600 sf</b>	<b>9.67 /sf</b>	<b>1,321,113</b>
<b>07.72.00 Roof Accessories</b>			
Roof accessories	63,155 sf	0.35 /sf	22,104
Roof vents & hatches	1 ls	25,000.00 /ls	25,000
Metal roof fascia	2,695 lf	35.00 /lf	94,325
Additional flashing, scuppers	63,155 sf	0.75 /sf	47,366
<b>Roof Accessories</b>	<b>136,600 sf</b>	<b>1.38 /sf</b>	<b>188,796</b>
<b>07-50 MEMBRANE ROOFING (TS)</b>	<b>136,600 sf</b>	<b>11.07 /sf</b>	<b>1,512,408</b>
<b>07-81 FIREPROOFING</b>			
<b>07.81.00 Applied Fireproofing</b>			
Sprayed fireproofing - steel beams and columns @ floor structure	64,740 sf	3.00 /sf	194,220
Sprayed fireproofing - steel beams and columns @ roof structure below 20'	33,575 sf	3.00 /sf	100,725
Patch Sprayed fireproofing - floor structure	5 days	3,500.00 /days	17,500
Patch Sprayed fireproofing - roof structure	5 days	3,500.00 /days	17,500
Intumescent fireproofing @ Learning Commons	1 ls	72,000.00 /ls	72,000
<b>Applied Fireproofing</b>	<b>136,600 sf</b>	<b>2.94 /sf</b>	<b>401,945</b>
<b>07-81 FIREPROOFING</b>	<b>136,600 sf</b>	<b>2.94 /sf</b>	<b>401,945</b>
<b>08-10 DOORS, FRAMES &amp; HARDWARE</b>			
<b>08.10.05 Doors &amp; Frames</b>			
Install exterior door, HW	14 ea	300.00 /ea	4,200
Install interior door, HW	300 ea	300.00 /ea	90,000
<b>Doors &amp; Frames</b>	<b>136,600 sf</b>	<b>0.69 /sf</b>	<b>94,200</b>
<b>08.11.13 Hollow Metal Doors &amp; Frames</b>			
HM doors - interior - flush	45 lvs	310.00 /lvs	13,950
HM doors - exterior flush	23 lvs	625.00 /lvs	14,375
HM frames - exterior single	5 ea	255.00 /ea	1,275
HM frames - exterior double	9 ea	440.00 /ea	3,960
HM frames - interior single	258 ea	310.00 /ea	79,980
HM frames - interior single, tandem	13 ea	360.00 /ea	4,680
HM frames - interior double	29 ea	385.00 /ea	11,165





Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Hollow Metal Doors &amp; Frames</b>	<b>136,600 sf</b>	<b>0.95 /sf</b>	<b>129,385</b>
<b>08.14.00 Wood Doors</b>			
Wood door - interior flush	297 lvs	390.00 /lvs	115,830
Fire rated wood doors - premium	44 lvs	390.00 /lvs	17,160
Acoustical doors (STC 45) - premium	1 ls	15,000.00 /ls	15,000
<b>Wood Doors</b>	<b>136,600 sf</b>	<b>1.08 /sf</b>	<b>147,990</b>
<b>08.71.00 Door Hardware</b>			
Hardware sets - exterior door/panic	14 set	1,920.01 /set	26,880
Hardware sets - auto operators	1 set	4,500.00 /set	4,500
Hardware sets - standard interior	287 set	1,015.00 /set	291,305
Hardware sets - interior, tandem	13 set	1,330.00 /set	17,290
<b>Door Hardware</b>	<b>136,600 sf</b>	<b>2.49 /sf</b>	<b>339,975</b>
<b>08-10 DOORS, FRAMES &amp; HARDWARE</b>	<b>136,600 sf</b>	<b>5.21 /sf</b>	<b>711,550</b>
<b>08-34 OVERHEAD DOORS &amp; GRILLES</b>			
<b>08.33.00 Coiling Doors &amp; Grilles</b>			
Coiling security screen - 4' high, manual	85 sf	70.00 /sf	5,950
Coiling security screen - 8' high, manual	690 sf	70.00 /sf	48,300
Custom security gate @ Learning Commons	2 lvs	6,000.00 /lvs	12,000
<b>Coiling Doors &amp; Grilles</b>	<b>136,600 sf</b>	<b>0.49 /sf</b>	<b>66,250</b>
<b>08.36.00 Panel Doors</b>			
Overhead coiling door	1 ea	7,500.00 /ea	7,500
<b>Panel Doors</b>	<b>136,600 sf</b>	<b>0.06 /sf</b>	<b>7,500</b>
<b>11.13.00 Loading Dock Equipment</b>			
Loading dock equipment	1 ls	1,000.00 /ls	1,000
<b>Loading Dock Equipment</b>	<b>136,600 sf</b>	<b>0.01 /sf</b>	<b>1,000</b>
<b>08-34 OVERHEAD DOORS &amp; GRILLES</b>	<b>136,600 sf</b>	<b>0.55 /sf</b>	<b>74,750</b>
<b>08-41 ALUMINUM STOREFRONT &amp; WINDOWS (TS)</b>			
<b>01.43.00 Quality Assurance</b>			
Exterior wall mockup - Windows, Allowance	1 allw	20,000.00 /allw	20,000
<b>Quality Assurance</b>	<b>136,600 sf</b>	<b>0.15 /sf</b>	<b>20,000</b>



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Windows)	(1) ls	73,000.00 /ls	(73,000)
Trade support - lull, laborer for cleanup (Windows)	1 ls	73,000.00 /ls	73,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>08.41.00 Entrances &amp; Storefronts</b>			
Aluminum storefront/windows	11,555 sf	100.00 /sf	1,155,500
Aluminum storefront - interior, School Guard	340 sf	140.00 /sf	47,600
Aluminum windows - interior, School Guard	2 ea	12,000.00 /ea	24,000
Aluminum storefront - School Guard	545 sf	140.00 /sf	76,300
Extruded aluminum perimeter angles	7,425 lf	30.00 /lf	222,750
Aluminum entrance doors, HW - exterior	4 lvs	6,000.00 /lvs	24,000
Aluminum entrance doors, HW - interior	1 lvs	6,000.00 /lvs	6,000
Aluminum entrance doors, HW - interior, School Guard	8 lvs	7,000.00 /lvs	56,000
Aluminum entrance doors, HW - exterior, School Guard	11 lvs	7,000.00 /lvs	77,000
<b>Entrances &amp; Storefronts</b>	<b>136,600 sf</b>	<b>12.37 /sf</b>	<b>1,689,150</b>
<b>08.63.00 Metal-Framed Skylights</b>			
Metal-framed skylights (8:12)	4,130 sf	150.00 /sf	619,500
Metal-framed skylights gable ends	490 sf	150.00 /sf	73,500
<b>Metal-Framed Skylights</b>	<b>136,600 sf</b>	<b>5.07 /sf</b>	<b>693,000</b>
<b>08.71.00 Door Hardware</b>			
Automatic operators	3 pair	4,400.00 /pair	13,200
<b>Door Hardware</b>	<b>136,600 sf</b>	<b>0.10 /sf</b>	<b>13,200</b>
<b>08-41 ALUMINUM STOREFRONT &amp; WINDOWS (TS)</b>	<b>136,600 sf</b>	<b>17.68 /sf</b>	<b>2,415,350</b>
<b>08-45 TRANSLUCENT PANEL SYSTEMS</b>			
<b>08.45.00 Translucent Wall &amp; Roof Assemblies</b>			
Polycarbonate glazing @ canopy	440 sf	150.00 /sf	66,000
Polycarbonate glazing @ canopy - VM E01	(440) sf	150.00 /sf	(66,000)
<b>Translucent Wall &amp; Roof Assemblies</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>08-45 TRANSLUCENT PANEL SYSTEMS</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>08-80 GLASS &amp; GLAZING (TS)</b>			
<b>08.80.00 Glazing</b>			



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>08.80.00 Glazing</b>			
Misc. interior glass & glazing	136,600 sf	0.25 /sf	34,150
Glazed partition	4,700 sf	60.00 /sf	282,000
Glazed partition - double acoustic	625 sf	110.00 /sf	68,750
Glazed partition @ sidelights	1,165 sf	75.00 /sf	87,375
Glass walls @ Breakout	2,323 sf	100.00 /sf	232,300
<b>Glass roof @ Breakout - N/A</b>	-	/-	
Glass roof @ canopy - VM E01	82 sf	150.00 /sf	12,300
Door glazing - full	159 ea	400.00 /ea	63,600
Door glazing - narrow	2 ea	100.00 /ea	200
Mirrors - unframed restroom	1,145 sf	35.00 /sf	40,075
Glass @ Bandshell (vertical) - 9/16" tempered, laminated	235 sf	150.00 /sf	35,250
Glass @ Bandshell (roof) - 9/16" tempered, laminated	300 sf	150.00 /sf	45,000
<b>Glazing</b>	<b>136,600 sf</b>	<b>6.60 /sf</b>	<b>901,000</b>
<b>08.88.00 Glazing Surface Films</b>			
Graduated glass film	3,675 sf	5.00 /sf	18,375
3M Safety and Security Window Film @ glass walls	4,090 sf	15.00 /sf	61,350
3M Safety and Security Window Film @ doors	67 lvs	450.00 /lvs	30,150
<b>Glazing Surface Films</b>	<b>136,600 sf</b>	<b>0.80 /sf</b>	<b>109,875</b>
<b>08-80 GLASS &amp; GLAZING (TS)</b>	<b>136,600 sf</b>	<b>7.40 /sf</b>	<b>1,010,875</b>
<b>08-90 LOUVERS</b>			
<b>08.90.00 Louvers &amp; Vents</b>			
Metal louver	625 sf	85.00 /sf	53,125
<b>Louvers &amp; Vents</b>	<b>136,600 sf</b>	<b>0.39 /sf</b>	<b>53,125</b>
<b>08-90 LOUVERS</b>	<b>136,600 sf</b>	<b>0.39 /sf</b>	<b>53,125</b>
<b>09-21 DRYWALL</b>			
<b>01.43.00 Quality Assurance</b>			
Exterior wall mockup - Drywall, Allowance	1 allw	10,000.00 /allw	10,000
<b>Quality Assurance</b>	<b>136,600 sf</b>	<b>0.07 /sf</b>	<b>10,000</b>
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Drywall)	(1) ls	188,000.00 /ls	(188,000)
Trade support - lull, laborer for cleanup (Drywall)	1 ls	188,000.00 /ls	188,000



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>05.40.00 Cold-Formed Metal Framing</b>			
Light gage metal framing @ Breakout floors	1,440 sf	60.00 /sf	86,400
Light gage metal framing @ Breakout walls	16,820 sf	25.00 /sf	420,500
<b>Cold-Formed Metal Framing</b>	<b>136,600 sf</b>	<b>3.71 /sf</b>	<b>506,900</b>
<b>06.10.00 Rough Carpentry</b>			
Roof blocking	5,390 lf	32.00 /lf	172,480
Window blocking	7,425 lf	12.75 /lf	94,669
Door blocking - exterior	265 lf	13.85 /lf	3,671
Door blocking - interior	4,965 lf	13.85 /lf	68,772
In-wall blocking	12,160 lf	12.75 /lf	155,040
Miscellaneous rough carpentry - Allowance	136,600 sf	0.50 /sf	68,300
<b>Rough Carpentry</b>	<b>136,600 sf</b>	<b>4.12 /sf</b>	<b>562,932</b>
<b>07.84.00 Firestopping</b>			
Firestopping @ rated walls	5,630 lf	16.20 /lf	91,206
Miscellaneous firestopping	136,600 sf	0.10 /sf	13,660
<b>Firestopping</b>	<b>136,600 sf</b>	<b>0.77 /sf</b>	<b>104,866</b>
<b>08.31.00 Access Doors &amp; Panels</b>			
Access panels	1 ls	15,000.00 /ls	15,000
<b>Access Doors &amp; Panels</b>	<b>136,600 sf</b>	<b>0.11 /sf</b>	<b>15,000</b>
<b>09.21.13 Gypsum Board Assemblies - Walls</b>			
Level 5 finish - Allowance	25,000 sf	2.55 /sf	63,750
Interior wall framing - 2-1/2"	3,370 sf	5.75 /sf	19,378
Interior wall framing - 3-5/8"/4"	96,355 sf	5.75 /sf	554,041
Interior wall framing - 6"	7,050 sf	7.65 /sf	53,933
Interior wall framing - 8"	21,965 sf	10.15 /sf	222,945
Interior wall framing - 10"	555 sf	12.10 /sf	6,716
GWB - 5/8", level 4	229,230 sf	4.15 /sf	951,305
GWB - 5/8", additional layer	96,320 sf	3.50 /sf	336,627
GWB - high impact	1 ls	50,000.00 /ls	50,000
Shaft liner - 1"	2,420 sf	4.15 /sf	10,043
Sound batt insulation	137,275 sf	1.60 /sf	219,640
Half height walls @ Auditorium	400 sf	22.90 /sf	9,160
LGMF framing @ locker guardrail	4,095 sf	5.10 /sf	20,885
GWB - 5/8", level 5 @ locker guardrail	4,095 sf	6.70 /sf	27,437
Curved walls - premium	5,205 sf	6.35 /sf	33,074



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>09.21.13 Gypsum Board Assemblies - Walls</b>			
Exterior walls - 10" studs, 1/2" sheathing, 5/8" GWB, insulation	44,220 sf	23.50 /sf	1,039,170
Framing @ phenolic fins per A102A, A315	380 sf	7.65 /sf	2,907
Install HM door frames - exterior single	5 ea	73.00 /ea	365
Install HM door frames - interior single	271 ea	73.00 /ea	19,783
Install HM door frames - exterior double	9 ea	117.00 /ea	1,053
Install HM door frames - interior double	29 ea	117.00 /ea	3,393
<b>Gypsum Board Assemblies - Walls</b>	<b>136,600 sf</b>	<b>26.69 /sf</b>	<b>3,645,602</b>
<b>09.21.16 Gypsum Board Assemblies - Ceilings &amp; Soffits</b>			
Gypsum board ceilings	21,010 sf	15.25 /sf	320,411
Gypsum board ceilings - 1 hr	655 sf	19.10 /sf	12,511
Gypsum board ceilings - 2 hr	80 sf	22.90 /sf	1,832
Gypsum board ceilings - resilient	5,350 sf	31.75 /sf	169,863
Stucco soffit	1,245 sf	11.35 /sf	14,131
Exterior soffit framing, sheathing, insulation	1,245 sf	23.90 /sf	29,756
Gypsum board soffits	28,335 sf	25.45 /sf	721,126
Gypsum board soffits - VM I11	(2,250) sf	25.45 /sf	(57,263)
Gypsum board soffits @ Learning Commons	4,920 sf	25.45 /sf	125,214
Gypsum board soffits @ Skylights	1,915 sf	25.45 /sf	48,737
<b>Gypsum Board Assemblies - Ceilings &amp; Soffits</b>	<b>136,600 sf</b>	<b>10.15 /sf</b>	<b>1,386,316</b>
<b>09.21.25 Gypsum Board Assemblies - Patching/Infills</b>			
Patch GWB	136,600 sf	0.35 /sf	47,810
<b>Gypsum Board Assemblies - Patching/Infills</b>	<b>136,600 sf</b>	<b>0.35 /sf</b>	<b>47,810</b>
<b>09.77.33 Fiberglass Reinforced Panels</b>			
Fiberglass reinforced panels (FRP) - wall panels	2,240 sf	8.00 /sf	17,920
<b>Fiberglass Reinforced Panels</b>	<b>136,600 sf</b>	<b>0.13 /sf</b>	<b>17,920</b>
<b>09-21 DRYWALL</b>	<b>136,600 sf</b>	<b>46.10 /sf</b>	<b>6,297,346</b>
<b>09-30 TILE (TS)</b>			
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Tile)	(1) ls	7,000.00 /ls	(7,000)
Trade support - lull, laborer for cleanup (Tile)	1 ls	7,000.00 /ls	7,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>09.30.00 Tiling</b>			
Ceramic wall tile	2,295 sf	18.00 /sf	41,310



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>09.30.00 Tiling</b>			
Porcelain floor tile	5,475 sf	25.00 /sf	136,875
Quarry floor tile	1,770 sf	20.00 /sf	35,400
Quarry tile base	280 lf	20.00 /lf	5,600
<b>Tiling</b>	<b>136,600 sf</b>	<b>1.61 /sf</b>	<b>219,185</b>
<b>09-30 TILE (TS)</b>	<b>136,600 sf</b>	<b>1.61 /sf</b>	<b>219,185</b>
<b>09-51 ACOUSTICAL CEILINGS (TS)</b>			
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Ceilings)	(1) ls	49,000.00 /ls	(49,000)
Trade support - lull, laborer for cleanup (Ceilings)	1 ls	49,000.00 /ls	49,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>09.51.00 Acoustical Ceilings</b>			
A1 - Armstrong Ultima #1911, random running bond pattern	21,400 sf	9.00 /sf	192,600
A1 - Armstrong Ultima #1911 @ Learning Commons corridors	9,980 sf	9.00 /sf	89,820
A2 - Armstrong Calla #2824	20,985 sf	8.00 /sf	167,880
A2 - Armstrong Calla #2824 - VM I03	1,393 sf	8.00 /sf	11,144
A3 - USG Geometrix 3 Dimensional	3,815 sf	35.00 /sf	133,525
A3 - USG Geometrix 3 Dimensional - VM I03	(1,393) sf	35.00 /sf	(48,755)
A4 - Armstrong Healthzone Ultima	1,760 sf	7.00 /sf	12,320
<b>Acoustical Ceilings</b>	<b>136,600 sf</b>	<b>4.09 /sf</b>	<b>558,534</b>
<b>09.80.00 Acoustical Treatment</b>			
Fabric wrapped acoustical panels	12,275 sf	20.00 /sf	245,500
Tectum wall panels	5,535 sf	18.00 /sf	99,630
<b>Mural panorama wall covering - By Others</b>	-	/-	
<b>Acoustical Treatment</b>	<b>136,600 sf</b>	<b>2.53 /sf</b>	<b>345,130</b>
<b>09-51 ACOUSTICAL CEILINGS (TS)</b>	<b>136,600 sf</b>	<b>6.62 /sf</b>	<b>903,664</b>
<b>09-64 WOOD FLOORING</b>			
<b>09.64.00 Wood Flooring</b>			
Hardwood stage assembly	1,610 sf	25.00 /sf	40,250
Wood athletic flooring	8,570 sf	20.00 /sf	171,400
<b>Wood Flooring</b>	<b>136,600 sf</b>	<b>1.55 /sf</b>	<b>211,650</b>
<b>09-64 WOOD FLOORING</b>	<b>136,600 sf</b>	<b>1.55 /sf</b>	<b>211,650</b>



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>09-65 RESILIENT FLOORING (TS)</b>			
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Resilient)	(1) ls	48,000.00 /ls	(48,000)
Trade support - lull, laborer for cleanup (Resilient)	1 ls	48,000.00 /ls	48,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>09.61.00 Flooring Treatment</b>			
Underlayment at 2nd and 3rd floor linoleum - Forbo NR99, exclude corridors	36,505 sf	4.00 /sf	146,020
<i>Moisture mitigation - Excluded</i>	-	-	
<b>Flooring Treatment</b>	<b>136,600 sf</b>	<b>1.07 /sf</b>	<b>146,020</b>
<b>09.65.00 Resilient Flooring</b>			
Linoleum tile	90,135 sf	6.00 /sf	540,810
Linoleum tile base w/trim	19,260 lf	9.00 /lf	173,340
Linoleum tile base w/trim - VM I10	(15,545) lf	9.00 /lf	(139,905)
Linoleum tile base - VM I10	15,545 lf	7.00 /lf	108,815
Rubber base	2,175 lf	3.50 /lf	7,613
Vented base @ Gym	370 lf	8.00 /lf	2,960
Rubber flooring @ ornamental stairs	770 sf	8.00 /sf	6,160
<b>Resilient Flooring</b>	<b>136,600 sf</b>	<b>5.12 /sf</b>	<b>699,793</b>
<b>09-65 RESILIENT FLOORING (TS)</b>	<b>136,600 sf</b>	<b>6.19 /sf</b>	<b>845,813</b>
<b>09-67 RESINOUS FLOORING</b>			
<b>09.67.00 Fluid-Applied Flooring</b>			
Epoxy flooring/base	5,780 sf	14.00 /sf	80,920
<b>Fluid-Applied Flooring</b>	<b>136,600 sf</b>	<b>0.59 /sf</b>	<b>80,920</b>
<b>09-67 RESINOUS FLOORING</b>	<b>136,600 sf</b>	<b>0.59 /sf</b>	<b>80,920</b>
<b>09-68 CARPET</b>			
<b>09.68.00 Carpeting</b>			
Carpet @ Auditorium	135 sy	45.00 /sy	6,075
<b>Carpeting</b>	<b>136,600 sf</b>	<b>0.04 /sf</b>	<b>6,075</b>
<b>12.48.13 Entrance Floor Mats &amp; Frames</b>			
Entry mats - recessed	435 sf	40.00 /sf	17,400



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Entrance Floor Mats &amp; Frames</b>	<b>136,600 sf</b>	<b>0.13 /sf</b>	<b>17,400</b>
<b>09-68 CARPET</b>	<b>136,600 sf</b>	<b>0.17 /sf</b>	<b>23,475</b>
<b>09-90 PAINTING (TS)</b>			
<b>09.90.00 Painting &amp; Coating</b>			
Paint GWB partitions	227,710 sf	0.80 /sf	182,168
<i>Paint CMU - N/A</i>	-	/-	
Epoxy wall paint	15,550 sf	2.30 /sf	35,765
Prep/paint Bandshell	1 ls	10,000.00 /ls	10,000
Prep/paint main and West Admin egress canopies	1 ls	10,000.00 /ls	10,000
Paint GWB ceilings	21,735 sf	1.00 /sf	21,735
Paint GWB soffits	35,170 sf	1.00 /sf	35,170
Paint HM doors - exterior	23 lvs	90.00 /lvs	2,070
Paint HM doors - interior	45 lvs	90.00 /lvs	4,050
Paint HM frames - exterior, single	5 ea	50.00 /ea	250
Paint HM frames - interior, single	271 ea	50.00 /ea	13,550
Paint HM frames - exterior, double	9 ea	60.00 /ea	540
Paint HM frames - interior, double	29 ea	60.00 /ea	1,740
Paint egress stairs	5 flt	2,000.00 /flt	10,000
Paint exposed ceilings	24,085 sf	1.50 /sf	36,128
Paint exposed ceilings @ Gym and Auditorium	14,385 sf	2.50 /sf	35,963
Seal concrete floor	7,245 sf	2.00 /sf	14,490
Seal concrete floor @ Auditorium	3,650 sf	2.00 /sf	7,300
Misc. exterior painting	73,210 sf	0.50 /sf	36,605
Touchup	136,600 sf	0.50 /sf	68,300
<b>Painting &amp; Coating</b>	<b>136,600 sf</b>	<b>3.85 /sf</b>	<b>525,823</b>
<b>09-90 PAINTING (TS)</b>	<b>136,600 sf</b>	<b>3.85 /sf</b>	<b>525,823</b>
<b>10-14 SIGNAGE</b>			
<b>10.14.00 Signage</b>			
Interior signage	136,600 sf	0.35 /sf	47,810
Exterior signage	1 ls	25,000.00 /ls	25,000
<b>Signage</b>	<b>136,600 sf</b>	<b>0.53 /sf</b>	<b>72,810</b>
<b>10-14 SIGNAGE</b>	<b>136,600 sf</b>	<b>0.53 /sf</b>	<b>72,810</b>
<b>10-24 OPERABLE PARTITIONS</b>			
<b>10.22.00 Partitions</b>			





Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>10.22.00 Partitions</b>			
Operable partitions w/writeable surface on one side	325 sf	77.00 /sf	25,025
Operable partitions w/writeable surface on both sides	2,740 sf	98.00 /sf	268,520
<b>Partitions</b>	<b>136,600 sf</b>	<b>2.15 /sf</b>	<b>293,545</b>
<b>10-24 OPERABLE PARTITIONS</b>	<b>136,600 sf</b>	<b>2.15 /sf</b>	<b>293,545</b>
<b>10-51 LOCKERS</b>			
<b>10.51.00 Lockers</b>			
Student lockers - phenolic	660 ea	580.00 /ea	382,800
Athletic lockers	80 ea	350.00 /ea	28,000
Staff lockers	12 ea	400.00 /ea	4,800
Locker benches	12 lf	55.00 /lf	660
<b>Lockers</b>	<b>136,600 sf</b>	<b>3.05 /sf</b>	<b>416,260</b>
<b>10-51 LOCKERS</b>	<b>136,600 sf</b>	<b>3.05 /sf</b>	<b>416,260</b>
<b>10-95 MISCELLANEOUS SPECIALTIES</b>			
<b>10.11.00 Visual Display Units</b>			
Magnetic writeable wall covering	9,045 sf	22.00 /sf	198,990
<b>Visual Display Units</b>	<b>136,600 sf</b>	<b>1.46 /sf</b>	<b>198,990</b>
<b>10.21.00 Compartments &amp; Cubicles</b>			
Toilet partition	23 ea	1,020.00 /ea	23,460
Toilet partition - handicap	16 ea	1,650.00 /ea	26,400
Urinal screens - wall-hung	15 ea	433.00 /ea	6,495
Cubicle curtains	45 lf	40.00 /lf	1,800
Cubicle curtain track	45 lf	11.50 /lf	518
<b>Compartments &amp; Cubicles</b>	<b>136,600 sf</b>	<b>0.43 /sf</b>	<b>58,673</b>
<b>10.26.00 Wall &amp; Door Protection</b>			
Corner guards	1 ls	20,000.00 /ls	20,000
<b>Wall &amp; Door Protection</b>	<b>136,600 sf</b>	<b>0.15 /sf</b>	<b>20,000</b>
<b>10.28.00 Toilet, Bath, &amp; Laundry Accessories</b>			
Toilet paper dispenser	54 ea	105.17 /ea	5,679
Grab bar	62 ea	141.38 /ea	8,765
Soap dispenser - surface mounted	59 ea	87.64 /ea	5,171
Paper towel dispenser - recessed	32 ea	136.79 /ea	4,377



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>10.28.00 Toilet, Bath, &amp; Laundry Accessories</b>			
Framed mirrors	15 ea	171.00 /ea	2,565
Sanitary napkin disposal	46 ea	274.00 /ea	12,604
Shower curtains, hooks & rod	3 ea	125.00 /ea	375
Shower seat	2 ea	668.00 /ea	1,336
Mop rack	3 ea	230.67 /ea	692
<b>Toilet, Bath, &amp; Laundry Accessories</b>	<b>136,600 sf</b>	<b>0.30 /sf</b>	<b>41,564</b>
<b>10.40.00 Safety Specialties</b>			
Fire extinguisher cabinet - fully recessed	27 ea	350.00 /ea	9,450
<b>Safety Specialties</b>	<b>136,600 sf</b>	<b>0.07 /sf</b>	<b>9,450</b>
<b>10.80.00 Other Specialties</b>			
Misc. specialties - Allowance	136,600 sf	0.25 /sf	34,150
<b>Other Specialties</b>	<b>136,600 sf</b>	<b>0.25 /sf</b>	<b>34,150</b>
<b>11.52.00 Audio-Visual Equipment</b>			
Projection screen @ Gym, Cafeteria	2 ea	10,000.00 /ea	20,000
Projection screen	1 ea	5,000.00 /ea	5,000
<b>Audio-Visual Equipment</b>	<b>136,600 sf</b>	<b>0.18 /sf</b>	<b>25,000</b>
<b>10-95 MISCELLANEOUS SPECIALTIES</b>	<b>136,600 sf</b>	<b>2.84 /sf</b>	<b>387,827</b>
<b>11-31 RESIDENTIAL APPLIANCES</b>			
<b>11.31.00 Residential Appliances</b>			
Refrigerator	7 ea	1,200.00 /ea	8,400
<i>Ice maker - None shown</i>	-	/-	
<i>Undercounter refrigerator - None shown</i>	-	/-	
Microwave oven	1 ea	450.00 /ea	450
Range hood	1 ea	650.00 /ea	650
Range	1 ea	900.00 /ea	900
Dishwasher	4 ea	925.00 /ea	3,700
Washer/dryer - stackable	2 ea	1,500.00 /ea	3,000
<b>Residential Appliances</b>	<b>136,600 sf</b>	<b>0.13 /sf</b>	<b>17,100</b>
<b>11-31 RESIDENTIAL APPLIANCES</b>	<b>136,600 sf</b>	<b>0.13 /sf</b>	<b>17,100</b>
<b>11-40 FOOD SERVICE EQUIPMENT</b>			
<b>11.40.00 Foodservice Equipment</b>			



**Fuller Middle School**  
**90% CD Reconciled Estimate**

10/7/2019

**CONSIGLI**  
*Est. 1905*

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>11.40.00 Foodservice Equipment</b>			
Food service equipment - Allowance	1 ls	415,270.00 /ls	415,270
<b>Foodservice Equipment</b>	<b>136,600 sf</b>	<b>3.04 /sf</b>	<b>415,270</b>
<b>11-40 FOOD SERVICE EQUIPMENT</b>	<b>136,600 sf</b>	<b>3.04 /sf</b>	<b>415,270</b>
<b>11-51 AUDIO-VISUAL EQUIPMENT</b>			
<b>11.52.00 Audio-Visual Equipment</b>			
Sound systems @ Auditorium - Allowance	1 allw	200,000.00 /allw	200,000
Sound systems @ Gym - Allowance	1 allw	120,000.00 /allw	120,000
Sound systems @ Cafeteria - Allowance	1 allw	50,000.00 /allw	50,000
Sound systems @ Band/Chorus - Allowance	2 allw	30,000.00 /allw	60,000
Sound systems @ Drama - Allowance	1 allw	20,000.00 /allw	20,000
<b>Audio-Visual Equipment</b>	<b>136,600 sf</b>	<b>3.29 /sf</b>	<b>450,000</b>
<b>11-51 AUDIO-VISUAL EQUIPMENT</b>	<b>136,600 sf</b>	<b>3.29 /sf</b>	<b>450,000</b>
<b>11-61 THEATER &amp; STAGE EQUIPMENT</b>			
<b>11.61.00 Theater &amp; Stage Equipment</b>			
<i>Orchestra enclosures - FFE</i>	-	-	
Theatrical rigging - Allowance	1 ls	158,300.00 /ls	158,300
Theatrical draperies - Allowance	1 ls	33,854.00 /ls	33,854
Theatrical lighting instruments & accessories - Allowance	1 ls	129,018.00 /ls	129,018
Theatrical lighting controls - Allowance	1 ls	95,749.00 /ls	95,749
<b>Theater &amp; Stage Equipment</b>	<b>136,600 sf</b>	<b>3.05 /sf</b>	<b>416,921</b>
<b>11-61 THEATER &amp; STAGE EQUIPMENT</b>	<b>136,600 sf</b>	<b>3.05 /sf</b>	<b>416,921</b>
<b>11-65 ATHLETIC/RECREATIONAL EQUIPMENT</b>			
<b>11.65.00 Athletic &amp; Recreational Equipment</b>			
Basketball backstop - ceiling-hung	6 ea	6,500.00 /ea	39,000
Gym divider curtain - electric roll up	1,530 sf	20.00 /sf	30,600
Athletic wall padding	835 sf	12.50 /sf	10,438
Volleyball system	1 ls	5,000.00 /ls	5,000
Scoreboards - basketball	1 ea	7,500.00 /ea	7,500
<b>Athletic &amp; Recreational Equipment</b>	<b>136,600 sf</b>	<b>0.68 /sf</b>	<b>92,538</b>
<b>11-65 ATHLETIC/RECREATIONAL EQUIPMENT</b>	<b>136,600 sf</b>	<b>0.68 /sf</b>	<b>92,538</b>



**Fuller Middle School**  
**90% CD Reconciled Estimate**

10/7/2019

**CONSIGLI**  
*Est. 1905*

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>11-95 VOCATIONAL SHOP EQUIPMENT</b>			
<b>11.51.00 Vocational Shop Equipment</b>			
Vocational shop equipment	1 ls	25,000.00 /ls	25,000
- <i>Welding booths - In Above</i>	-	/-	
- <i>Portable welding fumes extractor - In Above</i>	-	/-	
- <i>Paint spray hoods - In Above</i>	-	/-	
- <i>Portable wood working equipment dust collector - In HVAC</i>	-	/-	
Kiln	1 ls	12,000.00 /ls	12,000
<b>Vocational Shop Equipment</b>	<b>136,600 sf</b>	<b>0.27 /sf</b>	<b>37,000</b>
<b>11-95 VOCATIONAL SHOP EQUIPMENT</b>	<b>136,600 sf</b>	<b>0.27 /sf</b>	<b>37,000</b>
<b>12-20 WINDOW TREATMENTS</b>			
<b>12.20.00 Window Treatments</b>			
Roller shades	10,235 sf	8.00 /sf	81,880
Roller shades - motorized	970 sf	18.00 /sf	17,460
Roller shades - interior	3,300 sf	8.00 /sf	26,400
Roller shades - doors	50 ea	150.00 /ea	7,500
<b>Window Treatments</b>	<b>136,600 sf</b>	<b>0.98 /sf</b>	<b>133,240</b>
<b>12-20 WINDOW TREATMENTS</b>	<b>136,600 sf</b>	<b>0.98 /sf</b>	<b>133,240</b>
<b>12-35 LAB CASEWORK</b>			
<b>11.53.00 Laboratory Equipment</b>			
Misc. lab equipment - Allowance	1 ls	25,000.00 /ls	25,000
Fume hoods	3 ea	11,000.00 /ea	33,000
Fume hoods - 2-sided	1 ea	15,000.00 /ea	15,000
<b>Laboratory Equipment</b>	<b>136,600 sf</b>	<b>0.53 /sf</b>	<b>73,000</b>
<b>12.35.53 Laboratory Casework</b>			
Base cabinet w/epoxy top	30 lf	600.00 /lf	18,000
Epoxy countertop - open below	325 lf	375.00 /lf	121,875
Epoxy backsplash	635 lf	60.00 /lf	38,100
Wall cabinets	105 lf	400.00 /lf	42,000
<b>Laboratory Casework</b>	<b>136,600 sf</b>	<b>1.61 /sf</b>	<b>219,975</b>
<b>12-35 LAB CASEWORK</b>	<b>136,600 sf</b>	<b>2.15 /sf</b>	<b>292,975</b>



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>12-60 FIXED AUDITORIUM SEATING</b>			
<b>12.60.00 Multiple Seating</b>			
Fixed audience seating	406 ea	285.00 /ea	115,710
<b>Multiple Seating</b>	<b>136,600 sf</b>	<b>0.85 /sf</b>	<b>115,710</b>
<b>12-60 FIXED AUDITORIUM SEATING</b>	<b>136,600 sf</b>	<b>0.85 /sf</b>	<b>115,710</b>
<b>12-62 BLEACHERS</b>			
<b>12.60.00 Multiple Seating</b>			
Retractable Bleachers at Gym	650 seat	155.00 /seat	100,750
<b>Multiple Seating</b>	<b>136,600 sf</b>	<b>0.74 /sf</b>	<b>100,750</b>
<b>12-62 BLEACHERS</b>	<b>136,600 sf</b>	<b>0.74 /sf</b>	<b>100,750</b>
<b>14-20 ELEVATORS (TS)</b>			
<b>14.20.00 Elevators</b>			
Passenger elevators - cab, equipment	1 ls	40,000.00 /ls	40,000
Passenger elevators - stops	4 stop	45,000.00 /stop	180,000
<b>Elevators</b>	<b>136,600 sf</b>	<b>1.61 /sf</b>	<b>220,000</b>
<b>14-20 ELEVATORS (TS)</b>	<b>136,600 sf</b>	<b>1.61 /sf</b>	<b>220,000</b>
<b>21-01 FIRE PROTECTION (TS)</b>			
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Fire Protection)	(1) ls	31,000.00 /ls	(31,000)
Trade support - lull, laborer for cleanup (Fire Protection)	1 ls	31,000.00 /ls	31,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>21.01.00 Fire Suppression General Requirements</b>			
General requirements (management/design, permits, as-builts, coring, fire stopping)	136,600 sf	0.50 /sf	68,300
Hydraulic calculation & shop drawings	1 ls	8,000.00 /ls	8,000
3D/BIM coordination	1 ls	10,000.00 /ls	10,000
<b>Fire Suppression General Requirements</b>	<b>136,600 sf</b>	<b>0.63 /sf</b>	<b>86,300</b>
<b>21.11.00 Fire Suppression - Water-Service Piping</b>			
Fire dept. inlet connection - 2-1/2" polished brass - 3 -way	1 ea	1,863.93 /ea	1,864



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Fire Suppression - Water-Service Piping</b>	<b>136,600 sf</b>	<b>0.01 /sf</b>	<b>1,864</b>
<b>21.12.00 Fire-Suppression Standpipes</b>			
Standpipe - sch 40 black steel piping w/ fittings - 6"	125 lf	99.13 /lf	12,391
Drain riser - sch 40 black steel piping w/ fittings - 3"	125 lf	49.66 /lf	6,208
Fire hose valve - 2-1/2"	12 ea	353.36 /ea	4,240
Fire valve cabinet - steel - recessed	12 ea	894.50 /ea	10,734
<b>Fire-Suppression Standpipes</b>	<b>136,600 sf</b>	<b>0.25 /sf</b>	<b>33,573</b>
<b>21.13.13 Fire Suppression Wet-Pipe Sprinkler System</b>			
Sprinkler head - wet - recessed pendant	903 ea	125.42 /ea	113,250
Sprinkler head - wet - pendant or upright	522 ea	77.23 /ea	40,313
Sprinkler head - wet - sidewall	151 ea	87.51 /ea	13,213
Sprinkler head - wet - window	34 ea	87.51 /ea	2,975
Sprinkler head - extended coverage pendant or upright	120 ea	127.23 /ea	15,267
Sprinkler head - dry - sidewall (wet system)	22 ea	293.06 /ea	6,447
Sprinkler branch piping black steel sch. 40 w/ fittings 1"	3,465 lf	23.99 /lf	83,116
Sprinkler branch piping black steel sch. 40 w/ fittings 1-1/4"	600 lf	27.93 /lf	16,757
Sprinkler branch piping black steel sch. 40 w/ fittings 1-1/2"	5,200 lf	30.66 /lf	159,417
Sprinkler branch piping black steel sch. 40 w/ fittings 2"	650 lf	34.57 /lf	22,468
Sprinkler main piping black steel sch. 40 w/ fittings (avg. size)	1,000 lf	62.18 /lf	62,184
Sprinkler main piping black steel sch. 10 w/ fittings 3"	450 lf	36.32 /lf	16,345
Sprinkler main piping black steel sch. 10 w/ fittings 4"	3,180 lf	39.66 /lf	126,127
Sprinkler main piping black steel sch. 10 w/ fittings 6"	500 lf	69.39 /lf	34,695
Wet alarm valve - 6"	1 ea	3,656.71 /ea	3,657
Double check valve (BFP) assembly - 6"	1 ea	8,244.56 /ea	8,245
Butterfly valve - 6"	2 ea	1,566.71 /ea	3,133
Zone flow control valve - 4"	7 ea	2,521.71 /ea	17,652
Waterflow switch	8 ea	421.96 /ea	3,376
Tamper switch	8 ea	356.96 /ea	2,856
Water motor gong bell	1 ea	628.36 /ea	628
<b>Fire Suppression Wet-Pipe Sprinkler System</b>	<b>136,600 sf</b>	<b>5.51 /sf</b>	<b>752,122</b>
<b>21-01 FIRE PROTECTION (TS)</b>	<b>136,600 sf</b>	<b>6.40 /sf</b>	<b>873,859</b>
<b>22-01 PLUMBING (TS)</b>			
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Plumbing)	(1) ls	83,000.00 /ls	(83,000)
Trade support - lull, laborer for cleanup (Plumbing)	1 ls	83,000.00 /ls	83,000



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>22.00.05 PLUMBING - General Requirements</b>			
General requirements (management, permits, as-builts, coring, fire stopping)	136,600 sf	0.75 /sf	102,450
3D/BIM coordination	1 ls	12,000.00 /ls	12,000
Core drilling	1 ls	10,000.00 /ls	10,000
Project management	1 ls	50,000.00 /ls	50,000
Kitchen Equipment Tie ins	1 ls	12,000.00 /ls	12,000
<b>PLUMBING - General Requirements</b>	<b>136,600 sf</b>	<b>1.37 /sf</b>	<b>186,450</b>
<b>22.07.00 PLUMBING - Insulation</b>			
Insulation/copper pipe/fiberglass	7,975 lf	8.44 /lf	67,307
Insulation/rainleader pipe/fiberglass/PVC jacketed/horiz. & vert.	1,200 lf	40.61 /lf	48,737
<b>PLUMBING - Insulation</b>	<b>136,600 sf</b>	<b>0.85 /sf</b>	<b>116,044</b>
<b>22.08.00 Plumbing Commissioning Support</b>			
Commissioning support/day	5 day	824.56 /day	4,123
<b>Plumbing Commissioning Support</b>	<b>136,600 sf</b>	<b>0.03 /sf</b>	<b>4,123</b>
<b>22.10.00 Plumbing Facility Water Distribution</b>			
Water meter w/remote readout - 4"	1 ea	2,285.75 /ea	2,286
Water sub-meter - avg. size	1 ea	1,561.84 /ea	1,562
Water sub-meter - 1.5 Circ	1 ea	1,261.84 /ea	1,262
Water sub-meter - 2" Domestic WH	1 ea	1,277.30 /ea	1,277
Backflow preventer/RPZ-BFP - dishwasher	1 ea	1,809.21 /ea	1,809
Backflow preventer/RPZ-BFP - 2" LW	2 ea	1,657.68 /ea	3,315
Backflow preventer/RPZ-BFP - 4"	1 ea	1,960.75 /ea	1,961
Pressure reducing valve/PRV - 1"	1 ea	1,159.21 /ea	1,159
Pressure reducing valve - 4"	1 ea	2,210.75 /ea	2,211
Recirculation pump/bronze/6.5 gpm - 1/8 hp (B&G Ecocirc)	1 ea	1,806.14 /ea	1,806
Recirculation pump/bronze/10 gpm - 1/6 hp (B&G #SSF-22)	2 ea	709.14 /ea	1,418
Expansion tank/ASME/potable - 9 gal (B&G #PTA-30V)	1 ea	1,250.61 /ea	1,251
TMV/master/hi-lo temp.	1 ea	2,759.21 /ea	2,759
Hose bibbs w/vac. breaker/encased - interior	19 ea	382.50 /ea	7,268
Hose bibbs/exterior/encased (Zurn #Z1320)	3 ea	452.07 /ea	1,356
Trap primers/electronic - 8 outlet (PPP #PT-8)	8 ea	1,359.91 /ea	10,879
Shock absorbers/12 - 33 fixture units (Shoktrol #200)	3 ea	269.77 /ea	809
Valve box/washing machine	1 ea	226.54 /ea	227
Valve box/ice machine	3 ea	176.54 /ea	530
Domestic water entrance UG/ductile iron - 4"	20 lf	306.14 /lf	6,123



90% CD Reconciled Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>22.10.00 Plumbing Facility Water Distribution</b>			
Domestic water AG/type "L" copper/press fit ftgs. - avg. size	525 lf	23.31 /lf	12,235
Domestic water AG/type "L" copper/press fit - 1/2" TP	1,120 lf	13.02 /lf	14,577
Domestic water AG/type "L" copper/press fit - 1/2" NP	800 lf	13.02 /lf	10,412
Domestic water AG/type "L" copper/press fit - 1/2"	1,460 lf	13.02 /lf	19,002
Domestic water AG/type "L" copper/press fit - 3/4" NP	450 lf	15.76 /lf	7,091
Domestic water AG/type "L" copper/press fit - 3/4"	1,240 lf	15.76 /lf	19,539
Domestic water AG/type "L" copper/press fit - 1" NP	100 lf	20.56 /lf	2,056
Domestic water AG/type "L" copper/press fit - 1"	50 lf	20.57 /lf	1,028
Domestic water AG/type "L" copper/press fit - 1-1/4" NP	100 lf	25.23 /lf	2,523
Domestic water AG/type "L" copper/press fit - 1-1/4"	115 lf	25.23 /lf	2,902
Domestic water AG/type "L" copper/press fit - 1-1/2"	400 lf	30.31 /lf	12,125
Domestic water AG/type "L" copper/press fit - 2" NP	450 lf	41.16 /lf	18,523
Domestic water AG/type "L" copper/press fit - 2"	300 lf	41.16 /lf	12,349
Domestic water AG/type "L" copper/press fit - 2-1/2"	285 lf	66.38 /lf	18,919
Domestic water AG/type "L" copper/press fit - 3"	480 lf	84.91 /lf	40,759
Domestic water AG/type "L" copper/press fit - 4"	100 lf	116.00 /lf	11,600
Non-potable water AG/type "L" copper/solder - Hood Tie In	60 lf	22.94 /lf	1,377
- Domestic water piping accessories DOM	6,095 lf	2.78 /lf	16,917
- Domestic water piping accessories NP	1,900 lf	2.78 /lf	5,274
- Domestic water heat tracing/small bore piping All LHW	1,900 lf	25.97 /lf	49,340
- Domestic water pipe & equipment I.D. DOM	6,095 lf	1.61 /lf	9,817
- Domestic water pipe & equipment I.D. NP	1,900 lf	1.52 /lf	2,881
- Domestic water pressure gauges & thermometers	12 ea	120.61 /ea	1,447
- Domestic water support steel/additional to hangers & clamps	1 ls	1,074.56 /ls	1,075
- Layout Mech Room	1 ls	20,000.00 /ls	20,000
- Domestic water storage tank	1 ls	3.52 /ls	4
<b>Plumbing Facility Water Distribution</b>	<b>136,600 sf</b>	<b>2.67 /sf</b>	<b>365,038</b>
<b>22.13.00 PLUMBING - Sanitary, Waste &amp; Vent Piping</b>			
Floor drain - 3" (#ZN415-6B)	16 ea	294.07 /ea	4,705
Floor drain - 4" (#ZN415-8B)	4 ea	353.07 /ea	1,412
Floor sink/12x12 - 4" (#Z1900)	8 ea	2,581.14 /ea	20,649
Floor cleanouts - 4" (#ZN1400)	37 ea	291.07 /ea	10,770
Wall cleanouts - 4" (#Z1468)	10 ea	101.08 /ea	1,011
Grease interceptor/interior/size 800/75 gpm/150 gal.	2 ea	4,291.56 /ea	8,583
8000 Gallon Concrete Grease Trap	1 ea	17,649.12 /ea	17,649
Elevator sump pump/oil minder	1 ea	3,812.28 /ea	3,812
Grease interceptor flow control	1 ea	417.14 /ea	417
Sanitary UG/cast iron single hub pipe & ftgs. - 2"	220 lf	31.98 /lf	7,036
Sanitary UG/cast iron single hub pipe & ftgs. - 3"	236 lf	36.45 /lf	8,602





# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>22.13.00 PLUMBING - Sanitary, Waste &amp; Vent Piping</b>			
Sanitary UG/cast iron single hub pipe & ftgs. - 4"	610 lf	44.78 /lf	27,315
Sanitary UG/cast iron single hub pipe & ftgs. - 6"	275 lf	74.82 /lf	20,576
Sanitary AG/cast iron no hub pipe & ftgs. - avg. size Fixture Runouts	1,560 lf	47.33 /lf	73,828
Sanitary AG/cast iron no hub pipe & ftgs. - 1-1/2"	30 lf	33.82 /lf	1,015
Sanitary AG/cast iron no hub pipe & ftgs. - 2"	750 lf	34.83 /lf	26,119
Sanitary AG/cast iron no hub pipe & ftgs. - 3"	980 lf	44.36 /lf	43,468
Sanitary AG/cast iron no hub pipe & ftgs. - 4"	495 lf	52.52 /lf	25,999
Grease waste UG/cast iron single hub pipe & ftgs. - 2"	40 lf	31.98 /lf	1,279
Grease waste UG/cast iron single hub pipe & ftgs. - 3"	20 lf	36.45 /lf	729
Grease waste UG/cast iron single hub pipe & ftgs. - 4"	220 lf	44.78 /lf	9,851
Grease waste AG/cast iron no hub pipe & ftgs. - 2"	55 lf	34.83 /lf	1,915
Grease waste AG/cast iron no hub pipe & ftgs. - 3"	65 lf	44.36 /lf	2,883
Grease waste AG/cast iron no hub pipe & ftgs. - 4"	70 lf	52.52 /lf	3,677
- Sanitary waste & vent piping accessories	5,626 lf	1.77 /lf	9,976
- Sanitary piping & equipment I.D.	5,626 lf	1.81 /lf	10,171
<b>PLUMBING - Sanitary, Waste &amp; Vent Piping</b>	<b>136,600 sf</b>	<b>2.51 /sf</b>	<b>343,448</b>
<b>22.14.00 PLUMBING - Rainleader Piping</b>			
Roof drain/#ZC100 - 4"	9 ea	298.07 /ea	2,683
Roof drain/#ZC100 - 5"	2 ea	387.84 /ea	776
Roof drain/#ZC100 - 6"	14 ea	387.84 /ea	5,430
Floor cleanouts - 4" (#ZN1400)	6 ea	291.07 /ea	1,746
Wall cleanouts - 4" (#Z1468)	12 ea	101.07 /ea	1,213
Rainleader UG/cast iron single hub pipe & ftgs. - 4"	90 lf	44.77 /lf	4,030
Rainleader UG/cast iron single hub pipe & ftgs. - 6"	90 lf	74.82 /lf	6,734
Rainleader UG/cast iron single hub pipe & ftgs. - 8"	70 lf	103.25 /lf	7,228
Rainleader UG/cast iron single hub pipe & ftgs. - 10"	160 lf	141.04 /lf	22,566
Rainleader UG/cast iron single hub pipe & ftgs. - 12"	25 lf	186.99 /lf	4,675
Rainleader AG/cast iron no hub pipe & ftgs. - 4"	265 lf	52.53 /lf	13,919
Rainleader AG/cast iron no hub pipe & ftgs. - 6"	410 lf	81.16 /lf	33,274
Rainleader AG/cast iron no hub pipe & ftgs. - 8"	460 lf	133.84 /lf	61,565
Rainleader AG/cast iron no hub pipe & ftgs. - 10"	10 lf	198.47 /lf	1,985
- Rainleader piping accessories	1,580 lf	1.77 /lf	2,802
- Rainleader piping & equipment I.D.	1,580 lf	1.46 /lf	2,314
<b>PLUMBING - Rainleader Piping</b>	<b>136,600 sf</b>	<b>1.27 /sf</b>	<b>172,939</b>
<b>22.20.00 Plumbing Facility Gas Piping - Natural &amp; LP Gas</b>			
Gas Flow Meter - avg. size	1 ea	1,857.68 /ea	1,858
Emergency gas shut off/cabinet w/1" solenoid & UL ball valve 1114, 1111A	2 ea	3,968.42 /ea	7,937



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>22.20.00 Plumbing Facility Gas Piping - Natural &amp; LP Gas</b>			
Emergency gas shut off/cabinet w/1-1/2" solonoid & UL ball valve KIT	1 ea	5,093.42 /ea	5,093
- Remote panic buttons	2 ea	828.07 /ea	1,656
Gas turret/single	5 ea	212.07 /ea	1,060
Gas turret/double	5 ea	320.54 /ea	1,603
Gas piping/sch 40 black steel CW t&c - 1"	240 lf	28.68 /lf	6,882
Gas piping/sch 40 black steel CW t&c - 1-1/4"	120 lf	34.14 /lf	4,097
Gas piping/sch 40 black steel CW t&c - 1-1/2"	65 lf	37.25 /lf	2,421
Gas piping/sch 40 black steel CW t&c - 2"	10 lf	42.28 /lf	423
Gas piping/sch 40 blk stl ERW weld - 2-1/2"	30 lf	45.73 /lf	1,372
Gas piping/sch 40 blk stl ERW weld - 3"	75 lf	54.12 /lf	4,059
Gas piping/sch 40 blk stl ERW weld - 4"	60 lf	87.71 /lf	5,263
Gas piping for generator	250 lf	80.00 /lf	20,000
Gas piping/sch 40 blk stl ERW weld - 8"	25 lf	180.43 /lf	4,511
- Gas piping accessories	625 lf	2.52 /lf	1,577
- Gas piping link seals	1 ea	404.61 /ea	405
- Gas piping & equipment I.D.	625 lf	28.95 /lf	18,094
<b>Plumbing Facility Gas Piping - Natural &amp; LP Gas</b>	<b>136,600 sf</b>	<b>0.65 /sf</b>	<b>88,310</b>
<b>22.30.00 PLUMBING - Equipment</b>			
Domestic Boilers/gas fired/399 mbh (AO Smith #BTH-300A)	2 ea	15,618.42 /ea	31,237
Boiler Flues	1 ls	45,525.00 /ls	45,525
Water Heater Flues	1 ls	24,000.00 /ls	24,000
HWH/indirect fed - 300 gal	1 ea	7,418.42 /ea	7,418
<b>PLUMBING - Equipment</b>	<b>136,600 sf</b>	<b>0.79 /sf</b>	<b>108,180</b>
<b>22.40.00 PLUMBING - Fixtures</b>			
Water closet/wall mnt./carrier/flush valve	22 ea	1,330.12 /ea	29,263
Water closet/wall mnt./carrier/flush valve/ADA	32 ea	1,367.52 /ea	43,761
Urinal/wall mnt./carrier/flush valve	18 ea	1,202.85 /ea	21,651
Urinal/wall mnt./carrier/flush valve/ADA	5 ea	1,241.35 /ea	6,207
Lavatory/undermount/std 1-lever faucet	54 ea	523.24 /ea	28,255
Lavatory/undermount/std 1-lever faucet/ADA	10 ea	586.41 /ea	5,864
Lavatory/wall hung/std 1-lever faucet/carrier/ADA	15 ea	1,147.55 /ea	17,213
Sensor faucets/flush	1 ls	78,000.00 /ls	78,000
Mixing valve/single lav. (Leonard #170)	85 ea	348.84 /ea	29,651
P15 Sink/lay-in/1-bowl 20"x22"/std faucet/ADA	2 ea	1,560.75 /ea	3,121
P14 Sink/lay-in/1-bowl 20"x22"/std faucet/ADA Maker Space	2 ea	1,610.75 /ea	3,221
P7 Sink/lay-in/1-bowl 21"x15"/std faucet	36 ea	1,584.98 /ea	57,059
P9 Sink/lay-in/1-bowl 21"x15"/std faucet Art Room	3 ea	1,384.98 /ea	4,155
P9A Sink/lay-in/1-bowl 21"x15"/std faucet/ADA Art Room	1 ea	1,455.75 /ea	1,456



90% CD Reconciled Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>22.40.00 PLUMBING - Fixtures</b>			
P7A Sink/lay-in/1-bowl 21"x15"/std faucet/ADA	3 ea	1,860.75 /ea	5,582
P8 Sink/lay-in/1-bowl/22"x16"/bubbler	5 ea	1,715.35 /ea	8,577
P-13 Sink/acid waste/undermount/std 2-lever faucet/ss - 21"x15"x10"D	3 ea	1,508.82 /ea	4,526
- Solids interceptors (Art Room sinks)	4 ea	552.64 /ea	2,211
Mop sink/floor mnt - 24"x24"	5 ea	1,349.01 /ea	6,745
P6 Shower stall/std valve & access./3'x3' fiberglass	1 ea	2,704.96 /ea	2,705
P6-A Shower stall/std valve & access./5'x3' fiberglass/ADA	2 ea	3,701.67 /ea	7,403
P13 Emergency eye wash station/mixing valve/sink mount	3 ea	1,106.71 /ea	3,320
Emergency shower/eye wash sta./mixing valve/cabinet mount	7 ea	3,540.35 /ea	24,782
Water cooler/bi-level/ADA	10 ea	4,418.42 /ea	44,184
- Plumbing fixtures offload & distribution	239 ea	103.07 /ea	24,634
- Plumbing fixtures rough-in	239 ea	128.07 /ea	30,609
<b>PLUMBING - Fixtures</b>	<b>136,600 sf</b>	<b>3.62 /sf</b>	<b>494,156</b>
<b>22.66.00 Plumbing Acid Neutrization System</b>			
Acid neut. Tank/5 gallon - 1-sink (Orion style 5)	1 ea	622.14 /ea	622
Acid neut. tank/15 gallon - 3-sinks (Orion style 5)	3 ea	911.21 /ea	2,734
Acid neut. tank/55 gallon -	2 ea	1,912.28 /ea	3,825
- Limestone chips/50 lb. bag	24 ea	43.77 /ea	1,050
PH Monitoring (2) locations	2 ea	6,612.28 /ea	13,225
Floor drain - 6" (#ZN415-AA-8B)	3 ea	480.84 /ea	1,443
Floor cleanout/heavy duty - 4" (#ZN1400-K-AR)	5 ea	424.84 /ea	2,124
Wall cleanouts/#Z1468 - 4"	5 ea	101.07 /ea	505
Acid waste UG/sch 40 polypropylene fuseal & ftgs. - 3"	20 lf	58.29 /lf	1,166
Acid waste UG/sch 40 polypropylene fuseal & ftgs. - 4"	230 lf	68.91 /lf	15,849
Tie-ins to Lab Hoods acid waste & vent - A/G	3 ea	815.35 /ea	2,446
Acid waste AG/sch 40 polypropylene fuseal & ftgs. - 2"	800 lf	51.44 /lf	41,154
Acid waste AG/sch 40 polypropylene fuseal & ftgs. - 3"	400 lf	65.67 /lf	26,269
Acid waste AG/sch 40 polypropylene fuseal & ftgs. - 4"	360 lf	77.44 /lf	27,877
- Acid waste & vent piping accessories	1,810 lf	2.02 /lf	3,662
- Acid waste piping & equipment I.D.	1,810 lf	2.56 /lf	4,636
<b>Plumbing Acid Neutrization System</b>	<b>136,600 sf</b>	<b>1.09 /sf</b>	<b>148,587</b>
<b>22.90.00 Plumbing - Other</b>			
Wiring PH Monitor and Misc Control	1 ls	6,000.00 /ls	6,000
<b>Plumbing - Other</b>	<b>136,600 sf</b>	<b>0.04 /sf</b>	<b>6,000</b>
<b>22-01 PLUMBING (TS)</b>	<b>136,600 sf</b>	<b>14.89 /sf</b>	<b>2,033,274</b>



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>23-01 HVAC (TS)</b>			
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (HVAC)	(1) ls	343,000.00 /ls	(343,000)
Trade support - lull, laborer for cleanup (HVAC)	1 ls	343,000.00 /ls	343,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>23.00.05 HVAC - General Requirements</b>			
General requirements (sq. ft.)	136,600 sf	1.15 /sf	157,090
3D/BIM coordination	1 ls	100,000.00 /ls	100,000
<b>HVAC - General Requirements</b>	<b>136,600 sf</b>	<b>1.88 /sf</b>	<b>257,090</b>
<b>23.05.93 HVAC Testing Adjusting &amp; Balancing (TAB)</b>			
Testing & balancing/cost per sq. ft.	136,600 sf	0.65 /sf	88,790
<b>HVAC Testing Adjusting &amp; Balancing (TAB)</b>	<b>136,600 sf</b>	<b>0.65 /sf</b>	<b>88,790</b>
<b>23.07.00 HVAC - Insulation</b>			
Insulation/ductwork/blanket wrap	83,500 sf	3.55 /sf	296,088
Insulation/ductwork/weatherproof exposed	4,500 sf	12.89 /sf	57,986
Insulation/pipe/copper	14,483 lf	7.09 /lf	102,715
Insulation/pipe/weld	3,838 lf	12.50 /lf	47,975
<b>HVAC - Insulation</b>	<b>136,600 sf</b>	<b>3.70 /sf</b>	<b>504,764</b>
<b>23.08.00 HVAC - Commissioning Support</b>			
Commissioning support/lump sum	1 ls	15,000.00 /ls	15,000
<b>HVAC - Commissioning Support</b>	<b>136,600 sf</b>	<b>0.11 /sf</b>	<b>15,000</b>
<b>23.09.00 HVAC - Automatic Temperature Controls</b>			
Automatic temperature controls/cost per sq. ft.	136,600 sf	0.25 /sf	34,150
ATC - Air valve/hood exhaust/HEX	3 ea	4,194.32 /ea	12,583
ATC - Air valves/no coil control wiring - 3 pts./fume hood	9 pnt	437.00 /pnt	3,933
ATC - RTU's/custom - 30 pts.	240 pnt	1,303.18 /pnt	312,763
ATC - MUA units - 10 pts.	10 pnt	759.44 /pnt	7,594
ATC - Exhaust fans - 3 pts.	18 pnt	711.10 /pnt	12,800
ATC - Life safty fans - 8 pts.	32 pnt	766.15 /pnt	24,517
ATC - Lab exhaust fans - 5 pts./fan	25 pnt	766.15 /pnt	19,154
ATC - Boilers/modular - 10 pts.	20 pnt	821.19 /pnt	16,424
ATC - Pumps - 4 pts.	16 pnt	766.15 /pnt	12,258
ATC - VFD wiring for pumps (remote mount) - 4 pts.	16 pnt	763.91 /pnt	12,223
ATC - Circulators - 2 pts.	4 pnt	488.68 /pnt	1,955
ATC - Chillers - 15 pts.	15 pnt	1,303.18 /pnt	19,548
ATC - VAV box/no coil (ATC furn./factory install controls) 2 pts.	310 pnt	408.36 /pnt	126,592



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>23.09.00 HVAC - Automatic Temperature Controls</b>			
ATC - Fintube radiation zones - 2 pts.	20 pnt	381.96 /pnt	7,639
ATC - electric fintube radiation zones - 2 pts.	4 pnt	381.95 /pnt	1,528
ATC - Cabinet unit heaters - 3 pts.	42 pnt	381.96 /pnt	16,042
ATC - Unit heaters - 3 pts.	6 pnt	381.95 /pnt	2,292
ATC - Radiant ceiling panel zones - 2 pts.	246 pnt	381.96 /pnt	93,961
ATC - Plumbing points - 10 pts.	10 pnt	595.50 /pnt	5,955
ATC - Elctrical points - 10 pts.	10 pnt	595.50 /pnt	5,955
<b>HVAC - Automatic Temperature Controls</b>	<b>136,600 sf</b>	<b>5.49 /sf</b>	<b>749,864</b>
<b>23.21.13 Hydronic Piping</b>			
Hot water s&r/type "L" copper solder - 3/4"	8,970 lf	20.16 /lf	180,835
Hot water s&r/type "L" copper solder - 1"	1,760 lf	25.01 /lf	44,018
Hot water s&r/type "L" copper solder - 1-1/4"	1,260 lf	28.57 /lf	35,998
Hot water s&r/type "L" copper solder - 1-1/2"	890 lf	32.82 /lf	29,210
Hot water s&r/type "L" copper solder - 2"	1,550 lf	41.25 /lf	63,937
Hot water s&r/sch 40 blk stl ERW weld - 2-1/2"	605 lf	50.55 /lf	30,583
Hot water s&r/sch 40 blk stl ERW weld - 3"	475 lf	59.42 /lf	28,225
Hot water s&r/sch 40 blk stl ERW weld - 4"	756 lf	82.30 /lf	62,219
Hot water s&r/sch 40 blk stl ERW weld - 6"	520 lf	134.07 /lf	69,716
Hot water s&r/sch 40 blk stl ERW weld - 8"	220 lf	167.74 /lf	36,903
Glycol water s&r/type "L" copper solder - 2"	53 lf	41.25 /lf	2,186
Glycol water s&r/sch 40 blk stl ERW weld - 2-1/2"	47 lf	50.55 /lf	2,376
Glycol water s&r/sch 40 blk stl ERW weld - 3"	90 lf	59.42 /lf	5,348
Glycol water s&r/sch 40 blk stl ERW weld - 4"	152 lf	82.30 /lf	12,510
Glycol water s&r/sch 40 blk stl ERW weld - 6"	910 lf	134.07 /lf	122,004
Glycol water s&r/sch 40 blk stl ERW weld - 8"	110 lf	167.74 /lf	18,451
- Hydronic piping accessories	18,368 lf	2.53 /lf	46,506
<b>Hydronic Piping</b>	<b>136,600 sf</b>	<b>5.79 /sf</b>	<b>791,024</b>
<b>23.21.23 Hydronic Pumps &amp; Accessories</b>			
Pump/base mount/790 gpm (HW)	2 ea	8,167.68 /ea	16,335
Chilled water pump house (pumps & accesories, enclosure, piping, unit heater	1 ls	226,667.68 /ls	226,668
- Suction diffusers	2 ea	1,460.58 /ea	2,921
- Flex connector/HVAC pumps	4 ea	556.35 /ea	2,225
- Triple duty valves	2 ea	2,312.69 /ea	4,625
Air separators	1 ea	4,333.84 /ea	4,334
Expansion tanks/ASME	2 ea	7,167.68 /ea	14,335
<b>Hydronic Pumps &amp; Accessories</b>	<b>136,600 sf</b>	<b>1.99 /sf</b>	<b>271,444</b>



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>23.25.00 HVAC Water Treatment</b>			
Chemical treatment (lump sum)	1 ls	20,000.00 /ls	20,000
Glycol feed/50 gal. tank w/pump (Neptune #G-50-1)	2 ea	5,272.92 /ea	10,546
- Glycol solution/40% propylene	1,000 gal	25.21 /gal	25,212
<b>HVAC Water Treatment</b>	<b>136,600 sf</b>	<b>0.41 /sf</b>	<b>55,757</b>
<b>23.30.00 HVAC - Sheetmetal &amp; Fans</b>			
Sheetmetal & accessories/galvanized	111,320 lb	11.04 /lb	1,228,973
Sheetmetal & accessories/galvanized (perforated)	869 lb	14.49 /lb	12,592
Sheetmetal & accessories/galvanized (smoke exhasut)	9,735 lb	11.04 /lb	107,474
Sheetmetal & accessories/galvanized (perforated liner)	4,000 lb	14.49 /lb	57,960
Sheetmetal & accessories/stainless steel (dishwasher)	350 lb	22.28 /lb	7,798
Sheetmetal & accessories/welded stainless steel (kitchen exhaust)	1,060 lb	29.78 /lb	31,567
Sheetmetal & accessories/welded stainless steel (kiln exhaust)	500 lb	29.78 /lb	14,890
Sheetmetal & accessories/welded stainless steel (3 - fume hoods)	2,700 lb	29.78 /lb	80,406
Sheetmetal & accessories/fabric/1-row cable (DuctSox) - 20"	405 lf	76.50 /lf	30,982
Sheetmetal & accessories/fabric/1-row cable (DuctSox) - 24"	305 lf	81.29 /lf	24,792
Duct enclosure (roof)	1 ea	5,424.10 /ea	5,424
SM - Flue piping/double wall/stainless steel/6" pipe - linear foot DWH	600 lf	97.98 /lf	58,786
SM - Flue piping/double wall/stainless steel/6" fittings - each DWH	16 ea	122.47 /ea	1,960
SM - Flue piping/double wall/stainless steel/6" fittings - each DWH	8 lf	122.47 /lf	980
SM - Diffusers, registers & grilles	136,600 sf	0.20 /sf	27,320
SM - Linear slot diffusers (supply)	6 ea	465.39 /ea	2,792
<b>SM - Linear slot diffusers (exhaust) - architectural</b>	<b>lf</b>	<b>/lf</b>	
SM - Displ. Diffuser/Floor Mnt.	156 ea	1,289.88 /ea	201,221
SM - Combination fire/smoke dampers/louver type/UL	20 ea	776.53 /ea	15,530
SM - Motorized damper	14 ea	1,107.92 /ea	15,511
SM - Smoke detectors/duct mount	40 ea	747.47 /ea	29,899
SM - Sound attenuators/in-line/std. gauge	239,000 cfm	0.55 /cfm	131,341
SM - Kitchen exhaust hood/st. steel/install only (by KES)	1 ea	2,339.28 /ea	2,339
SM - Dishwasher exhaust hood/st. steel/install only (by KES)	1 ea	1,559.52 /ea	1,560
<b>HVAC - Sheetmetal &amp; Fans</b>	<b>136,600 sf</b>	<b>15.32 /sf</b>	<b>2,092,097</b>
<b>23.34.00 HVAC Fans - Exhaust &amp; Supply</b>			
SEF-1-4	4 ea	17,339.28 /ea	69,357
EF-3&4 /centrifugal downblast/roof/direct drive - 500 cfm	2 ea	1,069.31 /ea	2,139
EF-1&2 /centrifugal downblast/roof/direct drive - 2,500 cfm	2 ea	1,771.24 /ea	3,542
KEF-1&2/centrifugal upblast/roof	2 ea	2,734.82 /ea	5,470
FEF-1,2,3,4,5 Lab exhaust fan/roof - 1,200 cfm	5 ea	9,084.82 /ea	45,424



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>HVAC Fans - Exhaust &amp; Supply</b>	<b>136,600 sf</b>	<b>0.92 /sf</b>	<b>125,932</b>
<b>23.35.00 Specialty Exhaust Systems</b>			
Dust collection system	1 ea	17,339.28 /ea	17,339
Kiln exhaust	1 ls	5,500.00 /ls	5,500
<b>Specialty Exhaust Systems</b>	<b>136,600 sf</b>	<b>0.17 /sf</b>	<b>22,839</b>
<b>23.36.00 Air Terminal Units - VAV's, CAV's &amp;FPB's</b>			
Variable air volume box - small	12 ea	533.15 /ea	6,398
Variable air volume box - medium	143 ea	668.62 /ea	95,612
<b>Air Terminal Units - VAV's, CAV's &amp;FPB's</b>	<b>136,600 sf</b>	<b>0.75 /sf</b>	<b>102,010</b>
<b>23.50.00 HVAC - Central Heating Equipment</b>			
Boiler/HW/gas/high eff. cond. - 4,000 mbh Riello AR 4000	2 ea	57,501.52 /ea	115,003
Boiler circulator pump	2 ea	1,708.46 /ea	3,417
Boiler combustion air/galvanized steel 10"	200 lf	38.00 /lf	7,600
Flue piping/double wall/stainless steel 10"	205 lf	185.00 /lf	37,925
<b>HVAC - Central Heating Equipment</b>	<b>136,600 sf</b>	<b>1.20 /sf</b>	<b>163,945</b>
<b>23.60.00 HVAC - Central Cooling Equipment</b>			
Chiller/air cooled - 370 tons	1 ea	381,153.80 /ea	381,154
Buffer tanks/Lochinvar - 300 gals.	1 ea	8,750.76 /ea	8,751
<b>HVAC - Central Cooling Equipment</b>	<b>136,600 sf</b>	<b>2.85 /sf</b>	<b>389,905</b>
<b>23.70.00 HVAC - Central Air Handling Equipment</b>			
RTU-1-4 Classrooms (service enclosure, HW&CHW coils, energy recovery)	80,000 cfm	15.75 /cfm	1,260,000
RTU-5 Gymnasium (service enclosure, HW&CHW coils, energy recovery)	15,000 cfm	16.25 /cfm	243,750
RTU-6 Auditorium (service enclosure, HW&CHW coils, energy recovery)	12,000 cfm	16.25 /cfm	195,000
RTU-7 Lockers (service enclosure, HW&CHW coils, energy recovery)	2,000 cfm	18.25 /cfm	36,500
MAU-1 Make-up air unit/HW&CHW coil/	5,000 cfm	7.25 /cfm	36,250
<b>HVAC - Central Air Handling Equipment</b>	<b>136,600 sf</b>	<b>12.97 /sf</b>	<b>1,771,500</b>
<b>23.80.20 Mini-Split AC &amp; Heat Pump Systems</b>			
Mini-split AC system/1-zone/wall mnt./cool only - 12 mbh	1 ea	2,072.92 /ea	2,073
Mini-split AC system/1-zone/wall mnt./cool only - 18 mbh	5 ea	2,681.66 /ea	13,408
Mini-split AC system/1-zone/wall mnt./cool only - 24 mbh	2 ea	2,956.03 /ea	5,912
Mini-split refrigeration line set/6-12 mbh - 50'	2 ea	584.88 /ea	1,170
Mini-split refrigeration line set/15-18 mbh - 50'	10 ea	599.88 /ea	5,999



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>23.80.20 Mini-Split AC &amp; Heat Pump Systems</b>			
Mini-split refrigeration line set/24-30 mbh - 50'	4 ea	614.88 /ea	2,460
Mini-split condensate drains/type"L" copper	450 lf	19.43 /lf	8,744
A/C cond. pump	8 ea	253.74 /ea	2,030
INS - Mini-split Insulation/copper pipe	450 lf	6.87 /lf	3,090
ATC - Mini-split condensing units (w/factory controls)	8 ea	879.76 /ea	7,038
ATC - Mini-split indoor units (w/factory controls)	8 ea	587.35 /ea	4,699
<b>Mini-Split AC &amp; Heat Pump Systems</b>	<b>136,600 sf</b>	<b>0.42 /sf</b>	<b>56,622</b>
<b>23.82.00 Heating &amp; Cooling Terminal Equipment</b>			
Radiant ceiling panels/24" wide - ft.	1,450 lf	120.00 /lf	174,000
FTR-2 Finned-tube radiation w/enclosure - 1 row	260 lf	194.24 /lf	50,502
FTR-1 Finned-tube radiation w/enclosure - 2 row	570 lf	259.37 /lf	147,841
FTR-3 Finned-tube radiation w/enclosure - 2 row	40 lf	297.49 /lf	11,900
Fin-tube radiation/electric - 2 kW	8 ea	739.88 /ea	5,919
Cabinet unit heater/hot water/wall mount/recessed - avg. size	4 ea	1,573.62 /ea	6,294
Cabinet unit heater/hot water/ceiling mount - avg. size	10 ea	1,749.51 /ea	17,495
Unit heater/hot water/horiz./propeller - avg. size	2 ea	1,092.41 /ea	2,185
<b>Heating &amp; Cooling Terminal Equipment</b>	<b>136,600 sf</b>	<b>3.05 /sf</b>	<b>416,136</b>
<b>23.85.00 HVAC Equipment VFD's</b>			
Misc. VFD's	1 ls	35,000.00 /ls	35,000
VFD w/keypad/disconnect/bypass/NEMA 1 - HW pumps	2 ea	6,028.47 /ea	12,057
<b>VFD w/keypad/disconnect/bypass/NEMA 1 - CHW pumps w/ pump house</b>	<b>ea</b>	<b>/ea</b>	
<b>HVAC Equipment VFD's</b>	<b>136,600 sf</b>	<b>0.34 /sf</b>	<b>47,057</b>
<b>23.90.00 HVAC Equipment Rigging/Setting/Start Up</b>			
Equipment hoisting/rigging/setting/start-up	136,600 sf	1.50 /sf	204,900
<b>HVAC Equipment Rigging/Setting/Start Up</b>	<b>136,600 sf</b>	<b>1.50 /sf</b>	<b>204,900</b>
<b>23-01 HVAC (TS)</b>	<b>136,600 sf</b>	<b>59.49 /sf</b>	<b>8,126,676</b>
<b>26-01 ELECTRICAL (TS)</b>			
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Electrical)	(1) ls	230,000.00 /ls	(230,000)
Trade support - lull, laborer for cleanup (Electrical)	1 ls	230,000.00 /ls	230,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>26.00.05 Electrical General Requirements</b>			





# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>26.00.05 Electrical General Requirements</b>			
LEED Silver - premium (T.B.D.)	1 ls	9,400.00 /ls	9,400
Temp light stringers & GFCI power	136,600 sf	0.35 /sf	47,810
Temp 480Y/277V electrical service (400A)	3 ea	18,226.22 /ea	54,679
Temp power for welders	2 ea	2,398.27 /ea	4,797
Temp power for trailers	4 ea	1,302.42 /ea	5,210
Temp internet connection for trailers	4 ea	1,854.17 /ea	7,417
Material handling / project mgmt.	250 mh	97.71 /mh	24,428
3D/BIM coordination	500 mh	97.71 /mh	48,856
Record drawings / as-builts	1 ea	5,318.52 /ea	5,319
Seismic & testing (panels, generator, lighting control, fire alarm)	1 ls	18,800.00 /ls	18,800
Coring - patching - firestopping	136,600 sf	0.09 /sf	12,840
Project phasing (re-mobilization)	1 ls	9,400.00 /ls	9,400
Hoisting & rigging (generator & switchboard)	2 ls	7,050.00 /ls	14,100
<b>Electrical General Requirements</b>	<b>136,600 sf</b>	<b>1.93 /sf</b>	<b>263,055</b>
<b>26.05.05 Demolition for Electrical</b>			
Relocate existing emergency call box (provide new concrete base)	1 ea	2,994.80 /ea	2,995
Remove existing exterior site light fixture	11 ea	672.85 /ea	7,401
<b>Demolition for Electrical</b>	<b>136,600 sf</b>	<b>0.08 /sf</b>	<b>10,396</b>
<b>26.05.08 Electrical Distribution</b>			
Feeder (PVC/CU) - 150A [generator / LS]	135 lf	22.18 /lf	2,994
Feeder (PVC/CU) - 225A [generator / OS]	135 lf	33.46 /lf	4,517
Feeder (PVC/CU) - 400A [generator / LR] (exterior)	135 lf	56.93 /lf	7,685
Feeder (PVC/CU) - 2500A [secondary]	105 lf	414.00 /lf	43,470
Empty conduit - sch 40 PVC: 1 x 4" [generator]	135 lf	9.86 /lf	1,330
Empty conduit - sch 40 PVC: 1 x 4" [secondary / spare]	105 lf	9.86 /lf	1,035
Empty conduit - sch 40 PVC: 2 x 4" [primary]	250 lf	17.66 /lf	4,415
Magnetic warning tape - 1/8"	875 lf	4.37 /lf	3,826
Pole riser (GRC - 4"C)	2 ea	2,343.85 /ea	4,688
Electric manhole - 6'x12x7'	1 ea	6,773.56 /ea	6,774
Cast iron manhole frame/cover, 32"D x 6'H grade rings	1 ea	1,140.93 /ea	1,141
12" x 12" x 12"D ground mounted pullbox (Quazite #PC1212HG00 w/ Cover)	2 ea	752.15 /ea	1,504
Hand hole & cover - 4'x4'x4'	6 ea	1,937.11 /ea	11,623
17"x30"x12"D ground pullbox (Quazite #PC1730BA12 w/ cover)	11 ea	1,078.60 /ea	11,865
24" x 36" x 24"D ground mounted pullbox (Quazite #Pg2436BC-24 w/ Cover)	1 ea	1,718.39 /ea	1,718
<b>Electrical Distribution</b>	<b>136,600 sf</b>	<b>0.80 /sf</b>	<b>108,584</b>



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>26.05.26 Grounding &amp; Bonding for Electrical Systems</b>			
Building grounding & bonding	136,600 sf	0.11 /sf	15,408
Manhole / racking grounding & bonding	1 ea	701.05 /ea	701
Exterior (utility) transformer grounding & bonding	1 ea	1,066.05 /ea	1,066
Generator grounding & bonding	1 ea	1,066.05 /ea	1,066
SPD grounding (internal and external)	47 ea	120.29 /ea	5,653
Dry-type transformer grounding	4 ea	213.22 /ea	853
Copper ground bar - 2"x1/4" (ea.)	5 ea	280.03 /ea	1,400
Bare copper wire - #4/0 [duct bank]	875 lf	4.99 /lf	4,368
<b>Grounding &amp; Bonding for Electrical Systems</b>	<b>136,600 sf</b>	<b>0.22 /sf</b>	<b>30,516</b>
<b>26.05.83 Equipment Wiring</b>			
Science Classrooms - CO system solenoid shutdown- 120V power & control wiring	2 ea	5,326.40 /ea	10,653
Kitchen - Ansul system - 120V power & control wiring	1 ea	10,237.00 /ea	10,237
Gym scoreboards and shot clocks - wiring only, F&I by Div. 11	2 ea	5,344.80 /ea	10,690
Feeder (MC) - 20A (kitchen equipment - x42)	3,150 lf	5.75 /lf	18,111
Feeder (MC) - 30A (kitchen equipment - x2)	200 lf	5.87 /lf	1,173
1" PVC - 30A (3#8 & #10G)	250 lf	10.29 /lf	2,573
Feeder (MC) - 40A (kitchen equipment - x1)	100 lf	7.01 /lf	701
Feeder (MC) - 60A (kitchen equipment - x2)	200 lf	10.55 /lf	2,110
Power for automatic temperature control panels (BMS)	12 ea	460.91 /ea	5,531
Electric heat trace power (cables, sensors, controllers by Div. 21 / 22)	1,900 lf	3.50 /lf	6,650
Service switch: 20A/3P, NEMA-1	1 ea	107.43 /ea	107
Fused Disco: 20A/3P, NEMA-1	7 ea	323.22 /ea	2,263
Fused Disco: 100A/3P, NEMA-1	2 ea	1,185.41 /ea	2,371
Fused Disco: 200A/3P, NEMA-1	3 ea	1,555.38 /ea	4,666
Fused Disco: 1000A/3P, NEMA-1	2 ea	7,290.94 /ea	14,582
Wire gymnasium equipment SMC control stations (furnished by others)	8 ea	1,058.23 /ea	8,466
Electric vehicle charging station / dual pedestal / cable mgmt.	3 ea	10,512.40 /ea	31,537
Wire motors and controllers	15 ea	821.28 /ea	12,319
Kitchen equipment final connections (includes flexible whip)	47 ea	72.36 /ea	3,401
Mount & wire VFD's (furnished by Div. 23)	8 ea	646.55 /ea	5,172
MAU (5000cfm) - circuit / disconnect (3R) / connection	1 ea	2,503.41 /ea	2,503
RTU's - circuit / disconnect (3R) / connection (small)	3 ea	4,736.19 /ea	14,209
RTU's - circuit / disconnect (3R) / connection (large)	4 ea	7,010.29 /ea	28,041
Mini-split systems (indoor/outdoor) - circuits / disconnects (3R) / connections	8 ea	3,225.23 /ea	25,802
Chiller (370T) - circuit / disconnect (3R) / connection	1 ea	25,825.56 /ea	25,826
Smoke exhaust fans - circuit / disconnect / connection (100A)	4 ea	2,400.01 /ea	9,600



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>26.05.83 Equipment Wiring</b>			
Kitchen exhaust fans - circuit / disconnect / connection	2 ea	1,420.91 /ea	2,842
Kiln exhaust system - circuit / disconnect / connection	1 ea	2,655.30 /ea	2,655
Dust collection system - circuit / disconnect / connection	1 ea	3,579.00 /ea	3,579
Fume hood exhaust fans - circuit / disconnect / connection	5 ea	1,214.10 /ea	6,071
Exhaust fans - circuit / disconnect / connection	4 ea	1,214.11 /ea	4,856
Power to electronic trap primers - 120V	8 ea	100.19 /ea	801
Hot water pumps - circuit / disconnect / connection	2 ea	1,673.87 /ea	3,348
Boilers - circuit / disconnect / connection	2 ea	1,204.71 /ea	2,409
Chilled water pump house pumps & heaters - circuits / disconnects / connections	1 ls	6,158.00 /ls	6,158
Hot water heater - circuit / service switch / connection	1 ea	591.53 /ea	592
Cabinet unit heaters - circuit / service switch / connection	14 ea	868.28 /ea	12,156
Unit heaters - circuit / service switch / connection	2 ea	868.28 /ea	1,737
Elevator sump pump - circuit / disconnect (3R) / connection	1 ea	1,247.28 /ea	1,247
Domestic boilers - circuit / disconnect (3R) / connection	2 ea	1,247.28 /ea	2,495
Recirculation pumps - circuit / disconnect / connection	3 ea	997.87 /ea	2,994
Glycol feed pumps - circuit / disconnect / connection	2 ea	997.87 /ea	1,996
Boiler circulation pumps - circuit / disconnect / connection	2 ea	997.87 /ea	1,996
Fin-tube radiators (2kW) - circuit / disconnect / connection	8 ea	1,847.40 /ea	14,779
VAV's - circuit / disconnect / connection	155 ea	298.83 /ea	46,318
Acid neutralization tanks / PH monitoring - circuit / connection	2 ea	965.80 /ea	1,932
<b>Equipment Wiring</b>	<b>136,600 sf</b>	<b>2.78 /sf</b>	<b>380,253</b>
<b>26.09.23 Lighting Control Devices</b>			
On-site programming & startup (manufacturer)	1 ls	3,913.41 /ls	3,913
Single pole switch (120/277V)	13 ea	65.04 /ea	845
Key op switch (120/277V)	2 ea	72.44 /ea	145
Three position momentary contact switch	1 ea	226.42 /ea	226
Ceiling PIR occupancy sensor (24VDC)	323 ea	247.23 /ea	79,854
Occupancy sensor power packs (120V)	200 ea	82.04 /ea	16,408
Wall dimmer switch (0-10V)	227 ea	131.04 /ea	29,746
Photocells (daylight harvesting)	84 ea	265.06 /ea	22,265
Universal dimming room controller, 1-channel	50 ea	536.88 /ea	26,844
ALCS master switching / dimming station	1 ea	821.83 /ea	822
Plug load controllers (20A/120V)	50 ea	300.80 /ea	15,040
Emergency lighting transfer (bypass relay) - non-dimming	30 ea	236.81 /ea	7,104
Lighting contactor - 12 pole (exterior lighting)	1 ea	1,899.98 /ea	1,900
Astronomical time clock	1 ea	919.97 /ea	920
Rough in for Theater Lighting - Allowance	1 allw	9,400.01 /allw	9,400
Power for Theater Lighting - Allowance	1 allw	28,199.87 /allw	28,200



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>26.09.23 Lighting Control Devices</b>			
Sub lighting control panels	3 ea	2,394.56 /ea	7,184
Master lighting control panel	1 ea	4,383.41 /ea	4,383
Energy control unit	1 ea	2,157.58 /ea	2,158
System server unit	1 ea	1,316.75 /ea	1,317
Network Ethernet switch	1 ea	2,270.85 /ea	2,271
MC Cable (12/2) - 20A	12,500 lf	3.45 /lf	43,126
MC Cable (12/3) - 20A	3,500 lf	3.87 /lf	13,541
EMT (12/2) - 20A	2,000 lf	6.70 /lf	13,404
EMT (12/2) - 20A	50 lf	7.13 /lf	356
RJ45 Cable, 25LF (plenum-rated)	407 ea	72.10 /ea	29,344
RJ45 Cable, 50LF (plenum rated)	228 ea	111.05 /ea	25,318
<b>Lighting Control Devices</b>	<b>136,600 sf</b>	<b>2.83 /sf</b>	<b>386,033</b>
<b>26.10.00 Medium Voltage Electrical Distribution</b>			
Utility meter socket (meter by Util. Co.)	1 ea	289.66 /ea	290
CT meter enclosure for switchboard	1 ea	1,462.26 /ea	1,462
<b>Medium Voltage Electrical Distribution</b>	<b>136,600 sf</b>	<b>0.01 /sf</b>	<b>1,752</b>
<b>26.27.00 Low-Voltage Distribution Equipment</b>			
Circuit breaker - 20A/1P (panel)	1 ea	149.86 /ea	150
Switchboard: 3000A bus, 2500A rated MCB (100%), 480/277V, 3PH, 65kAIC	1 ea	45,417.04 /ea	45,417
Externally mounted SPD's	6 ea	3,131.70 /ea	18,790
Panelboard: 100A, 42-circuit	14 ea	2,550.41 /ea	35,706
Panelboard: 225A, 42-circuit	9 ea	3,420.66 /ea	30,786
Panelboard: 225A, 84-circuit	9 ea	4,338.66 /ea	39,048
Panelboard: 400A, 42-circuit	3 ea	5,435.74 /ea	16,307
Panelboard: 400A, 84-circuit	1 ea	10,724.46 /ea	10,724
Distribution panel: 600A	2 ea	9,886.92 /ea	19,774
Distribution panel: 800A	3 ea	12,443.25 /ea	37,330
Transformer: floor/wall - 75kVA, 480V:208V	1 ea	4,384.00 /ea	4,384
K-13 Transformer: floor - 225kVA, 480V:208V	3 ea	12,168.50 /ea	36,506
Engineered Services - Training (Manufacturer)	1 ea	4,165.70 /ea	4,166
Engineered Services - Start-Up Assistance (Manufacturer)	1 ea	3,519.08 /ea	3,519
<b>Low-Voltage Distribution Equipment</b>	<b>136,600 sf</b>	<b>2.22 /sf</b>	<b>302,606</b>
<b>26.27.05 Low-Voltage Distribution Feeders</b>			
Feeder (EMT/CU) - 20A [BMS to utility meter]	200 lf	7.43 /lf	1,486
Feeder (EMT/CU) - 20A [EP1A to Elevator Controller]	125 lf	7.43 /lf	929
Feeder (EMT/CU) - 60A [MSB to SPD]	50 lf	14.69 /lf	735



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>26.27.05 Low-Voltage Distribution Feeders</b>			
Feeder (EMT/CU) - 60A [2DP1A to SPD]	50 lf	14.69 /lf	735
Feeder (EMT/CU) - 60A [2DP1B to SPD]	50 lf	14.69 /lf	735
Feeder (EMT/CU) - 60A [2DP1C to SPD]	50 lf	14.69 /lf	735
Feeder (EMT/CU) - 60A [4DP1B to SPD]	50 lf	14.69 /lf	735
Feeder (EMT/CU) - 90A [2DP1A to KPP1A]	42 lf	15.96 /lf	670
Feeder (EMT/CU) - 100A [MSB to LP1A]	40 lf	20.74 /lf	830
Feeder (EMT/CU) - 100A [4DP1B to LP1B]	50 lf	20.74 /lf	1,037
Feeder (EMT/CU) - 100A [4DP1C to LP1C]	27 lf	20.74 /lf	560
Feeder (EMT/CU) - 100A [4DP1B to LP2B]	50 lf	20.74 /lf	1,037
Feeder (EMT/CU) - 100A [2DP1A to LP2C]	190 lf	20.74 /lf	3,940
Feeder (EMT/CU) - 100A [4DP1B to LP3B]	150 lf	20.74 /lf	3,111
Feeder (EMT/CU) - 100A [4DP1C to LP3C]	165 lf	20.74 /lf	3,422
Feeder (EMT/CU) - 100A [MSB to LP1D]	150 lf	20.74 /lf	3,111
Feeder (EMT/CU) - 100A [EHP1A to Elevator Controller]	125 lf	20.74 /lf	2,592
Feeder (EMT/CU) - 100A [TEP1A to TEP2B]	200 lf	20.74 /lf	4,148
Feeder (EMT/CU) - 100A [TEP1A to TEP2C]	200 lf	20.74 /lf	4,148
Feeder (EMT/CU) - 100A [TEP1A to TEP1D]	200 lf	20.74 /lf	4,148
Feeder (EMT/CU) - 100A [TEP1A to UPS]	50 lf	20.74 /lf	1,037
Feeder (EMT/CU) - 100A [2DP1A to MP1A]	410 lf	20.74 /lf	8,503
Feeder (EMT/CU) - 125A [UPS to EP1A]	150 lf	20.99 /lf	3,149
Feeder (EMT/CU) - 150A [2DP1B to MP1B]	50 lf	26.82 /lf	1,341
Feeder (EMT/CU) - 150A [2DP1C to MSB]	200 lf	26.82 /lf	5,365
Feeder (EMT/CU) - 150A [2DP1C to MP3C]	250 lf	26.82 /lf	6,706
Feeder (EMT/CU) - 150A [2DP1B to PP2B]	60 lf	26.82 /lf	1,609
Feeder (EMT/CU) - 150A [2DP1C to PP2C]	100 lf	26.82 /lf	2,682
Feeder (EMT/CU) - 150A [2DP1B to PP1B]	50 lf	26.82 /lf	1,341
Feeder (EMT/CU) - 150A [2DP1C to MP1C]	40 lf	26.83 /lf	1,073
Feeder (EMT/CU) - 150A [2DP1C to PP2C]	125 lf	26.82 /lf	3,353
Feeder (EMT/CU) - 150A [2DP1C to PP3C]	150 lf	26.82 /lf	4,024
Feeder (EMT/CU) - 150A [4DP1C to PP3B]	165 lf	26.82 /lf	4,426
Feeder (EMT/CU) - 150A [2DP1C to PP1C]	50 lf	26.82 /lf	1,341
Feeder (EMT/CU) - 150A [2DP1A to PP1D]	100 lf	26.82 /lf	2,682
Feeder (EMT/CU) - 200A [MSB to ATS-LS]	100 lf	32.13 /lf	3,213
Feeder (EMT/CU) - 200A [ATS-LS to ELP1A]	40 lf	32.13 /lf	1,285
Feeder (EMT/CU) - 200A [2DP1A to PP1A]	50 lf	32.13 /lf	1,607
Feeder (EMT/CU) - 200A [Cam Lock Box to ATS-LS]	60 lf	32.13 /lf	1,928
Feeder (EMT/CU) - 225A [MSB to Dimming Rack HDP]	250 lf	46.72 /lf	11,679
Feeder (EMT/CU) - 225A [2DP1A to Dimming Rack SDP]	200 lf	46.72 /lf	9,344
Feeder (EMT/CU) - 225A [EHP1A to EHP3C]	250 lf	46.72 /lf	11,679
Feeder (EMT/CU) - 225A [MP3C to PP3C]	45 lf	46.72 /lf	2,102



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>26.27.05 Low-Voltage Distribution Feeders</b>			
Feeder (EMT/CU) - 225A [2DP1B to MP3B]	100 lf	46.72 /lf	4,672
Feeder (EMT/CU) - 225A [4DP1C to MHP3C]	165 lf	49.70 /lf	8,200
Feeder (EMT/CU) - 225A [ATS-OS to EHP1A]	200 lf	49.70 /lf	9,940
Feeder (EMT/CU) - 225A [MSB to ATS-OS]	75 lf	49.70 /lf	3,727
Feeder (EMT/CU) - 400A [MSB to MHP1A]	50 lf	73.75 /lf	3,688
Feeder (EMT/CU) - 400A [EHP1C to EHP1A]	100 lf	73.75 /lf	7,375
Feeder (EMT/CU) - 400A [Generator to ATS-LR] (interior)	430 lf	73.75 /lf	31,713
Feeder (EMT/CU) - 400A [MSB to ATS-LR]	375 lf	78.46 /lf	29,422
Feeder (EMT/CU) - 400A [MHP-LR to ATS-LR]	10 lf	78.46 /lf	785
Feeder (EMT/CU) - 400A [ATS-LR to MHP-LR]	50 lf	73.75 /lf	3,688
Feeder (EMT/CU) - 600A [MSB to 4DP1B]	200 lf	108.91 /lf	21,782
Feeder (EMT/CU) - 600A [MSB to 2DP1A]	70 lf	108.91 /lf	7,624
Feeder (EMT/CU) - 800A [MSB to 2DP1C]	125 lf	138.78 /lf	17,348
Feeder (EMT/CU) - 800A [MSB to 4DP1C]	200 lf	138.78 /lf	27,757
Empty conduit (EMT) - 3/4" [utility meter to switchboard]	75 lf	6.28 /lf	471
Feeder (MC) - 125A [75kVA]	30 lf	12.82 /lf	385
Feeder (MC) - 225A [75kVA]	30 lf	35.43 /lf	1,063
Feeder (MC) - 400A [225kVA]	90 lf	59.32 /lf	5,339
Feeder (MC) - 800A [225kVA]	90 lf	111.65 /lf	10,048
M.I. Cable - 4-1/c #6 [ELP1B to ELP3B]	150 lf	36.15 /lf	5,422
M.I. Cable - 4-1/c #3 [EHP1A to EP3C]	165 lf	65.42 /lf	10,794
M.I. Cable - 4-1/c #3 [ELP1A to EDP]	125 lf	65.42 /lf	8,178
M.I. Cable - 4-1/c #3 [ELP1A to EP1C]	125 lf	65.42 /lf	8,178
M.I. Cable - 4-1/c #2 [EPL1A to ELP1B]	150 lf	72.60 /lf	10,890
M.I. Cable - 4-1/c #2 [ELP1A to ELP1D]	417 lf	77.24 /lf	32,208
Quick term kit - #6 4-1/c	2 ea	359.96 /ea	720
Quick term kit - #3 4-1/c	6 ea	710.21 /ea	4,261
Quick term kit - #2 4-1/c	4 ea	734.64 /ea	2,939
Brass plate (per hole)	12 ea	92.10 /ea	1,105
<b>Low-Voltage Distribution Feeders</b>	<b>136,600 sf</b>	<b>3.00 /sf</b>	<b>410,031</b>
<b>26.27.26 Wiring Devices</b>			
MC Cable (12/2) - 20A	11,370 lf	3.45 /lf	39,227
MC Cable (10/2) - 20A [homeruns - x372]	24,180 lf	4.36 /lf	105,516
EMT (12/2) - 20A	2,000 lf	6.70 /lf	13,404
PVC (10/2) - 20A	450 lf	6.68 /lf	3,007
Duplex receptacle - 20A - tamper resistant	497 ea	78.60 /ea	39,065
Duplex receptacle - 20A - switched with IO module	14 ea	67.78 /ea	949
Simplex receptacle - 20A [scoreboard control]	2 ea	70.18 /ea	140
Duplex receptacle - 20A - GFCI	187 ea	92.44 /ea	17,286



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>26.27.26 Wiring Devices</b>			
Duplex receptacle - 20A - GFCI - W.P.	29 ea	129.27 /ea	3,749
Duplex receptacle - 20A [kitchen equipment] - circuitry in Equipment Wiring]	33 ea	67.79 /ea	2,237
Duplex receptacle - 20A [A/V]	9 ea	67.79 /ea	610
Duplex receptacle - 20A [CR]	8 ea	67.80 /ea	542
Exterior pedestal receptacle, GFI type, Wayne Tyler, Inc. #CB-BOX	5 ea	1,292.26 /ea	6,461
Quadruplex receptacle - 20A	325 ea	93.78 /ea	30,479
Quadruplex receptacle - 20A - switched with IO module	18 ea	93.79 /ea	1,688
Duplex receptacle - 20A - USB	14 ea	99.44 /ea	1,392
Specialty receptacle - 20A - L5-20R	11 ea	101.01 /ea	1,111
Specialty receptacle - 20A - L14-20R	1 ea	104.81 /ea	105
Specialty receptacle - 30A - L5-30R	23 ea	111.69 /ea	2,569
Quadruplex receptacle - 20A - GFCI	5 ea	143.12 /ea	716
Hardwired A/C junction (MC) - 20A [A/V]	2 ea	318.93 /ea	638
Hardwired A/C junction (MC) - 20A [fume hoods]	4 ea	318.93 /ea	1,276
Power junction w/feed (MC) - 20A [water coolers/bottle fillers]	11 ea	221.21 /ea	2,433
Power junction w/feed (MC) - 20A	28 ea	221.21 /ea	6,194
Trash compactor feed & connection	2 ea	2,243.92 /ea	4,488
Overhead door power & connection	3 ea	1,223.50 /ea	3,671
Dock leveler feed & connection	1 ea	3,532.90 /ea	3,533
Emergency power offs (EPO)	10 ea	295.11 /ea	2,951
Wiremold receptacles - G4	110 ea	31.05 /ea	3,416
G4000 dual-channel wiremold - 24" spacing	220 lf	63.39 /lf	13,945
<b>Wiring Devices</b>	<b>136,600 sf</b>	<b>2.29 /sf</b>	<b>312,797</b>
<b>26.31.00 Provisions for Future Photovoltaic</b>			
Empty conduit - sch 40 PVC: 1 x 2" [future Canopy PV]	280 lf	26.88 /lf	7,526
Empty conduit - sch 40 PVC: 2 x 2" [future PV]	1,250 lf	35.04 /lf	43,800
Empty conduit - sch 40 PVC: 2 x 4" [future Canopy PV]	160 lf	45.14 /lf	7,222
<b>Provisions for Future Photovoltaic</b>	<b>136,600 sf</b>	<b>0.43 /sf</b>	<b>58,549</b>
<b>26.32.00 Packaged Generator Assemblies</b>			
Natural gas generator: 350kW / 437.5kVA	1 ea	133,322.25 /ea	133,322
Generator testing & start-up	1 ea	1,863.20 /ea	1,863
Generator annunciator panel	1 ea	1,447.40 /ea	1,447
Battery charger circuit (4#10 & 1#10G in 1"C)	140 lf	20.94 /lf	2,932
Jacket heater circuit	140 lf	34.49 /lf	4,828
Oil heater circuit	140 lf	53.66 /lf	7,512
Exterior W.P. sound attenuating enclosure (350kW)	1 ea	19,478.75 /ea	19,479
Remote status panel circuit	140 lf	9.64 /lf	1,349



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>26.32.00 Packaged Generator Assemblies</b>			
Starting circuits - 2#14 MI cable	140 lf	12.76 /lf	1,787
Remote annunciator panel - 16#14 (EMT)	100 lf	15.81 /lf	1,581
Quick connect switch, ESL Storm Switch 3020	1 ea	3,668.10 /ea	3,668
<b>Packaged Generator Assemblies</b>	<b>136,600 sf</b>	<b>1.32 /sf</b>	<b>179,769</b>
<b>26.33.00 Battery Equipment</b>			
UPS: 480-208/120V, 24kW (static ts,manual by-pass, 8min batt.BU)	2 ea	30,061.40 /ea	60,123
<b>Battery Equipment</b>	<b>136,600 sf</b>	<b>0.44 /sf</b>	<b>60,123</b>
<b>26.36.00 Transfer Switches</b>			
ATS-OS: 225A, 277/480V, 4P, no iso by-pass - open transition	1 ea	6,752.90 /ea	6,753
ATS-LS: 150A, 277/480V, 4P, w/ iso by-pass - open transition	1 ea	11,058.30 /ea	11,058
ATS-LR: 400A, 277/480V, 4P, w/ iso by-pass - open transition	1 ea	19,961.43 /ea	19,961
<b>Transfer Switches</b>	<b>136,600 sf</b>	<b>0.28 /sf</b>	<b>37,773</b>
<b>26.40.00 Electrical &amp; Cathodic Protection</b>			
Lightning prevention system subcontractor	1 ls	30,000.00 /ls	30,000
<b>Electrical &amp; Cathodic Protection</b>	<b>136,600 sf</b>	<b>0.22 /sf</b>	<b>30,000</b>
<b>26.50.00 Lighting</b>			
Reduce lighting by \$1.50/sf - VM E01	(136,600) sf	1.50 /sf	(204,900)
LK24: 2'x2' lay-in fixture [O]	24 ea	198.57 /ea	4,766
SPFL: LED flood light [C]	20 ea	682.90 /ea	13,658
SPNF: LED flood light, narrow [C]	20 ea	682.90 /ea	13,658
LR2 (emerg): 2' linear 2" aperature recessed luminaire [O]	183 ea	300.48 /ea	54,987
LR2: 2' linear 2" aperature recessed luminaire [O]	912 ea	300.48 /ea	274,033
G4: 4' linear rugged low profile 360 deg adjustable flood luminaire [O]	80 ea	1,160.93 /ea	92,874
LS4: 4' utility fixtre with frosted acrylic diffuser [O]	20 ea	246.16 /ea	4,923
LS4 (emerg): 4' utility fixture with frosted acrylic diffuser [O]	14 ea	246.16 /ea	3,446
LS8: 8' utility fixtre with frosted acrylic diffuser [O]	11 ea	411.94 /ea	4,531
LS4A (emerg): 4' utility fixtre with frosted acrylic diffuser [O]	12 ea	494.94 /ea	5,939
LS4A: 4' utility fixture with frosted acrylic diffuser [O]	12 ea	494.94 /ea	5,939
LP8 (emerg): Axis 8' LED fixture [O]	9 ea	1,027.94 /ea	9,251
LS8 (emerg): 8' utility fixture with frosted acrylic diffuser [O]	10 ea	411.94 /ea	4,119
JB: utility fixture with frosted tempered glass globe & guard [O]	4 ea	245.95 /ea	984
PC3: 6" down light fixture with dead-front gasketed trim [O]	1 ea	298.16 /ea	298
LRW (emerg): 6" aperature LED linear recessed fixture / qty. of 18 [C]	114 lf	146.99 /lf	16,757
PC1: 4" down light fixture, 0-10V dimming capable [O]	24 ea	298.16 /ea	7,156
RC1: 6" down light fixture [O]	45 ea	271.54 /ea	12,219
RC1 (emerg): 6" down light fixture [O]	18 ea	271.54 /ea	4,888





# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>26.50.00 Lighting</b>			
LS2 (emerg): 2' utility fixture [O]	2 ea	177.98 /ea	356
LSV4: 4' linear utility fixture with prismatic polcarbonate lens [C]	4 ea	675.93 /ea	2,704
RC2: 4" down light fixture, 0-10V dimming [O]	8 ea	230.56 /ea	1,844
LR4: 4' linear 2" aperature recessed luminaire with frosted lens [O]	1 ea	410.45 /ea	410
LUL: LED tape light with AL channel [C]	1,840 lf	88.49 /lf	162,829
LC3: linear cove Xeleum lighting / qty. of 96 [O]	1,925 lf	121.99 /lf	234,826
LWW: LED tape light with AL channel [C]	1,408 lf	88.49 /lf	124,599
RSH: 6" down light fixture with dead-front gasketed trim [O]	1 ea	306.54 /ea	307
LC2: linear cove fixture with frosted diffuser / qty. of 10 [O]	76 lf	148.23 /lf	11,265
PC2: 6" down light fixture with dead-front gasketed trim [O]	28 ea	298.16 /ea	8,348
LCL: LED tape light with AL channel [C]	3,051 lf	88.49 /lf	269,994
LSL: LED strip mounted on edge of stage / qty. of 1	59 lf	305.95 /lf	18,051
Exit sign, ceiling mounted, double sided [O]	34 ea	196.16 /ea	6,669
Exit sign, ceiling mounted, single sided [O]	16 ea	183.16 /ea	2,931
Exit sign, wall mounted	18 ea	313.16 /ea	5,637
Exit sign, ceiling mounted, single sided - handicap [O]	2 ea	433.16 /ea	866
LRC (emerg): 6" aperature LED linear recessed fixture / qty. of 46 [C]	596 lf	161.70 /lf	96,373
Revised lighting package from Omni-Lite	(1) ls	271,965.00 /ls	(271,965)
MC Cable (12/2) - 20A (concealed branch)	12,068 lf	3.67 /lf	44,291
MC Cable (10/2) - 20A (concealed homeruns)	2,400 lf	4.64 /lf	11,142
EMT (12/2) - 20A (exposed branch)	4,023 lf	7.13 /lf	28,679
EMT (10/2) - 20A (exposed homeruns)	500 lf	8.58 /lf	4,290
<b>Lighting</b>	<b>136,600 sf</b>	<b>8.01 /sf</b>	<b>1,093,973</b>
<b>26.56.00 Exterior Lighting</b>			
SL4: LED egress / perimeter lighting fixture - custom color/finish [O]	20 ea	565.36 /ea	11,307
SL5: exterior ampitheater RGB projector, DMX capable, IP65 rated [O]	8 ea	3,626.85 /ea	29,015
SLS: LED recessed step light, 0-10V dimming capable [C]	7 ea	732.90 /ea	5,130
SL1: LED pole mounted luminaires mounted on a 20' pole [O]	35 ea	2,891.40 /ea	101,199
SL2A: exterior post top fixture with 15' round tapered alum pole [O]	13 ea	5,492.50 /ea	71,403
SL3: exterior bollard 43.3 cast illuminum [O]	9 ea	1,929.78 /ea	17,368
SL10: LED mini in-ground flood fixture capable of 0-10V dimming [O]	12 ea	978.60 /ea	11,743
MC Cable (12/2) - 20A	1,200 lf	3.67 /lf	4,404
EMT (12/2) - 20A	1,400 lf	7.13 /lf	9,981
1" PVC - 30A (3#8 & #10G)	6,900 lf	10.95 /lf	75,528
1" GRC - 90 Deg Sweep	114 ea	174.22 /ea	19,861
<b>Exterior Lighting</b>	<b>136,600 sf</b>	<b>2.61 /sf</b>	<b>356,940</b>
<b>27.00.01 Data/Voice/Audio-Video Communications</b>			
Tel/data J-hook system (plenum)	136,600 sf	0.19 /sf	25,681



90% CD Reconciled Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>27.00.01 Data/Voice/Audio-Video Communications</b>			
Cable tray - 18"W (IDF/MDF only)	200 lf	75.55 /lf	15,109
Empty conduit (PVC) - 1"	250 lf	8.07 /lf	2,016
Empty conduit (EMT) - 2"	650 lf	11.19 /lf	7,271
Empty conduit (PVC) - 2"	700 lf	6.03 /lf	4,223
Empty conduit (sch 40 PVC) (4) 4"C (CATV, Telephone, Fiber, Spare)	220 lf	32.32 /lf	7,110
Three (3) 1.25" inner ducts for fiber	220 lf	15.50 /lf	3,411
Communications utility pole conduit riser (GRC - 4"C)	4 ea	2,343.84 /ea	9,375
Copper ground bar w/isolators - 2"x1/4"	4 ea	280.03 /ea	1,120
Conduit sleeve w/ fireproofing - 4"	20 ea	201.11 /ea	4,022
Data outlet - (1) CAT-6A cable	20 ea	264.84 /ea	5,297
Data outlet - (1) CAT-6A cable [audio-visual]	12 ea	264.84 /ea	3,178
Data outlet - (2) CAT-6A cables	131 ea	466.16 /ea	61,067
Tel/data outlet - (3) CAT-6A cables	91 ea	652.82 /ea	59,407
Floor box tel/data outlet - (3) CAT-6A cables	2 ea	652.83 /ea	1,306
Voice outlet - (1) CAT-6A cable (WAP's by Owner)	79 ea	263.70 /ea	20,832
Wireless access point - (1) CAT-6A cable (WAP's by Owner)	138 ea	263.70 /ea	36,390
TVE - Video outlet	56 ea	838.75 /ea	46,970
TVC - Video outlet	2 ea	838.77 /ea	1,678
Double gang junction box with (4) 1" C	54 ea	482.68 /ea	26,065
FO - 12 strand SM	1,750 lf	5.27 /lf	9,225
FO - 12 strand MM	1,500 lf	7.10 /lf	10,642
4-Post Full Height Rack	10 ea	1,170.17 /ea	11,702
Vertical cable wire manager	20 ea	314.09 /ea	6,282
Horizontal cable wire manager	10 ea	80.25 /ea	803
Copper patch panel - 96 port	15 ea	1,244.28 /ea	18,664
Fiber optic patch panel - 24 port	6 ea	570.06 /ea	3,420
Fiber enclosure (rack mtd.)	6 ea	485.85 /ea	2,915
Network switch - 24 port	2 ea	5,390.24 /ea	10,780
Telecom manhole & cover - 4'x6'x7'	1 ea	3,920.36 /ea	3,920
<b>Data/Voice/Audio-Video Communications</b>	<b>136,600 sf</b>	<b>3.07 /sf</b>	<b>419,882</b>

**27.40.00 Audio-Video Communications**

S1: wall mounted loudspeaker - 1 gang metal box w/ cover	2 ea	228.33 /ea	457
S2: ceiling loud speaker - custom backbox	6 ea	308.23 /ea	1,849
S3: ceiling loud speaker - 4" SQ metal box w/ cover	16 ea	179.94 /ea	2,879
S4: ceiling loud speaker - 4" SQ metal box w/ cover	2 ea	251.94 /ea	504
S5: ceiling loud speaker - 4" SQ metal box w/ cover (New)	2 ea	245.27 /ea	491
D1: display back box, Chief PAC-526	3 ea	371.35 /ea	1,114
F1: floor box, FSR FL-500P-6 floor box w/ finished cover	1 ea	469.58 /ea	470
V1: wall mounted video projector - 1 gang metal box w/ cover	1 ea	179.47 /ea	179



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>27.40.00 Audio-Video Communications</b>			
R1: receptacle panel - 2 gang metal box w/ cover	3 ea	242.43 /ea	727
R2: receptacle panel - 12"x12"x4" NEMA-1 enclosure w/ oversized flush	2 ea	242.43 /ea	485
R3: receptacle panel - 3 gang metal box w/ cover	4 ea	311.69 /ea	1,247
R5: receptacle panel - 3 gang metal box w/ cover	1 ea	242.43 /ea	242
R6: receptacle panel - 12"x12"x4" NEMA-1 enclosure w/ oversized flush	2 ea	405.94 /ea	812
BP: wall mounted button panel - 1 gang metal box w/ cover	3 ea	221.77 /ea	665
J1: junction box - type 1 - 12"x12"x4" NEMA-1 enclosure w/ oversized flush	2 ea	723.57 /ea	1,447
J2: junction box - type 2 - 18"x18"x4" NEMA-1 enclosure w/ oversized flush	1 ea	844.78 /ea	845
J3: junction box - type 3 - same as Type 2	3 ea	844.78 /ea	2,534
A1: Wall mounted antenna - 1 gang deep metal box w/ cover	2 ea	159.74 /ea	319
A2: Wall mounted antenna - 1 gang deep metal box w/ cover	1 ea	159.74 /ea	160
A3: Ceiling mounted antenna - 4" SQ metal box w/ cover	2 ea	138.32 /ea	277
A4: Ceiling mounted antenna - 4" SQ metal box w/ cover	1 ea	138.31 /ea	138
PS: Production communication speaker station - 4 gang deep metal box w/ cov	5 ea	385.28 /ea	1,926
PC: Production communication - 1 gang deep metal box w/ cover	1 ea	134.38 /ea	134
T1: Wall mounted touch panel - 3 gang metal box w/ cover	2 ea	249.04 /ea	498
VC: Wall mounted audio volume control - 1 gang deep metal box	2 ea	134.39 /ea	269
MC: Motor controller - 4" SQ metal box w/ cover	3 ea	86.46 /ea	259
C1: Wall mounted camera - 2 gang deep metal box w/ cover	1 ea	193.57 /ea	194
A/V Equipment Rack	2 ea	1,001.85 /ea	2,004
M1: Ceiling mounted microphone - 1 gang deep metal box w/ cover	1 ea	134.38 /ea	134
<b>Audio-Video Communications</b>	<b>136,600 sf</b>	<b>0.17 /sf</b>	<b>23,260</b>
<b>27.50.00 Distributed Communications &amp; Monitoring Systems</b>			
Intercom sub-stations	6 ea	1,009.28 /ea	6,056
Intercom master-stations	5 ea	3,327.13 /ea	16,636
<b>Distributed Communications &amp; Monitoring Systems</b>	<b>136,600 sf</b>	<b>0.17 /sf</b>	<b>22,691</b>
<b>27.51.19 Ceiling Speaker System</b>			
Speaker - ceiling mouted	269 ea	405.93 /ea	109,194
Speaker - wall mounted	32 ea	611.85 /ea	19,579
Volume control	24 ea	177.96 /ea	4,271
Power supply (80) units - speakers 24V DC	4 ea	2,661.71 /ea	10,647
PA console	1 ea	14,251.90 /ea	14,252
PA equipment power connection - 120V	1 ea	256.53 /ea	257



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>27.51.19 Ceiling Speaker System</b>			
AM/FM/CD/DVD tuner	1 ea	694.40 /ea	694
Speaker system testing	1 ea	1,986.71 /ea	1,987
<b>Ceiling Speaker System</b>	<b>136,600 sf</b>	<b>1.18 /sf</b>	<b>160,880</b>
<b>27.51.29 Emergency Communications Systems</b>			
Two way communication call box (recessed)	20 ea	799.75 /ea	15,995
Power supply w/battery back up	1 ea	1,714.28 /ea	1,714
Two way communication base station (28 zone)	1 ea	5,980.66 /ea	5,981
Power junction w/feed (EMT) - 20A	1 ea	337.91 /ea	338
Tel/data outlet - (1) CAT-6A cable	20 ea	264.84 /ea	5,297
Tel/data outlet - (2) CAT-6A cables	1 ea	466.16 /ea	466
Empty conduit (EMT) - 3/4"	2,000 lf	5.11 /lf	10,218
System testing	1 ea	1,016.70 /ea	1,017
<b>Emergency Communications Systems</b>	<b>136,600 sf</b>	<b>0.30 /sf</b>	<b>41,026</b>
<b>27.53.00 Clock System</b>			
Clock, wall mounted - 12" round	126 ea	283.06 /ea	35,665
Master clock w/ roof mounted antenna	1 ea	3,778.57 /ea	3,779
Wireless clock repeater	1 ea	647.06 /ea	647
Wireless clock transceiver	1 ea	647.06 /ea	647
Program unit	1 ea	991.96 /ea	992
Speaker baffle, clock back box	74 ea	202.78 /ea	15,006
Wire guard	20 ea	57.70 /ea	1,154
Clock wiring (EMT)	700 lf	7.03 /lf	4,923
Clock wiring (RS-485 plenum)	500 lf	3.08 /lf	1,540
System testing	1 ls	33.83 /ls	34
<b>Clock System</b>	<b>136,600 sf</b>	<b>0.47 /sf</b>	<b>64,387</b>
<b>28.10.00 Electronic Access Control &amp; Intrusion Detection</b>			
Card readers	22 ea	1,163.83 /ea	25,604
Card readers - W.P.	3 ea	1,967.78 /ea	5,903
Electro-magnetic lock	6 ea	657.91 /ea	3,947
Request to exit motion sensor	26 ea	322.33 /ea	8,380
Electric strike	40 ea	400.49 /ea	16,020
Thermal disconnecting means	20 ea	427.58 /ea	8,552
24V power supply	20 ea	295.11 /ea	5,902
Junction box - 6"x6"x4"	20 ea	130.61 /ea	2,612
Power transfer hinge	20 ea	377.68 /ea	7,554
Intrusion digital keypads	4 ea	984.97 /ea	3,940
Dual tech motion detectors	77 ea	595.80 /ea	45,876



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>28.10.00 Electronic Access Control &amp; Intrusion Detection</b>			
Door contacts	63 ea	465.74 /ea	29,342
Access control panel	1 ea	8,222.56 /ea	8,223
Tie in to lighting control system	1 ea	402.23 /ea	402
Security wiring - cable	7,500 lf	3.80 /lf	28,527
Security wiring (EMT)	2,250 lf	8.53 /lf	19,181
Power junctions - 120V/20A	2 ea	193.20 /ea	386
Connect to CCTV system	1 ea	665.43 /ea	665
Proximity cards	250 ea	2.35 /ea	588
Software / licenses, programming, testing, startup (manufacturer)	1 ea	13,308.52 /ea	13,309
<b>Electronic Access Control &amp; Intrusion Detection</b>	<b>136,600 sf</b>	<b>1.72 /sf</b>	<b>234,913</b>
<b>28.20.00 Video Surveillance</b>			
CCTV color monitors	2 ea	815.52 /ea	1,631
360-degree multi-sensor interior cameras	28 ea	1,659.85 /ea	46,476
Dome I.P. camera - exterior	19 ea	1,996.28 /ea	37,929
Dome I.P. camera - interior - fixed	27 ea	1,471.85 /ea	39,740
360-degree multi-sensor exterior cameras mounted on poles	3 ea	4,509.56 /ea	13,529
Camera monitoring station	1 ea	1,330.85 /ea	1,331
Video recorders	2 ea	3,131.71 /ea	6,263
Video switchers	2 ea	1,627.71 /ea	3,255
Camera wiring (EMT)	2,500 lf	8.76 /lf	21,899
Camera wiring (PVC)	600 lf	13.34 /lf	8,003
Camera wiring - cable	7,400 lf	4.04 /lf	29,885
Power junction - 120V/20A	2 ea	193.20 /ea	386
Software / licenses, programming, testing, startup (manufacturer)	1 ea	13,308.52 /ea	13,309
<b>Video Surveillance</b>	<b>136,600 sf</b>	<b>1.64 /sf</b>	<b>223,638</b>
<b>28.46.00 Temporary Fire Alarm</b>			
<i>Temporary fire alarm heat detection coverage / stairwell pull stations / temp notification - N/A</i>	-	-	
Fire alarm impairment plan (NFPA-101)	1 ls	10,000.00 /ls	10,000
<b>Temporary Fire Alarm</b>	<b>136,600 sf</b>	<b>0.07 /sf</b>	<b>10,000</b>
<b>28.46.20 Fire Detection and Alarm</b>			
Elevator fire alarm interfacing	1 ls	5,000.00 /ls	5,000
Manual pull stations	25 ea	202.12 /ea	5,053
Mass notification	1 ls	49,999.98 /ls	50,000
Smoke detectors	82 ea	220.39 /ea	18,072
Smoke detector w/ elevator recall	3 ea	373.26 /ea	1,120
Smoke detectors (for Atrium)	89 ea	220.39 /ea	19,615



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>28.46.20 Fire Detection and Alarm</b>			
Smoke detectors w/ elevator recall (for Atrium)	3 ea	373.25 /ea	1,120
Carbon monoxide detector (w/ monitor module)	5 ea	367.16 /ea	1,836
Beam detector (receiver & transmitter)	5 ea	416.88 /ea	2,084
Duct smoke detector (furnish & wire)	40 ea	838.91 /ea	33,556
Remote test switch w/ indicating light	40 ea	194.88 /ea	7,795
Control modules	20 ea	265.75 /ea	5,315
Addressable monitor modules	30 ea	160.83 /ea	4,825
Tamper switch connection (via monitor module)	8 ea	560.06 /ea	4,480
Flow switch connection (via monitor module)	8 ea	403.67 /ea	3,229
Door hold device (magnetic)	5 ea	388.88 /ea	1,944
Wire motorized dampers (120V)	14 ea	407.48 /ea	5,705
Wire combination fire/smoke damper (120V & SLC)	20 ea	608.50 /ea	12,170
Strobe only	48 ea	175.36 /ea	8,417
Speaker/strobes	150 ea	246.56 /ea	36,983
Speaker/strobe - W.P.	1 ea	309.72 /ea	310
Horn/visual - wall mounted	52 ea	222.79 /ea	11,585
Exterior beacons (weatherproof)	4 ea	388.83 /ea	1,555
Fire alarm transponder panels	6 ea	928.51 /ea	5,571
Fire alarm annunciators w/ microphones	3 ea	2,107.39 /ea	6,322
FACP w/ 60-minute battery backup (Notifier NFS640)	1 ea	6,999.66 /ea	7,000
Masterbox (local energy)	1 ea	4,212.70 /ea	4,213
Key (Knox) box	2 ea	806.43 /ea	1,613
Smoke control panel	1 ea	19,502.56 /ea	19,503
Generator monitoring control panel	1 ea	571.80 /ea	572
Fire pump/jockey pump connection	1 ea	402.23 /ea	402
Fire alarm graphic maps	3 ea	1,454.56 /ea	4,364
Fire alarm comissioning	1 ea	6,158.00 /ea	6,158
Fire alarm testing (manufacturer)	6 ea	1,338.28 /ea	8,030
Fire alarm system programming	397 ea	20.79 /ea	8,254
FPLP cable (red) - #14-4/c	11,475 lf	2.23 /lf	25,589
FPLP cable (red) - #16-2/c	12,330 lf	1.83 /lf	22,564
EMT (red) - 3/4"C w/ #16-2/c (exposed)	2,500 lf	7.19 /lf	17,981
EMT (red) - 3/4"C w/ #14-4/c (exposed)	1,200 lf	7.95 /lf	9,535
Circuit integrity cabling (CIC)	1,500 lf	18.31 /lf	27,465
Ductbank w/ IMSA cable - 2" PVC	320 lf	16.30 /lf	5,217
<b>Fire Detection and Alarm</b>	<b>136,600 sf</b>	<b>3.09 /sf</b>	<b>422,120</b>
<b>28.46.24 Distributed Antenna System (DAS)</b>			
BDA system - parts & smarts (dual-frequency)	136,600 sf	0.47 /sf	64,202
BDA system - installation & minor material (dual-frequency)	136,600 sf	0.19 /sf	25,681



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>28.46.24 Distributed Antenna System (DAS)</b>			
Directional couplers	20 ea	1,150.35 /ea	23,007
In-Line connectors	20 ea	249.01 /ea	4,980
Lightning protection units	5 ea	1,995.53 /ea	9,978
<b>Distributed Antenna System (DAS)</b>	<b>136,600 sf</b>	<b>0.94 /sf</b>	<b>127,848</b>
<b>26-01 ELECTRICAL (TS)</b>	<b>136,600 sf</b>	<b>42.27 /sf</b>	<b>5,773,794</b>
<b>31-23 SITEWORK</b>			
<b>02.41.13 Demolition - Site</b>			
<i>Demo hydrants</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo bituminous concrete paving</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo bituminous walk</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo Temporary Bituminous Parking &amp; Access Pavement</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo concrete sidewalks/pads/ramps</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo curbing</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Cut &amp; cap site utilities - water</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Cut &amp; cap site utilities - sewer</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo utility piping - water</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo utility piping - sewer</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo utility piping - electrical</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo utility piping - drain</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo utility piping - gas</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo drain structures</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo grease trap</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo fencing/guardrail</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Misc. site demolition</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Demo utility poles</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Demolition - Site</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>31.00.05 General Requirements</b>			
<i>Mobilizations</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Survey/layout</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Preconstruction survey and vibration monitoring &amp; compliance</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Street plates for protection</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Police details</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Precast Concrete Jersey Barriers for Temp. Parking Lot</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Temporary site signage</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>As-built plan preparation</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Localized dewatering</i>	<i>BP#1</i>	<i>/BP#1</i>	



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>General Requirements</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>31.10.00 Site Clearing</b>			
<i>Clear &amp; grub, vegetation removal</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Strip &amp; stockpile topsoil/loam</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Site Clearing</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>31.22.00 Grading</b>			
<i>Rough grading</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Fine grading - building SOG</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Fine grading - paving</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Fine grading - conc walks &amp; site pads</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Fine grading - bituminous walks</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Grading</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>31.23.00 Excavation &amp; Fill - Overall Site</b>			
<i>Cut to subgrade @ site</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Fill to subgrade from cut @ site</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Grind foundations for fill - In Demolition</i>	-	/-	
<i>Fill to subgrade @ site - import</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Site cuts to stockpile for temporary parking &amp; access layout</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Site surcharge</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Site cuts to site fills</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Excavation @ foundations</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Fill to subgrade @ building footprint - import (structural fill)</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Contaminated soil removal - unlined landfill</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Crushed stone base beneath S.O.G</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Crushed stone base beneath column &amp; wall footings</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Excavation &amp; Fill - Overall Site</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>31.23.01 Excavation &amp; Fill - Foundations</b>			
<i>Excavate for elevator pits</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Fine grade under building</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Excavation &amp; Fill - Foundations</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>31.23.02 Excavation &amp; Fill - Utilities</b>			
<i>Excavate/backfill utilities under SOG by machine</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Excavation &amp; Fill - Utilities</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>31.23.16 Rock Removal</b>			
<i>Rock removal - NIC</i>	-	/-	





# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Rock Removal</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>31.23.19 Dewatering</b>			
<i>Dewatering</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Construct Phase 2 Temp. Sediment Basins</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Additional dewatering</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Dewatering</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>31.25.00 Erosion &amp; Sedimentation Control</b>			
<i>SWPPP (Prep of SWPPP by civil engineer)</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>12" diameter Straw Wattles</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Silt sacks at catch basin</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Construction entrance</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Street sweeping</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Inspect / repair silt barrier weekly</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Remove erosion control measure at project completion</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Erosion &amp; Sedimentation Control</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>31.62.00 Ground Improvement</b>			
<i>Site surcharge/rigid inclusion</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Rammed aggregate piers</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Rigid inclusions Gym and Auditorium</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Ground Improvement</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>32.11.00 Base Courses</b>			
<i>Gravel base course @ asphalt pavements</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Gravel base course @ Raised Stamped asphalt pavement at Flagg Drive</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Processed Aggregate base course - bituminous walks</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>1 1/2" crushed stone base course - concrete walks &amp; site pads</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Gravel base course - misc site amenities- (i.e.- curbing, swales,etc.)</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Base Courses</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>32.12.00 Flexible Paving</b>			
<i>Asphalt paving - (Parking Lots &amp; Site Drives)</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Asphalt paving - Temp. Parking Layout</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Temporary roads and maintenance required during construction</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Asphalt paving - top course @ temporary to permanent</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Flexible Paving</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>32.13.00 Rigid Paving</b>			



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>32.13.00 Rigid Paving</b>			
<i>Stamped pavement at Flagg Drive</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Rigid Paving</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>32.16.13 Curbs &amp; Gutters</b>			
<i>Precast concrete curbs</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Vertical granite curbs</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Handicapped ramps at curbing</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Detectable Warning Plates at Handicapped Ramps</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Curbs &amp; Gutters</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>32.16.23 Sidewalks</b>			
<i>Bituminous sidewalks</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Sidewalks</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>32.17.00 Paving Specialties</b>			
<i>Speed bumps - bituminous</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Pavement markings</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Parking signage</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Paving Specialties</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>33.10.00 Water Utilities</b>			
<i>Fire hydrants</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Fire hydrant - relocate existing</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Gate valves, tees, bends, thrust blocks, restraints</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Water distribution connections to existing</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Water line - domestic</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Water line - hydrant &amp; fire services</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Pressure test &amp; chlorinate</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Water Utilities</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>33.30.00 Sanitary Sewerage Utilities</b>			
<i>Sanitary sewer piping</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Sanitary sewer manholes</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Connect to existing structures</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Utility and sewer tie-in at trailer</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Sanitary sewer testing - piping</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Video inspect incoming sewer, etc.</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Sanitary sewer testing - structures</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Sanitary Sewerage Utilities</b>	<b>136,600 sf</b>	<b>/sf</b>	



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>33.36.00 Utility Septic Tanks</b>			
<i>Grease interceptor - In Plumbing</i>	-	/-	
<i>Acid Neutralization - In Plumbing</i>	-	/-	
<b>Utility Septic Tanks</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>33.40.00 Storm Drainage Utilities</b>			
<i>Catch basins</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Granite Curb Inlets</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Storm drainage manholes</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Outlet control structures</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Storm headwalls</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Stormceptors</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Storm drainage piping</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Rip Rap Splash Pads</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Weir Overflows</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Check dams</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Storm Drainage Utilities</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>33.46.00 Subdrainage</b>			
<i>Foundation drainage piping</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Subdrainage</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>33.47.00 Infiltration Systems</b>			
<i>Infiltration system</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Infiltration Systems</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>33.50.00 Fuel Distribution Utilities</b>			
<i>Excavation / backfill for gas line</i>	<i>BP#1</i>	<i>/BP#1</i>	
<b>Fuel Distribution Utilities</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>33.70.00 Electrical Utilities</b>			
<i>Excavation/backfill for Emergency Generator ductbank</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Excavation/backfill for Primary Electric ductbank</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Excavation/backfill for Fire Alarm ductbank</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Excavation/backfill for Telcom ductbank</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Excavation/backfill for U.G. ductbank</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Excavation/backfill for 2"C Power Data ductbank (Amphitheather)</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Excavation/backfill for 2"C to IDF ductbank</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Concrete and rebar for electrical/telcom ductbanks</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Excavation/backfill for site lighting</i>	<i>BP#1</i>	<i>/BP#1</i>	



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>33.70.00 Electrical Utilities</b>			
Emergency Call Box base	BP#1	/BP#1	
EV Parking Station bases	BP#1	/BP#1	
Light pole bases	BP#1	/BP#1	
6" Concrete Filled Steel Pipe Bollards at Generator & Transformer Pads	BP#1	/BP#1	
<b>Electrical Utilities</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>31-23 SITEWORK</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>32-10 LANDSCAPING &amp; SITE IMPROVEMENTS</b>			
<b>12.93.00 Site Furnishings</b>			
Wood benches	20 lf	750.00 /lf	15,000
Bicycle Racks	20 ea	785.00 /ea	15,700
Basketball Poles & Hoops	2 ea	8,000.00 /ea	16,000
Miscellaneous site furnishings - Allowance	1 ls	30,000.00 /ls	30,000
<b>Site Furnishings</b>	<b>136,600 sf</b>	<b>0.56 /sf</b>	<b>76,700</b>
<b>32.01.90 Plant Maintenance</b>			
Landscaping maintenance	1 yr	8,000.00 /yr	8,000
<b>Plant Maintenance</b>	<b>136,600 sf</b>	<b>0.06 /sf</b>	<b>8,000</b>
<b>32.14.00 Unit Paving</b>			
Pavers - plaza paving	745 sf	25.00 /sf	18,625
Stone Dust at Raised Planter	32 sf	20.00 /sf	640
<b>Unit Paving</b>	<b>136,600 sf</b>	<b>0.14 /sf</b>	<b>19,265</b>
<b>32.18.00 Athletic &amp; Recreational Surfacing</b>			
<b>Basketball Court Pavement- (3 1/2" Total Paving w/ Gravel Base) - BP#1</b>	<b>sf</b>	<b>/sf</b>	
Basketball Court Pavement Markings	1 ls	2,000.00 /ls	2,000
<b>Athletic &amp; Recreational Surfacing</b>	<b>136,790 sf</b>	<b>0.02 /sf</b>	<b>2,000</b>
<b>32.31.50 Walk / Road / Parking Appurtenances</b>			
Flag pole	1 ea	9,000.00 /ea	9,000
<b>Bollards - 6" steel w/concrete - BP#1</b>	<b>BP#1</b>	<b>/BP#1</b>	
<b>Bollards - 6" steel w/concrete - BP#1</b>	<b>ea</b>	<b>/ea</b>	
<b>Bollards - architectural</b>	<b>0 ea</b>	<b>/ea</b>	
<b>Walk / Road / Parking Appurtenances</b>	<b>136,600 sf</b>	<b>0.07 /sf</b>	<b>9,000</b>



# Fuller Middle School

## 90% CD Reconciled Estimate

10/7/2019

**CONSIGLI**  
Est. 1905

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>32.32.00 Retaining Walls</b>			
Segmental retaining wall	2,600 sf	50.00 /sf	130,000
Additional segmental retaining wall per PR #12	220 sf	50.00 /sf	11,000
<b>Retaining Walls</b>	<b>136,600 sf</b>	<b>1.03 /sf</b>	<b>141,000</b>
<b>32.80.00 Irrigation</b>			
<i>Irrigation system @ south sports field - by others</i>	-	/-	
Irrigation @ amphitheater - Allowance	23,435 sf	2.00 /sf	46,870
Irrigation system @ north sports field - Allowance	81,000 sf	2.00 /sf	162,000
<b>Irrigation</b>	<b>136,600 sf</b>	<b>1.53 /sf</b>	<b>208,870</b>
<b>32.91.00 Planting Preparation</b>			
Mulch at trees and planting beds (3")	240 cy	105.00 /cy	25,200
Import loam & spread (6") at Lawns, Athletic Fields & Native Meadows	5,594 cy	40.00 /cy	223,760
Ammend & spread (6") at Lawns, Athletic Fields & Native Meadows	6,030 cy	12.00 /cy	72,360
Import loam & spread (6") at Detention Basins	802 cy	40.00 /cy	32,080
Import loam & spread (12") at Plant Beds	375 cy	40.00 /cy	15,000
Landscape Metal Edging at Building Mow Strip	2,330 lf	15.00 /lf	34,950
Building Mowing Strip- (Peastone)	100 tn	50.00 /tn	5,000
Import loam & spread (6") at Sodded Amphitheater Lawns	691 cy	40.00 /cy	27,640
<b>Planting Preparation</b>	<b>136,600 sf</b>	<b>3.19 /sf</b>	<b>435,990</b>
<b>32.92.00 Turf &amp; Grasses</b>			
Fine grade & hydroseed lawn areas	119,420 sf	0.30 /sf	35,826
Fine grade & seed (Native Wildflower Meadow)	104,005 sf	0.25 /sf	26,001
Fine grade & seed (Detention Basin Mix- Hydroseed)	33,330 sf	0.25 /sf	8,333
Fine grade & seed (Natural Turf Fields)	259,269 sf	0.25 /sf	64,817
Sod (Amphitheater Lawns)	28,719 sf	1.50 /sf	43,079
Sod (100'x170') - Temporary	17,000 sf	1.50 /sf	25,500
Sod northeast - Phase 3 play area, temporary	5,000 sf	1.50 /sf	7,500
Watering for sod areas - Fields	1 ls	7,500.00 /ls	7,500
Watering for sod areas - Amphitheater	1 ls	7,500.00 /ls	7,500
<b>Turf &amp; Grasses</b>	<b>136,600 sf</b>	<b>1.66 /sf</b>	<b>226,056</b>
<b>32.93.00 Plants</b>			
Trees	118 ea	750.00 /ea	88,500
Shrubs (478 Total)	7,736 sf	8.50 /sf	65,756
Groundcover/perennials	1,966 ea	20.00 /ea	39,320
Plantings @ planter beds	1 ls	20,000.00 /ls	20,000



**Fuller Middle School**  
**90% CD Reconciled Estimate**

10/7/2019

**CONSIGLI**  
*Est. 1905*

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>32.93.00 Plants</b>			
<i>Rain garden - N/A</i>	-	/-	
<b>Plants</b>	<b>136,600 sf</b>	<b>1.56 /sf</b>	<b>213,576</b>
<b>32-10 LANDSCAPING &amp; SITE IMPROVEMENTS</b>	<b>136,600 sf</b>	<b>9.81 /sf</b>	<b>1,340,457</b>
<b>32-31 FENCING</b>			
<b>32.31.00 Fences &amp; Gates</b>			
<i>Wooden Guardrailing</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Fencing - N/A</i>	-	/-	
24' wide Single Arm Gate	1 ea	3,500.00 /ea	3,500
<i>Wooden Guardrailing - BP#1</i>	<i>lf</i>	<i>/lf</i>	
<b>Fences &amp; Gates</b>	<b>136,600 sf</b>	<b>0.03 /sf</b>	<b>3,500</b>
<b>32-31 FENCING</b>	<b>136,600 sf</b>	<b>0.03 /sf</b>	<b>3,500</b>



**CONSIGLI**  
*Est. 1905*





Job #:	<b>2043</b>
Project:	<b>Fuller Middle School</b>
Location:	<b>Framingham, MA</b>
Date:	<b>9/9/2019</b>
Proposal:	<b>General Requirements</b>
Gross Area (SF):	<b>157,000</b>

DESCRIPTION	Fuller Proposed GR	Early Site	Steel & Concrete Package	Remaining
Temp Power - Allowance	\$ 125,000.00	\$ 5,000.00	\$ 5,000.00	\$ 115,000
Temp Heating - Allowance	\$ 80,000.00	\$ 5,000.00	\$ 20,000.00	\$ 55,000
Temp Heating Fuel - Allowance	\$ 50,000.00	\$ 3,000.00	\$ 17,000.00	\$ 30,000
Staging (Auditorium)	\$ 81,000.00			\$ 81,000
Dumpster - Allowance	\$ 125,000.00	\$ 15,000.00	\$ 15,000.00	\$ 95,000
Temp Toilets	\$ 20,000.00	\$ 5,000.00	\$ 6,000.00	\$ 9,000
Project Identification	\$ 10,000.00	\$ 10,000.00	\$ -	\$ -
Temporary Barriers	\$ 40,000.00	\$ 4,000.00		\$ 36,000
Temp Fencing	\$ 248,520.00	\$ 106,792.00	\$ 57,688.00	\$ 84,040
Police Details - Allowance	\$ 30,000.00	\$ 5,000.00	\$ 10,000.00	\$ 15,000
Weather Protection - Allowance	\$ 170,000.00	\$ 10,000.00	\$ 50,000.00	\$ 110,000
Winter Conditions - Allowance	\$ 140,000.00	\$ 5,000.00	\$ 40,000.00	\$ 95,000
Carpenter Foreman	\$ 658,908.00	\$ 85,866.00	\$ 21,255.00	\$ 551,787
Labor Foreman	\$ 594,074.00	\$ 87,362.00	\$ 35,159.00	\$ 471,553
Temp Water - Allowance	\$ 20,000.00	\$ 5,000.00	\$ 2,500.00	\$ 12,500
Safety & First Aid	\$ 60,000.00	\$ 14,000.00	\$ 21,000.00	\$ 25,000
Temp. Fire Extinguishers	\$ 10,000.00	\$ 1,000.00	\$ 1,500.00	\$ 7,500
Temp Stair Towers	\$ 120,000.00		\$ 12,000.00	\$ 108,000
Roof Edge Protection	\$ 50,000.00			\$ 50,000
Pest Control	\$ 10,000.00	\$ 10,000.00		\$ -
Building Layout	\$ 115,000.00	\$ 21,000.00	\$ 30,000.00	\$ 64,000
Final Cleaning - Interior	\$ 157,000.00			\$ 157,000
Final Cleaning - Glass - Interior	\$ 43,000.00			\$ 43,000
Final Cleaning - Glass - Exterior	\$ 43,000.00			\$ 43,000
Project and Site Traffic Signage (Temp)	\$ 20,000.00	\$ 9,000.00	\$ 11,000.00	\$ -
Time Lapse Camera	\$ 17,000.00	\$ 17,000.00		\$ -
Storage	\$ 15,000.00	\$ 3,000.00	\$ 3,000.00	\$ 9,000
Security	\$ 17,000.00	\$ 5,000.00	\$ 5,000.00	\$ 7,000
Air Quality Control	\$ 15,000.00			\$ 15,000
<b>TOTAL GENERAL REQUIREMENT COSTS</b>	<b>\$ 3,084,502.00</b>	<b>\$ 432,020.00</b>	<b>\$ 363,102.00</b>	<b>\$ 2,289,380.00</b>





CONSIGLI  
*Est. 1905*





---

## ASSUMPTIONS & QUALIFICATIONS

### FULLER MIDDLE SCHOOL

90% CONSTRUCTION DOCUMENT ESTIMATE

OCTOBER 7, 2019

---

### GENERAL

1. Pricing is based on the following:
  - 90% Construction Document Pricing Drawings by Jonathan Levi Architects, dated September 9, 2019.
  - 90% Construction Document Pricing Drawings by Jonathan Levi Architects, dated September 9, 2019.
2. Testing and/or inspections are not included.
3. Builders Risk Insurance is included in the Amendment #1 GMP value.
4. Building permit cost is not included.
5. A Payment and Performance Bond is included in the Amendment #1 GMP value.
6. Sales tax is not included as this project is assumed to be tax exempt.
7. Subcontractor insurances are included per Consigli standard subcontract.
8. Utility company back charges, user fees, etc. (temporary electric, water, gas, etc.) are excluded.
9. Work hours are assumed to be normal business hours (7:00AM to 3:00PM) Monday to Friday. Overtime, phasing, or off-hours work costs are not included.
10. Breakouts provided are for informational/accounting purposes only. We reserve the right to reprice our estimate if changes are made to the scope of the project.
11. Site Security costs or provisions are not included.
12. Uniform Fire watch is not included.
13. An exterior mockup is included as an allowance.
14. All design is by the Owner's Designer. Delegated design is excluded.

---

### TRADE SPECIFIC

15. Hazardous material testing is not included.
16. Removal and/or relocation of furniture is not included.
17. Barrier-1 or similar concrete additives are not included.
18. The concrete floor at the Auditorium is included as polished per sheet A141D.
19. Exterior masonry work includes staging.
20. Interior brick veneer is not shown and therefore not included.
21. White, plain face CMU is included in lieu of all ground face CMU except at the Auditorium per VM Item E02.
22. 82 sf of glass is included at the canopy in lieu of polycarbonate per VM Item E01.
23. The 'summer beams' in Classrooms are included at 11'-6" above the floor per VM Item I11.
24. 1,393 sf of ACT-2 is included in lieu of ACT-3 per VM Item I03.
25. Fluid applied moisture mitigation is not included.
26. Resilient tile base is included as surface applied.
27. Schluter strips are only included at bumper guards per VM Item I10.
28. The Learning Commons stairs are included with rubber treads, risers, and landings.
29. CMU walls are not painted.
30. (3) fume hoods are included.



## ASSUMPTIONS & QUALIFICATIONS

### FULLER MIDDLE SCHOOL

90% CONSTRUCTION DOCUMENT ESTIMATE

OCTOBER 7, 2019

31. We have not included any costs or provisions for FF & E items and assume this will be by the Owner.
32. The orchestra enclosures are not included. These will be FF & E by the Owner.
33. Mobile cabinets are not included per VM Item I05. They will be FFE by the Owner.
34. Elevator operator costs are included.
35. Hydrant flow tests are not included and are assumed to have been previously completed to inform the fire protection design.
36. A Fire pump is not included.
37. A Domestic Booster pump is not included.
38. A Compressed Air System is not included.
39. Two (2) Gas Fired Domestic water heaters are included.
40. One (1) Domestic Storage tank is included.
41. Laboratory Hot Water piping is wrapped with heat maintenance cable.
42. Gas piping is included to (2) science labs 111A and 1114.
43. Ten (10) Gas Turrets are included.
44. Two (2) interior kitchen grease traps are included.
45. One (1) Exterior 8000 Gallon precast concrete grease trap is included.
46. Radon venting is not included.
47. Primary roof drains and storm piping is included.
48. Overflow secondary roof drains and piping is not included.
49. Interior under-slab drainage is not included.
50. A rainwater reclaim system is not included.
51. Six (6) Acid Neutralization local Chip Tanks are included.
52. Two (2) PH Monitoring panels and sensors are included.
53. Central Acid Neutralization and exterior pump stations are not included.
54. Rectangular, single-walled ductwork is included for supply air medium distribution.
55. VAV's do not include hot water re-heat coils.
56. Electrical and fire alarm permit fee costs are excluded (assumed waived by City of Framingham).
57. Primary cable, primary terminations, and exterior pad mount transformer by Utility Co.
58. Concealed lighting, power, and fire alarm branch circuitry is routed in MC Cable (per NEC Article 330).
59. Distribution feeders are routed in EMT and copper wire (where not required to be MI Cable).
60. Power, switch stations, and LV cable for twenty-five (25) motorized window treatment locations are included.
61. VFD's, motor starters, and motor controllers furnished by Division 23, installed and wired by Division 26.
62. Provisions for a future roof mounted photovoltaic (PV) system are included.
63. Two (2) central uninterruptible power supplies (UPS's) - 480V: 208/120V, 24kW (8 min. backup) - are included.
64. ATS's provided as open transition, with bypass isolation functionality included for legal-required and life-safety.
65. Cable tray is included for MDF and IDF's (200LF total); all other horizontal cabling routed across j-hooks.
66. Audio-visual devices, jacks, cabling, head end equipment, monitors, terminations and labor by Owner's Vendor.
67. Assistive classroom listening systems are not included.



---

## ASSUMPTIONS & QUALIFICATIONS

### FULLER MIDDLE SCHOOL

90% CONSTRUCTION DOCUMENT ESTIMATE

OCTOBER 7, 2019

- 68. Emergency pull-cord or call-for-aid systems are not included.
- 69. Motorized window treatment power and/or controls are excluded; none are shown on the electrical drawings.
- 70. Electrical floor boxes and poke-thru devices are not shown on power plans, and none are included in estimate.
- 71. Theatrical light fixtures, theatrical rigging, and theatrical lighting controls are included with theater equipment.
- 72. Lighting has been reduced by \$1.50/sf per VM Item EL01.
- 73. Electrical heat trace cabling system or power connections are not included.
- 74. Exterior site and building mounted lighting are included as shown on drawings E003-1 and E003-2.
- 75. Addressable fire alarm Notifier system shall be capable of voice evacuation via speaker/strobe appliances; a stand-alone mass notification system is not included.
- 76. Play field equipment is not included.
- 77. Fencing is not shown and therefore not included.

### ALLOWANCES

---

78. Exterior wall mockup (excluding Concrete and Steel).	\$55,000
79. Miscellaneous rough carpentry.	\$68,300
80. Level 5 finish.	\$63,750
81. Miscellaneous specialties.	\$34,150
82. Food service equipment.	\$415,270
83. Sound systems.	\$450,000
84. Theater and stage equipment.	\$416,921
85. Miscellaneous lab equipment.	\$25,000
86. Theater lighting power and rough in.	\$37,600
87. Miscellaneous site furnishings.	\$30,000
88. Irrigation.	\$208,870





### 2.3.5 Reconciled Cost Estimate - Designer

Attached is the reconciled Designer Cost Estimate.



***Fuller Middle School***

Framingham, MA

**October 9, 2019**

**90% Construction Documents Estimate**

**Owner's Project Manager**

SMMA

1000 Massachusetts Ave.

Cambridge, MA

**Architect:**

Jonathan Levi Architects

266 Beacon Street

Boston, MA 02116

**Estimator:**

Miyakoda Consulting

PO Box 47

Raynham, MA 02767

(617) 799-5832

## **Fuller Middle School**

Fuller Middle School

### **INTRODUCTION**

#### **Description:**

- 8** Construction of the Framingham Middle School
- 9** The scope of the work includes all related sitework, hardscape/landscape, and underground utilities
- 10**

#### **Particulars:**

- 12** 90% CD Drawings and Specifications dated September 9, 2019, received from Jonathan Levi Architects
- 13** Detailed quantity takeoff from these documents where possible
- 14** Experience with similar projects of this nature with JLA
- 15**
- 16**

#### **Assumptions:**

- 18** The project will be constructed by a Construction Manager
- 19** Our costs assume that there will be at least three subcontractors submitting unrestricted bids in each sub-trade
- 20** Unit rates are based on current dollars
- 21** General Conditions and Requirements value covers Sub-Contractor's bond, site office overheads, and building permit applications
- 22** Fee markup is calculated on a percentage basis of direct construction costs. The value covers Contractor's bond, insurance and profit
- 23** Design and Pricing Contingency markup is an allowance for unforeseen design issues, design detail development and specification clarifications
- 24** Escalation has been included to midpoint of construction. The construction start date is June 2020.
- 25**
- 26**

#### **Exclusions:**

- 28** Design fees and other soft costs
- 29** Owner's project administration
- 30** Construction of temporary facilities
- 31** Relocation expenses
- 32** Printing and advertising
- 33** Existing condition surveys and investigations
- 34** Work beyond the boundary of the site
- 35** Testing
- 36** Specialties, loose furnishings, fixtures and equipment beyond those noted
- 37** Preconstruction Fee
- 38** Traffic Improvements

**Fuller Middle School**

Fuller Middle School

137,385 GSF

**MAIN SUMMARY - NEW CONSTRUCTION**

<b><u>DESCRIPTION</u></b>			<b><u>TOTAL</u></b>	<b><u>COST/SF</u></b>
<b>39 Direct Trade Costs With Site</b>				
<b>40 New Construction</b>	137,385 GSF		\$42,543,874	\$309.67
<b>41 Site Development</b>			\$1,401,720	\$10.20
<b>42 Direct Trade Cost SubTotal</b>			<b>\$43,945,594</b>	<b>\$319.87</b>
<b>43</b>				
<b>44 Demolish Existing Building</b>	195,400 GSF		\$1,465,500	\$10.67
<b>45 Hazardous Waste Abatement (Budget provided)</b>			\$1,294,490	\$9.42
<b>46 Building Cost Subtotal</b>			<b>\$46,705,584</b>	<b>\$339.96</b>
<b>47</b>				
<b>48 Design and Pricing Contingency</b>	3.00%	\$46,705,584	\$1,401,168	\$10.20
<b>49</b>				
<b>50 Building Cost Total</b>			<b>\$48,106,752</b>	<b>\$350.16</b>
<b>51</b>				
<b>52 Escal. to Midpoint of Construction (Consigli %)</b>	1.00%	\$48,106,752	\$481,068	\$3.50
<b>53 Trade Cost SubTotal</b>			<b>\$48,587,820</b>	<b>\$353.66</b>
<b>54</b>				
<b>55 General Conditions</b>			\$2,931,033	\$21.33
<b>56 General Requirements</b>			\$2,289,380	\$16.66
<b>57 SDI</b>			\$269,858	\$1.96
<b>58 Sub Bonds</b>			\$403,034	\$2.93
<b>59 General Liability Insurance</b>			\$576,109	\$4.19
<b>60 Construction Contingency</b>	2.50%	\$55,057,234	\$1,376,431	\$10.02
<b>61 CM Fee</b>			\$1,152,218	\$8.39
<b>62</b>				
<b>63 BP#1</b>			\$10,957,843	\$79.76
<b>64 BP#2</b>			\$8,738,800	\$63.61
<b>65 BP#2 Savings</b>			(\$50,755)	
<b>66 Estimated Construction Cost Total</b>			<b>\$77,231,771</b>	<b>\$562.16</b>
<b>67</b>				
<b>68</b>				
<b>69</b>				
<b>70</b>				
<b>71</b>				
<b>72</b>				
<b>73</b>				

# Fuller Middle School

Framingham, MA

## DIRECT TRADE COSTS SUMMARY - CSI

137,385 GSF

<u>Element</u>	<u>Filed Sub Bid</u>	<u>SITEWORK</u>	<u>BUILDING</u>	<u>TOTAL</u>	<u>\$/GSF</u>
74 02 30 00 Building Demolition				\$0	\$0.00
75 02 41 00 Demolition		\$0		\$0	\$0.00
76 02 60 00 Hazardous Waste Remediation			\$0	\$0	\$0.00
77 <b>02-EXISTING CONDITIONS</b>		<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0.00</b>
78					
79 03 30 00 Cast-In-Place Concrete			\$45,648	\$45,648	\$0.33
80 <b>03-CONCRETE</b>		<b>\$0</b>	<b>\$45,648</b>	<b>\$45,648</b>	<b>\$0.33</b>
81					
82 04 20 00 Unit Masonry	\$2,338,257		\$2,338,257	\$2,338,257	\$17.02
83 <b>04-MASONRY</b>		<b>\$0</b>	<b>\$2,338,257</b>	<b>\$2,338,257</b>	<b>\$17.02</b>
84					
85 05 12 00 Structural Steel Framing			\$0	\$0	\$0.00
86 05 31 00 Steel Decking			\$0	\$0	\$0.00
87 05 40 00 Cold-Formed Metal Framing			\$0	\$0	\$0.00
88 05 50 00* Miscellaneous and Ornamental Iron	\$836,941		\$836,941	\$836,941	\$6.09
89 <b>05-METALS</b>		<b>\$0</b>	<b>\$836,941</b>	<b>\$836,941</b>	<b>\$6.09</b>
90					
91 06 10 00 Rough Carpentry			\$0	\$0	\$0.00
92 06 16 50 Gypsum Sheathing			\$0	\$0	\$0.00
93 06 20 00 Finish Carpentry			\$1,692,555	\$1,692,555	\$12.32
94 06 40 00 Architectural Woodwork			\$88,675	\$88,675	\$0.65
95 <b>06-WOOD, PLASTICS &amp; COMPOSITES</b>			<b>\$1,781,230</b>	<b>\$1,781,230</b>	<b>\$12.97</b>
96					
97 07 00 01* Waterproofing, Dampproofing & Caulking	\$475,977		\$475,977	\$475,977	\$3.46
98 07 00 02* Roofing & Flashing	\$1,577,545		\$1,577,545	\$1,577,545	\$11.48
99 07 42 00 Wall Panels			\$1,289,894	\$1,289,894	\$9.39
100 07 81 00 Applied Fireproofing			\$395,500	\$395,500	\$2.88
101 07 84 10 Penetration Firestopping			\$0	\$0	\$0.00
102 <b>07-THERMAL AND MOISTURE PROTECTION</b>			<b>\$3,738,916</b>	<b>\$3,738,916</b>	<b>\$27.21</b>
103					
104 08 11 10 Hollow Metal Doors and Frames			\$284,350	\$284,350	\$2.07
105 08 14 00 Flush Wood Doors			\$10,000	\$10,000	\$0.07
106 08 31 10 Access Doors & Frames			\$30,000	\$30,000	\$0.22
107 08 33 10 Overhead Coiling Doors			\$50,433	\$50,433	\$0.37
108 08 00 01* Metal Windows			\$2,482,125	\$2,482,125	\$18.07
109 08 63 00 Metal-Framed Skylights			\$0	\$0	\$0.00
110 08 71 00 Door Hardware			\$406,000	\$406,000	\$2.96
111 08 00 02* Glass and Glazing	\$986,525		\$986,525	\$986,525	\$7.18
112 08 90 00 Louvers and Vents			\$53,125	\$53,125	\$0.39
113 <b>08-OPENINGS</b>			<b>\$4,302,558</b>	<b>\$4,302,558</b>	<b>\$31.32</b>
114					
115 09 29 00 Gypsum Drywall			\$5,627,244	\$5,627,244	\$40.96
116 09 30 00* Tiling	\$322,777		\$322,777	\$322,777	\$2.35
117 09 50 01* Acoustical Ceilings	\$763,811		\$763,811	\$763,811	\$5.56
118 09 60 01* Resilient Flooring	\$787,389		\$787,389	\$787,389	\$5.73

# Fuller Middle School

Framingham, MA

## DIRECT TRADE COSTS SUMMARY - CSI

137,385 GSF

<u>Element</u>	<u>Filed Sub Bid</u>	<u>SITEWORK</u>	<u>BUILDING</u>	<u>TOTAL</u>	<u>\$/GSF</u>
<b>119</b> 09 64 00 Wood Flooring			\$48,495	\$48,495	\$0.35
<b>120</b> 09 64 40 Wood Athletic Flooring			\$210,125	\$210,125	\$1.53
<b>121</b> 09 67 23 Resinous Flooring			\$119,100	\$119,100	\$0.87
<b>122</b> 09 68 00 Carpeting			\$27,700	\$27,700	\$0.20
<b>123</b> 09 72 00 Wall Coverings			\$449,932	\$449,932	\$3.27
<b>124</b> 09 91 00* Painting	\$556,240		\$556,240	\$556,240	\$4.05
<b>125</b> <b>09-FINISHES</b>			<b>\$8,912,813</b>	<b>\$8,912,813</b>	<b>\$64.87</b>
<b>126</b>					
<b>127</b> 10 00 01 Specialties			\$299,200	\$299,200	\$2.18
<b>128</b> 10 11 00 Visual Display Boards			\$377,584	\$377,584	\$2.75
<b>129</b> 10 14 23 Signage			\$72,634	\$72,634	\$0.53
<b>130</b> 10 21 13 Plastic Toilet Compartments			\$59,600	\$59,600	\$0.43
<b>131</b> 10 21 23 Cubicle Curtains, Tracks & Hardware			\$400	\$400	\$0.00
<b>132</b> 10 26 00 Wall Protection			\$10,000	\$10,000	\$0.07
<b>133</b> 10 28 13 Toilet Accessories			\$23,880	\$23,880	\$0.17
<b>134</b> 10 44 13 Fire Protection SpecialSies			\$7,982	\$7,982	\$0.06
<b>135</b> 10 51 24 Phenolic-Core Lockers			\$435,000	\$435,000	\$3.17
<b>136</b> <b>10-SPECIALTIES</b>			<b>\$1,286,280</b>	<b>\$1,286,280</b>	<b>\$9.36</b>
<b>137</b>					
<b>138</b> 11 00 00 Equipment			\$150,000	\$150,000	\$1.09
<b>139</b> 11 31 00 Appliances			\$10,900	\$10,900	\$0.08
<b>140</b> 11 40 00 Food Service Equipment			\$415,270	\$415,270	\$3.02
<b>141</b> 11 52 13 Projection Screens			\$23,000	\$23,000	\$0.17
<b>142</b> 11 61 00 Theater and Stage Equipment			\$953,366	\$953,366	\$6.94
<b>143</b> 11 66 23 Gymnasium Equipment			\$103,412	\$103,412	\$0.75
<b>144</b> 11 66 53 Gymnasium Dividers			\$20,000	\$20,000	\$0.15
<b>145</b> 11 66 80 Scoreboards			\$7,500	\$7,500	\$0.05
<b>146</b> <b>11-EQUIPMENT</b>			<b>\$1,683,448</b>	<b>\$1,683,448</b>	<b>\$12.25</b>
<b>147</b>					
<b>148</b> 12 24 12 Roller Shades			\$177,207	\$177,207	\$1.29
<b>149</b> 12 35 53 Caswork			\$273,165	\$273,165	\$1.99
<b>150</b> 12 48 13 Entrance Mats & Frames			\$13,860	\$13,860	\$0.10
<b>151</b> 12 66 00 Telescoping Stands			\$76,000	\$76,000	\$0.55
<b>152</b> <b>12-FURNISHING</b>			<b>\$540,232</b>	<b>\$540,232</b>	<b>\$3.93</b>
<b>153</b>					
<b>154</b> 13 00 00 Special Construction			\$0	\$0	\$0.00
<b>155</b> <b>13-SPECIAL CONSTRUCTION</b>			<b>\$0</b>	<b>\$0</b>	<b>\$0.00</b>
<b>156</b>					
<b>157</b> 14 24 00* Hydraulic Elevators	\$215,000		\$215,000	\$215,000	\$1.56
<b>158</b> <b>14-CONVEYING EQUIPMENT</b>			<b>\$215,000</b>	<b>\$215,000</b>	<b>\$1.56</b>
<b>159</b>					
<b>160</b> 21 00 00* Fire Protection	\$962,994		\$962,994	\$962,994	\$7.01
<b>161</b> 22 00 00* Plumbing	\$2,126,673		\$2,126,673	\$2,126,673	\$15.48
<b>162</b> 23 00 00* HVAC	\$7,879,869		\$7,879,869	\$7,879,869	\$57.36
<b>163</b> <b>21 - 23-MECHANICAL</b>			<b>\$10,969,536</b>	<b>\$10,969,536</b>	<b>\$79.85</b>

# Fuller Middle School

Framingham, MA

## DIRECT TRADE COSTS SUMMARY - CSI

137,385 GSF

<u>Element</u>	<u>Filed Sub Bid</u>	<u>SITEWORK</u>	<u>BUILDING</u>	<u>TOTAL</u>	<u>\$/GSF</u>
<b>164</b>					
<b>165</b> 26 00 00* Electrical	\$5,893,015	\$0	\$5,893,015	\$5,893,015	\$42.89
<b>166</b> 26,27,28-ELECTRICAL, COMMUNICATION, SECURITY		\$0	\$5,893,015	\$5,893,015	\$42.89
<b>167</b>					
<b>168</b> 31 00 00 Earthwork		\$0	\$0	\$0	\$0.00
<b>169</b> 31 10 00 Site Clearing		\$0		\$0	\$0.00
<b>170</b> 31 23 19 Dewatering and Drainage		\$0		\$0	\$0.00
<b>171</b> 31 25 00 Erosion and Sedimentation Controls		\$0		\$0	\$0.00
<b>172</b> 31-EARTHWORK		\$0	\$0	\$0	\$0.00
<b>173</b>					
<b>174</b> 32 12 00 Flexible Paving		\$0		\$0	\$0.00
<b>175</b> 32 14 00 Unit Paving		\$0		\$0	\$0.00
<b>176</b> 32 16 00 Curbs and Gutters		\$0		\$0	\$0.00
<b>177</b> 32 17 00 Paving Specialties		\$0		\$0	\$0.00
<b>178</b> 32 30 00 Site Improvements		\$267,425		\$267,425	\$1.95
<b>179</b> 32 31 00 Fences and Gates		\$89,750		\$89,750	\$0.65
<b>180</b> 32 32 00 Retaining Walls		\$0		\$0	\$0.00
<b>181</b> 32 80 00 Irrigation		\$0		\$0	\$0.00
<b>182</b> 32 92 00 Turfs and Grasses		\$819,947		\$819,947	\$5.97
<b>183</b> 32 93 00 Plants		\$224,598		\$224,598	\$1.63
<b>184</b> 32-EXTERIOR IMPROVEMENTS		\$1,401,720		\$1,401,720	\$10.20
<b>185</b>					
<b>186</b> 33 10 00 Water Distribution		\$0		\$0	\$0.00
<b>187</b> 33 31 00 Sanitary Sewerage		\$0		\$0	\$0.00
<b>188</b> 33 41 00 Storm Utility Drainage		\$0		\$0	\$0.00
<b>189</b> 33 50 00 Gas Service		\$0		\$0	\$0.00
<b>190</b> 33-UTILITIES		\$0		\$0	\$0.00
<b>191</b>					
<b>192</b>					
<b>193</b>					
<b>194</b> Direct Trade Costs Subtotal	\$25,723,013	\$1,401,720	\$42,543,874	\$43,945,594	\$319.87
<b>195</b>					



# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>196 02-EXISTING CONDITIONS</b>				
<b>197</b>				
<b>198 02 60 00 Hazardous Waste Remediation</b>				
<b>199</b> Removal and disposal of hazardous materials				<u>Main Summary</u>
<b>200 02 60 00 Hazardous Waste RemediationTotal</b>				
<b>201</b>				
<b>202</b>				
<b>203 03-CONCRETE</b>				
<b>204</b>				
<b>205 03 30 00 Cast-In-Place Concrete</b>				
<b>206</b> A1010 FOUNDATIONS				
<b>207</b> Concrete				
<b>208</b> Continuous footings; 3' x 1' 0" typ.	<b>2,049</b>	LF		
<b>209</b> 4' x 1' 0"				
<b>210</b> 5' x 1' 0"				
<b>211</b> Concrete; material	<b>247</b>	CY	\$135.00	BP#2
<b>212</b> Concrete; place (combination of pumping/trucking)	<b>247</b>	CY	\$95.00	BP#2
<b>213</b> Reinforcement w/ftn wall dowels (10#/lf)	<b>20,490</b>	LB	\$1.15	BP#2
<b>214</b> Formwork	<b>8,196</b>	SF	\$12.00	BP#2
<b>215</b> Spread footings	<b>133</b>	EA		
<b>216</b> Concrete; material	<b>465</b>	CY	\$135.00	BP#2
<b>217</b> Concrete; place	<b>465</b>	CY	\$95.00	BP#2
<b>218</b> Reinforcement (100#/cy)	<b>46,500</b>	LB	\$1.15	BP#2
<b>219</b> Formwork	<b>6,406</b>	SF	\$12.00	BP#2
<b>220</b> Pilasters	<b>133</b>	EA	\$1,100.00	BP#2
<b>221</b> Grade beam GB-1, GB-2	<b>288</b>	LF		
<b>222</b> Concrete; material	<b>57</b>	CY	\$135.00	BP#2
<b>223</b> Concrete; place (combination of pumping/trucking)	<b>57</b>	CY	\$95.00	BP#2
<b>224</b> Reinforcement (125#/cy)	<b>7,125</b>	LB	\$1.15	BP#2
<b>225</b> Formwork	<b>1,940</b>	SF	\$12.00	BP#2
<b>226</b> Foundation and frost walls; 16" thick x 4' 0" high typ.	<b>8,551</b>	SF		
<b>227</b> Concrete; material	<b>443</b>	CY	\$135.00	BP#2
<b>228</b> Concrete; place	<b>443</b>	CY	\$95.00	BP#2
<b>229</b> Reinforcement (150#/cy)	<b>66,450</b>	LB	\$1.15	BP#2
<b>230</b> Formwork	<b>17,212</b>	SF	\$8.00	BP#2
<b>231</b> Foundation walls; 21" thick x 4' 0" high typ.	<b>1,645</b>	SF		
<b>232</b> Concrete; material	<b>112</b>	CY	\$135.00	BP#2
<b>233</b> Concrete; place	<b>112</b>	CY	\$95.00	BP#2
<b>234</b> Reinforcement (150#/cy)	<b>16,800</b>	LB	\$1.15	BP#2
<b>235</b> Formwork	<b>3,289</b>	SF	\$8.00	BP#2
<b>236</b> Brick shelf	<b>2,049</b>	LF	\$5.00	BP#2
<b>237</b> Elevator pit; slab and walls	<b>1</b>	EA	\$5,000.00	BP#2

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
238 Anchor bolts	532	SET	\$35.00	BP#2
239 6" Ø hole through wall, backfill w/crushed stone	4	EA	\$500.00	BP#2
240				
241 Bandshell				
242 Footing	46	lf		
243 Concrete; material	7	CY	\$135.00	BP#2
244 Concrete; place	7	CY	\$95.00	BP#2
245 Reinforcing	455	LBS	\$1.15	BP#2
246 Formwork	96	SF	\$9.00	BP#2
247 Wall	182	sf		
248 Concrete	10	CY	\$135.00	BP#2
249 Placing	10	CY	\$95.00	BP#2
250 Reinforcing	1,500	LBS	\$1.15	BP#2
251 Formwork	382	SF	\$8.00	BP#2
252 Concrete steps	556	LFR	\$150.00	BP#2
253 Concrete steps , amphitheatre steps	385	LFR	\$125.00	BP#2
254 Miscellaneous concrete				
255 Ground improvements				BP#1
256				
257 Special Foundation Conditions				
258 Dewatering during excavation				BP#1
259				
260 Thermal & Moisture Protection				
261 2" rigid insulation at foundation walls	10,195	SF	\$2.50	\$25,488
262				
263 A1030 SLAB ON GRADE				
264 Concrete				
265 Slab on grade, 5" thick, WWF, top of slab 314' 0"	66,213	SF		
266 Concrete; material	1,030	CY	\$135.00	BP#2
267 Concrete; place & finish	66,213	SF	\$2.85	BP#2
268 Reinforcement (6x6 mesh)	76,145	SF	\$1.00	BP#2
269 Slab depressions	1,243	LF	\$65.00	BP#2
270 Slab thickening at stair 5'x2'x1' deep	6	LOC	\$2,500.00	BP#2
271 Slab on grade at loading dock, 6" thick, #4 bars	350	SF		
272 Concrete; material	6	CY	\$135.00	BP#2
273 Concrete; place & finish	350	SF	\$2.85	BP#2
274 Reinforcement; #4@12"bew	469	LBS	\$1.45	BP#2
275 Miscellaneous				
276 Concrete ramp @ Auditorium	2,440	SF	\$18.00	BP#2
277 Sloped walkway @ Cohort/Learning Common/Stage	320	SF	\$20.00	BP#2
278 Housekeeping & mechanical equipment pads	1	LS	\$5,000.00	BP#2
279 Miscellaneous concrete				BP#2

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>280</b>				
<b>281</b> B1010 UPPER FLOOR CONSTRUCTION				
<b>282</b> Concrete				
<b>283</b> Slab on deck topping, 3¼" light weight, WWF	69,572	SF		
<b>284</b> Concrete; material	966	CY	\$135.00	BP#2
<b>285</b> Reinforcement (6x6 mesh)	76,529	SF	\$1.00	BP#2
<b>286</b> Rebar at corners and openings	3,826	LBS	\$1.15	BP#2
<b>287</b> Concrete; place & finish	69,572	SF	\$5.00	BP#2
<b>288</b> Beam pocket	23	EA	\$750.00	BP#2
<b>289</b>				
<b>290</b> Concrete				
<b>291</b> Slab on deck topping, 3¼" light weight, WWF	1,600	SF		
<b>292</b> Concrete; material	22	CY	\$135.00	BP#2
<b>293</b> Reinforcement (6x6 mesh)	1,760	SF	\$1.00	BP#2
<b>294</b> Rebar at corners and openings	88	LBS	\$1.15	BP#2
<b>295</b> Concrete; place & finish	1,600	SF	\$5.00	BP#2
<b>296</b>				
<b>297</b> slab on grade power troweled concrete at seats	2,240	SF	\$9.00	\$20,160
<b>298</b>				
<b>299</b> PC; power troweled concrete @ Makerspace, Auditorium, AV	2,018	SF	\$9.00	BP#2
<b>300</b>				
<b>301</b> <b>03 30 00 Cast-In-Place Concrete Total</b>				<b>\$45,648</b>
<b>302</b>				
<b>303</b>				
<b>304</b> <b>04-MASONRY</b>				
<b>305</b>				
<b>306</b> <b>04 20 00 Unit Masonry</b>				
<b>307</b> 12" CMU wall reinforced; Gym & Auditorium, double hgt	7,942	SF	\$28.00	\$222,376
<b>308</b> 8" CMU wall, load bearing wall @ Auditorium	1,284	SF	\$24.00	\$30,816
<b>309</b> Stairs/elevator CMU wall	3,266	SF	\$24.00	\$78,384
<b>310</b> Premium for Acoustical Block	1,000	SF	\$6.00	\$6,000
<b>311</b> Exterior brick wall; scored brick veneer, "modular" 8x8x4 , and "utility" 4x12x4, iron spot finish	17,333	SF	\$35.00	\$606,655
<b>312</b> Exterior CMU wall; 8x12x16 , 4x8x16, and "utility" 4x12x4	24,140	SF	\$29.83	\$720,096
<b>313</b> 12" Reinforced ground face CMU wall backup @ Auditorium & Gym	14,805	SF	\$26.00	\$384,930
<b>314</b> Cont galv relieving angle at masonry wall	1,038	LF	\$100.00	BP#2
<b>315</b> 4" Utility brick, both sides @ parapet wall, Main Entrance	175	SF	\$32.00	\$5,600
<b>316</b> Precast colored coping on top of parapet wall	26	LF	\$150.00	\$3,900
<b>317</b> Premium for custom brick and CMU @ lintels & shelves	1,128	LF	\$50.00	\$56,400
<b>318</b> Precast planter	50	LF	\$750.00	\$37,500
<b>319</b> Through wall sheet metal flashing	1,424	LF	\$25.00	\$35,600

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
320 Exterior mockup	1	LS	\$50,000.00	\$50,000
321 Temporary	1	LS	\$100,000.00	\$100,000
322 <b>04 20 00 Unit Masonry Total</b>				<b>\$2,338,257</b>
323				
324				
325 <b>05-METALS</b>				
326				
327 <b>05 12 00 Structural Steel Framing</b>				
328 Structural Steel Framing	793	TNS		
329 Steel floor framing				
330 Wide flange beams	243	TNS	\$3,700.00	BP#2
331 Wide flange beams > 100	36	TNS	\$3,950.00	BP#2
332 HSS-shapes	47	TNS	\$4,150.00	BP#2
333 W-shapes ; columns	14	TNS	\$3,950.00	BP#2
334 HSS-shapes; columns	101	TNS	\$4,150.00	BP#2
335 HSS brace frames	40	TNS	\$4,250.00	BP#2
336 Remainder of steel framing; beams, columns, bridging	26	TNS	\$4,150.00	BP#2
337 Plates, bent plates and angles	133	EA	\$75.00	BP#2
338 Moment connections	157	EA	\$750.00	BP#2
339 Shear studs	10,170	EA	\$5.50	BP#2
340 3" deep x 18ga galv composite floor deck	71,172	SF	\$4.25	BP#2
341				
342 Structural steel roof framing	286	TNS		
343 Wide flange beams	124	TNS	\$3,650.00	BP#2
344 Wide flange beams > 100	87	TNS	\$3,900.00	BP#2
345 HSS-shape	18	TNS	\$4,100.00	BP#2
346 Support post HSS7.625x0.375; RTU screen	2	TNS	\$4,100.00	BP#2
347 L- ledger; L4x4x1/4 anchored to CMU, roof	1	TNS	\$3,550.00	BP#2
348 Roof steel framing incl's hanger support beam, 52DLH17, HSS trus	42	TNS	\$4,100.00	BP#2
349 Add reinforcement 7#/sf hot dip galv steel @ RTU	12	TNS	\$4,100.00	BP#2
350 Moment connections	241	EA	\$750.00	BP#2
351 Roof hanger @ main roof	47	EA	\$1,500.00	BP#2
352 3/4" rod hanger @ Gym and Auditorium roof	11	EA	\$1,500.00	BP#2
353 Other misc plates, connections	65,518	SF	\$4.50	BP#2
354 Premium for galv steel framing	14	TNS	\$500.00	BP#2
355 3" deep x 18ga galv comp roof deck (w/conc topping)	40,338	SF	\$4.25	BP#2
356 R3; 3" 18 ga roof deck above Learning Commons	8,610	SF	\$4.25	BP#2
357 R3C; 3" Cellular 18/16 ga roof deck, galv at Auditorium	7,615	SF	\$4.25	BP#2
358 R1.5; 1.5" 20 ga roof deck, Gym equipment storage	835	SF	\$6.00	BP#2
359 R1.5A; 1.5" Cellular acoustic 20 ga roof deck, galv at Gym	8,120	SF	\$6.50	BP#2
360				
361 Roof screen, galv; HSS shapes	15	TNS	\$3,950.00	BP#2

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>362 05 12 00 Structural Steel Framing Total</b>				
<b>363</b>				
<b>364 05 31 00 Steel Decking</b>				
<b>365</b> With Structural Steel				
<b>366 05 31 00 Steel Decking Total</b>				
<b>367</b>				
<b>368 05 40 00 Cold-Formed Metal Framing</b>				
<b>369</b> Light gage metal framing				Div 09
<b>370 05 40 00 Cold-Formed Metal Framing Total</b>				
<b>371</b>				
<b>372 05 50 00* Miscellaneous and Ornamental Iron</b>				
<b>373</b> Interior guardrails				
<b>374</b> Handrailing	150	LF	\$200.00	\$30,000
<b>375</b> Guardrail in Common areas	365	LF	\$103.00	\$37,595
<b>376</b> Guardrails at lockers	1,000	LF	\$550.00	BP#2
<b>377</b> Railings in auditorium	1	LS	\$35,000.00	\$35,000
<b>378</b> Trim detail	10,805	LF	\$15.00	\$162,075
<b>379</b>				
<b>380</b> Furnishings; miscellaneous metals	137,385	GSF	\$0.25	\$34,346
<b>381</b>				
<b>382</b> Elevator pit ladder	1	EA	\$1,500.00	\$1,500
<b>383</b> Elevator vent	1	EA	\$1,200.00	\$1,200
<b>384</b> Sill angles	4	EA	\$175.00	\$700
<b>385</b> Hoist beam	1	EA	\$5,000.00	\$5,000
<b>386</b>				
<b>387</b> Interior stairs				
<b>388</b> Egress stairs	6	FLT	\$25,000.00	\$150,000
<b>389</b> Monumental/open stairs #4 & #5				BP#2
<b>390</b> Monumental/open stairs #3	1	FLT	\$65,000.00	\$65,000
<b>391</b>				
<b>392</b> Stair finishes				
<b>393</b> Railings	165	LF	\$550.00	\$90,750
<b>394</b>				
<b>395</b> Miscellaneous metals for fittings	137,385	GSF	\$0.50	\$68,693
<b>396</b> Misc metals for interior construction	137,385	GSF	\$0.50	\$68,693
<b>398</b> Roof dunnage (SS)	7	TNS	\$7,500.00	BP#2
<b>399</b>				
<b>400</b> Galvanized bar grating	1,000	SF	\$55.00	BP#2
<b>401</b>				
<b>402</b> Loose lintel @ exterior wall openings	90	LF	\$200.00	\$18,000
<b>403</b> Miscellaneous metals in exterior closure	57,520	SF	\$0.50	\$28,760
<b>404</b>				

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
405 Operable partition framing support beam	633	LF	\$175.00	BP#2
406 Monumental/open stairs #4 & #5	460	LFR	\$85.00	BP#2
407 Monumental/open stairs	460	LFR	\$85.00	\$39,100
408				
409 Galvanized handrails @ ramps and steps	219	LF	\$250.00	\$54,750
410 <b>05 50 00* Miscellaneous and Ornamental Iron Total</b>				<b>\$836,941</b>
411				
412				
413 <b>06-WOOD, PLASTICS &amp; COMPOSITES</b>				
414				
415 <b>06 10 00 Rough Carpentry</b>				
416 See 09				
417 <b>06 10 00 Rough Carpentry Total</b>				
418				
419 <b>06 16 50 Gypsum Sheathing</b>				
420 Included				
421 <b>06 16 50 Gypsum Sheathing Total</b>				
422				
423 <b>06 20 00 Finish Carpentry</b>				
424 Window stools - Plam	1,250	LF	\$50.00	\$62,500
425				
426 <i>Toilets</i>				
427 Vanity counter; Toilets	319	LF	\$200.00	\$63,800
428 Vanity counter; Dressing	33	LF	\$200.00	\$6,600
429				
430 <i>Auditorium walls:</i>				
431 Plam wall panel to auditorium	2,900	SF	\$50.00	\$145,000
432 FRP; fiber reinforced panels in Kitchen	1,921	SF	\$15.00	\$28,815
433				
434 Solid epoxy backsplash	650	SF	\$75.00	\$48,750
435				
436 Wood MDF Trim	1,700	LF	\$30.00	\$51,000
437 Plam fin tube cover with lip	570	LF	\$60.00	\$34,200
438 P.lam panel wall cover at Breakout Room	330	SF	\$50.00	\$16,500
439				
440 Plam bumper w/marker tray	2,915	LF	\$100.00	\$291,500
441 Maple rail	1,600	LF	\$50.00	\$80,000
442				
443 Wall panels at auditorium	1,500	SF	\$85.00	\$127,500
444 Backsplash	1,100	SF	\$75.00	\$82,500
445				

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
446 Academic areas: classrooms, science, media, music, vocational, sped				
447 Bench; wood veneer cantilevered w/ptd supports	205	LF	\$350.00	\$73,850
448				
449 Plam admin desk, curved @ Admin	20	LF	\$500.00	\$10,000
450 Plam base cabinet	35	LF	\$205.00	\$7,175
451 Plam base cabinet; mobile on casters	175	EA	\$550.00	FF&E
452 Plam counter 24" wide	1,425	LF	\$200.00	\$285,000
453 Plam tall cabinets	4	EA	\$1,000.00	\$4,000
454 Plam tall cabinets w/tackable surface	3	EA	\$1,250.00	\$3,750
455 Plam upper cabinet	197	LF	\$175.00	\$34,475
456 Plam work counter oval @ Admin	10	LF	\$350.00	\$3,500
457 Free standing bench	34	LF	\$500.00	\$17,000
458 Display cases	5	EA	\$5,000.00	\$25,000
459 Mobil Storage	172	EA	\$1,000.00	\$172,000
460 plam custom base & upper cabinets w/solid surface counter	20	LF	\$715.00	\$14,300
461 tackable surface backsplash	160	SF	\$24.00	\$3,840
462 <b>06 20 00 Finish Carpentry Total</b>				<b>\$1,692,555</b>
463				
464 <b>06 40 00 Architectural Woodwork</b>				
465 Perforated arch grille curved @ Classrooms 1' h	1,345	LF	\$55.00	\$73,975
466 Wood cantelevered benches at classroom glazed partitions	42	EA	\$350.00	\$14,700
467 <b>06 40 00 Architectural Woodwork Total</b>				<b>\$88,675</b>
468				
469				
470 <b>07-THERMAL AND MOISTURE PROTECTION</b>				
471				
472 <b>07 00 01* Waterproofing, Dampproofing &amp; Caulking</b>				
473 <b>07 11 00 Bituminous Dampproofing</b>				
474 <b>07 13 00 Self-Adhering Waterproofing</b>				
475 <b>07 16 00 Cementitious Waterproofing</b>				
476 <b>07 27 00 Air Barrier</b>				
477 <b>07 92 00 Joint Sealants</b>				
478 2" rigid insulation to perimeter of slab	6,392	SF	\$2.65	BP#2
479 Vapor retarder under slab	76,145	SF	\$1.00	BP#2
480 Fluid applied air vapor barrier	24,140	SF	\$6.50	\$156,910
481 Fluid applied air vapor barrier	17,333	SF	\$6.50	\$112,665
482 Fluid applied air vapor barrier	4,578	SF	\$6.50	\$29,757
483 Fluid applied air vapor barrier	3,638	SF	\$6.50	\$23,647
484 Fluid applied air vapor barrier	6,581	SF	\$6.50	\$42,777
485 Caulking and sealants at corrugated metal panel	4,578	SF	\$0.65	\$2,976
486 Caulking and sealants at composite metal panel	3,638	SF	\$0.65	\$2,365

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
487 Caulking and sealants at Trespa cladding	6,581	SF	\$0.65	\$4,278
488 Caulking and sealants at brick & CMU	41,473	SF	\$0.65	\$26,957
489 Window caulking	7,906	LF	\$3.00	\$23,718
490 Waterproofing elevator pit	225	SF	\$18.00	\$4,050
491 Damp proofing to foundation walls	10,195	SF	\$4.50	\$45,879
492 <b>07 00 01* Waterproofing, Dampproofing &amp; Caulking Total</b>				<b>\$475,977</b>
493				
494 <b>07 00 02* Roofing &amp; Flashing</b>				
495 <b>07 54 00 Thermoplastic Membrane Roofing</b>				
496 <b>07 62 00 Sheet Metal Flashing and Trim</b>				
497 <b>07 72 00 Roof Accessories</b>				
498 Single-ply PVC membrane roofing system	65,518	SF		
499 Type 1; Main roof, lower roof	36,386	SF	\$13.25	\$482,115
500 Type 2; Gym	8,955	SF	\$13.25	\$118,654
501 Type 3; Raised roof above Learning Commons	8,610	SF	\$13.25	\$114,083
502 Type 4; Entry walkway & Terrace	1,216	SF	\$13.25	\$16,105
503 Type 5; Auditorium	7,615	SF	\$13.25	\$100,899
504 Vertical roof membrane, 5'-6" h at raised roof	2,736	SF	\$14.25	\$38,988
505 ½" roof cover board	65,518	SF	\$2.25	\$147,414
506 6" insulation	64,302	SF	\$2.50	\$160,755
507 Vapor retarder	65,518	SF	\$1.50	\$98,276
508 Add ½" fire rated roof board @ Auditorium, Gym & raised roof are	17,565	SF	\$2.75	\$48,304
509 Add 2 layers ½" fiber cement roof board @ Auditorium	7,615	SF	\$5.00	\$38,075
510 Add acoustic insulation in flutes @ Auditorium & Gym roof deck	16,570	SF	\$1.50	\$24,855
511 Precast concrete pavers over adjustable deck pedestal system @ r	1,216	SF	\$45.00	\$54,698
512 Glass canopy	82	SF	\$150.00	(\$58,000)
513 Prefinished aluminum fascia/roof edge	3,054	LF	\$50.00	\$152,700
514 Roof expansion joint	1	AL	\$15,000.00	\$15,000
515				
516 <i>Roofing Accessories</i>				
517 Roof hatch	2	EA	\$3,000.00	\$6,000
518 Paver walkway	745	SF	\$25.00	\$18,625
519 <b>07 00 02* Roofing &amp; Flashing Total</b>				<b>\$1,577,545</b>
520				
521 <b>07 42 00 Wall Panels</b>				
522 <b>07 42 10 Aluminum Composite Metal Panels</b>				
523 Corrugated metal panel w/exposed fasteners	4,578	SF	\$50.00	\$228,900
524 5" Fiberglass thermal Z-furring	4,578	SF	\$3.50	\$16,023
525 Corrugated perforated metal; mechanical RTU screen	1,678	SF	\$50.00	\$83,900
526 Composite metal panel w/exposed fasteners	3,638	SF	\$75.00	\$272,850
527 5" Fiberglass thermal Z-furring	3,638	SF	\$3.50	\$12,733
528				



# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
529 Wood grain phenolic panel - Trespa @ ext wall incl's projections/	6,581	SF	\$82.00	\$539,642
530 5" Fiberglass thermal Z-furring	6,581	SF	\$3.50	\$23,034
531				
532 Phenolic panel; Ext soffit at projection/window bay	1,250	SF	\$82.00	\$102,500
533 Furring	1,250	SF	\$4.25	\$5,313
534 4" mineral fiber insulation at Trespa cladding - Exterior soffit	1,250	SF	\$4.00	\$5,000
535 <b>07 42 00 Wall Panels Total</b>				<b>\$1,289,894</b>
536				
537 <b>07 81 00 Applied Fireproofing</b>				
538 Spray fireproofing	135,000	SF	\$2.30	\$310,500
539 Intumescent fireproofing	1	LS	\$85,000.00	\$85,000
540 <b>07 81 00 Applied Fireproofing Total</b>				<b>\$395,500</b>
541				
542 <b>07 84 10 Penetration Firestopping</b>				
543 See 09				
544 <b>07 84 10 Penetration Firestopping Total</b>				
545				
546				
547 <b>08-OPENINGS</b>				
548				
549 <b>08 11 10 Hollow Metal Doors and Frames</b>				
550 Security gate 7'-0" x 7'-10", steel @ 1st Floor Corridors	2	EA	\$975.00	\$1,950
551 Hollow Metal Doors:				
552 type B1, single	41	EA	\$325.00	\$13,325
553 type B2, pair	6	EA	\$650.00	\$3,900
554 HM frames	260	EA	\$225.00	\$58,500
555 HM frames for pair doors	29	EA	\$275.00	\$7,975
556 Wood Doors:				
557 type B1, single, wood	91	EA	\$325.00	\$29,575
558 same as above w/applied surface both sides	13	EA	\$775.00	\$10,075
559 type B1, 5'-0" x 26'-0" swinging panel @ AV rooms	2	EA	\$25,000.00	\$50,000
560 type B2, pair, wood	13	EA	\$650.00	\$8,450
561 type C1, single, wood w/full height glass	111	EA	\$400.00	\$44,400
562 type C2, pair, w/full height glass	9	EA	\$800.00	\$7,200
563 type C3, pair, w/vision panel 0'-5" x 6'-0"	1	EA	\$800.00	\$800
564				
565 Exterior HM doors; complete	45	LEAF		
566 Type A, single	1	LEAF	\$1,800.00	\$1,800
567 Type B1, single	5	LEAF	\$1,800.00	\$9,000
568 Type B2, pair	9	PR	\$3,600.00	\$32,400
569 Type B2, 10'-0" x 8'-6" @ Receiving	1	PR	\$5,000.00	\$5,000
570 <b>08 11 10 Hollow Metal Doors and Frames Total</b>				<b>\$284,350</b>

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
571				
572 <b>08 14 00 Flush Wood Doors</b>				
573 <b>08 34 70 Interior Sound Control Door Assemblies</b>				
574 <i>Premium cost for acoustical doors</i>	40	LOC	\$250.00	\$10,000
575 <b>08 14 00 Flush Wood Doors Total</b>				<b>\$10,000</b>
576				
577 <b>08 31 10 Access Doors &amp; Frames</b>				
578 <i>Access doors</i>	100	EA	\$300.00	\$30,000
579 <b>08 31 10 Access Doors &amp; Frames Total</b>				<b>\$30,000</b>
580				
581 <b>08 33 10 Overhead Coiling Doors</b>				
582 <b>08 33 10 Overhead Coiling Grilles</b>				
583 <i>Coiling drapery, security screen</i>				
584 <i>Cafeteria/Learning Commons; 21'-0" x 8'-0" (2 ea)</i>	336	SF	\$55.00	\$18,480
585 <i>Kitchen; 40'-0" x 8'-0" (1 ea)</i>	320	SF	\$55.00	\$17,600
586 <i>Admin area; 21'-0" x 5'-6" (1 ea)</i>	116	SF	\$55.00	\$6,353
587				
588 <i>OH door, 12'-0" x 10'-6" motor operated @ Makerspace</i>	1	EA	\$8,000.00	\$8,000
589 <b>08 33 10 Overhead Coiling Doors Total</b>				<b>\$50,433</b>
590				
591 <b>08 00 01* Metal Windows</b>				
592 <b>08 41 10 Aluminum-Framed Entrances and Storefronts</b>				
593 <b>08 44 10 Glazed Aluminum Curtain Walls</b>				
594 <b>08 45 23 Fiberglass-Sandwich-Panel Assemblies</b>				
595 <b>08 51 10 Aluminum Windows</b>				
596 <i>Aluminum entry doors including hardware</i>	17	LEAF		
597 <i>Type SF1, single</i>	7	LEAF	\$3,500.00	\$24,500
598 <i>Type SF2, pair</i>	5	PR	\$7,000.00	\$35,000
599 <i>School guard premium</i>	5	LVS	\$1,000.00	\$5,000
600				
601 <i>Aluminum-Framed Entrances and Storefronts, interior</i>				
602 <i>type SF1, single, aluminum/glass</i>	3	EA	\$2,500.00	\$7,500
603 <i>type SF2, pair, aluminum/glass</i>	2	PR	\$5,000.00	\$10,000
604 <i>School guard doors, premium</i>	6	LVS	\$1,000.00	\$6,000
605				
606 <i>Aluminum storefronts, double glazed w/security insul glazing, sch</i>	919	SF		
607 <i>Type 10A; 24'-8 1/4" x 12'-0"</i>	1	EA	\$32,800.00	\$32,800
608 <i>Type 11A; 9'-6 1/4" x 12'-0"</i>	1	EA	\$12,600.00	\$12,600
609 <i>Type 12A; 9'-7 1/2" x 12'-0"</i>	2	EA	\$11,100.00	\$22,200
610 <i>Type 13A; 7'-6" x 12'-0"</i>	1	EA	\$9,900.00	\$9,900
611 <i>Type 16A; 12'-0" x 13'-0 1/2"</i>	1	EA	\$17,200.00	\$17,200
612 <i>Bay windows</i>	2,912	SF		

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
613 Type 1; 9'-3" x 12'-0"	10	EA	\$11,700.00	\$117,000
614 Type 2; 9'-3" x 12'-0"	11	EA	\$11,700.00	\$128,700
615 Type 2A; 9'-3" x 11'-0 1/4"	2	EA	\$11,200.00	\$22,400
616 Type 3; 9'-3" x 11'-6"	9	EA	\$11,200.00	\$100,800
617 Type 3C; 7'-0" x 12'-0"	1	EA	\$8,900.00	\$8,900
618 Curtain wall/Windows	8,799	SF		
619 Type 4; 3'-0" x 10'-1"	57	EA	\$3,000.00	\$171,000
620 Type 5A; 3'-11" x 12'-0"	6	EA	\$5,100.00	\$30,600
621 Type 5B; 3'-11" x 11'-6"	22	EA	\$5,100.00	\$112,200
622 Type A1; 1'-4" x 3'-0"	1	EA	\$400.00	\$400
623 Type A2; 2'-0" x 4'-0"	1	EA	\$900.00	\$900
624 Type A3; 2'-0" x 12'-0"	27	EA	\$2,300.00	\$62,100
625 Type B1; 3'-4" x 12'-0"	10	EA	\$3,800.00	\$38,000
626 Type B1A; 3'-4" x 5'-10"	2	EA	\$1,600.00	\$3,200
627 Type B3; 3'-4" x 7'-0"	1	EA	\$2,600.00	\$2,600
628 Type B4; 3'-4" x 12'-0"	9	EA	\$3,800.00	\$34,200
629 Type C1; 3'-4" x 12'-0"	14	EA	\$3,800.00	\$53,200
630 Type D1; 5'-4" x 6'-2"	2	EA	\$3,600.00	\$7,200
631 Type D3; 5'-4" x 12'-0"	12	EA	\$6,200.00	\$74,400
632 Type E1; 5'-4" x 10'-0"	3	EA	\$6,200.00	\$18,600
633 Type E2; 5'-4" x 12'-0"	6	EA	\$6,200.00	\$37,200
634 Type F1; 7'-4" x 6'-2"	1	EA	\$5,000.00	\$5,000
635 Type F2; 7'-4" x 10'-0"	3	EA	\$8,100.00	\$24,300
636 Type F3; 7'-4" x 12'-0"	7	EA	\$8,500.00	\$59,500
637 Type G1; 7'-4" x 12'-0"	11	EA	\$8,500.00	\$93,500
638 Type H1; 9'-4" x 6'-0"	1	EA	\$6,200.00	\$6,200
639 Type H2; 9'-4" x 10'-0"	1	EA	\$10,800.00	\$10,800
640 Type H3; 9'-4" x 12'-0"	1	EA	\$12,300.00	\$12,300
641 Type I1; 9'-4" x 6'-0"	1	EA	\$6,200.00	\$6,200
642 Type I2; 9'-4" x 10'-0"	1	EA	\$10,800.00	\$10,800
643 Type I3; 9'-4" x 12'-0"	1	EA	\$10,800.00	\$10,800
644 Type K1; 11'-4" x 12'-0"	2	EA	\$15,000.00	\$30,000
645 Type L1; 13'-4" x 12'-0"	1	EA	\$15,400.00	\$15,400
646 Type M1; 10'-4" x 6'-2"	1	EA	\$7,000.00	\$7,000
647 Type N1; 6'-4" x 4'-4"	2	EA	\$3,100.00	\$6,200
648 Type N2; 6'-4" x 5'-10"	2	EA	\$4,100.00	\$8,200
649 Type O1; 6'-4" x 12'-0"	2	EA	\$8,400.00	\$16,800
650 Type Q1; 4'-4" x 7'-0"	1	EA	\$3,300.00	\$3,300
651 Type R1; 3'-4" x 6'-11" irregular shape	1	EA	\$2,500.00	\$2,500
652 Bandshell (windows only)	1	AL	\$80,000.00	\$80,000
653				
654 Glazed aluminum-framed skylight	4,015	SF	\$150.00	\$602,250

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
655				
656 Interior storefront				
657 Storefront @ vestibule	3,115	SF	\$85.00	\$264,775
658				
659 <b>08 00 01* Metal Windows Total</b>				<b>\$2,482,125</b>
660				
661 <b>08 63 00 Metal-Framed Skylights</b>				
662 See 08 00 01				
663 <b>08 63 00 Metal-Framed Skylights Total</b>				
664				
665 <b>08 71 00 Door Hardware</b>				
666 Interior:				
667 Hardware	318	SET	\$750.00	\$238,500
668 Powered door openers	4	LOC	\$3,500.00	\$14,000
669 CR; Card reader	15	EA	\$3,000.00	\$45,000
670 RDL; Remote door un/lock	14	EA	\$3,000.00	\$42,000
671				
672 Exterior:				
673 Card reader	3	EA	\$3,500.00	\$10,500
674 RDL; Remote door un/lock	16	EA	\$3,500.00	\$56,000
675 <b>08 71 00 Door Hardware Total</b>				<b>\$406,000</b>
676				
677 <b>08 00 02* Glass and Glazing</b>				
678 <b>08 80 00 Glazing</b>				
679 Door sidelights	900	SF	\$65.00	\$58,500
680 Glazing to doors	1,554	SF	\$65.00	\$101,010
681				
682 Interior windows				
683 Interior	5,215	SF	\$65.00	\$338,975
684 Glazed film	4,332	SF	\$5.00	\$21,660
685 Ballistic glass sliding window @ Admin	1	EA	\$2,500.00	\$2,500
686 Mirror frameless	1,454	SF	\$45.00	\$65,430
687 Graduated glass; premium	2,359	SF	\$50.00	\$117,950
688 Acoustical glass premium	505	SF	\$100.00	\$50,500
689 Breakout Space-A, B & C; Glazed	2,300	SF	\$100.00	\$230,000
690 <b>08 00 02* Glass and Glazing Total</b>				<b>\$986,525</b>
691				
692 <b>08 90 00 Louvers and Vents</b>				
693 Metal louver	625	SF	\$85.00	\$53,125
694 <b>08 90 00 Louvers and Vents Total</b>				<b>\$53,125</b>
695				
696				

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>697 09-FINISHES</b>				
<b>698</b>				
<b>699 09 29 00 Gypsum Drywall</b>				
<b>700 06 10 00 Rough Carpentry</b>				
<b>701</b> Furnishings; miscellaneous wood blocking	<b>137,385</b>	GSF	\$0.25	\$34,346
<b>702</b> Blocking at doors	<b>5,406</b>	LF	\$5.00	\$27,030
<b>703</b> Door Installation	<b>318</b>	EA	\$200.00	\$63,600
<b>704</b> Rough carpentry internal partitions and ceilings	<b>137,385</b>	GSF	\$1.50	\$206,078
<b>705</b> Blocking for openings	<b>7,906</b>	LF	\$8.00	\$63,248
<b>706</b> Rough carpentry/wood blocking to roof	<b>5,138</b>	LF	\$10.00	\$51,380
<b>707</b>				
<b>708</b> Firestopping	<b>137,385</b>	GSF	\$0.30	\$41,216
<b>709</b> Interior penetration firestopping				
<b>710</b> Top-of-partition firestopping	<b>137,385</b>	GSF	\$1.50	\$206,078
<b>711</b>				
<b>712</b> 3" Faced rigid cellular polyiso insulation	<b>17,333</b>	SF	\$4.00	\$69,332
<b>713</b> 3" Faced rigid cellular polyiso insulation	<b>24,140</b>	SF	\$4.00	\$96,560
<b>714</b> 4" Mineral fiber insulation	<b>4,578</b>	SF	\$4.50	\$20,601
<b>715</b> 4" Mineral fiber insulation	<b>3,638</b>	SF	\$4.50	\$16,371
<b>716</b> 4" Mineral fiber insulation at Trespa cladding -	<b>6,581</b>	SF	\$4.50	\$29,615
<b>717</b> 6" insulation	<b>64,302</b>	SF	\$2.50	\$160,755
<b>718</b>				
<b>719</b> <i>Gypsum board partitions</i>	<b>114,616</b>	<i>SF</i>		
<b>720</b> Type B3; 3 5/8" metal stud, 5/8" GWB	<b>203</b>	SF	\$8.75	\$1,776
<b>721</b> Type B4; same as type B3, add batt insulation	<b>5,145</b>	SF	\$10.25	\$52,736
<b>722</b> Type C2; 3 5/8" metal stud, 2x 5/8" GWB	<b>5,600</b>	SF	\$11.00	\$61,600
<b>723</b> Type C3; 3 5/8" metal stud, 2x 5/8" GWB, batt insulation	<b>6,483</b>	SF	\$12.50	\$81,038
<b>724</b> Type C4; same as type C3, add 1hr fire rated	<b>3,165</b>	SF	\$13.00	\$41,145
<b>725</b> Type C6; 6" metal stud, 2x 5/8" GWB, batt insulation	<b>2,468</b>	SF	\$14.50	\$35,786
<b>726</b> Type C7; same as type C6, add 1hr fire rated	<b>5,507</b>	SF	\$15.00	\$82,605
<b>727</b> Type C8; 8" metal stud, 2x 5/8" GWB, batt insulation	<b>172</b>	SF	\$17.50	\$3,010
<b>728</b> Type C10; 10" metal stud, 2x 5/8" GWB, batt insulation	<b>222</b>	SF	\$19.50	\$4,329
<b>729</b> Type D3; 3 5/8" metal stud, 2x 5/8" GWB, batt insulation	<b>1,526</b>	SF	\$12.50	\$19,075
<b>730</b> Type D6; 6" metal stud, 2x 5/8" GWB, batt insulation	<b>1,266</b>	SF	\$14.50	\$18,357
<b>731</b> Type E3; 3 5/8" metal stud, 3x 5/8" GWB, batt insulation	<b>23,327</b>	SF	\$14.75	\$344,073
<b>732</b> Type E4; same as type E3, add 1hr fire rated	<b>780</b>	SF	\$15.75	\$12,285
<b>733</b> Type E6; 6" metal stud, 3x 5/8" GWB, batt insulation	<b>1,158</b>	SF	\$17.00	\$19,686
<b>734</b> Type E7; 10" metal stud, 3x 5/8" GWB, batt insulation	<b>1,022</b>	SF	\$21.00	\$21,462
<b>735</b> Type E8; 8" metal stud, 3x 5/8" GWB, batt insulation	<b>18,060</b>	SF	\$19.00	\$343,140
<b>736</b> Type E9; same as type E8, add 1hr fire rated	<b>2,710</b>	SF	\$19.50	\$52,845
<b>737</b> Type F1; 3 5/8" metal stud, 4x 5/8" GWB, batt insulation	<b>4,988</b>	SF	\$16.95	\$84,547
<b>738</b> Type F2; same as type F1, add 1hr fire rated	<b>1,834</b>	SF	\$17.95	\$32,920

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
739 Type F6; 6" metal stud, 4x 5/8" GWB, batt insulation	9,646	SF	\$18.95	\$182,792
740 Type F7; 8" metal stud, 4x 5/8" GWB, batt insulation	227	SF	\$20.95	\$4,756
741 Type F8; same as type F7, add 1hr fire rated	1,065	SF	\$21.45	\$22,844
742 Type H4; 4" metal C-H stud, 3x 5/8" GWB, batt insulation, 2hr rate	67	SF	\$17.25	\$1,156
743 Type H6; 6" metal C-H stud, 3x 5/8" GWB, batt insulation, 2hr rate	1,561	SF	\$19.25	\$30,049
744 Type J1; 2 x (3 5/8" metal stud, 5/8" GWB, batt insulation)	6,552	SF	\$20.50	\$134,316
745 Type J2; same as type J1	1,157	SF	\$20.50	\$23,719
746 Type K1; 2 x (3 5/8" metal stud, 2x5/8" GWB, batt insulation)	6,245	SF	\$25.00	\$156,125
747 Type K2; same as typeK1, add 1hr fire rated	2,460	SF	\$25.50	\$62,730
748				
749				
750 Breakout framing	15,812	SF	\$28.00	\$442,736
751				
752 Roof soffit/fascia framing	500	LF	\$165.00	\$82,500
753 ½" Fiberglass faced gypsum sheathing	26,668	SF	\$2.00	\$53,336
754 10" Cold formed metal framing	26,668	SF	\$15.00	\$400,020
755 ⅝" GWB interior of exterior wall	26,668	SF	\$2.50	\$66,670
756				
757 ½" Fiberglass faced gypsum sheathing	4,578	SF	\$2.00	\$9,156
758 10" Cold formed metal framing	4,578	SF	\$15.00	\$68,670
759 ⅝" GWB interior of exterior wall	4,578	SF	\$2.50	\$11,445
760				
761 ½" Fiberglass faced gypsum sheathing	3,638	SF	\$2.00	\$7,276
762 10" Cold formed metal framing	3,638	SF	\$15.00	\$54,570
763 ⅝" GWB interior of exterior wall	3,638	SF	\$2.50	\$9,095
764				
765 ½" Fiberglass faced gypsum sheathing	6,581	SF	\$2.00	\$13,162
766 10" Cold formed metal framing	6,581	SF	\$15.00	\$98,715
767 ⅝" GWB interior of exterior wall	6,581	SF	\$2.50	\$16,453
768				
769 1/2" sheathing at Trespa cladding - Exterior soffit	1,250	SF	\$15.00	\$18,750
770 6" Metal stud at Trespa cladding - Exterior soffit	1,250	SF	\$16.00	\$20,000
771 5/8 GWB at Trespa cladding - Exterior soffit	1,250	SF	\$15.00	\$18,750
772				
773 Mockup	1	AL	\$25,000.00	\$25,000
774 GWB soffit, light cove	1,320	LF	\$35.00	\$46,200
775 Shadow relief	125	LF	\$1,200.00	\$150,000
776 GWB ceiling/soffit in classrooms	16,127	SF	\$32.00	\$516,064
777 Sloped GWB soffit @ Art.	175	SF	\$18.00	\$3,150
778 Suspended plam clouds	4,950	SF	\$55.00	\$272,250
779 Premium for resilient ceiling	5,500	SF	\$5.00	\$27,500
780 Gym ceiling; suspended lay in pre painted tegular edge tectum pla	2,101	SF	\$18.00	\$37,823

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
781 B1; GWB ceiling @ Atrium	6,402	SF	\$22.00	\$140,844
782 <b>09 29 00 Gypsum Drywall Total</b>				<b>\$5,627,244</b>
783				
784 <b>09 30 00* Tiling</b>				
785 Quarry tile at Kitchen	1,705	SF	\$25.00	\$42,625
786 Porcelain tile flooring	5,500	SF	\$35.00	\$192,500
787 Tile base	2,235	LF	\$18.00	\$40,230
788 Threshold	1	LS	\$10,000.00	\$10,000
789 Wall tile	1,701	SF	\$22.00	\$37,422
790 <b>09 30 00* Tiling Total</b>				<b>\$322,777</b>
791				
792 <b>09 50 01* Acoustical Ceilings</b>				
793 <b>09 51 10 Cementitious Wood Fiber Ceiling Panel</b>				
794 <b>09 51 13 Acoustical Panel Ceilings</b>				
795 <b>09 51 33 Metal Ceiling System</b>				
796 ACT ceilings at Corridors, Public, Admin areas, Teacher Pl	51,004	SF	\$5.00	\$255,020
797 ACT ceiling, washable in kitchen	1,705	SF	\$5.25	\$8,951
798 Circulation Corridors ceiling	12,581	SF	\$32.00	\$402,592
799 A1; ACT - MR ceiling at Toilets	6,869	SF	\$5.75	\$39,498
800 Lay in ACT ceiling at band/chorus	4,550	SF	\$5.00	\$22,750
Deduct for alt	-1	AL	40000	-40000
801 Staging	1	LS	\$75,000.00	\$75,000
802 <b>09 50 01* Acoustical Ceilings Total</b>				<b>\$763,811</b>
803				
804 <b>09 60 01* Resilient Flooring</b>				
805 <b>09 65 00 Resilient Floor Tile</b>				
806 <b>09 65 13 Resilient Wall Base &amp; Accessories</b>				
807 <b>09 65 66 Resilient Athletic Flooring</b>				
808 Linoleum treads & risers with rubber nosing	828	LFR	\$15.50	\$12,834
809 Linoleum tile at landings	1,717	SF	\$8.00	\$13,736
810 Acoustic underlayment under resilient flooring	36,505	SF	\$4.00	\$146,020
811 LT; Linoleum tile flooring, 13" x 13"	73,152	SF	\$7.00	\$512,064
812 LP; Plank linoleum flooring	1,100	SF	\$12.00	\$13,200
813				
814 Linoleum base	12,630	LF	\$7.00	\$88,410
815				
816 Vented rubber wall base	375	LF	\$3.00	\$1,125
817 <b>09 60 01* Resilient Flooring Total</b>				<b>\$787,389</b>
818				
819 <b>09 64 00 Wood Flooring</b>				
820 Stage wood flooring: 4" hardboard assembly- recessed:	1,590	SF	\$30.50	\$48,495
821 1/4" double tempered smooth both sides hardboard				

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
822 (2) layers 3/4" plywood on sleepers with insulation				
823 <b>09 64 00 Wood Flooring Total</b>				<b>\$48,495</b>
824				
825 <b>09 64 40 Wood Athletic Flooring</b>				
826 Wood athletic flooring at Gym	8,405	SF	\$25.00	\$210,125
827 <b>09 64 40 Wood Athletic Flooring Total</b>				<b>\$210,125</b>
828				
829 <b>09 67 23 Resinous Flooring</b>				
830 EP; epoxy flooring at Toilets	7,940	SF	\$15.00	\$119,100
831 <b>09 67 23 Resinous Flooring Total</b>				<b>\$119,100</b>
832				
833 <b>09 68 00 Carpeting</b>				
834 carpet at aisles	2,770	SF	\$10.00	\$27,700
835 <b>09 68 00 Carpeting Total</b>				<b>\$27,700</b>
836				
837 <b>09 72 00 Wall Coverings</b>				
838 over curved gwb partition at curved wall	3,156	SF	\$27.50	\$86,790
839 Fabric wrapped acoustic wall panels @ Music areas	1,443	SF	\$22.00	\$31,746
840 sloped fabric wrapped acoustic panel	8,359	SF	\$24.50	\$204,796
841 Cementitious wood fiber acoustical wall panel @ Gym	6,255	SF	\$20.00	\$125,100
842 Mural panorama wall cover; angeled @ Media, Admin Install				By Others
843 Wall pads with cutout for MEH units; allow	1	AL	\$1,500.00	\$1,500
844 <b>09 72 00 Wall Coverings Total</b>				<b>\$449,932</b>
845				
846 <b>09 91 00* Painting</b>				
847 Painting				
848 SC; sealed concrete at back of house	23,200	SF	\$1.75	\$40,600
849 E1; Exposed deck, painted @ Classrooms	24,380	SF	\$1.50	\$36,570
850 Gym exposed deck, painted	8,405	SF	\$2.00	\$16,810
851 Paint	137,385	GSF	\$0.75	\$103,039
852 Paint GWB ceilings w/high performance coating at Toilets	30,893	SF	\$1.10	\$33,983
853 Auditorium ceiling; painted exposed metal deck	6,600	SF	\$2.50	\$16,500
854 Epoxy paint wainscot @ Locker/Toilet	8,234	SF	\$2.00	\$16,468
855 Paint CMU wall	12,492	SF	\$1.00	\$12,492
856 Paint drywall partitions	273,034	SF	\$0.85	\$232,079
857 Paint door frames	318	EA	\$85.00	\$27,030
858 Paint door	318	EA	\$65.00	\$20,670
859 <b>09 91 00* Painting Total</b>				<b>\$556,240</b>
860				
861				
862 <b>10-SPECIALTIES</b>				
863				



# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>864</b>				
<b>865 10 00 01 Specialties</b>				
<b>866</b> Operable partitions	5,440	SF	\$55.00	\$299,200
<b>867 10 00 01 Specialties Total</b>				<b>\$299,200</b>
<b>868</b>				
<b>869 10 11 00 Visual Display Boards</b>				
<b>870</b> Tackboards	2,688	SF	\$18.00	\$48,384
<b>871</b> Markerboards	5,376	SF	\$25.00	\$134,400
<b>872</b> Tackable wall; allow	3,000	SF	\$18.00	\$54,000
<b>873</b>				
<b>874</b> Academic areas:				
<b>875</b> Magnetic writing surface	6,400	SF	\$22.00	\$140,800
<b>876 10 11 00 Visual Display Boards Total</b>				<b>\$377,584</b>
<b>877</b>				
<b>878 10 14 23 Signage</b>				
<b>879</b> Signage				
<b>880</b> Commerative plaque	2	LOC	\$1,500.00	\$3,000
<b>881</b> Dimensional characters; School name	1	AL	\$5,000.00	\$5,000
<b>882</b> Plastic panel signs for room idenfication, way finding, hazard identification	1	AL	\$7,500.00	\$7,500
<b>883</b> Framed paper signs	1	AL	\$2,180.00	\$2,180
<b>884</b> Miscellaneous signage	137,385	GSF	\$0.40	\$54,954
<b>885 10 14 23 Signage Total</b>				<b>\$72,634</b>
<b>886</b>				
<b>887 10 21 13 Plastic Toilet Compartments</b>				
<b>888</b> Toilet compartments (plastic laminate)				
<b>889</b> Toilet compartments	20	EA	\$1,200.00	\$24,000
<b>890</b> Toilet compartments - ADA	14	EA	\$1,400.00	\$19,600
<b>891</b> Urinal screen	20	EA	\$800.00	\$16,000
<b>892 10 21 13 Plastic Toilet Compartments Total</b>				<b>\$59,600</b>
<b>893</b>				
<b>894 10 21 23 Cubicle Curtains, Tracks &amp; Hardware</b>				
<b>895</b> Curtain track, carriers and curtains	2	EA	\$200.00	\$400
<b>896 10 21 23 Cubicle Curtains, Tracks &amp; Hardware Total</b>				<b>\$400</b>
<b>897</b>				
<b>898 10 26 00 Wall Protection</b>				
<b>899</b> Wall & corner guards				
<b>900</b> Stainless steel corner guards	1	LS	\$10,000.00	\$10,000
<b>901 10 26 00 Wall Protection Total</b>				<b>\$10,000</b>
<b>902</b>				
<b>903 10 28 13 Toilet Accessories</b>				
<b>904</b> Toilet accessories				

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
905 Combination PTD/WR unit	8	EA	\$150.00	\$1,200
906 Towel dispenser/waste receptacle	45	EA	\$100.00	\$4,500
907 Soap dispensers	45	EA	\$35.00	\$1,575
908 Toilet paper dispensers	48	EA	\$65.00	\$3,120
909 Sanitary napkin disposal units	21	EA	\$250.00	\$5,250
910 Robe hook	15	EA	\$25.00	\$375
911 Fold-down shower seat	1	EA	\$200.00	\$200
912 Grab bars	28	PR	\$160.00	\$4,480
913 Mirrors - in private bathrooms	14	EA	\$150.00	\$2,100
914 Mop holder w/shelf (Janitors)	6	EA	\$180.00	\$1,080
915 <b>10 28 13 Toilet Accessories Total</b>				<b>\$23,880</b>
916				
917 <b>10 44 13 Fire Protection Specialties</b>				
918 Fire extinguisher cabinets				
919 Fully recessed/non-rated	14	EA	\$450.00	\$6,182
920 Semi-recessed/non-rated	6	EA	\$300.00	\$1,800
921 <b>10 44 13 Fire Protection Specialties Total</b>				<b>\$7,982</b>
922				
923 <b>10 51 24 Phenolic-Core Lockers</b>				
924 Lockers				
925 Athletic / PE lockers: metal 2-tier 30"h. x 15"w x 15"d	50	EA	\$250.00	\$12,500
926 Kitchen staff lockers, single tier, 12" x 12" x 6' high	6	EA	\$250.00	\$1,500
927 Student lockers 15"x12"x36" w/angled top, phenolic w/plam finis	660	EA	\$600.00	\$396,000
928 Benches	500	LF	\$50.00	\$25,000
929 <b>10 51 24 Phenolic-Core Lockers Total</b>				<b>\$435,000</b>
930				
931				
932 <b>11-EQUIPMENT</b>				
933				
934 <b>11 00 00 Equipment</b>				
935 Vocational allowance	1	LS	\$100,000.00	\$100,000
936 Loading dock equipment	1	LS	\$10,000.00	\$10,000
937 Fume hoods	4	EA	\$10,000.00	\$40,000
938 <b>11 00 00 Equipment Total</b>				<b>\$150,000</b>
939				
940 <b>11 31 00 Appliances</b>				
941 Residential Appliances				
942 Refrigerator/Freezer, microwave oven	5	RMS	\$1,700.00	\$8,500
943 Dishwasher	1	EA	\$1,200.00	\$1,200
944 Undercounter refrigerator @ Nurse	1	EA	\$1,200.00	\$1,200
945 <b>11 31 00 Appliances Total</b>				<b>\$10,900</b>
946				

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>947 11 40 00 Food Service Equipment</b>				
948 Food service equipment				
949 Dining & Food Service (Budget provided, July 19, 2019)	1	AL	\$415,270.00	\$415,270
<b>950 11 40 00 Food Service Equipment Total</b>				<b>\$415,270</b>
951				
<b>952 11 52 13 Projection Screens</b>				
953 Projection Screens				
954 Motorized projection screen; Auditorium	1	EA	\$17,000.00	\$17,000
955 Projection screen - Media Center, room 1250	2	EA	\$3,000.00	\$6,000
<b>956 11 52 13 Projection Screens Total</b>				<b>\$23,000</b>
957				
<b>958 11 61 00 Theater and Stage Equipment</b>				
959 Auditorium/Theatre Equipment				
960 AV	1	AL	\$200,000.00	\$200,000
961 Lighting	1	AL	\$129,018.00	\$129,018
962 Dimming	1	AL	\$95,749.00	\$95,749
963 Rigging	1	AL	\$158,300.00	\$158,300
964 Curtains	1	AL	\$33,854.00	\$33,854
965 Orchestra	1	AL	\$175,000.00	FF&E
966 Gym AV sound system	1	AL	\$120,000.00	\$120,000
967 Cafeteria AV	1	AL	\$50,000.00	\$50,000
968 Band and chorus AV	1	AL	\$60,000.00	\$60,000
969 Aud. seating; stacked (48), fixed (321), removeable (46)	1	AL	\$106,445.00	\$106,445
<b>970 11 61 00 Theater and Stage Equipment Total</b>				<b>\$953,366</b>
971				
<b>972 11 66 23 Gymnasium Equipment</b>				
973 Gymnasium equipment				
974 Shot clock/shot timer	1	EA	\$1,250.00	\$1,250
975 Pull up bar	1	EA	\$850.00	\$850
976 Stall bar	1	EA	\$850.00	\$850
977 Vertical ladder	1	EA	\$550.00	\$550
978 Rope hoist	1	EA	\$500.00	\$500
979 Overhead mounted folding backstops w/glass backboards	6	EA	\$6,500.00	\$39,000
980 Sleeves & floor plates for badminton & volleyball uprights; allow	2	SETS	\$4,000.00	\$8,000
981 Gym equipment controls-power touch	1	LS	\$5,000.00	\$5,000
982 Gym wall safety pads to be 8'-8" high	2,634	SF	\$18.00	\$47,412
<b>983 11 66 23 Gymnasium Equipment Total</b>				<b>\$103,412</b>
984				
<b>985 11 66 53 Gymnasium Dividers</b>				
986 Gym motorized divider curtains	1	EA	\$20,000.00	\$20,000
<b>987 11 66 53 Gymnasium Dividers Total</b>				<b>\$20,000</b>
988				

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>989 11 66 80 Scoreboards</b>				
990 Electronic scoreboard	1	EA	\$7,500.00	\$7,500
<b>991 11 66 80 Scoreboards Total</b>				<b>\$7,500</b>
992				
993				
<b>994 12-FURNISHING</b>				
995				
<b>996 12 24 12 Roller Shades</b>				
997 Window treatment, manually operated roller shades	10,288	SF	\$6.00	\$61,728
998 motorized roller shades @ exterior CW and SF	1,456	SF	\$15.00	\$21,840
999 motorized shade units at skylights	4,015	SF	\$15.00	\$60,225
1000 roller shade at interior doors w/lites & glazed partitions	5,569	SF	\$6.00	\$33,414
<b>1001 12 24 12 Roller Shades Total</b>				<b>\$177,207</b>
1002				
<b>1003 12 35 53 Caswork</b>				
1004 Interior panel grille	450	LF	\$150.00	\$67,500
1005 (4) Adj shelves 12" wide melamine	602	LF	\$140.00	\$84,280
1006 (6) Adj shelves 12" wide melamine @ Media	56	LF	\$210.00	\$11,760
1007				
1008 Epoxy counter 24" wide	325	LF	\$325.00	\$105,625
1009				
1010 Mail slots, melamine	16	LF	\$250.00	\$4,000
<b>1011 12 35 53 Caswork Total</b>				<b>\$273,165</b>
1012				
<b>1013 12 48 13 Entrance Mats &amp; Frames</b>				
1014 Entrance mats				
1015 RG; Vestibule	396	SF	\$35.00	\$13,860
<b>1016 12 48 13 Entrance Mats &amp; Frames Total</b>				<b>\$13,860</b>
1017				
<b>1018 12 66 00 Telescoping Stands</b>				
1019 Motorized telescoping bleachers, motorized	760	SEAT	\$100.00	\$76,000
<b>1020 12 66 00 Telescoping Stands Total</b>				<b>\$76,000</b>
1021				
1022				
<b>1023 13-SPECIAL CONSTRUCTION</b>				
1024				
<b>1025 13 00 00 Special Construction</b>				
1026 No work in this section				
<b>1027 13 00 00 Special Construction Total</b>				
1028				
1029				
<b>1030 14-CONVEYING EQUIPMENT</b>				

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>1031</b>				
<b>1032 14 24 00* Hydraulic Elevators</b>				
<b>1033</b> Elevators; 3,500#, 4 stops	1	EA	\$215,000.00	\$215,000
<b>1034 14 24 00* Hydraulic Elevators Total</b>				<b>\$215,000</b>
<b>1035</b>				
<b>1036</b>				
<b>1037 21 - 23-MECHANICAL</b>				
<b>1038</b>				
<b>1039 21 00 00* Fire Protection</b>				
<b>1040</b> Upright Sprinkler Heads	260	EA	\$390.00	\$101,400
<b>1041</b> Pendent Sprinkler Heads	817	EA	\$415.00	\$339,055
<b>1042</b> Pendent/Upright Sprinkler Heads	120	EA	\$510.00	\$61,200
<b>1043</b> Upright Sprinkler Heads ( Gym)	70	EA	\$425.00	\$29,750
<b>1044</b> Upright Sprinkler Heads ( Auditorium)	40	EA	\$425.00	\$17,000
<b>1045</b> Upright Sprinkler Heads ( Skylights)	16	EA	\$440.00	\$7,040
<b>1046</b> Sidewall Sprinkler Heads	121	EA	\$514.00	\$62,194
<b>1047</b> Window Sprinkler Heads	22	EA	\$650.00	\$14,300
<b>1048</b> Dry Sprinkler Heads	16	EA	\$495.00	\$7,920
<b>1049</b> Additional heads	200	EA	\$495.00	\$99,000
<b>1050</b> 8" Water Service	1	EA	\$6,250.00	\$6,250
<b>1051</b> 6" Alarm Valves w/ trim	1	EA	\$5,560.00	\$5,560
<b>1052</b> 6" Backflow Preventer	1	EA	\$8,500.00	\$8,500
<b>1053</b> Zone control w/ standpipe (SCVA)	14	EA	\$3,650.00	\$51,100
<b>1054</b> 6" Riser Valves	2	EA	\$950.00	\$1,900
<b>1055</b> 6" FSP W/ Standpipe	5	EA	\$2,250.00	\$11,250
<b>1056</b> 4" FSP W/ Standpipe	3	EA	\$2,045.00	\$6,135
<b>1057</b> Fire Dept. Connections	1	EA	\$2,650.00	\$2,650
<b>1058</b> Riser Valve w/ tamper switch	2	EA	\$750.00	\$1,500
<b>1059</b> Main piping:				
<b>1060</b> - 6"	1,108	LF	\$80.00	\$88,640
<b>1061</b> Misc. Valves	1	LS	\$4,500.00	\$4,500
<b>1062</b> Commissioning	1	LS	\$1,250.00	\$1,250
<b>1063</b> Lifting	1	LS	\$3,800.00	\$3,800
<b>1064</b> Testing	1	LS	\$3,650.00	\$3,650
<b>1065</b> Coordination	1	LS	\$8,100.00	\$8,100
<b>1066</b> Coring, Sleeves & sleeves	1	LS	\$5,450.00	\$5,450
<b>1067</b> Seismic Restraints	1	LS	\$5,900.00	\$5,900
<b>1068</b> Shop drawings/hydraulic calculations	1	LS	\$8,000.00	\$8,000
<b>1069 21 00 00* Fire Protection Total</b>				<b>\$962,994</b>
<b>1070</b>				
<b>1071 22 00 00* Plumbing</b>				
<b>1072</b> 6" Water Service w/ sub metera	1	EA	\$9,500.00	\$9,500

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>1073</b> Hot Water Heater & Storage				
<b>1074</b> - WH-1	1	EA	\$65,000.00	\$65,000
<b>1075</b> - WH-2	1	EA	\$5,500.00	\$5,500
<b>1076</b> Mixing Valves	1	EA	\$2,450.00	\$2,450
<b>1077</b> Circulating Pumps	2	EA	\$1,050.00	\$2,100
<b>1078</b> Expansion Tank	1	EA	\$2,200.00	\$2,200
<b>1079</b> 4" Backflow Preventers	1	EA	\$5,560.00	\$5,560
<b>1080</b> Pressure Reducing Station	1	EA	\$3,650.00	\$3,650
<b>1081</b> 1" Backflow Preventers	2	EA	\$1,850.00	\$3,700
<b>1082</b> Grease Interceptor System 8,000 gal	1	EA	\$48,500.00	\$48,500
<b>1083</b> Grease Trap	1	EA	\$3,850.00	\$3,850
<b>1084</b> Oily Water Separator	1	EA	\$4,580.00	\$4,580
<b>1085</b> Acid Neutralization Tank	2	EA	By Others	
<b>1086</b> Condensate Pump:				
<b>1087</b> - CP-1 5 GPH	1	EA	\$950.00	\$950
<b>1088</b> Heat Tracing	1	LS	\$5,000.00	\$5,000
<b>1089</b> Elevator Sump Pump:				
<b>1090</b> - SP-1	1	EA	\$1,850.00	\$1,850
<b>1091</b> Reducer Pressure Backflow Preventer:				
<b>1092</b> - RBP-1	1	EA	\$2,500.00	\$2,500
<b>1093</b> Emergency Gas Shut Off Valve	2	EA	\$1,250.00	\$2,500
<b>1094</b> Fixtures				
<b>1095</b> Water Closet P-1	20	EA	\$2,455.00	\$49,100
<b>1096</b> Water Closet P-1A	31	EA	\$2,455.00	\$76,105
<b>1097</b> Urinal P-2	17	EA	\$2,510.00	\$42,670
<b>1098</b> Urinal P-2A	8	EA	\$2,510.00	\$20,080
<b>1099</b> Lavatory P-3	49	EA	\$2,365.00	\$115,885
<b>1100</b> Lavatory P-3A	28	EA	\$2,365.00	\$66,220
<b>1101</b> Drinking Fountain P-4	11	EA	\$3,250.00	\$35,750
<b>1102</b> Mop Sink P-5	5	EA	\$2,850.00	\$14,250
<b>1103</b> Shower P-6	2	EA	\$3,850.00	\$7,700
<b>1104</b> Science Room Sink P-7	40	EA	\$3,650.00	\$146,000
<b>1105</b> Science Room Sink P-7A	2	EA	\$3,650.00	\$7,300
<b>1106</b> Classroom Sink P-8	7	EA	\$2,565.00	\$17,955
<b>1107</b> Art Sink P-9	3	EA	\$3,250.00	\$9,750
<b>1108</b> Art Sink P-9A	1	EA	\$3,250.00	\$3,250
<b>1109</b> Eyewash/Shower P-10	5	EA	\$2,250.00	\$11,250
<b>1110</b> Fume Hood	3	EA	\$5,000.00	\$15,000
<b>1111</b> Lab Equipment	1	LS	\$25,000.00	\$25,000
<b>1112</b> labs & Consumer Science)	36	LS	\$385.00	\$13,860
<b>1113</b> Floor Clean Outs:				
<b>1114</b> - FCO-1	54	EA	\$725.00	\$39,150

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>1115</b> Floor Drains:				
<b>1116</b> - 3" FD-A	14	EA	\$1,050.00	\$14,700
<b>1117</b> - 3" FD-B	8	EA	\$1,065.00	\$8,520
<b>1118</b> - 4" FD-B	5	EA	\$1,165.00	\$5,825
<b>1119</b> Trap Primers	16	EA	\$1,250.00	\$20,000
<b>1120</b> Roof Drain:				
<b>1121</b> - 8 RD-0	2	EA	\$1,650.00	\$3,300
<b>1122</b> - 6" RD-1	12	EA	\$1,410.00	\$16,920
<b>1123</b> - 5" RD-2	4	EA	\$1,220.00	\$4,880
<b>1124</b> - 4" RD-3	8	EA	\$1,010.00	\$8,080
<b>1125</b> Cup Sinks	8	EA	\$1,850.00	\$14,800
<b>1126</b> Wall Hydrant				
<b>1127</b> - WHYD-1	18	EA	\$375.00	\$6,750
<b>1128</b> Hose Bibbs:				
<b>1129</b> - HB-1	12	EA	\$285.00	\$3,420
<b>1130</b> VTR	9	EA	\$650.00	\$5,850
<b>1131</b>				
<b>1132</b> Storm piping, below grade:				
<b>1133</b> - 12"	120	LF	\$125.00	\$15,000
<b>1134</b> - 8"	50	LF	\$85.25	\$4,263
<b>1135</b> - 6"	110	LF	\$62.55	\$6,881
<b>1136</b> - 4"	40	LF	\$43.75	\$1,750
<b>1137</b> Storm piping, above grade:				
<b>1138</b> - 10"	155	LF	\$110.00	\$17,050
<b>1139</b> - 8"	510	LF	\$92.35	\$47,099
<b>1140</b> - 6"	1,010	LF	\$65.05	\$65,701
<b>1141</b> - 4"	165	LF	\$45.10	\$7,442
<b>1142</b> Waste and vent piping, below grade:				
<b>1143</b> - 5"	650	LF	\$59.61	\$38,747
<b>1144</b> - 4"	560	LF	\$43.75	\$24,500
<b>1145</b> - 3"	265	LF	\$32.25	\$8,546
<b>1146</b> - 2"	110	LF	\$26.85	\$2,954
<b>1147</b> Waste and vent piping, above grade:				
<b>1148</b> - 4"	685	LF	\$43.10	\$29,524
<b>1149</b> - 3"	785	LF	\$31.55	\$24,767
<b>1150</b> - 2"	850	LF	\$26.25	\$22,313
<b>1151</b> Kitchen Waste Below grade:				
<b>1152</b> - 4"	510	LF	\$32.00	\$16,320
<b>1153</b> - 3"	40	LF	\$28.95	\$1,158
<b>1154</b> - 2"	290	LF	\$22.50	\$6,525
<b>1155</b> Acid Waste below grade:				
<b>1156</b> - 4"	425	LF	\$32.00	\$13,600

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>1157</b> - 2"	<b>290</b>	LF	\$18.00	\$5,220
<b>1158</b> Acid Waste below grade:				
<b>1159</b> - 4"	<b>295</b>	LF	\$32.00	\$9,440
<b>1160</b> - 3"	<b>210</b>	LF	\$28.25	\$5,933
<b>1161</b> - 2"	<b>265</b>	LF	\$18.00	\$4,770
<b>1162</b> Potable Water Piping:				
<b>1163</b> - 2-1/2"	<b>620</b>	LF	\$48.95	\$30,349
<b>1164</b> - 2"	<b>780</b>	LF	\$35.75	\$27,885
<b>1165</b> - 1-1/2"	<b>550</b>	LF	\$30.45	\$16,748
<b>1166</b> - 1-1/4"	<b>475</b>	LF	\$28.35	\$13,466
<b>1167</b> - Branch	<b>8,500</b>	LF	\$25.75	\$218,875
<b>1168</b> Insulate Potable Water Piping:				
<b>1169</b> - 2-1/2"	<b>620</b>	LF	\$16.40	\$10,168
<b>1170</b> - 2"	<b>780</b>	LF	\$15.65	\$12,207
<b>1171</b> - 1-1/2"	<b>550</b>	LF	\$14.75	\$8,113
<b>1172</b> - 1-1/4"	<b>475</b>	LF	\$14.05	\$6,674
<b>1173</b> - Branch	<b>8,500</b>	LF	\$13.75	\$116,875
<b>1174</b> Gas Piping				
<b>1175</b> - 6"	<b>50</b>	LF	\$56.25	\$2,813
<b>1176</b> - 4"	<b>80</b>	LF	\$48.95	\$3,916
<b>1177</b> - 3"	<b>120</b>	LF	\$42.25	\$5,070
<b>1178</b> - Branch	<b>980</b>	LF	\$29.65	\$29,057
<b>1179</b> Gas Hook-ups	<b>4</b>	EA	\$850.00	\$3,400
<b>1180</b> Master Gas Valves	<b>2</b>	EA	\$2,850.00	\$5,700
<b>1181</b> Pump	<b>1</b>	LS	\$25,000.00	\$25,000
<b>1182</b> Flues to water heater	<b>120</b>	LF	\$65.00	\$7,800
<b>1183</b> Generator Gas Connection	<b>1</b>	EA	\$5,000.00	\$5,000
<b>1184</b> Kitchen	<b>1</b>	LS	\$50,000.00	\$50,000
<b>1185</b> Storm Piping Insulation	<b>1</b>	LS	\$25,000.00	\$25,000
<b>1186</b> Seismic Restraints	<b>1</b>	LS	\$10,500.00	\$10,500
<b>1187</b> Lift & Hoisting	<b>1</b>	LS	\$18,500.00	\$18,500
<b>1188</b> General Requirements				
<b>1189</b> Coring, cutting and sleeves	<b>1</b>	LS	\$15,000.00	\$15,000
<b>1190</b> Commissioning	<b>1</b>	LS	\$25,000.00	\$25,000
<b>1191</b> Valves and specialties	<b>1</b>	LS	\$12,500.00	\$12,500
<b>1192</b> Permits & Fees	<b>1</b>	LS	\$7,850.00	\$7,850
<b>1193</b> Test and sterilize	<b>1</b>	LS	\$18,500.00	\$18,500
<b>1194</b> Shop drawings	<b>1</b>	LS	\$16,500.00	\$16,500
<b>1195</b> <b>22 00 00* Plumbing Total</b>				<b>\$2,126,673</b>
<b>1196</b>				
<b>1197</b> <b>23 00 00* HVAC</b>				
<b>1198</b> Boilers:				



# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>1199</b> - B-1 & 2 3,844 MBH	2	EA	\$84,568.00	\$169,136
<b>1200</b> Expantion Tank:				
<b>1201</b> - ET-1 Thru 3	3	EA	\$2,150.00	\$6,450
<b>1202</b> Air Separator:				
<b>1203</b> - AS-1 & 2 8"	2	EA	\$3,950.00	\$7,900
<b>1204</b> Buffer Tank:				
<b>1205</b> - BT-1	1	EA	\$2,500.00	\$2,500
<b>1206</b> Pumps:				
<b>1207</b> - P-1 & 2 HP 790 GPM	2	EA	\$12,500.00	\$25,000
<b>1208</b> - P-3 & 4 HP 800 GPM	2	EA		Pump House
<b>1209</b> - BP-1	2	EA	\$2,500.00	\$5,000
<b>1210</b> - CP-1 5 GPH	5	EA	\$450.00	\$2,250
<b>1211</b> Pumps House	1	EA	\$185,000.00	\$185,000
<b>1212</b>				
<b>1213</b> Chillers:				
<b>1214</b> - CH-1 350 Ton	1	EA	\$367,500.00	\$367,500
<b>1215</b> Rooftop Units:				
<b>1216</b> - RTU-1 22,000 CFM	1	EA	\$264,000.00	\$264,000
<b>1217</b> - RTU-2 22,000 CFM	1	EA	\$264,000.00	\$264,000
<b>1218</b> - RTU-3 22,000 CFM	1	EA	\$264,000.00	\$264,000
<b>1219</b> - RTU-4 22,000 CFM	1	EA	\$264,000.00	\$264,000
<b>1220</b> - RTU-5 15,000 CFM	1	EA	\$180,000.00	\$180,000
<b>1221</b> - RTU-6 12,000 CFM	1	EA	\$144,000.00	\$144,000
<b>1222</b> - RTU-7 2,000 CFM	1	EA	\$28,000.00	\$28,000
<b>1223</b> Make Up Units:				
<b>1224</b> - MAU-1 5,000 CFM	1	EA	\$32,500.00	\$32,500
<b>1225</b> Exhaust Fans:				
<b>1226</b> - EF-1 2,500 CFM	1	EA	\$3,250.00	\$3,250
<b>1227</b> - EF-2 2,500 CFM	1	EA	\$3,250.00	\$3,250
<b>1228</b> - EF-3 500 CFM	1	EA	\$980.00	\$980
<b>1229</b> - EF-4 500 CFM	1	EA	\$980.00	\$980
<b>1230</b> - EF-5 250 CFM	1	EA	\$685.00	\$685
<b>1231</b> - EF-6 250 CFM	1	EA	\$685.00	\$685
<b>1232</b> - SEF-1 50,000 CFM	1	EA	\$32,500.00	\$32,500
<b>1233</b> - SEF-2 50,000 CFM	1	EA	\$32,500.00	\$32,500
<b>1234</b> - SEF-3 50,000 CFM	1	EA	\$32,500.00	\$32,500
<b>1235</b> - SEF-4 50,000 CFM	1	EA	\$32,500.00	\$32,500
<b>1236</b> - KEF-1 4,170 CFM	1	EA	\$4,500.00	\$4,500
<b>1237</b> - FEF-1 1,200 CFM	1	EA	\$2,100.00	\$2,100
<b>1238</b> - FEF-2 1,200 CFM	1	EA	\$2,100.00	\$2,100
<b>1239</b> - FEF-3 1,200 CFM	1	EA	\$2,100.00	\$2,100
<b>1240</b> VAV Boxes:				

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>1241</b> - VAV-8	150	EA	\$1,050.00	\$157,500
<b>1242</b> Radiant Heat Panels:				
<b>1243</b> - R1	2,525	LF	\$135.00	\$340,875
<b>1244</b> Fin-Tube Radiators:				
<b>1245</b> - FT-1	100	LF	\$90.00	\$9,000
<b>1246</b> Cabinet & Unit Heaters:				
<b>1247</b> - CUH-1,2, 7 thru 16 350 MBH	12	EA	\$895.00	\$10,740
<b>1248</b> - CUH-3 1050 MBH	1	EA	\$1,150.00	\$1,150
<b>1249</b> - CUH-4 thru 6 450 MBH	3	EA	\$925.00	\$2,775
<b>1250</b> Ductless Split Units:				
<b>1251</b> - DCUe-1 1 Ton	1	EA	\$2,950.00	\$2,950
<b>1252</b> - DCUe-2 2 Ton	1	EA	\$4,425.00	\$4,425
<b>1253</b> - DCUe-3 2 Ton	1	EA	\$4,425.00	\$4,425
<b>1254</b> - DCUe-4 1.5 Ton	1	EA	\$3,850.00	\$3,850
<b>1255</b> - DCUe-5 1.5 Ton	1	EA	\$3,850.00	\$3,850
<b>1256</b> - DCUe-6 1.5 Ton	1	EA	\$3,850.00	\$3,850
<b>1257</b> - DCUe-7 1.5 Ton	1	EA	\$3,850.00	\$3,850
<b>1258</b> Register & Diffusers:				
<b>1259</b> - DD-1	22	EA	\$985.00	\$21,670
<b>1260</b> - DD-2	18	EA	\$985.00	\$17,730
<b>1261</b> - DD-3	16	EA	\$985.00	\$15,760
<b>1262</b> - DD-4	1	EA	\$985.00	\$985
<b>1263</b> - DD-5	42	EA	\$985.00	\$41,370
<b>1264</b> - DD-6	2	EA	\$985.00	\$1,970
<b>1265</b> - DD-7	4	EA	\$985.00	\$3,940
<b>1266</b> - Slot	750	LF	\$45.00	\$33,750
<b>1267</b> - E	80	EA	\$225.00	\$18,000
<b>1268</b> Misc Diffusers, grills and registers	1	LS	\$5,000.00	\$5,000
<b>1269</b> Fire & Motor Dampers	30	LS	\$1,850.00	\$55,500
<b>1270</b> Volume Dampers	1	EA	\$40,000.00	\$40,000
<b>1271</b> Flex Duct	1	LS	\$30,000.00	\$30,000
<b>1272</b> Misc. Duct Accessories	1	LS	\$25,000.00	\$25,000
<b>1273</b> Double Wall Galvanized Duct (Auditorium)	8,500	LBS	\$20.25	\$172,125
<b>1274</b> Galvanized Duct	130,000	LBS	\$12.50	\$1,625,000
<b>1275</b> Ductsox	680	LF	\$45.00	\$30,600
<b>1276</b> Duct Insulation	45,000	SF	\$4.65	\$209,250
<b>1277</b> Duct Insulation @ Kitchen area	1	LS	\$35,000.00	\$35,000
<b>1278</b> Black iron at kitchen	2,125	LBS	\$18.50	\$39,313
<b>1279</b> Duct S/S	5,000	LBS	\$20.20	\$101,000
<b>1280</b> Seal Ductwork	7,500	LF	\$1.60	\$12,000
<b>1281</b> Dust Collection System	1	LS	\$25,000.00	\$25,000
<b>1282</b> Sound Attenuators				

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
1283 - SA-1S	1	EA	\$6,500.00	\$6,500
1284 - SA-1R	1	EA	\$6,500.00	\$6,500
1285 - SA-2S	1	EA	\$6,500.00	\$6,500
1286 - SA-2R	1	EA	\$6,500.00	\$6,500
1287 - SA-3S	1	EA	\$6,500.00	\$6,500
1288 - SA-3R	1	EA	\$6,500.00	\$6,500
1289 - SA-4S	1	EA	\$6,500.00	\$6,500
1290 - SA-4R	1	EA	\$6,500.00	\$6,500
1291 - SA-5S	1	EA	\$6,500.00	\$6,500
1292 - SA-5R	1	EA	\$6,500.00	\$6,500
1293 - SA-6S	1	EA	\$7,800.00	\$7,800
1294 - SA-6R	1	EA	\$6,200.00	\$6,200
1295 - SA-7S	1	EA	\$3,850.00	\$3,850
1296 - SA-7R	1	EA	\$3,850.00	\$3,850
1297 - SA-8	1	EA	\$4,250.00	\$4,250
1298 Hot & Chilles Water Piping				
1299 - Large Bore	9,000	LF	\$40.00	\$360,000
1300 - Small Bore	10,500	LF	\$28.00	\$294,000
1301 Insulate Hot Water Piping				
1302 - Large Bore	9,000	LF	\$16.95	\$152,550
1303 - Small Bore	10,500	LF	\$12.50	\$131,250
1304 Equipment Hook-Ups:				
1305 - 4" Boilers	2	EA	\$8,950.00	\$17,900
1306 - 8" Pump		EA		Pump House
1307 - 4" Pump	3	EA	\$2,100.00	\$6,300
1308 - 8" Chiller	1	EA	\$14,500.00	\$14,500
1309 - RCP	95	EA	\$1,075.00	\$102,125
1310 - CUH	12	EA	\$1,025.00	\$12,300
1311 - FT	2	EA	\$1,075.00	\$2,150
1312 - DD	105	EA	\$285.00	\$29,925
1313 - VAV	140	EA	\$1,105.00	\$154,700
1314 - 4" RTU Coils	6	EA	\$6,500.00	\$39,000
1315 - 2" RTU Coils	3	EA	\$2,650.00	\$7,950
1316 VFD	1	LS	\$20,000.00	\$20,000
1317 Glycol:				
1318 - GF-1 & 2	2	EA	\$6,500.00	\$13,000
1319 Combustion	1	LS	\$30,000.00	\$30,000
1320 Flues S/S boiler	380	LF	\$120.00	\$45,600
1321 Seismic Restraints	1	LS	\$10,500.00	\$10,500
1322 Misc. Valves & specialties	1	LS	\$15,000.00	\$15,000
1323 Commissioning support	1	LS	\$32,000.00	\$32,000
1324 Controls	1	LS	\$755,000.00	\$755,000

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
1325 Testing & Balancing	1	LS	\$35,600.00	\$35,600
1326 Rigging & Lifting	1	LS	\$12,500.00	\$12,500
1327 Permits & Fees	1	LS	\$8,500.00	\$8,500
1328 Shop Drawing	1	LS	\$15,500.00	\$15,500
1329 <b>23 00 00* HVAC Total</b>				<b>\$7,879,869</b>
1330				
1331				
1332 <b>26,27,28-ELECTRICAL, COMMUNICATION, SECURITY</b>				
1333				
1334 <b>26 00 00* Electrical</b>				
1335 <b>27 00 00 Technology</b>				
1336 <b>28 00 00 Integrated Electronic Security System</b>				
1337 Switchgear, Panelboards, Transformers				
1338 3000/2500 Amp Main Switchboard	1	LS	\$110,739.20	\$110,739
1339 Meter Pan	1	EA	\$738.10	\$738
1340 SPD @ Swbd	1	EA	\$2,855.60	\$2,856
1341 SPD @ Panelboard	46	EA	\$1,113.20	\$51,207
1342 100 Amp Panel Board	14	EA	\$4,048.66	\$56,681
1343 225 Amp Panel Board	9	EA	\$6,749.38	\$60,744
1344 225 Amp Panel Board, 2-Section	9	EA	\$11,521.62	\$103,695
1345 400 Amp Panel Board	4	EA	\$9,571.10	\$38,284
1346 400 Amp Panel Board, 2-Section	1	EA	\$16,443.90	\$16,444
1347 600 Amp Panel Board	2	EA	\$13,013.55	\$26,027
1348 800 Amp Panel Board	2	EA	\$16,577.00	\$33,154
1349 75 Kva Transformer	1	EA	\$7,550.40	\$7,550
1350 225 Kva Transformer K13	3	EA	\$42,713.00	\$128,139
1351 800 Amp Disconnect @ Xfmr	2	EA	\$7,381.00	\$14,762
1352 Emergency Generator, UPS				
1353 350 Kw Emergency Generator, WP/Sound	1	LS	\$147,862.00	\$147,862
1354 Autotransfer Sw 150A	1	EA	\$7,148.08	\$7,148
1355 Autotransfer Sw 225A	1	EA	\$10,145.85	\$10,146
1356 Autotransfer Sw 400A	1	EA	\$12,541.65	\$12,542
1357 150 Amp EG Quick Connect	1	EA	\$3,049.20	\$3,049
1358 200/150 Amp Encl Ckt Brkr	1	EA	\$1,923.90	\$1,924
1359 225 Amp Encl Ckt Brkr	1	EA	\$3,693.53	\$3,694
1360 400 Amp Encl Ckt Brkr	1	EA	\$4,283.40	\$4,283
1361 24KW/30Kva UPS, batteries	2	LS	\$47,432.00	\$94,864
1362 200 Amp Disconnect @ UPS	2	EA	\$1,923.90	\$3,848
1363 Generator Annunciator	1	EA	\$1,621.40	\$1,621
1364 Motors:				
1365 Cond Pump Conn	12	EA	\$157.30	\$1,888
1366 Install Limit Switch FBO	3	EA	\$121.00	\$363
1367 Install Misc Gym CP FBO	8	EA	\$465.85	\$3,727
1368 Motor Backbd Conn's, Switch	8	EA	\$779.24	\$6,234

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>1369</b> Scoreboard Conn's, Switch	1	EA	\$779.24	\$779
<b>1370</b> Bleach Motor 20/3A Conn, Switch	7	EA	\$779.24	\$5,455
<b>1371</b> Manual Snap Switch Starter WP	5	EA	\$338.80	\$1,694
<b>1372</b> 20/2 Amp Disconnect	19	EA	\$444.07	\$8,437
<b>1373</b> 30/1 Amp Disconnect, Elev Cab	1	EA	\$444.07	\$444
<b>1374</b> 30/2 Amp Disconnect, mech	8	EA	\$584.43	\$4,675
<b>1375</b> 30 Amp Disconnect, mech,kit	16	EA	\$779.24	\$12,468
<b>1376</b> 60 Amp Disconnect, mech, kit	5	EA	\$1,333.42	\$6,667
<b>1377</b> 100 Amp Disconnect	6	EA	\$1,452.00	\$8,712
<b>1378</b> 200 Amp Disconnect, Elev	1	EA	\$2,214.30	\$2,214
<b>1379</b> 200/125 Amp Disconnect WP	4	EA	\$2,214.30	\$8,857
<b>1380</b> 200/175 Amp Disconnect WP	4	EA	\$2,214.30	\$8,857
<b>1381</b> 800 Amp Disconnect CH, WP	1	EA	\$8,845.10	\$8,845
<b>1382</b> Junc Box, mech controls by others	13	EA	\$66.55	\$865
<b>1383</b> Install Nema 0 Motor Starter FBO	11	EA	\$356.95	\$3,926
<b>1384</b> Install Nema 1 Motor Starter FBO	2	EA	\$471.90	\$944
<b>1385</b> Install <=10HP VFD FBO	5	EA	\$1,367.30	\$6,837
<b>1386</b> Install 20HP VFD FBO	2	EA	\$2,081.20	\$4,162
<b>1387</b> Install 25HP VFD FBO	2	EA	\$2,734.60	\$5,469
<b>1388</b> Install 50HP VFD FBO	4	EA	\$3,448.50	\$13,794
<b>1389</b> Chiller CP Conn's	1	EA	\$3,726.80	\$3,727
<b>1390</b>				
<b>1391</b> Power Circuitry				
<b>1392</b> 3/4" Emt, empty	520	LF	\$10.61	\$5,518
<b>1393</b> 3/4" Emt, 4#12	4,760	LF	\$13.85	\$65,924
<b>1394</b> 3/4" Emt, 4#10	2,880	LF	\$14.98	\$43,149
<b>1395</b> 1" Emt, 4#8	600	LF	\$21.47	\$12,879
<b>1396</b> 1 1/4" Emt, 4#4	200	LF	\$29.05	\$5,810
<b>1397</b> 1 1/4" Emt, 4#2	2,790	LF	\$32.34	\$90,238
<b>1398</b> 1 1/2" Emt, 4#1	850	LF	\$38.81	\$32,990
<b>1399</b> 2" Emt, 4 1/0	930	LF	\$44.39	\$41,287
<b>1400</b> 2" Emt, 4 2/0	800	LF	\$48.07	\$38,459
<b>1401</b> 2" Emt, 4 3/0	200	LF	\$53.49	\$10,699
<b>1402</b> 2 1/2" Emt, 4 4/0	80	LF	\$62.02	\$4,962
<b>1403</b> 2 1/2" Emt, 4 250Mcm	60	LF	\$66.48	\$3,989
<b>1404</b> 3" Emt, 4 350Mcm	420	LF	\$81.49	\$34,227
<b>1405</b> 3 1/2" Emt, 4 500 Mcm	1,820	LF	\$105.02	\$191,129
<b>1406</b> 4#6 MI Cable	50	LF	\$41.27	\$2,064
<b>1407</b> 4#2 MI Cable	200	LF	\$83.99	\$16,797
<b>1408</b>				
<b>1409</b> Service Grounding	1	LS	\$5,033.60	\$5,034
<b>1410</b> Lightning Protection System (Preventor)	1	LS	\$34,485.00	\$34,485
<b>1411</b>				
<b>1412</b> Light Fixtures				
<b>1413</b> Type G4	80	EA	\$886.93	\$70,954

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
1414 Type LK24	24	EA	\$474.32	\$11,384
1415 Type LP8	9	EA	\$1,185.80	\$10,672
1416 Type LR2	1,173	EA	\$411.40	\$482,572
1417 Type LS2	1	EA	\$411.40	\$411
1418 Type LS4	41	EA	\$310.97	\$12,750
1419 Type LS4A	22	EA	\$310.97	\$6,841
1420 Type LS8	21	EA	\$621.94	\$13,061
1421 Type LUL	61	EA	\$310.97	\$18,969
1422 Type PC1	24	EA	\$381.15	\$9,148
1423 Type PC2	29	EA	\$381.15	\$11,053
1424 Type PC3	186	EA	\$381.15	\$70,894
1425 Type RC1	88	EA	\$381.15	\$33,541
1426 Type RC2	56	EA	\$381.15	\$21,344
1427 Type RSH	1	EA	\$393.25	\$393
1428 Type SP1	83	EA	\$617.10	\$51,219
1429 Type Exit	71	EA	\$332.75	\$23,625
1430 Type LC2	72	LF	\$114.35	\$8,233
1431 Type LC3	3,090	LF	\$114.35	\$353,326
1432 Type LWS	624	LF	\$124.03	\$77,392
1433 Type LSL	60	LF	\$130.08	\$7,805
1434 Add for additional lighting	137,385	SF	\$0.35	\$48,085
1435 Reduce lighting	(1)	LS	\$221,000.00	(\$221,000)
1436 Branch Circuitry				
1437 3/4" Emt, 4#12	15,624	LF	\$12.65	\$197,635
1438 MC Cable	46,871	LF	\$5.18	\$242,733
1439 3/4" Emt, 4#10	880	LF	\$16.66	\$14,662
1440 1" Emt, 4#8	60	LF	\$21.47	\$1,288
1441 1" Emt, 4#6	160	LF	\$22.87	\$3,659
1442 Plenum Cable	9,930	LF	\$1.59	\$15,740
1443				
1444 Wiring Devices				
1445 Switches	11	EA	\$78.65	\$865
1446 Momentary Contact Switches	9	EA	\$124.03	\$1,116
1447 OS, PS Power Pack	145	EA	\$181.50	\$26,318
1448 Local Switch/Dimming Station L	226	EA	\$151.25	\$34,183
1449 Occupancy Sensor	322	EA	\$202.68	\$65,261
1450 Photo Sensor	114	EA	\$202.68	\$23,105
1451 Receptacles	512	EA	\$78.65	\$40,269
1452 Junc Boxes, Misc	5	EA	\$64.13	\$321
1453 Receptacles GFI	217	EA	\$96.80	\$21,006
1454 Receptacles Quad	317	EA	\$129.47	\$41,042
1455 Receptacles GFI Quad	5	EA	\$159.72	\$799
1456 Receptacles GFI WP	24	EA	\$177.87	\$4,269
1457 Receptacles w/ I/O Module	28	EA	\$96.80	\$2,710
1458 Receptacles Quad w/ I/O Modules	3	EA	\$181.50	\$545

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
1459 Receptacle USB	13	EA	\$102.85	\$1,337
1460 Cord Reel Receptacle	7	EA	\$580.80	\$4,066
1461 Cond Pump Conn	12	EA	\$133.10	\$1,597
1462 Install Leak Det FBO	12	EA	\$121.00	\$1,452
1463 Sol Valve Conn	2	EA	\$121.00	\$242
1464 FS Conn	7	EA	\$121.00	\$847
1465 GSM Conn	7	EA	\$121.00	\$847
1466 Floor Power Outlet	2	EA	\$399.30	\$799
1467 4-Pole Lighting Contactor	1	EA	\$635.25	\$635
1468 12-Pole Lighting Contactor	1	EA	\$1,500.40	\$1,500
1469 EPO Pushbutton	3	EA	\$229.90	\$690
1470 Fume Hood Conn	3	EA	\$157.30	\$472
1471 Manual Snap Switch Starter VRF, VAV,misc	177	EA	\$181.50	\$32,126
1472 20/1 Amp Receptacle L5-20	11	EA	\$84.70	\$932
1473 20/1 Amp Eqpt Conn	12	EA	\$66.55	\$799
1474 30/1 Amp Receptacle L5-30	11	EA	\$117.98	\$1,298
1475 30 Amp Receptacle	3	EA	\$130.08	\$390
1476 30 Amp Stage Receptacle / strip conn	8	EA	\$798.60	\$6,389
1477 50 Amp Receptacle	1	EA	\$193.60	\$194
1478 60 Amp Receptacle, weld	2	EA	\$205.70	\$411
1479				
1480 Fire Alarm				
1481 Teflon Cable	33,345	LF	\$2.34	\$78,113
1482 3" Rigid, Riser Cables	60	LF	\$114.95	\$6,897
1483 Pull Station	24	EA	\$229.90	\$5,518
1484 Audible/Visual	205	EA	\$347.88	\$71,314
1485 Audible/Visual WP	1	EA	\$405.35	\$405
1486 Smoke Detector	158	EA	\$387.20	\$61,178
1487 CO Detector	5	EA	\$350.90	\$1,755
1488 Beam-Type Smoke Detector	11	EA	\$1,052.70	\$11,580
1489 Strobe	51	EA	\$229.90	\$11,725
1490 WP Beacon	2	EA	\$287.38	\$575
1491 Duct Detector	40	EA	\$889.35	\$35,574
1492 Central Equipment, testing, Voice Command	1	LS	\$66,477.40	\$66,477
1493 Radio Box, Antenna, wiring	1	EA	\$4,549.60	\$4,550
1494 Fused Disc	1	EA	\$738.10	\$738
1495 Door Release DH	6	EA	\$459.80	\$2,759
1496 Ansul Conn's	1	LS	\$895.40	\$895
1497 Remote Mic EVAC	1	EA	\$580.80	\$581
1498 Annunciator Panel	3	EA	\$2,323.20	\$6,970
1499 Misc Connections, Relays	25	EA	\$272.25	\$6,806
1500 Knox Box	1	EA	\$520.30	\$520
1501				
1502 Communications System				
1503 MDF Rack, PP's, Terms	1	EA	\$14,762.00	\$14,762

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
1504 IDF Rack, PP's, Terms	3	EA	\$7,381.00	\$22,143
1505 4" Floor Sleeves	16	EA	\$229.90	\$3,678
1506 4" Wall Sleeves	16	EA	\$229.90	\$3,678
1507 Main Ground Bar	1	EA	\$1,476.20	\$1,476
1508 Tel Ground Bar	3	EA	\$738.10	\$2,214
1509 #3/0G Wire	600	LF	\$9.19	\$5,511
1510 Cable Tray 24" Alum	1,570	LF	\$41.62	\$65,350
1511 12 Strand Multi-Mode Fiber	600	LF	\$6.18	\$3,710
1512 6 Strand Multi-Mode Fiber	600	LF	\$4.30	\$2,577
1513 Cu Distr Cable	600	LF	\$10.29	\$6,171
1514 1" EMT CDT	172	LF	\$14.40	\$2,477
1515 2" EMT CDT	1,040	LF	\$22.90	\$23,819
1516 4" EMT Cdt	200	LF	\$34.64	\$6,928
1517 Cat 6 Cable	103,500	LF	\$1.59	\$164,058
1518 WAP Outlet AN 2c	14	EA	\$89.54	\$1,254
1519 Tel Outlet	60	EA	\$72.60	\$4,356
1520 Data Outlet	2	EA	\$72.60	\$145
1521 Data Duplex Outlet 2c	78	EA	\$89.54	\$6,984
1522 Tel/Data Outlet 3c	76	EA	\$111.93	\$8,506
1523 Floor Tel/Data Outlet 3c	6	EA	\$399.30	\$2,396
1524 Tel/Data Outlet T 2c	47	EA	\$89.54	\$4,208
1525 TVE 2c	50	EA	\$169.40	\$8,470
1526 TVC 2c	2	EA	\$169.40	\$339
1527				
1528 Clock/ Public Address System:				
1529 2 1/2" Emt, Riser Cables	50	LF	\$66.74	\$3,337
1530 3/4" EMT Cdt	2,730	LF	\$11.93	\$32,571
1531 1" EMT Cdt	2,530	LF	\$14.40	\$36,429
1532 Comm Cable	14,100	LF	\$1.59	\$22,350
1533 Main Sound Rack	1	LS	\$48,884.00	\$48,884
1534 Local Sound System Rack	2	EA	\$7,792.40	\$15,585
1535 Outlet S Speaker	232	EA	\$254.10	\$58,951
1536 Outlet S Speaker WP	19	EA	\$344.85	\$6,552
1537 Volume Control	26	EA	\$181.50	\$4,719
1538 Master Clock GPS	1	EA	\$5,493.40	\$5,493
1539 Clock Antenna	1	EA	\$1,863.40	\$1,863
1540 Wireless Clock Transceiver	1	EA	\$2,855.60	\$2,856
1541 Wireless Clock Repeater	4	EA	\$1,427.80	\$5,711
1542 Clock, wireless	73	EA	\$254.10	\$18,549
1543				
1544 A/V System:				
1545 1" EMT Cdt	1,600	LF	\$14.40	\$23,038
1546 BP Button Panel	41	EA	\$99.83	\$4,093
1547 R1 Receptacle Panel	41	EA	\$99.83	\$4,093
1548 V1 Video Projector	41	EA	\$99.83	\$4,093



# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
1549 S1 Speaker	82	EA	\$99.83	\$8,186
1550 AV Eqpt, Inst, LV Wiring - Proj/Assist List	41	RM		
1551 J1	2	EA	\$99.83	\$200
1552 Data Outlet P Projector	1	EA	\$99.83	\$100
1553 Screen	1	EA	\$99.83	\$100
1554 R2 Receptacle Panel	4	EA	\$169.40	\$678
1555 R3 Receptacle Panel	4	EA	\$169.40	\$678
1556 Speaker S1 Backbox	4	EA	\$99.83	\$399
1557 Speaker S2 Backbox	4	EA	\$99.83	\$399
1558 Speaker S3 Backbox	14	EA	\$99.83	\$1,398
1559 AV Rack Enclosure	1	EA	\$459.80	\$460
1560 AV Eqpt, Installation, LV Wiring - ALLOW	1	LS		
1561 Gym Sound System Mat'l Package	1	LS	\$45,000.00	\$45,000
1562 Auditorium AV Roughin	1	LS	\$45,000.00	\$45,000
1563 )				
1564 Theater Lighting & Control System:ALLOW (Eqpt in "Equipment S				
1565 Lighting and Controls included in "Equipment Section"				
1566 Theat Lighting & Power Roughin	1	LS	\$30,000.74	\$30,001
1567 Theat Lighting Controls Roughin	1	LS	\$10,000.25	\$10,000
1568				
1569 Security Intrusion Alarm System:				
1570 Power Supply Junc Box, 120v	1	EA	\$459.80	\$460
1571 Central Eqpt	1	EA	\$14,713.60	\$14,714
1572 3/4" Emt, 4#12	40	LF	\$13.85	\$554
1573 Plenum Cables	4,800	LF	\$1.59	\$7,608
1574 3/4" Emt	720	LF	\$11.93	\$8,590
1575 CR Card Reader	9	EA	\$810.70	\$7,296
1576 K Keypad	2	EA	\$810.70	\$1,621
1577 EL Electric Lock	5	EA	\$490.05	\$2,450
1578 EH Electric Hinge	30	EA	\$490.05	\$14,702
1579 Intercom	2	EA	\$520.30	\$1,041
1580 PT Install Power Transfer Hinge FBO	16	EA	\$411.40	\$6,582
1581 REX Req to Exit	21	EA	\$290.40	\$6,098
1582 DC Door Position Sw	54	EA	\$199.65	\$10,781
1583 M Motion Sensor	71	EA	\$411.40	\$29,209
1584 TS Door Switch	16	EA	\$181.50	\$2,904
1585 DJ Door Junc Box	16	EA	\$139.15	\$2,226
1586				
1587 CCTV System:				
1588 3/4" EMT Cdt	870	LF	\$11.41	\$9,927
1589 Signal Cables	11,400	LF	\$1.59	\$18,070
1590 Monitoring/Recording Eqpt	1	LS	\$33,577.50	\$33,578
1591 Viewing Console	2	EA	\$1,161.60	\$2,323
1592 Data Outlet CAM, Camera	55	EA	\$1,294.70	\$71,209
1593 Data Outlet CAM, Camera WP	15	EA	\$1,996.50	\$29,948

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>1594</b>				
<b>1595</b> BDA System	1	LS	\$136,000.00	\$136,000
<b>1596</b> Area of Rescue Assistance	1	LS	\$20,000.00	\$20,000
<b>1597</b>				
<b>1598</b> Temp Power and Lighting	1	LS	\$89,540.00	\$89,540
<b>1599</b>				
<b>1600</b> Site Lighting, Site Eqpt				
<b>1601</b> Type SL1, 1-Fixt, 30' pole	35	EA	\$4,767.40	\$166,859
<b>1602</b> Type SL1A, 1-Fixt, 30' pole		EA	\$4,767.40	
<b>1603</b> Type SL3, Wallpack	9	EA	\$701.80	\$6,316
<b>1604</b> Type SL5 Pedestrian Light Pole	8	EA	\$3,242.80	\$25,942
<b>1605</b> Type SL4 Exterior Wallpack	17	EA	\$701.80	\$11,931
<b>1606</b> WP Signage w/ Lights, FBO	1	EA	\$1,113.20	\$1,113
<b>1607</b> Type SL10 Plant uplight	12	EA	\$520.30	\$6,244
<b>1608</b> Type SL11	13	EA	\$1,113.20	\$14,472
<b>1609</b> Type SLS	7	EA	\$733.00	\$5,131
<b>1610</b> Receptacle WP GFI	5	EA	\$284.35	\$1,422
<b>1611</b> CCTV Camera, Pole Mtd	3	EA	\$1,863.40	\$5,590
<b>1612</b> Elect Vehicle Charging Station	3	EA	\$1,645.60	\$4,937
<b>1613</b> Relocate Exist EM Call Box	2	EA	\$1,113.20	\$2,226
<b>1614</b> Time Clock	1	EA	\$1,004.30	\$1,004
<b>1615</b>				
<b>1616</b> Branch Circuitry:				
<b>1617</b> 3/4" Emt, 4#10	280	LF	\$14.98	BP#1
<b>1618</b> 1" PVC CDT UG	7,110	LF	\$5.41	BP#1
<b>1619</b> 2" PVC CDT UG	900	LF	\$7.70	BP#1
<b>1620</b> 2 1/2" PVC CDT UG	3,600	LF	\$10.31	BP#1
<b>1621</b> 17x30x12" Site Pullbox	16	EA	\$2,323.20	\$37,171
<b>1622</b> Handhole	6	EA	\$2,323.20	\$13,939
<b>1623</b> #10 Wire	12,400	LF	\$1.25	\$15,535
<b>1624</b> #8 Wire	16,050	LF	\$1.76	\$28,261
<b>1625</b> #6 Wire	2,700	LF	\$2.11	\$5,707
<b>1626</b> Signal Cable	1,250	LF	\$1.82	\$2,269
<b>1627</b>				
<b>1628</b> Site Power, EG Feeders, Utilities:				
<b>1629</b> 4" PVC (Primary, empty) UG	460	LF	\$16.95	\$7,797
<b>1630</b> 4" PVC CDT, 4 600 Mcm, UG (service)	600	LF	\$104.70	\$62,819
<b>1631</b> 4" PVC CDT UG (spare)	100	LF	\$16.95	\$1,695
<b>1632</b> 4" PVC CDT, 4 500 Mcm, UG (EG)	100	LF	\$87.18	\$8,718
<b>1633</b> 2" PVC, 4#1/0 UG (EG)	100	LF	\$29.19	\$2,919
<b>1634</b> 2 1/2" PVC, 4#4/0 UG (EG)	100	LF	\$38.87	\$3,887
<b>1635</b> 1" PVC, EG Controls, Misc UG	200	LF	\$10.44	\$2,088
<b>1636</b> Utility Pole Riser	1	LF	\$4,767.40	\$4,767
<b>1637</b> Utility Transformer Pad	1	LS	\$4,162.40	\$4,162
<b>1638</b> Manhole	2	EA	\$11,616.00	\$23,232

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
1639 Trenching, Concrete, Backfill	1	LS	\$100,000.00	BP#1
1640				
1641 Miscellaneous:				
1642 4" PVC CDT UG (Comm)	800	LF	\$16.95	\$13,560
1643 Innerduct	600	LF	\$3.99	\$2,396
1644 Tel Utility Pole Riser	1	LS	\$3,121.80	\$3,122
1645 3'x3' Comm Handhole	1	EA	\$6,243.60	\$6,244
1646				
1647 Misc Site Demo	1	LS	\$10,890.00	BP#1
1648 Site Security Lighting	1	LS	\$12,584.00	\$12,584
1649 Temp Power and Lighting	1	LS	\$31,460.00	\$31,460
1650 Eqpt Rentals	1	LS	\$7,260.00	\$7,260
1651 <b>26,27,28-ELECTRICAL, COMMUNICATION, SECURITY TOTAL</b>				<hr/> \$5,893,015
1652				
1653				
1654 <b>31-EARTHWORK</b>				
1655				
1656 <b>31 00 00 Earthwork</b>				
1657 See Sitework				
1658 <b>31 00 00 Earthwork Total</b>				<hr/>
1659				
1660				
1661				

**Fuller Middle School**  
Framingham, MA

**SITWORK DIRECT TRADE COST DETAILS - CSI**

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>1662 02-EXISTING CONDITIONS</b>				
1663				
<b>1664 02 41 00 Demolition</b>				
1665				BP#1
1666 G1020.01 Building Demolition				\$0
1667 02 30 00 Building Demolition				\$0
1668 Building demoltion				See Main Summa
<b>1669 02 41 00 Demolition Total</b>				<u>\$0</u>
1670				
1671				
<b>1672 31-EARTHWORK</b>				
1673				
<b>1674 31 00 00 Earthwork</b>				
1675 Site prep	258,370	SF	\$1.00	BP#1
1676 Trench and backfill only	313	LF	\$45.00	BP#1
1677 Baseball field	0	0	\$0.00	<u>Existing to Rema</u>
<b>1678 31 00 00 Earthwork Total</b>				<u>\$0</u>
1679				
<b>1680 31 10 00 Site Clearing</b>				
1681 Site clearing	7	ACRE	\$5,000.00	BP#1
1682 Safety barricade	1	AL	\$60,000.00	BP#1
1683 Construction fence, install, maintain, remove & reinstall; f	11,344	LF	\$12.00	BP#1
1684 Double construction gate	2	PR	\$2,500.00	BP#1
1685 Temporary construction entrance	2	LOC	\$7,000.00	BP#1
1686 Add premium for moving and reinstalling for 3 phases	1	LS	\$37,385.00	BP#1
1687 Temporary Jersey Barriers; purchase and install	3,145	LF	\$65.00	BP#1
1688 Temp signs	1	LS	\$3,000.00	BP#1
1689 Wash down/re-fueling/parking allowance	3,000	SF	\$2.00	BP#1
1690 Temporary pavement	47,106	SF	\$3.00	BP#1
1691 Temporary sedimentation and runoff basin	7,348	SF	\$2.00	BP#1
<b>1692 31 10 00 Site Clearing Total</b>				<u>\$0</u>
1693				
<b>1694 31 23 19 Dewatering and Drainage</b>				
1695 Dewatering for sitework excavation; allow	1	LS	\$100,000.00	BP#1
<b>1696 31 23 19 Dewatering and Drainage Total</b>				<u>\$0</u>
1697				
<b>1698 31 25 00 Erosion and Sedimentation Controls</b>				
1699 Erosion control barrier	1,206	LF	\$14.00	BP#1
1700 Stockpile area (all phases), qty provided	35,000	CY	\$2.50	BP#1
1701 FM; discharge temp basin to existing DMH	271	LF	\$75.00	BP#1
1702 Stormwater basin	3,547	SF	\$2.50	BP#1
<b>1703 31 25 00 Erosion and Sedimentation Controls Total</b>				<u>\$0</u>
1704				

# Fuller Middle School

Framingham, MA

## SITWORK DIRECT TRADE COST DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>1705 32-EXTERIOR IMPROVEMENTS</b>				
<b>1706</b>				
<b>1707 32 12 00 Flexible Paving</b>				
1708 Existing public roadway 'Flagg Drive' to remain	0	SF	\$0.00	ETR
1709 Vehicular asphalt pavement, incl's temporary pavement	202,060	SF	\$3.00	BP#1
1710 Raised bituminous pavement (stamped)	11,716	SF	\$15.00	BP#1
1711 Gravel base to roadway & parking lot	9,445	CY	\$35.00	BP#1
1712 32 17 00 Paving Specialties	0	0	\$0.00	BP#1
1713 Crosswalk	2,350	SF	\$2.50	BP#1
1714 Parking stall painting	302	EA	\$15.00	BP#1
1715 Parking stall painting; HC	12	EA	\$75.00	BP#1
1716 Crosswalk striping, temporary	2,440	SF	\$2.50	BP#1
1717 Temporary parking spaces, incl's HC bus	162	EA	\$75.00	BP#1
1718 Jersey barrier between vehicle parking, temporary	745	LF	\$10.00	BP#1
1719 Misc. marking other than above	1	LS	\$50,000.00	BP#1
<b>1720 32 12 00 Flexible Paving Total</b>				<u>\$0</u>
<b>1721</b>				
<b>1722 32 14 00 Unit Paving</b>				
1723 Concrete paving/Conc sidewalk	17,115	SF	\$10.00	BP#2
<b>1724 32 14 00 Unit Paving Total</b>				<u>\$0</u>
<b>1725</b>				
<b>1726 32 16 00 Curbs and Gutters</b>				
1727 VGC; vertical granite curb	3,965	LF	\$42.00	BP#1
1728 SGC; sloped granite curb	191	LF	\$43.50	BP#1
1729 PCC; precast concrete curb	8,105	LF	\$25.00	BP#1
1730 Bit. berm curb	1,336	LF	\$5.00	BP#1
<b>1731 32 16 00 Curbs and Gutters Total</b>				<u>\$0</u>
<b>1732</b>				
<b>1733 32 17 00 Paving Specialties</b>				
1734 Bituminous conc sidewalk	26,443	SF	\$2.25	BP#1
1735 Gravel base to concrete pavement	807	CY	\$35.00	BP#1
1736 Curb cut	15	EA	\$450.00	BP#1
1737 Concrete pad	1	AL	\$24,000.00	BP#1
1738 Handicap ramp	402	SF	\$20.00	BP#1
1739 Temporary modular handicap ramp	138	SF	\$20.00	BP#1
<b>1740 32 17 00 Paving Specialties Total</b>				<u>\$0</u>
<b>1741</b>				
<b>1742 32 30 00 Site Improvements</b>				
1743 Unit block retaining wall	0	0	\$0.00	\$0
1744 Footing	361	lf	\$0.00	\$0
1745 Concrete	28	CY	\$135.00	BP#2
1746 Concrete; place	28	CY	\$85.00	BP#2
1747 Reinforcing	1,820	LBS	\$1.10	BP#2

# Fuller Middle School

Framingham, MA

## SITWORK DIRECT TRADE COST DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
1748 Formwork	2,166	SF	\$12.00 BP#2	
1749 Wall	1,264	sf	\$0.00	\$0
1750 Concrete material	42	CY	\$135.00 BP#2	
1751 Concrete; place	42	CY	\$85.00 BP#2	
1752 Reinforcing	6,300	LBS	\$1.10 BP#2	
1753 Formwork	2,166	SF	\$12.00 BP#2	
1754 Wall	1,264	SF	\$28.00 BP#2	
1755 Concrete bench w/wooden top	20	LF	\$275.00	\$5,500
1756 Segmented retaining wall	3,000	LF	\$50.00	\$150,000
1757 Flagpole	2	EA	\$7,500.00	\$15,000
1758 Traffic signs	1	AL	\$10,000.00 BP#1	
1759 Peastone drip edge around building; 1'-6" wide	50	CY	\$75.00	\$3,750
1760 Stonedust paving	1	LS	\$1,750.00	\$1,750
1761 Pavers at entry	745	SF	\$15.00	\$11,175
1762 Bicycle racks	20	EA	\$950.00	\$19,000
1763 Basketball pavement	0	0	\$0.00 BP#1	
1764 Basketball court; fence, gate, court marking	1,750	SF	\$35.00	\$61,250
1765 <b>32 30 00 Site Improvements Total</b>				<b>\$267,425</b>
1766				
1767 <b>32 31 00 Fences and Gates</b>				
1768 Guardrail	1	LS	\$35,000.00	\$35,000
1769 Galvanized handrails @ ramps and steps	219	LF	\$250.00	\$54,750
1770 <b>32 31 00 Fences and Gates Total</b>				<b>\$89,750</b>
1771				
1772 <b>32 80 00 Irrigation</b>				
1773 See the field				\$0
1774 <b>32 80 00 Irrigation Total</b>				<b>\$0</b>
1775				
1776 <b>32 92 00 Turfs and Grasses</b>				
1777 Topsoil for planting beds, shrubs and perennials	276	CY	\$25.00	\$6,900
1778 Sports field mix (seed)	258,370	SF	\$0.35	\$90,430
1779 Native wildflower meadow	104,342	SF	\$0.50	\$52,171
1780 Lawn (seed)	121,052	SF	\$0.35	\$42,368
1781 Sod at ampitheater	25,902	SF	\$1.50	\$38,853
1782 Sod at play areas	24,038	SF	\$1.50	\$36,057
1783 Plant bed	7,900	SF	\$10.00	\$79,000
1784 Temporary at playing field sod	5,000	SF	\$1.50	\$7,500
1785 Mulch	1	LS	\$30,000.00	\$30,000
1786 Remove and install new irrigation System	82,000	SF	\$3.00	\$246,000
1787 South Sports Field	0	0	\$0.00 By Others	
1788 Irrigation in front of Ampitheater	25,902	SF	\$2.00	\$51,804
1789 Irrigation at play areas	24,038	SF	\$2.00	\$48,076
1790 Fine grading	121,052	SF	\$0.75	\$90,789

# Fuller Middle School

Framingham, MA

## SITWORK DIRECT TRADE COST DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>1791 32 92 00 Turfs and Grasses Total</b>				<b>\$819,947</b>
<b>1792</b>				
<b>1793 32 93 00 Plants</b>				
<b>1794</b> Trees				
<b>1795</b> AL; Allegheny Serviceberry 2½ - 3" Cal	12	EA	\$900.00	\$10,800
<b>1796</b> AC; Shadblow Serviceberry 2½ - 3" Cal	1	EA	\$900.00	\$900
<b>1797</b> AR; Red Maple 3 - 3½" Cal	6	EA	\$850.00	\$5,100
<b>1798</b> CK; American Yellowwood 3 - 3½" Cal	24	EA	\$800.00	\$19,200
<b>1799</b> FG; American Beech 3 - 3½" Cal	11	EA	\$850.00	\$9,350
<b>1800</b> LT; Tulip Tree 3 - 3½" Cal	8	EA	\$900.00	\$7,200
<b>1801</b> NS; Black Tupelo 3 - 3½" Cal	15	EA	\$850.00	\$12,750
<b>1802</b> OA; Sourwood 2½-3" Cal	3	EA	\$750.00	\$2,250
<b>1803</b> PA; London Plain Tree 3 - 3½" Cal	24	EA	\$850.00	\$20,400
<b>1804</b> QP; Pin Oak 3 - 3½" Cal	7	EA	\$900.00	\$6,300
<b>1805</b> QR; Red Oak 3 - 3½" Cal	7	EA	\$950.00	\$6,650
<b>1806</b> Shrubs				
<b>1807</b> CA; Sweet Pepperbush 3½ - 4' HT	28	EA	\$95.00	\$2,660
<b>1808</b> HQ; Oak-leaf Hydrangea 3 - 3½' HT	49	EA	\$95.00	\$4,655
<b>1809</b> HV; Witch Hazel 7- 8' B+B	3	EA	\$350.00	\$1,050
<b>1810</b> IG; Compact Incberry 2½ - 3' HT	33	EA	\$125.00	\$4,125
<b>1811</b> IV; Winterberry 2 - 2½ HT	61	EA	\$95.00	\$5,795
<b>1812</b> JC; Common Juniper 24" SPD	0	EA	\$75.00	\$0
<b>1813</b> JH; Creeping Juniper 15-24" SPD	68	EA	\$75.00	\$5,100
<b>1814</b> JV; Eastern Red Cedar 7- 8' HT	26	EA	\$250.00	\$6,500
<b>1815</b> MG; Sweetgale 3½ - 4' HT	38	EA	\$95.00	\$3,610
<b>1816</b> PF; Pink Beauty Potentilla 24" SPD	22	EA	\$75.00	\$1,650
<b>1817</b> RA; Grow Low Sumac 2 - 2½' SPD	47	EA	\$115.00	\$5,405
<b>1818</b> RT; Staghorn Sumac 3 Gal	13	EA	\$115.00	\$1,495
<b>1819</b> RV; Virginia Rose 2½ - 3' SPD	0	EA	\$75.00	\$0
<b>1820</b> VA; Lowbush Blueberry 15-24" SPD	53	EA	\$75.00	\$3,975
<b>1821</b> VD; Arrowwood 4 - 4½' HT	31	EA	\$150.00	\$4,650
<b>1822</b> VT; Dwarf Cranberry Bush 3 - 3½' HT	12	EA	\$115.00	\$1,380
<b>1823</b> Groundcover				
<b>1824</b> CP; Sweet Fern 1 Gal	1,966	EA	\$20.00	\$39,320
<b>1825</b> Planting beds allowance	1	LS	\$20,000.00	\$20,000
<b>1826</b> Grass at temporary parking area	6,650	SF	\$0.35	\$2,328
<b>1827</b> Maintenance of landscaping	1	LS	\$10,000.00	\$10,000
<b>1828 32 93 00 Plants Total</b>				<b>\$224,598</b>
<b>1829</b>				
<b>1830</b>				
<b>1831 33-UTILITIES</b>				
<b>1832</b>				
<b>1833 33 10 00 Water Distribution</b>				

**Fuller Middle School**  
Framingham, MA

**SITWORK DIRECT TRADE COST DETAILS - CSI**

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
1834 2" Domestic water service	120	LF	\$60.00	BP#1
1835 6" Fire water service	170	LF	\$70.00	BP#1
1836 Water service; not sized	680	LF	\$95.00	BP#1
1837 Hydrant	5	EA	\$4,500.00	BP#1
1838 Miscellaneous gates, valves, etc. (gate valve 8x8x6)	1	LS	\$10,000.00	BP#1
<b>1839 33 10 00 Water Distribution Total</b>				<b>\$0</b>
1840				
<b>1841 33 31 00 Sanitary Sewerage</b>				
1842 6" DI	78	LF	\$70.00	BP#1
1843 6" PVC	42	LF	\$70.00	BP#1
1844 8" PVC	472	LF	\$75.00	BP#1
1845 SMH; Sewer manhole	4	EA	\$4,500.00	BP#1
1846 CO; Cleanout	1	EA	\$600.00	BP#1
1847 Connect to existing	1	EA	\$3,500.00	BP#1
1848 Acid neutralization tank	2	EA	\$7,500.00	BP#1
1849 Grease trap	1	EA	\$15,000.00	BP#1
<b>1850 33 31 00 Sanitary Sewerage Total</b>				<b>\$0</b>
1851				
<b>1852 33 41 00 Storm Utility Drainage</b>				
1853 All incl. trench and backfill	0	0	\$0.00	\$0
1854 6" PVC	47	LF	\$35.00	BP#1
1855 12" HDPE	2,435	LF	\$42.00	BP#1
1856 15" HDPE	635	LF	\$45.00	BP#1
1857 18" HDPE	548	LF	\$48.00	BP#1
1858 24" HDPE	371	LF	\$50.00	BP#1
1859 30" HDPE	547	LF	\$60.00	BP#1
1860 DMH; Manhole	9	EA	\$3,500.00	BP#1
1861 CB; catch basin	19	EA	\$4,500.00	BP#1
1862 Temporary CB, convert to DMH	3	EA	\$4,500.00	BP#1
1863 Headwall @ 24" HDPE end	2	EA	\$1,500.00	BP#1
1864 Allowances for:	0	0	\$0.00	BP#1
1865 Water quality structures	4	EA	\$15,000.00	BP#1
1866 Gravel and sod buffer for pretreatment	1	LS	\$10,000.00	BP#1
1867 Stormceptors:	0	0	\$0.00	BP#1
1868 450i	2	EA	\$10,000.00	BP#1
1869 3600	1	EA	\$35,000.00	BP#1
1870 6000	1	EA	\$60,000.00	BP#1
1871 Outlet structure	1	EA	\$5,000.00	BP#1
1872 Perimeter drainage	0	0	\$0.00	Bldg Tab
<b>1873 33 41 00 Storm Utility Drainage Total</b>				<b>\$0</b>
1874				
<b>1875 33 50 00 Gas Service</b>				
1876 33 50 00 Gas Service	0	0	\$0.00	\$0



**Fuller Middle School**  
Framingham, MA

**SITWORK DIRECT TRADE COST DETAILS - CSI**

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
1877 Connection to existing gas main	0	0	\$0.00	By Other
1878 Gas line piping, incl's valves (2)	0	0	\$0.00	By Other
1879 <b>33 50 00 Gas Service Total</b>				<u>\$0</u>
1880				
1881				
1882 <b>33 70 00 Electrical Utilities</b>				
1883 See building estimate (Section 26)				
1884 <b>33 70 00 Electrical Utilities Total</b>				<u>\$0</u>
1885				
1886				
1887				
1888				
1889				
1890				
1891				
1892				
1893				
1894				
			<b>SITWORK SUBTOTAL</b>	<b>\$1,401,720</b>

**Fuller Middle School**  
Fuller Middle School

**DIRECT COST SUMMARY - NEW CONSTRUCTION**

<b><u>DIV. ELEMENTS</u></b>	<b><u>90%CD TOTAL</u></b>	<b><u>60%CD TOTAL</u></b>	<b><u>DIFFERENCE</u></b>	<b><u>% DIFF</u></b>
	137,385 GSF	136,600 GSF	785 GSF	0.57%
<b>1895 A-G <u>BUILDING</u></b>				
<b>1896</b>				
<b>1897 <u>A SUBSTRUCTURES</u></b>				
<b>1898</b>				
<b>1899 A10 FOUNDATIONS</b>				
<b>1900</b> Foundations	\$75,417	\$1,119,012	(\$1,043,595)	-93.26%
<b>1901</b> Slab on Grade	\$0	\$594,006	(\$594,006)	-100.00%
<b>1902</b> FOUNDATIONS TOTAL	<b>\$75,417</b>	<b>\$1,713,019</b>	<b>(\$1,637,602)</b>	<b>-95.60%</b>
<b>1903</b>				
<b>1904 A20 BASEMENT CONSTRUCTION</b>				
<b>1905</b>				
<b>1906 A SUBSTRUCTURES TOTAL</b>	<b>\$75,417</b>	<b>\$1,713,019</b>	<b>(\$1,637,602)</b>	<b>-95.60%</b>
<b>1907</b>				
<b>1908</b>				
<b>1909 <u>B SHELL</u></b>				
<b>1910</b>				
<b>1911 B10 STRUCTURE</b>				
<b>1912</b> Upper Floor Construction	\$41,216	\$2,721,067	(\$2,679,851)	-98.49%
<b>1913</b> Roof Construction	\$478,000	\$2,333,165	(\$1,855,165)	-79.51%
<b>1914</b> STRUCTURE TOTAL	<b>\$519,216</b>	<b>\$5,054,232</b>	<b>(\$4,535,016)</b>	<b>-89.73%</b>
<b>1915</b>				
<b>1916 B20 EXTERIOR CLOSURE</b>				
<b>1917</b> Exterior walls	\$4,900,274	\$4,646,002	\$254,272	5.47%
<b>1918</b> Exterior windows	\$1,614,066	\$1,942,628	(\$328,562)	-16.91%
<b>1919</b> Exterior Doors	\$187,200	\$213,200	(\$26,000)	-12.20%
<b>1920</b> EXTERIOR CLOSURE TOTAL	<b>\$6,701,540</b>	<b>\$6,801,830</b>	<b>(\$100,290)</b>	<b>-1.47%</b>
<b>1921</b>				
<b>1922 B30 ROOFING</b>				
<b>1923</b> Roof Coverngs	\$2,231,175	\$2,265,314	(\$34,139)	-1.51%
<b>1924</b> ROOFING TOTAL	<b>\$2,231,175</b>	<b>\$2,265,314</b>	<b>(\$34,139)</b>	<b>-1.51%</b>
<b>1925</b>				
<b>1926 B SHELL TOTAL</b>	<b>\$9,451,930</b>	<b>\$14,121,376</b>	<b>(\$4,669,445)</b>	<b>-33.07%</b>
<b>1927</b>				
<b>1928</b>				
<b>1929 <u>C INTERIORS</u></b>				
<b>1930</b>				
<b>1931 C10 INTERIOR CONSTRUCTION</b>				
<b>1932</b> Partitions	\$4,676,743	\$4,412,924	\$263,820	5.98%
<b>1933</b> Interior Doors, frames & Hardware	\$979,423	\$895,898	\$83,525	9.32%
<b>1934</b> Fittings	\$1,062,573	\$915,361	\$147,212	16.08%
<b>1935</b> INTERIOR CONSTRUCTION TOTAL	<b>\$6,718,739</b>	<b>\$6,224,182</b>	<b>\$494,556</b>	<b>7.95%</b>
<b>1936</b>				
<b>1937 C20 STAIRCASES</b>				

**Fuller Middle School**

Fuller Middle School

**DIRECT COST SUMMARY - NEW CONSTRUCTION**

<b><u>DIV. ELEMENTS</u></b>	<b><u>90%CD TOTAL</u></b>	<b><u>60%CD TOTAL</u></b>	<b><u>DIFFERENCE</u></b>	<b><u>% DIFF</u></b>
	137,385 GSF	136,600 GSF	785 GSF	0.57%
<b>1938</b> Staircases	\$371,420	\$590,570	(\$219,150)	-37.11%
<b>1939</b> STAIRCASES TOTAL	<b>\$371,420</b>	<b>\$590,570</b>	<b>(\$219,150)</b>	<b>-37.11%</b>
<b>1940</b>				
<b>1941</b> C30 INTERIOR FINISHES				
<b>1942</b> Wall finishes	\$2,046,567	\$1,767,241	\$279,327	15.81%
<b>1943</b> Floor finishes	\$1,436,679	\$1,288,200	\$148,480	11.53%
<b>1944</b> Ceiling finishes	\$2,014,543	\$1,858,543	\$156,000	8.39%
<b>1945</b> INTERIOR FINISHES TOTAL	<b>\$5,497,790</b>	<b>\$4,913,983</b>	<b>\$583,807</b>	<b>11.88%</b>
<b>1946</b>				
<b>1947</b> C INTERIORS TOTAL	<b>\$12,587,948</b>	<b>\$11,728,735</b>	<b>\$859,213</b>	<b>7.33%</b>
<b>1948</b>				
<b>1949</b>				
<b>1950</b> <b><u>D SERVICES</u></b>				
<b>1951</b>				
<b>1952</b> D10 VERTICAL MOVEMENT				
<b>1953</b> Conveying System	\$223,400	\$213,400	\$10,000	4.69%
<b>1954</b> VERTICAL MOVEMENT TOTAL	<b>\$223,400</b>	<b>\$213,400</b>	<b>\$10,000</b>	<b>4.69%</b>
<b>1955</b>				
<b>1956</b> D20 PLUMBING				
<b>1957</b> Plumbing	\$2,126,673	\$2,126,673	\$0	0.00%
<b>1958</b> PLUMBING TOTAL	<b>\$2,126,673</b>	<b>\$2,126,673</b>	<b>\$0</b>	<b>0.00%</b>
<b>1959</b>				
<b>1960</b> D30 HVAC				
<b>1961</b> HVAC	\$7,879,869	\$7,842,369	\$37,500	0.48%
<b>1962</b> HVAC TOTAL	<b>\$7,879,869</b>	<b>\$7,842,369</b>	<b>\$37,500</b>	<b>0.48%</b>
<b>1963</b>				
<b>1964</b> D40 FIRE PROTECTION				
<b>1965</b> Fire Protection	\$962,994	\$852,994	\$110,000	12.90%
<b>1966</b> FIRE PROTECTION TOTAL	<b>\$962,994</b>	<b>\$852,994</b>	<b>\$110,000</b>	<b>12.90%</b>
<b>1967</b>				
<b>1968</b> D50 ELECTRICAL				
<b>1969</b> Service and distribution	\$5,893,015	\$5,110,258	\$782,757	15.32%
<b>1970</b> ELECTRICAL TOTAL	<b>\$5,893,015</b>	<b>\$5,110,258</b>	<b>\$782,757</b>	<b>15.32%</b>
<b>1971</b>				
<b>1972</b> D SERVICES TOTAL	<b>\$17,085,950</b>	<b>\$16,145,693</b>	<b>\$940,257</b>	<b>5.82%</b>
<b>1973</b>				
<b>1974</b>				
<b>1975</b> <b><u>E EQUIPMENT AND FURNISHINGS</u></b>				
<b>1976</b>				
<b>1977</b> E10 EQUIPMENT				
<b>1978</b> Institutional Equipment	\$1,759,448	\$1,644,448	\$115,000	6.99%
<b>1979</b> EQUIPMENT TOTAL	<b>\$1,759,448</b>	<b>\$1,644,448</b>	<b>\$115,000</b>	<b>6.99%</b>
<b>1980</b>				

**Fuller Middle School**

Fuller Middle School

**DIRECT COST SUMMARY - NEW CONSTRUCTION**

<b><u>DIV. ELEMENTS</u></b>	<b><u>90%CD TOTAL</u></b>	<b><u>60%CD TOTAL</u></b>	<b><u>DIFFERENCE</u></b>	<b><u>% DIFF</u></b>
	137,385 GSF	136,600 GSF	785 GSF	0.57%
<b>1981</b>				
<b>1982</b> E20 FURNISHINGS				
<b>1983</b> Specialties / Millwork	\$1,583,180	\$1,609,546	(\$26,367)	-1.64%
<b>1984</b> FURNISHINGS TOTAL	<b>\$1,583,180</b>	<b>\$1,609,546</b>	<b>(\$26,367)</b>	<b>-1.64%</b>
<b>1985</b>				
<b>1986</b> D EQUIPMENT AND FURNISHINGS TOTAL	<b>\$3,342,628</b>	<b>\$3,253,994</b>	<b>\$88,634</b>	<b>2.72%</b>
<b>1987</b>				
<b>1988</b>				
<b>1989</b> <b><u>F SPECIAL CONSTRUCTION &amp; DEMO</u></b>				
<b>1990</b>				
<b>1991</b> F10 SPECIAL CONSTRUCTION				
<b>1992</b> Special construction	\$0	\$0	\$0	0.00%
<b>1993</b> SPECIAL CONSTRUCTION TOTAL	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>0.00%</b>
<b>1994</b>				
<b>1995</b> F20 SELECTIVE DEMOLITION				
<b>1996</b> Selectice Demolition	\$0	\$0	\$0	0.00%
<b>1997</b> SELECTIVE DEMOLITION TOTAL	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>0.00%</b>
<b>1998</b>				
<b>1999</b> D SPECIAL CONSTRUCTION & DEMO TOTAL	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>
<b>2000</b>				
<b>2001</b> G EQUIPMENT AND FURNISHINGS TOTAL	<b>\$5,013,942</b>	<b>\$4,880,991</b>	<b>\$132,951</b>	<b>2.72%</b>
<b>2002</b>				
<b>2003</b> A-G BUILDING TOTAL	<b>\$42,543,873</b>	<b>\$46,962,817</b>	<b>(\$4,418,943)</b>	<b>-9.41%</b>
<b>2004</b>				
<b>2005</b>				
<b>2006</b> <b><u>G BUILDING SITEWORK</u></b>				
<b>2007</b>				
<b>2008</b> G10 G10 SITE PREPARATION				
<b>2009</b> G1010 Site Clearing	\$0	\$0	\$0	
<b>2010</b> G1020 Site Demolition and Relocation	\$0	\$0	\$0	
<b>2011</b> G1030 Site Earthwork	\$0	\$281,158	(\$281,158)	-100.00%
<b>2012</b> G10 SITE PREPARATION TOTAL	<b>\$0</b>	<b>\$281,158</b>	<b>(\$281,158)</b>	<b>-100.00%</b>
<b>2013</b>				
<b>2014</b> G20 G20 SITE IMPROVEMENTS				
<b>2015</b> G2020 Roadways	\$0	\$0	\$0	
<b>2016</b> G2030 Pedestrian Paving	\$16,675	\$227,154	(\$210,479)	-92.66%
<b>2017</b> G2040 Site Development	\$340,500	\$975,872	(\$635,372)	-65.11%
<b>2018</b> G2050 Landscaping	\$1,044,545	\$826,078		100.00%
<b>2019</b> G20 SITE IMPROVEMENTS TOTAL	<b>\$1,401,720</b>	<b>\$2,029,104</b>	<b>(\$845,851)</b>	<b>-41.69%</b>
<b>2020</b>				
<b>2021</b> G30 G30 SITE CIVIL/MECHANICAL UTILITIES				
<b>2022</b> G3010 Water Supply	\$0	\$0	\$0	
<b>2023</b> G3020 Sanitary Sewer	\$0	\$0	\$0	

**Fuller Middle School**  
Fuller Middle School

**DIRECT COST SUMMARY - NEW CONSTRUCTION**

<b><u>DIV. ELEMENTS</u></b>	<b><u>90%CD</u></b> <b><u>TOTAL</u></b>	<b><u>60%CD</u></b> <b><u>TOTAL</u></b>	<b><u>DIFFERENCE</u></b>	<b><u>% DIFF</u></b>
	137,385 GSF	136,600 GSF	785 GSF	0.57%
<b>2024</b>	G3030 Storm Sewer	\$0	\$0	\$0
<b>2025</b>	G3040 Heating Distribution	\$0	\$0	\$0
<b>2026</b>	G30 SITE CIVIL/MECHANICAL UTILITIES TOTAL	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>
<b>2027</b>				
<b>2028</b>	G40 G40 SITE ELECTRICAL UTILITIES			
<b>2029</b>	G4010 Site Electrical Utilities	\$0	\$476,743	(\$476,743) -100.00%
<b>2030</b>	G40 SITE ELECTRICAL UTILITIES TOTAL	<b>\$0</b>	<b>\$476,743</b>	<b>(\$476,743) -100.00%</b>
<b>2031</b>				
<b>2032</b>	BP BID PACKAGES			
<b>2033</b>	BP#1 (Main Summary)	<b>\$0 INCLUDED</b>	<b>\$0</b>	100.00%
<b>2034</b>	BP#2 (Main Summary)	<b>\$0</b>		
<b>2035</b>	BID PACKAGES TOTAL	<b>\$0</b>		<b>100.00%</b>
<b>2036</b>				
<b>2037</b>	<b>G BUILDING SITEWORK TOTAL</b>	<b>\$1,401,720</b>	<b>\$2,787,005</b>	<b>(\$1,603,752) -57.54%</b>
<b>2038</b>				
<b>2039</b>				
<b>2040</b>	<b>CONSTRUCTION TRADE TOTAL</b>	<b>\$43,945,593</b>	<b>\$49,749,822</b>	<b>(\$6,022,695) -12.11%</b>
<b>2041</b>				
<b>2042</b>	Demolish Existing Building	\$1,465,500	\$1,465,500	\$0 0.00%
<b>2043</b>	Hazardous Waste Abatement (Budget provided)	\$1,294,490	\$1,384,630	(\$90,140) -6.51%
<b>2044</b>	Design and Pricing Contingency	\$1,401,167	\$2,629,998	(\$1,228,831) -46.72%
<b>2045</b>				
<b>2046</b>	<b>Building Cost</b>	<b>\$48,106,750</b>	<b>\$55,229,950</b>	<b>(\$5,690,064) -10.30%</b>
<b>2047</b>				
<b>2048</b>	Escal. to Midpoint of Construction (June '20 Start)	\$481,068	\$828,449	(\$347,381) -41.93%
<b>2049</b>	<b>Trade Cost SubTotal</b>	<b>\$48,587,818</b>	<b>\$56,058,399</b>	<b>(\$7,968,175) -14.21%</b>
<b>2050</b>				
<b>2051</b>	General Conditions	\$2,931,033	\$3,401,447	(\$470,414) -13.83%
<b>2052</b>	General Requirements	\$2,289,380	\$2,652,483	(\$363,103) -13.69%
<b>2053</b>	Builder's Risk	\$0	\$0	\$0
<b>2054</b>	Traffic mitigation	\$0	\$0	\$0
<b>2055</b>	SDI	\$269,858	\$360,000	(\$90,142) -25.04%
<b>2056</b>	Sub Bonds	\$403,034	\$410,000	(\$6,966) -1.70%
<b>2057</b>	General Liability Insurance	\$576,109	\$668,571	(\$92,462) -13.83%
<b>2058</b>	Performance & Payment Bond	\$0	\$0	\$0
<b>2059</b>	Construction Contingency	\$1,376,431	\$1,401,460	(\$25,029) -1.79%
<b>2060</b>	CM Fee	\$1,152,218	\$1,337,143	(\$184,925) -13.83%
<b>2061</b>			\$10,957,843	
<b>2062</b>				
<b>2063</b>				
<b>2064</b>	<b>Estimated Construction Cost Total</b>	<b>\$77,231,769</b>	<b>\$77,247,346</b>	<b>(\$15,577) -0.02%</b>
<b>2065</b>				



### 2.3.6 Reconciled Cost Estimate - OPM

Attached is the reconciled OPM Cost Estimate and Cost Estimate Comparison Spreadsheet.





**90% Construction Documents  
Fuller Middle School  
Framingham, MA**

9-Oct-19

BUILDING AND SITEWORK	\$57,595,405
EARLY SITE PACKAGE #1	\$10,957,843
EARLY SITE PACKAGE #2	\$8,738,801
BUT OUT CREDIT	<b>(\$50,755)</b>
-----	
TOTAL CONSTRUCTION COST	\$77,241,293

**90% Construction Documents**  
**Fuller Middle School**  
**Framingham, MA**

9-Oct-19

NEW BUILDING				\$42,898,538
SITework				\$1,380,102
BUILDING DEMOLITION	196,000	GSF	\$6.98	\$1,367,800
ASBESTOS REMOVAL ( Consigli sub )				\$1,602,280
TOTAL DIRECT COST ( estimated to the mid-point of construction )				----- \$47,248,720
Chapter 149 a:				
DESIGN CONTINGENCY		3.0%		\$1,417,462
CM CONTINGENCY		2.5%		\$1,216,655
ESCALATION ( bid 12/19 )		1.0%		\$498,828
SDI				\$265,000
SUB BOND		inc. w/ trade		
GENERAL REQUIREMENTS				\$2,289,380
GENERAL CONDITIONS				\$2,931,033
TRAFFIC MITIGATION				\$0
BUILDING PERMIT		waived		
GENERAL LIABILITY INSURANCE				\$576,109
FEE				\$1,152,218
				-----
				TOTAL CONSTRUCTION COST
				\$57,595,405
				COST PER S.F.
				\$421.64

EARLY SITE PACKAGE #1		\$8,711,049
		-----
TOTAL DIRECT COST ( estimated to the mid-point of construction )		\$8,711,049
Chapter 149 a:		
SDI		\$120,894
CM CONTINGENCY	2.5%	\$220,799
ESCALATION ( bid 12/19 )	2%	\$0
GENERAL REQUIREMENTS		\$432,020
GENERAL CONDITIONS		\$586,777
BUILDERS RISK		\$115,218
GENERAL LIABILITY INSURANCE		\$111,429
P&P BOND		\$436,800
FEE		\$222,857
		-----
	TOTAL CONSTRUCTION COST	\$10,957,843

EARLY SITE PACKAGE #2		\$7,339,465
		-----
TOTAL DIRECT COST ( estimated to the mid-point of construction )		\$7,339,465
Chapter 149 a:		
SDI		\$102,386
CM CONTINGENCY	2.5%	\$186,046
GENERAL REQUIREMENTS		\$363,102
GENERAL CONDITIONS		\$470,414
BUILDERS RISK	IN BP #1	\$0
GENERAL LIABILITY INSURANCE		\$92,462
P&P BOND	IN BP #1	\$0
FEE		\$184,925
		-----
	TOTAL CONSTRUCTION COST	\$8,738,801

PROJECT: Fuller Middle School  
 LOCATION: Framingham, MA  
 CLIENT: SMMA Architects  
 DATE: 09-Oct-19

NO. OF SQ. FT.: 136,600  
 COST PER SQ. FT.: \$324.15

SUMMARY

No.: 18020

	DIVISION TOTAL	PERCENT OF PROJECT	COST PER SF
<b>DIVISION 02 - EXISTING CONDITIONS</b>			
024117 BUILDING DEMOLITION	75,000	0%	0.55
024180 ASBESTOS ABATEMENT	0	0%	0.00
<b>DIVISION 03 - CONCRETE</b>			
033000 CAST IN PLACE CONCRETE	0	0%	0.00
<b>DIVISION 04 - MASONRY</b>			
042000 UNIT MASONRY*	2,296,962	5%	16.82
<b>DIVISION 05 - METALS</b>			
051200 STRUCTURAL STEEL FRAMING	0	0%	0.00
053000 METAL DECKING	0	0%	0.00
054000 COLD FORMED METAL FRAMING	0	0%	0.00
055000 METAL FABRICATIONS*	1,162,710	3%	8.51
<b>DIVISION 06 - WOOD, PLASTICS &amp; COMPOSITES</b>			
061000 ROUGH CARPENTRY	0	0%	0.00
062000 FINISH CARPENTRY	2,078,706	5%	15.22
<b>DIVISION 07 - THERMAL &amp; MOISTURE PROTECTION</b>			
071000 DAMPPROOF., WATERPROOF. & CAULKING*	761,028	2%	5.57
070002 ROOFING AND FLASHING*	1,541,922	3%	11.29
072100 THERMAL INSULATION	0	0%	0.00
072600 VAPOR RETARDERS	0	0%	0.00
074214 EXTERIOR WALL PANELS	1,155,569	3%	8.46
078100 FIREPROOFING	381,208	1%	2.79
078400 FIRESTOPPING	0	0%	0.00
079513 EXPANSION JOINTS (NO SPEC)	40,000	0%	0.29

	DIVISION TOTAL	PERCENT OF PROJECT	COST PER SF
<b>DIVISION 08 - OPENINGS</b>			
080001 METAL WINDOWS*	2,270,752	5%	16.62
080002 GLASS AND GLAZING*	882,247	2%	6.46
081113 HOLLOW METAL DOORS & FRAMES	136,485	0%	1.00
081416 FLUSH WOOD DOORS	159,225	0%	1.17
083100 ACCESS DOORS AND PANELS	30,000	0%	0.22
083323 SPECIAL DOORS	80,793	0%	0.59
084513 STRUCT-POLYCARBONATE PNL ASSEMB. & SKYLIG	14,350	0%	0.11
087100 DOOR HARDWARE	366,760	1%	2.68
089000 LOUVERS & VENTS	84,000	0%	0.61
<b>DIVISION 09 - FINISHES</b>			
090003 TILE*	229,896	1%	1.68
090006 RESILIENT FLOORING*	868,464	2%	6.36
090009 PAINTING*	547,406	1%	4.01
092116 GYPSUM WALLBOARD ASSEMBLIES	5,724,632	13%	41.91
095100 ACOUSTICAL CEILINGS*	932,456	2%	6.83
096446 WOOD & ATHLETIC FLOORING	225,065	1%	1.65
096712 RESINOUS FLOORING	109,314	0%	0.80
096800 CARPET	8,456	0%	0.06
097217 DIGITAL IMAGE WALL COVERINGS	0	0%	0.00
097233 DRY-ERASE WALL COVERING	0	0%	0.00
097733 SANITARY WALL PANELS	0	0%	0.00
098100 ACOUSTICAL INSULATION	0	0%	0.00
098400 ACOUSTIC ROOM COMPONENTS	0	0%	0.00
098415 WOOD FIBER ACOUSTICAL PANELS	0	0%	0.00
<b>DIVISION 10 - SPECIALTIES</b>			
101100 MARKERBOARDS & TACKBOARDS	180,800	0%	1.32
101400 SIGNAGE	68,144	0%	0.50
102113 TOILET COMPARTMENTS	55,590	0%	0.41
102600 WALL AND DOOR PROTECTION	10,000	0%	0.07
102813 TOILET ACCESSORIES	35,127	0%	0.26
104000 SAFETY SPECIALTIES	22,800	0%	0.17
107113 EXTERIOR SUN CONTOL DEVICES	0	0%	0.00
109000 MISCELLANEOUS SPECIALTIES	710,940	2%	5.20
<b>DIVISION 11 - EQUIPMENT</b>			
113100 RESIDENTIAL APPLIANCES	10,350	0%	0.08
114000 FOOD SERVICE EQUIPMENT	415,270	1%	3.04
115213 PROJECTION SCREENS	65,000	0%	0.48
116143 THEATRICAL EQUIPMENT(No Spec)	866,921	2%	6.35
116600 ATHLETIC & SPORTS EQUIPMENT	102,621	0%	0.75
119000 MISC. EQUIPMENT	32,500	0%	0.24
	DIVISION TOTAL	PERCENT OF PROJECT	COST PER SF

<b>DIVISION 12 - FURNISHINGS</b>			
122400 WINDOW SHADES	136,136	0%	1.00
122414 MOTORIZED WINDOW SHADES	0	0%	0.00
123553 CASEWORK	323,013	1%	2.36
124813 FLOOR MATS	7,920	0%	0.06
124816 ENTRANCE GRILLES & FRAMES	0	0%	0.00
126613 TELESCOPING BLEACHERS	81,250	0%	0.59
129000 MISCELLANEOUS FURNISHING	106,445	0%	0.78
<b>DIVISION 13 - SPECIAL CONSTRUCTION</b>			
130000 SPECIAL CONSTRUCTION	0	0%	0.00
<b>DIVISION 14 - CONVEYING EQUIPMENT</b>			
140001 ELEVATORS*	212,000	0%	1.55
<b>DIVISION 21 - FIRE SUPPRESSION</b>			
210001 FIRE SUPPRESSION*	893,565	2%	6.54
<b>DIVISION 22 - PLUMBING</b>			
220001 PLUMBING*	2,150,852	5%	15.75
<b>DIVISION 23 - HVAC</b>			
230001 HVAC*	8,247,841	19%	60.38
<b>DIVISION 26 - ELECTRICAL</b>			
260001 ELECTRICAL*	6,000,049	14%	43.92
<b>DIVISION 31 - EARTHWORK</b>			
310000 EARTHWORK	0	0%	0.00
311000 SITE PREPARATION & CLEARING	0	0%	0.00
<b>DIVISION 32 - EXTERIOR IMPROVEMENTS</b>			
321000 PAVEMENT, CURBING & EDGING	0	0%	0.00
323100 SITE IMPROVEMENTS	271,675	1%	1.99
328000 IRRIGATION	165,792	0%	1.21
329000 LANDSCAPING	942,635	2%	6.90
<b>DIVISION 33 - UTILITIES</b>			
330000 UTILITIES	0	0%	0.00
	-----		
DIRECT COST	44,278,640	100%	324.15

\*DENOTES FILED SUB-BID

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
DIVISION 02 - EXISTING CONDITIONS				
024117 BUILDING DEMOLITION	SEE SUMMARY			
Staged Floor at Aud	1	LS	75,000.00	75,000
				----- 75,000
024180 ASBESTOS ABATEMENT	SEE SUMMARY			
				----- 0
DIVISION 03 - CONCRETE				
033000 CAST IN PLACE CONCRETE	SEE BID PACKAGE #2			
				----- 0
DIVISION 04 - MASONRY				
042000 UNIT MASONRY*				
Exterior Walls:				
Backup :				
Gym 12" CMU Back-up - Exposed	7,497	SF	25.50	191,174
Aud 12" CMU Back-up - Exposed	7,342	SF	25.50	187,221
Int GF finish premium	7,342	SF	5.50	40,381
*A462 GF is not noted				
Masonry Veneer Building ( QTY Noted):				
4x4x12 Scored brick veneer	6,252	SF	34.00	212,568
4x8x8 Scored brick veneer	6,722	SF	36.00	241,992
4x8x16 Scored ground face CMU	23,500	SF	31.00	728,500
4x4x12 Scored ground face CMU	3,512	SF	33.50	117,652
3" Mineral fiber insul @ masonry	43,331	SF	3.72	161,191
A501 Premium:				
Sill brick		w/Unit Cost		
Lip brick		w/Unit Cost		
Temporary shoring at CMU Bearing	1	LS	100,000.00	100,000
SS Masonry flashing	1	LS	35,000.00	35,000

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Staging		inc. w/ unit		
Precast Concrete:				
Misc. BLDG precast veneer		N/A		
*Site planters are included w/ site improvements				
2nd Floor Main Entry Terrace:				
(3/ A316)3'6"H Brick Partial HT wall-comj	26	LF	440.00	11,440
(3/ A316) Wall Cap	26	LF	175.00	4,550
Partitions:				
Interior 12" CMU Partition:				
Gym - 28'	4,480	SF	29.00	129,920
Auditorium - 28'	2,660	SF	29.00	77,140
Auditorium - 14'	420	SF	26.00	10,920
GF CMU - Aud. Only	2,660	SF	4.50	11,970
Acoustical Block - Premium	1,000	SF	6.50	6,500
Stage front CMU pier (5 loc)	22.5	SF	55.00	1,238
Int GF finish premium	5,740	SF	4.50	25,830
CMU Partition (Gym & Aud):				
Bond beam	37	LF	48.00	1,776
				-----
				2,296,962

DIVISION 05 - METALS

051200 STRUCTURAL STEEL FRAMING

SEE BID PACKAGE #2

-----  
0

053000 METAL DECKING

SEE BID PACKAGE #2

-----  
0

054000 COLD FORMED METAL FRAMING



DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
*w/ gypsum drywall				----- 0
055000 METAL FABRICATIONS*				
Elevators:				
Elev. framing	1	EA	3,000.00	3,000
Elev. pit ladder	1	EA	1,537.00	1,537
Elev. sump grate	1	EA	1,500.00	1,500
Exterior Walls:				
42" Perf Metal Guardrail:				
LVL 2 entry	11	LF	350.00	3,850
LVL 2 emerg. egress	42	LF	350.00	14,700
LVL 2 emerg. egress stair wall rail	8	LF	145.00	1,160
Galv, loose lintel (per 5600-604)	133	LF	36.00	4,788
Misc metals @ ext wall - allow	1	LS	25,000.00	25,000
Reliving angle		W /Structural		
Bolted galv. sill angle @ fnd		W /Structural		
Support clip @ skylight curb (spec)	567	LF	125.00	70,875
Exterior Doors:				
OH door frame @:				
Tech-Makerspace	1	EA	500.00	500
Special Doors:				
LVL 1 Corridor Security Gate- sgl ( 7' x7'1	2	EA	7,000.00	14,000
Partitions:				
Folding Panel partition Support (18/A620):				
Typ classroom (13 EA)	208	LF w/ pacakge #2		
Music classroom (DBL panel 1 EA)	19	LF w/ pacakge #2		
SPED suite (3 EA)	120	LF w/ pacakge #2		
Folding Grille Support @:				
Learning common	46	LF	200.00	9,200
Sgl custom security gate (7'w)	2	EA	4,000.00	8,000
Coiling Grille Support @:				
Servery	35	LF	100.00	3,500
Main office(1 EA)	21	LF	100.00	2,100
CMU Partition (Gym & Aud):				
CMU clip @ 4' oc	70	EA	115.00	8,050

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Misc Metals @ Corridor Locker Enclosure (nic mtl locker) - allow (7/A650):				
1st Floor (307 LF)		N/A		
Upper floors		w/ package #2		
Misc. metals	136,600	GSF	1.00	136,600
1/4" Stl plate @ tile - 6" w (10/A620)	1	LS	15,000.00	15,000
Fittings:				
Auditorium:				
Stage front access stair rails (9/A602)	32	LF	145.00	4,640
Aisle access stair rails (11/A602)	34	LF	145.00	4,930
Auditorium equip. supports	1	LS	15,000.00	15,000
Interior Metals:				
1st Flr guard rail (5.39)	20	LF	350.00	7,000
2nd & 3rd Flr Lobby guard rail (6/A650)	327	LF	450.00	147,150
Cohort # 2059 2nd Flr Lobby guard rail (6	19	LF	450.00	8,550
OT/PT equip support-allow	1	RM	2,500.00	2,500
Gym equip supports	1	LS	10,000.00	10,000
Concealed stl angle @ corr built-in bench		W/ Unit Cost		
Concealed stl angle @ casework ctr		W/ Unit Cost		
Ships ladder @ gym storage	1	EA	15,000.00	15,000
Interior:				
4/ A601 Curved perf arch grille - classroom	1,536	SF	50.00	76,800
Support atrium vert duct encl.	4	LOC	10,000.00	40,000
Exterior Rails:				
Roof ladder (3 EA)	30	VLF	425.00	12,750
Loading dock stair/ramp guardrail	15	LF	265.00	3,975
Loading dock stair/ramp wall rail	15	LF	150.00	2,250
2nd flr entry terrace guardrail	30	LF	500.00	15,000
High roof safety rail - allow	150	LF	125.00	18,750
Stair Construction:				
5' 6"W Metal Pan Stair #3 @ Learning Commons 1st- 2nd (1 FLT):				
Metal pan stair treads/risers	132	LFR	95.00	12,540
Metal pan landing	33	SF	75.00	2,475
Guardrail	66	LF	400.00	26,400
Cane rail	1	EA	1,350.00	1,350
8'6" W Metal Pan Stair #14 @ Learning Commons 1st- 2nd ( 1 FLT):				
Metal pan stair treads/risers	204	LFR	95.00	19,380
Metal pan landing	51	SF	75.00	3,825
Guardrail	66	LF	400.00	26,400

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Cane rail	1	EA	1,350.00	1,350
5'10" W Metal Pan Stair #6 @ Learning Commons 2nd - 3rd( 1 FLT):				
Metal pan stair treads/risers	138	LFR	95.00	13,110
Metal pan landing	33	SF	75.00	2,475
Guardrail	66	LF	400.00	26,400
8' 6"W Metal Pan Stair #5 @ Learning Commons 2nd - 3rd(1 FLT):				
Metal pan stair treads/risers		w/ package #2		
Metal pan landing		w/ package #2		
Guardrail	66	LF	400.00	26,400
5' W Metal Pan Stair Hall 1 & 2 ( 2 loc 1st - 3rd 4 FLT):				
Metal pan stair treads/risers	480	LFR	95.00	45,600
Metal pan landing	240	SF	75.00	18,000
Wall rail	128	LF	165.00	21,120
Guardrail	128	LF	400.00	51,200
Guardrail flr open	12	LF	400.00	4,800
Cane rail	2	EA	1,350.00	2,700
5' W Metal Pan Stair @ #1 Penthouse ( 1 FLT):				
Metal pan stair treads/risers	120	LFR	95.00	11,400
Metal pan landing	60	SF	75.00	4,500
Wall rail	32	LF	165.00	5,280
Guardrail	32	LF	400.00	12,800
Access gate	1	EA	1,800.00	1,800
Ceiling Finishes:				
Note #5.55 Perf Arch Grille:				
3rd Flr clg -12"W	210	SF	200.00	42,000
Site Development:				
Ramp and Planter Walls:				
Railings	146	LF	250.00	36,500
Site Stair:				
Site stair railing	33	LF	250.00	8,250
Site decorative bollard		deleted		
Stage Plenum (7/A602):				
Perf. arch grille - stage front	120	SF	225.00	27,000
				-----
				1,162,710

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

## DIVISION 06 - WOOD, PLASTICS &amp; COMPOSITES

## 061000 ROUGH CARPENTRY

-----  
0

## 062000 FINISH CARPENTRY

## Exterior Walls:

## Main Entry LVL 2:

Wd bench @ precast planter	24	LF	550.00	13,200
Phenolic bench @ col. M	7	LF	500.00	3,500

## Partitions:

## Interior Borrowed Light Window /Sidelight-A620 (NIC Break out Area):

PTD MDF sill 9"	866	LF	32.00	27,712
PTD MDF head 9"	866	LF	25.00	21,650
PTD MDF jamb 9"		N/A		

## Fittings:

## Finish Carpentry:

A312 Int window panel grilles (Rulon)	450	LF	150.00	67,500
---------------------------------------	-----	----	--------	--------

\*casework is included w/ E2010

## Wall Finishes:

## (16/A621) 18" PTD MDF Bumper w/HD Bamboo Wd Marker Tray:

Bumper Rail	3,480	LF	45.00	156,600
Bumper Top	3,480	LF	30.00	104,400

## Wall Finish:

## P.lam Wall Panel:

11/A600 Drinking Fountain Alcove (7 loc	245	SF	55.00	13,475
P.Lam wall panel @ class entry controls	59	LOC	550.00	32,450
Auditorium vestibule	393	SF	48.00	18,864
Stage full ht	2,880	SF	48.00	138,240

## Ceiling Finishes:

## Auditorium/Stage-(A461 &amp; A691):

Clouds - allow	2,076	SF	120.00	249,120
----------------	-------	----	--------	---------

\*Clouds 3/4" Veneer w/wood trim - includes hardware and hangers

Utility & closet shelving	1	LS	10,000.00	10,000
---------------------------	---	----	-----------	--------

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Solid surface lav ctr	243	LF	265.00	64,395
Display Case ( 6/A401)	18	LF	1,000.00	18,000
Art recess corridor #2000	1	LS	15,000.00	15,000
Classroom Entry:				
Corridor built-in bench A621 4'w	212	LF	400.00	84,800
Framing and Blocking:				
Corridor Locker Enclosure (nic mtl locker) - allow (7/A650):				
Freestanding - 1st flr	307	LF	320.00	98,240
Freestanding - upper flr	724	LF	320.00	231,680
Main Office 2nd Floor:				
P. lam Radial Reception counters	20	LF	650.00	13,000
Radial work island /work table	38	SF	165.00	6,270
Reception work ctr	10	LF	325.00	3,250
Tall storage unit 4'	3	EA	1,650.00	4,950
Mail unit wall cab	16	LF	750.00	12,000
Mail area work ctr	16	LF	250.00	4,000
Mobile storage cab (36"x27"h)		w/ ffe		
Copier area work ctr	16	LF	250.00	4,000
Large conf base cab w/ctr	15	LF	450.00	6,750
Work space work ctr	16	LF	250.00	4,000
Library / Media Center (1 EA):				
P. lam circulation desk - radial	11	LF	1,200.00	13,200
Book shelving sys - free standing		NIC		
8'6" Book shelving sys-perm fixed unit	39	LF	500.00	19,500
P. lam work ctr	27	LF	175.00	4,725
Mobile storage cab (36"x27"h)		w/ ffe		
30" P. lam work ctr	33	LF	220.00	7,260
Art Class Room (1 EA):				
3' Tall storage cab	4	EA	1,550.00	6,200
Tech-Makerspace ( 1 EA):				
30" P. lam counter w/backsplash(no base c	10.5	LF	230.00	2,415
Mobile storage cab (36"x27"h)		w/ ffe		
24" P. lam back splash	21	SF	25.00	525
4 Tier shelving unit	3	LF	400.00	1,200
(6.81) Shadow relief	2	EA	450.00	900
Fab-lab ( 1 EA):				
P.lam Counter	13.5	LF	230.00	3,105
Mobile storage cab (36"x27"h)		w/ ffe		
24" P. lam back splash	27	SF	25.00	675
4 Tier shelving unit	3	LF	400.00	1,200

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
(6.81) Shadow relief 3D mdo	2	EA	450.00	900
Class Closet ( 34 EA):				
12" MDO lowest Shelf w/ framing (4'6"/LC	153	LF	45.00	6,885
12" Shelving (4 tier- 18'/loc)	612	LF	42.00	25,704
Teacher Prep Room (24 EA):				
P Lam ctr w/ wd edge ( 11'/loc)		N/A		
12" MDO lowest Shelf w/ framing (9' LOC	216	LF	45.00	9,720
12" Shelving (4 tier- 36'/loc)	864	LF	42.00	36,288
Typ, SPED & ELL Classroom (32 EA - A410):				
30" P Lam ctr w/ wd edge ( 12' 6"/loc)	400	LF	275.00	110,000
30" P Lam flip top ctr w/ wd edge ( 3'/loc)	96	LF	325.00	31,200
Mobile storage cab (36"wx27"h 3/RM)		w/ ffe		
4 tier shelving unit (10' /loc)	320	LF	400.00	128,000
(6.81) Shadow relief 3D mdo (3/rm)	96	EA	450.00	43,200
Music Classroom ( 2 EA):				
30" P Lam ctr w/ wd edge	26	LF	275.00	7,150
Mobile storage cab (36"wx27"h 2/RM)		w/ ffe		
Ext wall 4 tier shelving unit 8'6" - (1/loc)	17	LF	400.00	6,800
(6.81) Shadow relief 3D mdo (2/rm)	4	EA	450.00	1,800
Drama Classroom ( 1 EA):				
30" P Lam ctr w/ wd edge	16	LF	275.00	4,400
24" P.lam backsplash	32	SF	25.00	800
Mobile storage cab (36"wx27"h)		w/ ffe		
SPED Classroom #1260 ( Additional casework 1 EA):				
Sink ctr w/skirt	6	LF	300.00	1,800
24" P.lam backsplash	17	SF	25.00	425
SPED Classroom #2260 ( Additional casework 1 EA):				
42" Wall cab	15	LF	225.00	3,375
Sink ctr w/skirt	15	LF	300.00	4,500
20" P.lam backsplash	25	SF	25.00	625
Staff Lunch Room ( 1 EA):				
Base cab w/p.lam ctr	7.5	LF	425.00	3,188
Custodian Office (1 EA):				
Work ctr	9	LF	165.00	1,485
Medical Suite (A425):				
Work ctr	15	LF	165.00	2,475
Wall cab	8	LF	200.00	1,600

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Open wall cab	7	LF	225.00	1,575
Microwave shelf	3	LF	225.00	675
Aud Dressing room (2 EA):				
P.lam counter w/ backsplash(no base cab)	38	LF	225.00	8,550
Auditorium:				
P.lam AV ctr	9	LF	165.00	1,485
P.lam projector support	1	LOC	1,500.00	1,500
P lam low wall @ seating complete	89	LF	475.00	42,275
Guidance Suite (3 Loc):				
Base cab w/ctr	8	LF	350.00	2,625
Wall cab	15	LF	210.00	3,150
Misc. Casework Allowance:				
Misc Display Cases (19/A621)	1	LS	20,000.00	20,000
Trash/ recycle ctr - allow	1	EA	10,000.00	10,000
Corridor bench	34	LF	600.00	20,400
Kit. serving ctr (4/603)		w/ food service		
*Counter tops include manufactures wall brackets				
Window Sill	1,100	LF	42.00	46,200
				-----
				2,078,706

DIVISION 07 - THERMAL & MOISTURE PROTECTION

071000 DAMPPROOF., WATERPROOF. & CAULKING\*

Foundations:				
Foundation dampproofing	6,884		w/ package #2	
Retaining wall waterproofing	1,360		w/ package #2	
Elev. pit waterproofing	1		w/ package #2	
Exterior Walls:				
Fluid Applied air & vapor barrier:				
Exterior Wall - CMU & Sheathing	59,125	SF	8.00	473,000
Bay covered entry	1,119	SF	8.00	8,952

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Exterior Windows:				
Flex flashing - perm	9,009	LF	8.00	72,072
Perm Window Caulking	9,000	LF	9.50	85,500
Exterior Doors:				
Perm. Ext HM & OH opening:				
Flex flashing - perm	348	LF	8.00	2,784
Exterior sealants - perm.	348	LF	7.50	2,610
Partitions:				
Joint sealants	136,600	GSF	0.85	116,110
				-----
				761,028

## 070002 ROOFING AND FLASHING\*

## Exterior Walls:

(1/A543) Raised Common Exterior Wall:

5'6"H Rigid Insul. W/ PVC Membrane( sa ) 2,486 SF 15.00 37,290

## Roofing (A502):

White 60 mil PVC Roofing w/R-36 (6" Insul ) :

Typ Flat roof	64,092	SF	16.25	1,041,495
1/2 " glass mat cover bd -100%	64,092	SF	1.45	92,933
1/2" glass mat protection bd(nic conc deck	23,302	SF	1.45	33,788
1/2" glass mat protection 2 lysr aud	7,563	SF	5.20	39,328
Poly vapor retarder-100%	64,092	SF	0.42	26,919
3' High Rubber Walkway Pad	765	SF	7.00	5,355
Membrane flashing	64,092	SF	0.50	32,046
Base flashing	1,620	LF	32.00	51,840
Alum Typ roof fascia	3,182	LF	22.00	70,004
Expansion joint - allow	86	LF	185.00	15,910
Flash gable skylight curb ( 4 EA)	567	LF	32.00	18,144
Scupper - allow	4	EA	750.00	3,000
Flash roof drain - allow	32	EA	135.00	4,320
Entry pier/chimney cap flashing -complete	55	SF	100.00	5,500

## Premium Terrace Paver Sys (1/A316):

Main entrance #2000 730 SF 45.00 32,850

\*Includes Sections 075419, 076200, 077236 &amp; 086300

## Roof Openings:

Roof hatch	1	EA	4,200.00	4,200
Stage vent-allow	2	EA	13,500.00	27,000



DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
				----- 1,541,922
072100 THERMAL INSULATION				
Slab on Grade:				
2" Rigid Slab Insul.- 4' @ perm.		SEE BID PACKAGE #1		----- 0
072600 VAPOR RETARDERS				
*Excludes under slab waterproofing system				
				----- 0
074214 EXTERIOR WALL PANELS				
Exterior Walls:				
Exterior Wall Panel System:				
Corrugated metal panel	5,500	SF	46.00	253,000
Composite metal panel	2,662	SF	50.00	133,100
Phenolic panel	8,518	SF	76.00	647,368
8'H Mech roof screen(NIC Struct Frame - 8/A325):				
8' Corrugated Perf Mtl wall panel-complete	1,112	SF	42.00	46,704
Screen wall cap - allow	139	LF	30.00	4,170
(2 sided) Phenolic fin - complete:				
3' Fin 12'4"H (5 loc)	200	SF	120.00	24,000
*Includes Sections 074214 & 074224				
Exterior Walls:				
Exterior Wall A501:				
4" Mineral fiber insul @ panel wall	11,380	SF	4.15	47,227
				----- 1,155,569

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

078100 FIREPROOFING

Floor Construction:

Allow:

Spray fireproofing	68,431	SF	3.00	205,293
--------------------	--------	----	------	---------

Roof Construction:

Allow:

Spray fireproofing	36,041	SF	2.80	100,915
--------------------	--------	----	------	---------

Roof Construction:

Intumescent paint - roof struct.	1	LS	75,000.00	75,000
----------------------------------	---	----	-----------	--------

\*Exposed structure @ atrium noted

\*Includes Section 099646

-----  
381,208

078400 FIRESTOPPING

-----  
0

079513 EXPANSION JOINTS (NO SPEC)

Exterior Walls:

Control and expansion joints	1	LS	30,000.00	30,000
------------------------------	---	----	-----------	--------

Partitions:

Int Wall Expansion joints	1	LS	10,000.00	10,000
---------------------------	---	----	-----------	--------

-----  
40,000

DIVISION 08 - OPENINGS

080001 METAL WINDOWS\*

Exterior Doors:

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Alum. Doors (Incl. Glass, Glazing):				
7' 1st Flr Entry - sgl	2	EA	4,100.00	8,200
7' 1st Flr Entry - dbl	3	PR	8,200.00	24,600
7' 2nd Flr Entry - sgl	1	EA	4,100.00	4,100
7' 2nd Flr Entry - dbl	1	PR	8,200.00	8,200
7' Main office egress - sgl	1	EA	4,100.00	4,100
7' Stair egress - sgl	2	EA	4,100.00	8,200
7' Staff lunch rm	1	EA	4,100.00	4,100
8' Media ctr - sgl	1	EA	4,100.00	4,100
Premium :				
Auto opener	3	EA	4,500.00	13,500
Ext. School Guard (6 lvs ) - Factory glazing	90	SF	36.00	3,240
Interior Doors:				
Aluminum ( Frame, Door, Glass, Glazing and Hdw):				
7' 1st Flr Entry Vestibule - sgl	1	EA	4,000.00	4,000
7' 1st Flr Entry Vestibule - dbl	2	PR	8,150.00	16,300
8' 2nd Flr Entry Vestibule- sgl	1	EA	4,400.00	4,400
8' 2nd Flr Entry Vestibule - dbl	1	PR	8,600.00	8,600
Premium:				
Int. School Guard ( 11 lvs ) - Factory glazing	154	SF	36.00	5,544
Exterior Windows - Allow:				
Storefront	12,130	SF	110.00	1,334,300
Exterior sealants - perm.	9,009	LF	7.50	67,568
ALLOW:				
Security Glazing Film 2nd flr entry	125	SF	36.00	4,500
Exterior Wall Mock-up	1	LS	35,000.00	35,000
Partitions:				
Aluminum Storefront Frame, Glass & Glazing-Allow:				
1st Floor Vestibule (11A/A221)		w/B2010		
Office/ vestibule security window (6/A403)				
2nd Flr Main office	1	EA	5,000.00	5,000
Roof Openings:				
Gable Skylight ( 4 loc)	4,261	SF	150.00	639,150
Gable Skylight End wall ( 8 loc)	427	SF	150.00	64,050
				-----
				2,270,752

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
080002 GLASS AND GLAZING*				
Fittings:				
Multi User Toilet & Locker Rm (16 ea):				
5'H mirror @ lav ctr	1,215	SF	38.00	46,170
Dressing Rm (2 ea):				
5'H mirror @ ctr	90	SF	38.00	3,420
Site Development:				
Band Shell (A500):				
9/16 " Temp. lam glazing - roof	132	SF	175.00	23,100
9/16 " Temp. lam glazing - wall	254	SF	175.00	44,450
Partitions:				
Interior Window /Sidelight-A620 (NIC Break out Area):				
SGL Alum channel ,glass & glazing	5,471	SF	62.00	339,202
DBL Alum channel ,glass & glazing	930	SF	88.00	81,840
GL-Graduated pattern film premium	3,094	SF	10.00	30,940
3m Safety Glazing	4,332	SF	15.00	64,980
Interior Doors:				
Glass & Glazing @ Interior Wood Door:				
Sgl C1 7'H ( 6 EA )	60	SF	48.00	2,880
Sgl C1 8'H ( 105 EA )	1,260	SF	48.00	60,480
Dbl C2 8'H ( 9 EA )	216	SF	48.00	10,368
Dbl C3 8'H ( 1 EA )	4	SF	48.00	192
Breakout Space:				
Breakout A( 2 story):				
Glass wall w/ perim trim	377	SF	75.00	28,275
Breakout B( 2 story):				
Glass wall w/ perim trim	906	SF	75.00	67,950
Breakout C ( 2 story):				
Glass wall w/ perim trim	677	SF	75.00	50,775
Breakout D( 1 story):				
Glass wall w/ perim trim	215	SF	75.00	16,125
Breakout E ( 1 story):				
Glass wall w/ perim trim	148	SF	75.00	11,100
				-----
				882,247

## 081113 HOLLOW METAL DOORS &amp; FRAMES

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Interior Doors:				
Int. HM Door Frame:				
Single Door 7'H	22	EA	285.00	6,270
Double Door 7'H	1	EA	305.00	305
Single Door 8' H	251	EA	320.00	80,320
Double door 8'H	26	EA	345.00	8,970
Int. HM Door:				
Sgl B1 7'H	15	EA	495.00	7,425
90 Min Sgl B1 7'H	1	EA	530.00	530
Dbl B2 7'H	1	EA	990.00	990
Sgl B1 8'H	25	EA	540.00	13,500
90 Min Sgl B1 8'H	1	EA	565.00	565
90 Min Dbl B2 8'H	3	EA	1,130.00	3,390
Exterior Doors:				
Ext Insulated HM Doors and Frame:				
Sgl B1 7'H	4	EA	585.00	2,340
Dbl B2 7'H	1	EA	1,170.00	1,170
Sgl B1 8'H	1	EA	630.00	630
Dbl B2 8'H	8	EA	1,260.00	10,080
Partitions:				
Interior HM Frame Glass & Glazing:		N/A		
				-----
				136,485

## 081416 FLUSH WOOD DOORS

Interior Doors:				
Int. Prefinished Wood Door (Glass):				
Sgl B1 2'x 8'H	35	EA	490.00	17,150
Sgl B1 3'x 8'H	77	EA	530.00	40,810
90 Min Sgl B1 3'x 8'H	8	EA	560.00	4,480
Dbl B2 8'H	13	EA	1,060.00	13,780
Sgl C1 7'H	6	EA	610.00	3,660
Sgl C1 8'H	105	EA	635.00	66,675
Dbl C2 8'H	9	EA	1,270.00	11,430
Dbl C3 8'H	1	EA	1,240.00	1,240
				-----
				159,225

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

083100 ACCESS DOORS AND PANELS

Partitions:

Access panels	1	LS	30,000.00	30,000
				-----
				30,000

083323 SPECIAL DOORS

Interior Doors:

Café/Learning Common:

Coiling Security Mesh Drape ( 21'x 8' -2EA	336	SF	95.00	31,920
--	-----	----	-------	--------

Servery :

Coiling Security Mesh Drape ( 40'x 8' -1EA	320	SF	95.00	30,400
--	-----	----	-------	--------

Main office:

Coiling Security Mesh Drape ( 21' x 5' 6"-1	116	SF	95.00	10,973
---	-----	----	-------	--------

Exterior Doors:

Motor Operated Insulated OH Door:

Tech-Makerspace (10'x10'6" )	1	EA	7,500.00	7,500
				-----
				80,793

084513 STRUCT-POLYCARBONATE PNL ASSEMB. & SKYLIGHTS

Roof Coverings:

Main Entrance Canopy -Complete:

Clear Polycarb glazing w/ alum struct -7'w	82	SF	175.00	14,350
--	----	----	--------	--------

\*Includes Section 086300

-----  
14,350

087100 DOOR HARDWARE

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Exterior Doors				
Hardware Set @ Ext. Alum Door:				
1	1	EA	750.00	750
2	1	EA	825.00	825
3	3	EA	2,250.00	6,750
4	2	EA	2,300.00	4,600
5	1	EA	3,850.00	3,850
SGL -allow	2	EA	2,500.00	5,000
9	1	EA	1,425.00	1,425
11	1	EA	5,900.00	5,900
12	1	EA	6,300.00	6,300
Terrace - sgl	-1	EA	2,000.00	-2,000
Terrace - dbl	-1	EA	4,000.00	-4,000
Entry - sgl	1	EA	4,000.00	4,000
Hardware Set # Ext HM Door:				
6	1	EA	1,150.00	1,150
8	3	EA	2,925.00	8,775
10	2	EA	4,500.00	9,000
13	1	EA	2,475.00	2,475
14	3	EA	2,325.00	6,975
16	1	EA	750.00	750
17	1	EA	3,350.00	3,350
18	1	EA	1,400.00	1,400
19	1	EA	5,100.00	5,100
*Hardware also included with 080001				
Interior Doors:				
Hardware Set @ Int. Alum Door:				
15	5	EA	5,425.00	27,125
Hardware Set @ Typ Int. Doors ( per Spec ):				
20	1	EA	1,500.00	1,500
22	2	EA	785.00	1,570
23	1	EA	805.00	805
24	13	EA	695.00	9,035
25	2	EA	485.00	970
26	1	EA	460.00	460
27	2	EA	590.00	1,180
28	23	EA	670.00	15,410
29	10	EA	510.00	5,100
30	44	EA	585.00	25,740
31	1	EA	480.00	480
32	39	EA	680.00	26,520
33	1	EA	510.00	510

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
34	1	EA	510.00	510
35	1	EA	810.00	810
36	12	EA	810.00	9,720
37	1	EA	910.00	910
38	2	EA	835.00	1,670
39	1	EA	835.00	835
40	49	EA	985.00	48,265
41	18	EA	835.00	15,030
42	2	EA	1,785.00	3,570
43	5	EA	785.00	3,925
44	1	EA	805.00	805
45	1	EA	1,835.00	1,835
46	6	EA	2,005.00	12,030
47	1	EA	3,085.00	3,085
48	2	EA	1,470.00	2,940
49	1	EA	885.00	885
50	1	EA	1,045.00	1,045
51	3	EA	1,345.00	4,035
52	1	EA	1,415.00	1,415
53	5	EA	1,665.00	8,325
54	3	EA	1,485.00	4,455
55	2	EA	1,135.00	2,270
56	3	EA	2,790.00	8,370
57	2	EA	1,945.00	3,890
58	1	EA	4,270.00	4,270
59	1	EA	4,465.00	4,465
60	1	EA	4,445.00	4,445
61	2	EA	4,610.00	9,220
62 - Coiling dr		w/Unit Cost		
Toilet rm - multi user	12	EA	1,200.00	14,400
Storage rm - sgl	1	EA	550.00	550

-----  
366,760

089000 LOUVERS & VENTS

Exterior Windows:

Vert Alum louver w/damper (RFI #17)	660	SF	125.00	82,500
-------------------------------------	-----	----	--------	--------

Roof Openings:

Elevator vent	1	EA	1,500.00	1,500
---------------	---	----	----------	-------

-----  
84,000



DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

## DIVISION 09 - FINISHES

## 090003 TILE\*

\*Noted 5'6" on A441

## Wall Finishes:

Drinking Fountain Alcove (7 loc):

Ceramic wall tile 6'h 405 SF 35.00 14,175

Multi User Toilet Rm (16 EA)

Ceramic wall tile 6'h 1,355 SF 23.00 31,165

Sgl User Toilet Rm (15 EA):

Ceramic wet wall tile 6'h 835 SF 23.00 19,205

## Floor Finishes:

Café/Learning Commons:

Porcelain tile 5,583 SF 24.00 133,992

## Quarry Tile:

Kitchen / servery 1,654 SF 17.25 28,532

Wall base 290 LF 9.75 2,828

-----  
229,896

## 090006 RESILIENT FLOORING\*

## Floor Finishes:

Moisture mitigation -spec 46,242 SF 1.00 46,242

LT-linoleum tile TYP 59,665 SF 5.00 298,325

LP - linoleum plank Corridor 28,786 SF 6.50 187,109

LP - linoleum plank breakout area w/ corr.

Acoustical Mat - nr 99 (2nd &amp; 3rd flr) 36,500 SF 3.50 127,750

\*Includes sections 0965000 &amp; 096513

## Wall Finishes:

Wall base 12" VCT tile w/ Schluter top edg 28,500 LF 6.50 185,250

Wall base 6" @ locker box 1,050 LF 5.00 5,250

Typ resilient wall base - allow 1 LS 7,500.00 7,500

## Stair Finishes:

Metal Pan Stair Learning Commons Stair ( 4 FLT):

VCT tile landing 172 SF 8.00 1,376

VCT treads &amp; risers w/rub nosing 678 LFR 14.25 9,662

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Aud Stair Finish		W/ C1030		
				----- 868,464
090009 PAINTING*				
Exterior Walls:				
Misc exterior painting -allow	1	LS	10,000.00	10,000
Exterior Doors:				
Paint HM door & Frame - sgl	5	EA	120.00	600
Paint HM door & Frame - dbl	9	EA	225.00	2,025
Interior Doors:				
Paint Int HM door frame:				
Single Door 7'H	22	EA	125.00	2,750
Double Door 7'H	1	EA	145.00	145
Single Door 8' H	251	EA	140.00	35,140
Double door 8'H	26	EA	160.00	4,160
Paint Int HM door:				
Sgl B1 7'H	15	EA	150.00	2,250
90 Min Sgl B1 7'H	1	EA	150.00	150
Dbl B2 7'H	1	EA	300.00	300
Sgl B1 8'H	25	EA	175.00	4,375
90 Min Sgl B1 8'H	1	EA	175.00	175
90 Min Dbl B2 8'H	3	EA	300.00	900
Stair Finishes:				
Paint Metal Pan Stair & Rail:				
5' W @ Learning Commons 1st- 3rd	2	FLTS	2,500.00	5,000
8' W @ Learning Commons 1st- 2nd	2	FLTS	2,750.00	5,500
5' W @ Stair Hall	5	FLTS	2,500.00	12,500
Seal Concrete Finish:				
5' W @ Stair Hall	5	FLTS	2,000.00	10,000
Wall Finishes:				
Interior painting- walls	136,600	GSF	1.90	259,540
Floor Finishes:				
SC Sealed Concrete Floor Finish (030513):				

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Storage, mech, elec & receiving	5,561	SF	2.00	11,122
Ceiling Finishes:				
Paint gyp ceiling	45,000	SF	1.00	45,000
Paint gyp soffits	1	LS	25,000.00	25,000
Paint exposed structure- 100%:				
Class Small Closet( 34 loc)	408	SF	2.00	816
Typ mech, elec & storage rm	5,759	SF	2.00	11,518
Auditorium & stage	5,996	SF	2.50	14,990
Main gym deck	8,268	SF	4.00	33,072
Typ, Sci, Art, Music, & Media - exp deck	23,986	SF	2.00	47,972
Stair hall	1,203	SF	2.00	2,406
				-----
				547,406
092116 GYPSUM WALLBOARD ASSEMBLIES				
Partitions:				
Firestopping	136,600	GSF	0.65	88,790
6/A323 Exterior Wall - Raised Commons:				
4" Mineral fiber insul	2,486	SF	2.65	6,588
Exterior Ceiling Insulation @ :				
Bay / covered entry	1,119	SF	5.00	5,595
Exterior Ceiling Stucco System:				
Bay/covered entry	1,119	SF	32.00	35,808
Spray foam at perm openings	9,299	LF	8.25	76,717
Exterior Windows:				
P.T. - perm blocking	9,009	LF	8.65	77,928
Exterior Doors:				
P.T. - perm blocking HM open	316	LF	8.00	2,528
Partitions:				
Interior blocking	136,600	GSF	0.50	68,300
Misc. rough carpentry	136,600	GSF	1.15	157,090
(5/A601) Frame AV monitor box	65	EA	250.00	16,250
Flat Roof Blocking @:				
Base flashing	1,620	LF	12.50	20,250

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Typ roof fascia	3,182	LF	12.50	39,775
Expansion joint	86	LF	40.00	3,440
Gable skylight curb ( 4 EA)	567	LF	45.00	25,515
Flash Pre Fab Roof Top Mech curb block	618	LF	35.00	21,630
Misc Equip blocking	1	LS	7,500.00	7,500
Roof hatch	1	EA	750.00	750
Atrium vent	4	EA	750.00	3,000
Exterior Walls:				
1 lyr 5/8" gyp @ stud	43,553	SF	3.25	141,547
Exterior Walls:				
Exterior wall Backup:				
10" x 16 Ga. stud @ Typ 14'	41,075	SF	11.70	480,578
10" x 16 Ga. stud @ raised common 5-6'h	2,486	SF	11.70	29,086
Entry pier/chimney framing-14'H	668	SF	9.85	6,580
1/2" Dens glass sheathing	44,229	SF	3.30	145,956
* Mech Penthouse Unit - Complete		W / HVAC		
Ext Ceiling Framing @ :				
Canopy & covered entry	1,056	SF	6.50	6,864
1/2" Dens glass sheathing	1,056	SF	3.50	3,696
Partitions:				
H6 Elevator shaft - 56'6"H	2,095	SF	18.00	37,710
C4 Auditorium -28'H	952	SF	18.00	17,136
C7 Auditorium - 28'H	4,755	SF	18.00	85,590
Stage front	120	SF	9.00	1,080
F1 gym storage -28'H	695	SF	18.00	12,510
F1 gym storage chase 1 side -28'H	105	SF	16.00	1,680
1 side class radial mech chase 14'H	7,318	SF	12.00	87,816
Chase @ fnd wall14'H	996	SF	10.00	9,960
Drinking fountain chase wing wall14'H	689	SF	10.00	6,890
D6 & D6 Bulkhead @ dbl op part - 6'H	114	SF	15.00	1,710
Curb 1'H @ glazed part	866	SF	15.00	12,990
Bulkhead 6'H @ glazed part	5,196	SF	12.00	62,352
F6 Bulkhead @ op part - 6'H	1,248	SF	12.00	14,976
B1 Atrium shaft 2nd - high roof	4,107	SF	16.50	67,766
TYP -14' Drywall Partitions:				
B1	1,621	SF	9.15	14,832
B3	417	SF	10.15	4,233
B4	4,116	SF	12.15	50,009
C2	5,578	SF	14.65	81,718
C3	9,149	SF	14.65	134,033
C4	2,589	SF	14.65	37,929
C6	3,620	SF	16.90	61,178

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
C7	1,112	SF	14.65	16,291
C8	181	SF	19.40	3,511
C10	229	SF	16.90	3,870
D3	1,429	SF	12.65	18,077
D6	455	SF	14.90	6,780
E3	10,614	SF	17.15	182,030
E4	580	SF	17.15	9,947
E6	1,181	SF	19.40	22,911
E7	894	SF	24.15	21,590
E8	18,658	SF	21.90	408,610
E9	2,588	SF	21.90	56,677
F1	4,933	SF	19.65	96,933
F2	2,142	SF	21.90	46,910
F6	4,592	SF	19.65	90,233
F8	775	SF	24.40	18,910
H4	1,232	SF	14.65	18,049
J1	7,734	SF	19.30	149,266
J2	596	SF	16.40	9,774
K1	7,317	SF	23.80	174,145
K2	1,724	SF	23.80	41,031
Tile Backer Bd Premium	2,595	SF	1.85	4,801
GWB @ Corridor Locker Enclosure (nic mtl locker) & Rails - allow:				
Freestanding locker box - 1st flr	307	LF	60.00	18,420
Freestanding - locker box upper flr w/ soffit	724	LF	120.00	86,880
Upper flr guardrail w/ soffit (6/A650)	327	LF	55.00	17,985
Cohort # 2059 2nd flr guard rail w/soffit(6/	19	LF	55.00	1,045
Additional framing @ sloped AWP (A601)	10,700	SF	7.50	80,250
(5/A601) frame AV monitor box	65	EA	100.00	6,500
Tile Backer Bd Premium		W / TILE FSB		
Impact resis. Gwb premium	1	LS	50,000.00	50,000
Misc. GWB assemblies (inc extruded alum	136,600	GSF	0.50	68,300
Load, Distribute and Misc.	136,600	GSF	0.50	68,300
*Partitions include sound attenuation, tape & joint compound finish				
Ceiling Finishes:				
Acoustical Gypsum Plaster (092313):				
Clg spray sys - allow	1	LS TBD		
Typ, Sci, Art, Music, SPED & ELL Classroom CLG & Soffits:				
Summer Beam bottom 3'W (1/A690)	3,530	SF	20.00	70,600
Summer Beam light cove & vert framing (1	2,354	LF	150.00	353,100
Typ. gyp clg bay	1,161	SF	15.00	17,415

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Complete soffit @ gyp bay	326	LF	48.00	15,648
Complete beam box 11'6" bot	998	LF	80.00	79,840
Sloped ACT clg - metal deck transition sol	1,365	LF	32.00	43,680
Complete soffit @ OP partition class (6/A601)		N/A		
Central Corridor CLG & Soffits:				
Horiz gyp clg 8'AFF	6,049	SF	14.00	84,686
Horiz gyp clg 12'AFF	2,735	SF	14.00	38,290
(9/A690) Soffit @ bot of sloped ACT	1,852	LF	35.00	64,820
(8/A690) Soffit @ top of sloped ACT	1,852	LF	45.00	83,340
(7/A650) Cap @ locker box	565	LF	50.00	28,250
(6/A650) Soffit @ guardrail	367	LF	50.00	18,350
Misc. Soffits @:				
Toilet rm light cove (7/A690)	570	LF	65.00	37,050
ACT - GWB transition 8" AFF	75	LF	32.00	2,400
Pyramid Skylight 2'H	1,134	SF	45.00	51,030
Gyp Ceiling System :				
Atrium 3rd flr sloped gyp clg	4,700	SF	30.00	141,000
Typ gyp ceiling	1,917	SF	15.00	28,755
Emergency shw gyp clg	54	SF	15.00	810
1 Hr gyp mech/elec	474	SF	15.00	7,110
2Hr gyp mech/elec	169	SF	22.00	3,718
A651 Underside monumental Stair w/ retur	800	SF	21.00	16,800
Underside proj rm/bridge	600	SF	21.00	12,600
Sub acoustical clg (2/A690)	5,296	SF	24.00	127,104
Breakout rm sloped gyp clg 50%	2,000	SF	16.00	32,000
Toilet/shw rm (3 loc)	438	SF	12.00	5,256
Partitions:				
<b>Breakout 3,400 GSF</b>				
Breakout Floor Framing -Allow:				
Light gauge floor	1,600	SF	20.00	32,000
9/16" Metal Deck	1,600	SF	4.00	6,400
Concrete Deck fill				w/ package #2
Breakout A( 2 story):				
P lam wall finish -allow	0	SF	55.00	0
Typ GWB wall -sgl stud	1,605	SF	25.00	40,125
GWB chase wall-complete	978	SF	25.00	24,450
GWB roof	260	SF	25.00	6,500
Breakout B( 3 story):				
P lam wall finish -allow	0	SF	55.00	0
GWB chase wall-complete	1,566	SF	25.00	39,150

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
GWB roof	300	SF	25.00	7,500
Breakout C( 2 story w/ guard rail 3rd flr):				
P lam wall finish -allow	0	SF	55.00	0
Typ GWB wall -sgl stud	1,488	SF	25.00	37,200
GWB chase wall-complete	1,038	SF	25.00	25,950
Typ GWB knee wall -sgl stud	42	SF	25.00	1,050
GWB chase knee wall-complete	107	SF	25.00	2,675
Cap @ knee wall walls	44	LF	25.00	1,100
Breakout D( 1 story):				
P lam wall finish -allow	0	SF	55.00	0
Typ GWB wall -sgl stud	617	SF	25.00	15,425
GWB roof	205	SF	25.00	5,125
Breakout E ( 1 story):				
P lam wall finish -allow	0	SF	55.00	0
Typ GWB wall -sgl stud	249	SF	25.00	6,225
GWB chase wall-complete	286	SF	25.00	7,150
GWB roof	292	SF	25.00	7,300
Wall Finish:				
8' FRP Wall Panel -allow:				
Main kitchen	2,233	SF	9.75	21,772
				-----
				5,724,632
095100 ACOUSTICAL CEILINGS*				
A1 2'x2'and 4' x 3/4"ACT Ceiling System @ :				
A1 Typ ACT	2,525	SF	9.00	22,725
A1 Splayed ACT (20%)	1,870	SF	8.25	15,428
A2 2'x2'and 4' x 5/8"ACT Ceiling System @ :				
A2 Typ ACT	6,546	SF	8.25	54,005
A2 Splayed ACT (20%)	20,732	SF	8.25	171,039
A2 Breakout rooms (50%)	1,715	SF	10.00	17,150
A 2 ACT 2 x 2 ( previously act -3 )	1,400	SF	8.25	11,550
A 4 Kitchen / servery	1,688	SF	6.75	11,394
Random Size Ultima:				
Corridor 8'w	13,564	SF	10.00	135,640
Exterior Soffit panel		W /Ext Wall		

\*Includes Sections 095100 & 095133

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

Wall Finish:

Fabric Wrapped Acoustical Panels 1":

Media ctr	1,260	SF	32.00	40,320
Science Lab Classroom (260 SF /6 EA)	1,560	SF	32.00	49,920
Makerspace ( 1 EA)	224	SF	32.00	7,168
Fab-lab ( 1 EA)	250	SF	32.00	8,000
Art Class Room ( 1 EA)	300	SF	32.00	9,600
Teacher Prep Room ( 24 EA)		N/A		
Typ, SPED & ELL Classroom 206SF / 32	6,592	SF	32.00	210,944
Drama Classroom ( 1 EA)	300	SF	32.00	9,600
Band Rm ( 1 EA)	912	SF	32.00	29,184
Chorus Classroom ( 1 EA)	309	SF	32.00	9,888
Guidance Suite (133 SF /3 Loc)	399	SF	32.00	12,768
Break out areas		NIC		
Auditorium		NIC		

Wall Finish:

Cementitious Wood Fiber Wall Panel:

Music practice rm ( 3 EA)	409	SF	19.00	7,771
Band Rm ( 1 EA)	833	SF	19.00	15,827
Gymnasium	4,344	SF	19.00	82,536

-----  
932,456

096446 WOOD & ATHLETIC FLOORING

Floor Finishes:

Main Gym:

Moisture mitigation -(vapor retarder)	8,276	SF	4.75	39,311
Wood Maple Gym flooring	8,276	SF	19.00	157,244
Vented wall base	365	LF	9.85	3,595

Auditorium (8/A602) - Finish Carp Spec:

Stage flooring - 4" assembly	1,540	SF	14.00	21,560
Stage nosing	59	LF	38.00	2,242
Stage wall base /transition	113	LF	9.85	1,113

\*Includes Sections 096429 & 096466

-----  
225,065



DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

096712 RESINOUS FLOORING

Floor Finishes:

SGL User Toilet Room (15 EA) :

Epoxy flr w/int base	997	SF	18.00	17,946
Shw receptor 3x3	1	EA	550.00	550
Shw receptor 5x3	2	EA	700.00	1,400
Threshold/transition	15	EA	200.00	3,000

Multi User Toilet & Locker Room( 18 EA):

Epoxy flr w/int base	4,601	SF	18.00	82,818
Threshold/transition	18	EA	200.00	3,600

-----  
109,314

096800 CARPET

Floor prep	1,033	SF	0.25	258
------------	-------	----	------	-----

Floor Finishes:

Auditorium:

Carpet aisle	1,033	SF	6.00	6,198
Carpet aisle stair/stage (4 riser)	4	FLT	500.00	2,000

-----  
8,456

097217 DIGITAL IMAGE WALL COVERINGS

Wall Finish:

Mural - Digital image wall covering - install only w/ 1 /2" GWB Back up:

Media center BY OTHERS

-----  
0

097233 DRY-ERASE WALL COVERING

---

---

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

---

---

-----  
0

097733 SANITARY WALL PANELS

-----  
0

098100 ACOUSTICAL INSULATION w/092116

-----  
0

098400 ACOUSTIC ROOM COMPONENTS

-----  
0

098415 WOOD FIBER ACOUSTICAL PANELS

-----  
0

DIVISION 10 - SPECIALTIES

101100 MARKERBOARDS & TACKBOARDS

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

## Fittings:

## Allow:

Media center tack surfaces	100	SF	28.00	2,800
4'H Tack Board	30	EA	400.00	12,000

\*Dry-erase magnetic wall covering is included in C3010

## Wall Finish:

Dry Erase Wall Finish	6,640	SF	25.00	166,000
-----------------------	-------	----	-------	---------

-----  
180,800

## 101400 SIGNAGE

## Exterior Walls:

## Ext. Signage:

18" Cast bronze letter (1 loc) - chimney	6	EA	650.00	3,900
Cast lettering @ entry ramp	18	EA	500.00	9,000

## Fittings

## Allow:

Building directory	1	EA	5,000.00	5,000
Dedication plaque	1	EA	3,800.00	3,800
Room ID sign	136,600	GSF	0.22	30,052
Misc Int. ADA signage	136,600	GSF	0.12	16,392

-----  
68,144

## 102113 TOILET COMPARTMENTS

## Fittings:

## HDPE Toilet Partitions:

Std. partition	23	EA	1,220.00	28,060
HC partition	16	EA	1,430.00	22,880
Urinal screen	15	EA	310.00	4,650

-----  
55,590

## 102600 WALL AND DOOR PROTECTION

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

Fittings:

Vinyl/Acrylic Composite:

Corner guard	1	LS	5,000.00	5,000
Crash rail	1	LS	5,000.00	5,000
				-----
				10,000

102813 TOILET ACCESSORIES

Fittings:

SGL User Toilet Rm Accessories ( 15 ea):

Tilt mirror @ wall hung lav	15	EA	220.00	3,300
Soap dispenser (owner furnish & installed)		NIC		
Toilet tissue dispenser	15	EA	48.00	720
San. prod. disposal	15	EA	60.00	900
Toilet grab bars	30	EA	85.00	2,550
Paper towel dispenser-allow	15	EA	135.00	2,025
Waste receptacle	15	EA	150.00	2,250
Elec hand dryer - allow		NIC		
Coat hook	15	EA	25.00	375
Fixed diaper changing sta - allow	3	EA	550.00	1,650
3' ADA SHW accessories -allow	1	EA	550.00	550

Multi User Toilet & Locker Rm Accessories (16 ea):

Soap dispenser (owner furnish & installed)		NIC		
Toilet tissue dispenser	39	EA	48.00	1,872
San. prod. disposal	27	EA	60.00	1,620
Toilet grab bars	32	EA	85.00	2,720
Paper towel dispenser- 2/rm	32	EA	135.00	4,320
Waste receptacle - 2/rm	32	EA	150.00	4,800
Elec hand dryer - allow		NIC		
Coat hook	39	EA	25.00	975
5' ADA shw accessories - allow	2	EA	550.00	1,100

Dressing Rm Accessories (2 ea):

Soap dispenser (owner furnish & installed)		NIC		
--	--	-----	--	--

Allow:

Misc. locker rm accessories	2	EA	1,000.00	2,000
Janitor shelf/mop holder	7	EA	200.00	1,400

\*Excludes classroom and workroom accessories

-----

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

35,127

104000 SAFETY SPECIALTIES

Fittings:				
Safety Specialties :				
Hose connection cabinet	16	EA	350.00	5,600
First aid kit (nic sci rm)	6	EA	450.00	2,700
Fire Dept key cab	2	EA	1,000.00	2,000
Fire extinguisher and cab (nic sci rm)	20	EA	475.00	9,500
AED & cabinets	4	EA	750.00	3,000
*See also science equipment				

-----  
22,800

107113 EXTERIOR SUN CONTROL DEVICES

N/A

-----  
0

109000 MISCELLANEOUS SPECIALTIES

Exterior Walls:				
LVL 2 entry flagpole 34' H	1	EA	9,000.00	9,000
Fittings:				
Phenolic Locker-Allow:				
15" wx12"dx36"H corridor (nic enclosure)	660	EA	580.00	382,800
Metal Locker:				
15"w x 15"d x 30"H PE student 2 tiered	40	EA	215.00	8,600
15"w x 15"d - Custodian/kitchen staff db	6	EA	265.00	1,590
12" Kitchen staff dbl tier	3	EA	265.00	795
Locker base @ :				
Student corridor		W /Enclosure		
PE student	50	LF	36.00	1,800
PE staff	9	LF	36.00	324

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Free Standing Wood Bench: PE locker rm (2 EA)	12	LF	125.00	1,500
Health office cubicle track w/ curtain	3	EA	1,325.00	3,975
Secure wall panels-Allow: OT/PT rm (1 ea)	320	SF	15.00	4,800
Padded athletic flr tiles - allow: OT/PT rm (1 ea)	100	SF	15.00	1,500
Partitions: Folding Panel partition: 16' x 8' H Typ classroom (13 EA)	1,664	SF	106.00	176,384
(22/A620)DbI 19' x 8'H Music rm acoustic	152	SF	106.00	16,112
8' H SPED suite (3 LOC)	960	SF	106.00	101,760
*Includes pass dr & white bd finish				
*Includes Sections 102123, 102239, 105113, 105123 & 107113				
				----- 710,940

DIVISION 11 - EQUIPMENT

113100 RESIDENTIAL APPLIANCES

Custodian Storage Rm #1216: Stack washer/dryer	1	EA	2,500.00	2,500
Custodian Office/Break Rm (1 EA): Refrigerator -full size	1	EA	1,400.00	1,400
Staff Dinning Rm ( 1 ea): Refrigerator -full size	1	EA	1,400.00	1,400
Medical Suite: Refrigerator -full size	1	EA	1,400.00	1,400
SPED Classroom 1260 (12/A410): Range	1	EA	750.00	750
Refrigerator	1	EA	1,400.00	1,400
Washer	1	EA	1,500.00	1,500
Range hood		NIC		
Dryer		NIC		
Dishwasher		NIC		

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Kitchen washer and dryer		W / Kitchen Equipment		
Science rm appliance		W / Science Equipment		
				----- 10,350
114000 FOOD SERVICE EQUIPMENT				
Kitchen equipment & casework	1	LS	415,270.00	415,270
*Kitchen equipment & casework Quote 7/19/2019				
				----- 415,270
115213 PROJECTION SCREENS				
Projection Screen - Elec Op. - Allow:				
18' auditorium (spec)	1	EA	15,000.00	15,000
18' Café/Learning commons (clg plan)	1	EA	15,000.00	15,000
18' Gym - allow	1	EA	15,000.00	15,000
Media center (spec)	2	EA	10,000.00	20,000
				----- 65,000
116143 THEATRICAL EQUIPMENT(No Spec)				
Auditorium (6/28/2019 Quote 420 Seat)- Allow:				
Theatrical Rigging	1	LS	158,300.00	158,300
Theatrical Draperies	1	LS	33,854.00	33,854
Theatrical Lighting Instruments & Access.	1	LS	129,018.00	129,018
Theatrical Lighting Control System	1	LS	95,749.00	95,749
Technology and Local Sound:				
Gym	1	EA	120,000.00	120,000
Café	1	LS	50,000.00	50,000
Aud Audio Visual System	1	LS	200,000.00	200,000
Band and Chorus Class	1	LS	60,000.00	60,000
Drama Class	1	LS	20,000.00	20,000
				----- 866,921

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
<b>116600 ATHLETIC &amp; SPORTS EQUIPMENT</b>				
Main Gym:				
Basketball backstops - electric	6	EA	9,500.00	57,000
Wall padding	861	SF	17.00	14,637
Motor op divider curtain (51'x24')-allow	1,224	SF	16.00	19,584
Volley ball court equip.	2	PR	700.00	1,400
Scoreboard (2 EA Spec 116643)		W / Electrical		
Batting cage (not shown)	1	EA	10,000.00	10,000
*Includes Sections 116623 - 116653				-----
				102,621

**119000 MISC. EQUIPMENT**

Allow:				
Loading dock bumpers	1	LS	3,500.00	3,500
Kiln (11.38)	1	EA	4,000.00	4,000
Metal storage shelving		NIC		
Library equipment		NIC		
Power op changing table- Hoyer lift		NIC		
Vocational shop equipment(spec 115700)	1	LS	25,000.00	25,000
A420 Exhaust hood Tech Lab		W/Vocational allowance		
*Includes Section 115300, 115313 & 115700				-----
				32,500

**DIVISION 12 - FURNISHINGS**

**122400 WINDOW SHADES**

Exterior Manual op Window Shade	10,000	SF	8.00	80,000
Motor Op shade	970	SF	28.00	27,160
Interior Roller Shade (4/A690):				
Int borrowed light	3,304	SF	6.50	21,476

Door Manual Shade



DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

Single Door	50	EA	150.00	7,500
				-----
				136,136

122414 MOTORIZED WINDOW SHADES

Motorized skylight shade (122414)		NIC		-----
				0

123553 CASEWORK

Allow -Science Lab Classroom Equipment ( 6 EA):

Safety glasses monitor case	6	EA	1,000.00	6,000
Glassware pegboards ( 1/RM) - allow	6	EA	350.00	2,100
Sgl sided fume hood #2210	1	EA	7,200.00	7,200
Dbl sided fume hood #2214	1	EA	9,500.00	9,500
First aid kit - allow	6	EA	300.00	1,800
OH track - equip support - allow		NIC		
Safety SHW		w/ plumbing		
Fire blanket	6	EA	500.00	3,000
Fire ext & cab ( 1/RM)	6	EA	425.00	2,550
Misc equipment	6	RM	500.00	3,000

Science Shared Prep Room Equipment ( 3 EA):

Refrigerator - full size	3	EA	750.00	2,250
Dishwasher under counter	3	EA	1,100.00	3,300
Glassware pegboards (1 RM) - allow	1	EA	350.00	350
Misc equipment	3	RM	500.00	1,500
Chem storage/fume unit	2	EA	8,500.00	17,000

\*Includes Sections 115300 - 115313

Science Lab Classroom ( 6 EA):

Sink		w/ plumbing		
24" Epoxy ctr (no base cab (48.5LF/RM)	291	LF	295.00	85,845
24"H Epoxy backsplash ( 48.5 LF/RM)	582	SF	95.00	55,290
Mobile storage cab (36"wx27"h 8/RM)	48	EA	1,200.00	57,600
P lam Wall cab ( 10 LF/RM)	60	LF	210.00	12,600
Teachers demo table		NIC		
Student table		NIC		

Science Shared Prep Room ( 3 EA):

Sink		w/ plumbing		
24" Epoxy ctr (no base cab )	54	LF	295.00	15,930

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
24"H Epoxy backsplash	109	SF	95.00	10,355
P lam Wall cab	30	LF	210.00	6,300
Mobile storage cab (36"wx27"h)	8	EA	1,200.00	9,600
Art Class Room (1 EA):				
Epoxy ctr (no base cab)	20.5	LF	295.00	6,048
24"H Epoxy backsplash	41	SF	95.00	3,895
				-----
				323,013

124813 FLOOR MATS

Floor Finishes:				
Recessed mtl vest. grille (2 loc)	360	SF	22.00	7,920
				-----
				7,920

124816 ENTRANCE GRILLES & FRAMES

w/124813

-----  
0

126613 TELESCOPING BLEACHERS

Wall Mtd Motor op Bleacher (qty noted)	650	SEAT	125.00	81,250
				-----
				81,250

129000 MISCELLANEOUS FURNISHING

Auditorium fixed seat	321	EA	295.00	94,695
Removable auditorium seat	46	EA	125.00	5,750
Stackable auditorium seat	48	EA	125.00	6,000

\*Includes Section 126100

Choral classroom risers W/FFE

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Band classroom risers		W/FFE		
Stage risers		W/FFE		
*Includes Section 126100				-----
				106,445
DIVISION 13 - SPECIAL CONSTRUCTION				
130000 SPECIAL CONSTRUCTION		N/A		
				-----
				0
DIVISION 14 - CONVEYING EQUIPMENT				
140001 ELEVATORS*				
Passenger elevator ( 1 door - 4,500 lb)	4	STOP	53,000.00	212,000
*Includes roof level stop				-----
				212,000
DIVISION 21 - FIRE SUPPRESSION				
210001 FIRE SUPPRESSION*				
6" BF Preventer	1	EA	7,450.00	7,450
Wet valve assembly	1	LS	3,500.00	3,500
Elec. bell	1	LS	1,500.00	1,500
Siamese fire dept connection	1	LS	1,350.00	1,350
Fire Dept. Connection:				
2 1/2" w/cabinet	9	EA	1,850.00	16,650
Siamese FD Connection	2	EA	1,235.00	2,470
FCVA - 4"	9	EA	1,050.00	9,450
Tamper sw	30	EA	225.00	6,750
Heads and Branch:				
Semi Recess head - typ.	946	EA	295.00	279,070
Concealed head - aud.	41	EA	750.00	30,750

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Upright head	315	EA	329.00	103,635
Upright w/ cage	71	EA	360.00	25,560
Sidewall	144	EA	285.00	41,040
Window wash	12	EA	385.00	4,620
Additional head	200	EA	295.00	59,000
3" drain	220	LF	31.50	6,930
2 1/2" - 6"	5,100	LF	39.00	198,900
4" Shut off	4	EA	1,025.00	4,100
6" Shut off	4	EA	1,185.00	4,740
Misc. Valve	1	LS	10,000.00	10,000
Underground Fire Prot. Service:				
6"	10	LF	110.00	1,100
Coring and firesafing	1	LS	5,000.00	5,000
Staging and Lifts	1	LS	30,000.00	30,000
Test, as built	1	LS	40,000.00	40,000
				-----
				893,565

## DIVISION 22 - PLUMBING

## 220001 PLUMBING\*

## Plumbing Fixtures ( Per Plumbing):

P-1 water closet	20	EA	1,850.00	37,000
P-1A water closet	31	EA	1,850.00	57,350
P-2 Urinal	18	EA	1,575.00	28,350
P-2A Urinal	8	EA	1,575.00	12,600
P-3 Lav ctr mtd	47	EA	1,100.00	51,700
P-3A Lav wall hung	31	EA	1,375.00	42,625
P-4 Drinking Fountain (high/low)	11	EA	3,150.00	34,650
P-5 Mop Receptor	5	EA	1,425.00	7,125
P-6 Shower 3x3	1	EA	2,850.00	2,850
P-6 Shower 5x3	2	EA	3,000.00	6,000
P-7 Science	40	EA	2,200.00	88,000
P-7A	2	EA	2,200.00	4,400
P - 8	4	EA	1,500.00	6,000
P - 9 Art Sink w/ Plaster Trap	4	EA	2,150.00	8,600
P - 10 Eye Wash Station	5	EA	2,800.00	14,000
Sink - Aud. dressing rm	4	EA	1,500.00	6,000
Sink - health office	1	EA	1,500.00	1,500
Sink - SPED	1	EA	1,500.00	1,500
Sink - Tech Lab	2	EA	1,500.00	3,000

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Sensor Faucet ( spec only)	78	EA	525.00	40,950
Sensor Flush ( spec not indicated)	77	EA	485.00	37,345
FPSC wall hydrant	8	EA	450.00	3,600
HB hose bibb	18	EA	350.00	6,300
IMB Conn	5	EA	500.00	2,500
Fix Connection	237	EA	300.00	71,100
Misc. Specialties:				
MV-1	1	EA	7,500.00	7,500
MV-2 - science room	5	EA	1,250.00	6,250
1" Mech BFP	3	EA	950.00	2,850
Misc. Mix valve	4	EA	450.00	1,800
P - 11 Fume Hood Connection	3	EA	2,500.00	7,500
Heat Trace non potable water ( spec )	1	LS	5,000.00	5,000
Fire sealing penetration	1	LS	45,000.00	45,000
Elevator Sump pump	1	EA	3,500.00	3,500
Pumps:				
RP-1 & RP-2	2	EA	15,000.00	30,000
RP-3	1	EA	4,500.00	4,500
RP-4	1	EA	4,500.00	4,500
Gas Fire Hot Water Supply Boiler:				
BLR-1, 2(Lochinvar - Armor AWN501P )	2	LS	19,500.00	39,000
HW Storage Tank	1	EA	18,000.00	18,000
Mech Rm Neutralization	1	EA	4,000.00	4,000
Boiler Valve and Trim	1	LS	30,000.00	30,000
Heat Trace	1	LS	7,500.00	7,500
Interior Grease Interceptor:				
GI-1 & GI-2	2	EA	8,500.00	17,000
Roof/Storm Drain System				
Underground D/W/V Pipe:				
4"	61	LF	46.00	2,806
6"	75	LF	61.00	4,575
8"	75	LF	96.00	7,200
10"	93	LF	110.00	10,230
12"	19	LF	132.00	2,508
FCO	8	LF	425.00	3,400
Above Ground D/W/V Pipe:				
4"	230	LF	48.00	11,040
6"	932	LF	63.00	58,716
8"	486	LF	99.50	48,357
10"	150	LF	112.00	16,800
CO	20	EA	400.00	8,000

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
RD - 4"	7	EA	1,275.00	8,925
RD - 5"	3	EA	1,320.00	3,960
RD - 6"	9	EA	1,460.00	13,140
RD - 8"	2	EA	1,545.00	3,090
Insulate leader	1,000	LF	13.00	13,000
Footing drain	100	LF	36.50	3,650
Acid Waster System:				
Underground D/W/V Pipe:				
2"	43	LF	41.00	1,763
4"	587	LF	62.00	36,394
FCO	6	EA	485.00	2,910
FD	5	EA	725.00	3,625
Above Ground Sanitary D/W/V Pipe:				
4"	1,200	LF	67.00	80,400
Chip Tank	6	EA	4,500.00	27,000
Domestic Piping:				
1 1/2"	339	LF	33.90	11,492
1 1/4"	754	LF	27.80	20,961
1"	2,900	LF	23.65	68,585
1/2"	1,245	LF	18.10	22,535
2 1/2"	533	LF	66.00	35,178
2"	735	LF	48.20	35,427
3"	50	LF	89.00	4,450
3/4"	1,590	LF	20.60	32,754
6"	100	LF	162.00	16,200
Kitchen conn	1	LS	30,000.00	30,000
Water Hammer arrestors	1	LS	5,000.00	5,000
1" Pipe Insulation:				
1 1/2"	339	LF	8.00	2,712
1 1/4"	754	LF	7.90	5,957
1"	2,900	LF	7.50	21,750
1/2"	1,245	LF	7.10	8,840
2 1/2"	533	LF	9.00	4,797
2"	735	LF	8.45	6,211
3"	50	LF	9.50	475
3/4"	1,590	LF	7.40	11,766
6"	100	LF	14.45	1,445
Sanitary System				
Underground D/W/V Pipe:				
2"	79	LF	32.00	2,528
3"	392	LF	38.00	14,896
4"	971	LF	49.00	47,579

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
5"	284	LF	56.00	15,904
6"	14	LF	63.00	882
8"	31	LF	99.50	3,085
Floor Drain	17	EA	580.00	9,860
Gas and Sand separator	1	EA	15,000.00	15,000
5,000 gal. Grease Trap	1	EA	22,000.00	22,000
Sewer manhole	1	EA	4,000.00	4,000
Floor Sink	8	EA	2,200.00	17,600
FCO	25	EA	425.00	10,625
Above Ground D/W/V Pipe:				
2"	1,600	LF	32.00	51,200
3"	600	LF	38.00	22,800
4"	1,249	LF	49.00	61,201
FD	18	EA	800.00	14,400
CO	20	EA	495.00	9,900
Trap primer Pipe	1	LS	5,000.00	5,000
Roof Vent Term.	8	EA	1,100.00	8,800
Gas Pipe:				
1" - Science hw conn?	300	LF	36.00	10,800
2" - main	135	LF	75.00	10,125
3/4" - kitchen	50	LF	30.00	1,500
1" - 1/2' lab connection	1	RM	30,000.00	30,000
Kitchen Connection	1	LS	5,000.00	5,000
Boiler Room Connections	1	LS	5,000.00	5,000
Kitchen Master Shut off	1	LS	4,000.00	4,000
Gas sub metering	3	EA	3,000.00	9,000
Flues:				
6" HW Flue	60	LF	95.00	5,700
Generator:				
Gas Connection	1	LS	25,000.00	25,000
Exhaust Breeching		NIC		
Underground Water Service:				
6"	10	LF	150.00	1,500
Meter Install Only	1	EA	2,500.00	2,500
Sub-meter	3	EA	3,000.00	9,000
6" BFP	1	EA	12,500.00	12,500
Staging and Lifts	1	LS	30,000.00	30,000
Commissioning Coordination	200	HRS	125.00	25,000
Sanitize system	1	LS	25,000.00	25,000
Test , permit misc gc	1	LS	75,000.00	75,000

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

-----  
2,150,852

## DIVISION 23 - HVAC

## 230001 HVAC\*

## Rooftop Units:

RTU-1 (22,000 cfm)	20,000	CFM	15.00	300,000
RTU-2 (22,000 cfm)	20,000	CFM	15.00	300,000
RTU-3 (22,000 cfm)	20,000	CFM	15.00	300,000
RTU-4 (22,000 cfm)	20,000	CFM	15.00	300,000
RTU-5 (15,000 cfm)	15,000	CFM	15.00	225,000
RTU-6 (12,000 cfm)	12,000	CFM	15.00	180,000
RTU-7 (2,000 cfm)	2,000	CFM	13.50	27,000

## Make Up Air Units:

MAU-1 (5,000 cfm)	4,170	CFM	12.00	50,040
Sound Attenuators ( 17 ea )	218,000	CFM	0.55	119,900

## Exhaust Fans:

EF-1 G-VG - roof	1	EA	3,150.00	3,150
EF-2 G-VG - roof	1	EA	3,150.00	3,150
EF-3 G-VG - roof	1	EA	3,150.00	3,150
EF-4 G-VG - roof	1	EA	3,150.00	3,150
EF-5 SQ-VG - kiln	1	EA	2,850.00	2,850
SEF-1 QEI - roof	1	EA	22,000.00	22,000
SEF-2 QEI - roof	1	EA	22,000.00	22,000
SEF-3 QEI - roof	1	EA	22,000.00	22,000
SEF-4 QEI - roof	1	EA	22,000.00	22,000
KEF-1 Cube - roof	1	EA	5,500.00	5,500
KEF-2 Cube - roof	1	EA	5,500.00	5,500
FEF-1 Vektor - roof	1	EA	12,250.00	12,250
FEF-2 Vektor - roof	1	EA	12,250.00	12,250
FEF-3 Vektor - roof	1	EA	12,250.00	12,250
FEF-4 Vektor - roof	1	EA	12,250.00	12,250
FEF-5 Vektor - roof	1	EA	12,250.00	12,250

## Dust Collection:

DC-1	1	EA	35,000.00	35,000
------	---	----	-----------	--------

## Dust Connection:

Bandsaw	1	EA	2,500.00	2,500
Combo sander	1	EA	2,500.00	2,500
Planer	1	EA	2,500.00	2,500
Table swa	1	EA	2,500.00	2,500
Jointer	1	EA	2,500.00	2,500



DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Miter saw	1	EA	2,500.00	2,500
HW System:				
HWB-1 (AR 4,000)	1	EA	52,500.00	52,500
HWB-2 (AR 4,000)	1	EA	52,500.00	52,500
HWP-1,2	2	EA	15,000.00	30,000
BP 1,2	2	EA	2,250.00	4,500
VFD	2	EA	3,200.00	6,400
Chemical feed	1	LS	35,000.00	35,000
Air separator	1	EA	2,800.00	2,800
Expansion tank	1	EA	3,200.00	3,200
8" Feed Manifold	50	LF	350.00	17,500
6" Manifold S&R	100	LF	225.00	22,500
Boiler piping trim and valves	1	LS	26,000.00	26,000
10" Flue	365	LF	185.00	67,525
Flue Roof Term and Mast	4	EA	1,500.00	6,000
PH Tank	1	LS	1,500.00	1,500
Intake Louver and Damper	1	LS	6,000.00	6,000
Exhaust Louver and Damper	1	LS	6,000.00	6,000
10" Boiler flue	275	LF	160.00	44,000
Elec Room Exhaust fan and Louver	1	LS	3,500.00	3,500
Air-Cooled Chiller:				
CH - 1	370	TON	1,050.00	388,500
Chiller rough in, valve and trim	1	LS	20,000.00	20,000
Pump Package	1	LS	175,000.00	175,000
Ductwork:				
Galv Ductwork	136,090	LBS	10.50	1,428,945
Stainless Steel - welded	4,000	LBS	25.00	100,000
Premium for perf atrium ducts	1	LS	25,000.00	25,000
20" Fabric duct soc	402	LF	36.50	14,673
24" Fabric duct soc	302	LF	41.00	12,382
Kitchen hood exhaust duct - welded	2,918	LBS	17.50	51,065
Alum. dishwasher ductwork	750	LBS	12.00	9,000
1" Duct insul	48,376	SF	4.10	198,342
Duct Liner	8,025	SF	6.25	50,156
Matt white Rigid duct insul;	20,000	SF	6.80	136,000
EPDM wrap	9,055	SF	12.00	108,660
2 HR Fire wrap - dbl wrap	849	SF	16.20	13,754
Plenum Air Intake				
Alum Louver	carried w/ exterior			
Motor Op damper	19	EA	4,500.00	85,500
Ducted Plenum intake	19	EA	3,000.00	57,000

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Air Devices:				
DD - 1	39	EA	450.00	17,550
DD - 2	116	EA	575.00	66,700
DD - 3	22	EA	375.00	8,250
DD - 4	7	EA	310.00	2,170
DD - 5	5	EA	875.00	4,375
DD - 6	4	EA	600.00	2,400
DD - 7	40	EA	775.00	31,000
DD - 8	3	EA	825.00	2,475
DD - 9	4	EA	975.00	3,900
E - 1	57	EA	195.00	11,115
R - 1	86	EA	185.00	15,910
R - 2	7	EA	195.00	1,365
SA - 1	14	EA	220.00	3,080
VAV Box	150	EA	1,250.00	187,500
CV Regulator	32	EA	980.00	31,360
Volume Damper	47	EA	245.00	11,515
Auto Damper	16	EA	1,400.00	22,400
Fire damper	30	EA	550.00	16,500
Destratification fan	3	EA	8,500.00	25,500
AC Split System:				
Ductless Cooling Unit Systems:				
DCUe-1	1	EA	7,800.00	7,800
DCUe-2	1	EA	10,500.00	10,500
DCUe-3	1	EA	10,500.00	10,500
DCUe-4	1	EA	9,500.00	9,500
DCUe-5	1	EA	9,500.00	9,500
DCUe-6	1	EA	9,500.00	9,500
DCUe-7	1	EA	9,500.00	9,500
DCUe-8	1	EA	9,500.00	9,500
Condensate Pumps:				
CP-1 & Cond. Piping	8	EA	1,200.00	9,600
Hydraulic Heater:				
Unit Heater	16	EA	1,100.00	17,600
RP - 1	1,341	LF	156.00	209,196
RP - 2	92	LF	156.00	14,352
FTR - 1	602	LF	68.00	40,936
FTR - 2	320	LF	68.00	21,760
FT Cover	934	LF	27.00	25,218
Modulating Valve	135	EA	285.00	38,475
Isolation valve	270	EA	92.00	24,840
Electric Fin Tube Heater	8	EA	950.00	7,600

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
<b>Piping:</b>				
1 1/2"	1,031	LF	33.25	34,281
1 1/4"	897	LF	27.30	24,488
1"	2,139	LF	22.00	47,058
2 1/2"	723	LF	66.00	47,718
2"	1,516	LF	44.00	66,704
3"	504	LF	91.00	45,864
3/4"	7,788	LF	19.50	151,866
4"	967	LF	103.00	99,601
6"	1,374	LF	144.50	198,543
8"	243	LF	187.00	45,441
<b>1" Pipe Insulation:</b>				
1 1/2"	1,031	LF	8.00	8,248
1 1/4"	897	LF	7.90	7,086
1"	2,139	LF	7.50	16,043
2 1/2"	723	LF	9.00	6,507
2"	1,516	LF	8.45	12,810
3"	504	LF	9.50	4,788
3/4"	7,788	LF	7.40	57,631
4"	967	LF	11.90	11,507
6"	1,374	LF	14.45	19,854
8"	243	LF	16.25	3,949
<b>Mechanical Piping:</b>				
AHU Valving	8	EA	3,500.00	28,000
Misc. Control Valve	8	EA	2,500.00	20,000
<b>Temperature Control:</b>				
AHU/ERV	8	EA	25,000.00	200,000
Chiller and Cooling Equipment	1	LS	30,000.00	30,000
Boiler and Heating	1	LS	20,000.00	20,000
Pump	6	EA	1,800.00	10,800
VAV	156	EA	1,500.00	234,000
Hydronic point	135	EA	750.00	101,250
Exhaust Fan	17	EA	1,500.00	25,500
AC Split	8	EA	750.00	6,000
CO2 Sensor	119	EA	650.00	77,350
T stat	188	EA	485.00	91,180
Misc. temp control	1	LS	50,000.00	50,000
Seismic & vibrator control	1	LS	35,000.00	35,000
Test and balance	136,600	GSF	0.65	88,790
Staging and Lifts	1	LS	30,000.00	30,000
Commission coordination	1	LS	25,000.00	25,000
GC & misc.	1	LS	25,000.00	25,000

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
				-----
				8,247,841

## DIVISION 26 - ELECTRICAL

## 260001 ELECTRICAL\*

## Lighting Fixtures:

Exit	43	EA	324.20	13,941
G\$ - gym	80	EA	837.00	66,960
LC3 - classroom cove	1,927	LF	97.76	188,384
LK24	15	EA	267.00	4,005
LP4	6	EA	452.00	2,712
LP4S - aud	81	EA	775.00	62,775
LP8	6	EA	836.40	5,018
LR2 - typical	763	EA	402.00	306,726
LRD 5 - bathroom	12	EA	1,119.00	13,428
LRS - corridor	104	EA	783.60	81,494
LS2	2	EA	332.00	664
LS4	53	EA	362.00	19,186
LS8	17	EA	526.40	8,949
LWS - bathroom cove	647	LF	84.10	54,413
RC-1	92	EA	267.00	24,564
RSH	1	EA	282.00	282
SC - commons	40	EA	888.00	35,520
SL4 - exterior	19	EA	507.80	9,648
UC (as shown only )	66	LF	50.40	3,326
Branch Wiring	136,000	SF	1.25	170,000
Lighting Control System	136,000	SF	2.00	272,000

## Mechanical:

VAV 20A 1 frac	89	EA	182.20	16,216
WH 20A 1 1a	3	EA	182.20	547
WH 30A-3P-250v	1	EA	344.00	344
GB 30A-3P-250v	2	EA	611.00	1,222
J\$M	3	EA	182.20	547
Meters & flows & solen \$M WP	14	EA	182.20	2,551
MC-14/2 W/G	1,500	LF	1.69	2,529
MC-12/2 W/G	1,900	LF	1.71	3,241
MC-12/3 W/G	1,400	LF	2.14	2,996
MC-12/4 W/G	1,180	LF	2.56	3,026
MC-10/4 W/G	400	LF	4.56	1,825
UH	21	EA	182.20	3,826
EMT 3/4"C-3#12	2,800	LF	5.34	14,952
VFD FBO I&W	17	EA	216.00	3,672

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
25 - 100/100A/3/480v	4	EA	466.00	1,864
EMT-1 1/2"C-4#2 & 1#8	500	LF	15.76	7,880
GFI WP roof	22	EA	97.00	2,134
Roof stonco	10	EA	228.00	2,280
WP roof Switch	10	EA	87.00	870
EMT-3"C-3#12 (roof)	3,450	LF	5.32	18,354
EMT-3"C-4#12 (roof)	3,100	LF	5.80	17,980
CP-1	11	EA	182.20	2,004
MC-12/2 W/G	700	LF	1.71	1,194
JB 8x8x4	11	EA	68.20	750
480v 3 30A	11	EA	706.00	7,766
480v 3 40A	2	EA	938.00	1,876
EUH 250v 1 30A/2P	3	EA	416.00	1,248
ECU 208v 1 15A	11	EA	182.20	2,004
DCU J 208v 1 30A	11	EA	436.00	4,796
EMT-3/4"C-4#10	1,200	LF	6.38	7,656
ET 120v 1	8	EA	182.20	1,458
MAU-1 60/40A/3/480v	1	EA	391.00	391
EMT-1"C - 4#8 & 1#10	70	LF	7.14	500
Mechanical (cont):				
Boiler 20A - 1 30A/2P	3	EA	513.00	1,539
Boiler pumps 20A 2P 208v	3	EA	366.00	1,098
Chiller 480v 600/600A/3	2	EA	2,148.00	4,296
EMT-3"C - 3#250 mcm & 1#4	260	LF	32.56	8,466
EMT-3/4"C 4#8 & 1#10	140	LF	8.39	1,175
SEF 100/100A/3/480v	4	EA	650.00	2,600
#2 MI cable	1,600	LF	19.32	30,912
#2 MI terms (quick)	32	EA	116.00	3,712
RTU - 400/250A/3/3R	4	EA	971.00	3,884
RTU - 200/150A/3/3R	2	EA	613.00	1,226
RTU - 100/70A/3/3R	1	EA	486.00	486
RTU - 60/50A/3/3R	1	EA	391.00	391
EMT-3"C-4#250 & 1#4	520	LF	40.38	20,998
EMT-2"C-4#1/0 & 1#6	325	LF	21.96	7,137
EMT-1 1/4"C-4#4 & 1#8	150	LF	12.62	1,893
EMT-1"C-4#6 & 10	150	LF	10.25	1,538
Wiring Devices & Scoreboard Work:				
Duplex	388	EA	58.84	22,830
GFI duplex	109	EA	61.84	6,741
WP GFI	8	EA	94.00	752
Surf double duplex	37	EA	124.00	4,588

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Switched rec w/IO module	24	EA	240.00	5,760
NEMA L14-20R	27	EA	107.00	2,889
LS limit switch	3	EA	107.00	321
CP cont pnl - wire only	8	EA	144.00	1,152
TML mtr conn	8	EA	83.80	670
J 4" sq w/cover	6	EA	41.00	246
ISO grd out shot clock	2	EA	87.00	174
Wire only scoreboard	1	EA	144.00	144
30/20A/3240v	2	EA	269.00	538
EMT-3/4"C-4#12	1,800	LF	5.79	10,422
Double duplex - color	216	EA	101.40	21,902
Tw loc @ tray	11	EA	102.00	1,122
Cable tray 24"c12'0"	6	EA	309.00	1,854
Poke thru	2	EA	666.00	1,332
Key sw	1	EA	64.00	64
MOM conn cw	6	EA	70.00	420
CP bleacher pwr	7	EA	366.00	2,562
MC-12/2 w/G	39,500	LF	1.71	67,387
MC-12/3 w/G	2,000	LF	2.14	4,280
EMT-3/4"C - 3#12	1,900	LF	5.32	10,108
Emergency Generator & ATS:				
300kw 277/480v Natural Gas Generator	1	EA	159,320.00	159,320
Enclosure	1	EA	432.00	432
400A/3P output c/b	1	EA	144.00	144
150A/3P output c/b	1	EA	144.00	144
Interior panel	1	EA	288.00	288
Receive rig & set	1	EA	11,152.00	11,152
Unit mtd EPO	1	EA	638.00	638
Bldg mtd EPO	1	EA	907.00	907
Annunciator	1	EA	576.00	576
ATS-OS 400A 4P	1	EA	432.00	432
ATS-LS 150A 4P	1	EA	576.00	576
PVC-1"C-4#10 & 1#10	150	LF	4.01	602
PVC-1"C-14#13	150	LF	5.60	840
EMT-3/4"C-2#14	280	LF	5.12	1,434
EMT-3/4"C-5#14	120	LF	6.09	731
MI - 4#1/0	140	LF	107.36	15,030
MI - quick terms	8	LF	133.20	1,066
WIC 4#500 & 1#3	130	LF	45.84	5,959
EMT-4"C-4#500 & 1#3	140	LF	67.24	9,414
EMT-2"C-4#10 & 1#6	150	LF	21.96	3,294
Fire Alarm System:				
Material	1	LS	219,942.00	219,942
Bi-directional antenna sys	1	LS	4,752.00	4,752
Elevator shaft & machine rm fitout	1	LS	3,456.00	3,456

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Floor plan under glass	3	LS	144.00	432
Sprinkler bell I&W only	1	LS	216.00	216
DK drill key switch	1	LS	72.00	72
FACP flush control pnl	1	LS	4,608.00	4,608
Red beacon	1	LS	216.00	216
As built cabinet	1	LS	144.00	144
FM flush master box	1	LS	360.00	360
K knox box	1	LS	216.00	216
W white strobe	1	LS	144.00	144
LOC local operator control pnl	1	LS	864.00	864
Smoke exhaust graphic plaque w/LED indicator of statue	1	EA	1,152.00	1,152
FATC term cabinet	3	EA	864.00	2,592
ANN annunciator	3	EA	432.00	1,296
VE voice evac pnl	1	EA	2,304.00	2,304
MNS ??	3	EA	288.00	864
LS limit sw	6	EA	72.00	432
BD beam det xmit/rcur	5	EA	180.00	900
MM monitor module	66	EA	72.00	4,752
CM control module	26	EA	72.00	1,872
IM isolation module	3	EA	72.00	216
CO2 det tie in	1	EA	144.00	144
Security tie in	2	EA	144.00	288
Refuge tie in	1	EA	144.00	144
BDA tie in	5	EA	144.00	720
CO MM CO2 det w/monitor mod	9	EA	144.00	1,296
Smoke w/base	89	EA	72.00	6,408
Smoke to control atrium smoke	115	EA	72.00	8,280
Strobe only	61	EA	108.00	6,588
A/V unit	0	EA	0.00	0
A/V unit w/ amber alert	270	EA	144.00	38,880
FS TS flow & tampers	42	EA	72.00	3,024
Fire Alarm System ( cont):				
F Pull station	29	EA	61.20	1,775
MAG door holders	6	EA	72.00	432
ST1 stopper II 6500	29	EA	36.00	1,044
J 4" oct j-box	218	EA	33.80	7,368
J 4" sq w/device ring	158	EA	42.00	6,636
BB back box	331	EA	53.20	17,609
Programming & pretest	1	EA	1,728.00	1,728
FFD testing & cert	1	EA	1,728.00	1,728
ir & smoke test	1	EA	576.00	576
Water flow testing	1	EA	576.00	576
EMT-3/4"C-4#14	1,200	LF	5.42	6,504

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
AFC-#4901-16/2 14/2	13,160	LF	4.46	58,694
MC-4/C#14 red jacket	13,240	LF	2.64	34,954
Induct smoke	40	EA	288.00	11,520
Rem test sat	40	EA	108.00	4,320
Relay modules	40	EA	72.00	2,880
Monitor modules	40	EA	72.00	2,880
Mass notif UL listed computer	1	LS	50,000.00	50,000
Kitchen Power & Conns:				
S clg speaker	9	EA	381.00	3,429
Wall clock	1	EA	247.00	247
Voice outlet	1	EA	225.00	225
Duplex	36	EA	59.84	2,154
J	36	EA	92.00	3,312
TML-3/4"C-3#12	46	EA	50.24	2,311
TML-3/4"C-4#12	2	EA	61.00	122
TML-3/4"C-5#12	3	EA	69.60	209
TML-3/4"C-4#10	2	EA	81.80	164
TML-1 1/4"C-4#4 & 1#0	2	EA	132.00	264
60/50/3/250v	2	EA	286.00	572
30/20/3/250v	1	EA	228.00	228
30/3P/250v	2	EA	208.00	416
30/2P/250v	4	EA	198.00	792
Ther sw w/OL	9	EA	150.00	1,350
EMT-3/4"C-3#12	2,000	LF	5.32	10,640
EMT-3/4"C-4#12	100	LF	5.78	578
EMT-3/4"C-5#12	160	LF	6.24	998
EMT-3/4"C-4#10	100	LF	6.38	638
EMT-1 1/4"C-4#4 & 1#10	100	LF	13.19	1,319
MC-12/2 w/G	1,500	LF	1.85	2,775
CO2 gas solenoid shutdown	1	LS	3,404.00	3,404
Hood/ansul/EP work	1	LS	6,206.00	6,206
Master Lightning Protector Systems & Theatre:				
Theatrical ltg Rough-in	1	LS	98,780.00	98,780
Heary Bros Lightning Preventer Systems	2	EA	13,820.00	27,640
Window shade installation	1	LS	10,760.00	10,760
Area of refuge system	1	LS	16,676.00	16,676



DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Integrated Electronic Security:				
Material - Turnkey:	1	LS	342,000.00	342,000
Includes:				
DSC Main cont pnl	1	EA		
12v 7 AH batteries	2	EA		
Xfmrs	2	EA		
Key lock w/relay mod	1	EA		
8 Zone expansion mod	1	EA		
16 Zone expansion mod	1	EA		
Addr. point modules	12	EA		
Touchscreen keypad	4	EA		
Wireless panic statin	6	EA		
Wireless received mod	1	EA		
Wall motions	35	EA		
Clg motions	38	EA		
Interface printer	1	EA		
Fargo photo badging	1	EA		
Flush door contacts	50	EA		
OHD central contacts	2	EA		
Cellular communicator	1	EA		
8 Reader controller	11	EA		
DSX proximity readers	18	EA		
Bosch rte motions	14	EA		
DSC lan module/software	1	EA		
160 TB Network video recorder	1	EA		
12MP camera	13	EA		
5 MP ext dome camera	2	EA		
Wall arms	2	EA		
5 MP Interior dome	27	EA		
5 MP indoor 360der dome	29	EA		
Rack w/receivers/mx mmtrs	1	EA		
Axis ect 360 deg camera	3	EA		
A1 phone master video	3	EA		
A1 phone IC-DF video door sta	4	EA		
Strong pole split 20'	3	EA		
43" Smart TV	2	EA		
55" Smart TV	2	EA		
Chief TV wall brkt	4	EA		
24 Port poe & sw	3	EA		
28 Port poe & sw	10	EA		
Programming	1	LS		
Accessories	1	LS		
Supervision & final conn	1	LS		
O&M manuals	1	LS		
Auto Cad dwgs	1	LS		
Owner training	1	LS		

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Structured Cabling System:				
Material - turnkey	1	LS	389,939.00	389,939
Includes:				
ACCU tech TS teacher sta	70	EA		
Programming	1	EA		
Supervision & final conn	1	EA		
O&M manuals w/closeout	1	EA		
Auto Cad drawings	1	EA		
Owner training	1	EA		
50 PR 66 blocks	6	EA		
25 PR 66 blocks	6	EA		
50 PR 110 blocks	6	EA		
Belden 2 post rack	8	EA		
Belden rack mt PDU	8	EA		
Belden 4 port face plate	150	EA		
Belden 2 port face plate	250	EA		
Belden F conn insert	70	EA		
Belden CAT6A green insert	400	EA		
Belden CAT6A blue insert	400	EA		
Belden 48 port patch pnl	12	EA		
Belden horiz cable mgr	40	EA		
Belden 10' patch cord	800	EA		
Belden CAT6A plenum blue	100	EA		
Belden CAT6A plenum green	100	EA		
Belden OS2 sm patch cord	100	EA		
Belden OM4 mm patch cord	100	EA		
Belden 4 cassettes hsg	8	EA		
Belden 6 fiber hsg	8	EA		
Belden 18 fiber hsg	8	EA		
Ground bars w/grd cable	1	LS	23,640.00	23,640
Conduit sleeves, cable tray and fiber backbone	1	LS	30,960.00	30,960
Intercom & Clock Systems:				
Material - turnkey	1	LS	119,970.00	119,970
Includes:				
Valcom 9 position back plane	1	EA		
Valcom main power supply	2	EA		
Valcom main VPV	1	EA		
Valcom Rack mount kit	1	EA		
Valcom dual 6A switching	1	EA		
Valcom 2x2 talkback spkr	240	EA		
Valcom call in pushbutton	66	EA		
Valcom GPS master clock	1	EA		
Valcom repeater	2	EA		

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Valcom 12" round clocks	84	EA		
Valcom administrative teleph	1	EA		
Valcom 16" clocks/repeater	2	EA		
Valcom wire guard	2	EA		
Valcom power supply	1	EA		
Cowell rack equip	1	LS		
Atlas paging horns	21	EA		
Atlas flush enclosures	21	EA		
Atlas grills	21	EA		
Valcom retro blocks	3	EA		
Valcom power amps	3	EA		
Valcom rack mount kit	3	EA		
Valcom 24 pt talk back	3	EA		
Valcom admin gateway	1	EA		
Valcom volume control	21	EA		
Valcom network port/cards	1	EA		
Programming	1	LS		
Supervisions & final conn	1	LS		
O&M manuals & closeout	1	LS		
Auto cad swgs & submit	1	LS		
System testing	1	LS		
System owner training	1	LS		
A/V Systems:				
FSR	1	EA	951.40	951
Clg proj	1	EA	700.00	700
Duplex	41	EA	60.84	2,494
Data drop	43	EA	250.00	10,750
Hardwired AC pwr	2	EA	97.00	194
Chief PAC 526	3	EA	741.00	2,223
VI Wall proj IG deep	41	EA	44.00	1,804
SI Wall spkr 1G deep	82	EA	44.00	3,608
RI Rec pnl 2G deep	42	EA	57.80	2,428
BP ?? 2G deep	42	EA	57.80	2,428
J1 12'x12'x4" flush	2	EA	203.00	406
R2 2 gang deep	4	EA	74.00	296
R3 3 gang deep	4	EA	82.00	328
S2 clg loud spkr - b.box	10	EA	74.00	740
S3 clg loud spkr - b.box	8	EA	74.00	592
EMT-1 1/4"C- w/PS	480	LF	7.66	3,677
EMT-1 "C- w/PS	300	LF	6.19	1,857
EMT-3/4"C- w/PS	2,500	LF	4.63	11,575

Section 274100 A/V  
Includes Systems for:

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Classrooms		NIC		
Auditorium		w/equipment		
Auditorium av Rough-in	1	EA	45,000.00	45,000
Switchgear Panels & Transformers:				
45 KVA xfmr	8	EA	5,232.00	41,856
75 KVA xfmr	6	EA	7,540.00	45,240
Xfmr ground	14	EA	394.00	5,516
100A/3P/480v	3	EA	304.00	912
200A/3P/480v	3	EA	372.00	1,116
SFD 2500A @ 480v	1	EA	1,788.00	1,788
SPD panel mounted	39	EA	422.00	16,458
SPD grounds	40	EA	172.00	6,880
Elev controller	1	EA	144.00	144
100/100A/3P/480v	1	EA	339.00	339
30/20A/3P/208v	1	EA	218.00	218
TML 40	1	EA	204.00	204
100A/3/250v	1	EA	274.00	274
UPS system 24 kw	1	EA	24,880.00	24,880
Rigging for UPS	1	EA	2,432.00	2,432
EPO power off setup	1	EA	274.00	274
ST1 6500 guard	1	EA	127.00	127
Main service grounding	1	EA	822.00	822
Meter socket	1	EA	544.00	544
Main swbrd 3000A @ 480v	1	EA	40,896.00	40,896
Feeders	136,000	EA	1.95	265,200
Dist pnl 4DP1B-800A @ 480v	1	EA	7,248.00	7,248
Dist pnl 2DP1C-400A @ 208v	1	EA	5,160.00	5,160
Double tub pnl @ 120/208v	10	EA	3,890.00	38,900
Single tub pnl @ 120/208v	12	EA	2,752.00	33,024
400A-480v pnl	3	EA	5,072.00	15,216
225A-480v pnl	3	EA	3,052.00	9,156
100A-480v pnl	8	EA	2,688.00	21,504
DENIS VERIFY SECONDARY FEED				
60% CD Adders/Deletes:				
Integrated Electronic Security - 60% Adders/Deducts:				
Turnkey - Includes:	1	EA	27,000.00	27,000
Reader controller - add	1	EA		
Elevator controller - add	3	EA		
CR REX DC DC PS - add	1	EA		
CR DC REX PS - add	3	EA		
Wall motions - add	9	EA		
Ext. wall camera - add	1	EA		
Int. dome camera - add	1	EA		
Int. 180 deg - add	30	EA		

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Ext. 180 deg - add	14	EA		
Int. 360 deg - deduct	-29	EA		
Ext. 360 deg - deduct	-9	EA		
VES - add	1	EA		
VMS - deduct	-2	EA		
OHD - DC - add	2	EA		
Structured Cabling - 60% Adders/Deducts:				
Turnkey - Includes:	1	LS	97,000.00	97,000
IDE closets - reduced	-1	EA		
Teachers station - add	1	EA		
TVE - add	4	EA		
AN - add	115	EA		
N2D - delete	-7	EA		
2 Data - add	39	EA		
TVS-48	3	EA		
TVC-96	1	EA		
CAT 6A ports	1,135	EA		
48 Port patch pnl's	15	EA		
P.A. & Intercom - 60% CD Adders:				
Turnkey - Includes:	1	LS	20,000.00	20,000
Speakers - add	41	EA		
Volume control - add	6	EA		
12" Clocks - add	8	EA		
Ext. flush horn spkrs - add	2	EA		
#of classrooms - reduced	-9	EA		
IDF closets - reduced	-1	EA		
Fire Alarm & Gear - 60% Adders/Deducts:				
FA - A/V w/ amber alert	7	EA	419.00	2,933
S - smoke w/base	3	EA	162.00	486
W WP - A/V - WP	1	EA	271.00	271
BB backbox	7	EA	53.20	372
BB WP backbox WP	1	EA	63.40	63
J - 4" oct	3	EA	33.80	101
AFC - #4901 cable	300	LF	4.46	1,338
MC - 14/4C red jacket	50	LF	2.64	132
Dist. pnl 2 DP1A - 600A @ 480	1	EA	7,248.00	7,248
Dist. pnl 2 DP1B - 600A @ 480	1	EA	7,248.00	7,248
Upsize ATS-LS from 150 to 200A	1	EA	1,144.00	1,144
Upsize ATS-OS from 400 to 600A	1	EA	3,216.00	3,216
Upsize G/S from 250kw to 300 kw	1	EA	5,500.00	5,500
Upsize G/S output d/b from 400 to 600A	1	EA	2,000.00	2,000

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
ESL storm sw w/feeder tie	1	EA	6,830.00	6,830
Power Wiring Devices - 60% Adders/Deducts:				
Duplex	105	EA	58.84	6,178
GFI duplex	23	EA	62.84	1,445
WP GFI duplex	18	EA	94.00	1,692
NEMA CIS 3OR	1	EA	107.00	107
20A GFI - color	28	EA	71.84	2,012
Double duplex	42	EA	113.20	4,754
MC-10/3	60	LF	2.83	170
\$MC	2	EA	70.00	140
\$DW disc sw - DW	1	EA	82.00	82
J - dishwasher	1	EA	96.20	96
J - fume hood	1	EA	117.00	117
EF	2	EA	182.20	364
SEF	2	EA	182.20	364
KEF	1	EA	344.00	344
FEF	1	EA	344.00	344
DCU	2	EA	436.00	872
CPJ - bleacher power	1	EA	366.00	366
Scoreboard power & cont.	1	EA	463.00	463
Turnkey - area of refuge AKA				
2 way communication	1	LS	14,953.00	14,953
90% CD Adders/Deducts:				
Service, Fire Alarm - 90% CD Adders/Deducts:				
24 kw UPS	1	EA	24,380.00	24,380
EPO em. pwr off	1	EA	491.00	491
Disc sw.	1	EA	344.00	344
TEP2B - add section 2	1	EA	938.00	938
MP1A - add section 2	1	EA	938.00	938
Pnl ELIID - F&I new	1	EA	3,296.00	3,296
SPD - pnl mtd	2	EA	539.00	1,078
PNI - MHP-LR-F&I new	1	EA	3,640.00	3,640
ATS - LR-400A 4P	1	EA	7,448.00	7,448
Increase gen/set to 350 kw	1	EA	7,000.00	7,000
Add output c/b	1	EA	144.00	144
Misc. additional feeders	1	LS	27,960.00	27,960
MI cable #2 w/terms	1	LS	13,320.00	13,320
TS tamper or flow	23	EA	84.00	1,932
MM monitor module	23	EA	147.00	3,381
F pull station	5	EA	126.20	631
F - strobe	4	EA	233.00	932
S - smoke	6	EA	162.00	972
J	6	EA	30.20	181

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
J square	51	EA	36.24	1,848
BB	4	EA	46.00	184
4901 cable	500	LF	4.46	2,230
14/4C cable	2,800	LF	2.64	7,392
Security & Misc. Wiring Devices - 90% CD Adders/Deducts:				
WP - ext. camera	2	EA	1,125.00	2,250
Int. camera	3	EA	975.00	2,925
CR WP	3	EA	1,295.00	3,885
IC WP	1	EA	978.00	978
Door setups - box & conduit	4	EA	800.00	3,200
CR - interior	5	EA	1,295.00	6,475
DC	8	EA	275.00	2,200
Welder	1	EA	184.00	184
Duplex	79	EA	58.84	4,648
Duplex - double	34	EA	124.00	4,216
CR - clg for cord reel	8	EA	128.00	1,024
GFI	40	EA	61.84	2,474
Mech conn w/j.box	1	EA	83.80	84
G - sw. rec. w/ IL mod.	15	EA	240.00	3,600
USB - duplex w/USB outlet	7	EA	133.00	931
WP GFI	1	EA	94.00	94
Backboard gym setups	2	EA	391.00	782
MC-12/2 wG	10,740	LF	1.72	18,430
MC-6/3 wG	100	LF	4.16	416
Lighting, Controls, Mechanical - 90% CD Adders/Deducts:				
LR5D - deleted	-10	EA	95.00	-950
LS4B - deleted	-15	EA	375.00	-5,625
L - LV switch - add	10	EA	230.00	2,300
PC1 - add	16	EA	480.00	7,680
PC2 - add	9	EA	480.00	4,320
LR4 - deleted	-8	EA	450.00	-3,600
JB wall fixt. - add	8	EA	280.00	2,240
LS4 - add	3	EA	362.00	1,086
LP8 - add	3	EA	526.00	1,578
OS clg occ - add	4	EA	420.00	1,680
LR2 - add	499	EA	385.00	192,115
LC3 - add	980	LF	97.76	95,805
J - 4" oct j-box	46	EA	30.20	1,389
Mtg hdwre	530	EA	8.20	4,346
MC-12/2 w/ground	2,000	LF	1.72	3,432
CH-1 - control conn/heat tape	2	EA	591.00	1,182
DCV-8-208v 1 30A	2	EA	713.00	1,426
EFT - elec BB 2 kw 208v	8	EA	571.00	4,568

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
FEF - F.H. ex fan 480v 3	2	EA	942.00	1,884
KEF-2 - ex. fan 120v 1	1	EA	541.00	541
UH - unit heater 120v 1	3	EA	541.00	1,623
Technology Drawings - 90% CD Adders/Deducts:				
AN - wifi	8	EA	275.00	2,200
2 Data	24	EA	300.00	7,200
W - wall voice	21	EA	215.00	4,515
S clg spkr	11	EA	129.00	1,419
S clg spkr	52	EA	189.00	9,828
?	3	EA	295.00	885
S	10	EA	129.00	1,290
T	1	EA	500.00	500
IV/2D	5	EA	385.00	1,925
OH&P - 10%	1	LS	500,295.85	500,296
DJE	1	LS	150,000.00	150,000
Site Electrical Work:				
Utilities:				
PRI manhole dressing	1	EA	1,576.00	1,576
Utility pole PRI & FA dressing	1	EA	1,364.00	1,364
Utility pole commun. dressing	1	EA	1,076.00	1,076
Gen/set pad grndg	1	EA	982.00	982
Xfmr pad grndg	1	EA	1,376.00	1,376
Gen/set pad 90 deg. & sleeves	1	EA	566.00	566
Xfmr pad 90 deg. & sleeves	1	EA	688.00	688
Duct Bank CC:				
PVC-4"C - w/PS (120')	600	LF	4.38	2,628
PVC-1"C- w/4#12	480	LF	3.62	1,738
Duct Bank AA:				
PVC-4"C - w/PS (270')	540	LF	4.38	2,365
Duct Bank BB:				
PVC-4"C - w/PS (110')	770	LF	4.38	3,373
Duct Bank FF:				
PVC-4"C - w/PS (120')	240	LF	4.38	1,051
Duct Bank Fire Alarm:				
PVC-2"C - w/PS (300')	300	LF	2.06	618



DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
IMSA 20-5 cable	350	LF	3.44	1,204
Duct Bank DD (230'):				
PVC-4"C - w/PS	920	LF	4.38	4,030
Inner duct 1 1/4"C- w/PS	690	LF	2.64	1,822
Ext camera on 20' pole	3	EA	5,470.00	16,410
Fiber optic w/PVC	1,000	LF	5.88	5,880
Pole foundation	3	EA	1,326.00	3,978
Electrical Manhole	2	EA	8,500.00	17,000
OH&P - 10%	1	LS	6,972.38	6,972
DJE	1	LS	20,000.00	20,000
Site Lighting:				
Lighting Fixtures:				
SL1 - 20' pole	37	EA	2,676.00	99,012
SL3 - poulsen bollard	9	EA	1,812.00	16,308
SL4 - egress perimeter lgt	21	EA	616.00	12,936
SL5 - in ground bega	16	EA	791.00	12,656
SL6 - bega flood w/remote driver	0	EA	0.00	0
SL10 - mini flood	0	EA	0.00	0
SL1A - 20' pole	4	EA	2,676.00	10,704
SL3 - wall mtd area lt - MV	4	EA	544.00	2,176
HH 12x12x12"d in gr p.box	3	EA	638.00	1,914
PB 17"x30"x12"d	12	EA	648.00	7,776
PB-24"x36"x24"d w/divider	2	EA	788.00	1,576
EV charging station - level 2	3	EA	3,754.00	11,262
J 8x8x4 inter j-box	3	EA	74.00	222
T/C 7 dy w/batt pack	1	EA	666.00	666
Pipe into & wire to exist pnl	1	EA	144.00	144
Demo exist pole w/fixt	4	EA	576.00	2,304
Penetrate m bay gym	1	EA	338.00	338
Relocated emer call box	2	EA	926.00	1,852
Call box base setup	2	EA	241.00	482
MC-12/2 w/G-fished	540	EA	1.99	1,077
PVC-1"C-3#8	9,320	EA	3.99	37,187
Pole base anchor bolts	48	EA	54.00	2,592
Pole base grounding	48	EA	162.00	7,776
Pole base sleeves & 90 deg	48	EA	137.00	6,576
Bollard base setups	42	EA	122.00	5,124
In ground hsg setups	16	EA	112.00	1,792
PVC-2 1/2"C-w/PS	1,500	EA	3.33	4,989
PVC-2"C-w/PS	620	EA	2.77	1,717
WP pedestal mtd Wayne Tyler CB box	5	EA	1,926.00	9,630

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Site - 60% Deducts:				
SL5 - Bega - in ground - delete	-11	EA	791.00	-8,701
SL4 - ext. pak - delete	-6	EA	616.00	-3,696
J WP - wall back box -WP- delete	-6	EA	43.00	-258
SL3 - poulson (bollard ) - delete	-18	EA	1,812.00	-32,616
PVC-1"C-3#8 - delete	-1,080	EA	3.99	-4,309
Bollard base setups - delete	-18	EA	122.00	-2,196
SL10 - in grade tree ltg - add	12	EA	816.00	9,792
Exist. ltg pole to demo - delete	-4	EA	576.00	-2,304
SL1 - 20' pole - delete	-10	EA	2,676.00	-26,760
SL1A - 20' pole - delete	-4	EA	2,676.00	-10,704
SL3 - wall mtd area lt- delete	-4	EA	616.00	-2,464
MC-12/2 - fished - delete	-540	EA	1.99	-1,077
8"x8"x4" interior j.box - delete	-3	EA	74.00	-222
T/C - 7 day w/batt pak - delete	-1	EA	666.00	-666
Penetrate M bay gym - delete	-1	EA	338.00	-338
PVC-1"C-3#8 - delete	-1,400	EA	3.99	-5,586
Pole base anchor bolts - delete	-14	EA	54.00	-756
Pole base grounding - delete	-14	EA	162.00	-2,268
Pole base sleeves & 90 degs - delete	-14	EA	137.00	-1,918
Add Site Elect				
SL1	12	EA	3,500.00	42,000
SL S	7	EA	1,500.00	10,500
Site - 90% CD Adders/Deducts:				
Early Site Plan - Phase 1 Dwg				
E-PH-1 back in		w package #1		
HH handhole for P.V. sys	3	EA	591.00	1,773
PVC-4"C w/p.s	600	EA	4.58	2,748
PVC-2"C w/p.s	400	EA	2.14	856
PVC-2 1/2"C w/p.s	760	EA	3.16	2,402
OH&P - 10%	1	LS	26,078.80	26,079
				-----
				6,000,049

DIVISION 31 - EARTHWORK

310000 EARTHWORK

-----  
0

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

311000 SITE PREPARATION & CLEARING

-----  
0

DIVISION 32 - EXTERIOR IMPROVEMENTS

321000 PAVEMENT, CURBING & EDGING

Pedestrian Paving:  
Site Pavement:  
HC tactile paver

w/ site package

-----  
0

323100 SITE IMPROVEMENTS

Entry Paver:  
Plaza Paver

745 SF 28.00 20,860

Basketball Court:  
Bit pavement  
Color seal coat  
8" Gravel

w/ site package  
1,750 SF 2.50 4,375  
w/ site package

Site Development:  
Site Improvements:  
Gateway and Bandstand

carried w/ building cost

Site Benches:  
Precast bench - wood top

20 LF 550.00 11,000

Bike loop  
8" Gravel Base

20 EA 675.00 13,500  
w/ site package

Versa loc Block - avg 10' high  
Filter Fabric

3,000 SF 48.00 144,000  
8,400 SF 1.10 9,240

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Allowance:				
Trash/recycle receptacle	10	EA	2,000.00	20,000
Entry sign		NIC		
Electronic school zone signals		NIC		
Flag pole w/base	1	EA	7,200.00	7,200
Traffic Gate	1	EA	3,500.00	3,500
Parking/traffic signage (C-7-5)	w/ site package			
Site Improvement - Allowance	1	SF	30,000.00	30,000
*site bollard carried with misc metals				
Basketball hoop	2	EA	4,000.00	8,000
				-----
				271,675

## 328000 IRRIGATION

Irrigate sod	41,496	SF	2.00	82,992
Irrigation System- Repair/Replace	82,800	SF	1.00	82,800
				-----
				165,792

## 329000 LANDSCAPING

Site Earthwork:				
12" Soil @ plant bed ( 8,122 sf)	301	CY	62.00	18,662
3" Planting bed mulch	76	CY	60.00	4,560
6" Loam - Lawn ( 288,987 sf)	5,351	CY	55.00	294,305
8" Loam - Athletic Field ( 260,744 sf)	6,431	CY	55.00	353,705
Credit to amend existing soil	-5,900	CY	35.00	-206,500

## Plantings:

## Trees:

## Sheet L2.0:

AC Shadblow Serviceberry (2.5-3" cal)	1	EA	775.00	775
AL Allegheny Serviceberry (2.5-3" cal)	12	EA	775.00	9,300
CK American Yellowwood (3-3.5" cal)	17	EA	900.00	15,300
FG American Beech (3-3.5" cal)	11	EA	900.00	9,900
NS Black Tupelo (3-3.5" cal)	8	EA	900.00	7,200
OA Sourwood (2.5-3" cal)	3	EA	775.00	2,325
PA London Plane Tree (3-3.5" cal)	24	EA	900.00	21,600
QP Pin Oak (3-3.5" cal)	7	EA	900.00	6,300
QR Red Oak (3-3.5" cal)	7	EA	900.00	6,300

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Sheet L2.1:				
AR Red Maple (3-3.5" cal)	6	EA	900.00	5,400
CK American Yellowwood (3-3.5" cal)	7	EA	900.00	6,300
LT Tulip Tree (3-3.5" cal)	8	EA	900.00	7,200
NS Black Tupelo (3-3.5" cal)	7	EA	900.00	6,300
Shrubs:				
CA Sweet Pepperbush (3.5-4' ht)	28	EA	215.00	6,020
HQ Oak Leaf Hydrangea (3-3.5' ht)	49	EA	200.00	9,800
HV Witch Hazel (7-8' B&B)	3	EA	450.00	1,350
IG Inkberry (4-4.5' ht)	33	EA	265.00	8,745
IV Winterberry (2.2.5' ht)	61	EA	185.00	11,285
JH Creeping Juniper (15-24" spd)	68	EA	50.00	3,400
JV Easter Red Cedar (7-8' ht)	26	EA	450.00	11,700
MG Sweetgale (3.5-4' ht)	38	EA	215.00	8,170
PF Pink Beauty Potentilla (24" spd)	22	EA	65.00	1,430
RA Grow Low Sumac (2-2.5' spd)	47	EA	80.00	3,760
RT Staghorn Sumac (3 gal)	13	EA	135.00	1,755
VA Lowbush Blueberry (15-24" spd)	53	EA	50.00	2,650
VD Arrowwood (4-4.5' ht)	31	EA	265.00	8,215
VT Dwarf Cranberry Bush (3-3.5' ht)	12	EA	265.00	3,180
Groundcover:				
Sheet L2.0:				
CP Sweet Fern (1 gal)	1,436	EA	36.00	51,696
Sheet L2.1:				
CP Sweet Fern (1 gal)	530	EA	36.00	19,080
Plant Maintance	1	LS	10,000.00	10,000
Sod:				
Sod at Amphitheater	25,334	SF	1.10	27,867
Sports Field	25,000	SF	1.10	27,500
Rake , Seed, Fertilize New Lawns:				
Lawn	119,912	SF	0.26	31,177
Meadow Mix	143,741	SF	0.28	40,247
Pea Stone drip edge	996	SF	12.00	11,952
Sports field	235,744	SF	0.30	70,723
Stone Dust - mech yard	500	SF	4.00	2,000
				-----
				942,635

## DIVISION 33 - UTILITIES

---

---

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

---

---

330000 UTILITIES

-----  
0

PROJECT: Fuller Middle School  
 LOCATION: Framingham, MA  
 CLIENT: SMMA Architects  
 DATE: 26-Sep-19

NO. OF SQ. FT.: 136,600  
 COST PER SQ. FT.: 63.77

No.: 18020

**EARLY SITE PACKAGE #1**

SUMMARY	DIVISION TOTAL	PERCENT OF PROJECT	COST PER SF
<b>DIVISION 02 - EXISTING CONDITIONS</b>			
<b>DIVISION 31 - EARTHWORK</b>			
310000 EARTHWORK	5,387,568	62%	39.44
311000 SITE CLEARING	756,447	9%	5.54
<b>DIVISION 32 - EXTERIOR IMPROVEMENTS</b>			
321000 BASES, BALLASTS AND PAVING	64,350	1%	0.47
323000 SITE IMPROVEMENTS	1,487,175	17%	10.89
<b>DIVISION 33 - UTILITIES</b>			
330000 UTILITIES	1,015,510	12%	7.43
	-----		
DIRECT COST	8,711,049	100%	63.77

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
DIVISION 31 - EARTHWORK				
310000 EARTHWORK				
Foundations:				
Ground Improvements:				
Geopiers	74,000	FTP	10.50	777,000
Rigid Inclusion towards RB - 1 and RB -	1	LS	50,000.00	50,000
Foundation Earthwork:				
Surcharge Bldg Footprint	1	LS	300,000.00	300,000
Excavate Footings	3,000	CY	15.00	45,000
Backfill Foundation	1,400	CY	15.00	21,000
Slab Fill	2,000	CY	28.00	56,000
Dewatering	1	LS	25,000.00	25,000
Foundation drain (1/S300)	120	LF	38.00	4,560
Slab on Grade:				
12" Gravel base - SOG	2,372	CY	34.00	80,648
Site Earthwork:				
Phase 1/2:				
Site Cut	2,847	CY	12.00	34,164
Stockpile cut	2,847	CY	10.00	28,470
Site Fill - supply	15,810	CY	18.00	284,580
Phase 3:				
Site Cut	21,721	CY	10.25	222,640
Site Fill - reuse mat'l	21,721	CY	11.00	238,931
Site Fill - supply	18,000	CY	18.00	324,000
Site Rough Grading	101,781	SY	2.30	234,096
Layout, Mobilization, Supervision	1	LS	250,000.00	250,000
Temp Drainage				
Dust Control	1	LS	10,000.00	10,000
Street Sweeping	1	LS	10,000.00	10,000
Surcharge Ampitheater	1	LS	200,000.00	200,000
Soils	1	LS	2,118,778.00	2,118,778
Soil Management:				
Dispose of contaminated soil - less than F	2,550	TONS	14.00	35,700
Dispose of contaminated soil - unlined	850	TONS	40.00	34,000
Add New Site Fill	4,000	CY	0.75	3,000



DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
				----- 5,387,568
311000 SITE CLEARING				
Site Preparation:				
Phase One:				
Jersey barriers	1,533	LF	75.00	114,975
Temp pavement	98,683	SF	1.50	148,025
Phase 1 - Grading & Drainage				
Erosion control	701	LF	7.50	5,258
Site prep	101,316	SF	0.20	20,263
Phase 2 - Grading & Drainage:				
Temp erosion basin Eroison control	307	LF	15.00	4,605
Construction entrance	1	EA	7,500.00	7,500
Construction fence	3,200	LF	12.00	38,400
Erosion control	2,500	LF	6.00	15,000
Drain inlet protection	25	EA	50.00	1,250
Erosion control maintenance	1	LS	15,000.00	15,000
Strip & stack top soil - 6"	5,900	CY	9.25	54,575
Selective Clear and Grub	1	LS	20,000.00	20,000
Saw cut walk	25	LF	5.00	125
Saw cut drive	25	LF	5.00	125
Site - Remove Existing:				
Cut and Cap	1	LS	5,000.00	5,000
Sanitary and Drain pipe	1,435	LF	35.00	50,225
Water Line	900	LF	31.00	27,900
Utility structures	10	EA	425.00	4,250
Wood guardrail	300	LF	15.00	4,500
Bit walk	201,786	SF	0.85	171,518
Conc. walk	14,967	SF	1.00	14,967
Bit Walkway	8,874	SF	0.90	7,987
Misc. site demolition	1	LS	25,000.00	25,000
				----- 756,447

## DIVISION 32 - EXTERIOR IMPROVEMENTS

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
<b>321000 BASES, BALLASTS AND PAVING</b>				
Pedestrian Paving:				
Bit sidewalk	1,862	SY	27.00	50,274
8" Gravel Base	414	CY	34.00	14,076
				-----
				64,350
<b>323000 SITE IMPROVEMENTS</b>				
Roadways:				
Phase 1:				
Bit pavement - parking and drive	8,147	SY	27.50	224,043
Raised Road Pavement w/ stamped finish	10,500	SF	15.00	157,500
12" Gravel base	2,715	SY	32.00	86,880
PCC- RAD	320	LF	32.00	10,240
PCC - straight	1,130	LF	26.00	29,380
SGC - straight	189	LF	39.50	7,466
VGC - RAD	79	LF	46.00	3,634
VGC - straight	365	LF	42.00	15,330
Line Painting	1	LS	5,000.00	5,000
Phase 2:				
Bit pavement	182	SF	30.00	5,460
12" Gravel base	61	SY	35.00	2,135
Base:				
Bit firelane pavement	1,685	SY	27.00	45,495
Bit pavement	14,204	SY	27.00	383,508
12" Gravel base	5,296	CY	32.00	169,472
VGC radial	1,646	LF	46.00	75,716
VGC straight	2,297	LF	42.00	96,474
Line Painting	1	LS	7,500.00	7,500
Street Patch at New Curb	1,154	LF	50.00	57,700
Pavement patch @ utilities	1	LS	15,000.00	15,000
Site Development:				
Site Improvements	1	LS	13,713.00	13,713
Vehicular guardrail - wood	952	LF	65.00	61,880
Utility Bollard	13	EA	1,050.00	13,650

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

-----  
1,487,175

## DIVISION 33 - UTILITIES

## 330000 UTILITIES

## Water:

## Phase 1 - Grading &amp; Drainage

2" Water	21	LF	70.00	1,470
6" Water	168	LF	92.00	15,456
CTE water	5	EA	3,000.00	15,000
Fire hydrant	3	EA	2,250.00	6,750
6" Gate Valve	4	EA	1,400.00	5,600
Misc Valves	4	EA	1,400.00	5,600

## Phase 2 - Grading &amp; Drainage:

2" Water line	147	LF	62.50	9,188
6" Water line	717	LF	88.00	63,096
Fire hydrant	1	EA	2,250.00	2,250
6" Gate Valve	1	EA	1,400.00	1,400
Misc Valves	2	EA	1,400.00	2,800
Site Connection	1	LOC	7,500.00	7,500

## Sanitary Sewer:

## Phase 2 - Grading &amp; Drainage:

8" PVC san	606	LF	80.00	48,480
Sewer manhole	3	EA	4,100.00	12,300
EGI-1	1	EA	12,500.00	12,500
Acid Waste tank	1	LS	15,000.00	15,000
Exist. sanitary manhole - site conn.	1	EA	7,500.00	7,500

## Storm Sewer:

## Phase 1 - Grading &amp; Drainage

12" HDPE	33	LF	76.00	2,508
18" HDPE	531	LF	94.00	49,914
24" HDPE	63	LF	145.00	9,135
30" HDPE	10	LF	210.00	2,100
6" PVC	45	LF	62.50	2,813
Catch Basin	6	EA	2,100.00	12,600
CTE drainage	1	EA	4,000.00	4,000
Cut & patch existing parking lot	431	LF	50.00	21,550
Drain man hole	3	EA	4,100.00	12,300
Head wall	1	LS	6,500.00	6,500
STC 6000	1	EA	60,000.00	60,000
STC 3600	1	EA	30,000.00	30,000

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
STC 450i	2	EA	11,500.00	23,000
Phase 2 - Grading & Drainage:				
12" HDPE	154	LF	76.00	11,704
Catch Basin	2	EA	4,100.00	8,200
Temp drain line	282	LF	100.00	28,200
Phase 3 ( per revised plane 4 /17/19):				
12" HDPE	262	LF	76.00	19,912
15" HDPE	665	LF	84.00	55,860
18" HDPE	152	LF	94.00	14,288
24" HDPE	305	LF	145.00	44,225
30" HDPE	537	LF	182.00	97,734
Catch Basin	10	EA	4,100.00	41,000
CB Conversion	1	EA	1,200.00	1,200
Drain Manhole	9	EA	4,100.00	36,900
Head Wall	1	EA	7,500.00	7,500
Outfall wier construction	1	LS	5,000.00	5,000
Infiltration field	1,292	SF	25.00	32,300
Fuel Distribution:				
Phase 2 - Grading & Drainage:				
Gas trench	311	LF	48.00	14,928
Gas Pipe		By utility		
Service Meter Pad	1	EA	2,500.00	2,500
Electrical Distribution:				
Light Pole base - 12' Precast	37	EA	1,350.00	49,950
Temporary Electrical Service	1	LS	75,800.00	75,800
				-----
				1,015,510

PROJECT: Fuller Middle School  
 LOCATION: Framingham, MA  
 CLIENT: SMMA Architects  
 DATE: 26-Sep-19

NO. OF SQ. FT.: 136,600  
 COST PER SQ. FT.: 53.73

No.: 18020

**EARLY SITE PACKAGE #2**

SUMMARY	DIVISION TOTAL	PERCENT OF PROJECT	COST PER SF
<b>DIVISION 03 - CONCRETE</b>			
033000 CAST IN PLACE CONCRETE	#####	46%	24.48
<b>DIVISION 05 - METALS</b>			
051000 STRUCTURAL METAL FRAMING	#####	54%	29.06
<b>DIVISION 07 - THERMAL &amp; MOISTURE PROTECTION</b>			
071000 DAMPPROOFING & WATERPROOFING	26,170	0%	0.19
	-----		
DIRECT COST	#####	100%	53.73

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

## DIVISION 03 - CONCRETE

## 033000 CAST IN PLACE CONCRETE

## Foundations:

Column Footing - (F 3 thru F 12 @ 135 ea):

4000 psi, NW, (incl. placement)	454	CY	205.00	93,070
Formwork	6,300	SFCA	9.50	59,850
Rebar	45,400	LBS	1.22	55,388

*\*unit cost \$458.83*

Perim Wall Footing 1' x 3/4' ( 1,578 LF ):

4000 psi, NW, (incl. placement)	180	CY	208.00	37,440
Formwork	3,200	SFCA	8.10	25,920
Rebar	9,000	LBS	1.22	10,980

*\*unit cost \$413.00*

Foundation Wall 16" thick x height varies ( 1,962 lf):

4000 psi, NW, (incl. placement)	442	CY	215.00	95,030
Formwork - 4' or less	8,808	SFCA	14.00	123,312
Formwork - 4' Aud/Gym	4,960	SFCA	14.00	69,440
Formwork - 15'	3,120	SFCA	20.00	62,400
Brick Shelf	1,962	LF	14.50	28,449
Reinforcing steel	66,300	LBS	1.22	80,886

*\*unit cost \$1,039.63*

Auditorium Interior Foundations - Stage front:

Wall footing	32	CY	350.00	11,200
12" Knee wall	27	CY	850.00	22,950

## Loading Dock:

Wall footing		inc. above		
Foundation wall	36	CY	975.00	35,100

## Misc. Foundations:

CMU Footing - aud/gym	28	CY	385.00	10,780
#1 - #5 Grade Beam	42	CY	675.00	28,350
12" Elevator mat	6	CY	650.00	3,900
Elev sump pit	1	EA	900.00	900
12" Elevator pit wall -5'D	7	CY	900.00	6,300
Interior Mechanical pads - allow	1	LS	5,000.00	5,000
Concrete Pilaster	28	CY	1,100.00	30,800
Setting Anchor Bolts and Grout	132	EA	310.00	40,920

*\*Includes Section 031000 - 033500*

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
<b>Band Shell Foundation:</b>				
Wall Footing 1' x 5'	6	CY	800.00	4,800
16" Radial Found wall	9	CY	1,300.00	11,700
<b>Slab on Grade:</b>				
5" Slab on Grade - Typ:				
3,500 psi, NW, (incl. placement)	988	CY	228.00	225,264
6x6 W2.9 X W2.9	64,048	SF	1.80	115,286
Control Joint	4,300	LF	2.60	11,180
15 Mil poly vapor barrier (2/A100)		w/072600		
Trowel Finish	64,048	SF	2.10	134,501
*unit cost \$7.59				
<b>Misc. Slabs and Concrete:</b>				
Premium Stepped/sloped slab	3,460	SF	8.00	27,680
Ext. 5" Loading Dock	1,125	SF	9.00	10,125
Ext. Loading Dock Stair Structure	1	FLT	7,500.00	7,500
Gyp cement underlayment(spec 035413)		w/C3020		
<b>Floor Construction:</b>				
3 1/4" LW Deck fill - typ floor	68,431	SF	9.80	670,624
3 1/4" LW Deck fill - stage plenum (7/A)	570	SF	10.00	5,700
<b>Roof Construction:</b>				
3 1/4" LW Deck fill :				
R 6.25 3" x 18 Ga. Comp Deck- Typ	3,641	SF	8.70	31,677
3 1/4" LW Deck fill :				
R 5.5 3" x 18 Ga. Comp Deck- Typ	29,586	SF	8.70	257,398
<b>Roof top 1'W x 2'H Concrete Curb @:</b>				
Mech RTU unit	618	LF	92.00	56,856
Misc Equip curbs	1	LS	9,998.00	9,998
<b>Stair Construction:</b>				
Conc stair pan fill :				
Metal pan stair treads and risers	1,278	LFR	22.00	28,116
Metal pan landing	472	SF	18.00	8,496
Aud cast stair @ grade (4 ft)	48	LFT	145.00	6,960
<b>Floor Finishes:</b>				
PC Power Troweled Concrete Floor Finish::				
Auditorium	3,788	SF	5.00	18,940
Makerspace ( 1 EA)	1,972	SF	5.00	9,860

SITWORK:

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Pedestrian Paving:				
Site Pavement:				
Entry Stoop	200	SF	22.00	4,400
Concrete sidewalk	21,127	SF	11.00	232,397
Plaza Paving	1,760	SF	20.00	35,200
Site Development:				
Pavilion Amphitheater Step:				
Amphitheater stair foundation	5	CY	1,100.00	5,500
Amphitheater stair tread (radial)	385	LF	190.00	73,150
Ramp and Planter Walls:				
Wall Footing	25	CY	475.00	11,875
12" Foundation Wall	82	CY	1,600.00	131,200
Ramp Slab	510	SF	15.00	7,650
Sandblast finish	1	LS	10,000.00	10,000
Site Stair:				
Site stair foundation	38	CY	1,100.00	41,800
Site stair tread	251	LF	110.00	27,610
Main stair tread	193	LF	110.00	21,230
Bike Conc Pad	426	SF	25.93	11,046
Foundations:				
2" Rigid found. insul w/ 1/2" drain bed -	1,360	SF	6.00	8,160
2" Rigid found. insul - frost wall	6,884	SF	3.20	22,029
Slab on Grade:				
Stegro vapor barrier (15 mil)	64,048	SF	1.71	109,522
				-----
				3,343,795

## DIVISION 05 - METALS

## 051000 STRUCTURAL METAL FRAMING

Floor Construction:				
Wide Flange - beam	210.52	TONS	3,800.00	799,976
HSS Beam	36.2	TONS	3,900.00	141,180
HSS Brace Frame	46.7	TONS	4,200.00	196,140
Wide Flange- Column	10.7	TONS	3,550.00	37,985
HSS Column	88.3	TONS	3,900.00	344,370
Bolted Ledger Angle	1.5	TONS	3,550.00	5,325
Relieving angle (S500)	1,043	LF	185.00	192,955



DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Wide flange - stage front	0.5	TON	3,700.00	1,850
4" x 4" x 1/8" Bolted angle at found - all	250	LF	65.00	16,250
Hilti bolt conn	74	EA	128.00	9,472
Moment Connection	194	EA	1,300.00	252,200
Shear stud ( 10/100sf)	16,200	EA	5.25	85,050
Atrium coped Beam Detailing #4/S500	1	LS	49,402.00	49,402
Roof Construction:				
Wide Flange - beam	200.8	TONS	3,800.00	763,040
HSS Beam	61.0	TONS	4,100.00	250,100
DLH Bar Joist	47.84	TONS	3,657.00	174,951
HD Galv pipe/ HSS Roof Screen	4.70	TONS	5,200.00	24,440
HD Galv HSS Entrance Canopy	2.60	TONS	6,000.00	15,600
HSS Brace Frame	w/ floor construction			
Wide Flange- Column	w/ floor construction			
HSS Column	w/ floor construction			
Bolted Ledger Angle	3	TONS	3,550.00	10,650
Hilti bolt conn	140	EA	128.00	17,920
Moment connection	38	EA	750.00	28,500
Galv Roof Dunnage:				
CH/WF	9	TONS	4,500.00	40,500
HSS post	1	TONS	4,500.00	4,140
Angle brace	500	LBS	4.00	2,000
Site Development:				
HD Color Galv HSS/ C Channel Band Sh	3.40	TONS	10,000.00	34,000
Floor Construction:				
3" x 18 Ga. Comp Deck- Typ	68,431	SF	3.40	232,665
3" x 18 Ga. Comp Deck- stage	570	SF	3.60	2,052
Roof Construction:				
R 1.5 1 1/2" x 20Ga Roof deck	765	SF	2.80	2,142
R3 3" X 18 Ga. Typical Roof Deck	13,702	SF	3.00	41,106
R 6.25 3" x 18 Ga. Comp Deck- Typ	3,641	SF	3.18	11,578
R 5.5 3" x 18 Ga. Comp Deck- Typ	29,586	SF	3.18	94,083
R 1.5A 1 1/2" Acoustical Roof Deck - gy	8,835	SF	7.25	64,054
R3C 3" Roof Deck - aud (acoustical dele	7,563	SF	3.15	23,823
				-----
				3,969,500

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
DIVISION 07 - THERMAL & MOISTURE PROTECTION				
071000 DAMPPROOFING & WATERPROOFING				
Bid Page #2 Foundation Waterproofing	1	LS	26,170.00	26,170
				-----
				26,170

PROJECT: Fuller Middle School  
 LOCATION: Framingham, MA  
 CLIENT: SMMA Architects  
 DATE: 09-Oct-19

NO. OF SQ. FT.: 136,600  
 COST PER SQ. FT.: \$324.15

SUMMARY

No.: 18020

	DIVISION TOTAL	PERCENT OF PROJECT	COST PER SF
<b>DIVISION 02 - EXISTING CONDITIONS</b>			
024117 BUILDING DEMOLITION	75,000	0%	0.55
024180 ASBESTOS ABATEMENT	0	0%	0.00
<b>DIVISION 03 - CONCRETE</b>			
033000 CAST IN PLACE CONCRETE	0	0%	0.00
<b>DIVISION 04 - MASONRY</b>			
042000 UNIT MASONRY*	2,296,962	5%	16.82
<b>DIVISION 05 - METALS</b>			
051200 STRUCTURAL STEEL FRAMING	0	0%	0.00
053000 METAL DECKING	0	0%	0.00
054000 COLD FORMED METAL FRAMING	0	0%	0.00
055000 METAL FABRICATIONS*	1,162,710	3%	8.51
<b>DIVISION 06 - WOOD, PLASTICS &amp; COMPOSITES</b>			
061000 ROUGH CARPENTRY	0	0%	0.00
062000 FINISH CARPENTRY	2,078,706	5%	15.22
<b>DIVISION 07 - THERMAL &amp; MOISTURE PROTECTION</b>			
071000 DAMPPROOF., WATERPROOF. & CAULKING*	761,028	2%	5.57
070002 ROOFING AND FLASHING*	1,541,922	3%	11.29
072100 THERMAL INSULATION	0	0%	0.00
072600 VAPOR RETARDERS	0	0%	0.00
074214 EXTERIOR WALL PANELS	1,155,569	3%	8.46
078100 FIREPROOFING	381,208	1%	2.79
078400 FIRESTOPPING	0	0%	0.00
079513 EXPANSION JOINTS (NO SPEC)	40,000	0%	0.29

	DIVISION TOTAL	PERCENT OF PROJECT	COST PER SF
<b>DIVISION 08 - OPENINGS</b>			
080001 METAL WINDOWS*	2,270,752	5%	16.62
080002 GLASS AND GLAZING*	882,247	2%	6.46
081113 HOLLOW METAL DOORS & FRAMES	136,485	0%	1.00
081416 FLUSH WOOD DOORS	159,225	0%	1.17
083100 ACCESS DOORS AND PANELS	30,000	0%	0.22
083323 SPECIAL DOORS	80,793	0%	0.59
084513 STRUCT-POLYCARBONATE PNL ASSEMB. & SKYLIG	14,350	0%	0.11
087100 DOOR HARDWARE	366,760	1%	2.68
089000 LOUVERS & VENTS	84,000	0%	0.61
<b>DIVISION 09 - FINISHES</b>			
090003 TILE*	229,896	1%	1.68
090006 RESILIENT FLOORING*	868,464	2%	6.36
090009 PAINTING*	547,406	1%	4.01
092116 GYPSUM WALLBOARD ASSEMBLIES	5,724,632	13%	41.91
095100 ACOUSTICAL CEILINGS*	932,456	2%	6.83
096446 WOOD & ATHLETIC FLOORING	225,065	1%	1.65
096712 RESINOUS FLOORING	109,314	0%	0.80
096800 CARPET	8,456	0%	0.06
097217 DIGITAL IMAGE WALL COVERINGS	0	0%	0.00
097233 DRY-ERASE WALL COVERING	0	0%	0.00
097733 SANITARY WALL PANELS	0	0%	0.00
098100 ACOUSTICAL INSULATION	0	0%	0.00
098400 ACOUSTIC ROOM COMPONENTS	0	0%	0.00
098415 WOOD FIBER ACOUSTICAL PANELS	0	0%	0.00
<b>DIVISION 10 - SPECIALTIES</b>			
101100 MARKERBOARDS & TACKBOARDS	180,800	0%	1.32
101400 SIGNAGE	68,144	0%	0.50
102113 TOILET COMPARTMENTS	55,590	0%	0.41
102600 WALL AND DOOR PROTECTION	10,000	0%	0.07
102813 TOILET ACCESSORIES	35,127	0%	0.26
104000 SAFETY SPECIALTIES	22,800	0%	0.17
107113 EXTERIOR SUN CONTOL DEVICES	0	0%	0.00
109000 MISCELLANEOUS SPECIALTIES	710,940	2%	5.20
<b>DIVISION 11 - EQUIPMENT</b>			
113100 RESIDENTIAL APPLIANCES	10,350	0%	0.08
114000 FOOD SERVICE EQUIPMENT	415,270	1%	3.04
115213 PROJECTION SCREENS	65,000	0%	0.48
116143 THEATRICAL EQUIPMENT(No Spec)	866,921	2%	6.35
116600 ATHLETIC & SPORTS EQUIPMENT	102,621	0%	0.75
119000 MISC. EQUIPMENT	32,500	0%	0.24
	DIVISION TOTAL	PERCENT OF PROJECT	COST PER SF

<b>DIVISION 12 - FURNISHINGS</b>			
122400 WINDOW SHADES	136,136	0%	1.00
122414 MOTORIZED WINDOW SHADES	0	0%	0.00
123553 CASEWORK	323,013	1%	2.36
124813 FLOOR MATS	7,920	0%	0.06
124816 ENTRANCE GRILLES & FRAMES	0	0%	0.00
126613 TELESCOPING BLEACHERS	81,250	0%	0.59
129000 MISCELLANEOUS FURNISHING	106,445	0%	0.78
<b>DIVISION 13 - SPECIAL CONSTRUCTION</b>			
130000 SPECIAL CONSTRUCTION	0	0%	0.00
<b>DIVISION 14 - CONVEYING EQUIPMENT</b>			
140001 ELEVATORS*	212,000	0%	1.55
<b>DIVISION 21 - FIRE SUPPRESSION</b>			
210001 FIRE SUPPRESSION*	893,565	2%	6.54
<b>DIVISION 22 - PLUMBING</b>			
220001 PLUMBING*	2,150,852	5%	15.75
<b>DIVISION 23 - HVAC</b>			
230001 HVAC*	8,247,841	19%	60.38
<b>DIVISION 26 - ELECTRICAL</b>			
260001 ELECTRICAL*	6,000,049	14%	43.92
<b>DIVISION 31 - EARTHWORK</b>			
310000 EARTHWORK	0	0%	0.00
311000 SITE PREPARATION & CLEARING	0	0%	0.00
<b>DIVISION 32 - EXTERIOR IMPROVEMENTS</b>			
321000 PAVEMENT, CURBING & EDGING	0	0%	0.00
323100 SITE IMPROVEMENTS	271,675	1%	1.99
328000 IRRIGATION	165,792	0%	1.21
329000 LANDSCAPING	942,635	2%	6.90
<b>DIVISION 33 - UTILITIES</b>			
330000 UTILITIES	0	0%	0.00
	-----		
DIRECT COST	44,278,640	100%	324.15

\*DENOTES FILED SUB-BID

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
DIVISION 02 - EXISTING CONDITIONS				
024117 BUILDING DEMOLITION	SEE SUMMARY			
Staged Floor at Aud	1	LS	75,000.00	75,000
				-----
				75,000
024180 ASBESTOS ABATEMENT	SEE SUMMARY			
				-----
				0
DIVISION 03 - CONCRETE				
033000 CAST IN PLACE CONCRETE	SEE BID PACKAGE #2			
				-----
				0
DIVISION 04 - MASONRY				
042000 UNIT MASONRY*				
Exterior Walls:				
Backup :				
Gym 12" CMU Back-up - Exposed	7,497	SF	25.50	191,174
Aud 12" CMU Back-up - Exposed	7,342	SF	25.50	187,221
Int GF finish premium	7,342	SF	5.50	40,381
*A462 GF is not noted				
Masonry Veneer Building ( QTY Noted):				
4x4x12 Scored brick veneer	6,252	SF	34.00	212,568
4x8x8 Scored brick veneer	6,722	SF	36.00	241,992
4x8x16 Scored ground face CMU	23,500	SF	31.00	728,500
4x4x12 Scored ground face CMU	3,512	SF	33.50	117,652
3" Mineral fiber insul @ masonry	43,331	SF	3.72	161,191
A501 Premium:				
Sill brick		w/Unit Cost		
Lip brick		w/Unit Cost		
Temporary shoring at CMU Bearing	1	LS	100,000.00	100,000
SS Masonry flashing	1	LS	35,000.00	35,000

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Staging		inc. w/ unit		
Precast Concrete:				
Misc. BLDG precast veneer		N/A		
*Site planters are included w/ site improvements				
2nd Floor Main Entry Terrace:				
(3/ A316)3'6"H Brick Partial HT wall-comj	26	LF	440.00	11,440
(3/ A316) Wall Cap	26	LF	175.00	4,550
Partitions:				
Interior 12" CMU Partition:				
Gym - 28'	4,480	SF	29.00	129,920
Auditorium - 28'	2,660	SF	29.00	77,140
Auditorium - 14'	420	SF	26.00	10,920
GF CMU - Aud. Only	2,660	SF	4.50	11,970
Acoustical Block - Premium	1,000	SF	6.50	6,500
Stage front CMU pier (5 loc)	22.5	SF	55.00	1,238
Int GF finish premium	5,740	SF	4.50	25,830
CMU Partition (Gym & Aud):				
Bond beam	37	LF	48.00	1,776
				-----
				2,296,962

DIVISION 05 - METALS

051200 STRUCTURAL STEEL FRAMING

SEE BID PACKAGE #2

-----  
0

053000 METAL DECKING

SEE BID PACKAGE #2

-----  
0

054000 COLD FORMED METAL FRAMING

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
*w/ gypsum drywall				----- 0
055000 METAL FABRICATIONS*				
Elevators:				
Elev. framing	1	EA	3,000.00	3,000
Elev. pit ladder	1	EA	1,537.00	1,537
Elev. sump grate	1	EA	1,500.00	1,500
Exterior Walls:				
42" Perf Metal Guardrail:				
LVL 2 entry	11	LF	350.00	3,850
LVL 2 emerg. egress	42	LF	350.00	14,700
LVL 2 emerg. egress stair wall rail	8	LF	145.00	1,160
Galv, loose lintel (per 5600-604)	133	LF	36.00	4,788
Misc metals @ ext wall - allow	1	LS	25,000.00	25,000
Reliving angle		W /Structural		
Bolted galv. sill angle @ fnd		W /Structural		
Support clip @ skylight curb (spec)	567	LF	125.00	70,875
Exterior Doors:				
OH door frame @:				
Tech-Makerspace	1	EA	500.00	500
Special Doors:				
LVL 1 Corridor Security Gate- sgl ( 7' x7'1	2	EA	7,000.00	14,000
Partitions:				
Folding Panel partition Support (18/A620):				
Typ classroom (13 EA)	208	LF w/ pacakge #2		
Music classroom (DBL panel 1 EA)	19	LF w/ pacakge #2		
SPED suite (3 EA)	120	LF w/ pacakge #2		
Folding Grille Support @:				
Learning common	46	LF	200.00	9,200
Sgl custom security gate (7'w)	2	EA	4,000.00	8,000
Coiling Grille Support @:				
Servery	35	LF	100.00	3,500
Main office(1 EA)	21	LF	100.00	2,100
CMU Partition (Gym & Aud):				
CMU clip @ 4' oc	70	EA	115.00	8,050



### 2.3.7 Prequalification Requirements

Electrical Trade Contractors were prequalified for the Early Site Package on May 6, 2019. The listing of the prequalified trade contractors is appended to the end of this section.

Waterproofing, Dampproofing and Caulking Trade Contractors were prequalified for the Early Concrete and Steel Package on August 5, 2019. The listing of the prequalified trade contractors is appended to the end of this section.

Masonry Trade Contractors were prequalified for the Early Masonry Package on September 16, 2019. The listing of the prequalified trade contractors is appended to the end of this section.

The full project trade contractor prequalification process is underway. Statements of Qualification were submitted on October 2, 2019 and are currently being reviewed by the Trade Contractor Prequalification Committee, who will bring their recommendation to the School Building Committee at the November 4, 2019 meeting for approval.

The list of submitted Statements of Qualifications is appended to the end of this section.



**New Fuller Middle School  
List of Prequalified Trade Contractors  
Electrical Work for Early Site Package  
April 29, 2019**

<b>Trade</b>	<b>Company</b>
<b>Electrical</b>	<b>Annese Electrical</b>
<b>Electrical</b>	<b>Brite-Lite Electrical Co.</b>
<b>Electrical</b>	<b>Energy Electric Co., Inc.</b>
<b>Electrical</b>	<b>Jupiter Electric</b>
<b>Electrical</b>	<b>Systems Contracting</b>
<b>Electrical</b>	<b>Wayne J. Griffin Electric, Inc.</b>



**New Fuller Middle School  
List of Prequalified Trade Contractors  
Waterproofing, Dampproofing and Caulking Work  
for Early Concrete and Steel Package  
August 6, 2019**

Trade	Company
<b>Waterproofing, Dampproofing and Caulking</b>	<b>Acme Waterproofing Co., Inc.</b>
<b>Waterproofing, Dampproofing and Caulking</b>	<b>Beacon Waterproofing &amp; Restoration</b>
<b>Waterproofing, Dampproofing and Caulking</b>	<b>Chapman Waterproofing &amp; Caulking</b>
<b>Waterproofing, Dampproofing and Caulking</b>	<b>Folan Waterproofing &amp; Construction Co., Inc.</b>
<b>Waterproofing, Dampproofing and Caulking</b>	<b>P.J. Spillane Company</b>
<b>Waterproofing, Dampproofing and Caulking</b>	<b>Superior Waterproofing &amp; Caulking</b>
<b>Waterproofing, Dampproofing and Caulking</b>	<b>The Waterproofing Company</b>



**New Fuller Middle School  
List of Prequalified Trade Contractors  
Masonry Work for Early Masonry Package  
September 10, 2019**

<b>Trade</b>	<b>Company</b>
<b>Masonry</b>	<b>Costa Brothers Masonry</b>
<b>Masonry</b>	<b>Empire Masonry Corp.</b>
<b>Masonry</b>	<b>Fernandes Masonry</b>
<b>Masonry</b>	<b>Lighthouse Masonry</b>
<b>Masonry</b>	<b>Marmelo Bros. Construction</b>
<b>Masonry</b>	<b>Sullivan and Narey Construction Company, Inc.</b>





**New Fuller Middle School  
List of Trade Contractor Submitted Statements of Qualification  
100% Construction Documents Package  
October 2, 2019**

Trade	Company
<p align="center"><b>MISCELLANEOUS &amp; ORNAMENTAL IRON</b></p>	<p>Avid Iron Works EDM Construction North Shore Steel Roman Iron Works, Inc. SMJ Metal Company, Inc. The Berlin Steel Construction Company United Steel Inc. V&amp;G Iron Works, Inc.</p>
<p align="center"><b>WATERPROOFING, DAMPPROOFING &amp; CAULKING</b></p>	<p>ACME Waterproofing Co., Inc. Beacon Waterproofing &amp; Restoration Inc. Chapman Waterproofing Company East Coast Air Barrier Folan Waterproofing &amp; Construction Co., Inc. Gleeson Powers, Inc. P.J. Spillane Co., Inc. Superior Caulking &amp; Waterproofing Co., Inc. The Waterproofing Company LLC</p>
<p align="center"><b>ROOFING</b></p>	<p>Capeway Roofing Systems, Inc. Feeley McAnespie, Inc. Gibson Roofs, Inc. Greenwood Industries J.D. Rivet &amp; Co., Inc. John F. Shea Co., Inc. Rockwell Roofing, Inc. Silktown Roofing Stanley Roofing Company, Inc Titan Roofing Inc.</p>
<p align="center"><b>METAL WINDOWS</b></p>	<p>A &amp; A Window Products, Inc Chandler Architectural Products, Inc. Cherry Hill Glass Co., Inc. GVW, INC Kapiloff's Glass, Inc. Lambrian Construction Corporation Lizotte Glass, Inc. Lockheed Window Corp. R&amp;R Window Contractors Inc</p>
<p align="center"><b>GLASS &amp; GLAZING</b></p>	<p>A &amp; A Window Products, Inc Aluminum &amp; Glass Concepts, Inc. Chandler Architectural Products, Inc. Cherry Hill Glass Co., Inc. GVW, INC Kapiloff's Glass, Inc. Lizotte Glass, Inc. Lockheed Window Corp. R&amp;R Window Contractors Inc</p>

**New Fuller Middle School**  
**List of Trade Contractor Submitted Statements of Qualification**  
**100% Construction Documents Package**  
**October 2, 2019**

*Page 2 of 3*

<b>Trade</b>	<b>Company</b>
<b>TILE</b>	Ayotte & King For Tile, Inc., Capital Carpet & Flooring Specialists, Inc. High Point Interiors, Inc. Joseph Cohn & Son M. Frank Higgins & Co., Inc. Pavilion Floors, Inc.
<b>ACOUSTICAL CEILING</b>	American Contractors Corp. Central Ceilings, Inc. Conn Acoustics, Inc. H. Carr & Sons, Inc. K & K Acoustical Ceilings Inc. The Cheviot Corporation
<b>RESILIENT FLOORING</b>	Ayotte & King For Tile, Inc. Capital Carpet & Flooring Specialists, Inc. CJM Services, Inc. M. Frank Higgins & Co., Inc. Pavilion Floors, Inc.
<b>PAINTING</b>	Bello Painting Co Inc Color Concepts Inc. Dandis Contracting Inc Homer Contracting LLC John W. Egan Co., Inc. King Painting Inc O'Byrne Painting & Contracting Inc. New Generation Painting, Inc.
<b>ELEVATORS</b>	Eagle Elevator Company Delta Beckwith Elevators
<b>FIRE PROTECTION</b>	Carlisle Engineering, Inc. City Point Fire Protection Cogswell Sprinkler Co., Inc. Covenant Fire Protection, Inc. Encore Fire Protection Johnson Controls Rustic Fire Protection, Inc. Wolverine Fire Protection Co. Xcel Fire Protection Inc. Yankee Sprinkler Co.
<b>PLUMBING</b>	Araujo Bros. Plumbing and Heating Charles M. Moran Plumbing & Heating E. Amanti & Sons, Inc. Grasseschi Plumbing & Heating, Inc. Harold Brothers N.B. Kenney Company, Inc. Patrick J. Kennedy & Son, Inc. William F. Lynch Co., Inc.

**New Fuller Middle School**  
**List of Trade Contractor Submitted Statements of Qualification**  
**100% Construction Documents Package**  
**October 2, 2019**

*Page 3 of 3*

<b>Trade</b>	<b>Company</b>
<b>HVAC</b>	CAM HVAC & Construction Inc. E. Amanti & Sons, Inc. General Mechanical Contractors, Inc. Harold Brothers J.F. White KMD-Bonner Mechanical N.B. Kenney Company, Inc. Patrick J. Kennedy & Son, Inc. Veterans Development Corporation Inc. William F. Lynch Co., Inc.
<b>ELECTRICAL</b>	Annese Electrical Services LeVangie Electric Co., Inc. Lynnwell Associates, Inc. Systems Contracting Inc. Wayne J Griffin Electric, Inc.



## 6C.3 Designer Deliverables

### 3.1 General Requirements

#### 3.1.1 Work Plan

Please reference the attached updated Fuller Middle School Work Plan.



Fuller Middle School  
Work Plan

Phase	Responsibility	Description of Key Tasks	Deliverable	Submittal Date	Status
	McPhail	Phase 1 Environmental Report	Forward copy of report to Designer	9/10/2018	Complete
	McPhail	Geotechnical Site Evaluation	Preliminary Geotechnical Report	9/10/2018	Complete
	JLA, FPS	Final Design Program	Excel spreadsheet and architect's signature	9/10/2018	Complete
	Vanasse	Traffic Study	Traffic Study	9/10/2018	Complete
	RSE, JLA, GGD	Building Description Narratives	Architectural, Sustainable Design, MEP, Fire Protection, Structural, and Technology	9/10/2018	Complete
	JLA	LEED Scorecard	LEED Scorecard and Potential rating	9/10/2018	Complete
	JLA GGD	Utility Analysis	Narrative	9/10/2018	Complete
	JLA, FPS, SMMA	DESE Approval	Plans and Program forwarded to SMMA and WPS Working Group. WPS' Narrative describing SPED Program Spaces	9/10/2018	Complete
	JLA	Document Updates: Plans, Site Plan, Exterior Elevations, Model Images, Specifications	Plans and Specs to Miyakoda and SMMA for Cost Estimate	9/10/2018	Complete
	JLA, SMMA	Site Development Plans and Analysis	Schematic Site Plan, and Surveys	9/10/2018	Complete
	JLA	Specifications	Outline Specifications	9/10/2018	Complete
	JLA, FPS	Schematic Building Floor Plans	Overall 1/8" Building Floor Plans	9/10/2018	Complete
	JLA	Schematic Roof Plans	Overall and 1/8" Roof Plans	9/10/2018	Complete
	JLA	Schematic Exterior Elevations	Overall and 1/8" exterior Elevations	9/10/2018	Complete
	JLA	Massing Study	Images of Exterior Design	9/10/2018	Complete
	SMMA	Preliminary Project Cash Flow	MSBA Formatted Cash Flow Projections	9/10/2018	Complete
	SMMA	Project Schedule	OPM Project Schedule	9/10/2018	Complete
	Miyakoda	Cost Estimate	Uniformat Detailed Estimate 100% SD	8/24/2018	Complete
	AM Fogarty	Cost Estimate	Uniformat Detailed Estimate 100% SD	8/24/2018	Complete
	Miyakoda, SMMA	Reconcile Cost Estimate	Reconciled Cost Estimates	9/10/2018	Complete
	SMMA	Project Budget Cost	Excel Spreadsheet 3011	9/10/2018	Complete
<b>SUBMITTALS</b>					
	SMMA	Submit Documents for DESE Review	Cover Letter, Space Summary, Plans	9/12/2018	Complete
	JLA	Submit Documents for Cost Estimates	Plans and Specifications	8/7/2018	Complete
	JLA	Submit Documents to SMMA	MSBA Formatted PS&B Submission	9/10/2018	Complete
	SMMA	Submit Documents to MSBA	Final PS&B Submittal	9/12/2018	Complete

Project Scope and Budget

Phase	Responsibility	Description of Key Tasks	Deliverable	Submittal Date	Status
	RSE	Geotechnical Site Evaluation	Updated Geotechnical Report	5/8/2019	Complete
	JLA	Program Comparison Analysis	Letter from Architect outlining differences from PS&B Space Summary Submittal	5/8/2019	Complete

<b>Design Development Documents</b>					
<b>100% Site Enabling Package</b>					
JLA	Program Space Summary	Space Summary Document signed by Architect	5/8/2019	Complete	
CDW	Site Related Code Analysis: Permitting and Zoning	Detailed Review of Framingham's Regulatory Requirements	5/10/2019	Complete	
SMMA	Updated Schedule	Schedule	5/8/2019	Complete	
Design Team	Design Development Documents	PDF Files	5/8/2019	Complete	
Design Team	Design Development Specification	PDF Files	5/8/2019	Complete	
Miyakoda	Design Development Cost Estimate	Detailed Cost Estimate	5/8/2019	Complete	
Miyakoda, Fogarty, Consigli	Reconcile Cost Estimate	Reconciled Estimates	5/8/2019	Complete	
SMMA	Value Engineering Report	VE Report	5/8/2019	Complete	
<b>SUBMITTALS</b>					
Design team	Design Development Documents	Drawings, Specifications, Binder	5/8/2019	Complete	
Design team	100% Site Enabling Package	Drawings & Specifications	5/8/2019	Complete	
SMMA	Submit Documents to MSBA	DD Submittal	5/10/2019	Complete	

<b>Phase</b>	<b>Responsibility</b>	<b>Description of Key Tasks</b>	<b>Deliverable</b>	<b>Submittal Date</b>	<b>Status</b>
<b>60% Construction Documents</b>					
<b>100% Structural Package</b>					
Howe Engineers SMMA /JLA	Site Related Code Analysis: Permitting Approval of Proprietary Items	Detailed Review of the Regulatory Requirements	8/7/2019	Complete	
JLA	Program Comparison Analysis	Letter from Architect outlining differences from PS&B Space Summary Submittal	6/5/2019	Complete	
JLA	Program Space Summary	Space Summary Document signed by Architect	8/7/2019	Complete	
JLA	Project Design Compliance	Letter from Architect verifying compliance of design with PS&B	8/7/2019	Complete	
SMMA	Updated Schedule	Schedule	8/7/2019	Complete	
Design Team	60% Construction Documents	PDF Files	8/7/2019	Complete	
Design Team	60% Construction Specification	PDF Files	8/7/2019	Complete	
Miyakoda	60% Cost Estimate	Detailed Cost Estimate	7/30/2019	Complete	
Miyakoda, Fogarty, Consigli	Reconcile Cost Estimate	Meeting	7/30/2019	Complete	
SMMA	Value Engineering Report	VE Report	8/2/2019	Complete	
<b>SUBMITTALS</b>					
Design team	60% Construction Documents	Drawings, Specifications, Binder	8/7/2019	Complete	
Design team	100% Structural Package	Drawings & Specifications	8/7/2019	Complete	
SMMA	Submit Documents to MSBA	60% CD Submittal	8/9/2019	Complete	

<b>Phase</b>	<b>Responsibility</b>	<b>Description of Key Tasks</b>	<b>Deliverable</b>	<b>Submittal Date</b>	<b>Status</b>
--------------	-----------------------	---------------------------------	--------------------	-----------------------	---------------



90% and 100% Construction Documents 100% Masonry Package			Space Summary Document signed and certified by Architect	10/18/2019	Complete
JLA	Program Space Summary		Review Questions and responses from design team	10/18/2019	Complete
Cx Agent	Cx Review		Letter from Architect and Code Review Consultant	10/18/2019	Complete
JLA, GGD	Building Code and Fire Safety Review				Complete
JLA	Utility Certification & Board Approval		Letter from Architect stating review meetings and approvals obtained from City Departments	10/18/2019	Complete
JLA	Program Comparison Analysis		Letter from Architect outlining differences from 60% Space Summary Submittal	10/18/2019	Complete
KMA	Site and Building ADA MAAB Review		Letter of Compliance from the Accessibility Consultant. Design Team's responses to the detailed Review Document provided by Accessibility Consultant	10/18/2019	Complete
JLA	Testings and Permits compliance		Letter from Architect stating all testing and permits have been obtained for the project	10/18/2019	Complete
JLA, GGD	Compliance with Energy Code		Com CHECK 3.8.1 2009 IEC Report	10/18/2019	Complete
RSE	Structural Design Calculations		Structural Design Calculation Report	10/18/2019	Complete
JLA	90% Construction Documents		Documents available for review by design team and independent estimator	10/18/2019	Complete
Design Team	90% Construction Documents		Bound AutoCAD files	10/18/2019	Complete
Design Team	90% Construction Specification		PDF File of Specification	10/18/2019	Complete
JLA RSE	100% Masonry Package		Drawings & Specifications	10/18/2019	Complete
JLA	Interior Materials Color Board		Color Board for FPS review	10/18/2019	Complete
Design Team	Designer review responses to the 60% MSBA review comments		Letters of compliance from Design Team	10/18/2019	Complete
Miyakoda	Final Designer Cost Estimate		Cost Estimates	10/4/2019	Complete
Fogarty	Final OPM Cost Estimate		Cost Estimates	10/4/2019	Complete
SMMA	Cost Estimate Comparison Spreadsheet		Cost Estimate Comparison Spreadsheet	10/4/2019	Complete
Miyakoda, Fogarty, Consigli	Reconcile Cost Estimate		Meeting	10/1/2019	Complete
JLA, SMMA	Independent Structural Peer Review		Letter of compliance to Building Code	9/30/2019	Complete
SMMA	Value Engineering Report		VE Report	10/4/2019	Complete
<b>SUBMITTALS</b>					
Design Team	90% Construction Documents to MSBA		Drawings & Specifications	10/18/2019	Complete
Design Team	100% Construction Documents to MSBA		Drawings & Specifications	11/22/2019	Complete



### 3.1.2 Basis of Design Narratives

#### *Architecture*

The new Fuller School's design builds on the District's Educational Program, first and foremost, by embodying the District's stated commitment to a 21st century STEAM, student centered approach to education, a commitment which is already been acted upon through advanced teaching and learning programs at the elementary school level in preparation for this project. STEAM compatible educational environments are achieved through the creation of student driven, problem-based, "hands-on project space" at three different scales within the proposed floor plan. These spaces are provided together with a high degree of visual and functional connectedness both in plan and in section.






The new school will be three-stories, oriented for energy efficiency and sustainability purposes to the south and to the north. The massing utilizes a compact footprint in order to conserve site space and allow for the creation of a sloped campus open space which will unify the District's three buildings in this location into a cohesive educational grouping. The building is located on the open space which now exists as a parking lot between the existing Fuller Middle School footprint to the west Farley School to the east. This location makes it possible to eliminate temporary swing space expenses and minimize disruption to ongoing educational activities by leaving the existing school in operation during the construction phase. Once the new school is complete, the existing 196,000 gsf single story school will be demolished, providing more than 90,000 sf of additional open space than exists today.

The site is organized with vehicular movements removed entirely from the public Flagg Drive. A bus drop-off lane with sufficient queuing space for 17 buses to be parked simultaneously is located directly in front of the school and stretches to the west with a separate exit from the main parking area. Upon demolition of the existing school a new single parking area will be built sufficient in size to accommodate the needs of the school staff and visitors.

The new school floor plan is characterized by two segmented arcs of classrooms facing one another across an open three-story Learning Common atrium. Classroom clusters can be flexibly arranged within the floors or by utilizing monumental stairs, aggregating floors of cohort classrooms. At the center of each one of these cohorts will be located in medium size cohort collaboration space which is co-located with a cohort satellite station area. These medium size collaboration spaces are located on balconies overlooking the main Learning Common and relate visually to one another. Several multi-use breakout spaces are also located on balconies directly adjacent to the classrooms which they serve so as to be highly visible to one another and to the Learning Common. Each cohort cluster also includes at its center a pair of science classrooms.



The school's main entry is at the second floor level, directly adjacent to the administration suite, and leads directly to a balcony overlooking the entire array schools educational program at once. Stairs will branch off from this location either upwards or downwards for ease of communication between floors. Arriving at the lowest ground-floor level Learning Common, one will be surrounded by an array of common shared spaces for the school community including the Media Center, Cafeteria, Maker Space, Music and Art classrooms, Fabrication Lab, Gymnasium and Auditorium. All are arrayed around a single open space will serve as a food court but also as a flexible use whole community collaboration and potential assembly space.

Community use functions will separable from classroom areas through the use of metal mesh partitions. A community entrance is located on the west side of the school, adjacent to the new parking area. The adjacent lobby joining the Gymnasium and the Auditorium will serve these event spaces for the both school and the larger community.

Please reference the attached Basis of Design Narratives:

- Sustainability/ LEED Scorecard
- Fire Protection
- Plumbing System
- HVAC System
- Electrical System
- Technology System







**LEED v4 for BD+C: Schools**  
Project Checklist

Project Name: Fuller Middle School  
Date: 09/17/2019



Y	?	N	Credit	Integrative Process	1
---	---	---	--------	---------------------	---

4	1	10	Location and Transportation	15
X	Credit	LEED for Neighborhood Development Location	15	
1	Credit	Sensitive Land Protection	1	
1	Credit	High Priority Site	2	
2	Credit	Surrounding Density and Diverse Uses	5	
4	Credit	Access to Quality Transit	4	
1	Credit	Bicycle Facilities	1	
1	Credit	Reduced Parking Footprint	1	
1	Credit	Green Vehicles	1	

5	2	5	Sustainable Sites	12
Y	Prereq	Construction Activity Pollution Prevention	Required	
Y	Prereq	Environmental Site Assessment	Required	
1	Credit	Site Assessment	1	
2	Credit	Site Development - Protect or Restore Habitat	2	
1	Credit	Open Space	1	
1	Credit	Rainwater Management	3	
2	Credit	Heat Island Reduction	2	
1	Credit	Light Pollution Reduction	1	
1	Credit	Site Master Plan	1	
1	Credit	Joint Use of Facilities	1	

5	0	7	Water Efficiency	12
Y	Prereq	Outdoor Water Use Reduction	Required	
Y	Prereq	Indoor Water Use Reduction	Required	
Y	Prereq	Building-Level Water Metering	Required	
1	Credit	Outdoor Water Use Reduction	2	
3	Credit	Indoor Water Use Reduction	7	
2	Credit	Cooling Tower Water Use	2	
1	Credit	Water Metering	1	

18	8	5	Energy and Atmosphere	31
Y	Prereq	Fundamental Commissioning and Verification	Required	
Y	Prereq	Minimum Energy Performance	Required	
Y	Prereq	Building-Level Energy Metering	Required	
Y	Prereq	Fundamental Refrigerant Management	Required	
5	Credit	Enhanced Commissioning	6	
13	Credit	Optimize Energy Performance	16	
3	Credit	Advanced Energy Metering	1	
1	Credit	Demand Response	2	
2	Credit	Renewable Energy Production	3	
1	Credit	Enhanced Refrigerant Management	1	
1	Credit	Green Power and Carbon Offsets	2	

4	1	8	Materials and Resources	13
Y	Prereq	Storage and Collection of Recyclables	Required	
Y	Prereq	Construction and Demolition Waste Management Planning	Required	
5	Credit	Building Life-Cycle Impact Reduction	5	
1	Credit	Building Product Disclosure and Optimization - Environmental Product Declarations	2	
1	Credit	Building Product Disclosure and Optimization - Sourcing of Raw Materials	2	
1	Credit	Building Product Disclosure and Optimization - Material Ingredients	2	
2	Credit	Construction and Demolition Waste Management	2	

7	2	Indoor Environmental Quality	16
Y	Prereq	Minimum Indoor Air Quality Performance	Required
Y	Prereq	Environmental Tobacco Smoke Control	Required
Y	Prereq	Minimum Acoustic Performance	Required
2	Credit	Enhanced Indoor Air Quality Strategies	2
2	Credit	Low-Emitting Materials	3
1	Credit	Construction Indoor Air Quality Management Plan	1
1	Credit	Indoor Air Quality Assessment	2
1	Credit	Thermal Comfort	1
1	Credit	Interior Lighting	2
3	Credit	Daylight	3
1	Credit	Quality Views	1
1	Credit	Acoustic Performance	1

5	1	0	Innovation	6
4	Credit	Innovation	5	
1	Credit	LEED Accredited Professional	1	

1	1	2	Regional Priority	4
1	Credit	Regional Priority: EAc2 Optimize Energy Performance (20%/8 pts)	1	
1	Credit	Regional Priority: EAc5 Renewable Energy Production (5%/2 pts)	1	
1	Credit	Regional Priority: LTC4 / LTC5	1	
1	Credit	Regional Priority: SSc2 / MRC1	1	

<b>49</b>	<b>21</b>	<b>40</b>	<b>TOTALS</b>	<b>Possible Points: 110</b>
-----------	-----------	-----------	---------------	-----------------------------

Certified: 40 to 49 points, Silver: 50 to 59 points, Gold: 60 to 79 points, Platinum: 80 to 110





## **FIRE PROTECTION SYSTEMS**

### **NARRATIVE REPORT**

The following is the Fire Protection system narrative, which defines the scope of work and capacities of the Fire Protection system, as well as, the Basis of Design.

1. CODES
  - A. All work installed under Section 21 00 00 shall comply with the MA Building Code, NFPA and all state, county, and federal codes, laws, statutes, and authorities having jurisdiction.
2. DESIGN INTENT
  - A. All work is new and consists of furnishing all materials, equipment, labor, transportation, facilities, and all operations and adjustments required for the complete and operating installation of the Fire Protection work and all items incidental thereto, including commissioning and testing.
3. GENERAL
  - A. In accordance with the provisions of the Massachusetts Building Code, a school building of greater than 12,000s.f. must be protected with an automatic sprinkler system.
4. DESCRIPTION
  - A. The new School will be served by new 8-inch fire service, double check valve assembly, and wet alarm valve complete with electric bell, and fire department connection meeting local thread standards.
  - B. The system will be a combined standpipe/sprinkler system with control valve assemblies to limit the sprinkler area controlled to less than 52,000 s.f. as required by NFPA 13-2013.
  - C. Control valve assemblies shall consist of a supervised shutoff valve, check valve, flow switch and test connection with drain. Standpipes meeting the requirements of NFPA 14-2013 shall be provided in the egress stairwells and in the Stage area.
  - D. All areas of the building, including all finished and unfinished spaces, combustible concealed spaces, all electrical rooms, and closets will be sprinkled.
  - E. All sprinkler heads will be quick response, concealed pendent in hung ceiling areas and upright in unfinished areas.
  - F. Fire department valves and cabinets will be provided on each side of the Stage in the Building.
5. BASIS OF DESIGN
  - A. The mechanical rooms, kitchen, science classrooms, and storage rooms are considered Ordinary Hazard Group 1; the stage is considered Ordinary Hazard Group 2; all other areas are considered light hazards.

Page 1 of 4

Phone: (508)869-0403 : Fax (508)869-2891  
Email: [ask@akalengineering.com](mailto:ask@akalengineering.com) : Web: [www.akalengineering.com](http://www.akalengineering.com)

B. Required Design Densities:

Light Hazard Areas	0.10 GPM over 1,500 s.f. with 100 gpm hose allowance
Ordinary Hazard Group 1	0.15 GPM over 1,500 s.f. with 250 gpm hose allowance
Ordinary Hazard Group 2	0.20 GPM over 1,500 s.f. with 250 gpm hose allowance

C. Sprinkler spacing (max.):

Light Hazard Areas:	225 s.f.
Ordinary Hazard Areas:	130 s.f.

D. A hydrant flow test was conducted on October 31, 2018, on Flagg Drive with the following results: 87 PSI static, 78 PSI residual, 1,048 GPM flow, 3,098 GPM flow at 20 PSI. There is adequate water to serve the project without a fire pump.

6. PIPING

A. Sprinkler piping 1-1/2 in. and smaller shall be ASTM A-53, Schedule 40 black steel pipe. Sprinkler/standpipe piping 2 in. and larger shall be ASTM A-135, Schedule 10 black steel pipe.

7. FITTINGS

A. Fittings on fire service piping, 2 in. and larger shall be Victaulic Fire Lock Ductile Iron Fittings conforming to ASTM A-536 with integral grooved shoulder and backstop lugs and grooved ends for use with Style 009-EZ or Style 005 couplings. Branch line fittings shall be welded or shall be Victaulic 920/920N Mechanical Tees. Schedule 10 pipe shall be roll grooved. Schedule 40 pipe, where used with mechanical couplings, shall be roll grooved and shall be threaded were used with screwed fittings. Fittings for threaded piping shall be malleable iron screwed sprinkler fittings.

8. JOINTS

A. Threaded pipe joints shall have an approved thread compound applied on male threads only. Teflon tape shall be used for threads on sprinkler heads. Joints on piping, 2 in. and larger shall be made up with Victaulic, or equal, Fire Lock Style 005, rigid coupling of ductile iron and pressure-responsive gasket system for wet sprinkler system as recommended by manufacturer.

9. FIRE STANDPIPE EQUIPMENT

- A. Fire Department Valves shall be 2-1/2 inch valves fitted with 2-1/2 inch x 1-1/2 inch reducer, caps, and chains all conforming to Local Fire Department thread standard. Valves shall be polished chrome plated and shall be mounted in a recessed cabinet.
- B. Cabinets for the Fire Department Valves shall be fully recessed, solid door, prime painted steel. Include graphic and door catch.
- C. Provide 32 inch x 32 inch access panels at floor control locations or recessed cabinets as appropriate to the wall construction.

10. SPRINKLER SYSTEM EQUIPMENT

A. Double-check valve assembly (Backflow Preventer) shall be UL listed FM approved, complete with test kit and spare parts kit. The Double Check Valve Assembly shall consist

of two independent tri-link check modules within a single housing, sleeve access port, four test cocks and two drip tight shut-off valves. Tri-link checks shall be removable and serviceable, without the use of special tools. The housing shall be constructed of Schedule 40 stainless steel pipe with grooved end connections. Tri-link checks shall have reversible elastomer discs and in operation shall produce drip tight closure against reverse flow caused by backpressure or backsiphonage. This Sub-contractor shall act as the Owner's agent in seeking approval from the Department of Environmental Protection or its designee.

- B. Gate valves, 2 inches and smaller shall be outside screw and yoke, bronze, rising stem, wedge disc type, threaded, conforming to MSS SP-80. Gate valve 2-1/2 inches and larger shall be iron body, bronze trim, outside screw, and yoke, flanged, UL/FM listed conforming to MSS SP-70. All valves shall be UL listed for at least 175 psi working water pressure (wwp).
- C. Globe and angle valves may be used as auxiliary valves (drain valves, test valves, trim valves and valves on compressed air piping) for diameters not over 2 in. They shall be bronze, rising stem, with the bronze disc, threaded, conforming to MSS SP-80 Class 150.
- D. Check valves shall be swing type except as noted. Valves 2 inches and smaller shall be bronze, regrinding type with the renewable disc, screwed caps, threaded, class 150 conforming to MSS SP-80. Check valves 2-1/2 inches and greater shall be iron body, bronze trim, bolted cover, flanged, conforming to MSS SP-71, UL listed for 175 psi wwp.
- E. Wet riser check valves shall be approved vertical type for wet systems, complete with drain valve and glycerin filled pressure gauges. Valve internal components shall be replaceable without removing the valve from the installed position. UL/FM Global approved.
- F. Fire Department connection shall be flush mount cast brass two-way inlet body with drop clappers, 2 1/2" x 2 1/2" x 4". Polished brass plate lettered with the approved signage. Two polished brass double female snoots with rigid end NPT x pin lug hose thread swivels, plugs and chain. The connection's lettering and threads shall match Local Fire Department requirements. Confirm finish with Architect prior to ordering.
- G. Fire protection test connection shall be polished brass plate with lettering to read "TEST". Polished brass double female snoot with rigid end N.P.T. x pin lug hose thread swivel, pin lug plug and chain.
- H. Water Flow Indicators: Vane type water flow detector, rated to 250 psig; designed for horizontal or vertical installation; have 2-SPDT circuit switches to provide isolated alarm and auxiliary contacts, 7 ampere 125 volts AC and 0.25 ampere 24 volts DC; complete with factory-set, field-adjustable retard element to prevent false signals, and tamper-proof cover which sends a signal when cover is removed.
- I. Electric Alarm: Electrically operated, red enameled gong with pressure alarm switch.
- J. Supervisory Switches: SPST, normally closed contacts, designed to signal valve in other than full open position.

## 11. SPRINKLERS

- A. All sprinklers to be used on this project shall be Quick Response type and shall be stamped with date of manufacture and temperature rating. Temperature ratings shall be determined

by the location of the heads per NFPA 13-2013, section 8.3.2.5, and shall be minimum 155° F throughout except in special areas around heat-producing equipment, skylights, and attics in which case use temperature rating to conform with hazard as specified in NFPA 13-2013. Orifice diameter and K factor shall be appropriate to meet the hydraulic design criteria, the available water supply, and NFPA Standards.

- B. Furnish spare heads of each type installed located in a cabinet along with special sprinkler wrenches. The number of spares and locations of cabinet shall be in complete accord with NFPA 13-2013.
- C. Sprinklers shall be manufactured by Tyco, Victaulic, Viking, or equal.
- D. Upright sprinkler heads in areas with no ceilings shall be Tyco Model "TY-FRB" Quick Response, upright natural brass finish heads. Include heavy-duty sprinkler guards in all mechanical rooms, storage rooms, and gymnasium. In pool equipment area, all heads shall be stainless steel.
- E. Sidewall heads shall be Tyco Model "TY-FRB" Quick Response with white polyester head and escutcheon.
- F. Pendent wet sprinkler heads shall be Tyco Model "TY-FRB" Quick Response recessed adjustable escutcheon, white polyester finish.
- G. Concealed heads shall be Tyco Model "RFII" Quick Response concealed type, 1-1/2 inch adjustment white cover plate. In special areas, as may be noted on the Drawings, provide alternate cover plate finishes (5 custom colors).

## PLUMBING SYSTEMS

### NARRATIVE REPORT

The following is the Plumbing system narrative, which defines the scope of work and capacities of the Plumbing system as well as the Basis of Design. The Plumbing Systems shall be designed and constructed for **LEED v4 for Schools** where indicated in this narrative.

#### 1. CODES

- A. All work installed under Section 22 00 01 shall comply with the MA Building Code, MA Plumbing Code and all state, county, and federal codes, laws, statutes, and authorities having jurisdiction.

#### 2. DESIGN INTENT

- A. All work is new and consists of furnishing all materials, equipment, labor, transportation, facilities, and all operations and adjustments required for the complete and operating installation of the Plumbing work and all items incidental thereto, including commissioning and testing.

#### 3. GENERAL

- A. The Plumbing Systems that will serve the project are cold water, hot water, tempered water, sanitary waste and vent system, grease waste system, special waste system, storm drain system, and natural gas.
- B. The Building will be serviced by Municipal water and Municipal sewer system.
- C. All Plumbing in the building will conform to Accessibility Codes and to Water Conserving sections of the Plumbing Code.

#### 4. DRAINAGE SYSTEM

- A. Soil, Waste, and Vent piping system is provided to connect to all fixtures and equipment. The system runs from 10 feet outside the building and terminates with stack vents through the roof.
- B. A separate Grease Waste System starting with a connection to an exterior concrete grease interceptor running the kitchen area fixtures. Chamber vent for outdoor grease interceptor and vent terminal through the roof. The point of use grease interceptors is to be provided at designated kitchen fixtures. The exterior grease interceptor shall be provided under Division 22 scope.
- C. The storm Drainage system is provided to drain all roofs with roof drains piped through the building to a point 10 feet outside the building.

- D. Drainage system piping will be service weight cast iron piping; hub and spigot with gaskets for below-grade; no hub with gaskets, bands, and clamps for above grade 2 in. and larger. Waste and vent piping 1-1/2 in. and smaller will be type 'L' copper.
- E. A separate Special Waste System shall be provided starting with a connection to a limestone chip acid neutralizer tank and shall collect science classroom fixtures. The tank vent and fixture acid vent terminals through the roof. Special Waste and Vent piping will be Schedule 40 electric heat-fused polypropylene piping, fittings and traps, flame retardant above grade and non-flame retardant below ground.

## 5. WATER SYSTEM

- A. A new 4-inch domestic water service from the municipal water system will be provided. A meter and backflow preventer is provided.
- B. Domestic cold water distribution main is provided. Non-freeze wall hydrants with integral back flow preventers are provided along the exterior of the building.
- C. Domestic hot water heating will be provided with a combination of gas-fired, high efficiency, condensing water heater (Two 400 MBH input), with a separate storage tank (300 gallon). The system is to be equipped with thermostatically controlled mixing devices to control water temperature to the fixtures.
- D. A pump will re-circulate hot water from the piping system. The water temperature will be 120 deg. to serve general use fixtures. A 140 deg. F hot water will be supplied to the kitchen dishwasher.
- E. Water piping will be type 'L' copper with copper sweat fittings, silver solder or press-fit system. All piping will be insulated with 1 in. thick high-density fiberglass.
- F. A dedicated non-potable cold and hot water system will be provided to Science Classrooms. The water system will be protected with a reduced pressure backflow preventer. Self-regulating heat tracing will be provided at lab/ hot water for temperature maintenance.
- G. Tepid (70 deg. F – 90 deg. F) water will be provided to the emergency shower/eyewash fixtures in Science Classrooms as required by code.

## 6. GAS SYSTEM

- A. Natural gas service will be provided for the building and will serve the boilers, domestic water heaters, kitchen cooking equipment, science classroom and emergency generator.
- B. Science classrooms requiring gas turrets will be provided with gas with master gas control shut off valve.
- C. Gas piping will be Schedule 40 black steel pipe with threaded gas pattern malleable fittings for 2 in. and under and butt welded fittings for 2-1/2 in. and larger.

## 7. FIXTURES *LEED v4*

- A. Furnish and install all fixtures, including supports, connections, fittings, and any incidentals to make a complete installation.
- B. Fixtures shall be the manufacturer's guaranteed label trademark indicating first quality. All acid-resisting enameled ware shall bear the manufacturer's symbol signifying acid-resisting material.
- C. Vitreous china and acid-resisting enameled fixtures, including stops, supplies, and traps shall be of one manufacturer by Kohler, American Standard, or Sloan, or equal. Supports shall be Zurn, Smith, Josam, or equal. All fixtures shall be white. Faucets shall be Speakman, Chicago, or equal.
- A. Fixtures shall be as scheduled on drawings.
  - a. Water Closet: High-efficiency toilet, 1.28 gallon per flush, wall hung, vitreous china, siphon jet. Manually operated 1.28 gallons per flush-flush valve.
  - b. Urinal: High efficiency 0.13 gallon per flush urinal, wall hung, vitreous china. Manually operated 0.13 gallons per flush-flush valve.
  - c. Lavatory: Wall-hung / countertop ADA lavatory with 0.35 GPM metering mixing faucet programmed for 10 seconds run-time cycle.
  - d. Sink: ADA stainless steel countertop sink with gooseneck faucet and 0.5 GPM aerator.
  - e. Drinking Fountain: Barrier-free hi-low wall mounted electric water cooler, stainless steel basin with bottle filling stations.
  - f. Janitor Sink: 24 x 24 x 10 Terrazo mop receptor Stern-Williams or equal.
  - g. Laboratory Sinks: Faucets with vacuum breakers and 0.74 GPM aerators.
  - h. Emergency Shower/Eyewash: Recessed barrier-free eyewash and shower safety station with ceiling mounted exposed shower and "in-wall" drop-down eyewash with drain pan.

## 8. DRAINS

- A. Drains are cast iron, caulked outlets, nickaloy strainers, and in waterproofed areas and roofs shall have galvanized iron clamping rings with 6 lb. lead flashings to bond 9 in. in all directions. Drains shall be Smith, Zurn, Josam, or equal.

## 9. VALVES

- A. Locate all valves so as to isolate all parts of the system. Shutoff valves 3 in. and smaller shall be ball valves, solder end or screwed, Apollo, or equal.

#### 10. INSULATION

- A. All water piping shall be insulated with snap-on fiberglass insulation Type ASJ-SSL, equal to Johns Manville Micro-Lok HP.

#### 11. CLEANOUTS

- A. Cleanouts shall be full size up to 4 in. threaded bronze plugs located as indicated on the drawings and/or where required in soil and waste pipes.
- B. Cleanouts for Special Waste System shall be Zurn #Z9A-C04 polypropylene cleanout plug with Zurn #ZANB-1463-VP nickel bronze scoriated floor access cover.

#### 12. ACCESS DOORS

- A. Furnish access doors for access to all concealed parts of the plumbing system that require accessibility. Coordinate types and locations with the Architect.

#### 13. WATER HEATER

- A. Two gas-fired, high efficiency, condensing water heaters (400,MBH input each) with separate storage tank (300 gallon).

#### 14. GREASE INTERCEPTOR

- A. The kitchen Grease Waste System shall be a completely separate system beginning at the exterior grease interceptor through the kitchen and vented individually through the roof. No soil lines will be connected to the grease waste nor sanitary vents to the grease vent. Furnish and install the cast iron tees and associated piping within the grease trap including the 5-foot length on the outlet. All the piping within the grease trap shall be made up with caulked and leaded joints. Install an exterior cleanout as detailed at the point where the line leaves the kitchen area. A grease trap is furnished and set in place including manhole access covers by the Plumbing Contractor.

#### 15. OIL / GAS INTERCEPTOR

- A. The Oil/Sand Trap shall be installed in accordance to Massachusetts Plumbing Code 248 CMR 10.22. Fig. 15.



Fuller Middle School  
Framingham, MA  
J#680 015 00.00  
L#60858/Page 1/October 18, 2019

## HVAC SYSTEMS

### NARRATIVE REPORT

The following is the HVAC Systems narrative, which defines the scope of work and capacities of the HVAC systems, as well as, the Basis of Design for the proposed Middle School.

#### 1. CODES

All work installed under Division 230000 shall comply with the Massachusetts State Building Code, IMC 2015, IECC 2015, and all local, county, and federal codes, laws, statutes, and authorities having jurisdiction.

#### 2. DESIGN INTENT

The work of Division 230000 is described within the narrative report. The HVAC project scope of work shall consist of providing new HVAC equipment and systems as described here within. All new work shall consist of furnishing all materials, equipment, labor, transportation, facilities, and all operations and adjustments required for the complete and operating installation of the Heating, Ventilating and Air Conditioning work and all items incidental thereto, including commissioning and testing.

#### 3. BASIS OF DESIGN

Project weather and Code temperature values are listed herein based on weather data values as determined from ASHRAE weather data tables and the International Energy Conservation Code.

Outside: Winter 5 deg. F, Summer 88 deg. F DB 73 deg. F WB

Inside: 70 deg. F +/- 2 deg. F for heating, 75 deg. F +/- 2 deg. F (50% +/- 5%RH) for cooling for [classroom, administration, auditorium, cafeteria and gymnasium] areas with full air conditioning. 80 deg. F +/- 2 deg. F (55% RH) for cooling for locker and kitchen areas with partial air conditioning/dehumidification ventilation. Unoccupied temperature setback will be provided at 60 deg. F (adj.) for heating and 80 deg. F. (adj.) for cooling.

Outside air is provided at the rate of a minimum of 15 cfm/person in all classrooms and large group spaces, and minimum of 15 cfm/person for the Auditorium, Gymnasium and Cafeteria areas. In all cases ASHRAE guide 62.1-2016 and the International Mechanical Code will be met as a minimum. All occupied areas will be designed to maintain 800 PPM carbon dioxide maximum.

The building HVAC system shall be designed as a high efficiency HVAC system that shall meet the related HVAC system requirements of LEED for Schools v4, with a minimum goal of Silver level certification.

Fuller Middle School  
Framingham, MA  
J#680 015 00.00  
L#60858/Page 2/October 18, 2019

4. SYSTEM DESCRIPTION

A. Central Heating Plant:

Heating for the entire building will be through the use of a high efficiency gas-fired condensing Boiler Plant.

The Boiler Plant shall be provided with (2) 4,000 MBH input/3,844 MBH output boilers and (2) end suction base mounted pumps with a capacity of 790 GPM each which will be located in the ground level mechanical room. In addition to new boilers and pumps, new hot water accessories including air separators and expansion tanks shall be provided.

The Boiler Plant will supply heating hot water to heating equipment and systems located throughout the building through a two-pipe fiberglass insulated schedule 40 black steel piping system. The Boiler Plants shall supply a maximum hot water temperature of 160 deg F on a design heating day and the hot water supply water temperature will be adjusted downward based on an outside temperature reset schedule to improve the overall operating efficiency of the power plants. Primary and standby end suction base mounted pumps will be provided with variable frequency drives for variable volume flow through the water distribution system for improved energy efficiency.

Combustion air for each boiler will be directly ducted to each boiler through a galvanized ductwork distribution system. Venting from each boiler shall be through separate double wall aluminized stainless steel (AL29-4C) vent system and shall discharge approximately 12 feet above the roof level. Final venting height will be dependent on the location of building intake air locations and adjacent roofs.

B. Central Cooling Plant:

Chilled water cooling for the majority of the building will be through the use of a high efficiency air cooled chiller plant.

The chiller plant shall be provided with (1) high efficiency modular 4 compressors at 92.5 tons each design oil-less magnetic compressor air cooled design chillers and (2) chilled water end suction base mounted pumps with VFD drives. The chillers will be mounted on the roof and the pumps and chilled water accessories will be located in nearby factory fabricated rooftop mechanical equipment enclosure. In addition to new boilers and pumps, new chilled water accessories including air separators, expansion tanks and buffer tank shall be provided.

The chiller plant will supply chilled water to air conditioning air handling unit equipment located throughout the building through a two-pipe fiberglass insulated schedule 40 black steel piping system. Primary and standby end suction base mounted pumps will be provided with variable frequency drives for variable volume flow through the water distribution system for improved energy efficiency.

The chiller plant shall be provided with (1) 369 ton chiller with (4) 92.5 ton modules and (2) chilled water end suction base mounted pumps with a capacity of approximately 800 GPM each. One chiller module is provided for redundancy.

Fuller Middle School  
Framingham, MA  
J#680 015 00.00  
L#60858/Page 3/October 18, 2019

- C. Classroom Heating and Ventilation (General Classrooms, including SPED, Art, Music, Maker Space, Fab Lab, Tech, Learning Commons/Cafeteria, Administration and Media Center areas):

Rooftop air handling units, with roof penthouse service enclosure, supply and return fan with VFDs, static plate type energy recovery section, hot water heating section with modulating capacity control, chilled water cooling coil with modulating capacity control, static plate reheat section, MERV 13 filtration, variable air volume and carbon dioxide demand ventilation controls which will reduce outside air as allowed maintaining a maximum of 800 PPM and will be provided to serve a full air conditioning displacement ventilation system. Supply air will be provided to the space through a galvanized steel supply duct distribution system and shall be connected to VAV (variable air volume) terminal boxes and wall mounted displacement ventilation diffusers located within the classrooms. Return air will be drawn back to the units by ceiling return air registers located within the classroom and will be routed back to the rooftop unit by a galvanized sheetmetal return air ductwork distribution system. Supplemental hot water radiation heating will be provided along exterior walls.

Classrooms with Displacement Ventilation and Full Air Conditioning:

The classroom space temperature would be controlled to 75 deg. F. +/- 2 deg F, based on a design cooling day of 88 deg F db/73 deg f. wb.

The following rooftop air handling equipment will be required to serve the Classroom areas to provide full air conditioning:

Four (4) air handling units with a capacity of 20,000 CFM (63% OA, 51 tons cooling, 840 MBH heating)

- D. Gymnasium:

The Gymnasium will be served by a rooftop air handling unit, with roof penthouse service enclosure, supply and return fan with VFDs, static plate type energy recovery section, hot water heating section with modulating capacity control, chilled water cooling coil, static plate reheat section, MERV 13 filtration, and carbon dioxide controls which will reduce outside air as allowed maintaining a maximum of 800 PPM and will be provided to serve a full air conditioning overhead supply distribution system. Supply air will be provided to the space through a combination galvanized steel and Fabric supply duct distribution system. The overhead fabric ductwork shall have integral supply air diffusers. As levels of carbon dioxide drop, generally relating to a reduction in population, the variable frequency drive located in the rooftop unit will modulate to reduce air flow and ventilation while always maintaining a maximum of 800 ppm. Return air will be drawn back to the unit by perforated ductwork return air registers located within the Gymnasium and will be routed back to the rooftop unit by a galvanized sheetmetal return air ductwork distribution system. Supplemental hot water radiation heating will be provided along exterior walls.

The Gymnasium will be served by (1) one rooftop air handling unit that will have a capacity of 15,000 CFM (73% OA, 40 Tons Cooling, 690 MBH Heating).

Fuller Middle School  
Framingham, MA  
J#680 015 00.00  
L#60858/Page 4/October 18, 2019

E. Locker Rooms and PE/Health Offices:

The Locker Rooms and adjacent office areas will be provided with new roof-mounted air handling units, of the 100% outside air design with static plate energy recovery section. The unit will be approximately 2,000 CFM (100% OA) and will include a supply and exhaust fan with VFDs, 112 MBH hot water heating section with modulating capacity control, 6.5-ton chilled water cooling for dehumidification, static plate type energy recovery and reheat sections and MERV 13 filtration.

Supply air ventilation will be provided to each space through new galvanized supply duct which will travel throughout the area to a series of ceiling mounted supply registers. New exhaust air ductwork and air distribution devices shall be installed and shall be routed from the rooms to the new air handling units.

F. Auditorium and Stage:

The Auditorium and Stage will be provided with a new roof-mounted air handling unit, with roof penthouse service enclosure, of the recirculation design capable of providing 100% outside air variable volume fully air conditioned overhead air distribution to the Auditorium and Stage areas. The Auditorium unit will be approximately 12,000 CFM (42% OA) and will include supply and return fans with VFDs, 410 MBH hot water heating section with modulating capacity control, 26 ton cooling coil with modulating capacity control, static plate energy recovery and reheat sections, and MERV 13 filtration.

Supply air ventilation to the Auditorium will be provided to the space through a combination galvanized steel and Fabric supply duct distribution system. The overhead fabric ductwork shall have integral supply air diffusers. In addition, carbon dioxide controls will be installed which will monitor the overall level of carbon dioxide at a threshold level of 800 ppm. As levels drop generally relating to a reduction in population, the air handling unit outside air damper will modulate to reduce air flow and ventilation while always maintaining a maximum of 800 ppm. Return air will be drawn back to the unit by ductwork with return air registers located at lower levels within the space. Supplemental hot water radiation heating will be provided along exterior walls.

G. Administration Area, Guidance Offices and adjacent Lobby/Circulation areas

Spatial heating and air-conditioning for the Administration area and Guidance offices will be served by variable volume air system with perimeter radiant heating panels. The system will be of a recirculation design with CO2 demand ventilation capable of providing 100% outside air (economizer) and variable air volume operation full air conditioning displacement ventilation air distribution.

These areas shall be served by the classroom rooftop air handling units. Supply air ventilation will be provided to each space that will satisfy both building code requirements based on population and spatial heating and air-conditioning for these zones will be provided by a full air conditioning displacement air ventilation system with CO2 demand ventilation controls. Supplemental hot water radiation heating will be provided along exterior walls.

Fuller Middle School  
Framingham, MA  
J#680 015 00.00  
L#60858/Page 5/October 18, 2019

H. Kitchen:

The Kitchen areas shall be provided with a new Kitchen exhaust air fan and make-up air rooftop unit with hot water heating. The Kitchen will be heated by a roof mounted heating and ventilation make-up air handling unit with hot water heating and chilled water dehumidification (partial cooling).

A variable volume Kitchen exhaust hood control system consisting of Kitchen exhaust stack temperature and smoke density sensors, supply and exhaust fan variable speed drives, and associated controller will be provided by the Kitchen Equipment Vendor. This system installation shall be field installed and coordinated with the ATC and Electrical Contractors.

I. Lobby, Corridor, and Entry Way Heating:

New hot water convectors, cabinet unit heaters and fin tube radiation heating equipment shall be installed to provide heating to these areas. Corridors shall be ventilated from adjacent air handling unit systems.

J. Custodial Support / Mechanical Room / Adjacent Storage Areas:

Custodial support areas will be heated and ventilated by the classroom rooftop air handling units. Storage areas will be heated by hot water radiation heating equipment. Horizontal type unit heaters will heat areas adjacent to the loading dock. All custodial closets will be exhausted by exhaust air fan systems.

K. Utility Areas:

Utility areas will be provided with exhaust air fan systems for ventilation, and will typically be heated with horizontal type ceiling suspended unit heaters.

The Main Electric Rooms and IDF Rooms will be air conditioned by high efficiency ductless AC cooling units.

L. Atrium Smoke Exhaust System

A smoke exhaust and control evacuation system will be provided for the atrium. The system, including all equipment and control components, shall be interlocked to the building fire alarm system and shall be powered by emergency power. The system shall consist of (4) four, 60,000 CFM each roof mounted smoke exhaust duty rated fans, ductwork, dampers and associated controls. The system shall be designed to purge smoke exhaust from the top of the Atrium. Make-up air shall be provided at the lower first and second floor levels through the use of operable doors, louvers, and/or windows with automatic operators that shall also be connected to the smoke control system.

The Atrium smoke control system design shall be modeled and reviewed by a third-party consultant. As part of the third party's design review CFD and fire dynamic modeling shall be performed to determine the proper smoke exhaust system equipment sizing. After the system is installed, the smoke control system operation shall be tested and verified by a third-party consultant to ensure proper system operation.

Fuller Middle School  
Framingham, MA  
J#680 015 00.00  
L#60858/Page 6/October 18, 2019

M. Testing, Adjusting, Balancing & Commissioning:

All new HVAC systems shall be tested, adjusted, balanced and commissioned as part of the project scope.

N. Automatic Temperature Controls – Building Energy Management System:

A new DDC (direct digital control) automatic temperature control (ATC) and building energy management (BEMS) system shall be installed to control and monitor building HVAC systems. The building lighting control system shall also be integrated into the new building energy management system. Energy metering shall be installed to monitor the energy usage of building HVAC systems and utilities (fuel, gas, water). A building energy dashboard system and kiosk shall be provided to display building energy and water usage. The new building energy management system shall be a BACnet open protocol system with Tridium Niagara JACE front end controller.

Fuller Middle School  
Framingham, MA  
J#680 015 00.00  
L#60587/Page 1/October 18, 2019

**ELECTRICAL SYSTEMS**

**NARRATIVE REPORT**

The following is the Electrical Systems narrative, which defines the scope of work and capacities of the Power and Lighting systems, as well as, the Basis of Design. The Electrical systems shall be designed and constructed for **LEED v4** where indicated on this narrative. This project shall conform to LEED Silver rating.

1. CODES

All work installed under Section 260000 shall comply with the International Building Code (IBC) as amended by Massachusetts and all local, county, and federal codes, laws, statutes, and authorities having jurisdiction.

2. DESIGN INTENT

The work of Section 260000 is indicated in this narrative report. All work is new and consists of furnishing all materials, equipment, labor, transportation, facilities, and all operations and adjustments required for the complete and operating installation of the Electrical work and all items incidental thereto, including commissioning and testing.

3. SEQUENCE OF OPERATIONS AND INTERACTIONS

- A. Classroom and Corridor lighting will be controlled via “addressable relays”, which is achieved through programming networked controls. The control of the relays will be by automatic means, such as an occupancy sensor in each classroom. The system will have a BacNet gateway and will be interfaced with the DDC control system for schedule functions. The controllability shall be in conformance with associated LEED credit in indoor environmental quality.
- B. Automatic control of receptacles based on occupancy will be provided for at least 50% of the receptacles installed in private offices, open offices, and computer classrooms. Controlled receptacles will be marked per NEC 406.3 (E).
- C. Exterior lighting will be controlled by photocell “ON” and “scheduled” for “OFF” operation. The parking area lighting will be controlled by “zones” with dimmable capability.
- D. Emergency and Exit lighting will be run through life safety panels to be “ON” during normal power conditions, as well as, power outage conditions. The emergency lighting system will have time control so that lights are “ON” only when building is occupied.

Fuller Middle School  
Framingham, MA  
J#680 015 00.00  
L#60587/Page 2/October 18, 2019

4. DESCRIPTION OF THE SYSTEMS

A. Electrical Distribution System:

1. Service ratings for the building are designed for a connected load of 10 watts/S.F. The service capacity will be sized for 2,500 Amperes with a 100% rated main breaker. The main buss will be sized at 3,000 Amperes and will have an available space provision at the end of the gear to accommodate a future grid connected photovoltaic array. The switchboard will be furnished with a service entrance transient voltage surge protection device (SPD) rated at 240 kA and digital metering unit to monitor voltage, current, power factor, demand KW and with a data communication port for interface with BMS. Main switchboards short circuit rating with a data communication port for interface with BMS. Main switchboards short circuit rating will be coordinated with the Utility Company but it is estimated to be 65 KAIC.

B. Interior Lighting System:

1. Classroom lighting fixtures consist of ceiling mounted indirect LED luminaires with dimming drivers. The fixtures will be pre-wired for dimming control where natural daylight is available and also for multi-level switching. Office lighting fixtures will consist of similar fixtures to classrooms. Offices on the perimeter with windows shall have daylight dimming controls.

In general, lighting power density will be 30 percent less than IECC 2015. The power density reduction relates to **LEED v4 for Schools**.

2. Lighting levels will be approximately 30 foot candles in classrooms and offices. The daylight dimming footcandle level will be in compliance with **LEED v4 for Schools**.
3. Gymnasium lighting will be comprised of indirect LED fixtures with dimming drivers. The fixtures will be provided with protective wire guards. The light level will be designed for approximately 50 foot candles.

Daylight dimming will be provided within 15 feet of skylights or glazing. Daylight dimming controls will be similar in operation to classrooms.

4. Corridor lighting will be comprised of linear indirect lighting using LED light source. The corridor light level will be designed for approximately 15 foot candles. Corridor lighting will be on a schedule through the DDC system control and only "on" during occupied hours. The corridor lighting will have two level control.
5. Auditorium lighting will be cove pendant LED fixtures with DMX dimming drivers. The light levels will be designed for approximately 20 foot candles.
6. Cafeteria lighting will consist of cove mounted LED linear fixtures with dimming drivers.



Fuller Middle School  
Framingham, MA  
J#680 015 00.00  
L#60587/Page 3/October 18, 2019

7. Kitchen and Served lighting will consist of recessed 2 ft. x 2 ft. lensed gasketed LED panels. Light levels will be approximately 50 foot candles.
8. Library lighting will consist of indirect LED fixtures and dimming drivers. Light levels will be approximately 30 foot candles.
9. Each area will be locally switched and designed for multi-level controls. Each classroom, office space and toilet rooms will have an occupancy sensor to turn lights off when unoccupied. Daylight sensors will be installed in each room where natural light is available for dimming of light fixtures. Corridors will have occupancy sensors for shutdown of lighting, similar to classrooms.
10. The entire school will be controlled with an automatic lighting control system using the DDC control system for schedule programming of lights.

C. Emergency Lighting System:

1. An exterior ground mounted 300 kW natural gas fueled emergency generator with sound attenuated housing will be provided. Light fixtures and LED exit signs will be installed to serve all egress areas such as corridors, intervening spaces, toilets, stairs and exit discharge exterior doors. The administration area lighting will be connected to the emergency generator.
2. The generator will be sized to include life safety systems, legally required systems (smoke evacuation) and optional standby systems including boilers and circulating pumps, communications systems and kitchen refrigeration.
3. Refer to the attached Generator Load Breakdown Dated April 30, 2019.

D. Site Lighting System:

1. Fixtures for area lighting will be pole mounted cut-off 'LED' luminaries in the parking area and roadways. The exterior lighting will be connected to the automatic lighting control system for photocell on and timed off operation. The site lighting fixtures will be dark sky compliant. The illumination level is 1.0 fc for parking areas.
2. Building perimeter fixtures will be wall mounted cut-off over exterior doors for exit discharge.

E. Wiring Devices:

1. Each classroom will have a minimum of (2) duplex receptacles per teaching wall and (2) double duplex receptacles on dedicated circuits at classroom computer workstations. The teacher's workstation will have a double duplex receptacle also on a dedicated circuit.
2. Office areas will generally have (1) duplex outlet per wall. At each workstation a double duplex receptacle will be provided.
3. Corridors will have a cleaning receptacle at approximately 25 foot intervals.

Fuller Middle School  
Framingham, MA  
J#680 015 00.00  
L#60587/Page 4/October 18, 2019

4. Exterior weatherproof receptacles will be installed at exterior doors. The outlets will automatically be switched off from schedule.
5. A system of computer grade panelboards with double neutrals and transient voltage surge suppressors will be provided for receptacle circuits.

F. Fire/Mass Notification System:

1. A fire/mass notification system and detection system will be provided with 60 battery back-up. The system will be of the addressable type where each device will be identified at the control panel and remote annunciator by device type and location to facilitate search for origin of alarms. The notification system will be in conformance with NFPA 72 Chapter 24 emergency communications systems.
2. Smoke detectors will be provided in open areas, corridors, stairwells and other egress ways.
3. The sprinkler system will be supervised for water flow and tampering with valves.
4. Speaker/strobes will be provided in egress ways, classrooms, assembly spaces, open areas and other large spaces. Strobe only units will be provided in single toilets and conference rooms.
5. Manual pull stations will be provided at exit discharge doors.
6. The system will be remotely connected to automatically report alarms to fire department via an approved method by the fire department.

G. Addressable Dual Speaker/Strobe Units for Fire and Mass Notification application:

1. One-way Tone/Voice Communication:
  - a. The evacuation alarm and alert signals shall be capable of being initiated automatically from the fire alarm control panel (FACP) and transmitted to any speaker circuit, selected speaker circuits or all speaker circuits.
  - b. The alarm signal, alert signal and live and pre-recorded voice announcements shall be capable of manual transmission from the FACP to any speaker circuit, selected speaker circuits or all speaker circuits by manual selection of the associated speaker circuit control switches.
  - c. Live voice announcements, via the hand-held microphone or patched in external source, by use of speaker control switches, shall take priority over all previously activated alarm inputs. In addition to NFPA 72 requirements, the system shall be capable of priority live voice announcements over subsequent alarm conditions. In no case shall subsequent alarms disrupt emergency live voice announcements. Mass notification activation is the only condition allowed to override the fire alarm event.

Fuller Middle School  
Framingham, MA  
J#680 015 00.00  
L#60587/Page 5/October 18, 2019

- d. Addressable Visual Unit (Xenon Strobe) and Visual/Fire/MNS unit:
    - 1) Combination white/amber strobe/MNS units - Provide Truealert Synchronized white strobe (fire)/yellow strobe (MNS event) all in one unit. Unit shall be red with "FIRE" in white lettering. Yellow strobe shall include "ALERT" in white lettering.
    - 2) Provide candela rating indicated on drawings and in accordance with NFPA requirements.
    - 3) Adjacent to all combination visual units shown on drawings provide an addressable speaker
    - 4) Systems that require separate wiring and control modules to support the specified functionality shall be provided at no additional cost.
  - 2. Addressable Textual Notification Appliance (MNS): Textual Notification Appliance is to operate on a compatible Signaling Line Circuit (SLC) and is to provide a high visibility, multi-color LED text message display.
- H. Uninterruptible Power Supply (UPS):
- 1. Two (2) 24 kW, three (3) phase centralized UPS systems will be provided with 8-minute battery back-up.
  - 2. The system will provide conditioned power to sensitive electronic loads, telecommunication systems, bridge over power interruptions of short duration and allow an orderly shutdown of servers, communication systems, etc. during a prolonged power outage.
  - 3. The UPS systems will also be connected to the stand by generator.
- I. Lightning Preventor System:
- 1. Lightning preventer devices will be provided to provide coverage for the entire building.
  - 2. The lightning preventer equipment will include lightning preventers, conductors, conduits, fasteners, connectors, ground rods, etc.

Renewable Energy System Provisions:

- 1. The base project will include:
  - a. Electrical provisions will be made for a roof mounted renewable energy system for a grid connected photovoltaic PV system intended to reduce the facilities demand for power.

Fuller Middle School  
Framingham, MA  
J#680 015 00.00  
L#60587/Page 6/October 18, 2019

J. Two-way Communication System:

1. A Two-Way Communications System will be provided at the elevator lobbies that do not have grade access. Area of rescue assistance call boxes will be provided at Elevator Lobbies with no grade access. The call boxes connect to a main panel located adjacent to the Fire Alarm annunciator panel.

K. Distributed Antennae System (DAS):

1. A public safety radio distributed antenna system (DAS) which consists of bi-directional amplifiers (BDA), donor antennas, coverage antennas, coax cable, coax connectors, splitters, combiners and couplers. These devices will be used as part of a system for in-building public safety 2-way radio system communication.

L. Closed-Circuit TV System(CCTV):

1. A Closed-Circuit TV system will consist of computer servers with image software, computer monitors and IP based closed circuit TV cameras. The head end server will be located in the head end (MDF) room and will be rack mounted. The system can be accessed from any PC within the facility or externally via an IP address. Each camera can be viewed independently. The network video recorders (SAN) will record all cameras and store this information for 45 days at 30 images per second (virtual real time).
2. The location of the cameras is generally in corridors and exterior building perimeter. The exterior cameras are 360 degree multi-sensor type.
3. The system will fully integrate with the access control system to allow viewing of events from a single alarm viewer. Camera images and recorded video will be linked to the access system to allow retrieval of video that is associated with an event.

M. Intrusion System:

1. An intrusion system will consist of security panel, keypads, motion detectors and door contacts. The system is addressable which means that each device will be identified when an alarm occurs. The system is designed so that each perimeter classroom with grade access will have dual tech sensors along the exterior wall and corridors, door contacts at each exterior door.
2. The system can be partitioned into several zones. Therefore, it is possible to use the Gym area while the remainder of the school remains alarmed.
3. The system will include a digital transmitter to summons the local police department in the event of an alarm condition
4. The intrusion system will be connected to the automated lighting control system to automatically turn on lighting upon an alarm.

Fuller Middle School  
Framingham, MA  
J#680 015 00.00  
L#60587/Page 7/October 18, 2019

N. Card Access System:

1. A card access system includes a card access controller, door controllers and proximity readers/keypads. Proximity readers will be located at various locations. Each proximity reader will have a distinctive code to identify the user and a log will be kept in memory. The log within the panel can be accessed through a computer.
2. The alarm condition will also initiate real time recording on the integrated CCTV System. The system may be programmed with graphic maps allowing the end-user to quickly identify alarm conditions and lock/unlock doors.
3. The system is modular and may be easily expanded to accommodate any additional devices.

5. TESTING REQUIREMENTS

The Electrical Contractor shall provide testing of the following systems with the Owner and Owner's Representative present:

- Lighting and power panels for correct phase balance.
- Emergency generator.
- Lighting control system (interior and exterior).
- Fire alarm system.
- Security system.
- Lightning preventor system.

Testing reports shall be submitted to the Engineer for review and approval before providing to the Owner.

6. OPERATION MANUALS AND MAINTENANCE MANUALS

When the project is completed, the Electrical Contractor shall provide operation and maintenance manuals to the Owner.

7. RECORD DRAWINGS AND CONTROL DOCUMENTS

When the project is completed, an as-built set of drawings, showing all lighting and power requirements from contract and addendum items, will be provided to the Owner.

8. COMMISSIONING

The project shall be commissioned per Section 018000 of the specifications.

Fuller Middle School  
Framingham, MA  
J#680 015 00.00  
L#60587/Page 8/October 18, 2019

9. SITE UTILITIES

The Electric, Telephone and Cable TV utilities will be underground for each system provided. Existing town network services shall be maintained.


M#66209r  
J#680 015 00.00

DATE: April 26, 2019, *Updated April 30, 2019*

MEMO

TO: Elizabeth Bugbee, AIA  
Jonathan Levi Architects.

FROM: David M. Pereira



PROJECT: Fuller Middle School  
Framingham, MA

SUBJECT: Generator Load Breakdown

---

Please be advised of the following:

The generator will be located on the exterior of the building and will be provided with a 10' emissions stack mounted on top of housing and supported from all four corners with Aircraft cable.

A 300kW natural gas fired generator will allow the facility to function as a Warm-up Shelter within the Student Commons during loss of normal power. Kitchen equipment necessary for warming food will be on generator power. (the use of the range and hood is not included). The system will be designed to lock out ATS-OS (optional stand-by loads) which are the loads listed in items B and C in the below load breakdown list. ATS-OS will be locked out when the smoke exhaust fans for the Atrium are initiated. This is done to avoid an oversized generator as when the smoke exhaust fans run the school is required to be evacuated.

The loads will include all required life safety equipment, legally required equipment as well as, optional standby loads and Warm-Up Shelter loads as listed below.

Emergency Generator Load Breakdown List

Load Breakdown for Life Safety Equipment:

- A. All Exit Signs and Emergency Lighting in the areas listed below are fed by Life Safety Emergency Power:
  - 1. Corridors
  - 2. Electrical Rooms
  - 3. Gymnasium & Locker Rooms
  - 4. Cafeteria Learning Commons
  - 5. Media Center
  - 6. Lobbies
  - 7. Central Administration Area
  - 8. Custodian Workshop/Office
  - 9. Domestic Water Room
  - 10. Health Suite/Nurses Office
  - 11. Toilets
  - 12. Auditorium & Stage
  - 13. Data Rooms "Head End Room & IDF Closets
  - 14. Kitchen & Servery
  - 15. Exterior Building mounted lights over doors required for egress lighting
  - 16. Pole mounted lights for parking areas used during warm-up shelter occupancy.

M#66209r

J#680 015 00.00

Page 2

17. Where required by code (egress areas)

Load Breakdown for Optional Standby Equipment:

B. Equipment listed below is fed by Optional Standby Power:

1. Door Access Controls, Security System, CCTV
2. Strategically located receptacles in the following areas. These receptacles will be RED in color:
  - a. Central Administration
  - b. Electric Rooms and Emergency Electric Rooms
  - c. Mechanical Rooms
3. Heating and Ventilation systems:
  - a. Boilers, Water Pumps
  - b. Building Management System Headend
  - c. Cooling unit serving Head End room & IDF rooms
  - d. Unit heater serving water service room.
4. Equipment within the Head End and IDF rooms including:
  - a. Paging/Intercom System
  - b. Telephone System
  - c. Network electronics
  - d. Servers
  - e. Telephone system
  - f. Clock system
5. Fire alarm system (system also has full battery back-up 15 minutes of alarm, 60 hours standby)
6. Elevator
7. Refrigeration Equipment

C. Warm-up Shelter Loads:

1. Heating and ventilation systems:
  - a. One Rooftop unit serving student commons to provide ventilation and heat to Student Commons.
2. Kitchen equipment necessary to warm food (excluding range and hood).
3. Strategically located receptacles in the following areas. These receptacles will be RED in color:
  - a. Student Commons
  - b. Kitchen/Servery

Load Breakdown for Legally Required Standby Power:

D. Equipment listed below is fed by legally required standby power:

1. Atrium smoke exhaust system.

DMP:jfm

Enc.

Cc: Carlos G. DeSousa, P.E., Garcia, Galuska & DeSousa, Inc.  
Christopher M. Garcia, P.E., Garcia, Galuska & DeSousa, Inc.  
Jose M. Carreiro, Garcia, Galuska & DeSousa, Inc.



**Generator Sizing Report**



**GARCIA • GALUSKA • DESOUSA**  
Consulting Engineers, Inc.

Project information

Project name: Fuller Middle School  
Customer's name: Jonathan Levi Architects  
Customer contact: Elizabeth Bugbee

Site requirements

Voltage:	277/480	Application:	Schools
Phase:	3	Emissions Requirement:	Stationary emergency (US EPA)
Frequency:	60Hz	Altitude:	180 Feet
Alt. Temp. Rise Duty:	130°C Standby	Max. Ambient Temp.:	82 Degrees F
Qty of Gensets:	1	Min. Genset Loading :	25 %
Fuel type:	Natural gas	Max. Genset Loading :	100 %
Country :	United States		

Site load requirements summary

Running kW:	269.94	Max. Starting kW:	100.50 in step 2
Running kVA:	307.37	Max. Starting kVA:	130.84 in step 2
Running P.F.:	0.88		

Generator selection

Genset Model:	300REZXB	Alternator:	4M4019	Rated kW :	300.00
Engine:	Doosan 18.3L	Alternator Leads:	12	Site Rated kW :	298.50
Emission level:	EPA Certified	Alt. Starting kVA at <b>35% V dip:</b>	1,730.00	UL 2200 Certified	
BHP:	530.00	Cal Alt Temp rise	80C		
Displacement:	1,115.00	with site loads:			
RPM:	1800	Excitation System :	PMG		

Generator Performance Summary

Voltage Dip Limit:	30.00 %	Calculated Voltage Dip:	4.36 %
Frequency Dip Limit:	10.00 %	Calculated Frequency Dip:	4.19 %
Harmonic Distortion Limit:	10.00 %	Calculated Harmonic Distortion:	7.72 %
		Calculated Genset % Loaded:	90.43 %

Report prepared by: david pereira

**TOTAL SYSTEM INTEGRATION**  
GENERATORS | TRANSFER SWITCHES | SWITCHGEAR | CONTROLS

The analysis provided from Power Solutions Center are for reference only. The installer must work with the local distributor and technician to confirm actual requirements when planning the installation. Kohler Co. reserves the right to change design or specifications without notice and without any obligation or liability whatsoever. Kohler Co. expressly disclaims any responsibility for consequential damages.

Report prepared by: david pereira

## **TOTAL SYSTEM INTEGRATION**

GENERATORS | TRANSFER SWITCHES | SWITCHGEAR | CONTROLS

The analysis provided from Power Solutions Center are for reference only. The installer must work with the local distributor and technician to confirm actual requirements when planning the installation. Kohler Co. reserves the right to change design or specifications without notice and without any obligation or liability whatsoever. Kohler Co. expressly disclaims any responsibility for consequential damages.


Software version: 1.0029.5.39

Tuesday, April 30, 2019

Model : 300REZXB, Alternator : 4M4019

Load Profile

Step # 1	Qty	Run		Start		Volt Dip %	Freq Dip %	Volt. Dist. %
		kW	kVA	kVA	kW			
Lighting Life Safety Lighting Evenly distributed LED Filtered Ballast	1	45.00	56.25	56.25	45.00			
Misc. Non-Linear Load Data Equipment 3 Phase IGBT	1	14.40	16.00	26.67	24.00			
Misc. Linear Load Fire alarm control panel 3 Phase	1	1.20	1.20	1.20	1.20			
Misc. Linear Load Hot food well 3 Phase Load Turns On/Off	1	4.00	4.00	4.00	4.00			
Misc. Linear Load Hot food well 3 Phase Load Turns On/Off	1	4.00	4.00	4.00	4.00			
Misc. Linear Load Disposer 3 Phase Load Turns On/Off	1	2.45	2.45	2.45	2.45			
<b>Step Total</b>		71.05	81.89	81.89	80.65	3.08	3.13	2.18
<b>Cum. Total</b>		71.05	81.89	81.89	80.65			




Report prepared by: david pereira

**TOTAL SYSTEM INTEGRATION**  
GENERATORS | TRANSFER SWITCHES | SWITCHGEAR | CONTROLS

The analysis provided from Power Solutions Center are for reference only. The installer must work with the local distributor and technician to confirm actual requirements when planning the installation. Kohler Co. reserves the right to change design or specifications without notice and without any obligation or liability whatsoever. Kohler Co. expressly disclaims any responsibility for consequential damages.

Step # 2	Qty	Run			Start			Volt Dip %	Freq Dip %	Volt. Dist. %
		kW	kVA	PF	kW	kVA	PF			
Lighting Additional shelter lighting Evenly distributed LED Filtered Ballast	1	50.00	62.50	0.80	50.00	62.50	0.80			
Air Conditioning DCUc-6 Phase B-C solid state current limit	1	1.38	1.38	1.00	2.62	4.15	0.63			
Air Conditioning DCUc-5 Phase A-B solid state current limit	1	1.38	1.38	1.00	2.62	4.15	0.63			
Air Conditioning DCUc-4 Phase A-C autotransformer w 65	1	1.38	1.38	1.00	3.82	6.07	0.63			
Air Conditioning DCUc-3 Phase A-C solid state current limit	1	1.38	1.38	1.00	2.62	4.15	0.63			
Air Conditioning DCUc-1 Phase A-B solid state current limit	1	3.69	3.69	1.00	6.09	11.08	0.55			
Office Equipment Office equipment 3 Phase	1	4.50	5.63	0.80	4.50	5.63	0.80			
Air Conditioning Walk in cooler 3 Phase soft start with ramp Load Turns On/Off	1	3.33	4.50	0.74	1.25	2.16	0.58			
Air Conditioning Walk in freezer 3 Phase soft start with ramp Load Turns On/Off	1	5.40	7.21	0.75	1.98	3.60	0.55			



Report prepared by: david pereira

**TOTAL SYSTEM INTEGRATION**  
GENERATORS | TRANSFER SWITCHES | SWITCHGEAR | CONTROLS

The analysis provided from Power Solutions Center are for reference only. The installer must work with the local distributor and technician to confirm actual requirements when planning the installation. Kohler Co. reserves the right to change design or specifications without notice and without any obligation or liability whatsoever. Kohler Co. expressly disclaims any responsibility for consequential damages.

Step # 2	Qty	Run			Start			Volt Dip %	Freq Dip %	Volt. Dist. %
		kW	kVA	PF	kW	kVA	PF			
Air Conditioning Reach in refrigerator Phase A-N solid state current limit Load Turns On/Off	1	0.67	0.98	0.68	0.67	0.98	0.68			
Office Equipment kitchen office and POS 3 Phase	1	4.50	5.63	0.80	4.50	5.63	0.80			
Air Conditioning Milk coolers 3 Phase wye delta closed Load Turns On/Off	2	3.48	4.90	0.71	0.99	1.62	0.61			
Motor P-1 20.00 HP 3 Phase Motor code : G Loaded NEMA Design VFD Load Turns On/Off	1	18.84	20.93	0.90	18.84	20.93	0.90			
<b>Step Total</b>		99.95	119.42	0.84	100.50	130.84	0.77	4.36	4.19	5.60
<b>Cum. Total</b>		171.00	201.23	0.85						


Report prepared by: david pereira

**TOTAL SYSTEM INTEGRATION**  
GENERATORS | TRANSFER SWITCHES | SWITCHGEAR | CONTROLS

The analysis provided from Power Solutions Center are for reference only. The installer must work with the local distributor and technician to confirm actual requirements when planning the installation. Kohler Co. reserves the right to change design or specifications without notice and without any obligation or liability whatsoever. Kohler Co. expressly disclaims any responsibility for consequential damages.

Software version: 1.0029.5.39

Step # 3	Qty	Run			Start			Volt Dip %	Freq Dip %	Volt. Dist. %
		kW	kVA	PF	kW	kVA	PF			
Misc. Linear Load Boiler-3 3 Phase Load Turns On/Off	1	2.34	2.34	1.00	2.34	2.34	1.00			
Misc. Linear Load Boiler-2 3 Phase Load Turns On/Off	1	2.34	2.34	1.00	2.34	2.34	1.00			
Air Conditioning DCUc-7 Phase A-C solid state current limit	1	1.38	1.38	1.00	2.62	4.15	0.63			
<b>Step Total</b>		6.07	6.07	1.00	7.30	7.98	0.91	0.25	0.20	5.60
<b>Cum. Total</b>		177.07	206.41	0.86						




Report prepared by: david pereira

**TOTAL SYSTEM INTEGRATION**  
GENERATORS | TRANSFER SWITCHES | SWITCHGEAR | CONTROLS

The analysis provided from Power Solutions Center are for reference only. The installer must work with the local distributor and technician to confirm actual requirements when planning the installation. Kohler Co. reserves the right to change design or specifications without notice and without any obligation or liability whatsoever. Kohler Co. expressly disclaims any responsibility for consequential damages.

Step # 4	Qty	Run			Start			Volt Dip %	Freq Dip %	Volt. Dist. %
		kW	kVA	PF	kW	kVA	PF			
Motor RTU-1 supply air 25.00 HP 3 Phase Motor code : G Loaded NEMA Design VFD	2	46.83	52.03	0.90	46.83	52.03	0.90			
Motor RTU-1 return air 15.00 HP 3 Phase Motor code : G Loaded NEMA Design VFD	2	28.75	31.94	0.90	28.75	31.94	0.90			
<b>Step Total</b>		75.58	83.97	0.90	75.58	83.97	0.90	2.96	2.87	7.72
<b>Cum.Total</b>		252.65	290.15	0.87						




Report prepared by: david pereira

**TOTAL SYSTEM INTEGRATION**  
GENERATORS | TRANSFER SWITCHES | SWITCHGEAR | CONTROLS

The analysis provided from Power Solutions Center are for reference only. The installer must work with the local distributor and technician to confirm actual requirements when planning the installation. Kohler Co. reserves the right to change design or specifications without notice and without any obligation or liability whatsoever. Kohler Co. expressly disclaims any responsibility for consequential damages.



Step # 6	Qty	Run			Start			Volt Dip %	Freq Dip %	Volt. Dist. %
		kW	kVA	PF	kW	kVA	PF			
Misc. Linear Load Kitchen equipment 3 Phase Load Turns On/Off	4	5.76	7.21	0.80	5.76	7.21	0.80			
Misc. Linear Load convection ovens 3 Phase Load Turns On/Off	4	11.53	11.53	1.00	11.53	11.53	1.00			
<b>Step Total</b>		17.29	17.82	0.97	17.29	17.82	0.97	0.60	0.50	7.72
<b>Cum. Total</b>		269.94	307.37	0.88						




Report prepared by: david pereira

**TOTAL SYSTEM INTEGRATION**  
GENERATORS | TRANSFER SWITCHES | SWITCHGEAR | CONTROLS

The analysis provided from Power Solutions Center are for reference only. The installer must work with the local distributor and technician to confirm actual requirements when planning the installation. Kohler Co. reserves the right to change design or specifications without notice and without any obligation or liability whatsoever. Kohler Co. expressly disclaims any responsibility for consequential damages.

Software version: 1.0029.5.39

Loads Turning OFF and ON	Qty	Run		Start			Volt Dip %	Freq Dip %	Volt. Dist. %
		kW	kVA	PF	kW	kVA			
Misc. Linear Load Boiler-3 3 Phase Load Turns On/Off	1	2.34	2.34	1.00	2.34	2.34	1.00		
Misc. Linear Load Boiler-2 3 Phase Load Turns On/Off	1	2.34	2.34	1.00	2.34	2.34	1.00		
Air Conditioning Walk in cooler 3 Phase soft start with ramp Load Turns On/Off	1	3.33	4.50	0.74	1.25	2.16	0.58		
Air Conditioning Walk in freezer 3 Phase soft start with ramp Load Turns On/Off	1	5.40	7.21	0.75	1.98	3.60	0.55		
Misc. Linear Load Kitchen equipment 3 Phase Load Turns On/Off	4	5.76	7.21	0.80	5.76	7.21	0.80		
Misc. Linear Load convection ovens 3 Phase Load Turns On/Off	4	11.53	11.53	1.00	11.53	11.53	1.00		
Air Conditioning Reach in refrigerator Phase A-N solid state current limit Load Turns On/Off	1	0.67	0.98	0.68	0.67	0.98	0.68		
Misc. Linear Load Hot food well 3 Phase Load Turns On/Off	1	4.00	4.00	1.00	4.00	4.00	1.00		



Report prepared by: david pereira

**TOTAL SYSTEM INTEGRATION**  
GENERATORS | TRANSFER SWITCHES | SWITCHGEAR | CONTROLS

The analysis provided from Power Solutions Center are for reference only. The installer must work with the local distributor and technician to confirm actual requirements when planning the installation. Kohler Co. reserves the right to change design or specifications without notice and without any obligation or liability whatsoever. Kohler Co. expressly disclaims any responsibility for consequential damages.

Loads Turning OFF and ON	Qty	Run			Start			Volt Dip %	Freq Dip %	Volt. Dist. %
		kW	kVA	PF	kW	kVA	PF			
Misc. Linear Load Hot food well 3 Phase Load Turns On/Off	1	4.00	4.00	1.00	4.00	4.00	1.00			
Air Conditioning Milk coolers 3 Phase wye delta closed Load Turns On/Off	2	3.48	4.90	0.71	0.99	1.62	0.61			
Misc. Linear Load Disposer 3 Phase Load Turns On/Off	1	2.45	2.45	1.00	2.45	2.45	1.00			
Motor P-1 20.00 HP 3 Phase Motor code : G Loaded NEMA Design VFD Load Turns On/Off	1	18.84	20.93	0.90	18.84	20.93	0.90			
<b>Step Total</b>		64.15	69.00	0.93	56.15	59.68	0.94	2.12	1.97	
<b>Cum. Total</b>		269.94	307.37	0.88						
<b>Grand Total</b>		269.94	307.37	0.88				4.36	4.19	7.72

Report prepared by: david pereira

**TOTAL SYSTEM INTEGRATION**  
GENERATORS | TRANSFER SWITCHES | SWITCHGEAR | CONTROLS

The analysis provided from Power Solutions Center are for reference only. The installer must work with the local distributor and technician to confirm actual requirements when planning the installation. Kohler Co. reserves the right to change design or specifications without notice and without any obligation or liability whatsoever. Kohler Co. expressly disclaims any responsibility for consequential damages.

Software version: 1.0029.5.39

**Generator Cut Sheet**






**EPA-Certified for Stationary  
Emergency Applications**

## Ratings Range

		60 Hz
Standby:	kW	230- 300
	kVA	230- 375



## Standard Features

- Kohler Co. provides one-source responsibility for the generating system and accessories.
- The generator set and its components are prototype-tested, factory-built, and production-tested.
- The 60 Hz generator set offers a UL 2200 listing.
- The generator set accepts rated load in one step.
- The 60 Hz generator set meets NFPA 110, Level 1, when equipped with the necessary accessories and installed per NFPA standards.
- A one-year limited warranty covers all generator set systems and components. Two- and five-year extended limited warranties are also available.
- Alternator features:
  - The unique Fast-Response® II excitation system delivers excellent voltage response and short-circuit capability using a permanent magnet (PM)-excited alternator.
  - The brushless, rotating-field alternator has broadrange reconnectability.

## Generator Set Ratings

Alternator	Voltage	Ph	Hz	Rich-Burn Natural Gas 130°C Rise Standby Rating	
				kW/kVA	Amps
4UA13	120/208	3	60	300/375	1041
4UA13	127/220	3	60	300/375	985
4UA13	120/240	1	60	230/230	959
4UA13	120/240	3	60	300/375	903
4UA13	139/240	3	60	300/375	903
4UA13	220/380	3	60	280/350	532
4UA13	240/416	3	60	300/375	521
4UA13	277/480	3	60	300/375	452
4UA13	347/600	3	60	300/375	361

RATINGS: All three-phase units are rated at 0.8 power factor. *Standby Ratings:* The standby rating is applicable to varying loads for the duration of a power outage. There is no overload capability for this rating. Ratings are in accordance with ISO-8528-1 and ISO-3046-1. Obtain technical information bulletin (TIB-101) for ratings guidelines, complete ratings definitions, and site condition derates. The generator set manufacturer reserves the right to change the design or specifications without notice and without any obligation or liability whatsoever.

# Alternator Specifications

Specifications	Alternator
Manufacturer	Kohler
Type	4-Pole, Rotating-Field
Exciter type	Brushless, Permanent-Magnet
Leads: quantity, type	12, Reconnectable
Voltage regulator	Solid State, Volts/Hz
Insulation:	NEMA MG1
Material	Class H
Temperature rise	130°C, Standby
Bearing: quantity, type	1, Sealed
Coupling	Flexible Disc
Amortisseur windings	Full
Voltage regulation, no-load to full-load	Controller Dependent
One-step load acceptance	100% of Rating
Unbalanced load capability	100% of Rated Standby Current
Peak motor starting kVA:	(35% dip for voltages below)
480 V	4UA13
	990 (60Hz)

- NEMA MG1, IEEE, and ANSI standards compliance for temperature rise and motor starting.
- Sustained short-circuit current of up to 300% of the rated current for up to 10 seconds.
- Sustained short-circuit current enabling downstream circuit breakers to trip without collapsing the alternator field.
- Self-ventilated and dripproof construction.
- Windings are vacuum-impregnated with epoxy varnish for dependability and long life.
- Superior voltage waveform from a two-thirds pitch stator and skewed rotor.
- Fast-Response® II brushless alternator with brushless exciter for excellent load response.

## Application Data

### Engine

Engine Specifications	
Manufacturer	Doosan
Engine model	D146L
Engine type	14.6 L, 4-Cycle, Turbocharged, Aftercooled
Cylinder arrangement	V-8
Displacement, L (cu. in.)	14.6 (892)
Bore and stroke, mm (in.)	128 x 142 (5.04 x 5.59)
Compression ratio	10.5:1
Piston speed, m/min. (ft./min.)	511 (1677)
Main bearings: quantity, type	10, Precision Half-Shell
Rated rpm	1800
Max. power at rated rpm, kWm (BHP)	342 (459)
Cylinder head material	Cast Iron
Piston: type, material	—
Crankshaft material	Forged Steel
Valve material	—
Governor: type	Electronic
Frequency regulation, no-load to full-load	Isochronous
Frequency regulation, steady state	±0.5%
Frequency	Fixed
Air cleaner type, all models	Dry

### Exhaust

Exhaust System	
Exhaust manifold type	Wet
Exhaust flow at rated kW, kg/hr. (cfm)	1308 (1895)
Exhaust temperature at rated kW, dry exhaust, °C (°F)	732 (1350)
Maximum allowable back pressure overall, kPa (in. Hg)	10.2 (3)
Maximum allowable back pressure after catalyst, kPa (in. Hg)	5.1 (1.5)
Engine exhaust outlet size, mm (in.)	Flanged Outlet at Catalyst, see ADV drawing

### Engine Electrical

Engine Electrical System		
Battery charging alternator:		
Ground (negative/positive)		Negative
Volts (DC)		24
Ampere rating		45
Starter motor rated voltage (DC)		24
Battery, recommended cold cranking amps (CCA):		
Qty., CCA rating each		Two, 1000
Battery voltage (DC)		12

### Fuel

Fuel System - Rich Burn	
Fuel type	Natural Gas
Fuel supply line inlet	2.0 NPTF
Natural gas fuel supply pressure, kPa (in. H <sub>2</sub> O)	1.74-2.74 (7.0- 11.0)
Fuel supply pressure, measured at the generator set fuel inlet downstream of any fuel system equipment accessories.	

Fuel Composition Limits *	Nat. Gas
Methane, % by volume	90 min.
Ethane, % by volume	4.0 max.
Propane, % by volume	1.0 max.
Propene, % by volume	0.1 max.
C <sub>4</sub> and higher, % by volume	0.3 max.
Sulfur, ppm mass	25 max.
Lower heating value, MJ/m <sup>3</sup> (Btu/ft <sup>3</sup> ), min.	33.2 (890)

\* Fuels with other compositions may be acceptable. If your fuel is outside the listed specifications, contact your local distributor for further analysis and advice.

# Application Data

## Lubrication

### Lubricating System

Type	Full Pressure
Oil pan capacity, L (qt.) §	40 (42.3)
Oil pan capacity with filter, L (qt.) §	47.1 (49.7)
Oil filter: quantity, type §	2, Cartridge
Oil cooler	Water-Cooled
§ Kohler recommends the use of Kohler Genuine oil and filters.	

## Cooling

### Radiator System

Ambient temperature, °C (°F) *	50 (122)
Engine jacket water capacity, L (gal.)	43.2 (9.5)
Radiator system capacity, including engine, L (gal.)	227.3 (50)
Engine jacket water flow, Lpm (gpm)	680 (180)
Heat rejected to cooling water at rated kW, dry exhaust, kW (Btu/min.)	284 (16189)
Heat rejected to air charge cooler at rated kW, dry exhaust, kW (Btu/min.)	47 (2670)
Water pump type	Centrifugal
Fan diameter, including blades, mm (in.)	1143 (45)
Fan, kWm (HP)	16 (22)
Max. restriction of cooling air, intake and discharge side of radiator, kPa (in. H <sub>2</sub> O)	0.125 (0.5)

\* Weather and sound enclosures with internal silencer reduce ambient temperature capability by 8°C (15°F).

## Operation Requirements

### Air Requirements

Radiator-cooled cooling air, m <sup>3</sup> /min. (scfm) †	638 (22500)
Combustion air, kg/hr. (cfm)	1227 (687)
Heat rejected to ambient air:	
Engine, kW (Btu/min.)	66 (3765)
Alternator, kW (Btu/min.)	23 (1309)


† Air density = 1.20 kg/m<sup>3</sup> (0.075 lbm/ft<sup>3</sup>)

### Fuel Consumption‡

Natural Gas, m <sup>3</sup> /hr. (cfh) at % load	Standby Rating
100%	85.4 (3015)
75%	68.8 (2428)
50%	52.2 (1843)
25%	38.1 (1345)

‡ Nominal fuel rating: Natural gas, 37 MJ/m<sup>3</sup> (1000 Btu/ft.<sup>3</sup>)

## Controllers



### APM402 Controller

Provides advanced control, system monitoring, and system diagnostics for optimum performance and compatibility.

- Digital display and menu control provide easy local data access
  - Measurements are selectable in metric or English units
  - Remote communication thru a PC via network or serial configuration
  - Controller supports Modbus® protocol
  - Integrated hybrid voltage regulator with ±0.5% regulation
  - Built-in alternator thermal overload protection
  - NFPA 110 Level 1 capability
- Refer to G6-161 for additional controller features and accessories.

Modbus® is a registered trademark of Schneider Electric.

## Standard Features

- Alternator Protection
- Battery Rack and Cables
- Closed Crankcase Ventilation (CCV) with Filters
- Integral Vibration Isolation
- Local Emergency Stop Switch
- Low Coolant Level Shutdown
- Oil Drain Extension
- Operation and Installation Literature
- Three-Way Exhaust Catalyst

## Available Options

### Approvals and Listings

- CSA Certified
- IBC Seismic Certification
- UL 2200 Listing
- Hurricane Rated Enclosure

### Enclosed Unit

- Sound Enclosure with Internal Silencer (Aluminum)
- Sound Enclosure with Internal Silencer (Steel)
- Weather Enclosure with Internal Silencer (Steel)

### Open Unit

- Exhaust Silencer, Critical (kit: PA-324470)
- Flexible Exhaust Connector, Stainless Steel

### Fuel System

- Flexible Fuel Lines  
(required when the generator set skid is spring mounted)
- Gas Filter
- Secondary Gas Solenoid Valve

### Controller

- Communications Products and PC Software
- Two Input/Five Output Module

- Remote Serial Annunciator Panel
- Run Relay
- Manual Speed Adjust

### Cooling System

- Block Heater; 2500 W, 120 V, 1 Ph
- Block Heater; 6000 W, 208 V, 1 Ph
- Block Heater; 6000 W, 240 V, 1 Ph or 3 Ph
- Block Heater; 6000 W, 480 V, 1 Ph  
Recommended for ambient temperatures below 10°C (50°F)
- Radiator Duct Flange

## Electrical System

- Alternator Strip Heater
- Battery
- Battery Charger, Equalize/Float Type
- Battery Charger Temperature Compensation
- Battery Heater
- Line Circuit Breaker (NEMA1 enclosure)
- Line Circuit Breaker with Shunt Trip (NEMA1 enclosure)

## Miscellaneous

- Air Cleaner Restriction Indicator
- Certified Test Report
- Engine Fluids Added
- Rated Power Factor Testing
- Rodent Guards

## Literature

- General Maintenance
- NFPA 110
- Overhaul
- Production

## Warranty


- 2-Year Basic Limited Warranty
- 5-Year Basic Limited Warranty
- 5-Year Comprehensive Limited Warranty

## Other Options

- \_\_\_\_\_
- \_\_\_\_\_
- \_\_\_\_\_
- \_\_\_\_\_

## Dimensions and Weights

Overall Size, L x W x H, max., mm (in.): 3500 x 1750 x 2148  
 (137.8 x 68.9 x 84.6)  
 Weight (radiator model), wet, max., kg (lb.): 3200 (7055)




NOTE: This drawing is provided for reference only and should not be used for planning installation. Contact your local distributor for more detailed information.

**DISTRIBUTED BY:**







REV	DATE	DESCRIPTION	BY	CHKD	DATE
1	6-2-11	NEW DRAWING (303942)	GFR	JMS	6-2-11
2	7-17-17	EMERGENCY STOP LOCATION ADDED. (B-11) VIEW REMOVED. SEE SHEET I LC1125008	GFR	JMS	7-17-17
3	7-17-17	EMERGENCY STOP LOCATION ADDED. (B-11) VIEW REMOVED. SEE SHEET I LC1125008	GFR	JMS	7-17-17
4	7-17-17	EMERGENCY STOP LOCATION ADDED. (B-11) VIEW REMOVED. SEE SHEET I LC1125008	GFR	JMS	7-17-17
5	7-17-17	EMERGENCY STOP LOCATION ADDED. (B-11) VIEW REMOVED. SEE SHEET I LC1125008	GFR	JMS	7-17-17
6	7-17-17	EMERGENCY STOP LOCATION ADDED. (B-11) VIEW REMOVED. SEE SHEET I LC1125008	GFR	JMS	7-17-17
7	7-17-17	EMERGENCY STOP LOCATION ADDED. (B-11) VIEW REMOVED. SEE SHEET I LC1125008	GFR	JMS	7-17-17
8	7-17-17	EMERGENCY STOP LOCATION ADDED. (B-11) VIEW REMOVED. SEE SHEET I LC1125008	GFR	JMS	7-17-17

REV	DATE	DESCRIPTION	BY	CHKD	DATE
1	6-2-11	NEW DRAWING (303942)	GFR	JMS	6-2-11
2	7-17-17	EMERGENCY STOP LOCATION ADDED. (B-11) VIEW REMOVED. SEE SHEET I LC1125008	GFR	JMS	7-17-17
3	7-17-17	EMERGENCY STOP LOCATION ADDED. (B-11) VIEW REMOVED. SEE SHEET I LC1125008	GFR	JMS	7-17-17
4	7-17-17	EMERGENCY STOP LOCATION ADDED. (B-11) VIEW REMOVED. SEE SHEET I LC1125008	GFR	JMS	7-17-17
5	7-17-17	EMERGENCY STOP LOCATION ADDED. (B-11) VIEW REMOVED. SEE SHEET I LC1125008	GFR	JMS	7-17-17
6	7-17-17	EMERGENCY STOP LOCATION ADDED. (B-11) VIEW REMOVED. SEE SHEET I LC1125008	GFR	JMS	7-17-17
7	7-17-17	EMERGENCY STOP LOCATION ADDED. (B-11) VIEW REMOVED. SEE SHEET I LC1125008	GFR	JMS	7-17-17
8	7-17-17	EMERGENCY STOP LOCATION ADDED. (B-11) VIEW REMOVED. SEE SHEET I LC1125008	GFR	JMS	7-17-17

**KOHLER CO. METRIC | PROE**  
 POWER SYSTEMS, KOHLER, WI 53044, U.S.A.  
 PROPERTY AND MUST NOT BE REPRODUCED WITHOUT THE WRITTEN PERMISSION OF KOHLER CO.  
 DESIGN OR INTENTIONALLY MISLEADING.

**300-350kW DOOSAN ENCLOSURE W/LIFTING BASE**

DATE: 6-2-11  
 CHKD: JMS  
 APPRVD: JMS

SCALE: 0.05  
 SHEET 2 OF 3

ADV-8162





Fuller Middle School  
Framingham, MA  
J#680 015 00.00  
L#60589/Page 1/ October 18, 2019

**TECHNOLOGY SYSTEMS**

**NARRATIVE REPORT**

The following is the Technology Systems narrative, which defines the scope of work and capacities of the Communications system infrastructure, as well as, the Basis of Design.

1. CODES

- A. All work installed under Section 270000 shall comply with the Massachusetts Building Code, IBC 2009, and all local, county, and federal codes, laws, statues, and authorities having jurisdiction.

2. DESIGN INTENT

- A. All work is new and consists of furnishing all materials, equipment, labor, transportation, facilities, and all operations and adjustments required for the complete and operating installation of the Technology and Security work and all items incidental thereto, including commissioning and testing.

3. TECHNOLOGY

- A. The data system infrastructure will consist of fiber optic backbone cabling. Horizontal wiring will consist of Category 6A UTP Non-Plenum rated cabling for both data and telephone systems for gigabit connectivity. The telephone infrastructure will accommodate VOIP based voice systems. A new IP telephone system will be used.
- B. Each classroom will have two (2) data outlets for student computers. Two (2) data with video and audio connections to a wall mounted touch screen monitor will be provided at teacher's station. A wall phone will be provided for communications with administration in each classroom. Wireless access points will be provided in all classrooms and other spaces with two (2) CAT6A cables.
- C. A central paging system will be provided and integrated with the telephone system. The speakers shall be IP.
- D. A wireless GPS/LAN based master clock system will be provided with 120V wireless remote clocks that act as transceivers.
- E. The Main Distribution Frame (MDF) will contain all core network switching and IP voice switch. Intermediate Distribution Frames (IDFs) will serve each floor/wing of the school. A fiber optic backbone will be provided from each IDF to MDF. The backbone will be designed for 10 Gbps Ethernet.

Fuller Middle School  
Framingham, MA  
J#680 015 00.00  
L#60589/Page 2/ October 18, 2019

4. TESTING REQUIREMENTS

The Technology Contractor shall provide testing of the following systems with the Owner and Owner's Representative present:

- Telephone and data cabling
- Fiber optic backbone cabling
- Paging system
- Wireless clock system

Testing reports shall be submitted to the Engineer for review and approval before providing to the Owner.

5. OPERATION MANUALS AND MAINTENANCE MANUALS

When the project is completed, the Technology Contractor shall provide operation and maintenance manuals to the Owner.

6. RECORD DRAWINGS AND CONTROL DOCUMENTS

When the project is completed, an as-built set of drawings, showing all lighting and power requirements from contract and addendum items, will be provided to the Owner.

7. COMMISSIONING

The project shall be commissioned per Commissioning Section of the specifications.

### 3.1.3 Building Code Analysis

Please reference the attached Building Code Analysis.





# Fire Protection and Life Safety Code Compliance Strategy

**FRAMINGHAM FULLER MIDDLE SCHOOL  
FRAMINGHAM, MA**

Prepared For:



Jonathan Levi Architects  
266 Beacon Street  
Boston, MA 02116

Prepared By:



101 Longwater Circle, Suite 203  
Norwell, MA 02061  
Phone: 781.878.3500  
Fax: 781.878.3551

**SUBMITTED: OCTOBER 15, 2019**  
90% Construction Documents - MSBA Submission

**Table of Contents**

**DOCUMENT HISTORY .....4**

**PURPOSE.....4**

**APPLICABLE CODES AND REQUIREMENTS.....5**

**PROJECT DESCRIPTION .....5**

**GENERAL OPERATING ASSUMPTIONS.....5**

**NEW CONSTRUCTION- CODE COMPLIANCE APPROACH .....6**

    OCCUPANCY CLASSIFICATION .....6

    OCCUPANCY SEPARATIONS .....6

**BUILDING CONSTRUCTION.....7**

    CONSTRUCTION TYPE .....7

    FIRE RESISTANCE RATING .....7

*Fire Resistance Ratings of Structural Elements for Type IB Construction .....8*

*Roof Rating Approach.....8*

    EXTERIOR WALLS.....9

*Interior Finishes and Floor Finishes .....10*

*Interior Wall & Ceiling Finish Requirements by Occupancy .....11*

*Interior Floor Finish Requirements by Occupancy.....11*

    LABORATORY HAZARDOUS CHEMICAL STORAGE .....11

*Control Area Approach.....11*

*MSBC Table 414.2.2 Design and Number of Control Areas.....12*

*Fire Code Requirements for Hazardous Chemicals.....12*

*Most restrictive requirements NFPA 30 and NFPA 45-.....13*

*NFPA 45 Laboratory Installation Requirements .....15*

*NFPA 45 Requirements for Maximum Allowable Quantities of Flammable Liquids.....15*

*NFPA 45 Instructional Laboratory classification .....17*

*Summary of the Maximum Allowable Quantities from IBC, NFPA 30 and NFPA 45.....17*

    PENETRATIONS OF DUCT AND AIR TRANSFER OPENINGS .....18

*MEP Shaft Enclosures.....18*

*Fire Dampers .....18*

*Smoke Dampers.....19*

*Combination Smoke/ Fire Dampers .....19*

*Through Penetration Protection .....20*

*Damper Exceptions .....20*

*Protected Vertical Openings .....21*

    ATRIUM DESIGN .....21

    STAGE DESIGN.....22

**MEANS OF EGRESS SYSTEM DESIGN.....24**

    GENERAL REQUIREMENTS .....24

*Occupant Load.....24*

*Arrangement of Means of Egress (MSBC Section 1007.1.1).....26*

*Exit Capacities .....26*

*Exit Access Travel Distance (MSBC Section 1017) .....27*

*Dead End Corridor Limits (MSBC Section 1020.4).....28*

*Exit Access Corridors (MSBC Section 1020).....28*

*Exit Stair Discharge.....28*

*Doors (MSBC Section 1010).....29*

*Exit signage (MSBC Section 1013) .....29*

*Means of Egress Lighting (MSBC Section 1008).....30*

    SUMMARY OF FIRE PROTECTION FEATURES .....31

AUTOMATIC SPRINKLER PROTECTION ..... 31  
STANDPIPES ..... 32  
FIRE ALARM ..... 32  
    *Manual Fire Alarm Pull Stations* ..... 32  
SMOKE CONTROL ..... 32  
EMERGENCY POWER..... 33  
ELEVATOR PROVISIONS ..... 33  
PORTABLE FIRE EXTINGUISHERS ..... 34  
    *Actual Mounting Locations (2013 Edition NFPA 10)* ..... 34  
FIRE DEPARTMENT ACCESS ..... 35  
EMERGENCY RESPONDER RADIO COVERAGE ..... 35  
**ACCESSIBILITY ..... 36**  
    GENERAL REQUIREMENTS ..... 36  
**PLUMBING FIXTURES ..... 39**  
**CONCLUSION ..... 41**  
**APPENDIX A: SMOKE CONTROL BASIS OF DESIGN ..... 42**

## **DOCUMENT HISTORY**

<i>50% Schematic Design Fire Protection and Life Safety Code Compliance Strategy .....</i>	<i>August 8, 2018</i>
<i>100% Schematic Design Fire Protection and Life Safety Code Compliance Strategy .....</i>	<i>September 7, 2018</i>
<i>75% Design Development Fire Protection and Life Safety Code Compliance Strategy .....</i>	<i>April 8, 2019</i>
<i>100% Design Development Fire Protection and Life Safety Code Compliance Strategy .....</i>	<i>May 13, 2019</i>
<i>50% Construction Document Fire Protection and Life Safety Code Compliance Strategy .....</i>	<i>July 8, 2019</i>
<i>60% Construction Document Fire Protection and Life Safety Code Compliance Strategy .....</i>	<i>August 9, 2019</i>
<i>90% Construction Document Fire Protection and Life Safety Code Compliance Strategy .....</i>	<i>August 29, 2019</i>
<i>90% Construction Document Fire Protection and Life Safety Code Compliance Strategy .....</i>	<i>October 15, 2019</i>

This document “Concept Design Fire Protection and Life Safety Code Compliance Strategy” is intended for use by the design team and code officials for understanding the building design concept for the proposed Framingham Fuller Middle School located in Framingham, MA. This document contains the code basis for the building design, functionality of the egress system, fire protection recommendations, the smoke control system design concept, and a comprehensive code outline.

This document is a draft based on the building plans from Jonathan Levi Architects dated October 15, 2019. This document is a work in progress, will be updated as the design progresses and discussions/agreements with the Authorities Having Jurisdiction occur.

## **PURPOSE**

The purpose of this report is to document and provide the code compliance strategy, including the framework for the fire protection and life safety concept, for the Framingham Fuller Middle School in Framingham, MA. This document will also identify design concepts that are not clearly addressed by the applicable building codes, which will require approval and or interpretation by the authorities having jurisdiction (AHJ).

## **APPLICABLE CODES AND REQUIREMENTS**

The following codes are presently adopted in the State of Massachusetts:

- **Building**                      Massachusetts State Building Code (MSBC), 9<sup>th</sup> Edition, which adopts and amends the 2015 International Building Code and the 2015 International Existing Building Code (IEBC).
- **Accessibility**                Massachusetts Architectural Access Board (MAAB), 521-CMR.  
2010 ADA Standards for Accessible Design
- **Electrical**                     Massachusetts Electrical Code, 527 CMR, 12.00. The Massachusetts Electrical Code is an amended version of the 2017 National Electrical Code (NFPA 70).
- **Elevators**                     Massachusetts Elevator Regulations, 524-CMR.
- **Energy**                        2015 Edition of the International Energy Conservation Code (IECC) as amended by the State of Massachusetts; Massachusetts Stretch Code
- **Fire Prevention**            527 CMR Massachusetts Fire Prevention Code, which adopts and amends the 2015 edition of NFPA 1.
- **Mechanical**                International Mechanical Code, 2015 edition, as adopted and amended by the MSBC (Chapter 28).
- **Plumbing**                    Massachusetts Fuel Gas and Plumbing Codes (248 CMR).
- **Other**                         National Fire Protection Association (NFPA) Standards, as referenced by the MSBC and the MFPR.

## **PROJECT DESCRIPTION**

Howe Engineers has prepared this document for the Framingham Fuller Middle School located in Framingham, MA. The proposed building will be a newly constructed, three (3) story building with a footprint area of approximately 64,780 square feet. The building contains primarily Group E Educational spaces for middle school students (6<sup>th</sup> to 8<sup>th</sup> grade), with accessory office and lounge spaces. There is a gymnasium and auditorium on the north side of the building that will be considered Group A-3 assembly spaces as public events will be held in these spaces.

This narrative addresses the requirements contained in the 9th edition of 780 CMR, The Massachusetts State Building Code (MSBC), which is an amended version of the 2015 International Building Code (IBC).

## **GENERAL OPERATING ASSUMPTIONS**

The following general operating assumptions serve as the basis for the Life Safety and Fire Protection design and should be incorporated into the new facilities operations plan. It is the responsibility of the Owner/Operator to ensure that these assumptions are enforced:

- The materials used shall meet the interior finish requirements of the International Building, and NFPA 1.
- Hazardous materials and explosives are not permitted within the Building unless protected in accordance with the International Building and Fire Codes and approved by the Authority Having Jurisdiction.

**NEW CONSTRUCTION- CODE COMPLIANCE APPROACH**

***OCCUPANCY CLASSIFICATION***

The proposed Fuller School is classified as Mixed Use, containing Educational, Group E Occupancies, along with Assembly Group A and Business Group B Occupancies. The building serves as an educational building for students from the 6<sup>th</sup> through 8<sup>th</sup> grade containing primarily classroom spaces. There is a gymnasium and auditorium on the north side of the building which will likely hold events for the general public. As these spaces will hold events for the public, they must be considered Assembly spaces as they will accommodate occupants other than the students of the Fuller School. The occupancies in the building on the respective levels are as follows:

<b>First Floor (Level of Exit Discharge)</b>	<b>USE GROUP</b>
Classrooms / Lab Spaces	E
Gymnasium	A-4
Auditorium / Lounge Space	A-3
Office / Administration	B
Storage	S-1
MEP	S-2
<b>Second Floor</b>	<b>USE GROUP</b>
Classrooms	E
Office / Administration	B
Lounge / Breakout Space	A-3
Storage	S-1
MEP	S-2
<b>Third Floor</b>	<b>USE GROUP</b>
Classrooms	E
Office / Administration	B
Lounge / Breakout Space	A-3
Storage	S-1
MEP	S-2

***OCCUPANCY SEPARATIONS***

The Building contains a number of different occupancies, not included in the same occupancy group, within the building and is classified as Mixed-Use Occupancy in accordance with MSBC Section 508.1. Therefore, the building is required to comply with the requirements of either Section 508.3 (non-separated uses) or Section 508.4 (separated uses), or combinations of these sections. As the gymnasium, auditorium, and cafeteria on the first floor of the building will be used for public events, they must be considered assembly spaces. A nonseparated, mixed-use approach will be used for the design of the building to limit the required rated separations between occupancies. Refer to the Building Construction section below for minimum construction type necessary to allow for the application of the nonseparated mixed-use provisions.

## **BUILDING CONSTRUCTION**

### ***CONSTRUCTION TYPE***

The Framingham Fuller School will be newly constructed using a nonseparated mixed-use approach. The building is three (3) stories in height, containing primarily Group A and E occupancies, with Group A Assembly spaces primarily consisting of the Gymnasium, Auditorium, and Cafeteria on the first floor. The building will be designed as Type IB fire resistive, non-combustible construction.

Under Type IB Construction, Group E occupancies are permitted to be six (6) stories in height with unlimited area per floor. Group A occupancies are permitted to be twelve (12) stories in height with unlimited area per floor. As the gymnasium, auditorium, and cafeteria will be used for public events, they are classified as Group A-3 spaces, while the balance of the school is classified as Group E educational use. The current design does not include occupancy separations as the building is permitted to be unlimited in area. As the building is 3-stories in height and permitted to have unlimited area, the current design is compliant.

In order to demonstrate compliance with the allowable building area requirements of MSBC Section 506, the sum of the ratios on each floor must be individually analyzed. This approach involves taking the area of each occupancy, and dividing this area by the allowable area of each occupancy on a floor-by-floor basis (MSBC Section 506.2.4). As the building is permitted to have unlimited area on each floor, the sum of the ratios calculation is not applicable.

As the building will be of Type IB construction, the stairs and shafts must be constructed of 2-hour construction as Type IB requires a 2-hour rated floor assembly.

### ***FIRE RESISTANCE RATING***

The fire-resistance rating requirements for Type IB construction can be found in MSBC Table 601. The fire-resistance ratings for the building structural elements are as follows:

**Fire Resistance Ratings of Structural Elements for Type IB Construction**

BUILDING STRUCTURAL ELEMENT	FIRE RESISTANCE RATING – TYPE IB
<b>Structural Frame</b> Including girders, beams and trusses (other than columns): Supporting a floor Supporting roof only Columns: Supporting a floor Supporting roof only	2-hour 1-hour 2-hour 1-hour
<b>Bearing Walls</b> Exterior Interior Walls: Supporting more than one floor Supporting only roof	2-hour 2-hour 2-hour
<b>Nonbearing Walls and Partitions</b> Exterior ( <i>not less than fire separation requirements</i> ) Interior ( <i>not less than fire separation requirements</i> )	See Fire Separation 0-hours
<b>Floor Construction</b> Including supporting beams and joists	2-hour
<b>Roof Construction</b> <i>Including supporting beams and joists:</i> Less than 20' in height to lowest member 20' or more in height to lowest member	1-hours 0-hours

**Roof Rating Approach**

MSBC Table 601 (summarized above) governs the required fire resistance rating of structural members in Type IB construction. Both the proposed gymnasium and auditorium spaces are designed with high ceilings (in excess of 20-feet). Roof construction and associated secondary members for buildings of Type IB construction are required to be provided with a 1-hour fire resistance rating in accordance with MSBC Table 601. Table 601 provides that fire protection of structural roof members (including decking) is not required where every part of the roof construction is 20 feet or more above any floor immediately below. The 2018 IBC, though not applicable, provides guidance on the requirements outlined in Table 601. Table 601 permits the reduction in roof rating for all primary and secondary structural members where the roof is located more than 20 feet above the any floor immediately below. Primary structural frame is defined as follows:

**[BG] PRIMARY STRUCTURAL FRAME.** The primary structural frame shall include all of the following structural members:

1. The columns.
2. Structural members having direct connections to the columns, including girders, beams, trusses and spandrels.
3. Members of the floor construction and roof construction having direct connections to the columns.
4. Bracing members that are essential to the vertical stability of the primary structural frame under gravity loading shall be considered part of the primary structural frame whether or not the bracing member carries gravity loads.



As such, columns, structural roof members connecting directly to columns, and members needed for vertical stability of the building still require a 1-hour rating in accordance with Table 601, but other roof members are permitted to be non-rated in accordance with Footnote B of Table 601. Additionally, the 2018 IBC commentary provides further guidance on the intent of the code regarding the rating of primary and secondary roof members (below). As the proposed roof in both the auditorium and gymnasium is greater than 20 feet above the floor below, the design team has requested to utilize Footnote B of Table 601 to rate only the columns with none of the roof members located in or at the roof, including primary members, being rated.

Note b<sup>7</sup> applies to the construction of the roof and related secondary members in all types of construction. It allows these elements to be of unprotected construction when all parts of the roof construction are more than 20 feet (6096 mm) above any floor below. This footnote was revised for 2018 to clarify that this allowance applies to both the primary and secondary members of the roof structure. This alternative is applicable for all occupancy classifications except Groups F-1, H, M and S-1.

**EXTERIOR WALLS**

The MSBC regulates the fire resistance rating of exterior walls and the extent to which protected and unprotected openings are permitted in the exterior walls of facing buildings based on the fire separation distance to the lot line or to the center of the street (MSBC Table 602 and Table 705.8).

It should be noted that the Farley building is located approximately 40-feet away from the proposed Fuller School. The Farley building is constructed of non-combustible brick exterior walls. As such, the Fuller School is not provided with 100% open frontage on all sides. **The existing Farley Building was confirmed by JLA to be of masonry construction, with no exterior openings on the portions closest to the proposed Fuller School.**

**In order to determine the allowable openings and rating of the exterior walls of the Fuller School, an assumed lot line must be developed between the Farley building and the Fuller School. Based on the masonry exterior walls of the Farley Building, it is assumed that the Farley Building is provided with 1-hour rated exterior walls. With no openings in the exterior wall, the Fuller School will be permitted to have unlimited openings and a non-rated exterior wall. Specific detail of the Farley wall construction should be provided for a detailed review to ensure a 1-hour rated exterior wall exists.**

**Fire Resistance Rating for Exterior Non-Loading-Bearing Walls**

Based on Fire Separation Distance (IBC Table 602)

FIRE SEPARATION DISTANCE (Building wall to property line for each side of the building)	FIRE-RESISTANCE RATING (GROUP A, B, E, S-2)
<i>Less than 5 feet</i>	1-hour
<i>Greater than or equal to 5 feet and less than 10 feet</i>	1-hour
<i>Greater than or equal to 10 feet and less than 30 feet</i>	1-hour
<i>Greater than or equal to 30 feet</i>	0-hour

The required fire-resistance rating of exterior walls with a fire separation distance of greater than 10 feet must be rated for exposure to fire from the inside. The required fire-resistance rating of exterior walls with a fire separation distance of less than or equal to 10 feet must be rated for exposure to fire from both sides.

### Maximum Area of Exterior Wall Openings

Based on IBC Table 705.8

Fire Separation Distance to Lot Line (feet)	Allowable Area of Opening (Sprinklered)
0 to less than 3	Not Permitted
3 to less than 5	15%
5 to less than 10	25%
10 to less than 15	45%
15 to less than 20	75%
20 to less than 25	No Limit
25 to less than 30	No Limit
30 or greater	No Limit

The Farley building is not provided with openings on the portions of the building that will face the proposed Fuller School. As mentioned above, the allowable openings of the Fuller School will be determined upon confirmation of the assumed lot line between the Fuller School and the Farley Building. The Fuller School will likely be permitted to have unlimited openings based on the 1-hour rated exterior walls and lack of openings in the Farley Building.

### Fire Resistant Joint Systems

Joints installed in or between fire-rated walls, floors or floor/ceiling assemblies and roofs or roof/ceiling assemblies must be protected by an approved fire-resistant joint assembly having a rating equal to the rating of the wall, floor, or roof. Joint systems shall be tested in accordance with MSBC Section 715.0.

Listed and approved joint assemblies must be provided for all concealed locations where fire resistance rated assemblies form a joint.

### Interior Finishes and Floor Finishes

Interior finishes in the building are required to meet the requirements of MSBC Section 803 for Interior Finish. Refer to the following tables for details. Interior finish applies to wall and ceiling finishes. Interior floor finish applies to floor coverings.

**Interior Wall & Ceiling Finish Requirements by Occupancy**

Sprinklered Building (Table 803.11)

USE GROUP	VERTICAL EXITS AND PASSAGEWAYS	EXIT ACCESS CORRIDORS	ROOMS AND ENCLOSED SPACES
A-3	A or B	A or B	A, B, or C
B / E	A or B	A, B, or C	A, B, or C
S	A, B, or C	A, B, or C	A, B, or C
Atrium	A or B	A or B	A or B

**Interior Floor Finish Requirements by Occupancy**

Interior floor finish and floor coverings must comply with IBC Section 804, unless the floor finish or covering material is of traditional type, such as wood, vinyl, linoleum, or terrazzo and resilient floor covering materials not comprised of fibers.

**LABORATORY HAZARDOUS CHEMICAL STORAGE**

**Control Area Approach**

The MSBC permits limited amounts of hazardous materials in a Use Group E Educational Occupancies. Under this approach, each floor of the building is permitted to have a certain number of Control Areas that are separated by fire resistance rated construction. The number of Control Areas and quantity of hazardous materials permitted on each floor varies based on the ease of fire department access to those given spaces.

The control areas should be separated from adjacent spaces by one (1)-hour fire resistance rated separations on the First through Third Floors (MSBC Table 414.2.2). The required fire resistance rating for the floors and their supporting construction is one (1) hour rated, which is satisfied by the 2-hour floors per Type IB Construction. Doors in the one (1)-hour control area separation should be rated for ¾-hour and doors (MSBC Table 716.5). It should be noted that unprotected vertical openings are not permitted in control areas, unless a sum of the ratios for chemical quantity is utilized.

Multiple control areas per floor can be provided if they are separated with fire resistance rated fire barrier. Table 414.2.2 of the MSBC (shown below) provides the requirements for control area design by floor level in the building. It should be noted that the number of control areas permitted, and the maximum allowable quantity of hazardous materials permitted per control area is reduced on floors above and below grade. Hazardous materials in storage and in use within this control area will be limited to the quantities specified in MSBC Table 307.1 (1) and (2). The quantity limits shown include an allowable increase for approved storage and automatic sprinkler protection.

**MSBC Table 414.2.2 Design and Number of Control Areas**

Floor Level		Percentage of the Maximum Allowable Quantity Per Control Area	Number of Control Areas Per Floor	Fire-Resistance Rating for Fire Barriers in Hours	Actual Control Areas Provided
Above Grade	3	50	2	1	2
Plane	2	75	3	1	1
	1	100	4	1	2

- a. Percentages shall be of the maximum allowable quantity per control area shown in Tables 307.1(1) and 307.1(2) with all increases allowed in the notes to those tables
- b. Fire barriers shall include walls and floors and supporting construction as necessary to provide separation from other portions of the building.

As can be seen from the table above, the First Floor is allowed to have four (4) control areas. Above grade floors are permitted to have fewer control areas and each control area above grade is permitted to store less hazardous materials.

Table 414.2.2 of the MSBC (shown above) provides the requirements for control area design by floor level in the building. The IBC has a defined threshold for when an occupancy must be classified as a Group H High Hazard occupancy. The maximum allowable quantity per control area for hazardous materials is found in IBC Section 307. **If the quantities from Table 307.1(1) are exceeded, the occupancy must be classified as a Group H occupancy.** Table 307.1(1) also indicates what Hazard Occupancy Group (Group H-1 through H-5) the building must be classified as when the quantities in Table 307.1(1) are exceeded.

**As previously detailed in the report, an atrium connects the three (3) floors of the building. There should be multiple control areas per floor, which would require that rated walls separate the science classrooms from the balance of the building which entails 1-hour rated separations per NFPA 45. The science classrooms on Levels 1 and 2 are currently designed with fume hoods and will be used for chemical storage. The lab spaces on Level 3 are not provided with fume hoods but are expected to be used for chemical storage, thus will be protected as their own control area.**

**The design approach for control areas in the building includes separating the two (2) science lab spaces on Levels 1, 2 and 3 from the balance of the building with 1-hour rated construction. As the floors of the building are 2-hour rated (based on Type IB Construction), each group of science classrooms can be considered its own control area as the classrooms will be separated from the spaces above and the spaces below by 2-hour construction, and separated from the adjacent spaces (including the atrium) by 1-hour rated construction. The lab approach has been reviewed with the City of Framingham Inspectional Services Department.**

**Fire Code Requirements for Hazardous Chemicals**

The Massachusetts Fire Code 527 CMR adopts and amends the 2015 version of NFPA 1. Chapter 66 from the Massachusetts fire code contains the requirements for Flammable and combustible liquids. The Massachusetts fire code requires that the storage, handling and use of flammable or combustible liquids comply with NFPA

30. According to Section 1.5.3, a laboratory installation made in accordance with NFPA 45 is determined to be in compliance with NFPA 30.

**66.1.1\*** The storage, handling, and use of flammable and combustible liquids, including waste liquids, as herein defined and classified, shall comply with this chapter; NFPA 30, *Flammable and Combustible Liquids Code*; Sections 60.1 through 60.4 of this *Code*; and NFPA 35 *Standards for the Manufacture of Organic Coatings, as applicable*.

### **Most restrictive requirements NFPA 30 and NFPA 45-**

It is noted that NFPA 30 does not govern storage of liquids in a laboratory. In the open work area of the laboratory, the quantity of flammable liquid in the work area is governed by NFPA 45, which is the standard on fire protection for laboratories using chemicals.

The Massachusetts Fire Code Section 66.1.4 from the states that a laboratory that is installed in accordance with NFPA 45 is considered in compliance with the NFPA 1. Furthermore, it is noted that in accordance with Section 1.5.3 of NFPA 30, a laboratory that is installed in accordance with NFPA 45 is considered in compliance with NFPA 30.

**As discussed above, Howe Engineers confirmed with the staff liaisons for NFPA 30 & NFPA 45 that a laboratory installed in compliance with NFPA 45 is considered to be in compliance with NFPA 30 per Section 1.5.3 of NFPA 30.**

**1.5.3 Installations made in accordance with the applicable requirements of the following standards shall be deemed to be in compliance with this code:**

- (1) NFPA 1, *Fire Code*
- (2) NFPA 20, *Standard for the Installation of Stationary Pumps for Fire Protection*
- (3) NFPA 30A, *Code for Motor Fuel Dispensing Facilities and Repair Garages*
- (4) NFPA 31, *Standard for the Installation of Oil-Burning Equipment*
- (5) NFPA 32, *Standard for Drycleaning Plants*
- (6) NFPA 33, *Standard for Spray Application Using Flammable or Combustible Materials*
- (7) NFPA 34, *Standard for Dipping, Coating, and Printing Processes Using Flammable or Combustible Liquids*
- (8) NFPA 35, *Standard for the Manufacture of Organic Coatings*
- (9) NFPA 36, *Standard for Solvent Extraction Plants*
- (10) NFPA 37, *Standard for the Installation and Use of Stationary Combustion Engines and Gas Turbines*
- (11) NFPA 45, *Standard on Fire Protection for Laboratories Using Chemicals*
- (12) NFPA 99, *Health Care Facilities Code*
- (13) NFPA 101, *Life Safety Code*

Figure 1: NFPA 30 Section 1.5.3 states installations made in accordance with NFPA 45 are considered in compliance with NFPA 30.

**66.1.4** Installations made in accordance with the applicable requirements of the following standards shall be deemed to be in compliance with this Code.

- (1) NFPA 20, *Standard for the Installation of Stationary Pumps for Fire Protection*
- (2) NFPA 30A, *Code for Motor Fuel Dispensing Facilities and Repair Garages*
- (3) NFPA 31, *Standard for the Installation of Oil-Burning Equipment*
- (4) NFPA 32, *Standard for Drycleaning Plants*
- (5) NFPA 33, *Standard for Spray Application Using Flammable or Combustible Materials*
- (6) NFPA 34, *Standard for Dipping, Coating, and Printing Processes Using Flammable or Combustible Liquids*
- (7) NFPA 35, *Standard for the Manufacture of Organic Coatings*
- (8) NFPA 36, *Standard for Solvent Extraction Plants*
- (9) NFPA 37, *Standard for the Installation and Use of Stationary Combustion Engines and Gas Turbines*
- (10) NFPA 45, *Standard on Fire Protection for Laboratories Using Chemicals*
- (11) NFPA 99, *Health Care Facilities Code*
- (12) NFPA 101, *Life Safety Code*

Figure 2: NFPA 1 Section 66.1.4 states installations made in accordance with NFPA 45 are considered in compliance with NFPA 1.

## NFPA 45 Laboratory Installation Requirements

In NFPA 45, Laboratories are classified as Laboratory Units A through D. Classification A representing a high hazard and D minimum fire hazard. The difference being the quantity of flammable and combustible liquids permitted to be utilized in the laboratory. Table 5.1.1 from NFPA 45 contains the requirements for the separation, maximum area and number of stories above and below grade that a lab can be located. This table is similar to the requirements contained in Table 414 of the International Building Code. (It is noted for reference that Table 5.1.1 has been updated in the 2015 version of NFPA 45 to clarify that Class C and D laboratories are permitted to be located in a story below grade.) In accordance with Table 5.1.1, fire separation is not required for Class C or D laboratories for Educational Buildings and be limited to 50% of the values shown in the table on the next page.

**Table 5.1.1 Separation Requirements and Height Allowances for Laboratory Units**

Laboratory Unit <sup>a</sup>	Area of Lab Unit	Fire Separation <sup>b</sup>	Permitted Stories Above Grade
A	≤929 m <sup>2</sup> (≤10,000 ft <sup>2</sup> )	2 hours	1-3 <sup>c</sup>
	>929 m <sup>2</sup> (>10,000 ft <sup>2</sup> )	Not permitted <sup>d</sup>	
B	≤929 m <sup>2</sup> (≤10,000 ft <sup>2</sup> )	1 hour	1-3 <sup>c</sup>
	≤929 m <sup>2</sup> (≤10,000 ft <sup>2</sup> )	2 hours	4-6 <sup>c</sup>
	>929 m <sup>2</sup> (>10,000 ft <sup>2</sup> )	Not permitted <sup>d</sup>	
C	Any size	Not required	1-3
	Any size	1 hour	4-6
	Any size	2 hours	Over 6
D	Any size	Not required	No limit

<sup>a</sup>Refer to Table 10.1.1 for laboratory unit classification.

<sup>b</sup>Separation in this table refers to separation from laboratory unit(s) to non-laboratory areas and/or separations from laboratory unit(s) of equal or lower hazard classification.

<sup>c</sup>Not allowed in structures below grade.

<sup>d</sup>Labs of this classification and size are not permitted.

## NFPA 45 Requirements for Maximum Allowable Quantities of Flammable Liquids.

Chapter 10 from NFPA 45 contains the quantity limitations for flammable and combustible liquids. The maximum allowable quantities for flammable and combustible liquids can be found in Table 10.1.1(b) (See Table 10.1.1(b) below).

**Table 10.1.1(b) Maximum Quantities of Flammable and Combustible Liquids in Laboratory Units Outside of Inside Liquid Storage Areas (U.S. Customary Units)**

Laboratory Unit Fire Hazard Class	Flammable and Combustible Liquid Class <sup>a</sup>	Quantities in Use <sup>a</sup>		Quantities in Use and Storage <sup>a</sup>	
		Maximum Quantity <sup>b</sup> per 100 ft <sup>2</sup> of Laboratory Unit <sup>c</sup>	Maximum Quantity <sup>b</sup> per Laboratory Unit	Maximum Quantity <sup>b</sup> per 100 ft <sup>2</sup> of Laboratory Unit <sup>c</sup>	Maximum Quantity <sup>b</sup> per Laboratory Unit
		gal	gal	gal	gal
A (high fire hazard)	I, II, and IIIA	10	480	20	480
		20	800	40	1600
B <sup>d</sup> (moderate fire hazard)	I, II, and IIIA	5	300	10	480
		10	400	20	800
C <sup>e</sup> (low fire hazard)	I, II, and IIIA	2	150	4	300
		4	200	8	400
D <sup>e</sup> (minimal fire hazard)	I, II, and IIIA	1	75	2	150
		1	75	2	150

Note: For maximum container sizes, see Table 10.1.2.

**The maximum amount in use in open systems is limited to 10 percent of the quantities listed.**

<sup>b</sup>See 4.2.2 for additional requirements for educational and instructional laboratories.

<sup>c</sup>The quantities per 100 ft<sup>2</sup> do not imply the quantities must be within that 100 ft<sup>2</sup> area; the quantities per 100 ft<sup>2</sup> are for calculation purposes to determine the total quantity allowed per laboratory work area and the total amount overall in the laboratory unit.

<sup>d</sup>Reduce quantities by 50 percent for B laboratory units located above the 3rd floor.

<sup>e</sup>Reduce quantities by 25 percent for C and D laboratory units located on the 4th–6th floors of a building and reduce quantities by 50 percent for C and D laboratory units located above the 6th floor.

- The maximum allowable quantity permitted by Table 10.1.1 is based on a per 100 sq. ft. of laboratory area.



### **NFPA 45 Instructional Laboratory classification**

It is noted that NFPA 45 has a designation for Instructional Laboratories, which is classified as a lab that is used for educational purposes for college aged students. Experiments and testing in an Instructional Lab is typically conducted under supervision of a lab instructor.

**3.3.31 Instructional Laboratory Unit.** A laboratory unit used for education past the 12th grade and before post-college graduate-level instruction for the purposes of instruction of six or more persons for four or more hours per day or more than 12 hours per week. Experiments and tests conducted in instructional laboratory units are under the direct supervision of an instructor. Laboratory units used for graduate or post-graduate research are not to be considered instructional laboratory units.

### **Summary of the Maximum Allowable Quantities from IBC, NFPA 30 and NFPA 45**

Howe Engineers has provided the following table to summarize the various requirements for maximum allowable quantities from the International Building Code, NFPA 30 and NFPA 45. It is noted that NFPA 45 is most restrictive in the maximum allowable quantities for storage and use of flammable and combustible liquids. It is noted that the maximum allowable quantities in Table 1 assumed that the NFPA 45 maximum allowable quantities are not reduced due to the floor area of the laboratory. **The maximum allowable quantity permitted by NFPA 45 Table 10.1.1 is based on a per 100 sq. ft. of laboratory area and a reduction of 50% of the maximum allowable quantity listed in the table below per the Educational requirements**

Please refer to Table 1 below for the for maximum allowable quantities from the International Building Code, NFPA 30 and NFPA 45:

## ***PENETRATIONS OF DUCT AND AIR TRANSFER OPENINGS***

### **MEP Shaft Enclosures**

A shaft is required when the duct penetrates two (2) or more floor/ceiling assemblies (MSBC Section 717.6.1). A shaft is not required in occupancies other than Groups I-2 and I-3, for a duct constructed of approved materials in accordance with the International Mechanical Code that penetrates not more than one (1) fire-resistance-rated floor/ceiling assembly (connecting only 2 stories), provided a listed fire damper is installed at the floor line or the duct is protected in accordance with MSBC Section 714.4 (MSBC Section 717.6).

MSBC Section 713.4 provides that shafts connecting less than four (4) stories, a 1-hour fire rated shaft enclosure is required. Shafts connecting four (4) or more stories require a fire-resistance rating of at least two (2) hours. Additionally, shaft enclosures must not have a fire resistance rating that is less than the rating of the floor that they are penetrating, but need not exceed two (2) hours. Openings in a shaft enclosure are required to be limited to those necessary for the purpose of the shaft (MSBC Section 713.8.1). Where shafts do not extend to the top or bottom of a building, adequate protection should be provided (MSBC Section 713.11 and Section 713.12). **It should be noted that as the building is of Type IB construction, shafts must be provided with a 2-hour fire resistance rating as they penetrate 2-hour rated floor assemblies.**

**The building will have shafts at each bathroom suite to accommodate bathroom exhaust. Additionally, shafts will be located above the administrative suites to accommodate ductwork associated with these office areas. Finally, kiln exhaust and various fume hoods throughout the building will be provided with 2-hour rated shafts.**

### **Fire Dampers**

Fire dampers should have a fire resistance rating in accordance with the table below (MSBC Table 717.3.2.1). The actuation temperature of the actuating device should be approximately 50°F above the normal temperature within the duct system (MSBC Section 717.3.3.1). If a fusible link is used, it should have a temperature rating not less than 160°F (MSBC Section 717.3.3.1).

### **Fire Damper Rating**

<b>Type of Penetration</b>	<b>Minimum Fire Damper Rating</b>
Less than 3-hour fire-resistance rated assemblies	1½ hours
3 hour or greater fire-resistance rated assemblies	3 hours

Fire dampers are required at locations where ducts or air transfer openings of an air distribution system penetrate fire resistance rated assemblies including the following:

- Fire barriers (MSBC Section 717.5.2);
- Shaft enclosures (MSBC Section 717.5.3);
- Fire partitions (MSBC Section 717.5.4);
- Horizontal assemblies (MSBC Section 717.6).

## Smoke Dampers

Actuation of smoke dampers should be achieved in accordance with the table below (MSBC Section 717.3.3.2).

### Smoke Damper Actuation Methods

Damper Location	Activation Method
Within a duct	Activation controlled by a smoke detector within 5-feet of the damper with no air outlets or inlets between the detector and the damper.
Above smoke barrier doors in a smoke barrier	Activation controlled by a spot type detector listed for releasing service should be installed on both sides of the smoke barrier door opening.
In an un-ducted opening in a wall	Activation controlled by a spot type detector listed for releasing service should be installed within 5-feet of the damper.
In a corridor wall	Activation controlled by smoke detector system in the corridor.
All	Where a total-coverage smoke detector system is provided within areas served by HVAC system, dampers are permitted to be controlled by the smoke detection system.

Smoke dampers are required at locations where ducts or air transfer openings of an air distribution system penetrate assemblies; including:

- Shaft enclosures (MSBC Section 717.5.3);
- Smoke barrier walls (MSBC Section 717.5.5);
- Horizontal Exits in fire walls (MSBC Section 717.5.1);
- Corridors (MSBC Section 717.5.4.1);
- Smoke Partitions (MSBC Section 717.5.7).
- Smoke-tight construction (MSBC Section 509.4.2)

**It should be noted that smoke dampers are not required in smoke control systems where actuation of the damper would interfere with the operation of the smoke control system (717.5.3 Exception 3).**

**The table below reiterates smoke damper (SD) requirements and provides a number of exceptions in accordance with the MSBC.**

### Combination Smoke/ Fire Dampers

Where penetration of a smoke barrier is required to be provided with a fire damper, a combination fire and smoke damper equipped and arranged to be both smoke and heat responsive should be provided (MSBC 717.5). Combination smoke / fire dampers are required in the following location:

- Shaft penetrations (MSBC 717.5.3).

**The table below reiterates combination smoke / fire damper requirements and provides a number of exceptions in accordance with the MSBC.**

**Through Penetration Protection**

Penetrations into or through fire barriers, smoke barrier walls, fire partitions, floor/ceiling assemblies, or the ceiling membrane of a roof/ceiling assembly are required to be protected with an approved penetration or membrane penetration assembly (MSBC 708). See MSBC 708 for exceptions.

**Damper Exceptions**

The table below been developed by Howe Engineers in identifying where dampers are required and where exceptions exist.

	FD	SD	MSBC	Applicable SD, FD & SD/FD Damper Exceptions
<b>Fire Barriers (including horizontal exits)<sup>1</sup></b>	Required	Not Required (NR)	717.5.2	Penetrations tested in accordance with ASTM E119 as part of a fire-resistance rated assembly (FD). [MSBC §717.5.2 Exception 1]
				Ducts used as part of an approved smoke control system (FD). [MSBC 717.5.2 Exception 2]
				Where fire barriers walls have a FRR of less than 1-hour and the following conditions apply: • The Building is protected throughout by automatic sprinklers; • Penetrations are limited to a ducted HVAC system conveying supply, return or exhaust air; • HVAC ducts are minimally 26 gage; • HVAC ducts are continuous from the AHU to the air outlet and inlet terminals (FD). [MSBC 717.5.2 Exception 3]
<b>Smoke Barriers<sup>2</sup></b>	NR	Required	717.5.5	Smoke dampers are not required where openings in ducts are limited to a single smoke compartment and ducts are constructed of steel (SD). [MSBC 717.5.5 Exception 1]
<b>Floor / Ceiling Assemblies</b>	Required	NR	717.6.1	A duct is permitted to penetrate two floors or less with a fire damper at each floor provided it meets all the requirements in 717.6.1 Exception (FD). [MSBC 717.6.1 Exception]
<b>Shafts</b>	Fire / Smoke Dampers Required		717.5.3	Steel exhaust sub ducts extending at least 22-inches vertically in an exhaust shaft provided there is a continuous upward airflow to the outside (FD). [MSBC 717.5.3 Exception 1.1]
				Penetrations tested in accordance with ASTM E119 as part of a fire-resistance rated assembly (FD). [MSBC 717.5.3 Exception 1.2]
				Ducts used as part of an approved smoke control system (FD). [MSBC 717.5.3 Exception 1.3]
				Fire dampers and combination fire/smoke dampers are not required in kitchen and clothes dryer exhaust systems when installed in accordance with the International Mechanical Code (SD/FD). [MSBC 717.5.3 Exception 5]. A duct that penetrates a fire-resistance rated floor/ceiling assembly that connects not more than 2 stories is permitted without a shaft enclosure, provided that a listed fire damper is installed at the floor line. [MSBC 717.6.3].
				Kitchen, clothes dryer, bathroom and toilet room exhaust openings are installed with steel exhaust sub ducts, having a minimum wall thickness of 0.187-inch (No. 26 gage), the sub ducts extend at least 22 inches vertically, and an exhaust fan providing continuous airflow to the outside is installed at the top of the shaft terminal. The exhaust fan should be provided with an uninterruptible power system for the first 15 minutes of loss of primary power (SD). [MSBC 717.5.3 Exception 2 for Group B and R occupancies only]
<b>Corridors</b>	NR	Required	717.5.4	Ductwork has a minimum wall thickness of 0.019 inches and there are not openings that serve the corridor (SD). [MSBC 717.5.4.1 Exception 2]
<b>Fire Partitions</b>	Required	NR	717.5.4	Ductwork does not exceed 100 square inches, constructed of steel a minimum of 0.0217 inch in thickness, does not have openings that communicate with the corridor, installed above the ceiling, shall not terminate at a wall register in the fire resistance rated wall, 12-inch long by 0.060-inch-thick steel sleeve centered in each duct opening and secured by rectangle angles (SD). [MSBC 717.5.4 Exception 3]

<sup>1</sup> Fire barriers within the building will include: Occupancy separations (if provided) and special use room enclosures.

<sup>2</sup> Smoke barriers within the building will include: Fire service elevator lobby separations.

### ***Protected Vertical Openings***

Vertical openings through floors will be protected by fire-rated assemblies in accordance with MSBC Section 707.3. Vertical openings include exit stairs, elevator shafts, and mechanical shafts. Shafts and exit enclosures, other than *exit access stairways* complying with MSBC Section 1019.3 Item 4, will be enclosed with listed and approved shaft enclosure assemblies that provide a 2-hour fire-resistant rated noncombustible shaft assembly per MSBC Section 707.3, as the shafts will connect less than four (4) stories but penetrate 2-hour rated floor slabs (Type IB Construction). **Enclosed exit stairs within the building will be designed with 2-hour fire-rated separations.**

The floor openings requiring shaft protection will include, but are not limited to:

- Grease Ducts, Trash chutes and linen chutes
- Elevator Shafts
- Mechanical, electrical and plumbing shafts
- Exit Stairways, other than exit access stairways complying with MSBC Section 1019.3 Item 4.

Duct systems throughout the building that do not connect more than two (2) stories and are not required to be enclosed in shafts and are not required to be provided with smoke dampers, provided the annular space around the shaft is sealed with an approved material (MSBC, Section 714).

### ***ATRIUM DESIGN***

The current Fuller School design includes a three (3) story opening in the center of the building, with numerous breakout spaces within the opening. As the opening connects more than two (2) stories, the space is considered an atrium and must be designed in accordance with MSBC Section 404. Atriums are only permitted to be installed in buildings provided with approved automatic sprinkler protection (MSBC 404.3). **The design for the smoke control system includes 240,000 CFM of mechanical exhaust through multiple exhaust points spaces between Levels 2 and 3. Louvers and doors will be provided on Levels 1, 2, and 3 to supply the make-up air for the smoke control system. It should be noted that the louvers on the exterior of the building are not considered dampers, thus are not required to be listed in accordance with UL 555. The topic of louvers requires further discussed with the City of Framingham.**

Section 404.5 requires a smoke control system to be installed in accordance with MSBC Section 909. The smoke control system can either be designed using natural or mechanical-ventilation but will require an engineering rational analysis to ensure adequate system performance. Equipment for the smoke control system must be provided with standby power. **The atrium will be provided with a smoke control system utilizing mechanical exhaust. Refer to Appendix A for the Smoke Control Rational Analysis report drafted by Howe Engineers for further clarification on the system design.**

Section 404.6 requires atrium spaces to be separated from adjacent spaces by a 1-hour fire barrier constructed in accordance with Section 707. A fire barrier is not required to enclose an atrium space when one (1) of the following arrangements are met:

- A glass wall forming a smoke partition is provided and sprinklers are provided along both sides of the separation walls and doors. Sprinklers must be located between 4 and 12-inches away from the glass at intervals along the glass not more than 6-feet. The sprinkler system must be designed to wet all surface of the glass upon activation. The glass wall must be installed in a gasketed frame in such a manner that the framing deflects without breaking the glass before the sprinkler operates. Where glass doors are provided, they must be self or automatic-closing.
- A glass block wall assembly complying with section 2110 having a ¾-hour rating is provided.
- A fire barrier is not required when the design is accounted for in the design of the smoke control system.

**The atrium is not separated from the balance of the building with 1-hour construction. The geometry of the building is considered in the design of the smoke control system as discussed in the smoke control rational analysis attached as Appendix A of this document.**

**It should be noted that that the cafeteria and learning commons are located at the base of the atrium on Level 1 of the building. The current design for the spaces includes a permeable, mesh separation screen to be installed to separate the east and west sides of the atrium thus allowing school-related, and public events to occur simultaneously at the base of the atrium. Additionally, doors will be constructed in the north and south side corridors adjacent to the atrium to further separate the school and public event spaces. Each side (east and west) of the atrium will be provided with two (2) means of egress. As noted above, the mesh screen is permeable, thus will not impact the functionality of the smoke control system.**

Atrium interior finishes must be class B or higher, with no reduction for sprinkler protection (Section 404.8).

It should be noted that unique egress requirements exist for atrium spaces in Section 404.9. Exit access travel distance through the atrium, not at the level of exit discharge, must not exceed 200-feet within the bounds of the atrium. Refer to the means of egress section of this report for further information.

### ***STAGE DESIGN***

The current Fuller School design includes a stage in the auditorium space on the First Floor. The requirements for stages are provided in MSBC Section 410. Section 410.3.1 requires stages to be constructed of materials as required for floors of the type of construction in which the stage is located. **As the building will be of Type IB Construction, the stage must be constructed of materials as required for floors.** In all types of construction, the finished floor must be constructed of wood or non-combustible materials. Openings through the stage floor must be equipped with tight-fitting, solid wood trap floors with approved safety locks.

Where the stage height is greater than 50-feet in height, all portions of the stage must be completely separated from the seating area by a proscenium wall with not less than a 2-hour fire-resistance rating extending continuously from the foundation to the roof (Section 410.3.4). Where a proscenium wall is required to have a fire-resistance rating, the stage openings must be provided with a fire curtain complying with NFPA 80, horizontal sliding doors complying with Section 716.5.2 having a fire protection rating of at least 1-hour, or an approved water curtain complying with section 903.3.1.1. **Based on the current set of drawings, the stage height is approximately 30-feet, thus a proscenium curtain is not required.**

Combustible scenery used in sets must meet the fire propagation performance criteria of Test Method 1 or 2, as appropriate of NFPA 701 in accordance with Section 806 of the International Fire Code.

It should be noted that the current stage design was measured to be approximately 1,560 square feet. Section 410.3.7 requires emergency ventilation for stages larger than 1000 square feet in floor area, or stages with a height greater than 50-feet. Ventilation must comply with Section 410.3.7.1 (roof vents) or 410.3.7.2 (Smoke control). **The stage will be provided with natural roof vents.**

Dressing and appurtenant rooms are required to be separated from the stage with rated construction in accordance with Section 410.5.1. Stages must be separated from dressing rooms, scene docks, workshops, storerooms and compartments appurtenant to the stage by fire barriers or horizontal assemblies. The fire-resistance rating must be 2-hour for stage heights greater than 50-feet, and not less than 1-hour for stage height of 50-feet or less. **As the stage is less than 50-feet in height, dressing rooms must be separated from the stage with 1-hour rated construction. Additionally, the AV rooms on the east and west sides of the stage will be provided with a 1-hour fire resistance rating.**

Stages must be provided with automatic sprinkler protection in accordance with Section 903.3.1.1. Sprinklers must be installed under the roof and gridiron and under all catwalks and galleries over the storage. Sprinklers must be installed in dressing rooms, performer lounges, and storerooms accessory to the stage (Section 410.7). Section 905.3.4 requires that stages greater than 1,000 square feet in area be provided with a Class III wet standpipe system with 1 ½-inch and 2 ½-inch hose connections on each side of the stage. **As the stage is greater than 1,000 square feet, it must be provided with a standpipe system as required by Section 905.3.4.**

It should also be noted that an accessible route must be provided to access the stage. **Refer to the accessibility section of this report for further clarification on the accessibility requirements associated with the auditorium space.**

**MEANS OF EGRESS SYSTEM DESIGN**

**GENERAL REQUIREMENTS**

**Occupant Load**

The occupant load for each space within the Building is determined using the occupant load factors listed in MSBC Table 1004.1.2, as shown in the table below.

OCCUPANT USE GROUP	OCCUPANT LOAD FACTOR PER PERSON
Classrooms	20 square feet (net) per person or actual occupant load
Lab Classrooms	50 square feet (net) per person
Unconcentrated Assembly Areas (Lounge, Collab, Cafeteria)	15 square feet (net) per person
Office/Business	100 square feet (gross) per person
Locker Rooms	50 square feet (gross) per person
Athletic Facility (Gymnasium)	50 square feet (gross) per person
Stage	15 square feet (net) per person)
Fixed Seating (Auditorium)	Actual Number of Seats
Circulation Space	100 square feet (gross) per person
Kitchen	200 square feet (gross) per person
Storage, Mechanical, Electrical	300 square feet (gross) per person
Bleacher Seating	18-inches per occupant

**Refer to the 90% CD Life Safety Drawings prepared by Howe Engineers for the occupant load of each floor of the proposed building.**

It should be noted that the design of the building entails classrooms with moveable partitions between individual rooms. As such, the calculated occupant load of individual classrooms does not represent the actual occupant load expected in each space. The life safety drawings depict an “actual” occupant load of 25-people per classroom, which includes students and staff members. **The approach of using a planned occupant load has been discussed and approved from the Authority Having Jurisdiction. The planned occupant load will be included on the certificate of occupancy for the building.**



### **Number of Exit Access Doorways**

Section 1006.2.1.1 requires that three (3) or more exits be provided when a space has a calculated occupant load of 501 to 1,000 and four (4) exits are required when the occupant load is greater than 1,000 occupants. Section 1006.2.1 requires two exits for all areas exceeding the occupant load in table 1006.2.1. For an A-3/E occupancy, two exits are required if the occupant load exceeds 49 occupants or where the common path of travel exceeds 75 feet. In Group B occupancy areas, two exits are required if the occupant load exceeds 49 occupants or where the common path of travel exceeds 100 feet. Further, in Group S-1/S-2 occupancy areas, two exits are required if the occupant load exceeds 29 occupants or where the common path of travel exceeds 100 feet.

**It should be noted that the first-floor occupant load exceeds 1,000, thus requiring four means of egress. The auditorium and gymnasium space are provided with their own dedicated egress doors leading directly to the exterior. The occupant load of the main school area is provided with four means of egress by means of doors to the exterior, and two (2) interior atrium stairways. The tech maker space, fab lab, art room, and media room on the first floor are all provided with a single 36-inch door that leads directly to the exterior of the building. Occupants in these rooms are expected to egress directly to the exterior of the building and do not need to enter the main building in order to egress. As such, the remainder of the first floor only requires three (3) means of egress, served by the two primary egress stairs, and the open stair within the atrium bounds.**

It should be noted that the means of egress for unique spaces such as boiler rooms, furnace rooms, and refrigeration machinery rooms is governed by Section 1006.2.2. Boiler rooms, incinerator rooms, and furnace rooms require two (2) means of egress where the area of the space is over 500 square feet and any fuel-fired equipment exceeds 400,000 BTU input capacity (Section 1006.2.2.1). Where two means of egress are required, one (1) is permitted to be a fixed ladder or an alternating tread device. The exits must be remotely located at a distance equal to one-half the length of the maximum overall diagonal dimension of the room. Refrigeration machinery rooms larger than 1,000 square feet must have at least two (2) exits (Section 1006.2.2.2). All portions of the machinery rooms must be within 150-feet of an exit or exit access doorway. Doors must swing in the direction of egress travel regardless of the occupant load served.

The current egress strategy involves occupants on the first-floor egressing upwards one story to exit through the main entry doors on Floor 2. MSBC Section 1006.3 permits the path of egress travel to pass through one (1) adjacent story to reach an exit. Occupants from Floor 1 would only pass through one adjacent story to reach the main entrance to the building, thus the approach complies with Section 1006.3. It should also be noted that Section 404.9.3 permits the exit access travel distance to be through an atrium, provided that the total exit access travel distance through the actual atrium space is not greater than 200 feet. This section is complied with in the designed atrium.

**Arrangement of Means of Egress (MSBC Section 1007.1.1)**

Where two (2) exits, or exit access doors are required from a space, they must be placed not less than one-third the overall diagonal distance of the space, measured in a straight line between the exit doors or exit access doors.

Where there are three (3) or more exits, or exit access doors, at least two (2) of the exits or exit access doors are required to meet the remoteness as defined above. The additional exits shall be located as remotely as possible.

**The current arrangement of means of egress meets these criteria. The primary egress stairs are on opposite sides of the building, satisfying the one-third remoteness criteria.**

**It should be noted that the office suite on the south side of Level 2 requires two (2) means of egress based on the calculated occupant load of the space. The primary means of egress is by way of the door into the corridor on the north side of the space. The secondary means of egress is by way of a door on the south west side of the space which leads directly to an area of rescue assistance on the south side of the building. The exterior walkway is provided with sufficient width to accommodate two (2) wheelchairs side by side thus meets the requirements of 521 CMR. The egress approach for the office suite has been discussed and approved by the Authority Having Jurisdiction for the project.**

**Exit Capacities**

The exits within the building will be designed using the exit capacity factors listed in MSBC Sections 1005.3.1 and 1005.3.2. The exit capacity for stairs is calculated at 0.2 inches per occupant, while all other means of egress are calculated at 0.15 inches per occupant as the building will be fully sprinklered and provided with emergency voice/communication capabilities (Section 1005.3). The minimum required clear width shall not be less than those outlined within other sections of this report, which have been excerpted in the table below for reference.

LOCATION	EXIT CAPACITY NON-SPRINKLERED	MINIMUM REQUIRED CLEAR WIDTH
Stairways	0.20 inches per person	44 inches (MSBC Section 1011.2)
Doors	0.15 inches per person	32 inches (MSBC Section 1010.1.1)

**Refer to the 90% CD Life Safety Drawings prepared by Howe Engineers for the egress capacity and exiting strategy of each floor level. As seen in the life safety drawings, the means of egress capacity exceeds the occupant load on all floors.**

### Exit Access Travel Distance (MSBC Section 1017)

The Travel distance for each of the occupancies will be in accordance with the requirements contained in MSBC Section 1017.2 and Table 1017.2. Refer to the Table below:

OCCUPANCY	MAXIMUM ALLOWABLE TRAVEL DISTANCE (Sprinklered)
Group A, E, S-1	250 feet
Group B	300 feet
Group S-2	400 feet
Atrium	200 feet within atrium

Exit access travel distance must be measured from the most remote point within a story along the natural and unobstructed path of horizontal and vertical egress travel to the entrance of an *exit* (MSBC Section 1017.3). Where an exit access stairway or ramp is used as part of the means of egress system, the travel distance along the exit access stairway or ramp must be included in the exit access travel distance measurement (MSBC Section 1017.3.1). The measurement along exit access stairways and ramps must comply with the following:

- Stairways: measurements must be made on a plane parallel and tangent to the stair tread and nosings in the center of the stair and landings.
- Ramps: measurement along ramps must be made on the walking surface in the center of the ramp and landing.

Note that an "exit" is defined by MSBC Section 202 as that portion of a means of egress system between the exit access and the exit discharge or public way. Exit components include exterior exit doors at the level of exit discharge, *interior exit stairways* and *ramps*, *exit passageways*, *exterior exit stairways* and *ramps* and *horizontal exits*.

As addressed in the atrium design section of this report, the travel distance within the atrium is governed by Section 404.9. Where the path of egress travel is not on a level of exit discharge (i.e. Floor 3), the portion of the total permitted exit access travel distance that occurs within the atrium must not exceed 200-feet (Section 400.9.3).

### Egress through Intervening Spaces (MSBC Section 1016.2)

Exit access from a room or space should not pass through an adjacent room or space, except where the room or area is accessory to the area being served. Exit access is not permitted to pass through kitchens, storerooms, restrooms, closets or other similar spaces. In addition, the exit access is not permitted to pass through rooms subject to locking.

### **Common Path of Travel Limits (MSBC Table 1006.2.1)**

Maximum common path of egress travel distance is limited based on individual occupancies as outlined below.

- Business and Storage Occupancies 100 feet
- Assembly / Educational occupancies 75 feet

**Common path of travel is less than 75-feet in the Fuller School and thus is compliant.**

### **Dead End Corridor Limits (MSBC Section 1020.4)**

Per MSBC Section 1020.4, where more than one exit or exit access doorway is required, the exit access must be arranged such that there is no dead ends more than:

- Assembly Occupancies 20 feet
- Business Occupancies 50 feet
- Storage Occupancies 50 feet
- Educational Occupancies 50 feet

Note that a dead-end corridor is not limited where the length is less than 2.5 times the minimum width of the dead end. **Dead ends in the building will not exceed 20-feet.**

### **Exit Access Corridors (MSBC Section 1020)**

Corridors used for the exit access portion of the means of egress will be constructed in accordance with the MSBC Section 1020. The exit access corridors will provide sufficient clear width to accommodate the number of occupants exiting through the corridor, but will never be less than 44 inches unless serving an occupant load of less than 50 people, in which case they can be 36 inches.

**Per MSBC Table 1020.1, as the building will be fully sprinklered, rated corridors are not required.**

**It should also be noted that corridors in Group E occupancies with greater than 100 occupants are required to be 72-inches in width (Section 1020.2).**

### **Exit Stair Discharge**

The MSBC requires 50-percent of the enclosed interior exit stairways discharge to the exterior of the building and through the atrium. The remainder of the enclosed interior exit stairways are permitted to discharge to interior lobbies and vestibules (MSBC Section 1028.1). **The primary egress stairs on the east and west sides of the building both discharge directly to the exterior on the first floor and thus are compliant.**

### **Doors (MSBC Section 1010)**

Doors throughout the building must comply with MSBC Section 1010.1.

1. Dimensional Requirements (MSBC 1010.1.1)

Minimum clear width:	32 inches
Maximum size of a door leaf:	48 inches
Minimum Clear Height:	6 feet – 8 inches
2. Doors shall be side-hinged swinging in all spaces except within storage areas.
3. Doors serving a space with 50 people or more are required to swing in the direction of egress travel towards the exit.
4. While opening, doors are not permitted to project more than 50 percent of the required clear width in an exit stair or exit access stairway at any moment during the swing when opening. In addition, doors, when fully open, are not permitted to project more than 7 inches into the required exit clear width

### **Exit signage (MSBC Section 1013)**

1. Exit signs must be provided in each room or space that requires more than one (1) exit or exit access.
2. Exit signs must be placed such that no point within an exit access corridor is more than 100 feet or the listed viewing distance of the sign, whichever is less, from the nearest visible sign.
3. Main exterior exit doors or gates which obviously and clearly are identifiable as exits are not required to be provided with an exit sign where approved by the building official.
4. Every exit sign and directional exit sign must have plainly legible letters not less than 6 inches high with the principal strokes of the letters not less than  $\frac{3}{4}$  inch wide. The word "EXIT" must be in high contrast with the background and shall be clearly discernible when the exit sign illumination means is or is not energized. When an arrow is provided as part of the exit sign, the construction shall be such that the arrow direction cannot be readily changed.
5. Exit signs and exit directional signs can be externally or internally illuminated. The level of illumination at the sign's surface must be no less than 5-foot candles.
6. Exit signs shall be illuminated at all times and connected to an emergency power source having a duration of not less than 90 minutes. Emergency power shall conform to the National Electrical Code (NFPA 70).
7. Exit signs must be provided within 18-inches of the floor in electric rooms if the electric room has over 1,200 amperes and is more than 6-feet wide. In addition, panic hardware should be provided from these spaces.
- 8. The International Symbol of Accessibility must be included on exit signs at exits to grade.**
9. Directional signage indicating the location of other means of egress and in which are accessible means of egress must be provided at the following locations:
  - a. At exits serving a required accessible space, but not providing an approved accessible means of egress.
  - b. At Elevator Landings
  - c. Within areas of refuge

## Means of Egress Lighting (MSBC Section 1008)

Work areas will meet the following criteria as MSBC Section 1008 requires the following for means of egress lighting:

- The means of egress, including the exit discharge, must be illuminated at all times the building space served by the means of egress is occupied, except aisle access ways in Group A occupancies.
- The means of egress illumination level must not be less than 1 foot-candle (11 lux) at the walking surface.
- The power supply for means of egress illumination must normally be provided by the premises' electrical supply. In the event of power supply failure, an emergency electrical system shall automatically illuminate all of the following areas:
  - Aisles and unenclosed egress stairways in rooms and spaces that require two or more means of egress.
  - Corridors, exit enclosures and exit passageways in buildings required to have two or more exits.
  - Exterior egress components at other than their levels of exit discharge until exit discharge is accomplished for buildings required to have two or more exits.
    - All components to the access to public way must be illuminated
  - Interior exit discharge elements, as permitted in Section 1027.1 of the MSBC, in buildings required to have two or more exits.
  - Exterior landings as required by Section 1008.1.6 for exit discharge doorways in buildings required to have two or more exits.
- The emergency power system must provide power for a duration of not less than 90 minutes and must consist of storage batteries, unit equipment or an on-site generator. The installation of the emergency power system must be in accordance with Chapter 27 of the MSBC.
- Emergency lighting facilities must be arranged to provide initial illumination that is at least an average of 1 foot-candle (11 lux) and a minimum at any point of 0.1 foot-candle (1 lux) measured along the path of egress at floor level. Illumination levels are permitted to decline to 0.6 foot-candle (6 lux) average and a minimum at any point of 0.06 foot-candle (0.6 lux) at the end of the emergency lighting time duration. A maximum-to-minimum illumination uniformity ratio of 40 to 1 must not be exceeded.

## **FIRE PROTECTION SYSTEMS**

### ***SUMMARY OF FIRE PROTECTION FEATURES***

*The following Fire Protection and Life Safety Features are being provided in the building:*

1. The building will be constructed of a Type IB fire resistive non-combustible construction.
2. The building will be fully sprinklered and provided with standpipes as outlined in this section.
3. A manual fire alarm system will be provided in the building and will meet current NFPA 72 spacing requirements
4. Emergency voice/alarm communication systems will be installed in accordance with Section 907.2.3
5. Emergency Power and Standby Power for all life safety systems
  - a. At least one elevator will be available to operate on Standby power
  - b. Egress Signage and Lighting will be provided with Emergency Power.
  - c. The atrium smoke control system will be provided with Standby Power.
6. Portable fire extinguishers are being provided in supervised locations in accordance with NFPA 10.
7. The system will be zoned relative to an atrium zone and non-atrium zone.

### ***AUTOMATIC SPRINKLER PROTECTION***

The Fuller School will be provided with an automatic sprinkler system as required for Group E occupancies with fire areas larger than 12,000 square feet and as required by the M. G. L. 148 26 G. The atrium and stage are also required to be provided with sprinkler protection. The design densities of the sprinkler system will be determined by the engineer of record.

**It should be noted that the auditorium on Level 1 of the building is currently designed with cloud ceilings below the roof of the space. The cloud ceilings are constructed of wood, thus the ceilings are combustible. The sprinkler approach for the cloud ceiling involves providing sprinklers above and below the clouds to ensure adequate performance of the sprinkler system with respect to the clouds and to the areas below the cloud ceilings. The design complies with the current MSBC and NFPA 13 and will be further discussed by Framingham Fire Department. As the cloud ceilings are provided with sprinkler protection above and below, they are permitted to be Class A, B, or C interior finish in accordance with MSBC Section 803.13.2 (below)**

**803.13.2 Set-out construction.** Where walls and ceilings are required to be of fire-resistance-rated or noncombustible construction and walls are set out or ceilings are dropped distances greater than specified in Section 803.13.1, Class A finish materials, in accordance with Section 803.1.1 or 803.1.2, shall be used.

#### **Exceptions:**

1. Where *interior finish* materials are protected on both sides by an *automatic sprinkler system* in accordance with Section 903.3.1.1 or 903.3.1.2.
2. Where *interior finish* materials are attached to noncombustible backing or furring strips installed as specified in Section 803.13.1.1.

### ***STANDPIPES***

Standpipes are required throughout the building when the highest floor is greater than 30 feet above the lowest level of fire department access (MSBC Section 905). **Based on the building elevation drawings provided by JLA, the building height from the lowest level of fire department vehicle access to the highest occupiable floor is 28-feet. It should be confirmed by JLA that the lowest level of fire department access is the first floor and that the landscape around the building is not sloped to provide fire department access at a lower point. It should be noted that Class I standpipes are permitted in buildings provided with automatic sprinkler protection in lieu of a Class III standpipe.**

It should also be noted that the stage will require a Class III wet standpipe system with a 1 ½-inch hose connection installed in accordance with NFPA 13 or NFPA 14 on each side of the stage (Section 905.3.4). This requirement is applicable as the stage is greater than 1,000 square feet in area.

### ***FIRE ALARM***

Section 907.2.3 requires a manual fire alarm system for group E occupancies having an occupant load that exceeds 50. The manual fire alarm system must initiate emergency voice/alarm communication features in the building. Where smoke detectors or automatic sprinkler systems are installed, the systems must be connected to the building fire alarm system. **It should be noted that manual fire alarm boxes are not required in Group E occupancies where the building is fully sprinklered, the emergency voice/alarm communication system will activate upon sprinkler waterflow, and where manual activation is provided from normally occupied spaces.**

### **Manual Fire Alarm Pull Stations**

Manual fire alarm devices will be located no more than five (5) feet from the entrance to each exit. Additional manual fire alarm boxes will be located so that travel distance to the nearest box is no more than 200 feet. A Manual pull station will also be provided in a constantly attended locations to provide the capability to manually activate the fire alarm system in an emergency situation.

### ***SMOKE CONTROL***

As indicated in the atrium design section of this report, the atrium will require a smoke control system designed in accordance with MSBC Section 909. The system may be designed as either a natural or mechanical ventilation system, and an engineering rational analysis should be provided to document the intended design of the system function. A smoke control panel must be provided in accordance with MSBC Section 909.16. As indicated throughout this report, the smoke control system must be provided with standby power.

**Refer to Appendix A for the atrium Smoke Control Rational Analysis.**



### ***EMERGENCY POWER***

The following systems shall be provided with emergency power:

1. Emergency lighting along the means of egress in the building and along the exit discharge at a minimum level of 1-foot candle. Emergency lighting shall be provided in those rooms when the area is occupied. Subject to the approval of the Authorities Having Jurisdiction.
  - a. Complete Emergency Lighting shall be provided to the exit discharge of the building exits as determined by the Authorities Having Jurisdiction.
2. Fire Alarm System and all associated equipment including but not limited to the following:
  - a. Fire alarm control panels (including all fire alarm control equipment throughout the facility).
  - b. Fire alarm controls.
  - c. Fire alarm power supply booster panels.
  - d. Digital fire alarm communicators and interface equipment.
  - e. Dedicated telephone line from the Fire Alarm Control Panel dialer.
  - f. Manual pull stations
3. Exit and Directional Exit Signs.
4. Elevators (transferable)
5. Power Operated Locks (if provided)
  - a. Manual override controls for any electric locking or hardware in the entire building.

It should be noted that the atrium smoke control system will be required to be provided with standby power.

### ***ELEVATOR PROVISIONS***

An elevator is proposed in the southwest portion of the building which will serve the first through the third floor and will provide roof access.

Phase I and Phase II recall equipment prescribed by the ASME 17.1 elevator code will be provided for the elevators. Accessible elevators shall be located with the required travel distance as per the Accessibility Standards.

**Two-way communication devices must be provided at elevator lobby areas above grade (i.e. second and third floors).**

**It should be noted that the elevator machine room will require a fire-resistance rating matching the rating of the elevator shaft. This rating must be provided where openings are provided from the elevator machine room into the elevator shaft as the machine room directly abuts the elevator shaft. The elevator machine room is currently designed with openings into the elevator shaft, thus the machine room will be provided with a 2-hour rating to match the rating of the elevator shaft.**

### ***PORTABLE FIRE EXTINGUISHERS***

The Massachusetts State Fire Code (MSFC) adopts and amends the 2015 edition of NFPA 1, which requires fire extinguishers in Groups A, B, and E occupancies. As such, fire extinguishers must be provided throughout all enclosed areas of the building. Portable fire extinguishers will be provided in locations where required by NFPA 10. Basic requirements are as follows.

In accordance with MSBC Section 906.1, extinguishers will be required in the following locations:

- Not more than 75 feet of travel distance to a fire extinguisher. Fire Extinguishers need not be located in each room if the travel distance can be achieved and the extinguisher has the correct hazard classification for each hazard within the 75-foot travel distance.
- Portable Class BC in elevator machine rooms and kitchens (kitchens may require class K depending on contents and use)
- Shall not exceed 40 lbs. capacity

### **Actual Mounting Locations (2013 Edition NFPA 10)**

- Bottom of extinguisher at least 4" above the floor
- Top of extinguisher not more than 5 ft. above the floor
- 1-6.6 Fire extinguishers shall not be obstructed or obscured from view
- 1-6.5 Cabinets shall not be locked (However, if extinguishers are in locations subject to malicious use, the cabinets can be locked, but there must be a means to open them in an emergency. Example: breaking the glass)
- 1-6.3 Fire extinguishers shall be conspicuously located where they will be readily accessible and immediately available in the event of a fire. Preferably they shall be located along normal paths of travel, including exits from areas.
- 1-6.11 Operating instruction shall be located on the front of the extinguisher and be clearly visible (manufacturer requirement)
- 1-6.12 Fire extinguishers mounted in cabinets or wall recesses shall be placed so that the fire extinguisher operating instructions face outward.
- The location of such fire extinguishers shall be marked conspicuously (see 1-6.6)

### ***FIRE DEPARTMENT ACCESS***

Per 527 CMR Section 18.2.3.2, a fire department access road must be maintained / provided in a manner that allows for at least one (1) exterior door to be within 50 feet of the access road that can be opened from the outside. In addition:

- All points of the building must be within 150 feet of the fire department access road which is increased to 250 feet when the building is protected throughout by an automatic sprinkler system.
- The fire department access road must have an unobstructed width of not less than 20 feet, and an unobstructed vertical clearance of 13 feet 6 inches.
- A minimum 25-foot turning radius must be provided / maintained.
- The access road must be designed and maintained to support the imposed loads of fire department apparatus and must be provided with an all-weather driving surface.
- Turning radius must be approved by the AHJ, with a minimum turning radius of 25 feet.
- Where necessary, dead ends are permitted provided they do not exceed 150 feet in cumulative length.
- The access road plan must include an analysis and evaluation of fire apparatus maneuvers throughout the access roads created by sweep path analysis and turn simulation software.

### ***EMERGENCY RESPONDER RADIO COVERAGE***

Per the MSBC Section 916.1, all buildings must have approved radio coverage for emergency responders within the building based upon the existing coverage levels of the public safety communication systems of the jurisdiction at the exterior of the building. This section does not require improvement of the existing public safety communication systems. The emergency responder radio coverage must be in accordance with Section 510 of the International Fire Code.

The building is considered to have acceptable emergency responder radio coverage when signal strength measurements in 95 percent of all areas on each floor of the building have a minimum signal strength of -95 dBm must be receivable within the building and a minimum signal strength of -100 dBm must be received by the agency's radio system when transmitted from within the building. **A bi-directional antenna should be provided for the project. Further discussion with Framingham is required to determine the number of antennas needed for Fire, Police and EMS.**

## **ACCESSIBILITY**

As a new construction building, the Fuller School will be designed to be fully accessible and comply with MAAB as well as the 2010 Americans with Disabilities Act.

### ***GENERAL REQUIREMENTS***

The Fuller School must be designed to meet MAAB as well as the 2010 Americans with Disabilities Act. Both ADAAG and MAAB require that all entrances are accessible, changing rooms and showers are accessible, and that all bathrooms be designed to be accessible. Finally, it should be noted that MAAB requires all exterior pathways to be fully accessible and that if parking is provided that a certain percentage be accessible.

The following accessible features should be provided in the building.

- All bathrooms and locker rooms should be accessible. Locker rooms should include the following features:
  - 36-inch wide accessible routes around all lockers. (including between benches and lockers)
  - 5% but not less than one accessible locker. 36" wide space should be provided between benches and lockers
  - At least one accessible shower stall
  - Accessible toilet and plumbing fixtures
- The elevator will be fully accessible and meet gurney requirements
- All entrances must be accessible
- All exterior walkways must be accessible
- Classrooms must be accessible including all laboratory/ science classrooms. 5% but not less than one (1) of each type of equipment/ learning station should be accessible
- All exterior paths should be accessible

### ***Public and Common Use Spaces***

The public and common use spaces are those spaces inside or outside the buildings that are used by residents and/or visitors. This includes the parking and assembly spaces on the ground floor. These spaces must be accessible per the requirements of 521 CMR and the 2010 ADAAG. These spaces should be on an accessible route at least 36- inches wide which connects accessible parking, accessible entrances, and public and common use spaces. Wherever possible, the accessible route should be the shortest possible route (521 CMR 10.2). All doorways and openings located in common use and public use spaces and along accessible routes should comply with 521 CMR Sections 26.2 through 26.11 and ADAAG Section 404.

**Accessible Means of Egress**

All spaces or elements that are required to be accessible must be provided with at least one accessible means of egress. In spaces required to be provided with multiple means of egress, each space must be served by at least two accessible means of egress. Exit access stairways are permitted to be considered part of the accessible means of egress when they are provided with a clear width of at least 48 inches between the handrails and two-way communication is provided at the elevator landings in accordance with 780 CMR Section 1009.3. The building is fully sprinklered and areas of refuge are not required to be provided at the exit access stairways. Two-way communication is required to be provided at the elevator landings, so that the exit access stairways in the school can be considered as part of the accessible means of egress.

**Parking**

Parking will be provided in accordance with the following MAAB table based on the number of spaces provided for the residential occupants and the potential assembly occupants. **One in eight accessible spaces, but not less than one, must be van accessible.**

23.2.1	<u>Total Parking in Lot</u>	<u>Required Minimum Number of Accessible Spaces</u>
	15-25	1
	26-50	2
	51-75	3
	76- 100	4
	101-150	5
	151-200	6
	201-300	7
	301-400	8
	401-500	9
	501-1,000	2% of total
	1,001 and over	20 plus 1 for each 100 over 1000

**Accessible Seating Requirements**

In places of assembly with fixed seating, the minimum number of accessible spaces provided must be in accordance with the table below:

<u>Total Seating</u>	<u>Wheelchair Spaces</u>
4 to 25	1
26 to 50	2
51 to 300	4
301 to 500	6
over 500	6, one additional space for each total seating capacity increase of 100.

When more than 150 seats are provided, the wheelchair seating locations must be provided in more than one (1) location and must be dispersed through the seating area. Accessible seating must be integral with the rest of the seating (i.e. shoulder to shoulder). Bleachers should be ordered with cutouts where accessible seating will be provided.

It should also be noted that ADAAG requirements will be applicable to the project. ADAAG Table 221.2.1.1 also requires six (6) wheelchair spaces to be provided in the auditorium as the space will have 412 fixed seats.

In addition to wheelchair seating locations, 1% of all fixed seats must be a companion seat consisting of an aisle seat with no armrests on the aisle side (or with removable or folding armrests on the aisle side).

Accessible seating positions are permitted to be clustered for bleachers, balconies and other areas having sight lights with a slope greater than 5%. Equivalent accessible viewing positions may be located on levels having accessible egress.

Ticket box offices and concession stands must be located on an accessible route, and a portion of the counter must be a maximum of 36 inches high for a length of at least 36 inches. A counter or auxiliary counter can be used to achieve this requirement.

**It should be noted that accessible seating must be provided in both the auditorium and the gym, which is provided with telescoping bleacher seating. The auditorium is provided with 412 fixed seats, thus must be provided with six (6) wheelchair seats (with a companion seat directly adjacent to the wheelchair space). The gymnasium must be provided with cutout sections in the telescoping seating to accommodate wheelchair spaces.**

**Additionally, within the auditorium spaces, assistive listening devices must be provided.** Assembly areas that accommodate at least 50 persons or with an audio-amplification systems must be provided with permanently installed assistive listening systems (521 CMR 14.5.1). If the assistive listening system serves individual fixed seats, such seats must be located within a 50-foot viewing distance of, and including the stage, and must have a complete view of the stage (521 CMR 14.5.3). Signage must be provided to notify patrons of the availability of a listening system and must comply with the signage provisions of 521 CMR 41.00.

**An accessible route must be provided to the performance area within the auditorium.**

**Where classrooms are provided with fixed seating, at least 5% but not less than one will be provided with an accessible route, accessible clear floor space, knee clearance, and table heights.**

## **PLUMBING FIXTURES**

The Massachusetts Plumbing Code requires specific plumbing fixtures for various spaces in the building. The number of plumbing fixtures shall be determined based on the following factors, as excerpted from the Massachusetts State Plumbing Code, Section 10.10 Table 1.

The following table outlines the plumbing fixture requirements for new construction. The factors that dictate the fixture counts for the building depend on the intended and future function of the Fuller School. It should be noted that separate toilet facilities are required for staff and students.

Occupancy	Water closets			Lavatories		Drinking Fountains	Other Fixtures
	Male	Female	Urinals	Male	Female		
Education (Secondary)	1 per 90	1 per 30	1 per 90	1 per 90	1 per 90	1 per 75	1 service sink per floor
Education (Staff)	1 per 25	1 per 20	33% substitution	1 per 40	1 per 40	-	1 service sink per floor
Auditorium	1 per 600 seats	1 per 200 seats	1 per 200 seats	-	-	-	-

The following tables outline the required plumbing fixtures for the Fuller School based on the use of a programmatic occupant load. A program occupant load captures the intended use of spaces, as opposed to the calculated occupant load which tends to be more conservative in nature. **The use of a program occupant load requires discussion and approval from the plumbing official.**

Gender neutral toilets have been discussed for the building. The following provisions are applicable for the installation of gender-neutral toilets in the Fuller School:

1. Gender neutral facilities are permitted for employees
2. Gender neutral toilets can only be counted one time towards plumbing fixture counts. Thus, they may be counted as either Male or Female.
3. When two (2) or more toilet facilities are required, Gender Neutral Toilets may replace these fixtures but only in pairs (E.g. one replaces a Male and the other replace a female fixture).
4. Once the minimum number of fixtures is provided Gender Neutral Toilets can be singularly provided.

**It should also be noted that 248 CMR Section 10.10(18)(h).6 requires all secondary schools that conduct physical activities on the school premises to be provided with separate men’s and women’s shower facilities to accommodate students. Based on preliminary discussion with the plumbing official, showers will be required at Framingham Fuller School. Showers should be provided for the largest population expected to use them at a given time (e.g. physical education class, or after school sporting event).**

**Fuller Plumbing Fixtures Calculation**  
630 Students 120 Staff

**Educational Use - Use Group E (elementary)**

Required Fixtures per Code	Occupants		Unisex Toilet		Toilet - Female		Toilet - Male		Urinals		Lavatories each sex		Drinking Fountain	
	Male	Female	Required	Provided	Required	Provided	Required	Provided	Required	Provided	Each sex Required	Each sex Provided	Required	Provided
Students			1 per 30		1 per 90		1 per 90		1 per 90		1 per 90		1 per 75	
Staff			1 per 20		1 per 25		33%		1 per 40					

Floor Level	Occupants		Unisex Toilet		Toilet - Female		Toilet - Male		Urinals		Lavatories		Drinking Fountain		Classrm Sinks	Showers	Mop Sinks	Notes
	Total	Male	Female	Required	Provided	Required	Provided	Required	Provided	Each sex Required	Each sex Provided	Required	Provided					
Floor 1 Students	210	105	105	0	1	4	12	2	5	2	7	2	11	3				
Floor 1 Staff	40	20	20	0	13	1	-	1	-	1	1	1	1	-				3
Floor 2 Students	210	105	105	0	1	4	8	2	2	2	6	2	8	3				
Floor 2 Staff	50	25	25	0	3	2	-	1	-	1	1	1	1	-				2
Floor 3 Students	210	105	105	0	1	4	8	2	2	2	6	2	8	3				
Floor 3 Staff	30	15	15	0	2	1	-	1	-	1	1	1	1	-				2
<b>750</b>	<b>375</b>	<b>375</b>	<b>0</b>	<b>21</b>	<b>16</b>	<b>28</b>	<b>9</b>	<b>19</b>	<b>9</b>	<b>9</b>	<b>30</b>	<b>30</b>	<b>9</b>	<b>9</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>7</b>

**Unisex Toilets provided:**  
 Staff 1 Central Office  
 Students 3 SPED  
 1 at Lockers  
 1 Medical Suite  
 1 Kitchen  
 6 General

**Total Toilet Fixtures Required 34**  
**Total Toilet Fixtures Provided 77**

**Community Service Areas - Use Group E - Non-Simultaneous Use**

420 Auditorium, 600 Gym

Required Fixtures per Code	Toilet Female Required	Toilet Male Required	Urinals Male Required
1 per 200	1 per 200	1 per 600	1 per 200

**Assembly Use**

Floor Level	Occupants		Unisex Toilet		Toilet - Female		Toilet - Male		Urinals		Drinking Fountain		Classrm Sinks	Showers	Mop Sinks	Notes	
	Total	Male	Female	Required	Provided	Required	Provided	Required	Provided	Each sex Required	Each sex Provided	Required					Provided
Floor 1	1,020	510	510	3	7	1	2	3	5								Plus 2 Unisex

**Total Toilet Fixtures Required 7**  
**Total Toilet Fixtures Provided 14 17 With Unisex**




## **CONCLUSION**

The building is to be constructed in accordance with the requirements of the applicable Codes. During this process, the building will be designed to provide levels of safety at least equivalent to the provisions contained in the applicable codes. To achieve these levels of safety, the following primary features are provided:

1. The Building will be of Type IB fire resistive non-combustible construction and will comply with the separated mixed-use provisions of the MSBC.
2. The building will be fully sprinklered and provided with standpipes as outlined herein.
3. The means of egress system will be provided as outlined in this report and will meet the requirements of MSBC.
  - a. Classrooms are proposed to use the actual number of students/ staff as opposed to the calculated occupant load.
  - b. Open stairs will be used as part of the exit access as permitted by Chapter 10 of the MSBC.
4. The building will be provided with a manual fire alarm system and emergency voice/alarm communication abilities.
5. The atrium will be provided with a smoke control system that maintains tenability 6-feet above the highest walking surface. The smoke control system will be provided with standby power.
6. The building will be designed to be fully accessible in accordance with MAAB and ADAAG.
7. Plumbing fixtures will be provided in accordance with the provisions in the tables detailed above.


Prepared by,

Howe Engineers, Inc.

  
\_\_\_\_\_  
Jeremy A. Mason, P.E.<sup>(MA)</sup>  
Associate Principal

**APPENDIX A: SMOKE CONTROL BASIS OF DESIGN**

# SMOKE CONTROL RATIONAL ANALYSIS



## FRAMINGHAM FULLER MIDDLE SCHOOL FRAMINGHAM, MA

Prepared for:



Jonathan Levi Architects  
266 Beacon Street  
Boston, MA 02116

Prepared by:



101 Longwater Circle, Suite 203  
Norwell, MA 02061  
Phone: 781.878.3500  
Fax: 781.878.3551

**SUBMITTED: OCTOBER 15, 2019**  
**Smoke Control System Design**

**Table of Contents**

PURPOSE .....5

APPLICABLE CODES AND STANDARDS .....5

PROJECT DESCRIPTION .....6

DESIGN OBJECTIVE .....6

METHODOLOGY .....6

    CFD MODELING .....7

DESIGN ASSUMPTIONS .....7

    SMOKE CONTROL CONFIGURATION .....8

        EXHAUST CONFIGURATION .....8

        MAKEUP AIR CONFIGURATION .....10

    DESIGN FIRE .....13

*Design Fire Selection and Details* .....14

            Location Analysis .....14

            Scenario 1 – Axisymmetric Design Fire Selection .....16

            Scenario 2 – Balcony-Spill (Beneath Floor 3 Walking Surface) Design Fire Selection .....17

            Scenario 3 – Balcony-Spill (Beneath Floor 3 Walking Surface) Design Fire Selection .....19

            Scenario 4 – Balcony-Spill (Beneath Floor 2 Walking Surface) Design Fire Selection .....21

TENABILITY CRITERIA & THRESHOLDS .....23

    SMOKE TOXICITY .....23

    HEAT EXPOSURE .....25

    VISIBILITY .....25

CFD MODELING ANALYSIS .....27

    GENERAL CFD MODELING PARAMETERS ASSUMPTIONS .....27

    FDS MESH RESOLUTION .....27

    CFD RESULTS .....28

*Scenario 1 – 3,500 kW Axisymmetric Fire Results* .....31

            SCENARIO 1 SMOKE TOXICITY RESULTS .....31

            SCENARIO 1 HEAT EXPOSURE RESULTS .....34

            SCENARIO 1 VISIBILITY RESULTS .....36

*Scenario 2 – 2,750 kW Balcony-Spill (Beneath Level 3 Walking Surface) Fire Results* .....38

            SCENARIO 2 SMOKE TOXICITY RESULTS .....38

            SCENARIO 2 HEAT EXPOSURE RESULTS .....41

            SCENARIO 2 VISIBILITY RESULTS .....43

*Scenario 3 – 2,100 kW Balcony-Spill (Beneath Level 3 Walking Surface) Fire Results* .....45

            SCENARIO 3 SMOKE TOXICITY RESULTS .....45

            SCENARIO 3 HEAT EXPOSURE RESULTS .....48

            SCENARIO 3 VISIBILITY RESULTS .....50

*Scenario 4 – 1,100 kW Balcony-Spill (Beneath Level 2 Walking Surface) Fire Results* .....52

            SCENARIO 4 SMOKE TOXICITY RESULTS .....52

            SCENARIO 4 HEAT EXPOSURE RESULTS .....55

            SCENARIO 4 VISIBILITY RESULTS .....57

*Summary of Results* .....59

    ADDITIONAL INTERNATIONAL BUILDING CODE SECTION 909 RATIONALE .....60

        HVAC Systems .....60

        Separation Distance .....60

        Stack Effect .....60

        Buoyancy .....61

        Stratification Analysis .....61

        Climate .....61

        Smoke Control Equipment Temperature .....61

Smoke Control Rational Analysis

---

EQUIPMENT AND CONTROLS..... 62

    SECONDARY POWER ..... 62

    EQUIPMENT..... 62

    FIREFIGHTER’S SMOKE CONTROL PANEL..... 64

    SEQUENCE OF OPERATION ..... 65

SPECIAL INSPECTION AND TEST REQUIREMENTS ..... 66

    OVERVIEW ..... 67

    COMPONENT AND ACCEPTANCE TESTING CONDITIONS..... 68

    PASS CRITERIA ..... 68

    FAILURE CRITERIA..... 69

    PERIODIC TESTING REQUIREMENTS ..... 69

CONCLUSION..... 70

APPENDIX A – HEAT RELEASE RATES..... 71

*Example: Two-Panel Workstation Fire*..... 72

    PUBLISHED HEAT RELEASE RATES (UNITED STATES RESEARCH) ..... 75

APPENDIX B – ATRIUM ZONE BOUNDARY..... 77

APPENDIX C – TIMED EGRESS ANALYSIS..... 79

    DETECTION TIME PHASE..... 79

    PRE-MOVEMENT TIME PHASE ..... 80

    MOVEMENT TIME PHASE ANALYSIS ..... 81

*Timed Egress Calculations*..... 81

            Moderate Movement Conditions..... 81

            Flow Time ..... 81

            Travel Time..... 83

CONCLUSIONS..... 84

**List of Figures**

Figure 1: Smoke Exhaust Configuration (RCP Floor 3) .....8

Figure 2: Smoke Exhaust Configuration (RCP Floor 2) .....9

Figure 3: Makeup Air Configuration – Floor 1 (Plan View) ..... 11

Figure 4: Makeup Air Configuration – Floor 2 (Plan View) ..... 12

Figure 5: Makeup Air Configuration – Floor 3 (Plan View) ..... 13

Figure 6: Floor 1 Fire Locations ..... 15

Figure 7: Kiosk Heat Release Rates with Variations ..... 16

Figure 8: Diagram of Alpert’s Equations Variables ..... 17

Figure 9: Scenario 2 Sprinkler Activation Calculation ..... 18

Figure 10: Diagram of Alpert’s Equations Variables ..... 19

Figure 11: Scenario 3 Sprinkler Activation Calculation ..... 20

Figure 12: Diagram of Alpert’s Equations Variables ..... 21

Figure 13: Scenario 4 Sprinkler Activation Calculation ..... 22

Figure 14: SFPE Handbook, 5<sup>th</sup> Edition, Figure 63.14 ..... 24

Figure 15: SFPE Handbook, 5<sup>th</sup> Edition, Figure 63.28 ..... 25

Figure 16: Predicted Makeup Air Velocity – Floor 1 (Plan View) ..... 30

Figure 17: Scenario 1 – Section View through Fire of CO Concentration ..... 32

Figure 18: Scenario 1 – CO concentration 6 ft. above Floor 3 Walking Surface ..... 33

Figure 19: Scenario 1 – Section View through Fire of Temperature ..... 34

Figure 20: Scenario 1 – Temperature 6 ft. above Floor 3 Walking Surface ..... 35

Figure 21: Scenario 1 – Section View through Fire of Visibility ..... 36

Figure 22: Scenario 1 – Visibility 6 ft. above Floor 3 Walking Surface ..... 37

Figure 23: Scenario 2 – Section View through Fire of CO Concentration ..... 39

Figure 24: Scenario 2 – CO concentration 6 ft. above Floor 3 Walking Surface ..... 40

Figure 25: Scenario 2 – Section View through Fire of Temperature ..... 41

Figure 26: Scenario 2 – Temperature 6 ft. above Floor 3 Walking Surface ..... 42

Figure 27: Scenario 2 – Section View through Fire of Visibility ..... 43

Figure 28: Scenario 2 – Visibility 6 ft. above Floor 3 Walking Surface ..... 44

Figure 29: Scenario 3 – Section View through Fire of CO Concentration ..... 46

Figure 30: Scenario 3 – CO concentration 6 ft. above Floor 2 Walking Surface ..... 47

Figure 31: Scenario 3 – Section View through Fire of Temperature ..... 48

Figure 32: Scenario 3 – Temperature 6 ft. above Floor 2 Walking Surface ..... 49

Figure 33: Scenario 3 – Section View through Fire of Visibility ..... 50

Figure 34: Scenario 3 – Visibility 6 ft. above Floor 2 Walking Surface ..... 51

Figure 35: Scenario 4 – Section View through Fire of CO Concentration ..... 53

Figure 36: Scenario 4 – CO concentration 6 ft. above Floor 3 Walking Surface ..... 54

Figure 37: Scenario 4 – Section View through Fire of Temperature ..... 55

Figure 38: Scenario 4 – Temperature 6 ft. above Floor 3 Walking Surface ..... 56

Figure 39: Scenario 4 – Section View through Fire of Visibility ..... 57

Figure 40: Scenario 4 – Visibility 6 ft. above Floor 3 Walking Surface ..... 58

Figure 41: Scenario 3 – Section View through Fire of Temperature ..... 61

Figure 42: Kiosk Heat Release Rates with Variations ..... 71

Figure 43: Heat Release Rate vs. Time (Individual Two-Panel Workstation Fire) ..... 72

Figure 44: Two Panel Workstation fire at time 0:00 and 2:00 minutes ..... 72

Figure 45: Two Panel Workstation fire at time 4:00 and 6:00 minutes ..... 73

Figure 46: Two Panel Workstation fire at time 8:00 and 10:00 minutes ..... 73

Figure 47: Two Panel Workstation fire at time 20:00 and 30:00 minutes ..... 73

Figure 48: Two Panel Workstation fire at time 42:00 minutes ..... 74

Figure 49: Floor 1 – Atrium Boundary Zone ..... 77

Figure 50: Floor 2 – Atrium Boundary Zone ..... 78

Figure 51: Floor 3 – Atrium Boundary Zone ..... 78

Figure 52: Egress Time Model ..... 79

**PURPOSE**

This report presents the design concept for the smoke control system provided within the Framingham Fuller Middle School in Framingham, Massachusetts, which will include a three (3) story atrium that connects the First Floor through Third Floor. The basis of this analysis represents the requirements of the Massachusetts State Building Code (MSBC), which is based on the International Building Code (IBC). The proposed smoke control system design will utilize the large smoke-filling reservoir (i.e., passive system) along with mechanical exhaust systems to maintain tenability 6 feet above the highest means of egress walking surface open to the atrium. The proposed design will be evaluated using a Computational Fluid Dynamics (CFD) model, known as Fire Dynamic Simulator (FDS), to demonstrate the design concepts of the smoke control system are compliant with the applicable codes.

**APPLICABLE CODES AND STANDARDS**

The following codes and standards are currently applicable to this project:

- 780 CMR Massachusetts State Building Code (MSBC), 9<sup>th</sup> Edition
  - 2015 International Building Code (IBC), with state amendments
  - 2015 International Mechanical Code (IMC), with state amendments
- Massachusetts Fire Prevention Code
  - 2015 Edition of NFPA 1, *The Fire Code*, with state amendments

Reference Standards from the Massachusetts State Building Code:

- 2015 Edition of NFPA 92, *Standard for Smoke Control Systems*
- 2009 Edition of NFPA 92B, *Standard for Smoke Management Systems in Malls, Atria and Large Spaces*

**PROJECT DESCRIPTION**

The Design Team is proposing a design for a new middle school located in Framingham, MA. The proposed building will be a newly constructed, three (3) story building with a footprint area of approximately 64,780 square feet. The building contains primarily Group E Educational spaces for middle school students (6<sup>th</sup> to 8<sup>th</sup> grade), with accessory office and lounge spaces. There is a gymnasium and auditorium on the north side of the building that will be considered Group A-3 assembly spaces as public events will likely be held in these spaces. Floors 1 and 2 serve as the primary circulation levels and provides the exits and entrances to the building. The floor levels of the project are described as follows:

Floor Level	Description
Floor 1	Classrooms, Lab Spaces, Gymnasium, Auditorium, Lounges, Offices, Storage, MEP
Floor 2	Classrooms, Lounges, Offices, Storage, MEP
Floor 3	Classrooms, Lounges, Offices, Storage, MEP

**DESIGN OBJECTIVE**

The design objective of this analysis, is to demonstrate compliance with the intent of the Building Code utilizing the natural smoke filling space and mechanical smoke control system to maintain tenable conditions along the means of egress during a fire event for a minimum of 1.5 times the required safe egress time, or 20 minutes, whichever is greater (MSBC Section 909.4.6). A tenable environment must be maintained at least 6 feet above any walking surface that forms a portion of the required means of egress system when traveling through the atrium spaces that are not intimate with fire ignition (MSBC Section 909.8.1).

**METHODOLOGY**

In order to demonstrate code compliance, the smoke control system must be evaluated using an engineering analysis that addresses characteristics of fuel load, separation requirements, heat release rates, and sprinkler effectiveness (MSBC Sections 909.4 and 909.8). In addition to these elements, this smoke control design will also utilize additional requirements as laid out by NFPA 92 Standard for Smoke Control Systems, and ASHRAE “Design of Smoke Management Systems” where not specifically addressed by the Building Code.

The ASHRAE “Design of Smoke Management Systems” manual and most recognized Building Codes indicate that effective smoke control design recommends multiple design approaches for large volume spaces when designing an effective system. These primary design approaches are:

1. Utilizing the large-volume space as a smoke reservoir and modeling smoke layer descent to determine if occupants are able to egress the space before they are exposed to smoke.
2. Removing the smoke in the large-volume space using a mechanical exhaust system sufficient to maintain the smoke layer interface at a predefined height for an indefinite period of time.
3. Removing smoke from the large-volume space, using a mechanical exhaust capacity that slows the rate of smoke layer descent for a period that allows occupants to safely egress the space.
4. Providing natural venting sufficient to maintain the smoke layer interface at a predefined height for an indefinite period of time.



---

**Smoke Control Rational Analysis**

---

5. Providing natural venting sufficient to slow the rate of smoke layer descent for a period that allows occupants to safely egress the space.

To provide a comprehensive and conservative design basis, the smoke control system will utilize the inherent large-volume space (Item 1 above) of the atrium skylight to provide a smoke reservoir which will aid the mechanical smoke control system (Item 2/3 above) to maintain tenability for a minimum of 1.5 times the calculated required safe egress time, or 20 minutes after detection, whichever is greater (MSBC Section 909.4.6).

NFPA 92, Section 5.1 provides a number of methods to justify the smoke control design approach chosen above, including basic algebraic calculations, compartment fire models, scale modeling, and zone models. NFPA 92 recommends computational fluid dynamics (CFD) modeling when evaluating complicated building geometries such as overhangs, pitched ceiling structures, and mesh ceiling structures causing smoke to spill to adjacent occupiable spaces.

**CFD MODELING**

A Computational Fluid Dynamics (CFD) model is used to evaluate the design fire scenarios within the Atrium Zone of the Framingham Fuller Middle School. CFD computer modeling is an advanced modeling method that is capable of predicting realistic heat and fluid flow through a space. The model consists of dividing a volume into a large number of small cubes (usually thousands or millions) and solving the fundamental conservation equations to calculate the movement of heat and mass across each cube as a function of time. The fundamental conservation equations include mass, energy, and momentum.

For the purposes of this analysis, a CFD modeling program called Fire Dynamics Simulator (FDS), Version 6.6.0, developed by the National Institute of Standards and Technology (NIST), will be used. This model has been developed for use in low speed transport of heat and combustion products from fire, as well as radiative and convective heat transfer between gas and solid surfaces. Further, the model has been verified for this type of application as indicated in the references provided in NFPA 92 Section A5.1.3. This model is available online at [www.fire.nist.gov](http://www.fire.nist.gov).

**DESIGN ASSUMPTIONS**

For the purpose of this analysis, it is not practical to evaluate all conditions for every possible fire scenario. Therefore, several assumptions had to be made to complete this analysis for a realistic worst-case scenario. These assumptions include design fire location, size and configuration, selection of tenability criteria (products of combustion) to evaluate, and tenability thresholds (or failure points). This section of the report is intended to address each of the assumptions in detail.

When sprinklers are provided in the location where the design fire is located, NFPA 92, Section A5.2.1 indicates that the heat release rate and growth of the fire is likely to be decreased or maintained at the value that the fire has reached when sprinklers activate. When applicable, fire sizes will be determined by the sprinkler effectiveness in accordance with MSBC Section 909.9.4.

In accordance with the requirements of the MSBC and NFPA 92, this analysis only contemplates one fire at one location within the building at a time for the design of the smoke control system. Multiple simultaneous fires at multiple locations are not contemplated, nor required to be contemplated by the adopted codes and standards.

Smoke Control Rational Analysis

**SMOKE CONTROL CONFIGURATION**

The building's smoke control system will utilize the exhaust method in accordance with MSBC Section 909.8. The system is comprised of mechanical exhaust fans for exhausting, and automatic-opening doors and louvers for supplying makeup air to maintain a tenable environment six (6) feet above all walking surfaces within the Atrium Zone.

**EXHAUST CONFIGURATION**

The proposed smoke control scheme provides a total of 240,000 cubic feet per minute (CFM) of mechanical exhaust. This is achieved via the exhaust points located at the ceiling of the atrium above the Third-Floor walking surface and located at the ceiling above the Second-Floor walking surface. Refer to Figure 1 and Figure 2 for a diagram of the exhaust configuration.




Figure 1: Smoke Exhaust Configuration (RCP Floor 3)

Smoke Control Rational Analysis




Figure 2: Smoke Exhaust Configuration (RCP Floor 2)

**MAKEUP AIR CONFIGURATION**

To assist in creating an established two-zone smoke layer environment within the atrium, makeup air must be introduced into the fire compartment at low enough velocity so that the plume filling and entrainment is not significantly increased as a result of turbulent flows. NFPA 92 limits air velocities to 200 feet per minute; however, higher velocities may be considered acceptable where supported by an engineering analysis, such as this Rational Analysis that utilizes CFD modeling (NFPA 92 Section 4.4.4.1.4).

Makeup air for the atrium smoke control system is provided via a combination of automatic doors and louvers (refer to Figure 3 through Figure 5), and summarized below. Selected doors/louvers are to be provided with UL 864 (UUKL) *Listed* power-operator motor controls that will activate upon alarm signal from appropriately zoned sprinkler waterflow switches, manual controls and via smoke detection that is located within the Atrium Zone. Refer to the Equipment and Controls section of this report for additional information.

- **Floor 1 (refer to Figure 3):**
  - Automatic Openings
    - Two (2) louvers providing a minimum of 63 ft<sup>2</sup> of free area each
- **Floor 2 (refer to Figure 4):**
  - Automatic Doors / Openings
    - Three (3) exterior single-leaf doors and three (3) interior single-leaf doors providing a minimum of 66 ft<sup>2</sup> of free area
    - Two (2) louvers providing a minimum of 63 ft<sup>2</sup> of free area each
- **Floor 3 (refer to Figure 5):**
  - Automatic Openings
    - Two (2) louvers providing a minimum of 63 ft<sup>2</sup> of free area each

Smoke Control Rational Analysis




Figure 3: Makeup Air Configuration – Floor 1 (Plan View)

Smoke Control Rational Analysis





Figure 4: Makeup Air Configuration – Floor 2 (Plan View)



**Figure 5: Makeup Air Configuration – Floor 3 (Plan View)**

Since the makeup air system relies on selected exterior openings to provide air into the Atrium Zone, it is imperative that the owner maintain the required exterior areas free from any impediments that would cause the doors/louvers not to open in an emergency. Specifically, the owner must maintain the surfaces outside all doors and louvers free from obstruction, including snow/ice accumulation anytime that the building is occupied so that the doors/louvers are capable of opening at any time.

#### ***DESIGN FIRE***

The single most important aspect of the Fire Protection Engineering process is the determination of the design fire for the completion of the modeling. Since, this building is an educational/assembly building that contains open spaces suitable for locating seating, tables and chairs, small displays and similar potential fuel loads, the design fire must be representative of this type of hazard.

The intent of the design fire, as one of the primary aspects of any performance-based analysis, is to be a challenging, but realistic scenario to determine factors critical to the outcome of the possible fire. Any given design fire scenario corresponds to only one of many fire conditions that could occur within a building or space. For this reason, a thorough smoke control design consists of analyzing the multiple fire scenarios considered hazardous to the building, its occupants, and its contents<sup>1</sup>.

<sup>1</sup> SFPE Engineering Guide to Performance-Based Fire Protection Analysis and Design of Buildings, pgs. 41-42, NFPA, Quincy, MA, 2000

**Design Fire Selection and Details**

For every design fire scenario, numerous factors must be explicitly accounted for as part of the analysis. Examples of factors that may directly influence the parameters of the design fire are listed below:

- Location and form of ignition
- Initial type of fuel ignited
- Initial location of fire
- Rate of growth of the fire (particularly the severity of early stages)
- Smoke generation from the fire
- Compartment geometry and configuration at the time of the fire
- Ventilation – mechanical, natural, HVAC
- Type of construction and materials used
- Room furnishings and contents
- Fire protection and life safety systems

Based on discussions with the Design Team, it is anticipated the atrium in the Framingham Fuller Middle School will be used for the following:

- Small sitting or waiting areas, including sofas, chairs, registration desk, other furniture seating, etc. (primary use of the space).
- Circulation/Waiting space
- Low hazard meeting events (includes tables and chairs only)

As such, from a use and fuel load standpoint, the fire load in the atrium will be a light hazard assembly space. For this reason, nationally recognized, published heat release rates have been researched and fire growth computer models have been completed to determine a realistic worst-case scenario for the purposes of analyzing the atrium smoke control system. Examples of typical fuels loads found in similar spaces can be found in Appendix A.


**Location Analysis**

In order to provide a conservative analysis, the design fire sizes were coupled with points of convergence within the means of egress systems. These points of convergence were chosen based on the following criteria and are discussed further in the following sections of this report:

- Largest Number of Potential Exits Blocked by a Single Realistic Fire
- Largest Reduction in Available Exit Capacity by a Single Realistic Fire
- Remoteness of Secondary Means of Egress
- Building Configuration that Limits Fire Protection and Life Safety System Response

Based on a review of the building, criteria listed above, and the smoke control system exhaust and makeup air configuration, the locations identified in Figure 6 are selected as part of this rational analysis.





**Figure 6: Floor 1 Fire Locations**

Scenario 1 consists of an axisymmetric design fire located in the center of the atrium on Floor 1. Such a fire would present the largest defined fire as sprinklers are the highest above the walking surface, allowing the fire to grow to a larger size relative to other areas of the building. Larger fires typically result in larger amounts of heat and hot gas; presenting a challenging scenario. This scenario does not contemplate sprinkler activation.

Scenario 2 consists of a sprinkler-controlled balcony-spill plume fire located on Floor 1 underneath the Floor 3 walking surface within the atrium. Such a scenario presents a challenging configuration as the effects of a balcony-spill allows for the heat and hot gas to cool due to the entrainment of cool air, diluting the smoke, causing the upper gas layer to descend. As such, this is considered a challenging location for the design fire.

Scenario 3 consists of a sprinkler-controlled balcony-spill plume fire located on Floor 1 underneath the Floor 3 walking surface nearby the Floor 2 walking surface. Such a scenario presents a challenging configuration as the effects of a balcony-spill allows for the heat and hot gas to cool due to the entrainment of cool air, diluting the smoke, causing the upper gas layer to descend. As such, this is considered a challenging location for the design fire.

Smoke Control Rational Analysis


Scenario 4 consists of a sprinkler-controlled balcony-spill plume fire located on Floor 1, underneath the Floor 2 walking surface within the atrium and adjacent to the automatic opening louvers. Such a scenario presents a challenging configuration as the effects of a balcony-spill allows for the heat and hot gas to cool due to the entrainment of cool air, diluting the smoke and potentially causing the upper gas layer to descend. Further, by locating the fire adjacent to the automatic opening louvers, the makeup air may disrupt the fire plume further increasing the amount of air entrained in the smoke layer. The intent of this scenario is to determine if a fire on Floor 1 nearby the makeup air openings will affect the surrounding areas of the atrium as intended by the rational analysis requirements in MSBC and NFPA 92.

In a continuing effort to provide a realistic, yet conservative analysis, four (4) specific case scenarios throughout the building are analyzed to evaluate the performance of the building smoke control system. These scenarios, which are based upon the location analysis above, consist of design fires with conservative, yet realistic potential fuel loads as determined in the following sections.

**Scenario 1 – Axisymmetric Design Fire Selection**

It is understood that the atrium will be used primarily for circulation space and is a relatively light hazard space. From a fuel load standpoint, the atrium space may be used for housing small displays, and seating arrangements (tables and chairs, or sofas, etc.). The limitations of this fire size have been discussed with Framingham Fuller Middle School, and this fire size is based on the furniture being located within the atrium.

A sofa fire can reach peak heat release rates of approximately 3,100 kW within 500 seconds before it begins to decay due to fuel consumption. Similarly, a kiosk fires reach a peak heat release rate of 1,800 kW before the fire decays. Using the peak heat release rate of the sofa as our steady state fire value would provide for a conservative analysis. To provide for an extra margin of safety, a fast-growth, steady state fire with an addition safety factor of approximately 10% will be added to the fire size. This allows for ceiling temperatures to rise faster than anticipated due to the fast-growth nature and accumulate as the fire will note decay. **For this reason, the contemplation of a fast growth 3,500 kW steady state fire is considered conservative.** Refer to Figure 7 for a comparison of nationally publicized heat release rate growth profiles compared to the selected fire size used to analyze the smoke control system.




**Figure 7: Kiosk Heat Release Rates with Variations**

**Scenario 2 – Balcony-Spill (Beneath Floor 3 Walking Surface) Design Fire Selection**

When sprinklers are provided in the location where the design fire is located, NFPA 92 Section 5.2.1 indicates that the heat release rate and growth of the fire is likely to be decreased or maintained at the value that the fire has reached when sprinklers activate. MSBC Section 909.9.4 also recognizes this provision. An automatic fire sprinkler system is installed throughout the Framingham Fuller Middle School.

Sprinkler activation calculations have been completed to determine the actual heat release rates where sprinklers activate. The results of this analysis are based on the calculations developed by R.L. Alpert<sup>2</sup> for ceiling jet activation of a sprinkler as shown in Equation 1 and Figure 8.



**Figure 8: Diagram of Alpert's Equations Variables**

By utilizing the Alpert's Ceiling Jet Temperature Correlations, it is possible to predict the temperature of the ceiling jet adjacent to the sprinkler and ultimately determine whether sprinkler activation is expected. The results of the calculation utilizing a small time step, and a fast growth rate fire, are shown in Figure 9. The equations utilized to predict the heat release rate from a fast growth rate t-squared fire as noted in Equation 2.

**Equation 2**

$$\dot{Q} = \alpha(t - t_v)^2$$

$$\dot{Q} = \left(\frac{1,055}{t_g^2}\right)(t - t_v)^2 [kW]$$

$$\dot{Q} = \left(\frac{1,000}{t_g^2}\right)(t - t_v)^2 [Btu/s]$$

Where:

$t_g$  = fire growth time to 1,000 kW (1,055 BTU/s)

$t_v$  = virtual ignition time


$\alpha$  = empirically determined HRR parameter (0.0468 for Fast Growth)

<sup>2</sup> *Ceiling Jet Flows*, p.431, Society of Fire Protection Engineers (SFPE) Handbook, 5<sup>th</sup> Edition, Springer-Verlag New York 2016

Smoke Control Rational Analysis

This analysis utilizes the following assumptions:

1. Sprinklers are located a maximum of approximately 26'-0" above the walking surface
2. Sprinkler activation temperature of 165°F
3. Quick response sprinklers having a maximum Response Time Index of 50 (meter-seconds)<sup>1/2</sup>
4. Ambient temperature within the conditions spaces is 68 degrees
5. Sprinkler spacing is a maximum 15' x 15' or 225 ft<sup>2</sup> is provided
6. Sprinklers are within 12" of ceiling and are located in the ceiling jet region
7. Burning surface of fuel is approximately 3 feet above the walking surface




**Figure 9: Scenario 2 Sprinkler Activation Calculation**

The calculations completed in this section indicate that sprinklers are expected to activate at approximately 215 seconds, resulting in an anticipated fire size of 2,168 kW (Figure 9). **Therefore, to be conservative, this analysis contemplates a fast-growth, 2,750 kW steady state fire for duration of 20 minutes. This fire size provides approximately 25% factor of safety, and considering the fire is steady state accounts for the potential spread of fire to additional fuel loads within the atrium.**

**Scenario 3 – Balcony-Spill (Beneath Floor 3 Walking Surface) Design Fire Selection**

When sprinklers are provided in the location where the design fire is located, NFPA 92 Section 5.2.1 indicates that the heat release rate and growth of the fire is likely to be decreased or maintained at the value that the fire has reached when sprinklers activate. MSBC Section 909.9.4 also recognizes this provision. An automatic fire sprinkler system is installed throughout the Framingham Fuller Middle School.

Sprinkler activation calculations have been completed to determine the actual heat release rates where sprinklers activate. The results of this analysis are based on the calculations developed by R.L. Alpert<sup>3</sup> for ceiling jet activation of a sprinkler as shown in Equation 3 and Figure 10.



By utilizing the Alpert's Ceiling Jet Temperature Correlations, it is possible to predict the temperature of the ceiling jet adjacent to the sprinkler and ultimately determine whether sprinkler activation is expected. The results of the calculation utilizing a small time step, and a fast growth rate fire, are shown in Figure 11. The equations utilized to predict the heat release rate from a fast growth rate t-squared fire as noted in Equation 4.

**Equation 4**

$$\dot{Q} = \alpha(t - t_v)^2$$

$$\dot{Q} = \left(\frac{1,055}{t_g^2}\right)(t - t_v)^2 [kW]$$

$$\dot{Q} = \left(\frac{1,000}{t_g^2}\right)(t - t_v)^2 [Btu/s]$$

Where:


- t<sub>g</sub> = fire growth time to 1,000 kW (1,055 BTU/s)
- t<sub>v</sub> = virtual ignition time
- α = empirically determined HRR parameter (0.0468 for Fast Growth)

<sup>3</sup> *Ceiling Jet Flows*, p.431, Society of Fire Protection Engineers (SFPE) Handbook, 5<sup>th</sup> Edition, Springer-Verlag New York 2016

Smoke Control Rational Analysis

This analysis utilizes the following assumptions:

1. Sprinklers are located a maximum of approximately 26'-3" above the walking surface
2. Sprinkler activation temperature of 165°F
3. Quick response sprinklers having a maximum Response Time Index of 50 (meter-seconds)<sup>1/2</sup>
4. Ambient temperature within the conditions spaces is 68 degrees
5. Sprinkler spacing is a maximum 10' x 13' or 130 ft<sup>2</sup> is provided
6. Sprinklers are within 12" of ceiling and are located in the ceiling jet region
7. Burning surface of fuel is approximately 3 feet above the walking surface




**Figure 11: Scenario 3 Sprinkler Activation Calculation**

The calculations completed in this section indicate that sprinklers are expected to activate at approximately 190 seconds, resulting in an anticipated fire size of 1,693 kW (Figure 11). **Therefore, to be conservative, this analysis contemplates a fast-growth, 2,100 kW steady state fire for duration of 20 minutes. This fire size provides approximately 20% factor of safety, and considering the fire is steady state accounts for the potential spread of fire to additional fuel loads within the atrium.**

**Scenario 4 – Balcony-Spill (Beneath Floor 2 Walking Surface) Design Fire Selection**

When sprinklers are provided in the location where the design fire is located, NFPA 92 Section 5.2.1 indicates that the heat release rate and growth of the fire is likely to be decreased or maintained at the value that the fire has reached when sprinklers activate. MSBC Section 909.9.4 also recognizes this provision. An automatic fire sprinkler system is installed throughout the Framingham Fuller Middle School.

Sprinkler activation calculations have been completed to determine the actual heat release rates where sprinklers activate. The results of this analysis are based on the calculations developed by R.L. Alpert<sup>4</sup> for ceiling jet activation of a sprinkler as shown in Equation 5 and Figure 12.



**Figure 12: Diagram of Alpert's Equations Variables**

By utilizing the Alpert's Ceiling Jet Temperature Correlations, it is possible to predict the temperature of the ceiling jet adjacent to the sprinkler and ultimately determine whether sprinkler activation is expected. The results of the calculation utilizing a small time step, and a fast growth rate fire, are shown in Figure 13. The equations utilized to predict the heat release rate from a fast growth rate t-squared fire as noted in Equation 6.

**Equation 6**

$$\dot{Q} = \alpha(t - t_v)^2$$

$$\dot{Q} = \left(\frac{1,055}{t_g^2}\right)(t - t_v)^2 [kW]$$

$$\dot{Q} = \left(\frac{1,000}{t_g^2}\right)(t - t_v)^2 [Btu/s]$$

Where:


- $t_g$  = fire growth time to 1,000 kW (1,055 BTU/s)
- $t_v$  = virtual ignition time
- $\alpha$  = empirically determined HRR parameter (0.0468 for Fast Growth)

<sup>4</sup> *Ceiling Jet Flows*, p.431, Society of Fire Protection Engineers (SFPE) Handbook, 5<sup>th</sup> Edition, Springer-Verlag New York 2016

Smoke Control Rational Analysis

This analysis utilizes the following assumptions:

1. Sprinklers are located a maximum of approximately 12'-0" above the walking surface
2. Sprinkler activation temperature of 165°F
3. Quick response sprinklers having a maximum Response Time Index of 50 (meter-seconds)<sup>1/2</sup>
4. Ambient temperature within the conditions spaces is 68 degrees
5. Sprinkler spacing is a maximum 15' x 15' or 225 ft<sup>2</sup> is provided
6. Sprinklers are within 12" of ceiling and are located in the ceiling jet region
7. Burning surface of fuel is approximately 3 feet above the walking surface



**Figure 13: Scenario 4 Sprinkler Activation Calculation**

The calculations completed in this section indicate that sprinklers are expected to activate at approximately 120 seconds, resulting in an anticipated fire size of 675 kW (Figure 13). **Therefore, to be conservative, this analysis contemplates a fast-growth, 1,100 kW steady state fire for duration of 20 minutes. This fire size provides approximately 50% factor of safety, and considering the fire is steady state accounts for the potential spread of fire to additional fuel loads within the atrium.**



**TENABILITY CRITERIA & THRESHOLDS**

There are many products of combustion that are produced by a fire. Not all of these products present an immediate hazard to humans. This report analyzes the tenability environment within the atrium for three major products of combustion during a fire scenario. These products include smoke toxicity, heat exposure (temperature), and visibility. The following sections address the end point criteria, defined as the point where occupants are no longer capable of exiting the building under their own power, for each product analyzed. The failure criteria established in this section is based on the end point thresholds with an additional safety factor to establish reasonable points of failure for the proposed smoke control system design.

**SMOKE TOXICITY**

Carbon Monoxide (CO), which is an asphyxiant, is one of the major products of combustion that presents a hazard to humans during a fire scenario. Carbon Monoxide inhalation creates a negative feedback loop in the following manner: the presence of increased amounts of carbon monoxide decrease the amount of oxygen consumed; as oxygen consumption decreases occupant respiratory rates increase; as occupant respiratory rates increase, the amount of carbon monoxide inhaled, increases. The intake of too much carbon monoxide leads to disorientation and possibly unconsciousness which negatively affect a person’s ability to self-evacuate a building.

Although other gases are produced, carbon monoxide is the most dangerous and one of the leading causes of death from a fire. Therefore, this analysis will focus on the concentration of carbon monoxide produced throughout the atrium for each scenario. It is assumed that other gases are not as hazardous as carbon monoxide, which is consistent with national practice and statistical data. Therefore, if carbon monoxide levels are demonstrated to be acceptable, other less lethal gases will be deemed acceptable.

The toxic effects of carbon monoxide vary based on the concentration, exposure time, and overall activity of the occupants. For example, a person exercising has a higher respiratory rate than a person sitting down. Therefore, a person at higher activity levels will consume more carbon monoxide than a person at rest and will lose consciousness faster. Respiratory levels for three (3) forms of activity can be seen in Table 1.

**Table 1: Respiration minute volume (RMV) (liters/min.) for a 70-kg man (SFPE Handbook 5<sup>th</sup> Edition, Chapter 63)**

Activity level of subject	V <sub>E</sub> (L/min)
Resting or sleeping	8.5
Light work—walking to escape	25
Heavy work—slow running, walking up stairs	50

Smoke Control Rational Analysis


The approximate time to loss of consciousness can be calculated based on the CO concentration produced by the design fire using the equation derived from Stewart-Peterson<sup>5</sup>. Stewart-Peterson's equation shown below calculates the amount of carboxyhemoglobin (COHb) produced in the blood stream, which results in a decrease in the blood's oxygen-carrying ability, based on CO concentrations. Documented endpoint criteria for the amount of COHb in one's blood stream before incapacitation has been calculated to be approximately 30-percent<sup>6</sup>. For the purposes of this analysis and to maintain conservatism, it is assumed every occupant is performing light work (i.e., walking around) and each will not be incapacitated for COHb levels less than 25-percent. In addition, for reference purposes, the figure below presents the time to loss of consciousness with respect to carbon monoxide concentration levels, as reproduced below (SFPE Handbook, 5<sup>th</sup> Edition, Figure 63.14).

**Equation 7 (SFPE Handbook, 5<sup>th</sup> Edition, Equation 63.18)**

$$\%COH_b = (3.317 \times 10^{-5})(ppmCO)^{1.036}(RMV)(t)$$

Where:

- %COHb = Percentage of Carboxyhemoglobin in blood stream
- PPM CO = CO concentration (PPM)
- RMV = Respiratory minute volume (L/min)
- t = exposure time (min)



**Figure 14: SFPE Handbook, 5<sup>th</sup> Edition, Figure 63.14**


<sup>5</sup> Assessment of Hazards to Occupants from Smoke, Toxic Gas, and Heat, p.2416, Society of Fire Protection Engineers (SFPE) Handbook, 5<sup>th</sup> Edition, Springer-Verlag New York 2016.

<sup>6</sup> Assessment of Hazards to Occupants from Smoke, Toxic Gas, and Heat, p.2332, Society of Fire Protection Engineers (SFPE) Handbook, 5<sup>th</sup> Edition, Springer-Verlag New York 2016.

**HEAT EXPOSURE**

Thermal effects of a fire typically present a hazard to occupants in close proximity to a fire or within the hot smoke layer. Due to the footprint of the atrium, it is assumed occupants will be able to maintain a sufficient distance away from any fire avoiding intense amounts of heat. However, hot smoke is buoyant and will rise to create a ceiling layer of hot air/smoke that could potentially affect occupants on higher floor levels where there are low ceiling heights.

Typical results from thermal exposure experienced by humans include hyperthermia, blistering, skin burns, and respiratory tract burns. The temperature thresholds for humans with respect to humidity can be seen in Figure 15.



**Figure 15: SFPE Handbook, 5<sup>th</sup> Edition, Figure 63.28**

As shown in the figure above, humid conditions result in lower temperature thresholds; therefore, to be conservative this analysis will assume the ambient air is humid. Assuming humid conditions, occupants are expected to be capable of exiting the building under temperatures less than 140°F.

**VISIBILITY**

Smoke is typically the biggest threat to building occupants during a fire. Smoke reduces visibility in an egress system which creates longer evacuation times and increased exposure times to the toxic gases and heat of a fire. Different from heat and gases, a reduction in visibility will not cause direct incapacitation of occupants. The concern with a reduction in visibility is that occupants may not be able to find an exit or take excessive amounts of time to reach an exit. This concern increases substantially when occupants are unfamiliar with the building layout. Therefore, a minimum visibility distance must be maintained along the means of egress within the atrium for a minimum of 1.5 times the calculated evacuation time, or 20 minutes after detection, whichever is greater.

Smoke Control Rational Analysis

Several studies have been conducted that evaluate minimum visibility criteria for both occupants familiar and unfamiliar with the building layout. The research conducted by Rasbash, documented in the Society of Fire Protection Engineering Handbook, 5<sup>th</sup> Edition, was used as a base point for this analysis. The table excerpted from the SFPE Handbook (Table 2) presents approximate visibility thresholds for people in areas with small enclosures and travel distances versus area with large enclosures and travel distances<sup>7</sup>.

**Table 2: Reported Effects of Smoke on Visibility and Behavior (SFPE Handbook, 5<sup>th</sup> Edition, Table 63.5)**

Smoke density and irritancy OD/m (extinction coefficient)		Approximate visibility (diffuse illumination)	Reported effects
None		Unaffected	Walking speed 1.2 m/s
0.5 (1.15)	Nonirritant	2 m	Walking speed 0.3 m/s
0.2 (0.5)	Irritant	Reduced	Walking speed 0.3 m/s
0.33 (0.76)	Mixed	3 m approx.	30 % people turn back rather than enter
<b>Suggested tenability limits for buildings with:</b>			
Small enclosures and travel distances:		OD/m 0.2 (visibility 5 m)	
Large enclosures and travel distances:		OD/m 0.08 (visibility 10 m)	

For the purpose of this analysis, the atrium walking surfaces are considered large enclosures and must maintain a visibility threshold of 10 meters. Narrow corridors that are outside the main atrium and within the atrium bounds must maintain a minimum visibility threshold of 5 meters along the centerline of the corridors. Note that such tenability criteria will be analyzed in areas that are not intimate with the fire.

<sup>7</sup> *Assessment of Hazards to Occupants from Smoke, Toxic Gas, and Heat*, p.2339, Society of Fire Protection Engineers (SFPE) Handbook, 5<sup>th</sup> Edition, Springer-Verlag New York 2016.

**CFD MODELING ANALYSIS**

The following sections outline the information utilized when determining the fire properties, as well as the pass/fail criteria for this assessment.

**GENERAL CFD MODELING PARAMETERS ASSUMPTIONS**

Along with well-established principles of engineering based on fire tests and historical data, this rational analysis will utilize the three-dimensional computational fluid dynamics computer model Fire Dynamics Simulator (FDS). When performing such analysis with FDS, an accurate combustion model, requires knowledge of the expected commodities that will be present, and must be specified. The design fire contemplates the burning of kiosks/displays, as well as a plastic blend foam cushioned furniture. To model this behavior, the following fuel and environment parameters were selected to represent an anticipated mixed fuel load. General assumptions and critical input parameters for the model were as follows:

1. Mixture Fraction
  - C = 4.56
  - H = 6.56
  - O = 2.34
  - N = 0.4
  - CO\_Yield – 0.018
  - Soot\_Yield – 0.05
  - Heat of Combustion – 22 kJ/g
2. Emissivity – 0.9
3. Visibility Factor – 8 for Light Emitting Signage

The values listed above are based on large-scale testing, along with well-established principles of engineering based on fire tests and historical data. A 22 kJ/g fuel load, as well as the mixture fraction, and CO and soot yields indicated above, is a conservative measurement for a fuel that is composed of 60-percent cellulosic blend and 40-percent plastic blend mixture. Such factors are an average for the use of the natural cellulose materials and for a plastic material in a 60-percent cellulosic blend and 40-percent plastic blend. The heat of combustion and soot yields are derived from Table 3-4.16 of the SFPE Handbook, 4<sup>th</sup> Edition.

**FDS MESH RESOLUTION**

All FDS calculations must be performed within a domain that is made up of rectilinear volumes called “meshes”. Each mesh is subdivided into thousands of uniform rectangular cells, the number of which depends on the desired resolution of the flow dynamics. When determining the appropriate mesh resolution, multiple factors must be considered. For simulations involving buoyant plumes, such as those included within this analysis, a measure of how well the flow field is resolved is given by the non-dimensional expression  $D^*/\delta x$ , where  $D^*$  is a characteristic fire diameter and  $\delta x$  is the nominal size of a mesh cell.  $D^*$  is calculated utilizing Equation 8 below. The reference (Verification and Validation of Selected Fire Models for Nuclear Plant Applications. NUREG 1824, United States Nuclear Regulatory Commission, 2007) states that FDS could accurately resolve fires when using a  $D^*/\delta x$  value between 4 and 16. The values used for each fire scenario are presented in Table 3.

Smoke Control Rational Analysis

**Equation 8**

$$D^* = \left( \frac{\dot{Q}}{\rho_{\infty} c_p T_{\infty} \sqrt{g}} \right)^{2/5}$$

Where:

- $\dot{Q}$  = Heat Release Rate (kW)
- $\rho_{\infty}$  = density = 1.204kg/m<sup>3</sup>
- $c_p$  = specific heat = 1.005 kJ/Kg-K
- $T_{\infty}$  = 293 K
- $g$  = gravitational acceleration = 9.8 m/s<sup>2</sup>

**Table 3: Mesh Resolution**

Scenario	Fire Size	Grid Spacing ( $\delta x$ )	D*/ $\delta x$ Desired Range	D*/ $\delta x$
1	3,500 kW	0.25 m	4 – 16 Based off reference within the FDS User Guide.	6.35
2	2,750 kW	0.25 m		5.77
3	2,100 kW	0.25 m		5.18
4	1,100 kW	0.25 m		4.00

**CFD RESULTS**

The criteria and design assumptions described in the sections above were inputted into FDS, a computational fluid dynamics model, and each design fire scenarios, as listed in Table 4, were simulated for a duration of 20 minutes after initial detection or 1.5 times the calculated egress time, whichever is greater. Refer to Appendix C for additional information on the Timed Egress Modeling performed as part of this overall analysis.

**Table 4: Fire Scenario Summary**

Scenario	Location	Fire Size	Design Fire Comments
1	Floor 1 – Axisymmetric – Center of Atrium	3,500 kW	Axisymmetric design fire. Fire located in a sprinklered area. Sprinkler activation is not contemplated. Fast-growth fire profile ( $\alpha = 0.0469$ kW/s <sup>2</sup> ).
2	Floor 1 – Balcony-Spill Plume (Beneath Floor 3 Walking Surface)	2,750 kW	Balcony-spill design fire. Fire located in a sprinklered area. Fire is controlled by sprinkler activation. Fast-growth fire profile ( $\alpha = 0.0469$ kW/s <sup>2</sup> ).
3	Floor 1 – Balcony-Spill Plume (Beneath Floor 3 Walking Surface)	2,100 kW	Balcony-spill design fire. Fire located in a sprinklered area. Fire is controlled by sprinkler activation. Fast-growth fire profile ( $\alpha = 0.0469$ kW/s <sup>2</sup> ).
4	Floor 1 – Balcony-Spill Plume (Beneath Floor 2 Walking Surface)	1,100 kW	Balcony-spill design fire. Fire located in a sprinklered area. Fire is controlled by sprinkler activation. Fast-growth fire profile ( $\alpha = 0.0469$ kW/s <sup>2</sup> ).

---

**Smoke Control Rational Analysis**

---

This section presents the results of the FDS computer model, which incorporates the following exhaust and makeup air values in the referenced Scenarios.

○ **Exhaust Configuration**


- 240,000 CFM of mechanically driven exhaust air
  - Exhaust air is provided via multiple points (refer to Figure 1 and Figure 2).

○ **Supply Configuration**

- Floor 1 (refer to Figure 3):
  - Automatic Openings
    - Two (2) louvers providing a minimum of 63 ft<sup>2</sup> of free area each
- Floor 2 (refer to Figure 4):
  - Automatic Doors / Openings
    - Three (3) exterior single-leaf doors and three (3) interior single-leaf doors providing a minimum of 66 ft<sup>2</sup> of free area
    - Two (2) louvers providing a minimum of 63 ft<sup>2</sup> of free area each
- Floor 3 (refer to Figure 5):
  - Automatic Openings
    - Two (2) louvers providing a minimum of 63 ft<sup>2</sup> of free area each

Although there are a number of aspects of the construction process and tightness of building construction that can affect the velocities, it is anticipated that the average velocities experienced in the field for the building are expected to be within +/- 10% of the predicted values included within the model. It is important to note that some small/localized areas in the areas adjacent to the doors may experience velocities higher than the averages noted herein. These higher velocities may be considered acceptable as long as the average velocities are consistent with the modeling analysis. Specifically, the computer modeling analysis contained herein takes into account effect of the increased velocities at the potential fire locations and their effect on the smoke production rates as required by NFPA 92. As a result, these velocities are allowed in accordance with this engineering analysis, the smoke control system design, and NFPA 92.

Utilizing the above listed smoke control configuration, and as illustrated in Figure 16, the maximum predicted air velocity within the atrium at a location where a potential fuel load may be present is approximately 748 feet per minute and does not impact the smoke control system's ability to maintain tenable conditions.



Time: 1500.0

**Figure 16: Predicted Makeup Air Velocity – Floor 1 (Plan View)**

For more detailed information, the Output File generated from FDS can be submitted upon request.



**Scenario 1 – 3,500 kW Axisymmetric Fire Results**

Scenario 1 consists of an axisymmetric 3,500 kW fire located in the center of the atrium on Floor 1. The fire size is based on conservative assumptions and fire test data. The fire is allowed to grow to full size before sprinklers activate and control the fire, allowing it to remain at steady state. Such a scenario presents a very conservative assumption as such fires will decay once the fuel is burned up.

As required by the MSBC, the mechanical exhaust smoke control system must be designed and capable of maintaining tenable conditions 6 feet above the highest walking surface for a minimum of 20 minutes after fire detection or 1.5 times the calculated egress time, whichever is greater. The means of detection in Scenario 1 consists of beam detection located across the ceiling of the atrium. Beam detectors are spaced a maximum of 30-feet apart, and the model assumes an obscuration of 20%, such a setpoint is typical for beam obscuration detection. The use of this detection configuration does not preclude other means of detection such as an air sampling system, or spot-type smoke detection located along underside of the ceiling/roof, as such configurations would provide equivalent levels of detection modeled herein. As a result of such a modeled configuration, detection is noted to occur within 42 seconds. Therefore, tenability criteria for Scenario 1 is analyzed for a minimum of 1,242 seconds of simulation time, as this is greater than 1.5 times the calculated egress time (refer to Appendix C for additional information). The following subsections outline the tenability results recorded for the duration of the scenario.

**SCENARIO 1 SMOKE TOXICITY RESULTS**


As discussed in the Design Assumptions section, carbon monoxide concentration levels were analyzed for the duration of the design fire. From the results, it is possible to determine the worst-case carbon monoxide (CO) concentration levels and where they occur within the occupied portions of the building. As the design fire progressed, concentration levels of CO six (6) feet above each occupied level were recorded with a maximum concentration level of less than 52.2 parts per million (PPM). See screen shots of the model below for illustrative results.

Using a maximum CO concentration of 52.2 PPM, the maximum exposure time before a human becomes incapacitated can be calculated. As discussed above, it is assumed a person may become incapacitated at COHb levels greater than 25-percent within the bloodstream. Using the calculations below, a person would need to be exposed to such conditions within the spaces for over 8.33 hours (500 minutes) during the design fire before they would become incapacitated from the effects of CO. This carbon monoxide concentration would provide occupants with more than enough time to evacuate the building and is considered acceptable conditions.

$$\%COH_b = (3.317 \times 10^{-5})(ppmCO)^{1.036}(RMV)(t)$$

$$(t) = \frac{\%COH_b}{(3.317 \times 10^{-5})(ppmCO)^{1.036}(RMV)}$$

$$(t) = \frac{25\%}{(3.317 \times 10^{-5})(52.2)^{1.036}(25)} = 500 \text{ min}$$



Time: 1500.0

Figure 17: Scenario 1 – Section View through Fire of CO Concentration




Figure 18: Scenario 1 – CO concentration 6 ft. above Floor 3 Walking Surface

**SCENARIO 1 HEAT EXPOSURE RESULTS**

The second product of combustion analyzed within the FDS model was temperature. Beginning with an ambient temperature of 68°F, temperature levels were recorded throughout the atrium for the duration of the design fire to determine where the worst-case conditions occur.

As shown in the screen shot captured below, similar to the carbon monoxide concentration, the highest temperature levels occur at the highest levels of the atrium within the smoke filling space. This can be expected because hot air is buoyant and will rise to the ceiling. As the design fire progressed, temperature levels continued to increase 6 feet above the walking surface with a small portion exceeding the maximum temperature level of 140°F. These elevated temperatures were intermittent and brief. Since the average temperature in the atrium is below the 140°F threshold for human tolerance, and the small portion exceeding 140°F was intermittent and brief, the temperature levels are considered acceptable.





Figure 19: Scenario 1 – Section View through Fire of Temperature



Time: 1500.0

Figure 20: Scenario 1 – Temperature 6 ft. above Floor 3 Walking Surface

**SCENARIO 1 VISIBILITY RESULTS**

Lastly, visibility conditions were analyzed and recorded within the FDS model throughout the atrium for the duration of the design fire to determine where the worst-case conditions occur. As shown in the screen shots captured below, visibility levels were maintained above the 10-meter tenability threshold in the large atrium spaces over the majority of the means of egress system walking surface. There were small intermittent pockets of reduced visibility, although they were of short duration (less than 60 seconds) and for that reason are acceptable. The visibility levels calculated in the model are sufficient to see all walls and exit signs along the means of egress and is therefore considered acceptable conditions.




Figure 21: Scenario 1 – Section View through Fire of Visibility




Figure 22: Scenario 1 – Visibility 6 ft. above Floor 3 Walking Surface

## Scenario 2 – 2,750 kW Balcony-Spill (Beneath Level 3 Walking Surface) Fire Results

Scenario 2 consists of a balcony-spill plume 2,750 kW fire located beneath the Level 3 walking surface. The fire size is based on conservative assumptions and fire test data. The fire is allowed to grow to full size before sprinklers activate and control the fire, allowing it to remain at steady state. Such a scenario presents a very conservative assumption as such fires will decay once the fuel is burned up.

As required by the MSBC, the mechanical exhaust smoke control system must be designed and capable of maintaining tenable conditions 6 feet above the highest walking surface for a minimum of 20 minutes after fire detection or 1.5 times the calculated egress time, whichever is greater. The means of detection in Scenario 2 consists of beam detection located across the ceiling of the atrium. Beam detectors are spaced a maximum of 30-feet apart, and the model assumes an obscuration of 20%, such a setpoint is typical for beam obscuration detection. The use of this detection configuration does not preclude other means of detection such as an air sampling system, or spot-type smoke detection located along underside of the ceiling/roof, as such configurations would provide equivalent levels of detection modeled herein. As a result of such a modeled configuration, detection is noted to occur within 51 seconds. Therefore, tenability criteria for Scenario 2 is analyzed for a minimum of 1,251 seconds of simulation time, as this is greater than 1.5 times the calculated egress time (refer to Appendix C for additional information). The following subsections outlines the tenability results recorded for the duration of the scenario.

### SCENARIO 2 SMOKE TOXICITY RESULTS

As discussed in the Design Assumptions section, carbon monoxide concentration levels were analyzed for the duration of the design fire. From the results, it is possible to determine the worst-case carbon monoxide (CO) concentration levels and where they occur within the occupied portions of the building. As the design fire progressed, concentration levels of CO six (6) feet above each occupied level were recorded with a maximum concentration level of less than 41.6 parts per million (PPM). See screen shots of the model below for illustrative results.


Using a maximum CO concentration of 41.6 PPM, the maximum exposure time before a human becomes incapacitated can be calculated. As discussed above, it is assumed a person may become incapacitated at COHb levels greater than 25-percent within the bloodstream. Using the calculations below, a person would need to be exposed to such conditions within the spaces for over 10.55 hours (633 minutes) during the design fire before they would become incapacitated from the effects of CO. This carbon monoxide concentration would provide occupants with more than enough time to evacuate the building and is considered acceptable conditions.

$$\%COH_b = (3.317 \times 10^{-5})(ppmCO)^{1.036}(RMV)(t)$$

$$(t) = \frac{\%COH_b}{(3.317 \times 10^{-5})(ppmCO)^{1.036}(RMV)}$$


$$(t) = \frac{25\%}{(3.317 \times 10^{-5})(41.6)^{1.036}(25)} = 633 \text{ min}$$





Time: 1500.0

Figure 23: Scenario 2 – Section View through Fire of CO Concentration




Time: 1500.0

Figure 24: Scenario 2 – CO concentration 6 ft. above Floor 3 Walking Surface

**SCENARIO 2 HEAT EXPOSURE RESULTS**

The second product of combustion analyzed within the FDS model was temperature. Beginning with an ambient temperature of 68°F, temperature levels were recorded throughout the atrium for the duration of the design fire to determine where the worst-case conditions occur.

As shown in the screen shot captured below, similar to the carbon monoxide concentration, the highest temperature levels occur at the highest levels of the atrium within the smoke filling space. This can be expected because hot air is buoyant and will rise to the ceiling. As the design fire progressed, temperature levels continued to increase 6 feet above the walking surface with a small portion exceeding the maximum temperature level of 140°F. This occurs along the walking surface directly above the fire, in addition these elevated temperatures were intermittent and brief. Since the average temperature in the atrium is below the 140°F threshold for human tolerance, and the small portion exceeding 140°F was intermittent and intimate with the fire plume, the temperature levels are considered acceptable.



Time: 1500.0

Figure 25: Scenario 2 – Section View through Fire of Temperature




Figure 26: Scenario 2 – Temperature 6 ft. above Floor 3 Walking Surface

**SCENARIO 2 VISIBILITY RESULTS**

Lastly, visibility conditions were analyzed and recorded within the FDS model throughout the atrium for the duration of the design fire to determine where the worst-case conditions occur. As shown in the screen shots captured below, visibility levels were maintained above the 10-meter tenability threshold in the large atrium spaces over the majority of the means of egress system walking surface. There were small pockets of reduced visibility along the walking surface directly above the fire. This area is intimate with the fire plume and for that reason is acceptable. The visibility levels calculated in the model are sufficient to see all walls and exit signs along the means of egress and is therefore considered acceptable conditions.




Figure 27: Scenario 2 – Section View through Fire of Visibility




Figure 28: Scenario 2 – Visibility 6 ft. above Floor 3 Walking Surface

**Scenario 3 – 2,100 kW Balcony-Spill (Beneath Level 3 Walking Surface) Fire Results**

Scenario 3 consists of a balcony-spill plume 2,100 kW fire located beneath the Level 3 walking surface. The fire size is based on conservative assumptions and fire test data. The fire is allowed to grow to full size before sprinklers activate and control the fire, allowing it to remain at steady state. Such a scenario presents a very conservative assumption as such fires will decay once the fuel is burned up.

As required by the MSBC, the mechanical exhaust smoke control system must be designed and capable of maintaining tenable conditions 6 feet above the highest walking surface for a minimum of 20 minutes after fire detection or 1.5 times the calculated egress time, whichever is greater. The means of detection in Scenario 3 consists of beam detection located across the ceiling of the atrium. Beam detectors are spaced a maximum of 30-feet apart, and the model assumes an obscuration of 20%, such a setpoint is typical for beam obscuration detection. The use of this detection configuration does not preclude other means of detection such as an air sampling system, or spot-type smoke detection located along underside of the ceiling/roof, as such configurations would provide equivalent levels of detection modeled herein. As a result of such a modeled configuration, detection is noted to occur within 76 seconds. Therefore, tenability criteria for Scenario 3 is analyzed for a minimum of 1,276 seconds of simulation time, as this is greater than 1.5 times the calculated egress time (refer to Appendix C for additional information). The following subsections outlines the tenability results recorded for the duration of the scenario.

**SCENARIO 3 SMOKE TOXICITY RESULTS**


As discussed in the Design Assumptions section, carbon monoxide concentration levels were analyzed for the duration of the design fire. From the results, it is possible to determine the worst-case carbon monoxide (CO) concentration levels and where they occur within the occupied portions of the building. As the design fire progressed, concentration levels of CO six (6) feet above each occupied level were recorded with a maximum concentration level of less than 55.7 parts per million (PPM). See screen shots of the model below for illustrative results.

Using a maximum CO concentration of 55.7 PPM, the maximum exposure time before a human becomes incapacitated can be calculated. As discussed above, it is assumed a person may become incapacitated at COHb levels greater than 25-percent within the bloodstream. Using the calculations below, a person would need to be exposed to such conditions within the spaces for over 7.8 hours (468 minutes) during the design fire before they would become incapacitated from the effects of CO. This carbon monoxide concentration would provide occupants with more than enough time to evacuate the building and is considered acceptable conditions.

$$\%COH_b = (3.317 \times 10^{-5})(ppmCO)^{1.036}(RMV)(t)$$

$$(t) = \frac{\%COH_b}{(3.317 \times 10^{-5})(ppmCO)^{1.036}(RMV)}$$

$$(t) = \frac{25\%}{(3.317 \times 10^{-5})(55.7)^{1.036}(25)} = 468 \text{ min}$$



Time: 1500.0

Figure 29: Scenario 3 – Section View through Fire of CO Concentration






Figure 30: Scenario 3 – CO concentration 6 ft. above Floor 2 Walking Surface

**SCENARIO 3 HEAT EXPOSURE RESULTS**

The second product of combustion analyzed within the FDS model was temperature. Beginning with an ambient temperature of 68°F, temperature levels were recorded throughout the atrium for the duration of the design fire to determine where the worst-case conditions occur.

As shown in the screen shot captured below, similar to the carbon monoxide concentration, the highest temperature levels occur along the Floor 2 walking surface underneath the Cohort Space. This can be expected because hot air is buoyant and will rise to the ceiling and descend towards the walking surfaces nearby the fire plume. As the design fire progressed, temperature levels continued to increase 6 feet above the walking surface with portions exceeding the maximum temperature level of 140°F. This occurs along the walking surface within the conical fire plume, in addition these elevated temperatures were intermittent. Occupants are capable of utilizing another exit without egressing through the fire plume. Since occupants are provided with other exits, and the average temperature in the atrium is below the 140°F threshold for human tolerance, and the portion exceeding 140°F was intermittent and intimate with the fire plume, the temperature levels are considered acceptable.




Figure 31: Scenario 3 – Section View through Fire of Temperature




Figure 32: Scenario 3 – Temperature 6 ft. above Floor 2 Walking Surface

**SCENARIO 3 VISIBILITY RESULTS**

Lastly, visibility conditions were analyzed and recorded within the FDS model throughout the atrium for the duration of the design fire to determine where the worst-case conditions occur. As shown in the screen shots captured below, visibility levels were maintained above the 10-meter tenability threshold over the majority of the means of egress system walking surface. There were small intermittent pockets of reduced visibility, although they were of short duration (less than 60 seconds) and intimate with the conical fire plume and for that reason are acceptable. The visibility levels calculated in the model are sufficient to see all walls and exit signs along the means of egress and is therefore considered acceptable conditions.




Figure 33: Scenario 3 – Section View through Fire of Visibility




Figure 34: Scenario 3 – Visibility 6 ft. above Floor 2 Walking Surface

#### Scenario 4 – 1,100 kW Balcony-Spill (Beneath Level 2 Walking Surface) Fire Results

Scenario 4 consists of a balcony-spill plume 1,100 kW fire located beneath the Level 2 walking surface adjacent to the mechanical makeup air, automatic opening doors, and louvers (this location is subject to the highest makeup air velocities). The fire size is based on conservative assumptions and fire test data. The fire is allowed to grow to full size before sprinklers activate and control the fire, allowing it to remain at steady state. Such a scenario presents a very conservative assumption as such fires will decay once the fuel is burned up.

As required by the MSBC, the mechanical exhaust smoke control system must be designed and capable of maintaining tenable conditions 6 feet above the highest walking surface for a minimum of 20 minutes after fire detection or 1.5 times the calculated egress time, whichever is greater. The means of detection in Scenario 4 consists of beam detection located across the ceiling of the atrium. Beam detectors are spaced a maximum of 30-feet apart, and the model assumes an obscuration of 20%, such a setpoint is typical for beam obscuration detection. The use of this detection configuration does not preclude other means of detection such as an air sampling system, or spot-type smoke detection located along underside of the ceiling/roof, as such configurations would provide equivalent levels of detection modeled herein. As a result of such a modeled configuration, detection is noted to occur within 103 seconds. Therefore, tenability criteria for Scenario 4 is analyzed for a minimum of 1,303 seconds of simulation time, as this is greater than 1.5 times the calculated egress time (refer to Appendix C for additional information). The following subsections outlines the tenability results recorded for the duration of the scenario.

#### SCENARIO 4 SMOKE TOXICITY RESULTS


As discussed in the Design Assumptions section, carbon monoxide concentration levels were analyzed for the duration of the design fire. From the results, it is possible to determine the worst-case carbon monoxide (CO) concentration levels and where they occur within the occupied portions of the building. As the design fire progressed, concentration levels of CO six (6) feet above each occupied level were recorded with a maximum concentration level of less than 13.7 parts per million (PPM). See screen shots of the model below for illustrative results.

Using a maximum CO concentration of 13.7 PPM, the maximum exposure time before a human becomes incapacitated can be calculated. As discussed above, it is assumed a person may become incapacitated at COHb levels greater than 25-percent within the bloodstream. Using the calculations below, a person would need to be exposed to such conditions within the spaces for over 33.3 hours (2,002 minutes) during the design fire before they would become incapacitated from the effects of CO. This carbon monoxide concentration would provide occupants with more than enough time to evacuate the building and is considered acceptable conditions.

$$\%COH_b = (3.317 \times 10^{-5})(ppmCO)^{1.036}(RMV)(t)$$

$$(t) = \frac{\%COH_b}{(3.317 \times 10^{-5})(ppmCO)^{1.036}(RMV)}$$

$$(t) = \frac{25\%}{(3.317 \times 10^{-5})(13.7)^{1.036}(25)} = 2,002 \text{ min}$$



Time: 1500.0

Figure 35: Scenario 4 – Section View through Fire of CO Concentration




Figure 36: Scenario 4 – CO concentration 6 ft. above Floor 3 Walking Surface



**SCENARIO 4 HEAT EXPOSURE RESULTS**

The second product of combustion analyzed within the FDS model was temperature. Beginning with an ambient temperature of 68°F, temperature levels were recorded throughout the atrium for the duration of the design fire to determine where the worst-case conditions occur.

As shown in the screen shot captured below, similar to the carbon monoxide concentration, the highest temperature levels outside of the fire plume occur at the highest levels of the atrium within the smoke filling space. This can be expected because hot air is buoyant and will rise to the ceiling. As the design fire progressed, temperature levels continued to increase with a maximum temperature of less than 140°F occurring 6 feet above highest walking surface. Since this temperature does not exceed the 140°F threshold for human tolerance and is considered acceptable conditions.




Figure 37: Scenario 4 – Section View through Fire of Temperature




Figure 38: Scenario 4 – Temperature 6 ft. above Floor 3 Walking Surface

**SCENARIO 4 VISIBILITY RESULTS**

Lastly, visibility conditions were analyzed and recorded within the FDS model throughout the atrium for the duration of the design fire to determine where the worst-case conditions occur. As shown in the screen shots captured below, visibility levels were maintained above the 10-meter tenability threshold outside of the fire plume in the large atrium spaces over the entirety of the means of egress system walking surface. The visibility levels calculated in the model are sufficient to see all walls and exit signs along the means of egress and is therefore considered acceptable conditions.




Figure 39: Scenario 4 – Section View through Fire of Visibility




Figure 40: Scenario 4 – Visibility 6 ft. above Floor 3 Walking Surface

**Summary of Results**

This report analyzes the tenability environment for a proposed passive smoke control system for the atrium in the Framingham Fuller Middle School in Framingham, MA. The analysis evaluates a means of egress system, under specific fire scenarios, for three (3) major products of combustion during a fire scenario; heat exposure (temperature), smoke toxicity, and visibility. The FDS computer model developed by NIST was used to evaluate each of the tenability criteria. The CFD Model analysis validated the following smoke control systems design criteria.

- **Exhaust Configuration**
  - 240,000 CFM of mechanically driven exhaust air
    - Exhaust air is provided via multiple points (refer to Figure 1 and Figure 2).
- **Supply Configuration**
  - Floor 1 (refer to Figure 3):
    - Automatic Openings
      - Two (2) louvers providing a minimum of 63 ft<sup>2</sup> of free area each
  - Floor 2 (refer to Figure 4):
    - Automatic Doors / Openings
      - Three (3) exterior single-leaf doors and three (3) interior single-leaf doors providing a minimum of 66 ft<sup>2</sup> of free area
      - Two (2) louvers providing a minimum of 63 ft<sup>2</sup> of free area each
  - Floor 3 (refer to Figure 5):
    - Automatic Openings
      - Two (2) louvers providing a minimum of 63 ft<sup>2</sup> of free area each

Using the maximum carbon monoxide concentration found in all fire scenarios the maximum exposure time before a human becomes incapacitated can be calculated. The calculated exposure time as a result of the maximum CO concentrations was determined to be 7.8 hours (468 min), before a person would become incapacitated from the effects of CO. This concentration would provide occupants with more than enough time to evacuate the building and are considered acceptable conditions.

Heat exposure was analyzed with a maximum recorded average temperature along the means of egress system within the Atrium Zone not exceeded 140°F and is not considered hazardous to humans. Therefore, the design objective is achieved because every occupant is expected to be capable of evacuating the without being overcome by the harmful effects of heat exposure.

Visibility conditions were analyzed and found to be capable of maintaining the minimum visibility thresholds for the time duration necessary to safely evacuate occupants. As indicated in the results, the visibility threshold was maintained for a minimum of 20 minutes after detection of the fire. Therefore, the design objective is achieved because every occupant is expected to be capable of evacuating the building without experiencing low visibility conditions.

---

 Smoke Control Rational Analysis
 

---

Although this analysis determined the atrium will maintain a tenable environment for the referenced design fires, several critical factors were overestimated and some not considered in this analysis, which contributed to providing a conservative analysis. These factors include:

- Sustained peak heat release rate for the duration of the model (Scenarios 1, 2, 3, and 4).
- Occupants are provided with multiple exits from the building,
- Overestimation of heat release rates based on the available fuel load,
- Delayed fire department and staff response/action (no manual suppression).

**ADDITIONAL INTERNATIONAL BUILDING CODE SECTION 909 RATIONALE**
**HVAC Systems**

Normal building HVAC systems, not associated with the smoke control system zone are designed to shut down when an automatic smoke detector, or sprinkler waterflow switch within the Atrium Zone is activated.

**Separation Distance**

Separation distances are required to be maintained between multiple fuel packages to reduce the possibility of adjacent fuel packages igniting during a fire, which may result in a fire larger than contemplated in the design. Separation distance requirements can be calculated using the equation below from MSBC Section 909.9.2.

$$R = \left( \frac{Q}{12\pi q''} \right)^{1/2}$$

Where:

- R = Separation distance from target to center of fuel package (m)
- Q = Heat release rate from fire (kW)
- q'' = Incident radiant heat flux required for non-piloted ignition (kW/m<sup>2</sup>)

For the purposes of this analysis, an incident radiant heat flux of 10kW/m<sup>2</sup> was used, which is the heat flux required to ignite wood and the most commonly used combustible material within the atrium; and a fire size of 3,500 kW was used. The separation distances can then be calculated as follows:

$$R = \left( \frac{3,500}{12 \times \pi \times 10} \right)^{1/2}$$

*3.05 meters (approximately 10'0")*

As shown in the calculation above the separation between fuel packages within the atrium consisting of heat release rate of 3,500 kW shall be no less than 10'0".

**Stack Effect**

Stack effect is inherently calculated within the CFD models. The results indicate that the smoke will overcome the effects of stack effect and reverse stack effect during a fire event.

**Buoyancy**

Buoyancy is inherently calculated within the CFD models. The results indicate that the smoke will overcome the height of the space.

**Stratification Analysis**


Stratification is inherently calculated within the CFD models. The results indicate that the smoke will overcome the effects of stratification during a fire event.

**Climate**

Since the makeup air system relies on selected exterior openings to provide air into the Atrium Zone, it is imperative that the owner maintain the required exterior areas free from any impediments that would cause the doors/louvers not to open in an emergency. Specifically, the owner must maintain the surfaces outside all doors free from blockage anytime that the building is occupied so that the doors/louvers are capable of opening in smoke mode.

**Smoke Control Equipment Temperature**

MSBC Section 909.10 requires smoke control equipment including, but not limited to, fans, ducts, automatic dampers, and balancing dampers be suitable for its intended use under probable exposure temperatures. All exhaust fans must be UL 705 listed. Upper Hot Gas Layer Temperatures were analyzed within the FDS model. Beginning with an ambient temperature of 68°F, temperature levels were recorded throughout the Building for the duration of the design fire to determine where the worst-case conditions occur. Temperatures within the analyzed model(s) reached steady-state conditions, with maximum temperatures along the ceiling level calculated to be approximately 452°F. Refer to Figure 42 for a section view throughout the building.



**Figure 41: Scenario 3 – Section View through Fire of Temperature**

**EQUIPMENT AND CONTROLS**

Details of specific equipment, control sequences of actual equipment, fire alarm annunciation points, and HVAC operation as it relates to the smoke control system are found in the following sections of this report. All equipment shall conform to the requirements of the MSBC, NFPA 92, and UL 864.

The mechanical exhaust smoke control system will be activated automatically by appropriately zoned sprinkler systems within the Atrium Zone, smoke detection (i.e. via spot-type, beam obscuration or air-sampling system) located along the underside of the atrium skylights, or manually via the firefighter's smoke control panel. Upon activation of the fire alarm system within the appropriate zone, the smoke exhaust system shall be activated in accordance with the integrated operation matrix to be prepared by the Engineer of Record. The zone that will activate the smoke control system will be coordinated with the proposed Atrium Zone boundary as depicted in Appendix B.

**SECONDARY POWER**

Secondary power must be provided and connected to all equipment associated with the smoke control system, which includes smoke control exhaust, automatic opening doors/louvers that are not fail-open used for makeup air, dampers, and any monitoring systems.

1. The emergency generator must be sized accommodate the demand of the smoke control system and equipment, automatic doors and dampers associated with makeup air, control panels, and controls for the smoke control sequence.
2. Transfer to full standby power must be automatic and occur within 60 seconds of failure of the primary power.

**EQUIPMENT**

The following requirements relate to the smoke control equipment installed for exhaust or makeup air systems within the atrium.

1. Smoke-Control System Fans
    - a. Smoke control fans are to be UL 864 listed.
    - b. 1.5 times required number of belts (minimum 2) must be provided for belt-driven fans.
    - c. Fan motors must have a minimum service factor of 1.15.
    - d. Operation of fans in smoke mode will be confirmed by positive indication by either adjustable differential pressure sensors, adjustable current sensors, or airflow switches.
      - i. Positive confirmation for smoke control fans is defined as the smoke control fan operating in its true ON condition. Where such a configuration is not achieved when required, a FAULT status must be displayed at the smoke control panel.
    - e. Fans must be capable of operating under temperatures as predicted by the Smoke Control Rational Analysis.
  2. Smoke-Control System Ducts
    - a. All ductwork must be tested in accordance with MSBC Section 909.10.2.
      - i. Duct leakage must be less than 5% of the design flow when tested to 1.5 times maximum design pressure.
      - ii. Flexible connections for the purpose of vibration isolation shall be allowed in the exhaust system ductwork configuration, and are not required to be included within the duct leakage testing
    - b. Air exhaust outlets must be located to minimize the potential for introducing smoke or flame into the building.
  3. Smoke-Control System Smoke Dampers
    - a. Each damper associated with the smoke control exhaust system must be provided with monitoring modules to provide positive indication of fully-open and fully-closed statuses.
-



---

**Smoke Control Rational Analysis**

---

- i. Positive confirmation for smoke control damper is defined as the smoke control damper is positioned in its true OPEN or true CLOSED position. Where such a configuration is not achieved when required, a FAULT status must be displayed at the smoke control panel.
    - b. HVAC systems in the alarm zone not used for smoke control must shut down in accordance with the sequence of operations.
    - c. Dampers must be capable of operating under temperatures as predicted by the Smoke Control Rational Analysis.
    - d. Dampers on smoke control exhaust fans must be arranged to fail in the OPEN position.
    - e. Dampers on non-smoke control related equipment must be arranged to fail in the CLOSED position.
  4. Automatic Doors/Louvers
    - a. The doors/louvers utilized for natural makeup air flow paths must be power operated doors/louvers to allow for makeup air infiltration from the adjacent spaces.
    - b. Each door/louver must be provided with monitoring modules for full open and closed statuses and control relays to ensure the door/louver operates appropriately.
      - i. Positive confirmation for doors and louvers that are used as part of the smoke control system is defined as the doors/louvers configured in the true OPEN or true CLOSED position. Where such a configuration is not achieved when required, a FAULT status must be displayed at the smoke control panel
      - ii. Each door leaf and louver must be provided with monitoring modules for fully open and fully closed statuses and control relays to ensure the door/louver operates appropriately for smoke mode.
    - c. If accessible switches are provided to shut power off to the doors/louvers, these switches must be monitored for position (report a fault on smoke control panel when disabled) or capable of being overridden by the smoke control system such that the doors/louvers are still capable of opening in smoke mode with the switch in the “disable” position.
    - d. Doors must be capable of opening and completing travel to the required smoke mode position within 75 seconds after receipt of an alarm signal.
    - e. It is recommended that a portion of automatic-opening interior makeup air doors/louvers open prior to operation of the smoke exhaust fans to prevent damage to the door motors.
  5. Power Systems
    - a. The smoke-control systems must be supplied with two (2) sources of power. Primary power may be from the normal building power systems. Secondary power must be from an approved standby source complying with the National Electric Code. It must be confirmed that the generator is capable of supporting the power loads of the smoke control system. Refer to the Secondary Power section of the Smoke Control Rational Analysis for additional information.
    - b. Elements of the smoke control system relying on volatile memories must be supplied with uninterruptible power sources of sufficient duration to span 15-minute primary power interruption.
      - i. It is recommended that makeup air door/louvers control systems associated with the smoke control system are provided with an Uninterruptible Power Supply (UPS) to ensure the doors/louvers will open accordingly and position tracking is not lost during a loss of power event, which can prevent the doors/louvers from re-opening.
    - c. Elements of the smoke-control system susceptible to power surges must be suitably protected by power conditioners, suppressors or other approved means.
    - d. All power wiring serving the smoke control equipment, regardless of voltage, must be fully enclosed within continuous raceways.

---

 Smoke Control Rational Analysis
 

---

- e. **Power to all smoke exhaust fans, dampers and automatic opening makeup air doors/louvers (where provided) must be monitored downstream of any disconnects and VFD's (where provided) at the smoke control panel. This includes monitoring all points of disconnect.**
    - i. Monitor all points of disconnect including VFD keypads (where provided), switchgear, local and remote disconnects, bypass switches, etc. Monitoring is not required if those points of disconnect can be automatically overridden by the smoke control system. This also includes monitoring of all points of disconnect for automatic door/louver openers and equipment serving makeup air doors/louvers.
    - ii. If the smoke control equipment is disabled due to a service disconnect, breaker, bypass, VFD keypad (where provided), or override switch on makeup air doors/louvers, it must display a fault signal on the smoke control panel.
6. Control Systems
- a. All control equipment associated with the smoke control system equipment must be UL 864 listed. This includes the Firefighter's smoke control panel, fire alarm control panel, fans, damper controls, and door controls.
  - b. Supervision for airflow sensing will be by differential pressure sensors, amperage monitoring relays, or airflow sensors. Required supervision will be indicated at the firefighter's control panel.
  - c. All wiring, regardless of voltage, will be fully enclosed within continuous raceways (MC Cable is not permitted)
  - d. Normal activation of the smoke-control system will be by automatic control.
  - e. VFD's (where provided) must be locked out via a passcode or have key pad removed after commissioning of system. It should not be possible to adjust VFDs (where provided) while the system is in alarm mode.
7. Detection Systems
- a. The new equipment installed throughout the atrium (i.e. the exhaust fans and makeup doors/louvers) must be connected to, and monitored by the Fire Alarm Control Panel and Firefighter's Smoke Control Panel.
  - b. The smoke control system must undergo a pre-programmed self-test automatically conducted by the fire alarm / smoke control system at a pre-determined time each week. The self-test must provide a printed report indicating the pass/fail of each equipment and overall system pass/fail status.
  - c. An appropriately zoned sprinkler system that is coordinated with the location of the smoke control zones is required to be provided. The sprinkler waterflow switch serving each smoke control zone will be programmed to activate the smoke control system serving that zone, depicted in Appendix B.
  - d. Appropriate smoke detection must be installed within the atrium at the ceiling level to activate the zoned smoke control system. This additional smoke detection may be beam detection, spot-type smoke detection, or air sampling system.

#### ***FIREFIGHTER'S SMOKE CONTROL PANEL***

A new Firefighter's Smoke Control Panel must be provided to incorporate the necessary controls and indication for the new smoke control system within the atrium. The firefighter's Smoke Control Panel must be located adjacent to the Fire Alarm Control Panel (MSBC Section 909.16).

The firefighter's control panel must be provided with:

- 1. An Uninterruptible Power Supply so that it does not lose power in the event of building power failure.
- 2. Manual control or override of automatic control for smoke-control systems.
  - a. The panel will graphically depict the building arrangement and smoke-control system zones served by the systems.

**Smoke Control Rational Analysis**

---

- b. Graphically depict the location of fans, makeup air locations, major ducts and dampers within the building that are portions of the smoke-control systems.
  - i. The Firefighter's Smoke Control Panel must provide a clear indication of the direction of airflow and the relationship of its components.
- 3. Control capabilities associated with the smoke control system will be as follows:
  - b. "ON – AUTO – OFF" control over each individual smoke control component, which activates/deactivates all necessary fans and opens/closes related dampers and makeup air doors/louvers.
    - i. If approved by the Authority Having Jurisdiction a single switch that controls all of the components required for the smoke control system to operate may be provided.
  - c. Firefighter's control panel will take highest priority over all other building sources.
  - d. The controls and indicators will be combined to control and indicate all elements of the smoke zone as one unit.
- 4. On the graphic zone panel, status lamps will be provided for the indication of operation of all smoke-control equipment within each smoke zone as a single unit as follows:
  - a. Fans, dampers, makeup air openings, and other operating equipment in their NORMAL status - White.
  - b. Fans, dampers, makeup air openings, and other operating equipment in their ON or OPEN mode - Green.
  - c. Fans, dampers, makeup air openings, and other operating equipment in FAULT mode - Yellow.
  - d. Fans, dampers, makeup air openings, and other operating equipment in OFF (or CLOSED) mode - Red.

**SEQUENCE OF OPERATION**

The smoke control zone will be activated automatically and independently by sprinkler water flow switches (sprinklers zoned within the Atrium Zone Boundary), smoke detection (i.e. via spot-type, beam obscuration or air-sampling system) located along the underside of the atrium roof, or manually via the firefighter's smoke control panel (location to be determined). Refer to Appendix B which depicts the Atrium Zone Boundary.

Upon activation of the fire alarm system, the smoke control system shall be activated in accordance with the operation matrix prepared by the Engineer of Record for the mechanical system at the time of original building construction. These operations include shutdown of normal HVAC within the Building, activation of the smoke exhaust fans, and opening the makeup and doors and louvers.

Upon receipt of an alarm signal, all smoke control equipment must report true positive status (doors, louvers, and dampers report to open status, exhaust fan 100-percent run) within 135 seconds. Makeup air doors/louvers shall open prior to prevent damage to the door motors. Exhaust fan dampers shall open prior to the fan running at 100-percent operation to prevent damage to the damper actuator and capitation of the exhaust fan. System shall be fully operational within 135 seconds of the detection of a fire within the atrium smoke zone.

**Table 5: Sequence of Operation**

Sequence	Event	Duration
<b>1</b>	Time for Dampers and Doors to Reach Full Open Position	75 Seconds maximum
<b>2</b>	Time for Exhaust Fan to Ramp Up and Achieve 100 percent Run	60 seconds maximum
<b>System Running at Full Capacity (after detection):</b>		<b>135 Seconds maximum</b>

\*Note: Fire detection time is dependent upon fire scenario. Detection time has been determined within the FDS scenarios, and subsequently the indicated sequence of operation occurs. Detection through sprinkler activation requires an additional 90 seconds to transmit the waterflow signal to the fire alarm control panel.

**SPECIAL INSPECTION AND TEST REQUIREMENTS**

In addition to the ordinary inspection and test requirements, smoke control systems are required to undergo special inspections and tests sufficient to verify the proper commissioning of the smoke control design in its final installed condition. The Special Inspector is responsible for verifying that the smoke control system is installed in accordance with the requirements of MSBC Section 909 and that the system achieves the performance defined in the Smoke Control Rational Analysis Report.

The Special Inspector must be employed by the Owner, Owner's Agent, Architect, or Engineer of Record. The Special Inspector must not be employed by the contractor or any other person responsible for the work being installed/performed. The Special Inspector must be a qualified person that can demonstrate competence to the satisfaction of the Building and Fire Department for the inspection and testing of smoke control systems, having expertise in fire protection engineering, mechanical engineering and certification as air balancers (MSBC Section 1705.18.2). Where necessary, testing agencies required by the Special Inspector must be engaged by the Owner or Owner's Agent. Testing agencies that measure HVAC performances (Testing and Balancing agencies) must be certified by the Associated Air Balance Council (AABC) or the National Environmental Balancing Bureau (NEBB). The Testing Agency must also produce documentation that all equipment used to test and balance the smoke control system has been calibrated in accordance with AABC or NEBB.

The smoke control system is required to be inspected and tested in accordance with MSBC Section 909.18.8. Special inspection and testing requirements shall include, at a minimum, the following:

1. The special inspections and tests shall be sufficient to verify the proper commissioning of the smoke control design and to determine the final installed condition is in compliance with the design documents and requirements of the NFPA 92 and the MSBC. Where determined necessary by the local jurisdiction, tests must be conducted in the presence of an authorized representative from the Department of Building Inspections and the Fire Department. Such parties are to be notified of testing to determine their availability and reschedule if necessary. A report of the results must be submitted to both Departments.
2. All smoke control ductwork must be tested for leakage. Duct leakage must be less than 5-percent of the design flow when tested to 1.5 times maximum design pressure. Note, all duct leakage testing must be witnessed by the Smoke Control Special Inspector prior to concealment of ductwork within walls/ceilings.
3. In accordance with IBC Section 909.12.1, NFPA 92 and UL 864 an automatic pre-programmed weekly self-test of the smoke control system must be provided within the system design. The functionality of this pre-programmed test will be required to be reviewed and documented by the smoke control special inspector. In addition, weekly records should be kept on site and a semi-annual test under standby power will be required.

Additionally, after occupancy of the building, all operating parts of the smoke-control systems must be retested every six (6) months in accordance with the retest requirements established by the Engineer of Record, Smoke Control Special Inspector retained at the time of initial commissioning, and with concurrence from the Department of Building and Safety and the Fire Department. The test should be conducted by an approved inspection agency or by the owner or the owner's representative when so approved by both Departments. A report of the test results should be submitted to both Departments.

**OVERVIEW**

Three types of testing exist for the smoke control system in the atrium. These three types of the tests are:

1. Component System Testing
  - a. Component System Testing shall be complete prior to any acceptance testing is to be conducted. The contractor shall certify that all component systems have been checked and are fully operational and meet all design specifications and applicable codes before acceptance testing begins.
  - b. This shall include inspection and review by the Smoke Control Special Inspector of all ductwork serving the smoke control system prior to concealment of ductwork within walls/ceilings. Ductwork must be tested in accordance with MSBC Section 909.10.2. Duct leakage must be less than 5-percent of the design flow when tested to 1.5 times maximum design pressure. Flexible connections for the purpose of vibration isolation shall be allowed in the exhaust system ductwork configuration and are not required to be included within the duct leakage testing
2. Acceptance Testing
  - a. Acceptance Testing takes place before a certificate of occupancy is obtained. Acceptance Testing will test the integrated smoke control system to confirm compliance with the design specifications and proper operation. Pass/Fail criteria for acceptance testing are outlined later in this section.
  - b. This shall include pressure difference testing, flow measurements and detection and control verification for all equipment serving the smoke control system, as well as reviewing the reliability of the monitoring system and controls at the Firefighter's Smoke Control Panel.
3. Periodic Testing and Maintenance
  - a. Weekly pre-programmed self-test automatically conducted by the fire alarm / smoke control system at a pre-determined time each week, with printed report indicating the pass/fail of each equipment and overall system pass/fail status.
  - b. To be conducted by the owner semi-annually to ensure proper operation after certificate of occupancy is obtained.

---

**Smoke Control Rational Analysis**

---

**COMPONENT AND ACCEPTANCE TESTING CONDITIONS**

The following tasks shall be completed prior to starting any smoke control system testing:

1. All ductwork must be testing in accordance with MSBC Section 909.10.2. Duct leakage must be less than 5-percent of the design flow when tested to 1.5 times maximum design pressure. Flexible connections for the purpose of vibration isolation shall be allowed in the exhaust system ductwork configuration and are not required to be included within the duct leakage testing. Note, all duct leakage testing must be witnessed by the Smoke Control Special Inspector prior to concealment of ductwork within walls/ceilings
2. All building equipment shall be placed in normal operations mode.
3. The smoke control system will be demonstrated for proper operation sequences without smoke.
4. Smoke control systems shall be activated manually from the fireman's control panel to verify proper operation for each smoke control zone.
5. Smoke control systems will be activated automatically by activation of sprinkler water flow switches, heat detectors, area smoke detectors or duct smoke detectors.
6. The engineer conducting the testing shall record the following:
  - a. Time
  - b. Date
  - c. Location of Test
  - d. Outside Weather Data (including wind speed, direction and temperature)
  - e. Inside Weather Data (including wind speed, direction, and temperature)
  - f. Initial pressure differences between inside and outside, if any
  - g. Number of doors initially open and initially closed
  - h. Status of HVAC system for the Building (ON/OFF)
7. Active firefighting equipment shall be available on site prior to any tests being conducted.
8. The building's life safety systems shall be fully operational and checked out for any errors. The Fire Alarm Control Panel shall be free of all alarm and trouble conditions that the engineer believes may pose a conflict with the testing. All exit signs and means of egress marking shall be in place and functioning properly.

**PASS CRITERIA**

All of the following criteria must be achieved during the same test for the Smoke Control System to be considered passing:

1. Activation of a sprinkler water flow switch serving the smoke zone being tested automatically activates the proper life safety and smoke control functions.
2. Designed air quantities are being delivered within 135 sections of fire alarm activation, or within a timeframe specified by determined by the Smoke Control Special Inspector or Authorities Having Jurisdiction.
3. Designated fire doors close at zone boundary within 75 seconds of fire alarm activation, or within a timeframe specified by determined by the Smoke Control Special Inspector or Authorities Having Jurisdiction.
4. Designated makeup air windows/louvers open within 75 seconds of fire alarm activation, or within a timeframe specified by determined by the Smoke Control Special Inspector or Authorities Having Jurisdiction.
5. Audible and visual fire alarm signal function in accordance with the requirements of the Code.
6. Smoke control systems activate in accordance with the sequence of operations when activated from the firefighter's smoke control panel (location to be determined).

---

**Smoke Control Rational Analysis**

---

7. Required dampers and fire doors close automatically without assistance of human beings.
8. Life Safety systems operated correctly while under emergency power.
9. Emergency power operates life safety systems (simulate a loss of normal building power while testing life safety systems).
10. Fire alarm and smoke control systems operate correctly on the fire floor when activated manually or automatically.
11. Doors at the zone boundaries are operable within the code requirements for opening forces.
  - a. Doors that are closed during the sequence of operation at zone boundaries can be opened and re-closed while fans are functioning.
  - b. The system is not designed to maintained pressure differences when the doors are open and the opening of doors during the test is not required.

***FAILURE CRITERIA***

If any of the following items occur during the test, the test is immediately considered failing.

1. Smoke control equipment does not operate or function.
2. Fire alarm system fails to activate the smoke control system.
3. Fans and related systems do not operate when activated manually at the firefighter's smoke control panel.
4. System does not meet the pass criteria above.
5. Smoke control equipment (dedicated and shared air distribution fans, dampers etc.) does not provide the required air quantities shown on the mechanical engineer's design documents.
6. System fails to return to normal mode when manual override is signaled.
7. Systems fail to function on emergency power.
8. Required doors, louvers, and dampers fail to open (as required).
9. Required doors, louvers, and dampers fail to close (as required).

***PERIODIC TESTING REQUIREMENTS***

Once the smoke control system has been fully commissioned, it is required to be maintained and comply with the periodic testing and maintenance requirements of IBC, IFC, NFPA 92, and UL 864

1. In accordance with MSBC Section 909.12.1, NFPA 92, and UL 864 an automatic pre-programmed weekly self-test of the smoke control system must be provided within the system design. The functionality of this pre-programmed test will be required to be reviewed and documented by the smoke control special inspector. In addition, weekly records should be kept on site and a semi-annual test under standby power will be required.
2. The smoke control system is required to be inspected and tested semi-annually in accordance with MSBC Section 909.18.8. Semi-annual testing must be performed to sufficiently verify that the smoke control system is properly maintained and still functions and performs in accordance with the final commissioning report prepared by the smoke control special inspector. Testing shall identify the current status of the system, indicate any deficiencies and provide recommendations for correcting such deficiencies. Such information should be kept on site and available for review.

**CONCLUSION**

This analysis utilized a mechanical smoke control system to maintain tenable conditions along the means of egress system throughout the Framingham Fuller Middle School atrium. This rational analysis demonstrates that tenable conditions are maintained at least 6 feet above any walking surface that forms a portion of the required atrium means of egress system for the evacuation of occupants (MSBC Section 909.8) when protected by the smoke control system outlined herein.


The rationale presented within this report is in accordance with the Massachusetts State Building Code and NFPA 92, and demonstrates compliance with the intent of the Code, which is to maintain tenable conditions along the means of egress during a fire event for a minimum of 1.5 times the required safe egress time, or 20 minutes after detection, whichever is greater (MSBC Section 909.4.6).



**APPENDIX A – HEAT RELEASE RATES**

This section of the report contains numerous examples of heat release rates expected from a variety of fuels commonly found in assembly occupancies such as this building. These heat release rates have been utilized to evaluate the trial designs and system performance contained in the analysis section of this report.

Figure 42 presents the results of five (5) kiosk fire tests, each with a different configuration including variations in T-shirt arrangement, composition of T-shirts, dimensions of kiosk, materials of the kiosk, variations in air current near the kiosk. Although the configurations of each test were different, the heat release rate curves were very similar, and in no case did the fuel load produce a heat release rate exceeding 2,000 BTU/s.




**Figure 42: Kiosk Heat Release Rates with Variations**

Using a fast growth, 2,000 kW steady state fire is generally considered larger than the fuel load found anticipated for a kiosk/display, and would likely exceed the expected fuel load contained on the space during a typical event.


**Example: Two-Panel Workstation Fire**

The results of the fire tests for the “Two Panel Workstation Fire” provided a peak heat release rate of 1,749 kilowatts (kW) at a time of 5 minutes. The ignition source for the fire was located below the desk adjacent to the office chair, such as could occur when using a power strip located on the floor. The duration of the fire from ignition to consumption of fuel/burnout was 42 minutes. Figure 43 illustrates the heat release rate as a function of time.



**Figure 43: Heat Release Rate vs. Time (Individual Two-Panel Workstation Fire)**

Figure 44 through Figure 48 illustrate the development of the Two-Panel Workstation fire, as observed during the testing performed by NIST, at various stages of fire progression.



**Figure 44: Two Panel Workstation fire at time 0:00 and 2:00 minutes**



Figure 45: Two Panel Workstation fire at time 4:00 and 6:00 minutes



Figure 46: Two Panel Workstation fire at time 8:00 and 10:00 minutes



Figure 47: Two Panel Workstation fire at time 20:00 and 30:00 minutes



**Figure 48: Two Panel Workstation fire at time 42:00 minutes**

## Smoke Control Rational Analysis

**PUBLISHED HEAT RELEASE RATES (UNITED STATES RESEARCH)**

Heat Release Rate (HRR) is the best and primary measure of fire hazard. Heat release rates can be affected by numerous factors, including:

1. Size and configuration of fuel package
2. Location of fuel package with respect to walls, other fuel packages, vents, etc.
3. Ignition source and location of ignition
4. Room size, construction material, vents, fire protection systems, etc.

**Table 6: Approximate “Typical” Examples of Peak Heat Release Rates**

MATERIALS	HEAT RELEASE RATE (kW)
<b><i>Kiosks and Displays</i></b>	
Display Kiosks (Kiosk structure only)	1,400 - 2,000
<b><i>Office Workstation Setup</i></b>	
Computer Workstation	1,000-1,300
One Unit Workstation	1,200 – 3,000
Two-Panel Workstation	2,000
<b><i>Garbage and Refuse</i></b>	
Medium Wastebasket with milk cartons	105
Large barrel with milk cartons	148
Trash Bag, One Sack, 1.17 kg	140
Trash Bag, Two Sacks, 2.34 kg	290
Trash Bag, Three Sacks, 3.51 kg	345
Trash Bag, One Sack, 4.1 kg	345
30 Gallon HDPE Garbage Can with Construction Debris	160 - 450
96 Gallon Polyethylene Garbage (empty, no contents)	1,000 - 2,400


## Smoke Control Rational Analysis

MATERIALS	HEAT RELEASE RATE (kW)
<b>Stackable Chairs</b>	
Chair Mockup	63-66
Chairs (<10, metal frame)	80-2,480
Single Metal Frame, upholstered stacking chair	90
Single Stackable Chair, Polypropylene with Steel Frame, no Padding	150
Metal Frame, upholstered stacking chair 4 chairs in 1 stack	240
Two Swivel Office Chairs	275
Upholstered chair with polyurethane foam	353
Two Metal Frame Chair	475
Metal Frame, upholstered stacking chair 8 chairs in 1 stack	500
5 Stackable Chairs in 1 row, Polypropylene with Steel Frame, no Padding	750
Metal Frame, upholstered stacking chair 8 chairs in 1 stack in the corner	900
8 Stackable Chairs in 4 rows, Polypropylene with Steel Frame, no Padding	1,250
6 Stackable Chairs in 1 stack, Polypropylene with Steel Frame, no Padding	1,900
12 Stackable Chairs in 2 stacks, Polypropylene with Steel Frame, no Padding	2,200
<b>Furnished Room (Dwelling Unit)</b>	
Wastepaper Basket (no contents)	4-18
TV set	120-290
Curtains, Acrylic/Cotton	130-150
Arm Chair	160
Curtain, Velvet, Cotton	160-240
Sofa	3,120
Small Air Conditioner with a Plastic Housing	300
Wooden Desk	640
Loveseats	940-2,980 (370, metal frame)
Latex foam mattress (heat at room door)	1265
Wooden Dresser	1,800
<b>Typical House Hold Furnishings</b>	
Palm, Slim Plastic House Plant	50
Ficus, Plastic House Plant	10
Manzanita Bush 1.11 kg, 87% Moisture Content	135
Ceanothus Bush 2.07 kg, 31% Moisture Content	95
Palm, Bushy Plastic House Plant	180
Rockrose Bush 2.03 kg, 14% Moisture Content	265
Christmas Tree, Dry	500-650
PVC Christmas Tree (peak was much greater, due to fast rise time)	600 - 978
Juniper Bush 2.07 kg, 31% Moisture Content	810

**APPENDIX B – ATRIUM ZONE BOUNDARY**

Appropriately zoned sprinkler water flow switches (sprinklers zoned within the Atrium Zone Boundary), or appropriately zoned partial coverage spot-type smoke detection and beam detection are required to activate the smoke control system. The intent of creating an Atrium Zone is to activate the smoke control system when a fire originates within the Atrium, or when the smoke from an adjacent space is spilling into the Atrium and activates a device within the Atrium. The smoke control system should not be activated upon the activation of a sprinkler/waterflow or smoke detection device outside of the Atrium Zone. This would cause smoke to migrate into the Atrium, creating a greater hazard.


To help facilitate the appropriate zoning of sprinkler/waterflow, and smoke detection devices please refer to the Figure 49 through Figure 51 below. All sprinkler/waterflow and smoke detection devices within the BLUE highlighted area are within the Atrium Zone and should activate the smoke control system. All sprinkler/waterflow and smoke detection devices outside the highlighted area should not activate the smoke control system.




**Figure 49: Floor 1 – Atrium Boundary Zone**

Smoke Control Rational Analysis

---



**Figure 50: Floor 2 – Atrium Boundary Zone**




**Figure 51: Floor 3 – Atrium Boundary Zone**



**APPENDIX C – TIMED EGRESS ANALYSIS**

An occupant movement and egress analysis utilizing the SFPE numerical calculation was performed for Floor 1 through Floor 3. The Life Safety Drawings created by Howe Engineers dated October 18, 2019 were utilized in order to perform the egress analysis (determine occupant loads and distribution to exits). Any changes to the Life Safety Drawings may impact the results of this analysis, thus requiring this analysis to be reevaluated. There are many components that contribute to calculating the available safe egress time (RSET). As shown in Figure 52 from the Society of Fire Protection Engineering, the calculated RSET is broken down into three (3) distinctive phases: Detection Time Phase (this phase includes detection time and alarm transmission time), Pre-movement/Delay Time to Start Phase (this phase includes recognition, and response time), and the Movement Time Phase. These components are described in more detail within the corresponding sections below.



**Figure 52: Egress Time Model**

***DETECTION TIME PHASE***

The interval between fire ignition and the first detection of the fire by a device or an individual. For this analysis, the means of fire detection is via smoke detection, or sprinkler activation and waterflow switch. Note, the building will be provided with smoke detection throughout.

1. **Detection Time:** Smoke detection is modeled within the building. The longest time to detection of a smoke detector in any of the scenarios presented in this report is approximately 103 seconds, therefore, to remain conservative a detection time of **103 seconds** was used for this analysis.
2. **Alarm Time:** The interval between detection of the fire and the time at which an alarm signal is activated or notification of occupants takes place. In most cases the alarm time occurs effectively simultaneously with the detection time and therefore no additional time is required to be added for alarm time. However, for conservatism, a **10 second** delay is included within this analysis, which is the maximum transmission time of an alarm signal allowed by NFPA 72.

**PRE-MOVEMENT TIME PHASE**

The interval between the time at which the alarm signal is given and the time at which the decision is made and the person starts evacuation. This consists of two (2) components:

1. Recognition Time: The interval between the time at which the alarm signal is perceived and the time at which the occupant interprets this signal as indicating a fire/emergency event. This time includes investigation and milling.
2. Response Time: The interval between recognition time and the time at which the first move is made to evacuate the building. This time includes activities such as firefighting, warning others, gathering family members and pets, dressing, retrieving personal belongings, calling the fire department, etc.

Table 7 below is provided to approximate the Alarm Time, Recognition Time and Response Time for given occupancies based on the type of warning system, the type of occupancy, and the characteristics of the occupants. The Framingham Fuller project, which is classified as primarily a Group E educational occupancy, will be provided with an emergency alarm/voice communication fire alarm system. Conservatively, a “W2” delay for buildings, which denotes occupants that are awake but not familiar with the building, shall be used for analyzing occupant movement, and an applicable occupant pre-movement time after alarm of **3 minutes (180 seconds)** will be used.

**Table 7: Estimated Delay Time to Start Evacuation**

Occupancy Type	W1 (min)	W2 (min)	W3 (min)
Offices, commercial and Industrial buildings, schools, colleges and universities (Occupants awake and familiar with the building, the alarm system, and evacuation procedure.)	< 1	3	> 4
Shops, museums, leisure-sport centers, and other assembly buildings (Occupants awake but may be unfamiliar with building, alarm system, and evacuation procedure.)	< 2	3	> 6
Dormitories, residential mid-rise and high-rise (Occupants may be asleep but are predominantly familiar with the building, alarm system, and evacuation procedure.)	< 2	4	> 5
Hotels and boarding houses (Occupants may be asleep and unfamiliar with the building, alarm system, and evacuation procedure.)	< 2	4	> 6
Hospitals, nursing homes, and other institutional establishment (A significant number of occupants may require assistance.)	< 3	5	> 8

W1: live directives using a voice communication system from a control room with closed-circuit television facility, or live directives in conjunction with well-trained, uniformed staff that can be seen and heard by all occupants in the space  
W2: nondirective voice messages (pre-recorded) and/or informative warning visual display with trained staff  
W3: warning system using fire alarm signal and staff with no relevant training

**MOVEMENT TIME PHASE ANALYSIS**

The interval between when occupants begin to move toward an exit and when all occupants reach a place of safety. In order to evaluate the performance of the egress components, and to compare it to the results of the CFD modeling, the SFPE Hand Calculations for egress time have been performed for Floor 3, which is the limiting required egress time. The smoke would reach Floor 3, and therefore if all occupants are egressed from Floor 3 prior to smoke reaching them it is assumed that the other levels would also be provided with enough time for the associated occupants to egress appropriately. Please note that the smoke control rational analysis demonstrates that the smoke layer is maintained above Floor 3 for the duration of the scenarios.

**Timed Egress Calculations**

The timed egress calculation analyzes expected evacuation times from the building under moderate movement conditions, which is expected. A moderate movement scenario may include the evacuation of the floor when everyone leaves the facility, and assumes no blocked exits.

The total time for evacuation can be considered the time required to travel from the most remote point in the building to the rated stair enclosure plus the flow time required for each occupant to pass through the most restrictive egress component (this approach is identified in the SFPE Handbook).

**Moderate Movement Conditions**

This scenario considers the evacuation of Floor 3 (highest level within the Framingham Fuller Middle School Atrium) when everyone begins to exit the building. The following assumptions were made in calculating the evacuation times:

- Every means of egress from the floor is available for use and not considered blocked.
- The total occupant load of the floor is 636 people, as indicated by Life Safety Plan LS103.
- Occupant distribution to the varying exits varies as indicated by Life Safety Plan LS103.

The following evacuation time calculations are based on adding the time it takes for a person to travel the most remote distance to the time it takes everyone to pass through the most restrictive egress component. For occupant load distribution please reference the Life Safety Drawings.

**Flow Time**

The flow is the measurement of the flow of evacuating persons past a point in the exit route per unit of time per unit of effective width. The specific flow is calculated by applying Equation (59.6) from the 5<sup>th</sup> Edition of the SFPE Handbook, Chapter 59, entitled, "Employing the Hydraulic Model in Assessing Emergency Movement" by Steven M.V. Gwynne and Eric R. Rosenbaum. The specific flow is calculated as follows:

$$F_s = SD$$

Where:

$F_s$  = specific flow in persons/minute/ft of effective width

$S$  = speed in persons/minute

$D$  = density in persons/ft<sup>2</sup>

Table 8 shows the specific flows for various aspects of the egress system at moderate densities.

---

Smoke Control Rational Analysis

**Table 8: Specific Flow for Moderate and Crush Densities**

Egress System Component	Speed (persons/minute)	Density (persons/ft <sup>2</sup> )	Specific Flow (persons/minute/ft)
Doorways	196.35	0.1	<b>19.64</b>
Stairs with 7 inch riser and 11 inch tread	151.37	0.1	<b>15.12</b>

The calculated flow for a given point is determined by applying Equation (59.8) from the 5<sup>th</sup> Edition of the SFPE Handbook, Chapter 59, entitled, "Employing the Hydraulic Model in Assessing Emergency Movement" by Steven M.V. Gwynne and Eric R. Rosenbaum. Calculated flow is determined by multiplying the specific flow by the effective width of the given point (ie: doorway, stair, ramp, etc.).

$$F_c = F_s W_e$$

Where:

$F_c$  = calculated flow in persons/minute

$F_s$  = specific flow in persons/minute/ft = 19.64 persons/min/ft for doors

$W_e$  = effective width in feet = Door width – 6" boundary from each side

The estimated flow (minutes) can then be determined by dividing the number of persons exiting (provided on the Life Safety Drawings) by the Calculated Flow ( $F_c$ ). A summary for each of the exits on Floor 3 is provided below:

FLOW TIME RESULTS <sup>1</sup>					
Flow Point	Limiting Component	Width	Number of Persons Exiting	Calculated Flow [ $F_c$ ] (persons/min)	Estimated Flow Time (minutes)
<b>Stair 1</b>	Door	2'10"	213	36.00	<b>5.91</b>
<b>Stair 2</b>	Door	2'10"	101	36.00	<b>2.80</b>
<b>Stair 3</b>	Stair	4'7"	121	54.18	<b>2.23</b>
<b>Stair 5</b>	Stair	8'4"	201	110.88	<b>1.81</b>
Notes:					
1. Please Reference Life Safety drawings for occupant load distribution information					

As shown in the table above, since the occupant load distribution varies, Stair 1 has a larger number of occupants using the stair. Therefore, the flow time at Stair 1 is significantly longer. The flow time for Stair 1 of **5.91 minutes** will be used in calculating the total evacuation time. This assumes no aid in the evacuation process from operations personnel to produce a conservative approach.

Smoke Control Rational Analysis

**Travel Time**

The speed along the line of travel can be determined by applying Equation (59.5) and Table 59.2 from the 5<sup>th</sup> Edition of the SFPE Handbook, Chapter 59, entitled, "Emergency Movement" by Harold Nelson and Hamish MacLennan. The speed of movement along a level line of travel is calculated as follows:

$$S = k - aD$$

Where:

S = speed

D = density; (Moderate Density = .1 persons/ft<sup>2</sup>)

k = constant, from Table 3-14.2, seen below.

a = 2.86 for speed in ft/minute and a density in persons/ft<sup>2</sup>

Table 9 shows the speed of movement along a line of travel for various aspects of the egress system.

**Table 9: Speed of Movement for Moderate and Crush Densities**

Egress System Component	k = constant from Table 3-14.2	D = Density (persons/ft <sup>2</sup> )	Speed (ft/minute)
Level Surfaces & Doorways	275	0.1	<b>196.35</b>
Stairs with 7 inch riser and 11 inch tread	212	0.1	<b>151.37</b>

The travel time is calculated from the most remote point to the egress component which yields the longest flow time. In this case, travel time is calculated for the maximum travel distance to each of the stair exits as shown on the Life Safety Drawing. The travel time is calculated as follows:

TRAVEL TIME RESULTS			
Travel Points	Estimated Distance on Level Surface (ft)	Speed on Level Surface (ft/min) <sup>1</sup>	Estimated Travel Time (minutes)
<b>Stair 2</b>	237'0"	196.35	<b>1.21</b>
<b>Maximum Travel Time (min) =</b>			<b>1.21</b>
Notes:			
1. Speed of occupants is based on travel over a relatively flat surface and equation $S = k - aD$ (SFPE Handbook); where $k = 275$ for ramps; $a = 2.86$ (constant); and $D = 0.1$ for moderate density			

As shown in the table above, the total travel time that can be expected from the most remote area to the stair of the building is **1.21 minutes**. Therefore, the TOTAL evacuation time expected for every occupant on Floor 3 to reach an exit enclosure **7.12 minutes** (5.91 min + 1.21 min= 7.12 min).

**CONCLUSIONS**

The Required Safe Egress Time (RSET) is based on the time at which the last occupant in the timed egress analysis leaves the interior portions of Floor 3 via an exit enclosure (i.e. exit stairway or exit passageway). The total RSET for the building is based on the maximum time for an occupant, within the atrium, to reach an exit. A 50-percent margin of safety is applied to calculate the movement time that was used to determine the Required Safe Egress Time (RSET), as required by MSBC Section 909.4.6.

The atrium spaces are large volume spaces and there is active smoke control to prevent large exits from being blocked by fire locations, the analysis is not required to address blocking of exits.

Given the information presented above, we would expect the following total Required Safe Escape Time (RSET):

**Fire Alarm Detection Time + Pre-Movement Time + Movement Time (+ 50% Safety Factor) = Required Safe Escape Time**

*1 min 53 seconds + 3 mins 00 seconds + 10 mins 41 seconds = 15 mins 34 seconds*

**Based on the Smoke Control Rational Analysis Report, the smoke control system is capable of maintaining Available Safe Egress Time (ASET) in excess of 25 minutes. Since the ASET is greater than the RSET of 15 minutes 34 seconds, it can be determined occupants will be able to evacuate the building while tenable conditions are maintained along the egress paths in the atrium of the building. Additionally, it is important to note, the results within smoke control rational analysis demonstrate the smoke control system reaches steady state smoke level conditions within the 25-minute model duration. Therefore, it is expected that tenable conditions will be maintained indefinitely, provided the smoke control system is operational.**

### 3.1.4 Proprietary Items

The SBC voted to approve the attached proprietary specification at their 9/16/19 meeting and requested the School Committee to approve at an upcoming meeting.

Also attached is the listing of Proprietary Specifications, dated May 22, 2019, recommended to be included in the Fuller Middle School project. The proprietary items were approved by the following elected bodies of the District:

School Building Committee on Monday, June 3, 2019

School Committee on Wednesday, June 5, 2019

Approval documentation is included in the certified attached School Committee Meeting Minutes from June 5, 2019.





## Memorandum

To:	Fuller Middle School Building Committee	Date:	9/16/2019
From:	Joel G. Seeley	Project No.:	17050
Project:	New Fuller Middle School		
Re:	Proprietary Specification		
Distribution:	School Building Committee (MF)		

---

School Building Committee Members,

Please find the supplemental listing of Proprietary Specifications, dated September 9, 2019, recommended to be included in the project by Framingham Public Schools Building and Grounds Department. These have been reviewed by the architect and they agree with the recommendation. This is a supplement to the list approved by the School Building Committee at the June 3, 2019 School Building Committee meeting.

The School Building Committee is requested to approve the attached recommended listing of Proprietary Specifications and recommend approval by the School Committee.

**MEMORANDUM**

DATE: September 9, 2019

**PROJECT: Fuller Middle School Framingham, MA**

**SUBJECT: Proprietary Items**

TO: Joel Seeley, SMMA

FROM: Philip Gray, AIA Jonathan Levi Architects

On July 29, 2019 the architects reviewed the use of 2 ballistic glazing products for use in the new Fuller Middle School with the Framingham Public Schools Director of Safety and Security, the FPS Building and Grounds Department, and the School principal. These products were unanimously recommended to be listed as proprietary in the specifications for the new Fuller School. These will need to be voted on and approved by the SBC in order to be included in the specification for the new Fuller Middle School.

SYSTEM	MANUFACTURER	REASON FOR RECOMMENDATION
School Guard Glass, product SG4	LTI Smart Glass, Inc. 14 Federico Drive, Pittsfield, MA 01201	Where proposed in building, provides greatest degree of protection in combination with standard framing systems
3M Scotchshield S Series Safety and Security Window Film	3M commercial Solutions, 3M Center, Bldg. 220-12-E-04; St. Paul, MN 55144-1000	Where proposed in building, provides greatest degree of protection in combination with standard framing systems

- Provide a list identifying all proposed proprietary items (if any) with an affidavit which shall indicate an elected body of the district (school committee, city or town council, or selectmen, - but not an ad-hoc building committee) has been presented with proposals for proprietary requirements approval action, has had an opportunity to investigate, or to require staff or consultant investigation upon each item so proposed, and has majority voted in an open public session that is in the public interest to do so. Provide MSBA with a certified copy of the vote of the elected body.
- An interior color theory statement describing proposed paint and material selections and colors for typical and special spaces, why they have been selected and how these selections relate to exterior materials and colors. Confirm that color and material selections have been presented to and approved by the District
- Confirmation of project registration with CHPS or USGBC
- Structural narrative including methods of lateral bracing and how requirements of earthquake code will be met
- Structural calculations and required floor loads
- Energy calculations
- Life Cycle cost analysis for energy and water consuming devices
- Heat gain and loss calculations for Heating, Ventilating and Air Conditioning systems
- Calculations showing total electrical load
- Security and visual access requirements:
  - Confirmation that the persons responsible for implementation of the District's emergency procedures, and responding emergency medical, fire protection, and police agency representatives have been consulted in the planning process and any associated requirements have been included in the project
  - Identification of any other security related items particular to the District and/or the proposed project
  - Verification that the following safety and security related issues have been reviewed and are in accordance with the District's procedures as noted above:
    - Main entrance design – describe District protocol for visitor entry and check-in related to the current design for visitors to remain in the vestibule versus a side sub-vestibule
    - Classroom lockset hardware - confirm hardware functions are compatible with the District's protocols related to lockdown
    - Classroom / Instructional spaces visibility - confirm that the inclusion of sidelights at entrance locations is compatible with the District's current standards related to visibility from corridors and whether any related vision control option measures are to be incorporated
    - Alternative entry locations - confirm project includes site and building signage, as may be required by District's emergency procedures, to identify locations where first responders may more directly reach a person needing medical attention; Knox



## Memorandum

To:	Fuller Middle School Building Committee	Date:	6/3/2019
From:	Joel G. Seeley	Project No.:	17050
Project:	New Fuller Middle School		
Re:	Proprietary Specification		
Distribution:	School Building Committee (MF)		

---

School Building Committee Members,

Please find the updated listing of Proprietary Specifications, dated May 22, 2019, recommended to be included in the project by Framingham Public Schools Building and Grounds Department. These have been reviewed by the architect and the engineers and they agree with the recommendation. This is an update of the list reviewed at the April 8, 2019 School Building Committee Meeting.

Also attached is an excerpt from the MSBA's Detailed Design Requirements Module 6, which requires a vote by an elected body of the District for proprietary specifications.

The School Building Committee is requested to approve the attached recommended listing of Proprietary Specifications and recommend approval by the School Committee.

**MEMORANDUM**

DATE: March 15, 2019, *Revised March 21, 2019, Revised April 8, 2019, Revised May 22, 2019*

**PROJECT: Fuller Middle School Framingham, MA**  
**SUBJECT: Proprietary Items**

TO: Joel Seeley, SMMA  
FROM: Elizabeth Bugbee, AIA Jonathan Levi Architects


On February 20, 2019 the Framingham Public Schools Building and Grounds Department identified and recommended the following items to be listed as proprietary in the specifications for the new Fuller School. These items were reviewed with the architect and MEP engineers, who agree with the recommendations. These will need to be voted on and approved by the SBC in order to be included in the specification for the new Fuller Middle School.

SYSTEM	MANUFACTURER	REASON FOR RECOMMENDATION
Automatic Temperature Controls	Tridium Niagara N4 Supervisor - JACE Controller	Tridium Niagara N4/Supervisor is the current City standard for the Building Management System (BMS). This would be an extension of the City's existing building management Architecture system with Tridium Niagara N4/JACE controllers and will provide a seamless tie-in to the existing City's building management system BMS Server. The Tridium Niagara N4/Jace would therefore result in the reduction of costs of maintenance staff training and servicing, to improve reliability of service from contractors, and improve integration of systems into the existing Facility control network. The Tridium Niagara N4 Supervisor system provides an open platform to allow integration of a variety of other control system protocols with JACE Controller (eg BACNet IP, etc.)
Network Switches	HP	Maintaining a standard set of manufacturers for this type of equipment helps to lower the total cost of ownership of the system by allowing the City to maintain a standard operating procedure for installation, operation, support and maintenance.
Access Control	S2	Maintaining a standard set of manufacturers for this type of equipment helps to lower the total cost of ownership of the system by allowing the City to maintain a standard operating procedure for installation, operation, support and maintenance.
Closed Circuit TV	Cisco Meraki System	Maintaining a standard set of manufacturers for this type of equipment helps to lower the total cost of ownership of the system by allowing the City to maintain a standard operating procedure for installation, operation, support and maintenance.
Door Hardware Key System and Lock Cylinders	Schlage Classic Keyways: C, E, EF and F.	The existing Framingham Public Schools master key system is a registered system with Schlage Lock. The school district would like Fuller Middle School keyed into the existing registered master key system.
Classroom Door Hardware	Securitech QID	Allows user to quickly lock classroom door via push button in lieu of thumb turn or key and has visual indicator to notify occupants that the door is deadbolted and the outside lever is locked.

- Provide a list identifying all proposed proprietary items (if any) with an affidavit which shall indicate an elected body of the district (school committee, city or town council, or selectmen, - but not an ad-hoc building committee) has been presented with proposals for proprietary requirements approval action, has had an opportunity to investigate, or to require staff or consultant investigation upon each item so proposed, and has majority voted in an open public session that is in the public interest to do so. Provide MSBA with a certified copy of the vote of the elected body.
- An interior color theory statement describing proposed paint and material selections and colors for typical and special spaces, why they have been selected and how these selections relate to exterior materials and colors. Confirm that color and material selections have been presented to and approved by the District
- Confirmation of project registration with CHPS or USGBC
- Structural narrative including methods of lateral bracing and how requirements of earthquake code will be met
- Structural calculations and required floor loads
- Energy calculations
- Life Cycle cost analysis for energy and water consuming devices
- Heat gain and loss calculations for Heating, Ventilating and Air Conditioning systems
- Calculations showing total electrical load
- Security and visual access requirements:
  - Confirmation that the persons responsible for implementation of the District's emergency procedures, and responding emergency medical, fire protection, and police agency representatives have been consulted in the planning process and any associated requirements have been included in the project
  - Identification of any other security related items particular to the District and/or the proposed project
  - Verification that the following safety and security related issues have been reviewed and are in accordance with the District's procedures as noted above:
    - Main entrance design – describe District protocol for visitor entry and check-in related to the current design for visitors to remain in the vestibule versus a side sub-vestibule
    - Classroom lockset hardware - confirm hardware functions are compatible with the District's protocols related to lockdown
    - Classroom / Instructional spaces visibility - confirm that the inclusion of sidelights at entrance locations is compatible with the District's current standards related to visibility from corridors and whether any related vision control option measures are to be incorporated
    - Alternative entry locations - confirm project includes site and building signage, as may be required by District's emergency procedures, to identify locations where first responders may more directly reach a person needing medical attention; Knox







# Framingham Public Schools

Robert A. Tremblay, Ed.D., Superintendent of Schools

## SCHOOL COMMITTEE

Adam Freudberg, Chair • Gloria Pascual, Vice Chair • Tracey Bryant, Clerk  
Noval Alexander • Geoffrey Epstein • Richard A. Finlay  
Beverly Hugo • Tiffanie Maskell • Scott Wadland  
Yvonne M. Spicer, Mayor

73 Mount Wayte Avenue, Second Floor, Framingham, MA 01702  
Telephone: 508-626-9121 Fax: 508-877-4240

---

### SCHOOL COMMITTEE: OPEN MEETING MINUTES

**DATE AND TIME:** June 5, 2019 at 7:00 p.m.

**LOCATION:** Memorial Building-Blumer Room  
150 Concord Street, Framingham

**MEETING CALLED BY:** Chair Adam Freudberg

**PRESENT:** Noval Alexander  
Tracey Bryant  
Geoffrey Epstein  
Richard A. Finlay  
Adam Freudberg  
Beverly Hugo  
Tiffanie Maskell\*  
Gloria Pascual\*  
Mayor Yvonne Spicer\*

**ABSENT:** Scott Wadland

**ALSO PRESENT:** Nicholas Small, Chair of Student Advisory Committee  
Dr. Tremblay, Superintendent  
Lincoln Lynch, Director of Finance and Operations  
Rose Bailey, Student Advisory Committee  
Matt Torti, Director of Building and Grounds

---

The Chair called the meeting to order at 7:01 p.m.

#### Call to Order

The Chair announced that this meeting was being broadcast live on local cable, as well as for later playback, and on Facebook Live.

### Public Comment

Ron Chick said he is a representative for the Sue Haskell Watershed for Framingham, and he brought Riverfest brochures. He said that there are many events coming up, including a water cleanup on June 22nd at 151 Central Street starting at 8:00 a.m., and a senior tour of the river at 11:00 a.m. He said he is looking for volunteers, especially student volunteers, for various clean ups in the area, and would like to work with the Ecology Club at the High School. He said he is working on a project on invasive vegetation on the Cochituate Rail Trail in Saxonville, and eliminating invasive water chestnuts on the Sudbury River. He suggested that students could possibly get credits for volunteering. He said he is also the Chair of the Friends of Saxonville and welcomes participation. The Chair asked the Superintendent to have someone from his team follow up on the ideas regarding student participation.

Noval Alexander said he wanted to make a brief comment on commemorating D-Day tomorrow and asked for a moment of silence. He said that on this day 75 years ago, hundreds of thousands of young soldiers, sailors, marines and airmen were staging in southern England to commence Operation Overlord, otherwise known as D-Day, where they crossed the English Channel to liberate Europe from Nazi Germany. He said that no matter what race, religion or natural origin, all had the common purpose to defeat the tyrannical German dictator Adolf Hitler. He said that day, over 10,000 allied soldiers died on the beach in Northern France, and he would like to take a moment of silence and remember that.

Richard Finlay said he wanted to send get well wishes to Mr. Wadland who is home recovering.

### Announcements from the Chair

No announcements from the Chair.

### Student Advisory Committee Presentation on Intramural Sports and School Spirit

Student Advisory Committee members Nicholas Small and Rose Bailey presented a report based on a survey sent to students regarding interest in intramural sports and thoughts on school spirit. They said that they found from these surveys that a large number of students are interested in intramurals, and school spirit at FHS is good but could be improved - with ideas such as adding more pep rallies, themed events and improved faculty support at student events.

**Questions.** Mr. Epstein asked what the next steps are in regards to starting intramurals. Mr. Small said they had a brief discussion with Mr. Spear, the Athletic Director, and he said that the biggest issue would be space, but an intramural like Dance would be more do-able because there are specific classrooms that could accommodate Dance. Mr. Epstein said that there are a lot of high intensity sports that take over all the facilities and a lot of money spent on those: Maybe they could skip those sports one day a week or use the facilities when they have games out of town. He said there is a need to look at how to service intramurals, rather than just say it is an interesting idea that we cannot do.

### Action Civics Commission Presentation on Homework Policy

Dr. Tremblay said starting the Action Civics Commission was one of his goals, and it will provide grades 9-12 with a representation of government. Action Civics Commission members Mira

Donaldson, Hailey Vanaelstyn, Laura Scaria, Anne Culhane-Williams, Sanga Esther Kalemba, Ava Caiola, and Harold Pacheco Diaz presented their proposed homework policy, which they developed after they had reviewed other policies from other schools, and news articles, as well as taking information from interviewing students and teachers. Ava Caiola said that along with the proposal of no homework for those who are in MCAS testing, they also want to add the ACCESS testing for ELL and ESL students, but that was not included in this draft. She said that they also met with the faculty to present their draft, get feedback, and answer questions on their proposed policy. Mira Donaldson added that edits from that meeting were able to be added to the policy.

Mr. Freudberg said that last year this policy was voted on to refer to the Policy Subcommittee, so now they have some insight to determine next steps.

**Questions.** Mr. Finlay spoke about the stress on students for homework and having to balance it with extracurricular activities and sports. Ms. Bryant asked which neighboring schools' policies were looked at, as well as how they decided that homework on weekends should not exceed that of a weekday. She added that sometimes students who have extracurricular activities during the week, use the weekend to catch up on schoolwork. Mira Donaldson said they looked at policies from Hopkinton, Holliston and Natick. Ava Caiola said that the biggest issue seems to be that whenever there is time to relax, teachers have tried to fit an extra assignment in to fill the time, and students have felt a bit of an overload. She said that they felt that students should still have homework on the weekend, but with a limit; this will allow students to still be able to do activities they want to do, while still staying involved with school. She added that this is the same with school vacations - for students to keep on track and be thinking of school work, but also be able to enjoy time away from school. Ms. Pascual suggested the possibility of forms being used for the observance of religious holidays, to be able to make it clearer to teachers to put this consideration into action, for equity, and forms could possibly be used for other things going on in life besides just holidays. She also suggested that teacher communication to students be improved - such as the family and guidance counselor being contacted after two missing assignments, so everyone is aware before students get too far behind, and are not able to recover. Ava Caiola said that teacher feedback suggested the possibility of students being referred for after-school help with peer tutoring after a few missed assignments. Ms. Pascual said there is a need to look at holding teachers accountable for putting this into place, and making sure there is a measurement, as well as to allow teachers, counselors, and parents to know when there is a need to help students and get them that help. Ms. Maskell asked what the expectation for the amount of homework per night is currently, and suggested that there be a defined amount of time for homework; since students work at different levels and if they can't master it by a certain point, should they really be spending hours on it. Mira Donaldson said that the current policy has a three hour minimum and no maximum. Anna Culhane-Williams said that when they talked to the teachers this came up, and they discussed how the amount of time each student spends on homework depends on each individual student, and defining a specific time would be a bigger discussion. Ava Caiola said they also discussed possibly defining it per department, but this again would be a larger conversation, and would take more time to get into and implement.

\*Mayor Spicer arrived at 7:40 p.m.

Ms. Maskell said that the proposed policy notes that homework is lessened for all classes, except for AP classes. Laura Scaria said AP classes have a set curriculum to get through for the year in order to take the AP test, so it is hard to limit the homework. Ms. Maskell said she's

sure some kids would abuse it if there was a set amount of time defined, but the majority of students seem to be working hard at whatever level they are at. Hailey Vanaelstyn said that AP tests happen earlier than the end of the year testing, so that time is made up in the school breaks, which is why a break is not listed during vacation week for AP classes. Ms. Hugo asked if the students researched the types of homework that seemed to be most beneficial vs. homework that just seemed like busy work; and if they had researched flipped classrooms where students listen to the lesson at home and do a project or discussion in class. Esther Kalemba said she had talked to a teacher about flipped classrooms, and it seems like it wouldn't work for all teachers. She added that it seems like it would mostly work for math classes, but for English and history it would be harder for students to do at home, and harder for teachers to create a lecture. Anne Culhane-Williams said flipped classrooms would possibly take away from in-class learning - being able to learn and ask clarifying questions, and she thinks it would vary between students if it would be beneficial or not. Hailey Vanaelstyn said a lot of students' complaints were that teachers were assigning busy work to just give homework. Ava Caiola said it was a point of contention with teachers, as teachers argue that they can think everything they assign is important and beneficial, and pushed back on how the students define what's meaningful. Mr. Epstein said part of this touches on learning style, and asked how many students contributed feedback when they were gathering it. Anna Culhane-Williams said they asked friends, along with the members of the Commission, but it was not sent out as a survey. Mr. Epstein asked if students find that teachers coordinate homework assignments, and suggested that teachers look to spread out the homework and coordinate, so not everyone is assigning a lot on a certain night. Mira Donaldson said teachers within the same department sometimes coordinate, but the classes are not always at the same place in the curriculum. Ava Caiola said if all teachers used the same program, such as Google Classroom or Canvas, they could see what other teachers assigned, but teachers all use different programs and there is no coordination; students can have multiple tests on the same day. Mr. Epstein asked if students felt that homework was graded in a timely fashion. Hailey Vanaelstyn said that it varies widely depending on the teacher, and that it seems that teachers may not be able to keep up with grading the amount of homework that they are assigning. Mr. Epstein asked that the administration look into an information management system, so teachers can see who has homework assigned etc., as well as keep track of when it is graded. Ava Caiola said within this proposed policy, they added that teachers try to give a weeklong look at homework, so students are able to plan ahead.

#### Update on BLOCKS Capital Project

Director of Building and Grounds Matt Torti gave an update on the Blocks Capital Project. He said that the library, which is now closed, was being used as breakout learning spaces for special programs and multiple functions, and these programs are now displaced. He said that in January there was a roof leak, and once opened up there was some structural damage and the insurance company would not pay for any remedial work. He said they have enlisted the services of an architect to do a preliminary design, provide cost estimates, and that the project still needs to go out to bid. He said that this is past the date of the Capital Project Request, so this has been deemed as an emergency capital budget request. He said that the Chair has sent a letter to the Mayor asking for additional funding, but they are currently paying for the architect out of the operating budget to make sure the project is started as soon as possible. He said they are presenting on this to the City Council on June 12th, and the full vote is on June

18th. Mr. Lynch said, originally they were thinking to swap out this project with the Potter Road project, but that is no longer the case. He said that they are keeping the initial request and adding this project on top of the Capital Budget Request, which increases the request from \$3,295,277 to \$3,785,277. Mr. Freudberg said this does not need a vote from the School Committee since it is an off-cycle appropriation, and the City Council voted last night to refer it to the City Council's Finance Subcommittee. He said it is a 2,500 square foot room that cannot be currently used. Mayor Spicer asked if there are plans to add anything besides the original footprint. Mr. Torti said the cost estimate is to just refurbish and put the area back to the former use. He said that due to it being an added modular unit, they were able to completely isolate it from the rest of the school and no-one is allowed in there, as it is currently an unsafe situation. Mayor Spicer suggested there be a complete assessment of all the buildings done in order to determine if any more of the buildings are currently in jeopardy, and going forward, to prioritize project order based on building conditions. Mr. Torti said the only other modules are at the Hemenway and Brophy Schools. He said that they do periodic inspections, annually have the City's Building Department perform inspections, and get occupancy permits. He said that this roof was different than the other modular units.

\*Ms. Pascual left the meeting for a short break.

#### Approval of Proprietary Specification for the Fuller Building as Required by the MA School Building Authority

The Chair said that the School Building Committee voted to approve the proprietary specifications for the Fuller Building Project this past Monday night, and a step required by the Massachusetts School Building Authority is for another elected board, in this case the School Committee, to concur with the vote.

**Motion:** To affirm the vote of the School Building Committee to accept the approval of proprietary specifications for the Fuller Building Project.

**Moved:** Ms. Bryant                      **Seconded:** Mr. Alexander                      **Vote:** Unanimous (7-0-0)

(Yes: Hugo, Finlay, Freudberg, Alexander, Epstein, Maskell, Bryant. Ms. Pascual had stepped out of the meeting momentarily at the time of the vote.)

Mr. Torti said that the Design Day for the **McCarthy Playground** is tomorrow, hosted by Kaboom who gave the grant, and will involve the PTO, volunteers, parents, and children and they can help with the design. He said that TJX Sierra Trading Post is a main donator, and are providing 120 volunteers on build day. Mr. Freudberg asked about keeping the tires that are in the current playground, and asked for scheduling between the build day and construction on the Fuller Project. Mr. Torti said they will be planning in conjunction with the Fuller Project, due to parking. He said that they cannot put in new tires because of code issues; but they are going to try and leave the current tires in place. He said that most of the existing playground will be removed to make way for new equipment, and the total value is probably upwards of \$120,000.

#### Progress Report on Superintendent's Goals

Mr. Freudberg reminded members that the Evaluation of the Superintendent is due June 11, 2019. Dr. Tremblay presented an orientation on the evaluation and went over his progress report on his goals, and said that in the Team Drive there are items of evidence, which is also embedded within his progress report. He said that last year members gave feedback on him

being more involved in the instructional practices, and he believes that he has been fully invested in that this year, including the visits to the schools every morning, meeting with senior team and principals. He asked that if members had any questions on any of the indicators, or want to see any other evidence, to let him know. He said that this upcoming year is going in to the third and last year of the current Strategic Plan, and they will be starting to work on the next Strategic Plan in August. He also spoke about the progress that has been made within the District: The dual language programming will be expanded to four elementary schools beginning next year and they already have a wait list; they created a Bilingual Parent Advisory Council; senior advisors have been going to events in the community to engage with families and constituents in a program they call “Be Heard Tours” - to talk to them about their needs in school; they have expanded the King School autism strand; and by moving away from ACCEPT for transportation, the District saved \$800,000 in next year’s budget; and many other accomplishments.

**Questions.** Mr. Finlay asked if there were any grants available to start implementing free Pre-K programs, such as they used when the District implemented free universal Kindergarten. Dr. Tremblay said part of the current research is to find out how Pre-K - K programs are being funded, as well as the availability of money and a location. He said that this can be worked on with the Strategic Initiatives and Financial Oversight Committee. Mr. Finlay said that there was \$75,000 earmarked for a feasibility study for Hemenway, and he would like to see this be done. Dr. Tremblay said they have already done this, and the Request for Qualifications (RFQ) for the Feasibility Study and will be looking to see other possible viable options in the City. Mr. Epstein asked if Barbieri’s small cafeteria, that has five lunch sessions, will be looked into. Mr. Lynch said this will be looked at next year. Mr. Epstein asked about the role of online and remote instruction in the high school, and suggested offering this to students who are advanced and want more material, or for the lower-enrolled classes that sometimes get cut. Dr. Tremblay said that they have online credit recovery, and many teachers use a hybrid approach with online elements. Dr. Tremblay said they have looked at Virtual University, but would need to look at the space to do this which would come into play in the next phase of the High School Space Study. Ms. Bryant said time in actual classes also help students learn socialization, how to ask for help, and how to interact with authority figures - so we would need to balance any online classes, and use them to augment the students’ experiences. Mr. Alexander asked about the use of technology such as using blizzard bags when there are snow days. Dr. Tremblay said that currently DESE has put a halt on approving any more districts using blizzard bags, in order to take a look at the districts that are currently implementing it, to see if they actually are meeting the requirements of the 180 school days. Dr. Tremblay said they are piloting a 1:1 with chromebooks in some of the schools, and will see what kind of problems they encounter, such as internet accessibility at home. Ms. Hugo said she did not see any S.M.A.R.T. goals in the Strategic Plan. Dr. Tremblay said that the Strategic Plan is the framework, and the School Improvement Plans improve upon it, and they show the percentages and S.M.A.R.T. goals, as they are different for each school. Ms. Hugo said she only saw one mention of advanced learners, and nothing about SAGE. Dr. Tremblay said the plan for these are within the budget documents, and he will also do a presentation at the next meeting with the SAGE Department Head Judy LeBlanc about the forward movement of SAGE and investments in it. He said part of the discussion at the schools with the principals is how they are differentiating between English Language Learners, gifted students and special needs students. He said that they have more work to do for gifted kids, but first they are looking to make sure they are providing for ELL and

special needs students. Mr. Alexander asked about the lottery system and what the plans are for the goal going forward. Dr. Tremblay said he is continuing to try and fix school choice every year, it is very difficult to fix and the majority of students are largely in one part of the community, while the majority of the schools are on the other side. He said there are only so many seats available in each school, and the District looks to make sure there is a good representation of our kids across all the schools; they look to spread ELL and special needs students throughout to be balanced, and there has been an increase of ELL students. He said that they were able to accommodate 91% or so, for first choices and are constantly looking to see how to make it better. He added that they are looking at this within the Equity, Diversity and Community Development Office, in conjunction with the Parent Information Center. He said he is not sure it will be fixed without considering another school, possibly on the South Side. Mr. Alexander asked if parents are getting a basic overview on how it works, when they come to place their student in the lottery, as he is getting the sense that they don't know exactly what the process is. Dr. Tremblay said they talk about it at Kindergarten Orientation Night, and provide the information in multiple languages. He said that he is striving to make every single one of the nine elementary schools desirable, then it will not matter what choice you get.

\*Ms. Maskell left the meeting at 9:15 p.m

\*Mr. Finlay stepped out of the meeting from 9:15-9:18 p.m.

#### Superintendent's Update

Mr. Lynch said that at the meeting on June 19th, he will be giving a full narrative with recommendations for any end-of-year transfers for **FY19**. He said that there is just under 80% expended, and salaries are not encumbered. He added that he will have a projected end budget for June 30th. He said that the food service negative balance will be covered by the operating budget before June 30th.

Mr. Lynch said that last night was the first reading by the City Council on the **FY20 Budget**, the second reading will be on June 18th. He said that the current District proposed budget is the 4.11% the School Committee voted on.

Ms. Bryant asked if there is currently a soft freeze. Mr. Lynch said that there was, but they are still spending money - departments and schools just have to submit what they want to expend, with information on amount and what for, to get approved; and salaries still need to be taken out.

Dr. Tremblay said that the District participates in two educational collaboratives, he is the voting member for ACCEPT and the law requires a formal vote for him to continue in that capacity.

**Motion:** To appoint Dr. Tremblay as the School Committee's representative to the ACCEPT Board of Directors for the 2019-2020 fiscal year.

**Moved:** Ms. Bryant

**Seconded:** Ms. Hugo.

**Vote:** Unanimous (7-0-0)

#### Subcommittee Reports

##### **Policy**

**Motion:** To approve Policy JJF: Student Activity Accounts for a first reading.

**Moved:** Ms. Hugo

**Seconded:** Mr. Alexander

**Discussion:** Mr. Epstein asked for a friendly amendment within this proposed policy, as it is not clear if there are other accounts besides the agency account and the checking account, and he

thinks the structure should be explained - the hierarchy of accounts should be part of the definitions. All in agreement. Mr. Epstein will work with Mr. Lynch on adding this information.

**Vote:** Unanimous (7-0-0)

**Finance and Operations.** Mr. Epstein said that two warrants were signed. He said that the Finance Subcommittee met and the auditor will be making one amendment to the audit report in order to follow the DESE requirements. He said that then, from the subcommittee's view, the audit will look complete, acceptable, and satisfy the requirements. He said that the audits for FY19 are going to be different: Next year the School Committee will hire their own auditor as opposed to being part of the City's audit, and will be in charge of how it is done, what they should be looking for, what level should be considered acceptable, and the timeframe. Mr. Lynch said that he will look into material donations that were brought up in the subcommittee meeting, and will report on these to the subcommittee as it comes in.

#### Approval of Grants/Gifts/Field Trips

**Motion:** To approve the Open Session Minutes of April 24, 2019 with the suggested minor amendments.

**Moved:** Ms. Bryant

**Seconded:** Mr. Finlay

**Vote:** 6-0-1

(Yes: Hugo, Finlay, Freudberg, Alexander, Epstein, Bryant. Abstained: Pascual)

#### Adjournment

**Motion:** To adjourn.

**Moved:** Mr. Epstein

**Seconded:** Mr. Finlay

**Vote:** Unanimous (7-0-0)

Meeting adjourned at 9:32 p.m.

#### Meeting Materials

Agenda

Student Advisory Committee Presentation

Action Civics Commission Presentation on Homework Policy

BLOCKS Estimate Report

Proprietary Specification Vote for Fuller Project

Progress Report on Superintendent's Goals

FY19 Year to Date Budget

Food Services Negative Balance report

Memo on ACCEPT Collaborative Representative

Policy Summary

Policy JJF: Student Activity Account Audits

Warrants

April 24, 2019 Open Session Draft Minutes

*These minutes were approved at the School Committee Open Session held on July 17, 2019.*

*These minutes were sent to the City of Framingham for posting on July 18, 2019.*



### 3.1.5 Color Theory Statement

The material and the range of color selection choices have been reviewed by the Framingham Fuller School Building Committee and confirmed during their meeting on 7/1/19. However, by agreement with the committee, finalization of color values within those materials will be concluded during construction when availability of manufacturer's options can be confirmed prior to submittal approval. Any future color and/or material selections will not affect the materials and colors included in the cost estimates.

#### *Exterior:*

Color at the exterior of the new Fuller Middle School is conceived with a priority on responding to the existing context of surrounding school buildings including the adjacent Farley and McCarthy buildings. Civic or institutional buildings in Framingham tend to be constructed of brick. However the Fuller/Farley/McCarthy campus is sited in the midst of a residential neighborhood. Therefore the materials and color palette for new building will be mixed with accents of artificial or 'phenolic' wood trim. The primary color will be established by the brick which has been selected on a preliminary basis in a brown/ochre to reddish range relating to the directly abutting Farley school. Mortar color will be selected to minimize contrast with the brick but without an overt color of its own.

To complement the brick, trim around the bay window projections and interspersed field accent panels have been depicted, again, on a preliminary basis, in a light to medium wood tone. The combination of reddish brown brick and wood tone reflects similar combinations of masonry and wood found in the immediate context of residences. Metal window trim will be finished with metallic paint in a similar range




of color, perhaps, as was shown on a preliminary basis, in a copper color.

**Interior:**

The color palette on the interior is set primarily by the criteria of maximizing the collection and distribution of natural light to create a bright, uplifting atmosphere throughout all spaces. Therefore the floor will be a light grey for reflectivity. Bumper rails and parapet cap trim consisting of a natural light grey bamboo finish or cohort color coded painted MDO will provide a feature horizontal accent running through all public circulation and program areas.

To provide some variation and identification of grade cohorts, lockers will be assigned colors relating to the three grade cohorts – on a preliminary basis in chartreuse, yellow, light blue and red.

Complementing the flooring material at each program space, upper wall surfaces out of student reach and painted soffits will have matching but lighter toned color. Upper exposed metal deck ceilings and light shelves will be bright white for maximum reflectivity. The auditorium and gymnasium spaces and adjacent corridors will be surfaced with low maintenance ground face CMU or CMU tile in grey concrete with primarily white aggregate – again to allow for maximum reflectivity. The auditorium will also be accented by suspended plywood acoustic reflector clouds



Flooring finishes presented at School Buildign Committee meeting 7/1/19.




Finishes presented at School Buildign Committee meeting 7/1/19.


Options for accent paint colors for the bumper rails in the Classrooms and Corridors were presented, and selections approved, at the 10/7/19 SBC meeting:

- Option A series approved for Corridors
- Option B series approved for Classrooms


Option A selected for  
Corridor bumper rails



Option B selected for  
Classroom bumper rails



Option C not selected





### 3.1.6 Independent Structure Review

Please reference the attached documentation prepared by the Independent Structural Reviewer, LeMessurier.

- Structural Peer Review letter
- Independent Structural Review Comments and Responses



September 30, 2019

Mr. Joel G. Seeley  
Symmes Maini & McKee Associates, Inc.  
1000 Massachusetts Avenue  
Cambridge, Massachusetts 02138

Reference: New Fuller Middle School - Structural Peer Review  
Framingham, Massachusetts  
LeM File No. 19.0153


Dear Joel:


As requested, LeMessurier completed our independent structural engineering review for the referenced project in accordance with 780 CMR Section 105.9 of the Massachusetts State Building Code (Ninth Edition).

We reviewed the Construction Document structural package dated September 9, 2019 and titled 90% Construction Document Pricing Set and prepared by the structural engineer of record, RSE Associates of Watertown, Massachusetts.

We determined that the design of the building structure appears conceptually correct, and we did not discover any major errors in the design. LeMessurier concluded that the design is appropriate to conform to the prescriptive criteria of the Ninth Edition of the Massachusetts State Building Code with Amendments and with reference to the 2015 International Building Code.

Very truly yours,  
LeMessurier Consultants Inc.

  
William D. Lovallo, P.E.  
Vice President



S:\2019\19.0153\06-wd\Fuller Middle School LeM peer review letter 2019-0930.docx

**LeMessurier.**

1380 SOLDIERS FIELD ROAD BOSTON, MA 02135 TEL 617.868.1200 WWW.LEMESSURIER.COM

**Fuller**  
Construction Documents 90%  
Fuller Middle School, Framingham, Massachusetts





# LeMessurier.

Fuller Middle School - Framingham  
19.0153

## Structural Peer Review Comments

Number	Drawing	LeM Comment (2019-08-02)	Response
1	General	ground improvement does not appear to be defined on foundation plans, information required for bidders will include column footing loads, wall loads, and slab loads for proper design of system and bidding	RSE: Loading information has been provided on drawing S101L
2	General	details for brick relieve showing extent, elevations, connections, etc. are lacking other than typical not and section which generally leads to bidder confusion, coordination challenges, and change orders	RSE: Elevation sheets of relieving angle extent has since been provided
3	General	slab diaphragm reinforcement does not appear in set	RSE: additional reinforcement beyond what has been provided is not deemed necessary
4	General	significant architectural stairs lacking structural information – leaving these stairs up to delegated design may lead to serviceably problems, missing scope, or solutions not consisting with architectural design intent	RSE: Stair 4 stringers are by structural steel and sizes are now shown on structural drawings
5	General	no slab edge bent plate information provided – example is interior atrium slab edge on architectural drawings shows structural steel slab edge	RSE: atrium slab edge details have since been provided.
6	General	footing elevations not clearly defined on plans	RSE: all bottoms of footing elevations have since been provided
7	General	hanger details in atrium do not appear in set	RSE: Details are still in development
8	S101C	grade beam reinforcement does not appear in set	RSE: information has since been provided
9	S101D	reinforcement for footing under breakout space does not appear in set	RSE: information has since been provided

# LeMessurier.

Fuller Middle School - Framingham  
19.0153

## Structural Peer Review Comments

Number	Drawing	LeM Comment (2019-08-02)	Response
10	S102A	symbol shows 5.5 on arrow but no description of system is provided	RSE: The legend has since been updated to reflect this comment
11	S102C	breakout space structure noted as designed by others however no structural loading, load, path, configuration, connection details to base building structure, minimum ratings, etc. provided for delegated design	RSE: information has since been provided
12	S103A	structure for chimney does not appear in set	RSE: Details are still in development
13	S103C	how will bottom/top of stair be detailed to accommodate anticipated roof deflection from snow that is translated down to stair landing at level 3	RSE: See response to #20
14	S103C S103D	RTU support on 1½" steel roof deck may require supplemental steel support between roof purlins	RSE: Steel dunnage and concrete roof curbs have since been provided under mechanical units
15	S103D	RTU 5 and 6 labeled as 48,000 pounds – distribution of this load onto joists is not clear – platform is noted but not shown	RSE: Loads have since been clearly communicated for joist design
16	S103D	roof joists appear to be missing uplift bridging at first bottom panel point	RSE: uplift bridging lines have since been shown to reflect this comment
17	S103D	sloping roofs over gymnasium and auditorium not described in set including tops of sloping masonry walls and associated details	RSE: sloping roof bottoms of deck geometry has since been defined
18	S103D	joist loading diagrams do not appear in drawing set	RSE: joist loading diagrams have since been fully developed

# LeMessurier.

Fuller Middle School - Framingham  
19.0153

## Structural Peer Review Comments

Number	Drawing	LeM Comment (2019-08-02)	Response
19	S104C	detail connections not shown for small beams framing into large flange sections at significant skewed angles – beams likely fail in shear requiring reinforcement or size change	RSE: beam sizes have been adjusted at severe skews to assure connections will not fail
20	S104B S104C	review of anticipated deflections of supporting girders over atrium with hung floor and superimposed roof loads should consider sequence of construction, camber on roof, and camber at hung floors, strain on hangers, and anticipated deflections at floors based on roof deflections	RSE: Deflection is within reasonable limits since the stair hangers are near the end of roof beam spans. Roof beam live load deflection criteria has also been tightened to 1.5" max at midspan (~L/600 for longest roof beam span). Hanger connections will have vertical adjustability to account for erection sequencing.
21	S104C	no details shown for support of large skylights on edge of roof framing	RSE: detail has since been included
22	S105B	lateral stability of stair roof may be lacking (same for elevator roof)	RSE: stair and elevator pop ups have since been moment framed
23	S202	bracing elevations do not include connection design forces	RSE: braced frame forces have since been included
24	S500	section 4 does not include weld sizes for coped beam reinforcement	RSE: weld sizes have since been included
25	S303 S400	base plate details do not appear to be coordinated with perimeter foundation sections	RSE: base plate designs have since been finalized and coordinated with the perimeter geometry
26	General	loading conditions for roof does not define ponding – confirm ponding depth is considered for secondary drainage system and/or overflow	RSE: the secondary roof drain scuppers are less than 7" above roof level and therefore roof ponding doesn't govern over snow loading.



### 3.1.7 Quality Control Documents

JLA's primary approach to Quality Control/Quality Assurance is the full team's integration of Building Information Modeling (BIM). BIM documentation for the Fuller Middle School commenced with schematic design and is continually updated and maintained through the present submission.

The success of QA/QC during document production relies heavily on the adoption, full and complete documentation and coordination of all information through BIM by all primary disciplines including architectural, structural, HVAC, plumbing, electrical and fire protection. JLA, together with structural engineer RSE Assoc., ME engineers Garcia, Galuska, DeSousa, and Plumbing & Fire Protection engineers AKAL Engineering share a BIM platform through the utilization of REVIT 2020. We have also since included A/V and Food Service BIM models.

Throughout the Construction Documents phase, the increasingly comprehensive REVIT model has been uploaded each week on Wednesday and shared between this core design team. Each week, the members of the individual discipline staffs review issues of conflict and coordination. We also utilize google documents for each discipline in order to record action items and progress.

In addition, the team's integrated design methodology is implemented through regular in-person sessions in the JLA studio with all primary and relevant secondary disciplines (such as acoustics). During these sessions coordination action items are identified, tasks assigned and resolution paths are scheduled.

Some highlights on each topic are below:

#### *Ceiling Heights*

BIM model shows all duct and piping sizes for coordination purposes.

#### *Mechanical Room and Shaft Sizes*

BIM model shows all duct and piping sizes for coordination purposes.

#### *Coordinate Specifications and Drawings*

JLA provides marked up specifications to our spec writer for incorporation into the project manual.

#### *Filed Sub-Bid Work*

Spec writer provides a public bid check document to OPM & JLA. This provides key information for spec writer to incorporate into the entire project manual.

#### *Scheduling*

The OPM, CM, and Architect meet and agree on scheduling items on a weekly basis.

### ***Equipment and Power***

We have had various meetings with the users of the current and proposed fuller middle school. This is so we can understand their equipment needs in order to include provisions in the construction documents.

### ***Existing and New Construction***

The benefit of having a Construction Manager perform pre-construction services for the client aid in the development of coordination items related to the old fuller middle school which will be demolished after the proposed fuller middle school is completed.

### ***Phasing***

The benefit of having a Construction Manager perform pre-construction services for the client aid in the development of phasing.

In addition, two complete progress check sets of both drawings and specifications were produced for redline review and mark up by Associate Principal Mark Warner and Principal in Charge, Architect of Record, Jonathan Levi. Remaining 90% CD appropriate coordination issues were then distributed to the team and picked up prior to final 90% CD submission.

Finally, the 90% pricing set was reviewed by both the OPM and commissioning agent, with detailed comments tracked.

### 3.1.8 Security and Visual Access Requirements

#### *City Representatives Consulted:*

The design team has met with representatives of the Framingham Police Department and Framingham Fire department on 2/6/18, 4/5/18, 7/30/18, 3/11/19, 4/8/19, 6/28/19, 7/29/19 and 10/8/19 to consult on the planning process for both site and building design issues. The Director of Safety and Security for the Framingham Public School District participated as well in the meetings held during the Design Development and CD phases. Their input has been included in the project. Included in these meetings were discussions of:

- Main entrance design
- Emergency Medical Procedures
- Ballistic glazing treatments
- Classroom hardware (thumb turn lock function from interior, key lock function from exterior)
- Classroom Visibility – manual shades at interior and exterior windows
- Alternative entry locations, knox boxes
- Emergency vehicle access around entire building
- CCTV camera surveillance
- Site Phasing Plans
- Construction Traffic

#### *General Description:*

The floor plan of the new school has been organized to allow for a prudent balance between the need for school security and the need for a warm and welcoming environment for the grades 6 through 8 population. The transparency and interconnectedness, which are desirable features of the educational program, also make for a favorable scheme for internal school security. The open floor plans provide a high degree of visual access from one portion of the school to another. This has been enhanced through the fine adjustment of classroom corridors to allow sightlines to connect the far corners of the school, including all 3 floors. All the classroom corridors include passive supervision from both teacher planning spaces and cohort commons.

The new building design locates the medical office adjacent to the main entry and central administration, which allows the emergency medical responders ideal access. This is a substantial improvement from the existing Fuller School design, which has the medical office remotely located from the entry. In the event of a medical emergency, the nurse calls 911, and both the Fire Department and EMS arrive at the school, are met by central administration personnel, and escorted to the medical area. The project includes all site and building signage required by Framingham's emergency procedures to identify locations where first responders may more directly reach a person needing medical attention. The elevator has been sized to accommodate a gurney, in the event that is required to move an injured person to the medical area.

A Knox Box is provided at both the main entry and the community entry, with an annunciator panel and graphic map located in each of the associated vestibules. Per discussions with the Framingham Police and Fire Departments, building plans will be delivered to each of these departments as part of the building permit process. FPD and FFD have indicated that it is anticipated that the "Command Center" in an emergency would be outside of the building, so no special location has been so designated inside the building itself.

Regarding security for the school from the visitors' perspective, the middle school central administration has been located adjacent to the main entrance of the school at the second floor level. Broad expanses of glass will allow observation of approaching visitors from the main school reception desk to the entrance approach and to the vestibule. The main entrance approach is configured with an outer covered area and an inner vestibule. The progress of an intruder can therefore be impeded at either line of doors. It is intended that the vestibule will be attended by administrative personnel facing into the vestibule from the central administration area. The administration area is safeguarded behind a glass wall partition with a locking door.

Upon arriving, visitors will follow the following procedure:

1. Visitors will ring the bell located at the exterior door:
2. Through the voice intercom system, visitors will be asked to identify themselves and if they have an appointment in the building.
3. Once this information is received and verified for accuracy, visitors will be let into the vestibule.
4. Visitors will need to present driver's license which must be queried through the school's background check system.
5. After passing clearance, visitors will be issued a visitor badge.
6. Visitors who do not gain clearance, may be asked to leave the building immediately.
7. Anyone given a visitor badge cannot be left unattended in the building and will have staff accompany them to the designated location.
8. No visitor can ever be left unattended.

In the instance of an intruder who has successfully passed through the outer security measures of the school an intruder alarm system can be triggered. Additionally, all classrooms will be provided with roll down shades at windows facing the corridor, so that an intruder could not look directly into classrooms.

It should be noted that the intruder alarm strategy will not interfere with life safety issues during a fire alarm.

In order to allow for community access, the school is also compartmentalized for usage modes in addition to that uses during school hours. Access will be allowed through the west entrance



vestibule to allow the community to utilize the auditorium and athletic facilities, and the ground floor locker rooms. This vestibule will be outfitted with security cameras and electronic door locking hardware, which may be accessed and operated remotely by building security. Sliding metal fabric partitions will prevent access to the main school space.



## 3.2 Space Summary

### 3.2.1 Space Summary

Please reference the attached updated CD-90% Space Summary.



Proposed Space Summary - Middle Schools

Change from MSBA Template over 5%  
 Change from 8/9/19 60% CD Submission over 5%

FULLER Middle School 630 Students Grades 6-8			
ROOM TYPE	Existing Conditions		
	ROOM NFA <sup>1</sup>	# OF RMS	area totals
<b>CORE ACADEMIC SPACES</b>			<b>31,685</b>
<i>(List classrooms of different sizes separately)</i>			
Classroom - General	775	20	15,500
ELL Classrooms	675	9	6,075
Teacher Planning	0	0	0
Classroom Breakout	0	0	0
Small Group Seminar (20-30 seats) / Resource	0	0	0
Science Classroom / Lab	915	10	9,150
Prep Room	240	4	960
Science Teacher Planning	0	0	0
<b>SPECIAL EDUCATION</b>			<b>10,875</b>
<i>(List classrooms of different sizes separately)</i>			
Self-Contained SPED	930	5	4,650
SPED Teacher Planning	0	0	0
SPED Classroom Breakout	620	7	4,340
Self-Contained SPED Toilet	0	0	0
Resource Room	935	1	935
Small Group Room / Reading	0	0	0
SPED Office w/Storage	190	5	950
<b>ART &amp; MUSIC</b>			<b>5,620</b>
Art Classroom	600	2	1,200
Art Workroom w/ Storage & kiln	0	0	0
Band / Chorus - 100 seats	2,120	2	4,240
Music Practice / Ensemble	60	3	180
<b>VOCATIONS &amp; TECHNOLOGY</b>			<b>3,350</b>
Tech Clm. - (E.G. Drafting, Business)	1,660	1	1,660
Tech Shop - (E.G. Consumer, Wood)	1,690	1	1,690
Fab Lab	0	0	0
<b>HEALTH &amp; PHYSICAL EDUCATION</b>			<b>24,265</b>
Gymnasium	9,680	1	9,680
Gym Storeroom	200	2	520
Health Instructor's Office w/ Shower & Toilet	685	3	2,055
Locker Rooms - Boys / Girls w/ Toilets	3,500	2	7,000
Unisex Toilet / Shower	140	1	140
Fitness Center	4,870	1	4,870
<b>MEDIA CENTER</b>			<b>3,720</b>
Media Center / Reading Room	3,720	1	3,720
Cohort Commons	0	0	0
<b>DINING &amp; FOOD SERVICE</b>			<b>13,740</b>
Cafetorium / Dining	8,570	1	8,570
Stage	0	0	0
Chair / Table / Equipment Storage	440	1	440
Kitchen	3,485	1	3,485
Staff Lunch Room	1,245	1	1,245
<b>MEDICAL</b>			<b>1,560</b>
Medical Suite Toilet	50	3	150
Nurses' Office / Waiting Room	930	1	930
Examination Room / Resting	160	3	480
<b>ADMINISTRATION &amp; GUIDANCE</b>			<b>4,600</b>
General Office / Waiting Room / Toilet	1,540	1	1,540
Teachers' Mail and Time Room	100	1	100
Duplicating Room	130	1	130
Records Room	90	1	90
Principal's Office w/ Conference Area	560	1	560
Principal's Secretary / Waiting	80	1	80
Assistant Principal's Office - AP1	110	1	110
Assistant Principal's Office - AP2	0	0	0
Supervisory / Spare Office	170	1	170
Conference Room	310	1	310
Small Conference Room	0	0	0
Guidance Office (Student Support)	170	8	1,360
Guidance Waiting Room w/ Sto Closet	0	0	0
Guidance Storeroom	60	1	60
Teachers' Work Room			0

Schematic Design			Design Development 5/17/19			Design Development MSBA Comment Response 6/21/19			Construction Documents 60% 8/9/19			Construction Documents 90% 10/18/19		
ROOM NFA <sup>1</sup>	# OF RMS	area totals	ROOM NFA <sup>1</sup>	# OF RMS	area totals	ROOM NFA <sup>1</sup>	# OF RMS	area totals	ROOM NFA <sup>1</sup>	# OF RMS	area totals	ROOM NFA <sup>1</sup>	# OF RMS	area totals
		<b>36,000</b>			<b>35,600</b>			<b>35,600</b>			<b>35,530</b>			<b>35,530</b>
900	21	18,900	885	21	18,585	885	21	18,585	885	21	18,585	885	21	18,585
900	6	5,400	885	6	5,310	885	6	5,310	885	6	5,310	885	6	5,310
90	15	1,350	95	15	1,425	95	15	1,425	95	15	1,425	95	15	1,425
290	7	2,030	290	7	2,030	290	7	2,030	280	7	1,960	280	7	1,960
400	1	400	405	1	405	405	1	405	405	1	405	405	1	405
1,195	6	7,170	1,180	6	7,080	1,180	6	7,080	1,180	6	7,080	1,180	6	7,080
80	6	480	80	6	480	80	6	480	80	6	480	80	6	480
90	3	270	95	3	285	95	3	285	95	3	285	95	3	285
		<b>9,150</b>			<b>9,075</b>			<b>9,075</b>			<b>9,075</b>			<b>9,150</b>
900	6	5,400	885	6	5,310	885	6	5,310	885	6	5,310	900	6	5,400
90	3	270	95	3	285	95	3	285	95	3	285	90	3	270
300	2	600	300	2	600	300	2	600	300	2	600	300	2	600
95	3	285	95	3	285	95	3	285	95	3	285	95	3	285
520	3	1,560	520	3	1,560	520	3	1,560	520	3	1,560	520	3	1,560
345	3	1,035	345	3	1,035	345	3	1,035	345	3	1,035	345	3	1,035
0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
		<b>3,675</b>			<b>3,640</b>			<b>3,640</b>			<b>3,640</b>			<b>3,640</b>
1,185	1	1,185	1,175	1	1,175	1,175	1	1,175	1,175	1	1,175	1,175	1	1,175
150	1	150	80	2	160	80	2	160	80	2	160	80	2	160
970	2	1,940	950	2	1,900	950	2	1,900	950	2	1,900	950	2	1,900
200	2	400	135	3	405	135	3	405	135	3	405	135	3	405
		<b>3,170</b>			<b>3,185</b>			<b>3,185</b>			<b>3,150</b>			<b>3,150</b>
950	0	0	950	0	0	950	0	0	950	0	0	950	0	0
1,980	1	1,980	1,960	1	1,960	1,960	1	1,960	1,960	1	1,960	1,960	1	1,960
1,190	1	1,190	1,225	1	1,225	1,225	1	1,225	1,190	1	1,190	1,190	1	1,190
		<b>9,985</b>			<b>9,795</b>			<b>9,795</b>			<b>9,765</b>			<b>9,765</b>
8,300	1	8,300	8,265	1	8,265	8,265	1	8,265	8,265	1	8,265	8,265	1	8,265
300	1	300	315	1	315	315	1	315	315	1	315	315	1	315
150	2	300	150	2	300	150	2	300	150	2	300	150	2	300
500	2	1,000	415	2	830	415	2	830	400	2	800	400	2	800
85	1	85	85	1	85	85	1	85	85	1	85	85	1	85
		<b>6,280</b>			<b>6,250</b>			<b>6,250</b>			<b>6,250</b>			<b>6,085</b>
1,990	1	1,990	1,990	1	1,990	1,990	1	1,990	1,990	1	1,990	1,990	1	1,990
1,430	3	4,290	1,420	3	4,260	1,420	3	4,260	1,420	3	4,260	1,365	3	4,095
		<b>8,960</b>			<b>8,690</b>			<b>8,640</b>			<b>8,640</b>			<b>8,640</b>
4,725	1	4,725	4,725	1	4,725	4,725	1	4,725	4,725	1	4,725	4,725	1	4,725
1,590	1	1,590	1,510	1	1,510	1,510	1	1,510	1,510	1	1,510	1,510	1	1,510
430	1	430	270	1	270	420	1	420	420	1	420	420	1	420
1,915	1	1,915	1,820	1	1,820	1,820	1	1,820	1,820	1	1,820	1,820	1	1,820
300	1	300	365	1	365	365	1	365	365	1	365	365	1	365
		<b>610</b>			<b>620</b>			<b>620</b>			<b>620</b>			<b>610</b>
60	1	60	60	1	60	60	1	60	60	1	60	60	1	60
250	1	250	260	1	260	260	1	260	260	1	260	250	1	250
100	3	300	100	3	300	100	3	300	100	3	300	100	3	300
		<b>5,250</b>			<b>5,245</b>			<b>5,245</b>			<b>5,235</b>			<b>5,235</b>
425	1	425	445	1	445	445	1	445	445	1	445	445	1	445
95	1	95	100	1	100	100	1	100	100	1	100	100	1	100
200	1	200	200	1	200	200	1	200	200	1	200	200	1	200
200	1	200	210	1	210	210	1	210	210	1	210	210	1	210
375	1	375	480	1	480	480	1	480	470	1	470	470	1	470
125	1	125	130	1	130	130	1	130	130	1	130	130	1	130
150	1	150	150	1	150	150	1	150	150	1	150	150	1	150
150	0	0	150	0	0	150	0	0	150	0	0	150	0	0
150	1	150	145	1	145	145	1	145	145	1	145	145	1	145
350	1	350	365	1	365	365	1	365	365	1	365	365	1	365
210	1	210	205	1	205	205	1	205	205	1	205	205	1	205
150	6	900	150	6	900	150	6	900	150	6	900	150	6	900
75	3	225	75	3	225	75	3	225	75	3	225	75	3	225
15	3	45	15	3	45	15	3	45	15	3	45	15	3	45
300	3	900	200	3	600	200	3	600	200	3	600	200	3	600

MSBA Guidelines (refer to MSBA Educational Program & Space Standard Guidelines)			
ROOM NFA <sup>1</sup>	# OF RMS	area totals	Comments
		<b>29,580</b>	
950	22	20,900	850 SF min - 950 SF max, includes closet
			includes closet
			Shared between classrooms
			Shared between classrooms. Includes SPED use
500	2	1,000	Professional Development/ Itinerant / Workspace. Some uses served in Admin
1,200	6	7,200	Teachers Work Rooms*
80	6	480	
			Shared between classrooms
		<b>7,550</b>	
950	5	4,750	All match SD figures
			All match SD figures
			Shared between classrooms. SPED use also in Gen Classroom Breakout
60	5	300	For medically fragile students
500	3	1,500	Should be divisible
500	2	1,000	Allows division into 2 smaller spaces
		<b>3,250</b>	



Proposed Space Summary - Middle Schools

Change from MSBA Template over 5%  
 Change from 8/9/19 60% CD Submission over 5%

FULLER Middle School 630 Students Grades 6-8			
ROOM TYPE	Existing Conditions		
	ROOM NFA <sup>1</sup>	# OF RMS	area totals
Dept Head / Coach offices	90	1	90
Office / Conference Room			
<b>CUSTODIAL &amp; MAINTENANCE</b>			<b>3,515</b>
Custodian's Office	100	1	100
Custodian's Workshop	250	1	250
Custodian's Storage	105	9	945
Recycling Room / Trash	0	0	0
Receiving and General Supply	220	1	220
Storeroom	1,240	1	1,240
Network / Telecom Room	380	2	760
Outdoor Equipment Storage			
<b>OTHER</b>			<b>27,670</b>
Other (specify)			
Adult ESL Offices	2,370	1	2,370
City Offices, (PIC, Bldg & Grounds, BOH)	17,300	1	17,300
Auditorium	5,400	1	5,400
Stage	1,900	1	1,900
Auditorium Storage	160	1	160
Dressing Rooms	270	2	540
Total Building Net Floor Area (NFA)			<b>130,600</b>
Proposed Student Capacity / Enrollment			
<b>NON-PROGRAMMED SPACES</b>			
Other Occupied Rooms (list separately)			
Unoccupied MEP/FP Spaces			
Unoccupied Closets, Supply Rooms & Storage Rooms			
Toilet Rooms			
Circulation (corridors, stairs, ramps & elevators)			
Remaining <sup>3</sup>			
Total Building Gross Floor Area (GFA) <sup>2</sup>			195,900
Grossing factor (GFA/NFA)			1.50

Schematic Design			Design Development 5/17/19			Design Development MSBA Comment Response 6/21/19			Construction Documents 60% 8/9/19			Construction Documents 90% 10/18/19			
ROOM NFA <sup>1</sup>	# OF RMS	area totals	ROOM NFA <sup>1</sup>	# OF RMS	area totals	ROOM NFA <sup>1</sup>	# OF RMS	area totals	ROOM NFA <sup>1</sup>	# OF RMS	area totals	ROOM NFA <sup>1</sup>	# OF RMS	area totals	
150	6	900	150	6	900	150	6	900	150	6	900	150	6	900	
			145	1	145	145	1	145	145	1	145	145	1	145	
		<b>2,140</b>			<b>2,630</b>			<b>2,480</b>			<b>2,555</b>			<b>2,545</b>	
165	1	165	385	1	385	385	1	385	385	1	385	385	1	385	
250	1	250	250	1	250	250	1	250	250	1	250	250	1	250	
130	3	390	105	4	420	90	3	270	110	3	330	110	3	330	
400	1	400	395	1	395	395	1	395	395	1	395	395	1	395	
310	1	310	310	1	310	310	1	310	310	1	310	310	1	310	
145	3	435	120	3	360	120	3	360	125	3	375	125	3	375	
190	1	190	200	1	200	200	1	200	200	1	200	200	1	200	
			310	1	310	310	1	310	310	1	310	300	1	300	
		<b>6,700</b>			<b>6,755</b>			<b>6,755</b>			<b>6,630</b>			<b>6,705</b>	
0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
4,200	1	4,200	4,405	1	4,405	4,405	1	4,405	4,435	1	4,435	4,390	1	4,390	
1,600	1	1,600	1,590	1	1,590	1,590	1	1,590	1,555	1	1,555	1,530	1	1,530	
400	1	400	120	3	360	120	3	360	100	3	300	125	3	375	
250	2	500	200	2	400	200	2	400	170	2	340	205	2	410	
		<b>91,920</b>			<b>91,485</b>			<b>91,485</b>			<b>91,290</b>			<b>91,255</b>	
		<b>% of GFA 44,870</b>			<b>% of GFA 45,275</b>			<b>% of GFA 45,275</b>			<b>% of GFA 45,810</b>			<b>% of GFA 45,845</b>	
		0%			0%			0%			0%			0%	
		1%	1,685		1%	1,415		1%	1,415		1%	1,400		1%	1,410
		0%	235		0%	280		0%	280		0%	350		0%	350
		3%	3,560		2%	3,325		2%	3,325		2%	2,970		2%	2,980
		25%	34,175		19%	25,970		19%	25,970		19%	26,350		19%	26,195
		4%	5,215		10%	14,285		10%	14,285		11%	14,740		11%	14,910
		<b>136,790</b>			<b>136,760</b>			<b>136,760</b>			<b>137,100</b>			<b>137,100</b>	
		<b>1.49</b>			<b>1.49</b>			<b>1.49</b>			<b>1.50</b>			<b>1.50</b>	

Date: 10/18/2019 90% Construction Documents

MSBA Guidelines (refer to MSBA Educational Program & Space Standard Guidelines)			
ROOM NFA <sup>1</sup>	# OF RMS	area totals	Comments
			Distributed 2 per cohort
			Allows for shared collaboration space
		<b>2,105</b>	
150	1	150	includes custodial staff break area/ lockers, toilet area
250	1	250	
375	1	375	
400	1	400	
310	1	310	
420	1	420	alternates with Academic Storage
200	1	200	includes head end and IDF rooms
			outdoor equipment storage
		<b>0</b>	
			Larger auditorium storage closer to approved SD area
			Larger dressing rooms closer to approved SD area
		<b>74,250</b>	
		<b>630</b>	
			Non-Programmed space areas are
			Design Development Submittal
			60% Construction Documents
			90% Construction Documents
			Final Construction Documents
			includes wall thickness change at e/w side corridors from curtainwall to brick assembly and added circulation area for auditorium vestibule interior discharge
		<b>107,280</b>	
		<b>1.44</b>	

<sup>1</sup> Individual Room Net Floor Area (NFA) Includes the net square footage measured from the inside face of the perimeter walls and includes all specific spaces assigned to a particular program area including such spaces as non-communal toilets and storage rooms.

<sup>2</sup> Total Building Gross Floor Area (GFA) Includes the entire building gross square footage measured from the outside face of exterior walls

<sup>3</sup> Remaining Includes exterior walls, interior partitions, chases, and other areas not listed above. Do not calculate this area, it is assumed to equal the difference between the Total Building Gross Floor Area and area not accounted for above.

**Architect Certification**

I hereby certify that all of the information provided in this "Proposed Space Summary" is true, complete and accurate and, except as agreed to in writing by the Massachusetts School Building Authority, in accordance with the guidelines, rules, regulations and policies of the Massachusetts School Building Authority to the best of my knowledge and belief. A true statement, made under the penalties of perjury.

Name of Architect Firm: Jonathan Levi Architects

Name of Principal Architect: Jonathan Levi

Signature of Principal Architect: \_\_\_\_\_

Date: 10/15/2019





### 3.2.2 Space Summary - Education Program Comparison

The overall Fuller Middle School parti documented in Schematic Design has been carried forward with the pedagogical objectives described in the Education Plan unchanged. There have been a few refinements which are outlined below, mostly from minor adjustments resulting from building design efforts. Any changes over 5% of nsf floor area have been highlighted in orange in the attached Proposed Space Summary. Overall, the total educational NSF has gone down by 35 sf from 91,290 nsf to 91,255 nsf since the previous submission. The building is designed, with a grossing factor of 1.50. The overall gsf has gone up 310 sf from SD and is unchanged from the previous submission at 137,100 gsf. This change in gsf resulted primarily from a change from a curtainwall enclosure to a more cost effective storefront / brick system, which has thicker walls, and therefore expanded the exterior perimeter by a few inches around much of the building footprint.

#### *Core Academic Spaces*

Total NSF of 35,530 remains unchanged from the previous submission, and remains 470 nsf less than the SD submission.

#### *Special Education*

The Special Education room configuration and 9,150 NSF are as approved by the DESE September 27, 2018.

#### *Art and Music*

Total NSF of 3,640 sf remains unchanged from the previous submission, and remains 35 nsf less than the SD submission.

#### *Vocations and Technology*

Total NSF of 3,150 sf remains unchanged from the previous submission and remains 20 nsf less than the SD submission.

#### *Health and Physical Education*

Total NSF of 9,765 sf remains unchanged from the previous submission and remains 220 nsf less than the SD submission.

#### *Media Center*

Total NSF has gone down from SD by 195 sf due to adjustments to the cohort commons, which resulted in a reduction of 165 nsf from the previous submission.

#### *Dining and Food Service*

Total NSF of 8,840 sf remains unchanged from the previous submission, and remains 120 nsf less than the SD submission.

#### *Medical*

Total NSF of 610 sf has gone down from the previous submission by 10 sf, and is unchanged from the SD submission.

***Administration and Guidance***

Total NSF of 5,235 sf remains unchanged from the previous submission, and remains 15 nsf less than the SD submission.

***Custodial and Maintenance***

Total NSF of 610 sf has gone down from the previous submission by 10 sf due to a reduction in the outdoor equipment storage, and is 405 nsf more than the SD submission.

***Other***

Total NSF has increased by 75 nsf from the previous submission due to an increase in the size of the auditorium storage and the dressing rooms, which are now closer in size to the approved SD figures. The overall size of 6,705 nsf is 5 sf larger than SD.

### 3.3 Project Approvals

#### 3.3.1 Approval Status

Approval status is as follows

1. *DESE - Special Education approval by Department of Elementary and Secondary Education.*
  - APPROVED. Please see attached signed approval dated 9/27/18 also included in CD-60% submission.
2. *MHC - Project Notification Form and approvals by MA Historical Commission.*
  - APPROVED. Please see attached signed approval dated 1/2/18 also included in CD-60% submission.
3. *OIG - Construction Manager at Risk approval by the Office of Inspector General*
  - APPROVED. Please see signed approval dated 12/21/18 included in CD-60% submission.
4. *Executive Office of Energy and Environmental Affairs / EEA*
  - Not Applicable
5. *MA DEP - Massachusetts Department of Environmental Protection*
  - Remediation of contaminated soil is complete (both arsenic in peat and underground storage tanks). Final closure reports for UST to be filed in October 2019. RAM completion report in regard to arsenic in soil to be issued November 2019.
6. *MA DOT - Massachusetts Department of Transportation*
  - Not Applicable
7. *MA DPH - Massachusetts Department of Public Health*
  - Not Applicable
8. *EPA – NPDES National Pollutant Discharge Elimination System Notice of Intent approval by the US Environmental Protection Agency*
  - Please see application certified by CMR on 6/10/19 included in CD-60% submission.
9. *MAAB - Accessibility variances by MA Architectural Access Board*
  - Not Applicable. No accessibility variances are anticipated.
10. *Framingham Zoning Board of Appeals.*
  - Variance for height approved Please see signed approval dated 5/15/18 included in CD-60% submission.
11. *Framingham Planning Board.*
  - APPROVED. Please see documentation included in CD-60% submission.

**12. Framingham Conservation Commission.**

- APPROVED. Please see Order of Conditions dated 7/1/19 included in CD-60% submission.

**13. Framingham Building Department**

- Permit received to perform sitework and geotechnical ground improvements
- Stamped Building Permit application filed after approval of GMP for Structural Package, October 2019
- Supplemental Permit application to be filed after approval of GMP, January 2020
- 

**14. Framingham Fire Department.**

- Permit application to be filed after approval of GMP, January 2020

**15. Framingham Board of Health.**


- Permit application for kitchen to be filed after approval of GMP, January 2020
- RAM plan (see #5 above)

**16. Framingham Department of Public Works**

- Framingham DPW (includes water and sewer utilities) reviewed project as part of the successful Planning Board Approval. See flow test letter dated 11/2/18 and letter from Framingham DPW dated 4/30/19 included in CD-60% submission.

**17. Framingham Utilities**

- Please see correspondence with Eversource confirming adequate supply of Natural Gas and Electrical / Cable work orders included in section 3.3.3 Utility Certifications.



# Massachusetts Department of Elementary and Secondary Education

75 Pleasant Street, Malden, Massachusetts 02148-4906

Telephone: (781) 338-3000  
TTY: N.E.T. Relay 1-800-439-2370

Jeffrey C. Riley  
Commissioner

September 27, 2018

Mary Pichetti  
Director of Capital Planning  
Massachusetts School Building Authority  
40 Broad Street, Suite 500  
Boston, MA 02109

Dear Ms. Pichetti:

We have reviewed the space summary and accompanying documentation submitted by the Framingham Public Schools for a construction project at the Fuller Middle School. We have done so in accordance with M.G.L. chapter 70B, section 6(6), which instructs us to certify "...that adequate provisions have been made in the school project for children with disabilities, as defined in section 1 of chapter 71B...".

We are satisfied with the district's proposed floor plans and believe that their special education plan will provide the community with an opportunity to serve its special education students well. We accompany this approval with a suggestion that one pair of special education rooms on the second floor be relocated to the third floor in order to more equitably distribute that programming, though we submit that there may be good programmatic reasons to have all of those rooms on the second floor.

The Massachusetts Department of Elementary and Secondary Education therefore certifies that this school project has been planned to adequately provide appropriate space to serve the programs and school populations referenced in M.G.L. chapter 70B, section 6(6) noted above.

Sincerely,

A handwritten signature in black ink, appearing to read "Matthew J. Deninger".

Matthew J. Deninger  
DESE designee on the MSBA Board of Directors

Cc: Vani Rastogi-Kelly, Director, Public School Monitoring, ESE  
Amy Paulin, Supervisor, Public School Monitoring, ESE  
Katie DeCristofaro, Capital Program Manager, MSBA

Allison Jones, Project Coordinator, MSBA  
Fenton Bradley, Project Manager, MSBA



**The Commonwealth of Massachusetts**  
William Francis Galvin, Secretary of the Commonwealth  
Massachusetts Historical Commission

January 2, 2018

Phillip Gray  
266 Beacon Street  
Boston, MA 02116

RE: Fuller Middle School, 31 Flagg Drive, Framingham, MA; MHC# RC.63588

Dear Mr. Gray:

The Massachusetts Historical Commission (MHC) is in receipt of a Project Notification Form (PNF) for the project referenced above, received at this office on December 7, 2017. The staff of the MHC have reviewed the information submitted and have the following comments.

The proposed project consists of three options for the existing Kennedy Middle School at 31 Flagg Drive in Framingham. The options include either the renovation of the existing school building, partial demolition and construction of an addition, or full demolition of the existing school and construction of a new school on the site. The information provided indicates that the project will use funding from the Massachusetts School Building Authority

Review of MHC's files indicates that the Fuller Middle School is not included in MHC's Inventory of Historic and Archaeological Assets of the Commonwealth, nor listed in the National and State Registers of Historic Places. No further review by the MHC is required for the MSBA-funded project.

These comments are offered to assist in compliance with Massachusetts General Laws, Chapter 9, Sections 26-27C, as amended by Chapter 254 of the Acts of 1988 (950 CMR 71.00). Please do not hesitate to contact me if you have any questions.

Sincerely,

A handwritten signature in blue ink, appearing to read "Linda Santoro".

Linda Santoro  
Preservation Planner  
Massachusetts Historical Commission

xc: MSBA





### 3.3.2 Approval Letter

Attached is a letter of Approval from Framingham Public Schools.





**Framingham Public Schools**  
Robert A. Tremblay, Ed.D., Superintendent of Schools

73 Mount Wayte Avenue, Suite #5  
Framingham, Massachusetts 01702  
Telephone: 508-626-9118 Fax: 508-877-4240

---

August 9, 2019

Mr. Brian Lynch  
Project Coordinator  
Massachusetts School Building Authority  
40 Broad Street, Suite 500  
Boston, Massachusetts 02109


**Re: New Fuller Middle School** **Framingham, Massachusetts**  
*60% Construction Documents Submission to the MSBA*

---

Dear Brian,

In accordance with Article 4.12 of the executed Project Funding Agreement, dated March 1, 2019, this letter shall confirm that approval from the Massachusetts Historical Commission was received on January 2, 2018, approval from the Secretary of Environmental Affairs is not applicable as no ENF or EIR is required for the project, and approval from the Massachusetts Architectural Access Board is not applicable as no variances are being sought for the project.

Very truly yours,

  
Robert Tremblay, Ed.D  
Superintendent of Schools



### 3.3.3 Utility Certifications

Attached are Utility Certifications including loading of the following:

- Gas Load Letter - Eversource 10/8/19
- Electrical Load Letter - Eversource 10/10/19



Date: 10/8/2019

Eversource Energy  
 157 Cordaville Road  
 Southborough, MA 01772

Attn: Ms. Margie McDonald  
 Strategic Account Executive

Reference: Gas Load Letter for New Fuller Middle School, Framingham, MA.

Dear Margie,

As discussed earlier, please find updated gas load information of the above-referenced facility at 31 Flagg Dr., Framingham. The project is scheduled to go into construction by early next year. The project scope includes construction of a new school. The existing gas service at the existing school will remain be active until the new building is occupied.

Summary of gas load requirement of the facility is as below:

Gas Equipment	Gas Load (MBH)
(2) Boilers	(2) @ 4,000 = 8,000 MBH
(2) Domestic Water Heaters	(2) @ 400 = 800 MBH
Kitchen appliances	= 1,450 MBH
Science Room	= 30 MBH
Emergency Generator	=3,100 MBH
Sub Total	13,380 MBH

**Total Building Load: 10,280 CFH**  
**Outdoor generator gas load 3,100 CFH**

The gas pressure requirement for the building gas load is in the range of 7 -11" of W.C. and for a dedicated gas line to the emergency generator require 11" W.C.

The site utility plan is attached for the location of a new meter. Let me know if you need any additional information.

Regards



Anup S Khatra P.E  
 AKAL Engineering Inc.







**GARCIA • GALUSKA • DESOUSA**

Consulting Engineers Inc.

370 Faunce Comer Road, Dartmouth, MA 02747-1217

L#65302r  
J#680 015 00.00

February 13, 2019, *Revised May 3, 2019, Revised October 10, 2019*

Eversource  
247 Station Drive, SW 340  
Westwood, MA 02090

Attn: Bryan Rooney

RE: Fuller Middle School  
Flagg Drive  
Framingham MA

Dear Mr. Rooney,

The City of Framingham will be constructing a new Middle School consisting of 136,790 SF located on the same site adjacent to the existing Middle School. The existing Middle School at 31 Flagg Drive will remain occupied during the construction phase and will then be demolished once the new school is complete. Construction will be phased.

The new incoming primary service will run underground between an onsite utility pole and the new transformer pad. The transformer will be a padmount located in the vicinity as shown on the Site Plan. We are proposing one new service to feed the Middle School. The existing Middle School primary service, pad mounted transformer and secondary service will be removed at the end of the construction phase.

We anticipate secondary metering with the C/Ts located in the switchboard C/T section. The transformer will be supplied by the Utility Company.

Attached are copies of our proposed Electrical Site Plan, Site Details, and Power Riser Diagram. Please review and send back with your comments.

The job will be going out to bid in May 2019. Construction will start in June 2019. The Facility will be complete in July 2021.

In addition, we request that you send us the following information:

1. Available short circuit duty at the secondary of the transformer.
2. Anticipated transformer size and impedance.
3. Transformer pad installation requirements.
4. Primary line installation details and the work to be performed by the contractor.
5. Requirements for reduced voltage starting.
6. Metering rate schedule.
7. Metering requirements, including location and hot or cold sequence installation.
8. Anticipated back charges.

Our projected breakdown of loads are as follows:

A. HVAC:

HVAC Units			Electric Rating		KVA
RTU - 1		@	70 Tons	=	105.0
RTU - 2		@	70 Tons	=	105.0
RTU - 3		@	70 Tons	=	105.0
RTU - 4		@	70 Tons	=	105.0
RTU - 5		@	21 Tons	=	31.0
RTU - 6		@	40 Tons	=	60.0
RTU - 7		@	40 Tons	=	60.0
RTU - 8		@	14 Tons	=	21.0
			<b>RTU Sub-Total</b>	<b>=</b>	<b>592.5</b>
CH-1		@	175 Tons (258 amps)	=	214.4
CH-2		@	175 Tons (258 amps)	=	214.4
			<b>Chiller Sub-Total</b>	<b>=</b>	<b>428.8</b>
MAU-1		@	10 HP	=	12.0
P-1		@	25 HP	=	27.0
P-2 (standby)		@	25 HP	=	-0-
P-3		@	25 HP	=	27.0
P-4 (standby)		@	25 HP	=	-0-
SEF-1 & SEF-2	2	@	50 HP	=	104.0
SEF-3 & SEF-4	2	@	50 HP	=	104.0
UH's	43	@	1/5 HP	=	25.8
KEF-1		@	3 HP	=	3.3
KEF-2		@	2 HP	=	2.2
EF's	12	@	½ HP	=	10.8
EUH-1, 2 & 3	3	@	5 KW	=	15.0
Condensate Pumps	15	@	70 W	=	1.1
Stand alone DCU's	11	@	2 Tons	=	33.0
B-1, 2, 3	3	@	8 Amps	=	2.9
			<b>Misc. Sub-total</b>	<b>=</b>	<b>350.1</b>
			<b>HVAC Total</b>	<b>=</b>	<b>1,371.4</b>

L#65302r  
 J#680 015 00.00  
 Page 3

B. Plumbing/Fire Protection:

					KVA
Domestic Water Booster Pumps	2	@	5 HP	=	12.0
Water Coolers	5	@	¼ HP	=	2.5
Circulator Pumps	3	@	1/3 HP	=	2.7
			Sub-total	=	17.2 KVA

C. Elevator:

	1	@	40 HP	=	42.0
--	---	---	-------	---	------

D. Exterior Lighting:

					10.0
--	--	--	--	--	------

E. Interior Lighting:

	136,790 S.F @		1.0 W/S.F.	=	136.8 KVA
--	---------------	--	------------	---	-----------

F. General Power:

	136,790 S.F @		2.0 W/S.F.	=	273.6 KVA
--	---------------	--	------------	---	-----------

G. Kitchen Dishwasher/Booster Heater  
 Other Equipment

	20.0
	75.0
<b>Subtotal</b>	<b>= 95.0</b>

H. Theatrical Lighting

90.0

A.	=	1,371.4
B.	=	17.2
C.	=	42.0
D.	=	10.0
E.	=	136.8
F.	=	273.6
G.	=	95.0
H.	=	90.0
<b>Total</b>	<b>=</b>	<b>2,036.0</b>

2,036.0 kVA @ 277/480V, 3 phase, 4 wire

= 2,450.0 Amps

A standard 2,500 Ampere, 277/480V, 3 phase, and 4 wire service was selected. The main breaker will be 100% rated.

Secondary Service will consist of (6) sets of 4 #600 KCM copper in (6) 4" conduits plus (1) 4" spare.

We intend to participate in the incentive programs that you are offering. This facility will be a LEED School. Please provide a contact so that we may schedule a meeting.

We would like to schedule a site meeting with you at your earliest convenience to coordinate the incoming service. Please contact this office with your availability.

The facility will have an emergency stand-by 300 KW natural gas generator.

L#65302r  
J#680 015 00.00  
Page 4

The facility will have provisions for a roof mounted grid connected photovoltaic system.

Please contact our office should you require anything further regarding this matter.

Sincerely,

**GARCIA • GALUSKA • DESOUSA**  
Consulting Engineers Inc.

A handwritten signature in black ink, appearing to read "Jose M. Carreiro", with a long horizontal flourish extending to the right.

Jose M. Carreiro

JMC:jfm

Enc.

Cc: Philip Gray, Jonathan Levi Architects  
Carol Harris, Jonathan Levi Architects  
Carlos G. DeSousa, P.E., Garcia, Galuska & DeSousa, Inc.  
Mark Bibby, Garcia, Galuska & DeSousa, Inc.

## Appendices

- 1 Energy Calculations
- 2 Life Cycle Cost Analysis
- 3 Heat Gain and Loss Calculations HVAC
- 4 Draft Cost Estimates



## Appendix

### 1 Energy Calculations





## Appendix

### 2 Life Cycle Cost Analysis

- Water Use Reduction Life Cycle Analysis
- Mechanical System Lifecycle Engineering Economic Analysis



## Appendix

### 3 Heat Gain and Loss Calculations HVAC



## Appendix

### 4 Draft CostEstimate

- Draft Estimate Comparison
- CMR draft estimate
- Designer draft estimate
- OPM draft estimate and comparison analysis



## Appendices

- 1 Energy Calculations
- 2 Life Cycle Cost Analysis
- 3 Heat Gain and Loss Calculations HVAC
- 4 Draft Cost Estimates





## Appendix

### 1 Energy Calculations



**MSBA Design Development Submission  
LEED Energy Savings Analysis  
For  
Fuller Middle School**

**Framingham, MA**

**October 11, 2019  
(90% Construction Documents Update)**

Prepared for:



Prepared by:



**Garcia, Galuska & DeSousa**  
Consulting Engineers, Inc.



## **Fuller Middle School – 90% Construction Documents LEED Energy Savings Analysis**

### Section 1.0: Executive Summary

A mechanical lifecycle engineering economic analysis was performed to assess the performance of various mechanical systems in comparison to a baseline mechanical system to determine the most cost effective system for the project. The results of the report concluded that a variable air volume (VAV) mixed-air full air-conditioning displacement ventilation system was the most cost effective system studied with an instant payback and an approximate \$1,891,411 savings over the 30 year study period. The design system is as follows:

- Multiple low wall-mounted displacement diffusers at approximately 600-800 CFM (1 per classroom) each for each classroom and support area
- Multiple low wall-mounted displacement diffusers located throughout the administration, cafeteria, and media center areas
- Multiple low wall-mounted fully air-conditioned displacement diffusers located throughout the auditorium/stage and gymnasium areas
- Variable air volume boxes with demand ventilation control and temperature sensor to modulate airflow based on occupancy and space heating/cooling demand for each zone
- Dedicated overhead galvanized ventilation distribution system feeding each displacement diffuser
- Hot water radiant heating located along exterior walls
- Variable air volume hot water coil heating/chilled water coil cooling rooftop air handling units with demand control ventilation and static plate energy recovery providing fully air conditioned displacement ventilation to the terminal variable air volume boxes serving the administration, classroom, cafeteria, and media center areas
- Variable air volume hot water coil heating/chilled water coil cooling rooftop air handling units with static plate energy recovery and demand control ventilation providing mixed-air overhead distribution to the auditorium/stage, and gymnasium areas
- Variable air volume 100% outside air tempered hot water coil heating/chilled water coil cooling rooftop air handling units with static plate energy recovery and terminal variable air volume boxes serving the locker room areas
- Chilled water cooling/hot water coil rooftop make-up air handling unit and variable air volume exhaust air fan system serving the kitchen
- Limited use of hot water radiant heating and unit heaters
- (2) 4,000 MBH input high-efficiency gas-fired condensing boilers hot water heating plant
- 369.6 ton high-efficiency air-cooled chiller plant

- Four-pipe heating/cooling piping system serving air handling units
- Two-pipe hot water distribution system serving radiant heating panels and unit heaters
- Chilled and hot water primary pumping with variable frequency drives
- Direct digital controls throughout

To confirm that the design building meets the MSBA requirements of 16% energy cost savings for LEED V4 EAc1 – Optimize Energy Performance, updated energy model simulations have been performed comparing the design building in comparison to a baseline ASHRAE Standard 90.1-2010 building. The design building simulation has been updated to reflect the system capacities as indicated in the design development documents.

### Section 1.0: LEED Building Systems Description

1. The ASHRAE Standard 90.1-2010 baseline building is as follows:

- Envelope:
  - Wall: R-13 + R-7.5 c.i.
  - Roof: R-20 c.i.
  - Underslab: R-10 perimeter
  - Curtainwall: 0.45 U-Value, 0.40 SHGC
- Mechanical System:
  - Hot water coil heating/chilled water coil cooling VAV AHU systems with energy recovery wheels serving terminal VAV boxes with hot water reheat coils
  - (2) 82% efficient gas-fired hot water boilers
  - (2) 0.68 kW/ton high-efficiency water-cooled chillers with associated cooling tower
- Domestic Hot Water System:
  - 80% efficient gas-fired domestic hot water system
- Lighting System:
  - 0.99 w/s.f.

2. The design building is as follows:

- Envelope:
  - Walls: R-13 c.i.
  - Roof: R-36 c.i.
  - Underslab: R-10 perimeter
  - Curtainwall: 0.38 U-Value, 0.38 SHGC (N) / 0.29 SHGC (S,E,W)
- Mechanical System:
  - (As outlined above)
- Domestic Hot Water System:
  - 94% efficient gas-fired domestic hot water system
- Lighting System:
  - 0.50 w/s.f.

## Section 1.2: LEED Energy Savings Analysis Conclusion

A comparison of the Design Building against the ASHRAE Standard 90.1-2010 Baseline Building results in a projected energy cost savings of 34.6% exceeding the MSBA required 16% energy cost savings and resulting in 13 points for LEED V4 EAc2 – Optimize Energy Performance.

### Note:

The values indicated above are based on energy modelling performed for system comparison purposes only. Our office strongly recommends adding a 30% safety factor to the calculated values of this report for budgeting purposes to account for potential variances to the actual operation of the building. Per ASHRAE Standard 90.1-2010:

*Neither the proposed building performance nor the baseline building performance are predictions of actual energy consumption or costs for the proposed design after construction. Actual experience will differ from these calculations due to variations such as occupancy, building operation and maintenance, weather, energy use not covered by this procedure, changes in energy rates between design of the building and occupancy, and the precision of the calculation tool.*




**Fuller Middle School - LEED Energy Savings Summary  
(90% Construction Documents Update)**

Baseline	System	Annual Elec. Cons. (kWh)	Annual Gas Cons. (MBTU)	Annual Electric Cost	Annual Gas Cost	Combined Utility Cost	Annual Utility \$/s.f.	Annual kBTU/s.f. (EUI)	Combined Expense Savings*	Energy Cost Savings Percentage	LEED EAc2 Points
LEED Baseline	1. ASHRAE Standard 90.1-2010 Envelope (Wall Insulation R-13 + R-7.5 c.i., Roof Insulation R-20 c.i., Windows 0.55 U-Value/0.40 SHGC, Curtainwall 0.45 U-Value/0.40 SHGC) 2. ASHRAE Standard 90.1-2010 Mechanical Systems (System 7 - Packaged VAV w/ Reheat with 0.68 kW/ton Water-Cooled Chillers and 82% Eff. Hot Water Boilers) 3. ASHRAE Standard 90.1-2010 Lighting System (0.99 w/s.f.) 4. ASHRAE Standard 90.1-2010 Domestic Hot Water Systems (82% Eff. Hot Water Heaters)	1,075,200	3,340.5	\$197,738	\$24,710	\$222,448	\$1.48	46.73	-	-	-


Option	System	Annual Elec. Cons. (kWh)	Annual Gas Cons. (MBTU)	Annual Electric Cost	Annual Gas Cost	Combined Utility Cost	Annual Utility \$/s.f.	Annual kBTU/s.f. (EUI)	Combined Expense Savings*	Energy Cost Savings Percentage	LEED EAc2 Points
Design Building	1. Design Envelope (Wall Insulation R-12 c.i., Pre-Engineered Walls: R-22 c.i., Roof Insulation R-36 c.i., Windows 0.45 U-Value/0.39 SHGC, Curtainwall 0.38 U-Value/0.39 SHGC) 2. Design Mechanical Systems (VAV Full AC Displacement Ventilation Static Plate ERV Systems and 1.05 High-Efficiency kW/ton Air-Cooled Chillers and 94% High-Efficiency Condensing Boilers) 3. Design High-Efficiency Lighting System (0.5 w/s.f.) 4. Design High-Efficiency Domestic Hot Water Systems (94% Eff. Hot Water Heaters)	668,090	3,048.4	\$122,861	\$22,549	\$145,410	\$0.97	35.52	\$77,038	34.6%	13

\*Combined expense savings is the difference between the combined annual expense of the baseline and building in comparison.

### Electric Consumption (kWh)



### Gas Consumption (Btu)



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling

#### Electric Consumption (kWh x000)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	4.2	3.8	3.9	4.4	7.6	12.0	16.4	13.5	15.5	5.8	4.1	3.7	94.9
Heat Reject.	0.0	0.0	0.0	0.0	0.4	1.0	1.3	1.2	1.1	0.2	0.0	0.0	5.3
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	-	-	-	-	-	-	-	-	-	-	-	-	-
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	30.3	26.1	23.8	20.0	21.8	20.9	17.7	15.8	23.5	20.6	19.0	26.6	266.2
Pumps & Aux.	16.8	14.6	15.4	12.1	9.4	8.9	8.5	8.3	9.3	9.9	12.5	16.1	141.9
Ext. Usage	0.8	0.6	0.7	0.6	0.5	0.4	0.5	0.7	0.7	0.7	0.8	0.8	7.8
Misc. Equip.	16.8	17.5	14.8	16.0	19.4	13.6	8.8	8.6	16.6	20.0	17.1	10.7	179.7
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	35.0	36.2	32.1	33.9	40.4	28.5	19.1	18.5	34.5	41.0	35.9	24.3	379.4
<b>Total</b>	<b>103.8</b>	<b>98.8</b>	<b>90.7</b>	<b>87.1</b>	<b>99.6</b>	<b>85.3</b>	<b>72.3</b>	<b>66.7</b>	<b>101.1</b>	<b>98.3</b>	<b>89.4</b>	<b>82.2</b>	<b>1,075.2</b>

#### Gas Consumption (Btu x000,000)


	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	451.4	358.7	246.2	158.5	58.6	32.9	23.5	25.2	34.0	98.4	184.7	342.4	2,014.5
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	113.9	120.4	101.2	108.7	119.7	81.2	53.0	49.2	86.8	108.1	98.1	69.8	1,110.0
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	23.4	24.7	19.5	22.1	27.3	13.0	0.1	0.1	20.8	28.5	23.4	13.1	216.0
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>588.7</b>	<b>503.8</b>	<b>366.9</b>	<b>289.3</b>	<b>205.5</b>	<b>127.2</b>	<b>76.6</b>	<b>74.5</b>	<b>141.5</b>	<b>235.0</b>	<b>306.1</b>	<b>425.3</b>	<b>3,340.5</b>




**Annual Energy Consumption by Enduse**

	<b>Electricity kWh (x000)</b>	<b>Natural Gas MBtu</b>	<b>Steam Btu</b>	<b>Chilled Water Btu</b>
Space Cool	94.9	-	-	-
Heat Reject.	5.3	-	-	-
Refrigeration	-	-	-	-
Space Heat	-	2,014.5	-	-
HP Supp.	-	-	-	-
Hot Water	-	1,110.0	-	-
Vent. Fans	266.2	-	-	-
Pumps & Aux.	141.9	-	-	-
Ext. Usage	7.8	-	-	-
Misc. Equip.	179.7	216.0	-	-
Task Lights	-	-	-	-
Area Lights	379.4	-	-	-
<b>Total</b>	<b>1,075.2</b>	<b>3,340.5</b>	-	-

- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling




**Electricity**




**Natural Gas**

**Monthly Utility Bills (\$)**




**Total Annual Bill Across All Rates: \$ 222,448**

**Electric Demand (kW)**



**Gas Demand (Btu/h)**



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling

**Electric Demand (kW)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	9.5	14.1	13.0	15.4	75.3	126.4	131.8	119.9	161.6	36.6	20.8	8.2	732.6
Heat Reject.	-	-	-	0.5	4.8	4.8	12.7	4.8	12.1	3.1	1.3	-	44.1
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	-	-	-	-	-	-	-	-	-	-	-	-	-
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	68.7	73.8	72.5	80.1	117.8	118.7	93.5	91.4	148.5	92.2	68.6	69.6	1,095.4
Pumps & Aux.	23.7	23.9	23.8	23.6	25.6	26.1	31.0	27.1	33.4	24.0	23.8	23.7	309.7
Ext. Usage	-	-	-	-	-	-	-	0.4	0.4	-	-	-	0.7
Misc. Equip.	80.8	73.8	80.8	80.8	64.4	77.8	24.0	24.3	49.7	76.8	77.8	80.8	791.8
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	117.3	117.3	117.3	117.3	117.3	117.3	55.6	53.8	112.9	117.3	117.3	117.3	1,277.8
<b>Total</b>	<b>300.0</b>	<b>302.9</b>	<b>307.3</b>	<b>317.6</b>	<b>405.2</b>	<b>471.2</b>	<b>348.6</b>	<b>321.6</b>	<b>518.5</b>	<b>350.0</b>	<b>309.6</b>	<b>299.7</b>	<b>4,252.2</b>


**Gas Demand (Btu/h x1000,000)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	2.19	2.64	2.30	2.44	0.38	0.16	0.19	0.26	0.22	1.35	2.36	2.44	16.93
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	0.46	0.24	0.24	0.23	0.43	0.40	0.15	0.06	0.36	0.19	0.20	0.22	3.18
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	0.38	0.00	0.00	0.00	0.38	0.38	-	-	0.38	0.00	0.00	0.00	1.54
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>3.03</b>	<b>2.88</b>	<b>2.54</b>	<b>2.68</b>	<b>1.20</b>	<b>0.94</b>	<b>0.34</b>	<b>0.33</b>	<b>0.96</b>	<b>1.54</b>	<b>2.56</b>	<b>2.66</b>	<b>21.65</b>


**Annual Peak Demand by Enduse**

	Electricity kW	Natural Gas Btu/h (x000)	Steam Btu/h	Chilled Water Btu/h
Space Cool	161.56	-	-	-
Heat Reject.	12.10	-	-	-
Refrigeration	-	-	-	-
Space Heat	-	2,186.6	-	-
HP Supp.	-	-	-	-
Hot Water	-	459.7	-	-
Vent. Fans	148.49	-	-	-
Pumps & Aux.	33.44	-	-	-
Ext. Usage	0.37	-	-	-
Misc. Equip.	49.72	379.5	-	-
Task Lights	-	-	-	-
Area Lights	112.86	-	-	-
<b>Total</b>	<b>518.53</b>	<b>3,025.7</b>	-	-

- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling




**Electricity**




**Natural Gas**

### Electric Consumption (kWh)



### Gas Consumption (Btu)



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling

#### Electric Consumption (kWh x000)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	4.08	3.94	4.22	4.98	12.22	21.53	28.61	24.50	24.62	7.77	4.88	4.90	146.24
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	0.58	0.48	0.43	0.34	0.14	0.07	0.04	0.04	0.07	0.21	0.30	0.52	3.22
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	10.01	10.64	8.95	9.23	8.76	9.14	10.60	8.57	11.14	10.84	10.14	6.70	114.71
Pumps & Aux.	2.10	1.93	2.02	1.97	2.10	2.30	2.58	2.46	2.48	2.06	1.96	2.14	26.09
Ext. Usage	0.66	0.51	0.56	0.54	0.39	0.38	0.39	0.63	0.61	0.63	0.64	0.66	6.60
Misc. Equip.	16.76	17.46	14.78	15.98	19.43	13.57	8.82	8.63	16.59	19.96	17.08	10.66	179.72
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	17.65	18.26	16.21	17.09	20.41	14.38	9.66	9.32	17.40	20.72	18.13	12.27	191.51
<b>Total</b>	<b>51.85</b>	<b>53.22</b>	<b>47.16</b>	<b>50.14</b>	<b>63.43</b>	<b>61.36</b>	<b>60.70</b>	<b>54.15</b>	<b>72.92</b>	<b>62.19</b>	<b>53.13</b>	<b>37.85</b>	<b>668.09</b>


#### Gas Consumption (Btu x000,000)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	376.2	302.2	220.5	151.9	47.8	20.1	11.3	10.9	22.5	83.3	159.5	313.3	1,719.6
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	114.0	120.6	101.4	109.0	120.0	81.5	53.1	49.4	87.1	108.4	98.4	69.9	1,112.8
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	23.4	24.7	19.5	22.1	27.3	13.0	0.1	0.1	20.8	28.5	23.4	13.1	216.0
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>513.6</b>	<b>447.5</b>	<b>341.4</b>	<b>282.9</b>	<b>195.1</b>	<b>114.7</b>	<b>64.6</b>	<b>60.3</b>	<b>130.4</b>	<b>220.3</b>	<b>281.3</b>	<b>396.3</b>	<b>3,048.4</b>


**Annual Energy Consumption by Enduse**

	<b>Electricity kWh (x000)</b>	<b>Natural Gas MBtu</b>	<b>Steam Btu</b>	<b>Chilled Water Btu</b>
Space Cool	146.24	-	-	-
Heat Reject.	-	-	-	-
Refrigeration	-	-	-	-
Space Heat	3.22	1,719.6	-	-
HP Supp.	-	-	-	-
Hot Water	-	1,112.8	-	-
Vent. Fans	114.71	-	-	-
Pumps & Aux.	26.09	-	-	-
Ext. Usage	6.60	-	-	-
Misc. Equip.	179.72	216.0	-	-
Task Lights	-	-	-	-
Area Lights	191.51	-	-	-
<b>Total</b>	<b>668.09</b>	<b>3,048.4</b>	<b>-</b>	<b>-</b>

- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling




**Electricity**




**Natural Gas**

**Monthly Utility Bills (\$)**




**Total Annual Bill Across All Rates: \$ 145,410**

**Electric Demand (kW)**



**Gas Demand (Btu/h)**



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling

**Electric Demand (kW)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	10.1	10.1	10.1	52.9	109.5	203.0	211.0	163.0	270.2	81.8	52.0	15.5	1,189.3
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	0.9	0.9	0.9	0.5	0.2	0.3	0.2	0.2	0.2	0.4	0.5	0.9	6.1
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	49.8	51.2	51.4	23.3	69.9	86.2	63.2	66.9	118.3	56.6	22.8	48.3	707.9
Pumps & Aux.	3.9	3.8	3.8	4.2	6.2	9.1	9.6	9.6	12.6	5.5	4.2	3.9	76.5
Ext. Usage	-	-	-	-	-	-	-	0.3	0.3	-	-	-	0.6
Misc. Equip.	80.8	80.8	80.8	76.8	77.8	77.8	24.0	24.3	49.7	76.8	77.8	80.8	808.2
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	59.2	59.2	59.2	59.2	59.2	59.2	28.1	29.1	57.0	59.2	59.2	59.2	647.0
<b>Total</b>	<b>204.9</b>	<b>206.1</b>	<b>206.2</b>	<b>216.9</b>	<b>322.8</b>	<b>435.7</b>	<b>336.2</b>	<b>293.4</b>	<b>508.3</b>	<b>280.2</b>	<b>216.4</b>	<b>208.6</b>	<b>3,435.5</b>

**Gas Demand (Btu/h x1000,000)**


	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	3.22	3.20	2.18	2.76	1.04	0.13	0.10	0.11	0.20	1.46	2.31	2.39	19.10
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	0.23	0.24	0.24	0.23	0.22	0.40	0.15	0.14	0.36	0.19	0.20	0.22	2.82
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	0.00	0.00	0.00	0.00	0.00	0.38	-	-	0.38	0.00	0.00	0.00	0.79
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>3.46</b>	<b>3.45</b>	<b>2.42</b>	<b>3.00</b>	<b>1.26</b>	<b>0.91</b>	<b>0.26</b>	<b>0.25</b>	<b>0.94</b>	<b>1.65</b>	<b>2.51</b>	<b>2.61</b>	<b>22.71</b>




**Annual Peak Demand by Enduse**

	<b>Electricity kW</b>	<b>Natural Gas Btu/h (x000)</b>	<b>Steam Btu/h</b>	<b>Chilled Water Btu/h</b>
Space Cool	270.23	-	-	-
Heat Reject.	-	-	-	-
Refrigeration	-	-	-	-
Space Heat	0.20	3,224.5	-	-
HP Supp.	-	-	-	-
Hot Water	-	231.4	-	-
Vent. Fans	118.27	-	-	-
Pumps & Aux.	12.61	-	-	-
Ext. Usage	0.31	-	-	-
Misc. Equip.	49.72	3.8	-	-
Task Lights	-	-	-	-
Area Lights	56.97	-	-	-
<b>Total</b>	<b>508.30</b>	<b>3,459.7</b>	<b>-</b>	<b>-</b>

- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling



**Electricity**



**Natural Gas**



## Appendix

### 2 Life Cycle Cost Analysis

- Water Use Reduction Life Cycle Analysis
- Mechanical System Lifecycle Engineering Economic Analysis





# **Water Use Reduction Life Cycle Analysis**

**for**

**Fuller Middle School**

**Framingham, MA**

**October 18, 2019**

Prepared for:



Prepared by:

**AKAL Engineering Inc**

## Water Use Reduction Summary

October 18, 2019

The Fuller Middle School will utilize high water efficiency equipment in order to minimize water consumption and reduce the burden on the aquifer and well water supply. The plumbing fixtures selected for the project are intended to reduce water consumption by greater than 30% beyond a typical code required design.

High efficiency fixtures specified for the project include the following:

- High-efficiency water closets equipped with 1.28 gallon per flush flushometers in lieu of code required 1.6 gallon per flush.
- High-efficiency urinals equipped with 0.125 gallon per flush flushometers in lieu of code required 1.0 gallon per flush urinal.
- Metering lavatory faucets with 0.35 GPM aerators in lieu of code required 0.5 GPM.
- General sinks equipped with 0.5 gallon per minute restricting faucets.
- Showers equipped with 1.5 GPM shower head in lieu of 2.5 GPM.

The attached spreadsheet will quantify the water use reduction expected. The spreadsheet calculates the baseline (code required) water use and the design water use. The approximate annual water savings is 335,043 gallons of water with a simple payback of less than 1 year for the high efficiency plumbing fixtures.



<b>DESIGNED</b>							
<b>PROJECT : FULLER MIDDLE SCHOOL, MA</b>							
<b>Credit 4 Water use Reduction</b>							

**Design Indoor Water Consumption Calculation**

Fixture Type	Flow-rate	Rate	Duration	Unit	Occupants	Daily Uses	Water Use
Conventional Toilet -Staff	1.28	gpf	1	flush	110	3	422.4
Low flow Flush Toilet (Male Student)	1.28	gpf	1	flush	450	1	576
Urinals (ultra low flow)-Male student	0.125	gpf	1	flush	450	2	112.5
Low Flow Flush Toilet (Female Student)	1.28	gpf	1	flush	450	3	1728
Lavatory (low flow hand free)	0.5	gal/min	0.5	min	1010	3	757.5
Class Room Sink s	1.5	gal/min	0.25	min	110	2	82.5
Shower	2.5	gpm	15	min.	11	1	413
Hand Sink- Kitchen	1.2	gal/min	15	min	4	1	72
Wash Down -Sprayer	0.67	gal/min	15	min.	1	1	10.05
Efficient Clothes Washer	20	gal/load	1	load	1	4	80
Total Daily Volume							3831.05
Number of School Days							180
Design Total Annual Volume (gal)							689,589.00

**Credit Water Efficiency-Credit for water use reduction.**

Design	Annual Water Consumption (gal)	Annual Water Saving (gal)	% of water Reduction
<b>Designed</b>	<b>689,589.00</b>	<b>365,436.00</b>	<b>34.64%</b>
<b>Baseline</b>	<b>1,055,025.00</b>	<b>-</b>	<b>-</b>


Total annual water saving will be 365,435 gallon or 48,855 cubic feet water and sewer saving. Cost saving can be calculated based on the town of Framingham Water Department.



## Water Conservation & LCCA

Conservation Method	Number of Installations	Total Initial Cost (\$)	Annual Savings (\$)			Payback Period* (yrs) <small>*Includes Direct Energy Only</small>
			Direct Water	Direct Energy	Indirect Energy	
Installation of ULF toilets and ULF urinals	72	\$6,500	\$7,828	\$0	\$90	0.83
Installation of automatic faucets	83	\$6,480	\$6,445	\$1,856	\$376	0.78
Installation of faucet aerators	83	\$2,200	\$1,463	\$4,800	\$85	0.35
Low Flow showerhead	1	\$140	\$256	\$5,800	\$78	0.02
Boiler blowdown optimization	0	\$0	\$0	\$0	\$0	0.00
Efficient dishwashers	2	\$150	\$4,000	\$3,500	\$791	0.02
Efficient washing machines	1	\$300	\$11,688	\$4,034	\$791	0.02
Landscape irrigation optimization	#N/A	\$6	\$12	\$0	\$0	Annual
<b>Total (excluding Landscape)</b>		<b>\$15,770</b>	<b>\$31,680</b>	<b>\$19,990</b>	<b>\$2,211</b>	<b>0.31</b>

**Payback Periods and Net Worth of Each WCM Including only Direct Energy and Water Savings**





**Engineering Economic Analysis  
for  
Fuller Middle School  
Framingham, MA**

**May 3, 2019  
75% Design Documents**

Prepared for:



Prepared by:



**Garcia, Galuska & DeSousa**  
Consulting Engineers, Inc.

Fuller Middle School Engineering Economic Analysis

Table of Contents

Executive Summary .....	3
Mechanical System Payback Summary Chart.....	12
LEED Energy Savings Summary Charts .....	13
Life Cycle Analyses Outputs .....	15
Cost Estimates.....	31
Energy Profiles.....	41

# **EXECUTIVE SUMMARY**

## Section 1.0: Executive Summary

The Fuller Middle School is a new four-story school with an approximate gross area of 150,000 s.f. The building has been simulated with the school's anticipated hours of operation including evening and summer programming.

The goal of the mechanical system lifecycle engineering economic analysis is to assess the performance of various mechanical systems in comparison to a baseline mechanical system.

Each option is compared to the baseline system to determine the lowest combined savings over a 30 year cycle to determine the most advantageous system considering anticipated hours of operation, electrical costs, gas costs, maintenance costs, and initial construction costs.

The conditioned spaces of the building are simulated to maintain indoor air temperature conditions of 70°F DB for heating and 75°F DB with 55% RH for cooling for all options. Unoccupied temperature setback of 60°F DB heating and 85°F DB cooling is provided for all options.

By comparison of each option to the baseline system, the option with the greatest total life-cycle savings is generally recommended. To further enhance controllability and overall system performance, additional options should be considered that will enhance year round temperature control and comfort at a possible marginal increase in capital cost.

Upon completion of the mechanical system lifecycle engineering economic analysis, the design building is simulated with the recommended mechanical system in comparison to an ASHRAE Standard 90.1-2010 baseline building to project the anticipated energy cost percentage savings for LEED V4 EAc2 – Optimize Energy Performance.

## Section 1.1: Mechanical System Analysis

### 1.1.A: Baseline Mechanical System – ASHRAE/IECC Baseline Variable Air Volume Systems

- Hot water coil heating/chilled water coil cooling rooftop air handling units with energy recovery wheels and terminal variable air volume boxes with hot water reheat coils serving the administration, classrooms, auditorium/stage, cafeteria, gymnasium, media center, and locker room areas
- Chilled water cooling/hot water coil rooftop make-up air handling unit and variable air volume exhaust air fan system serving the kitchen
- Overhead fiberglass insulated supply and return air ductwork distribution systems
- Limited use of radiant heating panels and unit heaters
- (4) 2,000 MBH code-efficient gas-fired boiler power plant
- (2) 175 ton code high-efficiency water-cooled chillers and cooling tower chilled water plant (350 ton total capacity)
- Four-pipe heating/cooling piping system serving air handling units

- Two-pipe hot water distribution system serving radiant heating panels, unit heaters, and variable air volume boxes with hot water reheat coils
- Chilled, condenser, and hot water primary pumping with variable frequency drives
- Direct digital controls throughout

#### 1.1.B: Mechanical System Option One – High-Efficiency Variable Air Volume Systems

- Hot water coil heating/chilled water coil cooling rooftop air handling units with energy recovery wheels and terminal variable air volume boxes with hot water reheat coils serving the administration, classrooms, auditorium/stage, cafeteria, gymnasium, media center, and locker room areas
- Chilled water cooling/hot water coil rooftop make-up air handling unit and variable air volume exhaust air fan system serving the kitchen
- Overhead fiberglass insulated supply and return air ductwork distribution systems
- Limited use of radiant heating panels and unit heaters
- (4) 2,000 MBH high-efficiency gas-fired condensing boiler power plant
- (2) 175 ton high-efficiency water-cooled chillers and cooling tower chilled water plant (350 ton total capacity)
- Four-pipe heating/cooling piping system serving air handling units
- Two-pipe hot water distribution system serving radiant heating panels, unit heaters, and variable air volume boxes with hot water reheat coils
- Chilled, condenser, and hot water primary pumping with variable frequency drives
- Direct digital controls throughout

#### 1.1.C: Mechanical System Option Two – Variable Air Volume Mixed-Air Full Air-Conditioning Displacement Systems

- Multiple low wall-mounted displacement diffusers at approximately 600-800 CFM (1 per classroom) each for each classroom and support area
- Multiple low wall-mounted displacement diffusers located throughout the administration, cafeteria, and media center areas
- Multiple low wall-mounted fully air-conditioned displacement diffusers located throughout the auditorium/stage and gymnasium areas
- Variable air volume boxes with demand ventilation control and temperature sensor to modulate airflow based on occupancy and space heating/cooling demand for each zone
- Dedicated overhead galvanized ventilation distribution system feeding each displacement diffuser

- Radiant heating panels located along exterior walls
- Variable air volume hot water coil heating/chilled water coil cooling rooftop air handling units with demand control ventilation and energy recovery wheels providing fully air conditioned displacement ventilation to the terminal variable air volume boxes serving the administration, auditorium/stage, classroom, cafeteria, gymnasium, and media center areas
- Chilled water cooling/hot water coil rooftop make-up air handling unit and variable air volume exhaust air fan system serving the kitchen
- Limited use of radiant heating panels and unit heaters
- (4) 2,000 MBH high-efficiency gas-fired condensing boiler power plant
- (2) 175 ton high-efficiency water-cooled chillers and cooling tower chilled water plant (350 ton total capacity)
- Four-pipe heating/cooling piping system serving air handling units
- Two-pipe hot water distribution system serving radiant heating panels and unit heaters
- Chilled, condenser, and hot water primary pumping with variable frequency drives
- Direct digital controls throughout

1.1.D: Mechanical System Option Two (a) – Variable Air Volume Mixed-Air Full Air-Conditioning Displacement Systems with Static Plate Energy Recovery

- This option is identical to Option 3 as outlined above but will utilize static plate energy recovery in each air handling unit rather than energy recovery wheels

1.1.E: Mechanical System Option Two (b) – Variable Air Volume Mixed-Air Full Air-Conditioning Displacement Systems with Static Plate Energy Recovery with Air-Cooled Chiller Plant

- This option is identical to Option 2b as outlined above but will utilize (2) 175 ton code high-efficiency air-cooled chillers (350 ton total capacity) rather than water-cooled chillers and the associated cooling tower

1.1.F: Mechanical System Option Three – Variable Air Volume Displacement Systems with Supplemental Passive Chilled Beam Air-Conditioning Units

- Multiple low wall-mounted displacement diffusers at approximately 450-600 CFM (1 per classroom) each for each classroom and support area
- Multiple low wall-mounted displacement diffusers located throughout the administration, cafeteria, and media center areas
- Radiant passive chilled beam cooling/heating panels providing full air-conditioning located throughout the classroom, administration, cafeteria, and media center areas



- Multiple low wall-mounted fully air-conditioned displacement diffusers located throughout the auditorium/stage and gymnasium areas
- Variable air volume boxes with demand ventilation control and temperature sensor to modulate airflow based on occupancy and space heating/cooling demand for each zone
- Dedicated overhead galvanized ventilation distribution system feeding each displacement diffuser
- Radiant heating panels located along exterior walls
- Variable air volume 100% outside air hot water coil heating/chilled water coil cooling rooftop air handling units with demand control ventilation and energy recovery wheels providing displacement ventilation to the terminal variable air volume boxes serving the classroom, cafeteria, and media center areas
- Variable air volume hot water coil heating/chilled water coil cooling rooftop air handling units with demand control ventilation and energy recovery wheels providing displacement ventilation to the terminal variable air volume boxes serving the gymnasium areas
- Variable air volume hot water coil heating/chilled water coil cooling rooftop air handling units with demand control ventilation and energy recovery wheels providing fully air conditioned displacement ventilation to the administration and auditorium/stage areas
- Chilled water cooling/hot water coil rooftop make-up air handling unit and variable air volume exhaust air fan system serving the kitchen
- Limited use of radiant heating panels and unit heaters
- (4) 2,000 MBH high-efficiency gas-fired condensing boiler power plant
- (2) 175 ton high-efficiency water-cooled chillers and cooling tower chilled water plant (350 ton total capacity)
- Four-pipe heating/cooling piping system serving air handling units and passive chilled beam units
- Two-pipe hot water distribution system serving radiant heating panels and unit heaters
- Chilled, condenser, and hot water primary pumping with variable frequency drives
- Direct digital controls throughout

1.1.G: Mechanical System Option Three (a) – Variable Air Volume Displacement Systems with Static Plate Energy Recovery and Supplemental Passive Chilled Beam Air-Conditioning Units

- This option is identical to Option 3 as outlined above but will utilize static plate energy recovery in each air handling unit rather than energy recovery wheels

1.1.H: Mechanical System Option Three (b) – Variable Air Volume Displacement Systems with Static Plate Energy Recovery and Supplemental Passive Chilled Beam Air-Conditioning Units with Air-Cooled Chiller Plant

- This option is identical to Option 3a as outlined above but will utilize (2) 175 ton code high-efficiency air-cooled chillers (350 ton total capacity) rather than water-cooled chillers and the associated cooling tower

1.1.I: Mechanical System Option Four – Geothermal Plant serving Variable Air Volume Mixed-Air Full Air-Conditioning Displacement Systems with Static Plate Energy Recovery

- Multiple low wall-mounted displacement diffusers at approximately 600-800 CFM (1 per classroom) each for each classroom and support area
- Multiple low wall-mounted displacement diffusers located throughout the administration, cafeteria, and media center areas
- Multiple low wall-mounted fully air-conditioned displacement diffusers located throughout the auditorium/stage and gymnasium areas
- Variable air volume boxes with demand ventilation control and temperature sensor to modulate airflow based on occupancy and space heating/cooling demand for each zone
- Dedicated overhead galvanized ventilation distribution system feeding each displacement diffuser
- Radiant heating panels located along exterior walls
- Variable air volume hot water coil heating/chilled water coil cooling rooftop air handling units with demand control ventilation and static plate energy recovery providing fully air conditioned displacement ventilation to the terminal variable air volume boxes serving the administration, auditorium/stage, classroom, cafeteria, gymnasium, and media center areas
- Chilled water cooling/hot water coil rooftop make-up air handling unit and variable air volume exhaust air fan system serving the kitchen
- Limited use of radiant heating panels and unit heaters
- (2) 2,000 MBH high-efficiency gas-fired condensing boiler power plant
- (140) 500' deep geothermal closed loop wells (350 tons total capacity)
- 350 ton total capacity high-efficiency water-to-water source geothermal modular heat pump chiller plant providing chilled and hot water throughout the building
- Four-pipe heating/cooling piping system serving air handling units
- Two-pipe hot water distribution system serving radiant heating panels and unit heaters
- Chilled, condenser, geothermal well, and hot water primary pumping with variable frequency drives
- Direct digital controls throughout

## Section 1.2: Mechanical System Analysis Conclusion

The variable air volume air handling unit system is selected as the baseline system since it is an ASHRAE Standard 90.1/IECC baseline system that results in a low installed cost and relatively energy efficient system. Unfortunately, the selection results in overall ownership costs that in some cases are higher when compared to the alternative systems primarily relating to increased annual operating costs while potentially compromising the thermal comfort conditions of the building. The option comparison of each alternative system to the baseline assesses the benefits of improved systems with potentially reduced combined operating costs and improved thermal comfort with the goal of selecting the system with the highest ownership savings over the 30 year study period.

Annual electrical and gas consumption is calculated thru the results of a thermal dynamic heat transfer analysis utilizing Department of Energy (DOE-2)/eQuest software with all architectural data provided by Jonathan Levi Architects.

The building envelope reflects Jonathan Levi Architects' high-efficiency design. The roof has R-36 continuous insulation and the walls have R-12 continuous insulation. Windows have a U-Value of 0.24 and a SHGC of 0.39. The walls of the gymnasium and auditorium building are a pre-engineered metal sandwich panel assembly with an R-22 assembly rating.

Utility cost data for natural gas (\$0.7397/therm) was obtained from utility bills of the existing school provided by the town. Utility cost data for electricity (\$0.1839/kWh) was based from published average utility rates of the local utility providers.

The "Building Life-Cycle" analysis included future worth of each system option considered using standard industry discount, inflation, and interest rates.

Our observations of the Mechanical System Payback Summary suggest that Option 3b, Variable Air Volume Displacement Systems with Static Plate Energy Recovery and Supplemental Passive Chilled Beam Air-Conditioning Units with Air-Cooled Chiller Plant, represents the lowest life cycle by yielding an approximate \$1,925,347 savings over the 30 year study period with an instant payback as it has a lower installed cost than the code baseline system.

Option 2b, Variable Air Volume Mixed-Air Full Air-Conditioning Displacement Systems with Static Plate Energy Recovery with Air-Cooled Chiller Plant, represents the second lowest life cycle cost by yielding an approximate \$1,891,411 savings over the 30 year study period with an instant payback as it has a lower installed cost than the code baseline system. Due to the town's concerns with increased maintenance for the additional control valves and condensation considerations for the passive chilled beams of Option 3b's design, Option 2b is the recommended system for the project.

## Section 2.0: LEED Energy Savings Summary

To confirm that the design building meets the MSBA requirements of 16% energy cost savings for LEED V4 EAc2 – Optimize Energy Performance, updated energy model simulations have been performed comparing the design building in comparison to a baseline ASHRAE Standard 90.1-2010 building.

1. The ASHRAE Standard 90.1-2010 baseline building is as follows:

- Envelope:
  - Wall: R-13 + R-7.5 c.i.
  - Roof: R-20 c.i.
  - Underslab: R-10 c.i.
  - Windows: 0.55 U-Value, 0.40 SHGC
  - Curtainwall: 0.45 U-Value, 0.40 SHGC
- Mechanical System:
  - Hot water coil heating/chilled water coil cooling VAV AHU systems with energy recovery wheels serving terminal VAV boxes with hot water reheat coils
  - (2) 82% efficient gas-fired hot water boilers
  - (2) 0.68 kW/ton high-efficiency water-cooled chillers with associated cooling tower
- Domestic Hot Water System:
  - 80% efficient gas-fired domestic hot water system
- Lighting System:
  - 0.99 w/s.f.

2. The design building with Mechanical System Option 3b is as follows:

- Envelope:
  - Walls: R-12 c.i.
  - Pre-Engineered Walls: R-22 c.i.
  - Roof: R-36 c.i.
  - Underslab: R-10 c.i.
  - Windows: 0.45 U-Value, 0.39 SHGC
  - Curtainwall: 0.38 U-Value, 0.39 SHGC
- Mechanical System:
  - Hot water coil heating/chilled water coil displacement ventilation AHU systems with static plate energy recovery serving terminal VAV boxes with demand ventilation controls (Mechanical System Option 2b)
  - (4) 94% efficient gas-fired hot water boilers
  - (2) 0.62 kW/ton high-efficiency water-cooled chillers with associated cooling tower
- Domestic Hot Water System:
  - 94% efficient gas-fired domestic hot water system
- Lighting System:
  - 0.50 w/s.f.

## Section 2.1: LEED Energy Savings Analysis Conclusion

A comparison of the Design Building, with Mechanical System Option 2b, against the ASHRAE Standard 90.1-2010 Baseline Building results in an energy cost savings of 36.9% achieving 14 LEED points. Exceeding the MSBA required 16% energy cost savings for LEED V4 EAc2 – Optimize Energy Performance.

### Note:

The values indicated above are based on energy modelling performed for system comparison purposes only. Our office strongly recommends adding a 30% safety factor to the calculated values of this report for budgeting purposes to account for potential variances to the actual operation of the building. Per ASHRAE Standard 90.1-2010:

*Neither the proposed building performance nor the baseline building performance are predictions of actual energy consumption or costs for the proposed design after construction. Actual experience will differ from these calculations due to variations such as occupancy, building operation and maintenance, weather, energy use not covered by this procedure, changes in energy rates between design of the building and occupancy, and the precision of the calculation tool.*

Fuller Middle School - Mechanical System Payback Summary

Baseline	System	Gross Capital Investment*	Annual Elec. Cons. (kWh)	Annual Gas Cons. (MBTU)	Annual Electric Cost	Annual Gas Cost	Combined Utility Cost	Annual Utility \$/s.f.	Annual kBTU/s.f. (EUI)	Annual Maint. Cost	Combined Annual Expense	Combined Expense Savings**	Total Life-Cycle Savings***	Discounted Payback (Years)****
-	1. Hot water coil heating/chilled water coil cooling VAV AHU system with energy recovery (where code required) and terminal VAV boxes with hot water reheat coils 2. Code efficient gas-fired non-condensing boiler plant 3. High efficiency (code) water-cooled chiller plant with cooling tower	\$7,490,250	951,950	4,287.9	\$175,064	\$31,718	\$206,782	\$1.38	50.2	\$31,225	\$238,007	-	-	-

Option	System	Gross Capital Investment*	Annual Elec. Cons. (kWh)	Annual Gas Cons. (MBTU)	Annual Electric Cost	Annual Gas Cost	Combined Utility Cost	Annual Utility \$/s.f.	Annual kBTU/s.f. (EUI)	Annual Maint. Cost	Combined Annual Expense	Combined Expense Savings**	Total Life-Cycle Savings***	Discounted Payback (Years)****
1	1. Hot water coil heating/chilled water coil cooling VAV AHU system with energy recovery and terminal VAV boxes with hot water reheat coils and CO2 controls 2. High efficiency gas-fired condensing boiler plant 3. High efficiency (code) water-cooled chiller plant with cooling tower	\$7,595,750	951,320	3,612.6	\$174,949	\$26,722	\$201,671	\$1.34	45.7	\$31,225	\$232,896	\$5,111	\$21,899	25
2	1. Full air-conditioning displacement ventilation diffusers with passive heating radiation 2. Hot water coil heating/chilled water cooling VAV ventilating units with energy recovery with terminal VAV boxes with CO2 controls 3. High efficiency gas-fired condensing boiler plant 4. High efficiency water-cooled chiller plant with cooling tower	\$7,326,500	650,930	2,949.7	\$119,706	\$21,819	\$141,525	\$0.94	34.5	\$26,900	\$168,425	\$69,582	\$1,844,797	Instant*****
2a	1. Full air-conditioning displacement ventilation diffusers with passive heating radiation 2. Hot water coil heating/chilled water cooling VAV ventilating units with <u>static plate energy recovery</u> with terminal VAV boxes with CO2 controls 3. High efficiency gas-fired condensing boiler plant 4. High efficiency water-cooled chiller plant with cooling tower	\$7,380,000	666,870	2,961.0	\$122,637	\$21,903	\$144,540	\$0.96	34.9	\$24,900	\$169,440	\$68,567	\$1,761,490	Instant*****
2b	1. Full air-conditioning displacement ventilation diffusers with passive heating radiation 2. Hot water coil heating/chilled water cooling VAV ventilating units with <u>static plate energy recovery</u> with terminal VAV boxes with CO2 controls 3. High efficiency gas-fired condensing boiler plant 4. High efficiency air-cooled chiller plant	\$7,317,500	657,560	2,961.0	\$120,925	\$21,903	\$142,828	\$0.95	34.7	\$23,700	\$166,528	\$71,479	\$1,891,411	Instant*****
3	1. Displacement ventilation diffusers providing full air-conditioning with passive chilled beam cooling/heating radiation 2. Hot water coil heating/chilled water cooling VAV ventilating units with energy recovery with terminal VAV boxes with CO2 controls 3. High efficiency gas-fired condensing boiler plant 4. High efficiency water-cooled chiller plant with cooling tower	\$7,274,750	639,710	2,958.5	\$117,643	\$21,884	\$139,527	\$0.93	34.3	\$30,250	\$169,777	\$68,230	\$1,872,422	Instant*****
3a	1. Displacement ventilation diffusers providing full air-conditioning with passive chilled beam cooling/heating radiation 2. Hot water coil heating/chilled water cooling VAV ventilating units with <u>static plate energy recovery</u> with terminal VAV boxes with CO2 controls 3. High efficiency gas-fired condensing boiler plant 4. High efficiency water-cooled chiller plant with cooling tower	\$7,319,100	652,030	2,959.6	\$119,908	\$21,892	\$141,800	\$0.95	34.6	\$28,250	\$170,050	\$67,957	\$1,816,268	Instant*****
3b	1. Displacement ventilation diffusers providing full air-conditioning with passive chilled beam cooling/heating radiation 2. Hot water coil heating/chilled water cooling VAV ventilating units with <u>static plate energy recovery</u> with terminal VAV boxes 3. High efficiency gas-fired condensing boiler plant 4. High efficiency air-cooled chiller plant	\$7,256,600	647,400	2,959.6	\$119,057	\$21,892	\$140,949	\$0.94	34.5	\$27,050	\$167,999	\$70,008	\$1,925,347	Instant*****
4	1. Displacement ventilation diffusers providing full air-conditioning with passive chilled beam cooling/heating radiation 2. Hot water coil heating/chilled water cooling VAV ventilating units with <u>static plate energy recovery</u> with terminal VAV boxes 3. High efficiency gas-fired condensing boiler plant 4. <u>Geothermal wells with water-to-water source heat pump chillers</u>	\$10,119,500	861,810	1,395.4	\$158,487	\$10,322	\$168,809	\$1.13	28.9	\$25,900	\$194,709	\$43,298	-\$1,578,949	N/A*****

\* Gross capital investment based upon in-house cost estimate utilizing cost data from similar past projects and industry standard estimating references. Costs have been estimated for system comparison purposes only and do not incorporate all supplemental/independent HVAC system costs which would be required for all systems studied (i.e. kitchen exhaust, overhead and profit).

\*\* Combined expense savings is the difference between the combined annual expense of the baseline and system in comparison.

\*\*\* Total life-cycle savings is based on a 30 year study period.

\*\*\*\* Discounted payback years is based upon BLCC5 Life Cycle Analysis.

\*\*\*\*\* Discounted payback never reached within 30 year study period.

\*\*\*\*\* Discounted payback never reached because system is more efficient and/or less expensive than baseline system.

Note 1: Values based on energy model performed for HVAC System Life Cycle Cost Analysis purposes. A 30% safety factor should be applied for budgeting purposes to account for potential variances to the actual operation of the building. Per ASHRAE Standard 90.1-2010:

Neither the proposed building performance nor the baseline building performance are predictions of actual energy consumption or costs for the proposed design after construction. Actual experience will differ from these calculations due to variations such as occupancy, building operation and maintenance, weather, energy use not covered by this procedure, changes in energy rates between design of the building and occupancy, and the precision of the calculation tool.



Fuller Middle School - LEED Energy Savings Summary

Baseline	System	Annual Elec. Cons. (kWh)	Annual Gas Cons. (MBTU)	Annual Electric Cost	Annual Gas Cost	Combined Utility Cost	Annual Utility \$/s.f.	Annual kBtu/s.f. (EUI)	Combined Expense Savings*	Energy Cost Savings Percentage	LEED EAc2 Points
LEED Baseline	1. ASHRAE Standard 90.1-2010 Envelope (Wall Insulation R-13 + R-7.5 c.i., Roof Insulation R-20 c.i., Windows 0.55 U-Value/0.40 SHGC, Curtainwall 0.45 U-Value/0.40 SHGC) 2. ASHRAE Standard 90.1-2010 Mechanical Systems (System 7 - Packaged VAV w/ Reheat with 0.68 kW/ton Water-Cooled Chillers and 82% Eff. Hot Water Boilers) 3. ASHRAE Standard 90.1-2010 Lighting System (0.99 w/s.f.) 4. ASHRAE Standard 90.1-2010 Domestic Hot Water Systems (82% Eff. Hot Water Heaters)	1,059,800	4,263.4	\$194,891	\$31,536	\$226,427	\$1.51	52.53	-	-	-

Option	System	Annual Elec. Cons. (kWh)	Annual Gas Cons. (MBTU)	Annual Electric Cost	Annual Gas Cost	Combined Utility Cost	Annual Utility \$/s.f.	Annual kBtu/s.f. (EUI)	Combined Expense Savings*	Energy Cost Savings Percentage	LEED EAc2 Points
2b	1. Design Envelope (Wall Insulation R-12 c.i., Pre-Engineered Walls: R-22 c.i., Roof Insulation R-36 c.i., Windows 0.45 U-Value/0.39 SHGC, Curtainwall 0.38 U-Value/0.39 SHGC) 2. Design Mechanical Systems (VAV Full AC Displacement Ventilation Static Plate ERV Systems and 1.05 High-Efficiency kW/ton Air-Cooled Chillers and 94% High-Efficiency Condensing Boilers) 3. Design High-Efficiency Lighting System (0.5 w/s.f.) 4. Design High-Efficiency Domestic Hot Water Systems (94% Eff. Hot Water Heaters)	657,560	2,961.0	\$120,925	\$21,903	\$142,828	\$0.95	34.70	\$83,599	36.9%	14

\*Combined expense savings is the difference between the combined annual expense of the baseline and building in comparison.

# **LIFE CYCLE ANALYSES**



## NIST BLCC 5.3-15: Comparative Analysis

Consistent with Federal Life Cycle Cost Methodology in OMB Circular A-94

### Base Case: Baseline - VAV

### Alternative: Option 1 - VAV

### General Information

**File Name:** C:\Users\keith\_lane\BLCC 5\projects\Fuller Middle School.xml  
**Date of Study:** Thu Jul 26 10:08:42 EDT 2018  
**Project Name:** Fuller Middle School  
**Project Location:** Massachusetts  
**Analysis Type:** OMB Analysis, Non-Energy Project  
**Analysis Purpose:** Public Investment or Regulatory Analysis  
**Analyst:** Keith Lane  
**Base Date:** September 1, 2020  
**Service Date:** September 1, 2020  
**Study Period:** 30 years 0 months(September 1, 2020 through August 31, 2050)  
**Discount Rate:** 4.3%  
**Discounting Convention:** End-of-Year

### Comparison of Present-Value Costs

#### PV Life-Cycle Cost

	Base Case	Alternative	Savings from Alternative
<b>Initial Investment Costs:</b>			
Capital Requirements as of Base Date	\$7,490,250	\$7,595,750	-\$105,500
<b>Future Costs:</b>			
Energy Consumption Costs	\$5,030,611	\$4,903,211	\$127,399
Energy Demand Charges	\$0	\$0	\$0
Energy Utility Rebates	\$0	\$0	\$0
Water Costs	\$0	\$0	\$0
Recurring and Non-Recurring OM&R Costs	\$675,485	\$675,485	\$0
Capital Replacements	\$0	\$0	\$0
Residual Value at End of Study Period	\$0	\$0	\$0
	-----	-----	-----
Subtotal (for Future Cost Items)	\$5,706,095	\$5,578,696	\$127,399
	-----	-----	-----
<b>Total PV Life-Cycle Cost</b>	<b>\$13,196,345</b>	<b>\$13,174,446</b>	<b>\$21,899</b>

#### Net Savings from Alternative Compared with Base Case

PV of Non-Investment Savings \$127,399

- Increased Total Investment     \$105,500

-----

Net Savings                             \$21,899

## Savings-to-Investment Ratio (SIR)

SIR = 1.21

## Adjusted Internal Rate of Return

AIRR = 4.96%

## Payback Period

### Estimated Years to Payback (from beginning of Service Period)

Simple Payback occurs in year     17

Discounted Payback occurs in year 25

## Energy Savings Summary

### Energy Savings Summary (in stated units)

Energy Type	-----Average Base Case	Annual Alternative	Consumption----- Savings	Life-Cycle Savings
Electricity	951,950.0 kWh	951,320.0 kWh	630.0 kWh	18,897.4 kWh
Natural Gas	42,879.0 Therm	36,126.0 Therm	6,753.0 Therm	202,562.3 Therm

### Energy Savings Summary (in MBtu)

Energy Type	-----Average Base Case	Annual Alternative	Consumption----- Savings	Life-Cycle Savings
Electricity	3,248.2 MBtu	3,246.0 MBtu	2.1 MBtu	64.5 MBtu
Natural Gas	4,287.9 MBtu	3,612.6 MBtu	675.3 MBtu	20,256.3 MBtu

## Emissions Reduction Summary

Energy Type	-----Average Base Case	Annual Alternative	Emissions----- Reduction	Life-Cycle Reduction
<b>Electricity</b>				
CO2	586,203.48 kg	585,815.53 kg	387.95 kg	11,636.88 kg
SO2	1,628.06 kg	1,626.98 kg	1.08 kg	32.32 kg
NOx	510.70 kg	510.36 kg	0.34 kg	10.14 kg
<b>Natural Gas</b>				
CO2	226,502.05 kg	190,830.31 kg	35,671.74 kg	1,070,005.56 kg
SO2	1,827.94 kg	1,540.06 kg	287.88 kg	8,635.28 kg
NOx	190.03 kg	57.18 kg	132.85 kg	3,985.05 kg

**Total:**

<b>CO2</b>	812,705.53 kg	776,645.84 kg	36,059.68 kg	1,081,642.44 kg
<b>SO2</b>	3,456.00 kg	3,167.04 kg	288.96 kg	8,667.60 kg
<b>NOx</b>	700.73 kg	567.54 kg	133.19 kg	3,995.19 kg

## NIST BLCC 5.3-15: Comparative Analysis

Consistent with Federal Life Cycle Cost Methodology in OMB Circular A-94

### Base Case: Baseline - VAV

### Alternative: Option 2 - Full AC Displacement

#### General Information

**File Name:** C:\Users\keith\_lane\BLCC 5\projects\Fuller Middle School.xml  
**Date of Study:** Thu Jul 26 10:09:12 EDT 2018  
**Project Name:** Fuller Middle School  
**Project Location:** Massachusetts  
**Analysis Type:** OMB Analysis, Non-Energy Project  
**Analysis Purpose:** Public Investment or Regulatory Analysis  
**Analyst:** Keith Lane  
**Base Date:** September 1, 2020  
**Service Date:** September 1, 2020  
**Study Period:** 30 years 0 months(September 1, 2020 through August 31, 2050)  
**Discount Rate:** 4.3%  
**Discounting Convention:** End-of-Year

#### Comparison of Present-Value Costs

##### PV Life-Cycle Cost

	Base Case	Alternative	Savings from Alternative
<b>Initial Investment Costs:</b>			
Capital Requirements as of Base Date	\$7,490,250	\$7,326,500	\$163,750
<b>Future Costs:</b>			
Energy Consumption Costs	\$5,030,611	\$3,443,125	\$1,587,485
Energy Demand Charges	\$0	\$0	\$0
Energy Utility Rebates	\$0	\$0	\$0
Water Costs	\$0	\$0	\$0
Recurring and Non-Recurring OM&R Costs	\$675,485	\$581,923	\$93,562
Capital Replacements	\$0	\$0	\$0
Residual Value at End of Study Period	\$0	\$0	\$0
	-----	-----	-----
Subtotal (for Future Cost Items)	\$5,706,095	\$4,025,048	\$1,681,047
	-----	-----	-----
<b>Total PV Life-Cycle Cost</b>	<b>\$13,196,345</b>	<b>\$11,351,548</b>	<b>\$1,844,797</b>

#### Net Savings from Alternative Compared with Base Case

PV of Non-Investment Savings \$1,681,047

- Increased Total Investment      -\$163,750

-----

Net Savings                              \$1,844,797

**NOTE: Meaningful SIR, AIRR and Payback can not be computed unless incremental savings and total savings are both positive.**

## Energy Savings Summary

### Energy Savings Summary (in stated units)

Energy Type	-----Average Base Case	Annual Alternative	Consumption----- Savings	Life-Cycle Savings
Electricity	951,950.0 kWh	650,930.0 kWh	301,020.0 kWh	9,029,363.8 kWh
Natural Gas	42,879.0 Therm	29,497.0 Therm	13,382.0 Therm	401,405.0 Therm

### Energy Savings Summary (in MBtu)

Energy Type	-----Average Base Case	Annual Alternative	Consumption----- Savings	Life-Cycle Savings
Electricity	3,248.2 MBtu	2,221.1 MBtu	1,027.1 MBtu	30,809.5 MBtu
Natural Gas	4,287.9 MBtu	2,949.7 MBtu	1,338.2 MBtu	40,140.7 MBtu

## Emissions Reduction Summary

Energy Type	-----Average Base Case	Annual Alternative	Emissions----- Reduction	Life-Cycle Reduction
<b>Electricity</b>				
CO2	586,203.48 kg	400,837.68 kg	185,365.80 kg	5,560,212.66 kg
SO2	1,628.06 kg	1,113.24 kg	514.81 kg	15,442.33 kg
NOx	510.70 kg	349.21 kg	161.49 kg	4,844.01 kg
<b>Natural Gas</b>				
CO2	226,502.05 kg	155,813.59 kg	70,688.46 kg	2,120,363.46 kg
SO2	1,827.94 kg	1,257.46 kg	570.48 kg	17,112.00 kg
NOx	190.03 kg	46.69 kg	143.35 kg	4,299.78 kg
<b>Total:</b>				
CO2	812,705.53 kg	556,651.27 kg	256,054.26 kg	7,680,576.13 kg
SO2	3,456.00 kg	2,370.71 kg	1,085.29 kg	32,554.33 kg
NOx	700.73 kg	395.89 kg	304.83 kg	9,143.79 kg

## NIST BLCC 5.3-15: Comparative Analysis

Consistent with Federal Life Cycle Cost Methodology in OMB Circular A-94

### Base Case: Baseline - VAV

### Alternative: Option 2A - Static Plate ERV Full AC Displacement

#### General Information

**File Name:** C:\Users\keith\_lane\BLCC 5\projects\Fuller Middle School.xml  
**Date of Study:** Thu Jul 26 10:09:47 EDT 2018  
**Project Name:** Fuller Middle School  
**Project Location:** Massachusetts  
**Analysis Type:** OMB Analysis, Non-Energy Project  
**Analysis Purpose:** Public Investment or Regulatory Analysis  
**Analyst:** Keith Lane  
**Base Date:** September 1, 2020  
**Service Date:** September 1, 2020  
**Study Period:** 30 years 0 months(September 1, 2020 through August 31, 2050)  
**Discount Rate:** 4.3%  
**Discounting Convention:** End-of-Year

#### Comparison of Present-Value Costs

##### PV Life-Cycle Cost

	Base Case	Alternative	Savings from Alternative
<b>Initial Investment Costs:</b>			
Capital Requirements as of Base Date	\$7,490,250	\$7,380,000	\$110,250
<b>Future Costs:</b>			
Energy Consumption Costs	\$5,030,611	\$3,516,199	\$1,514,412
Energy Demand Charges	\$0	\$0	\$0
Energy Utility Rebates	\$0	\$0	\$0
Water Costs	\$0	\$0	\$0
Recurring and Non-Recurring OM&R Costs	\$675,485	\$538,657	\$136,828
Capital Replacements	\$0	\$0	\$0
Residual Value at End of Study Period	\$0	\$0	\$0
	-----	-----	-----
Subtotal (for Future Cost Items)	\$5,706,095	\$4,054,856	\$1,651,240
	-----	-----	-----
<b>Total PV Life-Cycle Cost</b>	<b>\$13,196,345</b>	<b>\$11,434,856</b>	<b>\$1,761,490</b>

#### Net Savings from Alternative Compared with Base Case

PV of Non-Investment Savings \$1,651,240

- Increased Total Investment      -\$110,250

-----

Net Savings                              \$1,761,490

**NOTE: Meaningful SIR, AIRR and Payback can not be computed unless incremental savings and total savings are both positive.**

## Energy Savings Summary

### Energy Savings Summary (in stated units)

Energy Type	-----Average Base Case	Annual Alternative	Consumption----- Savings	Life-Cycle Savings
Electricity	951,950.0 kWh	666,870.0 kWh	285,080.0 kWh	8,551,229.2 kWh
Natural Gas	42,879.0 Therm	29,610.0 Therm	13,269.0 Therm	398,015.5 Therm

### Energy Savings Summary (in MBtu)

Energy Type	-----Average Base Case	Annual Alternative	Consumption----- Savings	Life-Cycle Savings
Electricity	3,248.2 MBtu	2,275.5 MBtu	972.7 MBtu	29,178.0 MBtu
Natural Gas	4,287.9 MBtu	2,961.0 MBtu	1,326.9 MBtu	39,801.7 MBtu

## Emissions Reduction Summary

Energy Type	-----Average Base Case	Annual Alternative	Emissions----- Reduction	Life-Cycle Reduction
<b>Electricity</b>				
CO2	586,203.48 kg	410,653.41 kg	175,550.07 kg	5,265,781.10 kg
SO2	1,628.06 kg	1,140.50 kg	487.55 kg	14,624.60 kg
NOx	510.70 kg	357.76 kg	152.94 kg	4,587.51 kg
<b>Natural Gas</b>				
CO2	226,502.05 kg	156,410.50 kg	70,091.55 kg	2,102,458.73 kg
SO2	1,827.94 kg	1,262.28 kg	565.66 kg	16,967.51 kg
NOx	190.03 kg	46.87 kg	143.17 kg	4,294.42 kg
<b>Total:</b>				
CO2	812,705.53 kg	567,063.91 kg	245,641.62 kg	7,368,239.83 kg
SO2	3,456.00 kg	2,402.79 kg	1,053.21 kg	31,592.11 kg
NOx	700.73 kg	404.62 kg	296.10 kg	8,881.92 kg

## NIST BLCC 5.3-15: Comparative Analysis

Consistent with Federal Life Cycle Cost Methodology in OMB Circular A-94

### Base Case: Baseline - VAV

### Alternative: Option 2B - ACC Static Plate ERV Full AC Displacement

#### General Information

**File Name:** C:\Users\keith\_lane\BLCC 5\projects\Fuller Middle School.xml  
**Date of Study:** Thu Jul 26 10:10:22 EDT 2018  
**Project Name:** Fuller Middle School  
**Project Location:** Massachusetts  
**Analysis Type:** OMB Analysis, Non-Energy Project  
**Analysis Purpose:** Public Investment or Regulatory Analysis  
**Analyst:** Keith Lane  
**Base Date:** September 1, 2020  
**Service Date:** September 1, 2020  
**Study Period:** 30 years 0 months(September 1, 2020 through August 31, 2050)  
**Discount Rate:** 4.3%  
**Discounting Convention:** End-of-Year

#### Comparison of Present-Value Costs

##### PV Life-Cycle Cost

	Base Case	Alternative	Savings from Alternative
<b>Initial Investment Costs:</b>			
Capital Requirements as of Base Date	\$7,490,250	\$7,317,500	\$172,750
<b>Future Costs:</b>			
Energy Consumption Costs	\$5,030,611	\$3,474,737	\$1,555,874
Energy Demand Charges	\$0	\$0	\$0
Energy Utility Rebates	\$0	\$0	\$0
Water Costs	\$0	\$0	\$0
Recurring and Non-Recurring OM&R Costs	\$675,485	\$512,698	\$162,787
Capital Replacements	\$0	\$0	\$0
Residual Value at End of Study Period	\$0	\$0	\$0
	-----	-----	-----
Subtotal (for Future Cost Items)	\$5,706,095	\$3,987,435	\$1,718,661
	-----	-----	-----
<b>Total PV Life-Cycle Cost</b>	<b>\$13,196,345</b>	<b>\$11,304,935</b>	<b>\$1,891,411</b>

#### Net Savings from Alternative Compared with Base Case

PV of Non-Investment Savings \$1,718,661



- Increased Total Investment      -\$172,750

-----

Net Savings                              \$1,891,411

**NOTE: Meaningful SIR, AIRR and Payback can not be computed unless incremental savings and total savings are both positive.**

## Energy Savings Summary

### Energy Savings Summary (in stated units)

Energy Type	-----Average Base Case	Annual Alternative	Consumption----- Savings	Life-Cycle Savings
Electricity	951,950.0 kWh	657,560.0 kWh	294,390.0 kWh	8,830,491.0 kWh
Natural Gas	42,879.0 Therm	29,610.0 Therm	13,269.0 Therm	398,015.5 Therm

### Energy Savings Summary (in MBtu)

Energy Type	-----Average Base Case	Annual Alternative	Consumption----- Savings	Life-Cycle Savings
Electricity	3,248.2 MBtu	2,243.7 MBtu	1,004.5 MBtu	30,130.9 MBtu
Natural Gas	4,287.9 MBtu	2,961.0 MBtu	1,326.9 MBtu	39,801.7 MBtu

## Emissions Reduction Summary

Energy Type	-----Average Base Case	Annual Alternative	Emissions----- Reduction	Life-Cycle Reduction
<b>Electricity</b>				
CO2	586,203.48 kg	404,920.38 kg	181,283.09 kg	5,437,748.34 kg
SO2	1,628.06 kg	1,124.58 kg	503.48 kg	15,102.21 kg
NOx	510.70 kg	352.76 kg	157.93 kg	4,737.32 kg
<b>Natural Gas</b>				
CO2	226,502.05 kg	156,410.50 kg	70,091.55 kg	2,102,458.73 kg
SO2	1,827.94 kg	1,262.28 kg	565.66 kg	16,967.51 kg
NOx	190.03 kg	46.87 kg	143.17 kg	4,294.42 kg
<b>Total:</b>				
CO2	812,705.53 kg	561,330.88 kg	251,374.65 kg	7,540,207.08 kg
SO2	3,456.00 kg	2,386.86 kg	1,069.14 kg	32,069.71 kg
NOx	700.73 kg	399.63 kg	301.10 kg	9,031.74 kg

## NIST BLCC 5.3-15: Comparative Analysis

Consistent with Federal Life Cycle Cost Methodology in OMB Circular A-94

### Base Case: Baseline - VAV

### Alternative: Option 3 - CB Full AC Displacement

#### General Information

**File Name:** C:\Users\keith\_lane\BLCC 5\projects\Fuller Middle School.xml  
**Date of Study:** Thu Jul 26 10:10:43 EDT 2018  
**Project Name:** Fuller Middle School  
**Project Location:** Massachusetts  
**Analysis Type:** OMB Analysis, Non-Energy Project  
**Analysis Purpose:** Public Investment or Regulatory Analysis  
**Analyst:** Keith Lane  
**Base Date:** September 1, 2020  
**Service Date:** September 1, 2020  
**Study Period:** 30 years 0 months(September 1, 2020 through August 31, 2050)  
**Discount Rate:** 4.3%  
**Discounting Convention:** End-of-Year

#### Comparison of Present-Value Costs

##### PV Life-Cycle Cost

	Base Case	Alternative	Savings from Alternative
<b>Initial Investment Costs:</b>			
Capital Requirements as of Base Date	\$7,490,250	\$7,274,750	\$215,500
<b>Future Costs:</b>			
Energy Consumption Costs	\$5,030,611	\$3,394,781	\$1,635,830
Energy Demand Charges	\$0	\$0	\$0
Energy Utility Rebates	\$0	\$0	\$0
Water Costs	\$0	\$0	\$0
Recurring and Non-Recurring OM&R Costs	\$675,485	\$654,393	\$21,092
Capital Replacements	\$0	\$0	\$0
Residual Value at End of Study Period	\$0	\$0	\$0
	-----	-----	-----
Subtotal (for Future Cost Items)	\$5,706,095	\$4,049,174	\$1,656,922
	-----	-----	-----
<b>Total PV Life-Cycle Cost</b>	<b>\$13,196,345</b>	<b>\$11,323,924</b>	<b>\$1,872,422</b>

#### Net Savings from Alternative Compared with Base Case

PV of Non-Investment Savings \$1,656,922

- Increased Total Investment      -\$215,500

-----

Net Savings                              \$1,872,422

**NOTE: Meaningful SIR, AIRR and Payback can not be computed unless incremental savings and total savings are both positive.**

## Energy Savings Summary

### Energy Savings Summary (in stated units)

Energy Type	-----Average Base Case	Annual Alternative	Consumption----- Savings	Life-Cycle Savings
Electricity	951,950.0 kWh	639,710.0 kWh	312,240.0 kWh	9,365,917.7 kWh
Natural Gas	42,879.0 Therm	29,585.0 Therm	13,294.0 Therm	398,765.4 Therm

### Energy Savings Summary (in MBtu)

Energy Type	-----Average Base Case	Annual Alternative	Consumption----- Savings	Life-Cycle Savings
Electricity	3,248.2 MBtu	2,182.8 MBtu	1,065.4 MBtu	31,957.8 MBtu
Natural Gas	4,287.9 MBtu	2,958.5 MBtu	1,329.4 MBtu	39,876.7 MBtu

## Emissions Reduction Summary

Energy Type	-----Average Base Case	Annual Alternative	Emissions----- Reduction	Life-Cycle Reduction
<b>Electricity</b>				
CO2	586,203.48 kg	393,928.49 kg	192,274.99 kg	5,767,459.98 kg
SO2	1,628.06 kg	1,094.05 kg	534.00 kg	16,017.91 kg
NOx	510.70 kg	343.19 kg	167.51 kg	5,024.57 kg
<b>Natural Gas</b>				
CO2	226,502.05 kg	156,278.44 kg	70,223.61 kg	2,106,419.96 kg
SO2	1,827.94 kg	1,261.22 kg	566.73 kg	16,999.47 kg
NOx	190.03 kg	46.83 kg	143.21 kg	4,295.60 kg
<b>Total:</b>				
CO2	812,705.53 kg	550,206.93 kg	262,498.60 kg	7,873,879.93 kg
SO2	3,456.00 kg	2,355.27 kg	1,100.73 kg	33,017.39 kg
NOx	700.73 kg	390.01 kg	310.71 kg	9,320.17 kg

## NIST BLCC 5.3-15: Comparative Analysis

Consistent with Federal Life Cycle Cost Methodology in OMB Circular A-94

### Base Case: Baseline - VAV

### Alternative: Option 3A - Static Plate ERV CB Full AC Displacement

#### General Information

**File Name:** C:\Users\keith\_lane\BLCC 5\projects\Fuller Middle School.xml  
**Date of Study:** Thu Jul 26 10:11:16 EDT 2018  
**Project Name:** Fuller Middle School  
**Project Location:** Massachusetts  
**Analysis Type:** OMB Analysis, Non-Energy Project  
**Analysis Purpose:** Public Investment or Regulatory Analysis  
**Analyst:** Keith Lane  
**Base Date:** September 1, 2020  
**Service Date:** September 1, 2020  
**Study Period:** 30 years 0 months(September 1, 2020 through August 31, 2050)  
**Discount Rate:** 4.3%  
**Discounting Convention:** End-of-Year

#### Comparison of Present-Value Costs

##### PV Life-Cycle Cost

	Base Case	Alternative	Savings from Alternative
<b>Initial Investment Costs:</b>			
Capital Requirements as of Base Date	\$7,490,250	\$7,319,100	\$171,150
<b>Future Costs:</b>			
Energy Consumption Costs	\$5,030,611	\$3,449,851	\$1,580,760
Energy Demand Charges	\$0	\$0	\$0
Energy Utility Rebates	\$0	\$0	\$0
Water Costs	\$0	\$0	\$0
Recurring and Non-Recurring OM&R Costs	\$675,485	\$611,127	\$64,358
Capital Replacements	\$0	\$0	\$0
Residual Value at End of Study Period	\$0	\$0	\$0
	-----	-----	-----
Subtotal (for Future Cost Items)	\$5,706,095	\$4,060,978	\$1,645,118
	-----	-----	-----
<b>Total PV Life-Cycle Cost</b>	<b>\$13,196,345</b>	<b>\$11,380,078</b>	<b>\$1,816,268</b>

#### Net Savings from Alternative Compared with Base Case

PV of Non-Investment Savings \$1,645,118

- Increased Total Investment      -\$171,150

-----

Net Savings                              \$1,816,268

**NOTE: Meaningful SIR, AIRR and Payback can not be computed unless incremental savings and total savings are both positive.**

## Energy Savings Summary

### Energy Savings Summary (in stated units)

Energy Type	-----Average Base Case	Annual Alternative	Consumption----- Savings	Life-Cycle Savings
Electricity	951,950.0 kWh	652,030.0 kWh	299,920.0 kWh	8,996,368.3 kWh
Natural Gas	42,879.0 Therm	29,596.0 Therm	13,283.0 Therm	398,435.4 Therm

### Energy Savings Summary (in MBtu)

Energy Type	-----Average Base Case	Annual Alternative	Consumption----- Savings	Life-Cycle Savings
Electricity	3,248.2 MBtu	2,224.8 MBtu	1,023.4 MBtu	30,696.9 MBtu
Natural Gas	4,287.9 MBtu	2,959.6 MBtu	1,328.3 MBtu	39,843.7 MBtu

## Emissions Reduction Summary

Energy Type	-----Average Base Case	Annual Alternative	Emissions----- Reduction	Life-Cycle Reduction
<b>Electricity</b>				
CO2	586,203.48 kg	401,515.05 kg	184,688.43 kg	5,539,894.30 kg
SO2	1,628.06 kg	1,115.12 kg	512.93 kg	15,385.90 kg
NOx	510.70 kg	349.80 kg	160.90 kg	4,826.31 kg
<b>Natural Gas</b>				
CO2	226,502.05 kg	156,336.54 kg	70,165.51 kg	2,104,677.02 kg
SO2	1,827.94 kg	1,261.69 kg	566.26 kg	16,985.41 kg
NOx	190.03 kg	46.84 kg	143.19 kg	4,295.08 kg
<b>Total:</b>				
CO2	812,705.53 kg	557,851.60 kg	254,853.93 kg	7,644,571.32 kg
SO2	3,456.00 kg	2,376.81 kg	1,079.19 kg	32,371.30 kg
NOx	700.73 kg	396.64 kg	304.09 kg	9,121.39 kg

## NIST BLCC 5.3-15: Comparative Analysis

Consistent with Federal Life Cycle Cost Methodology in OMB Circular A-94

### Base Case: Baseline - VAV

### Alternative: Option 3B - ACC Static Plate ERV CB Full AC Displacement

#### General Information

**File Name:** C:\Users\keith\_lane\BLCC 5\projects\Fuller Middle School.xml  
**Date of Study:** Thu Jul 26 10:11:37 EDT 2018  
**Project Name:** Fuller Middle School  
**Project Location:** Massachusetts  
**Analysis Type:** OMB Analysis, Non-Energy Project  
**Analysis Purpose:** Public Investment or Regulatory Analysis  
**Analyst:** Keith Lane  
**Base Date:** September 1, 2020  
**Service Date:** September 1, 2020  
**Study Period:** 30 years 0 months(September 1, 2020 through August 31, 2050)  
**Discount Rate:** 4.3%  
**Discounting Convention:** End-of-Year

#### Comparison of Present-Value Costs

##### PV Life-Cycle Cost

	Base Case	Alternative	Savings from Alternative
<b>Initial Investment Costs:</b>			
Capital Requirements as of Base Date	\$7,490,250	\$7,256,600	\$233,650
<b>Future Costs:</b>			
Energy Consumption Costs	\$5,030,611	\$3,429,231	\$1,601,380
Energy Demand Charges	\$0	\$0	\$0
Energy Utility Rebates	\$0	\$0	\$0
Water Costs	\$0	\$0	\$0
Recurring and Non-Recurring OM&R Costs	\$675,485	\$585,168	\$90,317
Capital Replacements	\$0	\$0	\$0
Residual Value at End of Study Period	\$0	\$0	\$0
	-----	-----	-----
Subtotal (for Future Cost Items)	\$5,706,095	\$4,014,399	\$1,691,697
	-----	-----	-----
<b>Total PV Life-Cycle Cost</b>	<b>\$13,196,345</b>	<b>\$11,270,999</b>	<b>\$1,925,347</b>

#### Net Savings from Alternative Compared with Base Case

PV of Non-Investment Savings \$1,691,697

- Increased Total Investment      -\$233,650

-----

Net Savings                              \$1,925,347

**NOTE: Meaningful SIR, AIRR and Payback can not be computed unless incremental savings and total savings are both positive.**

## Energy Savings Summary

### Energy Savings Summary (in stated units)

Energy Type	-----Average Base Case	Annual Alternative	Consumption----- Savings	Life-Cycle Savings
Electricity	951,950.0 kWh	647,400.0 kWh	304,550.0 kWh	9,135,249.3 kWh
Natural Gas	42,879.0 Therm	29,596.0 Therm	13,283.0 Therm	398,435.4 Therm

### Energy Savings Summary (in MBtu)

Energy Type	-----Average Base Case	Annual Alternative	Consumption----- Savings	Life-Cycle Savings
Electricity	3,248.2 MBtu	2,209.0 MBtu	1,039.2 MBtu	31,170.8 MBtu
Natural Gas	4,287.9 MBtu	2,959.6 MBtu	1,328.3 MBtu	39,843.7 MBtu

## Emissions Reduction Summary

Energy Type	-----Average Base Case	Annual Alternative	Emissions----- Reduction	Life-Cycle Reduction
<b>Electricity</b>				
CO2	586,203.48 kg	398,663.93 kg	187,539.54 kg	5,625,416.14 kg
SO2	1,628.06 kg	1,107.21 kg	520.85 kg	15,623.41 kg
NOx	510.70 kg	347.31 kg	163.38 kg	4,900.82 kg
<b>Natural Gas</b>				
CO2	226,502.05 kg	156,336.54 kg	70,165.51 kg	2,104,677.02 kg
SO2	1,827.94 kg	1,261.69 kg	566.26 kg	16,985.41 kg
NOx	190.03 kg	46.84 kg	143.19 kg	4,295.08 kg
<b>Total:</b>				
CO2	812,705.53 kg	555,000.48 kg	257,705.05 kg	7,730,093.16 kg
SO2	3,456.00 kg	2,368.89 kg	1,087.11 kg	32,608.82 kg
NOx	700.73 kg	394.16 kg	306.57 kg	9,195.90 kg

## NIST BLCC 5.3-15: Comparative Analysis

Consistent with Federal Life Cycle Cost Methodology in OMB Circular A-94

### Base Case: Baseline - VAV

### Alternative: Option 4 - Geothermal Static Plate ERV Full AC Displacement

#### General Information

**File Name:** C:\Users\keith\_lane\BLCC 5\projects\Fuller Middle School.xml  
**Date of Study:** Thu Jul 26 14:44:51 EDT 2018  
**Project Name:** Fuller Middle School  
**Project Location:** Massachusetts  
**Analysis Type:** OMB Analysis, Non-Energy Project  
**Analysis Purpose:** Public Investment or Regulatory Analysis  
**Analyst:** Keith Lane  
**Base Date:** September 1, 2020  
**Service Date:** September 1, 2020  
**Study Period:** 30 years 0 months(September 1, 2020 through August 31, 2050)  
**Discount Rate:** 4.3%  
**Discounting Convention:** End-of-Year

#### Comparison of Present-Value Costs

##### PV Life-Cycle Cost

	Base Case	Alternative	Savings from Alternative
<b>Initial Investment Costs:</b>			
Capital Requirements as of Base Date	\$7,490,250	\$10,119,500	-\$2,629,250
<b>Future Costs:</b>			
Energy Consumption Costs	\$5,030,611	\$4,095,504	\$935,107
Energy Demand Charges	\$0	\$0	\$0
Energy Utility Rebates	\$0	\$0	\$0
Water Costs	\$0	\$0	\$0
Recurring and Non-Recurring OM&R Costs	\$675,485	\$560,290	\$115,195
Capital Replacements	\$0	\$0	\$0
Residual Value at End of Study Period	\$0	\$0	\$0
	-----	-----	-----
Subtotal (for Future Cost Items)	\$5,706,095	\$4,655,794	\$1,050,301
	-----	-----	-----
<b>Total PV Life-Cycle Cost</b>	<b>\$13,196,345</b>	<b>\$14,775,294</b>	<b>-\$1,578,949</b>

#### Net Savings from Alternative Compared with Base Case

PV of Non-Investment Savings \$1,050,301



**- Increased Total Investment**      \$2,629,250

-----

**Net Savings**                              -\$1,578,949

## Savings-to-Investment Ratio (SIR)

SIR = 0.40

**SIR is lower than 1.0; project alternative is not cost effective.**

## Adjusted Internal Rate of Return

AIRR = 1.16%

**AIRR is lower than your discount rate; project alternative is not cost effective.**

## Payback Period

### Estimated Years to Payback (from beginning of Service Period)

**Simple Payback never reached during study period.**

**Discounted Payback never reached during study period.**

## Energy Savings Summary

### Energy Savings Summary (in stated units)

Energy Type	-----Average Base Case	Annual Alternative	Consumption----- Savings	Life-Cycle Savings
Electricity	951,950.0 kWh	861,810.0 kWh	90,140.0 kWh	2,703,829.8 kWh
Natural Gas	42,879.0 Therm	13,954.0 Therm	28,925.0 Therm	867,631.2 Therm

### Energy Savings Summary (in MBtu)

Energy Type	-----Average Base Case	Annual Alternative	Consumption----- Savings	Life-Cycle Savings
Electricity	3,248.2 MBtu	2,940.6 MBtu	307.6 MBtu	9,225.8 MBtu
Natural Gas	4,287.9 MBtu	1,395.4 MBtu	2,892.5 MBtu	86,763.4 MBtu

## Emissions Reduction Summary

Energy Type	-----Average Base Case	Annual Alternative	Emissions----- Reduction	Life-Cycle Reduction
<b>Electricity</b>				
CO2	586,203.48 kg	530,695.96 kg	55,507.52 kg	1,664,997.57 kg
SO2	1,628.06 kg	1,473.90 kg	154.16 kg	4,624.18 kg
NOx	510.70 kg	462.34 kg	48.36 kg	1,450.53 kg
<b>Natural Gas</b>				

<b>CO2</b>	226,502.05 kg	73,709.97 kg	152,792.08 kg	4,583,135.04 kg
<b>SO2</b>	1,827.94 kg	594.86 kg	1,233.08 kg	36,987.35 kg
<b>NOx</b>	190.03 kg	22.09 kg	167.95 kg	5,037.73 kg
<b>Total:</b>				
<b>CO2</b>	812,705.53 kg	604,405.92 kg	208,299.60 kg	6,248,132.61 kg
<b>SO2</b>	3,456.00 kg	2,068.76 kg	1,387.24 kg	41,611.53 kg
<b>NOx</b>	700.73 kg	484.42 kg	216.30 kg	6,488.26 kg

# **COST ESTIMATES**



**GARCIA • GALUSKA • DESOUSA**  
Consulting Engineers Inc.

370 Fauces Comer Road, Dartmouth, MA 02747-1217

<b>PROJECT:</b> Fuller Middle School					
<b>JOB NO:</b> 68001500					
<b>CLIENT:</b> Jonathan Levi Architects, Inc.					
<b>DATE:</b> 7/16/2018			<b>BY:</b> KL		
<b>Baseline - ASHRAE Std. 90.1-2010 CHW/HHW Coil VAV Air Handling Unit System</b>					
ITEM OF WORK	NO.	UNIT PRICE	AREA	PRICE/S.F.	TOTAL
VAV Box with Hot Water Reheat Coils	147	\$1,500			\$ 220,500
RTU-1: Classrooms, Band, Stage (NW) Full AC VAV w/ ERV	27,000 CFM	\$14.5/CFM			\$ 391,500
RTU-2: Classrooms, Media, Admin (NE) Full AC VAV w/ ERV	17,000 CFM	\$14.5/CFM			\$ 246,500
RTU-3: Classrooms, Cafe (SE) Full AC VAV w/ ERV	22,000 CFM	\$14.5/CFM			\$ 319,000
RTU-4: Classrooms, Café, Tech (SW) Full AC VAV w/ ERV	24,000 CFM	\$14.5/CFM			\$ 348,000
RTU-5: Admin.(S) Full AC VAV w/ ERV	7,500 CFM	\$14.5/CFM			\$ 108,750
RTU-6: Gym Full AC VAV w/ ERV	12,000 CFM	\$14.5/CFM			\$ 174,000
RTU-7: Auditorium, Stage Full AC VAV w/ ERV	12,000 CFM	\$14.5/CFM			\$ 174,000
RTU-8: Lockers 100% O.A. Overhead w/ ERV	3,000 CFM	\$15.5/CFM			\$ 46,500
MAU-1: Kitchen MAU	5,500 CFM	\$11/CFM			\$ 60,500
(4) 2,000 MBH 80% Code-Efficient Gas-Fired Boilers	4	\$35,000			\$ 140,000
Pumps (HHW) including VFD's	2	\$18,000			\$ 36,000
(2) 175 Ton (Code) High-Efficiency TurboCor Water-Cooled Chillers Plant and Cooling Towers	350 tons	\$1,500/ton			\$ 525,000
Pumps (CHW) including VFD's	2	\$22,500			\$ 45,000
HHW Piping & Insulation including Terminal Heating Units			150,000	\$4.75	\$ 712,500
CHW Piping & Insulation and Condensate Piping			150,000	\$3.25	\$ 487,500
Cooling Tower Pumps and VFDs	2	\$22,500			\$ 45,000
Cooling Tower CW Piping	1	\$30,000			\$ 30,000
Ductwork including GRD's, Dampers, & General Exhaust Systems			150,000	\$14.50	\$ 2,175,000
ATC/DDC Controls			150,000	\$5.25	\$ 787,500
Split System Ductless Cooling Units	3	\$7,500			\$ 22,500
Exhaust Fans (Misc. Areas)					\$ 20,000
HVAC General Conditions (as-builts, coordination, shop drawings, testing and balancing, Cx support, Project Management)			150,000	\$2.5	\$ 375,000
<b>TOTAL</b>					\$ 7,490,250
<b>TOTAL (\$/FT<sup>2</sup>)</b>					\$ 49.94

Cost estimates have been derived for system comparison purposes only. Estimates do not necessarily include HVAC systems and equipment that would typically be required for all system options studied; example: supplemental cooling systems for elevator machine rooms, tel/data rooms, etc. and radiation heating for unoccupied areas such as storage rooms, corridors, vestibules etc.



**GARCIA • GALUSKA • DESOUSA**  
Consulting Engineers Inc.

370 Fauces Comer Road, Dartmouth, MA 02747-1217

**PROJECT:** Fuller Middle School

**JOB NO:** 68001500

**CLIENT:** Jonathan Levi Architects, Inc.

**DATE:** 7/16/2018 **BY:** KL

**Option 1 - CHW/HHW Coil VAV Air Handling Unit System**

ITEM OF WORK	NO.	UNIT PRICE	AREA	PRICE/S.F.	TOTAL
VAV Box with Hot Water Reheat Coils	147	\$1,500			\$ 220,500
RTU-1: Classrooms, Band, Stage (NW) Full AC VAV w/ ERV & DCV	27,000 CFM	\$14.5/CFM			\$ 391,500
RTU-2: Classrooms, Media, Admin (NE) Full AC VAV w/ ERV & DCV	17,000 CFM	\$14.5/CFM			\$ 246,500
RTU-3: Classrooms, Cafe (SE) Full AC VAV w/ ERV & DCV	22,000 CFM	\$14.5/CFM			\$ 319,000
RTU-4: Classrooms, Café, Tech (SW) Full AC VAV w/ ERV & DCV	24,000 CFM	\$14.5/CFM			\$ 348,000
RTU-5: Admin.(S) Full AC VAV w/ ERV & DCV	7,500 CFM	\$14.5/CFM			\$ 108,750
RTU-6: Gym Full AC VAV w/ ERV & DCV	12,000 CFM	\$14.5/CFM			\$ 174,000
RTU-7: Auditorium, Stage Full AC VAV w/ ERV & DCV	12,000 CFM	\$14.5/CFM			\$ 174,000
RTU-8: Lockers 100% O.A. Overhead w/ ERV	3,000 CFM	\$15.5/CFM			\$ 46,500
MAU-1: Kitchen MAU	5,500 CFM	\$11/CFM			\$ 60,500
(4) 2,000 MBH High-Efficiency Gas-Fired Condensing Boilers	4	\$49,000			\$ 196,000
Pumps (HHW) including VFD's	2	\$18,000			\$ 36,000
(2) 175 Ton (Code) High-Efficiency TurboCor Water-Cooled Chillers Plant and Cooling Towers	350 tons	\$1,500/ton			\$ 525,000
Pumps (CHW) including VFD's	2	\$22,500			\$ 45,000
HHW Piping & Insulation including Terminal Heating Units			150,000	\$4.75	\$ 712,500
CHW Piping & Insulation and Condensate Piping			150,000	\$3.25	\$ 487,500
Cooling Tower Pumps and VFDs	2	\$22,500			\$ 45,000
Cooling Tower CW Piping	1	\$30,000			\$ 30,000
Ductwork including GRD's, Dampers, & General Exhaust Systems			150,000	\$14.50	\$ 2,175,000
ATC/DDC Controls			150,000	\$5.50	\$ 825,000
Split System Ductless Cooling Units	3	\$7,500			\$ 22,500
Exhaust Fans (Misc. Areas)					\$ 32,000
HVAC General Conditions (as-builts, coordination, shop drawings, testing and balancing, Cx support, Project Management)			150,000	\$2.5	\$ 375,000
<b>TOTAL</b>					\$ 7,595,750
<b>TOTAL (\$/FT<sup>2</sup>)</b>					\$ 50.64

Cost estimates have been derived for system comparison purposes only. Estimates do not necessarily include HVAC systems and equipment that would typically be required for all system options studied; example: supplemental cooling systems for elevator machine rooms, tel/data rooms, etc. and radiation heating for unoccupied areas such as storage rooms, corridors, vestibules etc.



**GARCIA - GALUSKA - DESOUSA**  
Consulting Engineers Inc.

370 Faunce Corner Road, Dartmouth, MA 02747-1217

<b>PROJECT:</b> Fuller Middle School
<b>JOB NO:</b> 68001500
<b>CLIENT:</b> Jonathan Levi Architects, Inc.
<b>DATE:</b> 7/26/2018
<b>BY:</b> KL

**Option 2 - VAV Full AC Displacement Ventilation Systems**

ITEM OF WORK	NO.	UNIT PRICE	AREA	PRICE/S.F.	TOTAL
AC Displacement Diffuser Assemblies	78	\$1,150			\$ 89,700
Small Displacement Diffuser Assemblies (Admin.)	51	\$850			\$ 43,350
Large AC Displacement Diffuser Assemblies	31	\$1,150			\$ 35,650
VAV Box with Demand Ventilation Controls	134	\$1,200			\$ 160,800
RTU-1: Classrooms, Band, Stage (NW) Full AC Displacement VAV w/ ERV & DCV	23,000 CFM	\$14.5/CFM			\$ 333,500
RTU-2: Classrooms, Media, Admin (NE) Full AC Displacement VAV w/ ERV & DCV	14,000 CFM	\$14.5/CFM			\$ 203,000
RTU-3: Classrooms, Cafe (SE) Full AC Displacement VAV w/ ERV & DCV	18,000 CFM	\$14.5/CFM			\$ 261,000
RTU-4: Classrooms, Cafe, Tech (SW) Full AC Displacement VAV w/ ERV & DCV	21,000 CFM	\$14.5/CFM			\$ 304,500
RTU-5: Admin.(S) Full AC Displacement VAV w/ ERV & DCV	6,000 CFM	\$14.5/CFM			\$ 87,000
RTU-6: Gym Dehumid Displacement VAV w/ ERV & DCV	11,000 CFM	\$14.5/CFM			\$ 159,500
RTU-7: Auditorium, Stage Full AC Displacement VAV w/ ERV & DCV	11,000 CFM	\$14.5/CFM			\$ 159,500
RTU-8: Lockers 100% O.A. Overhead w/ ERV	3,000 CFM	\$15.5/CFM			\$ 46,500
MAU-1: Kitchen MAU	5,500 CFM	\$11/CFM			\$ 60,500
(4) 2,000 MBH High-Efficiency Gas-Fired Condensing Boilers	4	\$49,000			\$ 196,000
Pumps (HHW) including VFD's	2	\$18,000			\$ 36,000
(2) 175 Ton High-Efficiency TurboCor Water-Cooled Chillers Plant and Cooling Towers	350 tons	\$1,500/ton			\$ 525,000
Pumps (CHW) including VFD's	2	\$22,500			\$ 45,000
Cooling Tower Pumps and VFDs	2	\$22,500			\$ 45,000
Cooling Tower CW Piping	1	\$30,000			\$ 30,000
HHW Piping & Insulation including Terminal Heating Units			150,000	\$5.50	\$ 825,000
CHW Piping & Insulation and Condensate Piping			150,000	\$3.25	\$ 487,500
Ductwork including GRD's, Dampers, & General Exhaust Systems			150,000	\$13.00	\$ 1,950,000
ATC/DDC Controls			150,000	\$5.50	\$ 825,000
Split System Ductless Cooling Units	3	\$7,500			\$ 22,500
Exhaust Fans (Misc. Areas)					\$ 20,000
HVAC General Conditions (as-builts, coordination, shop drawings, testing and balancing, Cx support, Project Management)			150,000	\$2.5	\$ 375,000
<b>TOTAL</b>					\$ 7,326,500
<b>TOTAL (\$/FT<sup>2</sup>)</b>					\$ 48.84

Cost estimates have been derived for system comparison purposes only. Estimates do not necessarily include HVAC systems and equipment that would typically be required for all system options studied; example: supplemental cooling systems for elevator machine rooms, tel/data rooms, etc. and radiation heating for unoccupied areas such as storage rooms, corridors, vestibules etc.



**GARCIA - GALUSKA - DESOUSA**  
Consulting Engineers Inc.

370 Faunce Corner Road, Dartmouth, MA 02747-1217

**PROJECT:** Fuller Middle School

**JOB NO:** 68001500

**CLIENT:** Jonathan Levi Architects, Inc.

**DATE:** 7/26/2018 **BY:** KL

**Option 2a - Static Plate Energy Recovery VAV Full AC Displacement Ventilation Systems**

ITEM OF WORK	NO.	UNIT PRICE	AREA	PRICE/S.F.	TOTAL
AC Displacement Diffuser Assemblies	78	\$1,150			\$ 89,700
Small Displacement Diffuser Assemblies (Admin.)	51	\$850			\$ 43,350
Large AC Displacement Diffuser Assemblies	31	\$1,150			\$ 35,650
VAV Box with Demand Ventilation Controls	134	\$1,200			\$ 160,800
RTU-1: Classrooms, Band, Stage (NW) Full AC Displacement VAV w/ Static Plate ERV & DCV	23,000 CFM	\$15/CFM			\$ 345,000
RTU-2: Classrooms, Media, Admin (NE) Full AC Displacement VAV w/ Static Plate ERV & DCV	14,000 CFM	\$15/CFM			\$ 210,000
RTU-3: Classrooms, Cafe (SE) Full AC Displacement VAV w/ Static Plate ERV & DCV	18,000 CFM	\$15/CFM			\$ 270,000
RTU-4: Classrooms, Cafe, Tech (SW) Full AC Displacement VAV w/ Static Plate ERV & DCV	21,000 CFM	\$15/CFM			\$ 315,000
RTU-5: Admin.(S) Full AC Displacement VAV w/ Static Plate ERV & DCV	6,000 CFM	\$15/CFM			\$ 90,000
RTU-6: Gym Dehumid Displacement VAV w/ Static Plate ERV & DCV	11,000 CFM	\$15/CFM			\$ 165,000
RTU-7: Auditorium, Stage Full AC Displacement VAV w/ Static Plate ERV & DCV	11,000 CFM	\$15/CFM			\$ 165,000
RTU-8: Lockers 100% O.A. Overhead w/ Static Plate ERV	3,000 CFM	\$16/CFM			\$ 48,000
MAU-1: Kitchen MAU	5,500 CFM	\$11/CFM			\$ 60,500
(4) 2,000 MBH High-Efficiency Gas-Fired Condensing Boilers	4	\$49,000			\$ 196,000
Pumps (HHW) including VFD's	2	\$18,000			\$ 36,000
(2) 175 Ton High-Efficiency TurboCor Water-Cooled Chillers Plant and Cooling Towers	350 tons	\$1,500/ton			\$ 525,000
Pumps (CHW) including VFD's	2	\$22,500			\$ 45,000
Cooling Tower Pumps and VFDs	2	\$22,500			\$ 45,000
Cooling Tower CW Piping	1	\$30,000			\$ 30,000
HHW Piping & Insulation including Terminal Heating Units			150,000	\$5.50	\$ 825,000
CHW Piping & Insulation and Condensate Piping			150,000	\$3.25	\$ 487,500
Ductwork including GRD's, Dampers, & General Exhaust Systems			150,000	\$13.00	\$ 1,950,000
ATC/DDC Controls			150,000	\$5.50	\$ 825,000
Split System Ductless Cooling Units	3	\$7,500			\$ 22,500
Exhaust Fans (Misc. Areas)					\$ 20,000
HVAC General Conditions (as-builts, coordination, shop drawings, testing and balancing, Cx support, Project Management)			150,000	\$2.5	\$ 375,000
<b>TOTAL</b>					\$ 7,380,000
<b>TOTAL (\$/FT<sup>2</sup>)</b>					\$ 49.20

Cost estimates have been derived for system comparison purposes only. Estimates do not necessarily include HVAC systems and equipment that would typically be required for all system options studied; example: supplemental cooling systems for elevator machine rooms, tel/data rooms, etc. and radiation heating for unoccupied areas such as storage rooms, corridors, vestibules etc.



**GARCIA • GALUSKA • DESOUSA**  
Consulting Engineers Inc.

370 Fauce Comer Road, Dartmouth, MA 02747-1217

**PROJECT:** Fuller Middle School

**JOB NO:** 68001500

**CLIENT:** Jonathan Levi Architects, Inc.

**DATE:** 7/26/2018 **BY:** KL

**Option 2b - Air-Cooled Chiller Static Plate Energy Recovery VAV Full AC Displacement Ventilation Systems**

ITEM OF WORK	NO.	UNIT PRICE	AREA	PRICE/S.F.	TOTAL
AC Displacement Diffuser Assemblies	78	\$1,150			\$ 89,700
Small Displacement Diffuser Assemblies (Admin.)	51	\$850			\$ 43,350
Large AC Displacement Diffuser Assemblies	31	\$1,150			\$ 35,650
VAV Box with Demand Ventilation Controls	134	\$1,200			\$ 160,800
RTU-1: Classrooms, Band, Stage (NW) Full AC Displacement VAV w/ Static Plate ERV & DCV	23,000 CFM	\$15/CFM			\$ 345,000
RTU-2: Classrooms, Media, Admin (NE) Full AC Displacement VAV w/ Static Plate ERV & DCV	14,000 CFM	\$15/CFM			\$ 210,000
RTU-3: Classrooms, Cafe (SE) Full AC Displacement VAV w/ Static Plate ERV & DCV	18,000 CFM	\$15/CFM			\$ 270,000
RTU-4: Classrooms, Café, Tech (SW) Full AC Displacement VAV w/ Static Plate ERV & DCV	21,000 CFM	\$15/CFM			\$ 315,000
RTU-5: Admin.(S) Full AC Displacement VAV w/ Static Plate ERV & DCV	6,000 CFM	\$15/CFM			\$ 90,000
RTU-6: Gym Dehumid Displacement VAV w/ Static Plate ERV & DCV	11,000 CFM	\$15/CFM			\$ 165,000
RTU-7: Auditorium, Stage Full AC Displacement VAV w/ Static Plate ERV & DCV	11,000 CFM	\$15/CFM			\$ 165,000
RTU-8: Lockers 100% O.A. Overhead w/ Static Plate ERV	3,000 CFM	\$16/CFM			\$ 48,000
MAU-1: Kitchen MAU	5,500 CFM	\$11/CFM			\$ 60,500
(4) 2,000 MBH High-Efficiency Gas-Fired Condensing Boilers	4	\$49,000			\$ 196,000
Pumps (HHW) including VFD's	2	\$18,000			\$ 36,000
(2) 175 Ton High-Efficiency TurboCor Air-Cooled Chillers Plant	350 tons	\$1,450/ton			\$ 507,500
Pumps (CHW) including VFD's	2	\$22,500			\$ 45,000
Exterior CHW Piping	1	\$30,000			\$ 30,000
HHW Piping & Insulation including Terminal Heating Units			150,000	\$5.50	\$ 825,000
CHW Piping & Insulation and Condensate Piping			150,000	\$3.25	\$ 487,500
Ductwork including GRD's, Dampers, & General Exhaust Systems			150,000	\$13.00	\$ 1,950,000
ATC/DDC Controls			150,000	\$5.50	\$ 825,000
Split System Ductless Cooling Units	3	\$7,500			\$ 22,500
Exhaust Fans (Misc. Areas)					\$ 20,000
HVAC General Conditions (as-builts, coordination, shop drawings, testing and balancing, Cx support, Project Management)			150,000	\$2.5	\$ 375,000
<b>TOTAL</b>					\$ 7,317,500
<b>TOTAL (\$/FT<sup>2</sup>)</b>					\$ 48.78

Cost estimates have been derived for system comparison purposes only. Estimates do not necessarily include HVAC systems and equipment that would typically be required for all system options studied; example: supplemental cooling systems for elevator machine rooms, tel/data rooms, etc. and radiation heating for unoccupied areas such as storage rooms, corridors, vestibules etc.





**GARCIA - GALUSKA - DESOUSA**  
Consulting Engineers Inc.

370 Faunce Corner Road, Dartmouth, MA 02747-1217

<b>PROJECT:</b> Fuller Middle School
<b>JOB NO:</b> 68001500
<b>CLIENT:</b> Jonathan Levi Architects, Inc.
<b>DATE:</b> 7/26/2018
<b>BY:</b> KL

<b>Option 3 - 100% O.A. VAV Displacement Ventilation Systems with Passive Chilled Beam Full AC</b>					
ITEM OF WORK	NO.	UNIT PRICE	AREA	PRICE/S.F.	TOTAL
Displacement Diffuser Assemblies	78	\$950			\$ 74,100
Small Displacement Diffuser Assemblies (Admin.)	51	\$850			\$ 43,350
Large AC Displacement Diffuser Assemblies	31	\$1,150			\$ 35,650
VAV Box with Demand Ventilation Controls	134	\$1,200			\$ 160,800
RTU-1: Classrooms, Band, Stage (NW) Displacement VAV w/ ERV & DCV w/ CB Full AC	17,500 CFM	\$14.5/CFM			\$ 253,750
RTU-2: Classrooms, Media, Admin (NE) Displacement VAV w/ ERV & DCV w/ CB Full AC	11,000 CFM	\$14.5/CFM			\$ 159,500
RTU-3: Classrooms, Cafe (SE) Displacement VAV w/ ERV & DCV w/ CB Full AC	15,000 CFM	\$14.5/CFM			\$ 217,500
RTU-4: Classrooms, Café, Tech (SW) Displacement VAV w/ ERV & DCV w/ CB Full AC	16,000 CFM	\$14.5/CFM			\$ 232,000
RTU-5: Admin (S) Displacement VAV w/ ERV & DCV w/ CB Full AC	4,200 CFM	\$15.5/CFM			\$ 65,100
RTU-6: Gym Full AC Displacement VAV w/ ERV & DCV	11,000 CFM	\$14.5/CFM			\$ 159,500
RTU-7: Auditorium, Stage Full AC Displacement VAV w/ ERV & DCV	11,000 CFM	\$14.5/CFM			\$ 159,500
RTU-8: Lockers 100% O.A. Overhead w/ ERV	3,000 CFM	\$15.5/CFM			\$ 46,500
MAU-1: Kitchen MAU	5,500 CFM	\$11/CFM			\$ 60,500
(4) 2,000 MBH High-Efficiency Gas-Fired Condensing Boilers	4	\$49,000			\$ 196,000
Pumps (HHW) including VFD's	2	\$18,000			\$ 36,000
(2) 175 Ton High-Efficiency TurboCor Water-Cooled Chillers Plant and Cooling Towers	350 tons	\$1,500/ton			\$ 525,000
Pumps (CHW) including VFD's	2	\$22,500			\$ 45,000
Cooling Tower Pumps and VFDs	2	\$22,500			\$ 45,000
Cooling Tower CW Piping	1	\$30,000			\$ 30,000
HHW Piping & Insulation including Terminal Heating Units			150,000	\$5.50	\$ 825,000
Additional Passive Radiant Heating/Cooling Panels					\$ 75,000
CHW Piping & Insulation and Condensate Piping including Terminal Cooling Units (upcharge to radiant heating panels)			150,000	\$6.25	\$ 937,500
Ductwork including GRD's, Dampers, & General Exhaust Systems			150,000	\$10.25	\$ 1,537,500
ATC/DDC Controls			150,000	\$6.25	\$ 937,500
Split System Ductless Cooling Units	3	\$7,500			\$ 22,500
Exhaust Fans (Misc. Areas)					\$ 20,000
HVAC General Conditions (as-builts, coordination, shop drawings, testing and balancing, Cx support, Project Management)			150,000	\$2.5	\$ 375,000
<b>TOTAL</b>					\$ 7,274,750
<b>TOTAL (\$/FT<sup>2</sup>)</b>					\$ 48.50

Cost estimates have been derived for system comparison purposes only. Estimates do not necessarily include HVAC systems and equipment that would typically be required for all system options studied; example: supplemental cooling systems for elevator machine rooms, tel/data rooms, etc. and radiation heating for unoccupied areas such as storage rooms, corridors, vestibules etc.



**GARCIA - GALUSKA - DESOUSA**  
Consulting Engineers Inc.

370 Faunce Corner Road, Dartmouth, MA 02747-1217

<b>PROJECT:</b> Fuller Middle School
<b>JOB NO:</b> 68001500
<b>CLIENT:</b> Jonathan Levi Architects, Inc.
<b>DATE:</b> 7/26/2018
<b>BY:</b> KL

**Option 3a - Static Plate Energy Recovery 100% O.A. VAV Displacement Ventilation Systems with Passive Chilled Beam Full AC**

ITEM OF WORK	NO.	UNIT PRICE	AREA	PRICE/S.F.	TOTAL
Displacement Diffuser Assemblies	78	\$950			\$ 74,100
Small Displacement Diffuser Assemblies (Admin.)	51	\$850			\$ 43,350
Large AC Displacement Diffuser Assemblies	31	\$1,150			\$ 35,650
VAV Box with Demand Ventilation Controls	134	\$1,200			\$ 160,800
RTU-1: Classrooms, Band, Stage (NW) Displacement VAV w/ Static Plate ERV & DCV w/ CB Full AC	17,500 CFM	\$15/CFM			\$ 262,500
RTU-2: Classrooms, Media, Admin (NE) Displacement VAV w/ Static Plate ERV & DCV w/ CB Full AC	11,000 CFM	\$15/CFM			\$ 165,000
RTU-3: Classrooms, Cafe (SE) Displacement VAV w/ Static Plate ERV & DCV w/ CB Full AC	15,000 CFM	\$15/CFM			\$ 225,000
RTU-4: Classrooms, Cafe, Tech (SW) Displacement VAV w/ Static Plate ERV & DCV w/ CB Full AC	16,000 CFM	\$15/CFM			\$ 240,000
RTU-5: Admin.(S) Displacement VAV w/ Static Plate ERV & DCV w/ CB Full AC	4,200 CFM	\$16/CFM			\$ 67,200
RTU-6: Gym Full AC Displacement VAV w/ Static Plate ERV & DCV	11,000 CFM	\$15/CFM			\$ 165,000
RTU-7: Auditorium, Stage Full AC Displacement VAV w/ Static Plate ERV & DCV	11,000 CFM	\$15/CFM			\$ 165,000
RTU-8: Lockers 100% O.A. Overhead w/ Static Plate ERV	3,000 CFM	\$16/CFM			\$ 48,000
MAU-1: Kitchen MAU	5,500 CFM	\$11/CFM			\$ 60,500
(4) 2,000 MBH High-Efficiency Gas-Fired Condensing Boilers	4	\$49,000			\$ 196,000
Pumps (HHW) including VFD's	2	\$18,000			\$ 36,000
(2) 175 Ton High-Efficiency TurboCor Water-Cooled Chillers Plant and Cooling Towers	350 tons	\$1,500/ton			\$ 525,000
Pumps (CHW) including VFD's	2	\$22,500			\$ 45,000
Cooling Tower Pumps and VFDs	2	\$22,500			\$ 45,000
Cooling Tower CW Piping	1	\$30,000			\$ 30,000
HHW Piping & Insulation including Terminal Heating Units			150,000	\$5.50	\$ 825,000
Additional Passive Radiant Heating/Cooling Panels					\$ 75,000
CHW Piping & Insulation and Condensate Piping including Terminal Cooling Units (upcharge to radiant heating panels)			150,000	\$6.25	\$ 937,500
Ductwork including GRD's, Dampers, & General Exhaust Systems			150,000	\$10.25	\$ 1,537,500
ATC/DDC Controls			150,000	\$6.25	\$ 937,500
Split System Ductless Cooling Units	3	\$7,500			\$ 22,500
Exhaust Fans (Misc. Areas)					\$ 20,000
HVAC General Conditions (as-builts, coordination, shop drawings, testing and balancing, Cx support, Project Management)			150,000	\$2.5	\$ 375,000
<b>TOTAL</b>					\$ 7,319,100
<b>TOTAL (\$/FT<sup>2</sup>)</b>					\$ 48.79

Cost estimates have been derived for system comparison purposes only. Estimates do not necessarily include HVAC systems and equipment that would typically be required for all system options studied; example: supplemental cooling systems for elevator machine rooms, tel/data rooms, etc. and radiation heating for unoccupied areas such as storage rooms, corridors, vestibules etc.



**GARCIA - GALUSKA - DESOUSA**  
Consulting Engineers Inc.

370 Faunce Corner Road, Dartmouth, MA 02747-1217

<b>PROJECT:</b> Fuller Middle School
<b>JOB NO:</b> 68001500
<b>CLIENT:</b> Jonathan Levi Architects, Inc.

**Option 3b - Air-Cooled Chiller Static Plate Energy Recovery  
100% O.A. VAV Displacement Ventilation Systems with  
Passive Chilled Beam Full AC**

<b>DATE:</b> 7/26/2018	<b>BY:</b> KL
------------------------	---------------

ITEM OF WORK	NO.	UNIT PRICE	AREA	PRICE/S.F.	TOTAL
Displacement Diffuser Assemblies	78	\$950			\$ 74,100
Small Displacement Diffuser Assemblies (Admin.)	51	\$850			\$ 43,350
Large AC Displacement Diffuser Assemblies	31	\$1,150			\$ 35,650
VAV Box with Demand Ventilation Controls	134	\$1,200			\$ 160,800
RTU-1: Classrooms, Band, Stage (NW) Displacement VAV w/ Static Plate ERV & DCV w/ CB Full AC	17,500 CFM	\$15/CFM			\$ 262,500
RTU-2: Classrooms, Media, Admin (NE) Displacement VAV w/ Static Plate ERV & DCV w/ CB Full AC	11,000 CFM	\$15/CFM			\$ 165,000
RTU-3: Classrooms, Cafe (SE) Displacement VAV w/ Static Plate ERV & DCV w/ CB Full AC	15,000 CFM	\$15/CFM			\$ 225,000
RTU-4: Classrooms, Cafe, Tech (SW) Displacement VAV w/ Static Plate ERV & DCV w/ CB Full AC	16,000 CFM	\$15/CFM			\$ 240,000
RTU-5: Admin.(S) Displacement VAV w/ Static Plate ERV & DCV w/ CB Full AC	4,200 CFM	\$16/CFM			\$ 67,200
RTU-6: Gym Full AC Displacement VAV w/ Static Plate ERV & DCV	11,000 CFM	\$15/CFM			\$ 165,000
RTU-7: Auditorium, Stage Full AC Displacement VAV w/ Static Plate ERV & DCV	11,000 CFM	\$15/CFM			\$ 165,000
RTU-8: Lockers 100% O.A. Overhead w/ Static Plate ERV	3,000 CFM	\$16/CFM			\$ 48,000
MAU-1: Kitchen MAU	5,500 CFM	\$11/CFM			\$ 60,500
(4) 2,000 MBH High-Efficiency Gas-Fired Condensing Boilers	4	\$49,000			\$ 196,000
Pumps (HHW) including VFD's	2	\$18,000			\$ 36,000
(2) 175 Ton High-Efficiency TurboCor Air-Cooled Chillers Plant	350 tons	\$1,450/ton			\$ 507,500
Pumps (CHW) including VFD's	2	\$22,500			\$ 45,000
Exterior CHW Piping	1	\$30,000			\$ 30,000
HHW Piping & Insulation including Terminal Heating Units			150,000	\$5.50	\$ 825,000
Additional Passive Radiant Heating/Cooling Panels					\$ 75,000
CHW Piping & Insulation and Condensate Piping including Terminal Cooling Units (upcharge to radiant heating panels)			150,000	\$6.25	\$ 937,500
Ductwork including GRD's, Dampers, & General Exhaust Systems			150,000	\$10.25	\$ 1,537,500
ATC/DDC Controls			150,000	\$6.25	\$ 937,500
Split System Ductless Cooling Units	3	\$7,500			\$ 22,500
Exhaust Fans (Misc. Areas)					\$ 20,000
HVAC General Conditions (as-builts, coordination, shop drawings, testing and balancing, Cx support, Project Management)			150,000	\$2.5	\$ 375,000
<b>TOTAL</b>					\$ 7,256,600
<b>TOTAL (\$/FT<sup>2</sup>)</b>					\$ 48.38

Cost estimates have been derived for system comparison purposes only. Estimates do not necessarily include HVAC systems and equipment that would typically be required for all system options studied; example: supplemental cooling systems for elevator machine rooms, tel/data rooms, etc. and radiation heating for unoccupied areas such as storage rooms, corridors, vestibules etc.



**GARCIA • GALUSKA • DESOUSA**  
Consulting Engineers Inc.

370 Faunce Corner Road, Dartmouth, MA 02747-1217

PROJECT: Fuller Middle School

JOB NO: 68001500

CLIENT: Jonathan Levi Architects, Inc.

DATE: 7/26/2018

BY: KL

**Option 4 - Geothermal Plant Static Plate Energy Recovery VAV Full AC Displacement Ventilation Systems**

ITEM OF WORK	NO.	UNIT PRICE	AREA	PRICE/S.F.	TOTAL
AC Displacement Diffuser Assemblies	78	\$1,150			\$ 89,700
Small Displacement Diffuser Assemblies (Admin.)	51	\$850			\$ 43,350
Large AC Displacement Diffuser Assemblies	31	\$1,150			\$ 35,650
VAV Box with Demand Ventilation Controls	134	\$1,200			\$ 160,800
RTU-1: Classrooms, Band, Stage (NW) Full AC Displacement VAV w/ Static Plate ERV & DCV	23,000 CFM	\$15/CFM			\$ 345,000
RTU-2: Classrooms, Media, Admin (NE) Full AC Displacement VAV w/ Static Plate ERV & DCV	14,000 CFM	\$15/CFM			\$ 210,000
RTU-3: Classrooms, Cafe (SE) Full AC Displacement VAV w/ Static Plate ERV & DCV	18,000 CFM	\$15/CFM			\$ 270,000
RTU-4: Classrooms, Café, Tech (SW) Full AC Displacement VAV w/ Static Plate ERV & DCV	21,000 CFM	\$15/CFM			\$ 315,000
RTU-5: Admin (S) Full AC Displacement VAV w/ Static Plate ERV & DCV	6,000 CFM	\$15/CFM			\$ 90,000
RTU-6: Gym Dehumid Displacement VAV w/ Static Plate ERV & DCV	11,000 CFM	\$15/CFM			\$ 165,000
RTU-7: Auditorium, Stage Full AC Displacement VAV w/ Static Plate ERV & DCV	11,000 CFM	\$15/CFM			\$ 165,000
RTU-8: Lockers 100% O.A. Overhead w/ Static Plate ERV	3,000 CFM	\$16/CFM			\$ 48,000
MAU-1: Kitchen MAU	5,500 CFM	\$11/CFM			\$ 60,500
(2) 2,000 MBH High-Efficiency Gas-Fired Condensing Boilers	2	\$49,000			\$ 98,000
Pumps (HHW) including VFD's	2	\$18,000			\$ 36,000
High-Efficiency Water-to-Water Source Heat Pump Chiller Plant	350 tons	\$1,250/ton			\$ 437,500
Geothermal System Glycol Feed & Water Treatment System	1	\$30,000			\$ 30,000
Pumps (CHW) including VFD's	2	\$22,500			\$ 45,000
Pumps (Geo) including VFD's	2	\$22,500			\$ 45,000
Geothermal CW Piping Mains	1	\$50,000			\$ 50,000
500' Deep Closed Loop Geothermal Wells (350 Tons total capacity) including Underground Piping, Coring, Sleeves, etc	140	\$20,000			\$ 2,800,000
HHW Piping & Insulation including Terminal Heating Units			150,000	\$5.50	\$ 825,000
CHW Piping & Insulation and Condensate Piping			150,000	\$3.25	\$ 487,500
Ductwork including GRD's, Dampers, & General Exhaust Systems			150,000	\$13.00	\$ 1,950,000
ATC/DDC Controls			150,000	\$6.00	\$ 900,000
Split System Ductless Cooling Units	3	\$7,500			\$ 22,500
Exhaust Fans (Misc. Areas)					\$ 20,000
HVAC General Conditions (as-builts, coordination, shop drawings, testing and balancing, Cx support, Project Management)			150,000	\$2.5	\$ 375,000
<b>TOTAL</b>					\$ 10,119,500
<b>TOTAL (\$/FT<sup>2</sup>)</b>					\$ 67.46

Cost estimates have been derived for system comparison purposes only. Estimates do not necessarily include HVAC systems and equipment that would typically be required for all system options studied; example: supplemental cooling systems for elevator machine rooms, tel/data rooms, etc. and radiation heating for unoccupied areas such as storage rooms, corridors, vestibules etc.



**Fuller Middle School - Annual Maintenance Costs**

**Baseline - VAV**

Unit Type	Quantity	Cost/Unit	Annual Cost
VAV Box w/ Reheat Coil	147	\$75	\$11,025
Large CHW RTU's	7	\$2,000	\$14,000
Small CHW RTU's	1	\$1,500	\$1,500
MAU's	1	\$1,200	\$1,200
Boiler Plant	1	\$1,000	\$1,000
Chiller Plant w/ Cooling Tower	1	\$2,500	\$2,500
<b>TOTAL</b>			<b>\$31,225</b>

**Option 1 - High-Efficiency VAV**

Unit Type	Quantity	Cost/Unit	Annual Cost
VAV Box w/ Reheat Coil	147	\$75	\$11,025
Large CHW RTU's	7	\$2,000	\$14,000
Small CHW RTU's	1	\$1,500	\$1,500
MAU's	1	\$1,200	\$1,200
Boiler Plant	1	\$1,000	\$1,000
Chiller Plant w/ Cooling Tower	1	\$2,500	\$2,500
<b>TOTAL</b>			<b>\$31,225</b>

**Option 2 - Full AC Displacement**

Unit Type	Quantity	Cost/Unit	Annual Cost
VAV Box	134	\$50	\$6,700
Large CHW RTU's	7	\$2,000	\$14,000
Small CHW RTU's	1	\$1,500	\$1,500
MAU's	1	\$1,200	\$1,200
Boiler Plant	1	\$1,000	\$1,000
Chiller Plant w/ Cooling Tower	1	\$2,500	\$2,500
<b>TOTAL</b>			<b>\$26,900</b>

**Option 2a - Static Plate ERV Full AC Displacement**

Unit Type	Quantity	Cost/Unit	Annual Cost
VAV Box	134	\$50	\$6,700
Large CHW RTU's (static plate)	7	\$1,750	\$12,250
Small CHW RTU's (static plate)	1	\$1,250	\$1,250
MAU's	1	\$1,200	\$1,200
Boiler Plant	1	\$1,000	\$1,000
Chiller Plant w/ Cooling Tower	1	\$2,500	\$2,500
<b>TOTAL</b>			<b>\$24,900</b>

**Option 2b - Static Plate ERV & Air-Cooled Chiller Full AC Displacement**

Unit Type	Quantity	Cost/Unit	Annual Cost
VAV Box	134	\$50	\$6,700
Large CHW RTU's (static plate)	7	\$1,750	\$12,250
Small CHW RTU's (static plate)	1	\$1,250	\$1,250
MAU's	1	\$1,200	\$1,200
Boiler Plant	1	\$1,000	\$1,000
Air-Cooled Chiller Plant	1	\$1,300	\$1,300
<b>TOTAL</b>			<b>\$23,700</b>

**Option 3 - Displacement w/ Radiant Cooling Full AC**

Unit Type	Quantity	Cost/Unit	Annual Cost
VAV Box	134	\$50	\$6,700
CHW Panel & Control Valve	134	\$25	\$3,350
Large CHW RTU's	7	\$2,000	\$14,000
Small CHW RTU's	1	\$1,500	\$1,500
MAU's	1	\$1,200	\$1,200
Boiler Plant	1	\$1,000	\$1,000
Chiller Plant w/ Cooling Tower	1	\$2,500	\$2,500
<b>TOTAL</b>			<b>\$30,250</b>

**Option 3a - Static Plate ERV Displacement w/ Radiant Cooling Full AC**

Unit Type	Quantity	Cost/Unit	Annual Cost
VAV Box	134	\$50	\$6,700
CHW Panel & Control Valve	134	\$25	\$3,350
Large CHW RTU's (static plate)	7	\$1,750	\$12,250
Small CHW RTU's (static plate)	1	\$1,250	\$1,250
MAU's	1	\$1,200	\$1,200
Boiler Plant	1	\$1,000	\$1,000
Chiller Plant w/ Cooling Tower	1	\$2,500	\$2,500
<b>TOTAL</b>			<b>\$28,250</b>

**Option 3b - Static Plate ERV & Air-Cooled Chiller Displacement w/ Radiant Cooling Full AC**


Unit Type	Quantity	Cost/Unit	Annual Cost
VAV Box	134	\$50	\$6,700
CHW Panel & Control Valve	134	\$25	\$3,350
Large CHW RTU's (static plate)	7	\$1,750	\$12,250
Small CHW RTU's (static plate)	1	\$1,250	\$1,250
MAU's	1	\$1,200	\$1,200
Boiler Plant	1	\$1,000	\$1,000
Air-Cooled Chiller Plant	1	\$1,300	\$1,300
<b>TOTAL</b>			<b>\$27,050</b>

**Option 4 - Geothermal Static Plate ERV Full AC Displacement**


Unit Type	Quantity	Cost/Unit	Annual Cost
VAV Box	134	\$50	\$6,700
Large CHW RTU's (static plate)	7	\$1,750	\$12,250
Small CHW RTU's (static plate)	1	\$1,250	\$1,250
MAU's	1	\$1,200	\$1,200
Boiler Plant	1	\$1,000	\$1,000
Geothermal Plant	1	\$3,500	\$3,500
<b>TOTAL</b>			<b>\$25,900</b>

# **ENERGY PROFILES**

### Electric Consumption (kWh)



### Gas Consumption (Btu)



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling

#### Electric Consumption (kWh x000)


	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	18.89	15.67	16.59	11.07	15.48	23.13	27.72	25.73	23.90	12.04	12.63	17.75	220.60
Heat Reject.	0.00	0.00	0.01	0.01	0.56	2.02	3.30	2.74	2.31	0.18	0.03	0.01	11.18
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	-	-	-	-	-	-	-	-	-	-	-	-	-
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	20.96	17.66	15.34	10.98	8.35	9.09	10.40	9.25	9.59	9.50	12.12	16.88	150.12
Pumps & Aux.	21.62	19.59	20.81	16.89	12.22	11.87	11.94	11.66	11.91	14.28	18.45	20.97	192.23
Ext. Usage	0.66	0.51	0.56	0.54	0.39	0.38	0.39	0.63	0.61	0.63	0.64	0.66	6.60
Misc. Equip.	16.76	17.46	14.78	15.98	19.43	13.57	8.82	8.63	16.59	19.96	17.08	10.66	179.72
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	17.65	18.26	16.21	17.09	20.41	14.38	9.66	9.32	17.40	20.72	18.13	12.27	191.51
<b>Total</b>	<b>96.56</b>	<b>89.15</b>	<b>84.30</b>	<b>72.56</b>	<b>76.85</b>	<b>74.44</b>	<b>72.23</b>	<b>67.96</b>	<b>82.32</b>	<b>77.30</b>	<b>79.08</b>	<b>79.21</b>	<b>951.95</b>

#### Gas Consumption (Btu x000,000)


	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	615.2	493.3	363.6	232.9	90.8	61.8	44.4	56.7	64.7	152.6	281.9	498.8	2,956.7
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	114.4	120.9	101.7	109.1	120.2	81.6	53.1	49.4	87.2	108.7	98.7	70.2	1,115.2
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	23.4	24.7	19.5	22.1	27.3	13.0	0.1	0.1	20.8	28.5	23.4	13.1	216.0
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>753.0</b>	<b>638.9</b>	<b>484.9</b>	<b>364.1</b>	<b>238.3</b>	<b>156.4</b>	<b>97.6</b>	<b>106.2</b>	<b>172.7</b>	<b>289.9</b>	<b>404.0</b>	<b>582.1</b>	<b>4,287.9</b>

**Annual Energy Consumption by Enduse**

	Electricity kWh (x000)	Natural Gas MBtu	Steam Btu	Chilled Water Btu
Space Cool	220.60	-	-	-
Heat Reject.	11.18	-	-	-
Refrigeration	-	-	-	-
Space Heat	-	2,956.7	-	-
HP Supp.	-	-	-	-
Hot Water	-	1,115.2	-	-
Vent. Fans	150.12	-	-	-
Pumps & Aux.	192.23	-	-	-
Ext. Usage	6.60	-	-	-
Misc. Equip.	179.72	216.0	-	-
Task Lights	-	-	-	-
Area Lights	191.51	-	-	-
<b>Total</b>	<b>951.95</b>	<b>4,287.9</b>	-	-




**Electricity**



**Natural Gas**




**Monthly Utility Bills (\$)**




**Total Annual Bill Across All Rates: \$ 206,782**

**Electric Demand (kW)**



**Gas Demand (Btu/h)**



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Ventilation Fans
- Misc. Equipment
- Space Heating
- Space Cooling

**Electric Demand (kW)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	21.8	22.2	48.2	56.8	97.5	128.7	126.0	120.4	163.6	82.2	60.4	24.1	951.8
Heat Reject.	-	-	2.2	-	13.2	22.0	27.6	24.0	28.3	6.0	0.4	-	123.7
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	-	-	-	-	-	-	-	-	-	-	-	-	-
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	58.1	56.3	29.6	30.2	52.7	59.5	51.5	53.0	69.6	52.9	28.8	51.6	593.7
Pumps & Aux.	32.6	32.5	30.4	28.4	35.1	37.0	38.1	37.7	38.6	33.5	28.5	32.3	404.7
Ext. Usage	-	-	-	-	-	-	-	0.3	-	-	-	-	0.3
Misc. Equip.	80.8	80.8	80.8	79.7	77.8	77.8	24.3	24.3	79.7	76.8	77.8	80.8	841.4
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	59.2	59.2	59.2	59.2	59.2	59.2	29.1	27.1	59.2	59.2	59.2	59.2	648.3
<b>Total</b>	<b>252.5</b>	<b>251.0</b>	<b>250.4</b>	<b>254.3</b>	<b>335.5</b>	<b>384.2</b>	<b>296.6</b>	<b>286.9</b>	<b>439.0</b>	<b>310.6</b>	<b>255.1</b>	<b>247.9</b>	<b>3,563.9</b>


**Gas Demand (Btu/h x1000,000)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	4.39	4.39	3.45	3.41	1.48	0.38	0.32	0.47	0.47	2.06	3.58	3.75	28.17
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	0.23	0.24	0.24	0.23	0.22	0.40	0.15	0.08	0.36	0.19	0.20	0.22	2.76
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	0.00	0.00	0.00	0.00	0.00	0.38	-	-	0.38	0.00	0.00	0.00	0.79
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>4.63</b>	<b>4.63</b>	<b>3.69</b>	<b>3.65</b>	<b>1.71</b>	<b>1.16</b>	<b>0.47</b>	<b>0.55</b>	<b>1.21</b>	<b>2.25</b>	<b>3.79</b>	<b>3.98</b>	<b>31.71</b>


**Annual Peak Demand by Enduse**

	<b>Electricity kW</b>	<b>Natural Gas Btu/h (x000)</b>	<b>Steam Btu/h</b>	<b>Chilled Water Btu/h</b>
Space Cool	163.60	-	-	-
Heat Reject.	28.27	-	-	-
Refrigeration	-	-	-	-
Space Heat	-	4,387.3	-	-
HP Supp.	-	-	-	-
Hot Water	-	239.6	-	-
Vent. Fans	69.61	-	-	-
Pumps & Aux.	38.57	-	-	-
Ext. Usage	-	-	-	-
Misc. Equip.	79.71	3.8	-	-
Task Lights	-	-	-	-
Area Lights	59.19	-	-	-
<b>Total</b>	<b>438.96</b>	<b>4,630.7</b>	<b>-</b>	<b>-</b>

- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling




**Electricity**




**Natural Gas**

**Electric Consumption (kWh)**



**Gas Consumption (Btu)**



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling

**Electric Consumption (kWh x000)**


	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	20.64	17.00	17.54	11.54	15.68	22.49	25.43	24.00	22.96	12.30	13.25	19.35	222.17
Heat Reject.	0.02	0.02	0.01	0.01	0.60	1.78	2.63	2.19	2.14	0.20	0.03	0.02	9.65
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	0.49	0.40	0.34	0.22	0.11	0.09	0.08	0.09	0.09	0.15	0.25	0.40	2.69
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	19.96	16.75	14.88	10.97	8.19	8.19	8.20	7.51	9.09	9.33	11.57	16.76	141.41
Pumps & Aux.	22.31	20.25	21.38	17.37	12.50	12.17	12.25	11.96	12.18	14.66	18.97	21.57	197.58
Ext. Usage	0.66	0.51	0.56	0.54	0.39	0.38	0.39	0.63	0.61	0.63	0.64	0.66	6.60
Misc. Equip.	16.76	17.46	14.78	15.98	19.43	13.57	8.82	8.63	16.59	19.96	17.08	10.66	179.72
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	17.65	18.26	16.21	17.09	20.41	14.38	9.66	9.32	17.40	20.72	18.13	12.27	191.51
<b>Total</b>	<b>98.51</b>	<b>90.65</b>	<b>85.70</b>	<b>73.71</b>	<b>77.30</b>	<b>73.05</b>	<b>67.45</b>	<b>64.32</b>	<b>81.07</b>	<b>77.95</b>	<b>79.92</b>	<b>81.69</b>	<b>951.32</b>

**Gas Consumption (Btu x000,000)**


	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	489.8	397.5	284.5	176.3	61.1	39.2	25.8	36.2	40.9	109.7	220.3	400.2	2,281.4
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	114.4	120.9	101.7	109.1	120.2	81.6	53.1	49.4	87.2	108.7	98.7	70.2	1,115.2
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	23.4	24.7	19.5	22.1	27.3	13.0	0.1	0.1	20.8	28.5	23.4	13.1	216.0
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>627.6</b>	<b>543.1</b>	<b>405.7</b>	<b>307.5</b>	<b>208.5</b>	<b>133.8</b>	<b>79.0</b>	<b>85.6</b>	<b>148.9</b>	<b>247.0</b>	<b>342.4</b>	<b>483.5</b>	<b>3,612.6</b>

**Annual Energy Consumption by Enduse**

	Electricity kWh (x000)	Natural Gas MBtu	Steam Btu	Chilled Water Btu
Space Cool	222.17	-	-	-
Heat Reject.	9.65	-	-	-
Refrigeration	-	-	-	-
Space Heat	2.69	2,281.4	-	-
HP Supp.	-	-	-	-
Hot Water	-	1,115.2	-	-
Vent. Fans	141.41	-	-	-
Pumps & Aux.	197.58	-	-	-
Ext. Usage	6.60	-	-	-
Misc. Equip.	179.72	216.0	-	-
Task Lights	-	-	-	-
Area Lights	191.51	-	-	-
<b>Total</b>	<b>951.32</b>	<b>3,612.6</b>	<b>-</b>	<b>-</b>




**Electricity**




**Natural Gas**

**Monthly Utility Bills (\$)**




**Total Annual Bill Across All Rates: \$ 201,671**

**Electric Demand (kW)**



**Gas Demand (Btu/h)**



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling

**Electric Demand (kW)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	44.9	46.4	49.0	57.9	98.0	117.1	93.6	92.3	143.5	89.8	49.2	39.5	921.2
Heat Reject.	-	-	2.1	-	10.7	20.8	22.1	17.5	26.9	8.3	-	-	108.4
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	2.6	2.6	0.6	0.4	0.4	0.4	0.4	0.3	0.3	0.4	1.9	2.2	12.6
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	98.2	92.1	29.6	30.2	55.8	55.5	39.4	41.4	66.3	53.6	73.3	80.4	715.8
Pumps & Aux.	35.0	35.0	31.4	29.2	36.6	38.9	38.1	37.7	40.6	36.3	35.2	34.8	428.8
Ext. Usage	-	-	-	-	-	-	-	0.3	-	-	-	-	0.3
Misc. Equip.	49.9	49.9	80.8	79.7	80.8	77.8	24.3	24.3	79.7	76.8	51.0	49.9	724.9
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	53.8	53.8	59.2	59.2	59.2	59.2	29.1	29.1	59.2	59.2	53.8	53.8	628.6
<b>Total</b>	<b>284.5</b>	<b>279.9</b>	<b>252.7</b>	<b>256.6</b>	<b>341.5</b>	<b>369.7</b>	<b>247.0</b>	<b>242.9</b>	<b>416.5</b>	<b>324.4</b>	<b>264.5</b>	<b>260.5</b>	<b>3,540.6</b>


**Gas Demand (Btu/h x1000,000)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	3.48	3.44	2.72	2.87	1.14	0.28	0.23	0.28	0.35	1.92	2.82	2.92	22.45
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	0.23	0.24	0.24	0.23	0.22	0.40	0.15	0.15	0.36	0.19	0.20	0.22	2.83
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	0.00	0.00	0.00	0.00	0.00	0.38	-	-	0.38	0.00	0.00	0.00	0.79
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>3.72</b>	<b>3.69</b>	<b>2.96</b>	<b>3.11</b>	<b>1.37</b>	<b>1.06</b>	<b>0.38</b>	<b>0.43</b>	<b>1.09</b>	<b>2.11</b>	<b>3.02</b>	<b>3.14</b>	<b>26.06</b>


**Annual Peak Demand by Enduse**

	<b>Electricity kW</b>	<b>Natural Gas Btu/h (x000)</b>	<b>Steam Btu/h</b>	<b>Chilled Water Btu/h</b>
Space Cool	143.49	-	-	-
Heat Reject.	26.89	-	-	-
Refrigeration	-	-	-	-
Space Heat	0.34	3,480.2	-	-
HP Supp.	-	-	-	-
Hot Water	-	232.0	-	-
Vent. Fans	66.32	-	-	-
Pumps & Aux.	40.57	-	-	-
Ext. Usage	-	-	-	-
Misc. Equip.	79.71	3.8	-	-
Task Lights	-	-	-	-
Area Lights	59.19	-	-	-
<b>Total</b>	<b>416.51</b>	<b>3,716.0</b>	-	-

- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling




**Electricity**




**Natural Gas**



**Electric Consumption (kWh)**



**Gas Consumption (Btu)**



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling

**Electric Consumption (kWh x000)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	3.55	3.19	3.35	3.52	7.37	13.10	16.57	14.65	14.62	4.80	3.38	3.86	91.97
Heat Reject.	0.00	0.00	-	0.01	0.29	1.13	2.02	1.60	1.48	0.10	0.01	0.00	6.65
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	0.56	0.45	0.39	0.29	0.10	0.04	0.03	0.03	0.05	0.17	0.28	0.51	2.92
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	6.37	6.58	5.35	6.00	7.22	7.50	7.21	5.96	9.25	7.75	6.22	4.06	79.47
Pumps & Aux.	7.90	7.60	7.59	7.47	7.21	7.60	8.00	7.50	7.67	7.69	7.50	8.36	92.09
Ext. Usage	0.66	0.51	0.56	0.54	0.39	0.38	0.39	0.63	0.61	0.63	0.64	0.66	6.60
Misc. Equip.	16.76	17.46	14.78	15.98	19.43	13.57	8.82	8.63	16.59	19.96	17.08	10.66	179.72
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	17.65	18.26	16.21	17.09	20.41	14.38	9.66	9.32	17.40	20.72	18.13	12.27	191.51
<b>Total</b>	<b>53.46</b>	<b>54.06</b>	<b>48.22</b>	<b>50.90</b>	<b>62.42</b>	<b>57.70</b>	<b>52.71</b>	<b>48.34</b>	<b>67.68</b>	<b>61.82</b>	<b>53.23</b>	<b>40.39</b>	<b>650.93</b>


**Gas Consumption (Btu x000,000)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	368.9	291.7	205.3	128.6	34.5	11.7	10.1	10.2	16.1	70.6	151.8	319.3	1,618.7
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	114.4	120.9	101.7	109.1	120.2	81.6	53.1	49.3	87.2	108.7	98.7	70.2	1,115.0
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	23.4	24.7	19.5	22.1	27.3	13.0	0.1	0.1	20.8	28.5	23.4	13.1	216.0
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>506.7</b>	<b>437.3</b>	<b>326.5</b>	<b>259.8</b>	<b>182.0</b>	<b>106.3</b>	<b>63.2</b>	<b>59.6</b>	<b>124.1</b>	<b>207.8</b>	<b>273.9</b>	<b>402.6</b>	<b>2,949.7</b>


**Annual Energy Consumption by Enduse**

	<b>Electricity kWh (x000)</b>	<b>Natural Gas MBtu</b>	<b>Steam Btu</b>	<b>Chilled Water Btu</b>
Space Cool	91.97	-	-	-
Heat Reject.	6.65	-	-	-
Refrigeration	-	-	-	-
Space Heat	2.92	1,618.7	-	-
HP Supp.	-	-	-	-
Hot Water	-	1,115.0	-	-
Vent. Fans	79.47	-	-	-
Pumps & Aux.	92.09	-	-	-
Ext. Usage	6.60	-	-	-
Misc. Equip.	179.72	216.0	-	-
Task Lights	-	-	-	-
Area Lights	191.51	-	-	-
<b>Total</b>	<b>650.93</b>	<b>2,949.7</b>	<b>-</b>	<b>-</b>

- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling




**Electricity**




**Natural Gas**

**Monthly Utility Bills (\$)**




**Total Annual Bill Across All Rates: \$ 141,525**

**Electric Demand (kW)**



**Gas Demand (Btu/h)**



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling

**Electric Demand (kW)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	17.9	10.3	10.6	29.5	73.0	106.8	82.3	87.0	128.1	48.4	31.7	9.7	635.5
Heat Reject.	-	-	-	-	7.5	14.6	16.0	15.0	18.9	4.6	0.4	-	77.0
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	1.0	1.1	0.8	0.6	0.2	0.3	0.1	0.2	0.3	0.4	0.4	0.9	6.3
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	36.7	34.5	31.7	21.8	56.5	68.9	44.8	37.3	89.1	41.9	20.5	32.4	515.8
Pumps & Aux.	22.1	22.3	21.4	16.2	25.1	31.5	26.3	26.3	33.1	23.6	16.4	21.8	286.0
Ext. Usage	-	-	-	-	-	-	-	0.3	-	-	-	-	0.3
Misc. Equip.	80.8	79.7	80.8	79.7	77.8	77.8	24.0	24.3	79.7	76.8	77.8	80.8	840.1
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	59.2	59.2	59.2	59.2	59.2	59.2	28.1	27.1	59.2	59.2	59.2	59.2	647.2
<b>Total</b>	<b>217.6</b>	<b>207.2</b>	<b>204.6</b>	<b>206.9</b>	<b>299.3</b>	<b>359.1</b>	<b>221.7</b>	<b>217.5</b>	<b>408.3</b>	<b>254.8</b>	<b>206.4</b>	<b>204.7</b>	<b>3,008.2</b>


**Gas Demand (Btu/h x1000,000)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	3.02	2.98	2.18	2.57	0.92	0.11	0.10	0.10	0.19	1.42	2.27	2.48	18.33
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	0.23	0.24	0.24	0.23	0.22	0.40	0.15	0.15	0.36	0.19	0.20	0.22	2.83
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	0.00	0.00	0.00	0.00	0.00	0.38	-	-	0.38	0.00	0.00	0.00	0.79
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>3.25</b>	<b>3.22</b>	<b>2.43</b>	<b>2.80</b>	<b>1.14</b>	<b>0.89</b>	<b>0.25</b>	<b>0.24</b>	<b>0.93</b>	<b>1.61</b>	<b>2.47</b>	<b>2.70</b>	<b>21.95</b>


**Annual Peak Demand by Enduse**

	Electricity kW	Natural Gas Btu/h (x000)	Steam Btu/h	Chilled Water Btu/h
Space Cool	128.14	-	-	-
Heat Reject.	18.86	-	-	-
Refrigeration	-	-	-	-
Space Heat	0.25	3,016.1	-	-
HP Supp.	-	-	-	-
Hot Water	-	232.0	-	-
Vent. Fans	89.11	-	-	-
Pumps & Aux.	33.05	-	-	-
Ext. Usage	-	-	-	-
Misc. Equip.	79.71	3.8	-	-
Task Lights	-	-	-	-
Area Lights	59.19	-	-	-
<b>Total</b>	<b>408.31</b>	<b>3,251.9</b>	-	-

- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling




**Electricity**




**Natural Gas**

**Electric Consumption (kWh)**



**Gas Consumption (Btu)**



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling

**Electric Consumption (kWh x000)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	3.38	3.11	3.35	3.57	7.64	13.50	17.29	15.19	15.34	5.01	3.46	3.99	94.84
Heat Reject.	0.00	0.00	-	0.01	0.30	1.16	2.10	1.67	1.55	0.11	0.01	0.00	6.90
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	0.57	0.46	0.40	0.29	0.10	0.04	0.03	0.03	0.05	0.17	0.28	0.51	2.92
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	7.81	8.39	6.93	7.71	8.95	9.33	9.14	7.47	11.65	9.83	8.05	5.16	100.41
Pumps & Aux.	6.93	6.50	6.72	6.63	6.97	7.23	7.23	6.96	7.35	6.93	6.56	7.96	83.97
Ext. Usage	0.66	0.51	0.56	0.54	0.39	0.38	0.39	0.63	0.61	0.63	0.64	0.66	6.60
Misc. Equip.	16.76	17.46	14.78	15.98	19.43	13.57	8.82	8.63	16.59	19.96	17.08	10.66	179.72
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	17.65	18.26	16.21	17.09	20.41	14.38	9.66	9.32	17.40	20.72	18.13	12.27	191.51
<b>Total</b>	<b>53.77</b>	<b>54.68</b>	<b>48.95</b>	<b>51.82</b>	<b>64.18</b>	<b>59.59</b>	<b>54.66</b>	<b>49.90</b>	<b>70.54</b>	<b>63.36</b>	<b>54.20</b>	<b>41.21</b>	<b>666.87</b>


**Gas Consumption (Btu x000,000)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	377.9	295.6	206.3	128.5	34.3	11.1	8.4	9.6	15.9	70.2	152.1	320.1	1,630.1
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	114.4	120.9	101.7	109.1	120.2	81.6	53.1	49.3	87.2	108.7	98.7	70.2	1,115.0
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	23.4	24.7	19.5	22.1	27.3	13.0	0.1	0.1	20.8	28.5	23.4	13.1	216.0
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>515.6</b>	<b>441.2</b>	<b>327.5</b>	<b>259.7</b>	<b>181.8</b>	<b>105.7</b>	<b>61.6</b>	<b>59.0</b>	<b>123.8</b>	<b>207.5</b>	<b>274.1</b>	<b>403.5</b>	<b>2,961.0</b>


**Annual Energy Consumption by Enduse**

	<b>Electricity kWh (x000)</b>	<b>Natural Gas MBtu</b>	<b>Steam Btu</b>	<b>Chilled Water Btu</b>
Space Cool	94.84	-	-	-
Heat Reject.	6.90	-	-	-
Refrigeration	-	-	-	-
Space Heat	2.92	1,630.1	-	-
HP Supp.	-	-	-	-
Hot Water	-	1,115.0	-	-
Vent. Fans	100.41	-	-	-
Pumps & Aux.	83.97	-	-	-
Ext. Usage	6.60	-	-	-
Misc. Equip.	179.72	216.0	-	-
Task Lights	-	-	-	-
Area Lights	191.51	-	-	-
<b>Total</b>	<b>666.87</b>	<b>2,961.0</b>	<b>-</b>	<b>-</b>

- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling




**Electricity**



**Natural Gas**


**Monthly Utility Bills (\$)**




**Total Annual Bill Across All Rates: \$ 144,540**



**Electric Demand (kW)**



**Gas Demand (Btu/h)**



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling

**Electric Demand (kW)**


	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	15.0	6.5	10.9	31.0	81.9	112.5	92.3	93.7	138.9	50.9	32.6	9.3	675.5
Heat Reject.	-	-	-	-	8.4	15.4	17.2	15.7	19.9	5.3	0.4	-	82.2
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	1.0	1.0	0.8	0.6	0.2	0.3	-	0.2	0.2	0.3	0.4	0.9	5.8
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	46.6	44.2	40.6	25.8	77.1	89.0	58.1	47.8	116.4	55.2	24.3	41.6	666.7
Pumps & Aux.	16.8	16.8	16.6	16.7	20.9	26.9	21.3	21.9	28.3	19.5	16.9	16.6	239.1
Ext. Usage	-	-	-	-	-	-	-	0.3	-	-	-	-	0.3
Misc. Equip.	80.8	80.8	80.8	79.7	64.4	77.8	24.0	24.3	79.7	63.3	77.8	80.8	814.3
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	59.2	59.2	59.2	59.2	59.2	59.2	28.1	27.1	59.2	59.2	59.2	59.2	647.3
<b>Total</b>	<b>219.3</b>	<b>208.5</b>	<b>209.0</b>	<b>212.8</b>	<b>312.0</b>	<b>381.1</b>	<b>241.0</b>	<b>231.0</b>	<b>442.6</b>	<b>253.8</b>	<b>211.7</b>	<b>208.4</b>	<b>3,131.1</b>

**Gas Demand (Btu/h x1000,000)**


	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	3.00	2.96	2.18	2.54	0.92	0.11	0.09	0.10	0.18	1.41	2.26	2.47	18.20
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	0.23	0.24	0.24	0.23	0.22	0.40	0.18	0.14	0.36	0.19	0.20	0.22	2.85
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	0.00	0.00	0.00	0.00	0.00	0.38	-	-	0.38	0.00	0.00	0.00	0.79
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>3.23</b>	<b>3.20</b>	<b>2.42</b>	<b>2.78</b>	<b>1.14</b>	<b>0.89</b>	<b>0.26</b>	<b>0.25</b>	<b>0.92</b>	<b>1.60</b>	<b>2.47</b>	<b>2.69</b>	<b>21.84</b>

**Annual Peak Demand by Enduse**

	<b>Electricity kW</b>	<b>Natural Gas Btu/h (x000)</b>	<b>Steam Btu/h</b>	<b>Chilled Water Btu/h</b>
Space Cool	138.91	-	-	-
Heat Reject.	19.90	-	-	-
Refrigeration	-	-	-	-
Space Heat	0.25	2,997.8	-	-
HP Supp.	-	-	-	-
Hot Water	-	232.0	-	-
Vent. Fans	116.40	-	-	-
Pumps & Aux.	28.27	-	-	-
Ext. Usage	-	-	-	-
Misc. Equip.	79.71	3.8	-	-
Task Lights	-	-	-	-
Area Lights	59.19	-	-	-
<b>Total</b>	<b>442.62</b>	<b>3,233.6</b>	<b>-</b>	<b>-</b>




**Electricity**




**Natural Gas**

### Electric Consumption (kWh)



### Gas Consumption (Btu)



- Area Lighting
- Task Lighting
- Misc. Equipment
- Exterior Usage
- Pumps & Aux.
- Ventilation Fans
- Water Heating
- Ht Pump Supp.
- Space Heating
- Refrigeration
- Heat Rejection
- Space Cooling

#### Electric Consumption (kWh x000)


	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	5.31	4.86	5.22	5.53	12.09	21.52	27.80	23.66	25.33	7.89	5.40	6.23	150.83
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	0.57	0.46	0.40	0.29	0.10	0.04	0.03	0.03	0.05	0.17	0.28	0.51	2.92
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	7.81	8.39	6.93	7.71	8.95	9.33	9.14	7.47	11.65	9.83	8.05	5.16	100.41
Pumps & Aux.	2.07	1.89	1.97	1.92	2.05	2.27	2.49	2.35	2.46	2.01	1.92	2.17	25.57
Ext. Usage	0.66	0.51	0.56	0.54	0.39	0.38	0.39	0.63	0.61	0.63	0.64	0.66	6.60
Misc. Equip.	16.76	17.46	14.78	15.98	19.43	13.57	8.82	8.63	16.59	19.96	17.08	10.66	179.72
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	17.65	18.26	16.21	17.09	20.41	14.38	9.66	9.32	17.40	20.72	18.13	12.27	191.51
<b>Total</b>	<b>50.84</b>	<b>51.83</b>	<b>46.06</b>	<b>49.06</b>	<b>63.41</b>	<b>61.48</b>	<b>58.33</b>	<b>52.09</b>	<b>74.09</b>	<b>61.21</b>	<b>51.49</b>	<b>37.66</b>	<b>657.56</b>

#### Gas Consumption (Btu x000,000)


	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	377.9	295.6	206.3	128.5	34.3	11.1	8.4	9.6	15.9	70.2	152.1	320.1	1,630.1
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	114.4	120.9	101.7	109.1	120.2	81.6	53.1	49.3	87.2	108.7	98.7	70.2	1,115.0
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	23.4	24.7	19.5	22.1	27.3	13.0	0.1	0.1	20.8	28.5	23.4	13.1	216.0
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>515.6</b>	<b>441.2</b>	<b>327.5</b>	<b>259.7</b>	<b>181.8</b>	<b>105.7</b>	<b>61.6</b>	<b>59.0</b>	<b>123.8</b>	<b>207.5</b>	<b>274.1</b>	<b>403.5</b>	<b>2,961.0</b>

**Annual Energy Consumption by Enduse**

	<b>Electricity kWh (x000)</b>	<b>Natural Gas MBtu</b>	<b>Steam Btu</b>	<b>Chilled Water Btu</b>
Space Cool	150.83	-	-	-
Heat Reject.	-	-	-	-
Refrigeration	-	-	-	-
Space Heat	2.92	1,630.1	-	-
HP Supp.	-	-	-	-
Hot Water	-	1,115.0	-	-
Vent. Fans	100.41	-	-	-
Pumps & Aux.	25.57	-	-	-
Ext. Usage	6.60	-	-	-
Misc. Equip.	179.72	216.0	-	-
Task Lights	-	-	-	-
Area Lights	191.51	-	-	-
<b>Total</b>	<b>657.56</b>	<b>2,961.0</b>	<b>-</b>	<b>-</b>




**Electricity**




**Natural Gas**

**Monthly Utility Bills (\$)**




**Total Annual Bill Across All Rates: \$ 142,828**

**Electric Demand (kW)**



**Gas Demand (Btu/h)**



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling

**Electric Demand (kW)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	23.8	9.8	17.0	50.9	135.9	219.0	165.4	145.2	263.2	88.5	50.2	14.3	1,183.2
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	1.0	1.0	0.8	0.4	0.2	0.2	-	-	0.2	0.3	0.4	0.9	5.5
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	46.6	44.2	40.6	26.0	77.1	93.1	58.1	55.2	116.4	55.2	24.3	41.6	678.3
Pumps & Aux.	4.0	4.0	3.8	4.1	8.1	10.3	8.5	8.5	10.9	6.7	4.1	3.8	76.7
Ext. Usage	-	-	-	-	-	-	-	0.3	-	-	-	-	0.3
Misc. Equip.	80.8	80.8	80.8	76.8	64.4	64.4	24.0	24.3	79.7	63.3	77.8	80.8	797.9
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	59.2	59.2	59.2	59.2	59.2	59.2	28.1	29.1	59.2	59.2	59.2	59.2	649.3
<b>Total</b>	<b>215.3</b>	<b>199.0</b>	<b>202.2</b>	<b>217.3</b>	<b>344.8</b>	<b>446.2</b>	<b>284.1</b>	<b>262.7</b>	<b>529.7</b>	<b>273.2</b>	<b>216.1</b>	<b>200.6</b>	<b>3,391.2</b>


**Gas Demand (Btu/h x1000,000)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	3.00	2.96	2.18	2.54	0.92	0.11	0.09	0.10	0.18	1.41	2.26	2.47	18.20
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	0.23	0.24	0.24	0.23	0.22	0.40	0.18	0.14	0.36	0.19	0.20	0.22	2.85
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	0.00	0.00	0.00	0.00	0.00	0.38	-	-	0.38	0.00	0.00	0.00	0.79
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>3.23</b>	<b>3.20</b>	<b>2.42</b>	<b>2.78</b>	<b>1.14</b>	<b>0.89</b>	<b>0.26</b>	<b>0.25</b>	<b>0.92</b>	<b>1.60</b>	<b>2.47</b>	<b>2.69</b>	<b>21.84</b>


**Annual Peak Demand by Enduse**

	Electricity kW	Natural Gas Btu/h (x000)	Steam Btu/h	Chilled Water Btu/h
Space Cool	263.24	-	-	-
Heat Reject.	-	-	-	-
Refrigeration	-	-	-	-
Space Heat	0.25	2,997.8	-	-
HP Supp.	-	-	-	-
Hot Water	-	232.0	-	-
Vent. Fans	116.40	-	-	-
Pumps & Aux.	10.90	-	-	-
Ext. Usage	-	-	-	-
Misc. Equip.	79.71	3.8	-	-
Task Lights	-	-	-	-
Area Lights	59.19	-	-	-
<b>Total</b>	<b>529.69</b>	<b>3,233.6</b>	-	-

- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling




**Electricity**




**Natural Gas**

### Electric Consumption (kWh)



### Gas Consumption (Btu)



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Ventilation Fans
- Space Heating
- Space Cooling

#### Electric Consumption (kWh x000)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	3.03	2.82	2.96	3.12	6.89	12.30	16.06	13.97	14.10	4.43	3.07	3.45	86.21
Heat Reject.	0.00	-	0.00	0.01	0.30	1.09	1.92	1.55	1.45	0.11	0.01	0.00	6.44
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	0.61	0.49	0.43	0.31	0.10	0.04	0.03	0.03	0.05	0.18	0.30	0.56	3.13
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	5.25	5.58	4.72	5.44	7.80	8.43	8.01	6.46	10.06	7.67	5.54	3.73	78.70
Pumps & Aux.	7.52	7.19	7.16	7.03	6.95	7.21	7.71	7.17	7.33	7.36	7.09	7.69	87.40
Ext. Usage	0.66	0.51	0.56	0.54	0.39	0.38	0.39	0.63	0.61	0.63	0.64	0.66	6.60
Misc. Equip.	16.76	17.46	14.78	15.98	19.43	13.57	8.82	8.63	16.59	19.96	17.08	10.66	179.72
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	17.65	18.26	16.21	17.09	20.41	14.38	9.66	9.32	17.40	20.72	18.13	12.27	191.51
<b>Total</b>	<b>51.50</b>	<b>52.32</b>	<b>46.81</b>	<b>49.52</b>	<b>62.26</b>	<b>57.41</b>	<b>52.60</b>	<b>47.77</b>	<b>67.60</b>	<b>61.06</b>	<b>51.85</b>	<b>39.02</b>	<b>639.71</b>

#### Gas Consumption (Btu x000,000)


	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	377.5	294.9	205.8	129.7	33.8	11.6	9.6	10.0	16.0	69.8	150.3	318.6	1,627.6
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	114.4	120.9	101.7	109.1	120.2	81.6	53.0	49.3	87.2	108.7	98.7	70.2	1,114.9
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	23.4	24.7	19.5	22.1	27.3	13.0	0.1	0.1	20.8	28.5	23.4	13.1	216.0
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>515.3</b>	<b>440.4</b>	<b>327.0</b>	<b>260.9</b>	<b>181.2</b>	<b>106.2</b>	<b>62.8</b>	<b>59.5</b>	<b>123.9</b>	<b>207.0</b>	<b>272.4</b>	<b>401.9</b>	<b>2,958.5</b>




**Annual Energy Consumption by Enduse**

	<b>Electricity kWh (x000)</b>	<b>Natural Gas MBtu</b>	<b>Steam Btu</b>	<b>Chilled Water Btu</b>
Space Cool	86.21	-	-	-
Heat Reject.	6.44	-	-	-
Refrigeration	-	-	-	-
Space Heat	3.13	1,627.6	-	-
HP Supp.	-	-	-	-
Hot Water	-	1,114.9	-	-
Vent. Fans	78.70	-	-	-
Pumps & Aux.	87.40	-	-	-
Ext. Usage	6.60	-	-	-
Misc. Equip.	179.72	216.0	-	-
Task Lights	-	-	-	-
Area Lights	191.51	-	-	-
<b>Total</b>	<b>639.71</b>	<b>2,958.5</b>	<b>-</b>	<b>-</b>

- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling




**Electricity**




**Natural Gas**

**Monthly Utility Bills (\$)**




**Total Annual Bill Across All Rates: \$ 139,527**

**Electric Demand (kW)**



**Gas Demand (Btu/h)**



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling

**Electric Demand (kW)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	5.6	5.6	9.8	5.4	85.9	104.2	84.2	87.8	129.0	43.2	27.8	8.9	597.4
Heat Reject.	-	-	-	-	10.1	13.9	14.7	13.6	17.6	4.3	0.3	-	74.4
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	1.0	0.9	0.9	0.7	0.2	0.3	-	0.2	0.3	0.4	0.4	1.0	6.3
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	30.8	29.6	28.1	37.3	62.7	76.1	50.2	41.5	94.8	32.3	21.5	28.3	533.0
Pumps & Aux.	20.8	20.6	20.3	20.5	25.4	30.4	25.6	28.3	30.6	19.6	14.8	20.7	277.6
Ext. Usage	-	-	-	-	-	-	-	0.3	-	-	-	-	0.3
Misc. Equip.	80.8	80.8	80.8	80.8	64.4	77.8	24.0	24.3	79.7	76.8	77.8	80.8	828.7
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	59.2	59.2	59.2	59.2	59.2	59.2	27.9	27.1	59.2	59.2	59.2	59.2	647.1
<b>Total</b>	<b>198.2</b>	<b>196.7</b>	<b>199.1</b>	<b>203.9</b>	<b>307.8</b>	<b>361.9</b>	<b>226.5</b>	<b>223.2</b>	<b>411.1</b>	<b>235.7</b>	<b>201.8</b>	<b>198.9</b>	<b>2,964.9</b>


**Gas Demand (Btu/h x1000,000)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	3.59	3.55	2.59	3.16	1.02	0.11	0.12	0.12	0.17	1.64	2.81	2.95	21.83
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	0.23	0.24	0.24	0.23	0.22	0.40	0.15	0.15	0.36	0.19	0.20	0.22	2.83
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	0.00	0.00	0.00	0.00	0.00	0.38	-	-	0.38	0.00	0.00	0.00	0.79
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>3.82</b>	<b>3.80</b>	<b>2.84</b>	<b>3.40</b>	<b>1.24</b>	<b>0.89</b>	<b>0.27</b>	<b>0.27</b>	<b>0.91</b>	<b>1.83</b>	<b>3.02</b>	<b>3.17</b>	<b>25.45</b>


**Annual Peak Demand by Enduse**

	<b>Electricity kW</b>	<b>Natural Gas Btu/h (x000)</b>	<b>Steam Btu/h</b>	<b>Chilled Water Btu/h</b>
Space Cool	128.98	-	-	-
Heat Reject.	17.57	-	-	-
Refrigeration	-	-	-	-
Space Heat	0.27	3,588.2	-	-
HP Supp.	-	-	-	-
Hot Water	-	232.0	-	-
Vent. Fans	94.81	-	-	-
Pumps & Aux.	30.60	-	-	-
Ext. Usage	-	-	-	-
Misc. Equip.	79.71	3.8	-	-
Task Lights	-	-	-	-
Area Lights	59.19	-	-	-
<b>Total</b>	<b>411.13</b>	<b>3,824.0</b>	<b>-</b>	<b>-</b>

- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling




**Electricity**




**Natural Gas**

### Electric Consumption (kWh)



### Gas Consumption (Btu)



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling

#### Electric Consumption (kWh x000)


	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	2.99	2.76	2.97	3.16	7.04	12.67	16.78	14.51	14.87	4.58	3.14	3.53	89.00
Heat Reject.	0.00	-	0.00	0.01	0.30	1.12	2.03	1.62	1.51	0.11	0.01	0.00	6.71
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	0.61	0.49	0.43	0.31	0.10	0.04	0.03	0.03	0.05	0.18	0.30	0.56	3.13
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	6.46	6.98	5.95	6.81	9.47	10.34	10.00	7.98	12.46	9.55	6.98	4.60	97.59
Pumps & Aux.	6.34	5.94	6.17	6.07	6.59	6.78	6.87	6.56	6.91	6.46	6.02	7.06	77.77
Ext. Usage	0.66	0.51	0.56	0.54	0.39	0.38	0.39	0.63	0.61	0.63	0.64	0.66	6.60
Misc. Equip.	16.76	17.46	14.78	15.98	19.43	13.57	8.82	8.63	16.59	19.96	17.08	10.66	179.72
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	17.65	18.26	16.21	17.09	20.41	14.38	9.66	9.32	17.40	20.72	18.13	12.27	191.51
<b>Total</b>	<b>51.49</b>	<b>52.41</b>	<b>47.06</b>	<b>49.98</b>	<b>63.72</b>	<b>59.29</b>	<b>54.57</b>	<b>49.28</b>	<b>70.42</b>	<b>62.19</b>	<b>52.29</b>	<b>39.33</b>	<b>652.03</b>

#### Gas Consumption (Btu x000,000)


	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	379.9	296.4	206.2	129.5	33.4	11.3	8.1	9.7	15.7	69.4	150.5	318.6	1,628.7
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	114.4	120.9	101.7	109.1	120.2	81.6	53.0	49.3	87.2	108.7	98.7	70.2	1,114.9
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	23.4	24.7	19.5	22.1	27.3	13.0	0.1	0.1	20.8	28.5	23.4	13.1	216.0
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>517.7</b>	<b>442.0</b>	<b>327.4</b>	<b>260.7</b>	<b>180.9</b>	<b>105.9</b>	<b>61.3</b>	<b>59.1</b>	<b>123.6</b>	<b>206.6</b>	<b>272.6</b>	<b>401.9</b>	<b>2,959.6</b>

**Annual Energy Consumption by Enduse**

	<b>Electricity kWh (x000)</b>	<b>Natural Gas MBtu</b>	<b>Steam Btu</b>	<b>Chilled Water Btu</b>
Space Cool	89.00	-	-	-
Heat Reject.	6.71	-	-	-
Refrigeration	-	-	-	-
Space Heat	3.13	1,628.7	-	-
HP Supp.	-	-	-	-
Hot Water	-	1,114.9	-	-
Vent. Fans	97.59	-	-	-
Pumps & Aux.	77.77	-	-	-
Ext. Usage	6.60	-	-	-
Misc. Equip.	179.72	216.0	-	-
Task Lights	-	-	-	-
Area Lights	191.51	-	-	-
<b>Total</b>	<b>652.03</b>	<b>2,959.6</b>	<b>-</b>	<b>-</b>




**Electricity**




**Natural Gas**

**Monthly Utility Bills (\$)**




**Total Annual Bill Across All Rates: \$ 141,800**

**Electric Demand (kW)**



**Gas Demand (Btu/h)**



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling

**Electric Demand (kW)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	5.7	5.7	10.1	27.1	85.5	119.3	90.5	89.9	140.5	45.1	28.5	8.5	656.5
Heat Reject.	-	-	-	-	10.1	15.3	15.7	13.8	18.7	4.7	0.4	-	78.6
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	1.0	1.2	0.9	0.5	0.2	0.2	-	-	0.3	0.3	0.4	1.0	6.0
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	34.2	37.5	34.9	27.0	79.0	102.0	64.8	61.1	122.7	51.2	25.2	35.3	674.7
Pumps & Aux.	15.0	15.4	14.8	14.9	19.8	25.5	23.0	19.9	24.9	17.6	15.1	14.8	220.7
Ext. Usage	-	-	-	-	-	-	-	0.3	-	-	-	-	0.3
Misc. Equip.	80.8	79.7	80.8	79.7	64.4	64.4	24.0	24.3	79.7	63.3	77.8	80.8	799.8
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	59.2	59.2	59.2	59.2	59.2	59.2	28.1	29.1	59.2	59.2	59.2	59.2	649.3
<b>Total</b>	<b>195.9</b>	<b>198.6</b>	<b>200.8</b>	<b>208.4</b>	<b>318.2</b>	<b>386.0</b>	<b>246.1</b>	<b>238.4</b>	<b>445.9</b>	<b>241.5</b>	<b>206.6</b>	<b>199.6</b>	<b>3,085.9</b>

**Gas Demand (Btu/h x1000,000)**


	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	3.59	3.55	2.59	3.14	1.01	0.11	0.11	0.08	0.17	1.63	2.81	2.95	21.74
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	0.23	0.24	0.24	0.23	0.22	0.40	0.15	0.17	0.36	0.19	0.20	0.22	2.85
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	0.00	0.00	0.00	0.00	0.00	0.38	-	-	0.38	0.00	0.00	0.00	0.79
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>3.83</b>	<b>3.79</b>	<b>2.83</b>	<b>3.38</b>	<b>1.23</b>	<b>0.89</b>	<b>0.27</b>	<b>0.25</b>	<b>0.91</b>	<b>1.83</b>	<b>3.02</b>	<b>3.17</b>	<b>25.38</b>




**Annual Peak Demand by Enduse**

	Electricity kW	Natural Gas Btu/h (x000)	Steam Btu/h	Chilled Water Btu/h
Space Cool	140.50	-	-	-
Heat Reject.	18.66	-	-	-
Refrigeration	-	-	-	-
Space Heat	0.26	3,593.1	-	-
HP Supp.	-	-	-	-
Hot Water	-	232.0	-	-
Vent. Fans	122.68	-	-	-
Pumps & Aux.	24.88	-	-	-
Ext. Usage	-	-	-	-
Misc. Equip.	79.71	3.8	-	-
Task Lights	-	-	-	-
Area Lights	59.19	-	-	-
<b>Total</b>	<b>445.88</b>	<b>3,828.9</b>	-	-

- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling




**Electricity**




**Natural Gas**

### Electric Consumption (kWh)



### Gas Consumption (Btu)



- Area Lighting
- Task Lighting
- Exterior Usage
- Pumps & Aux.
- Ventilation Fans
- Water Heating
- Ht Pump Supp.
- Refrigeration
- Heat Rejection
- Space Cooling

#### Electric Consumption (kWh x000)


	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	4.72	4.33	4.64	4.94	11.29	20.47	26.99	22.64	24.75	7.34	4.95	5.53	142.58
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	0.61	0.49	0.43	0.31	0.10	0.04	0.03	0.03	0.05	0.18	0.30	0.56	3.13
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	6.46	6.98	5.95	6.81	9.47	10.34	10.00	7.98	12.46	9.55	6.98	4.60	97.59
Pumps & Aux.	2.10	1.91	2.02	1.96	2.13	2.36	2.62	2.48	2.52	2.07	1.96	2.14	26.28
Ext. Usage	0.66	0.51	0.56	0.54	0.39	0.38	0.39	0.63	0.61	0.63	0.64	0.66	6.60
Misc. Equip.	16.76	17.46	14.78	15.98	19.43	13.57	8.82	8.63	16.59	19.96	17.08	10.66	179.72
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	17.65	18.26	16.21	17.09	20.41	14.38	9.66	9.32	17.40	20.72	18.13	12.27	191.51
<b>Total</b>	<b>48.98</b>	<b>49.95</b>	<b>44.58</b>	<b>47.63</b>	<b>63.21</b>	<b>61.54</b>	<b>58.51</b>	<b>51.70</b>	<b>74.39</b>	<b>60.45</b>	<b>50.03</b>	<b>36.42</b>	<b>647.40</b>

#### Gas Consumption (Btu x000,000)


	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	379.9	296.4	206.2	129.5	33.4	11.3	8.1	9.7	15.7	69.4	150.5	318.6	1,628.7
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	114.4	120.9	101.7	109.1	120.2	81.6	53.0	49.3	87.2	108.7	98.7	70.2	1,114.9
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	23.4	24.7	19.5	22.1	27.3	13.0	0.1	0.1	20.8	28.5	23.4	13.1	216.0
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>517.7</b>	<b>442.0</b>	<b>327.4</b>	<b>260.7</b>	<b>180.9</b>	<b>105.9</b>	<b>61.3</b>	<b>59.1</b>	<b>123.6</b>	<b>206.6</b>	<b>272.6</b>	<b>401.9</b>	<b>2,959.6</b>

**Annual Energy Consumption by Enduse**

	<b>Electricity kWh (x000)</b>	<b>Natural Gas MBtu</b>	<b>Steam Btu</b>	<b>Chilled Water Btu</b>
Space Cool	142.58	-	-	-
Heat Reject.	-	-	-	-
Refrigeration	-	-	-	-
Space Heat	3.13	1,628.7	-	-
HP Supp.	-	-	-	-
Hot Water	-	1,114.9	-	-
Vent. Fans	97.59	-	-	-
Pumps & Aux.	26.28	-	-	-
Ext. Usage	6.60	-	-	-
Misc. Equip.	179.72	216.0	-	-
Task Lights	-	-	-	-
Area Lights	191.51	-	-	-
<b>Total</b>	<b>647.40</b>	<b>2,959.6</b>	<b>-</b>	<b>-</b>




**Electricity**




**Natural Gas**

**Monthly Utility Bills (\$)**



**Total Annual Bill Across All Rates: \$ 140,949**



**Electric Demand (kW)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	35.6	8.7	15.7	44.7	134.7	214.2	175.3	146.1	275.7	83.8	44.0	13.2	1,191.6
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	1.1	1.2	0.9	0.4	0.2	0.2	-	-	0.2	0.2	0.4	1.0	5.8
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	39.7	37.5	34.9	27.8	79.0	102.0	64.8	61.1	137.6	48.0	25.2	35.3	692.8
Pumps & Aux.	4.3	4.2	3.7	3.9	8.6	10.3	7.8	8.8	10.8	6.6	3.9	3.7	76.6
Ext. Usage	0.6	-	-	-	-	-	-	0.3	0.3	-	-	-	1.2
Misc. Equip.	49.7	79.7	80.8	76.8	64.4	64.4	24.0	24.3	49.7	63.3	77.8	80.8	735.8
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	57.0	59.2	59.2	59.2	59.2	59.2	28.1	29.1	57.0	59.2	59.2	59.2	644.8
<b>Total</b>	<b>187.9</b>	<b>190.4</b>	<b>195.2</b>	<b>212.8</b>	<b>346.1</b>	<b>450.4</b>	<b>300.0</b>	<b>269.7</b>	<b>531.3</b>	<b>261.2</b>	<b>210.5</b>	<b>193.0</b>	<b>3,348.6</b>


**Gas Demand (Btu/h x000,000)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	3.59	3.55	2.59	3.14	1.01	0.11	0.11	0.08	0.17	1.63	2.81	2.95	21.74
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	0.23	0.24	0.24	0.23	0.22	0.40	0.15	0.17	0.36	0.19	0.20	0.22	2.85
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	0.00	0.00	0.00	0.00	0.00	0.38	-	-	0.38	0.00	0.00	0.00	0.79
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>3.83</b>	<b>3.79</b>	<b>2.83</b>	<b>3.38</b>	<b>1.23</b>	<b>0.89</b>	<b>0.27</b>	<b>0.25</b>	<b>0.91</b>	<b>1.83</b>	<b>3.02</b>	<b>3.17</b>	<b>25.38</b>


**Annual Peak Demand by Enduse**

	<b>Electricity kW</b>	<b>Natural Gas Btu/h (x000)</b>	<b>Steam Btu/h</b>	<b>Chilled Water Btu/h</b>
Space Cool	275.67	-	-	-
Heat Reject.	-	-	-	-
Refrigeration	-	-	-	-
Space Heat	0.20	3,593.1	-	-
HP Supp.	-	-	-	-
Hot Water	-	232.0	-	-
Vent. Fans	137.64	-	-	-
Pumps & Aux.	10.82	-	-	-
Ext. Usage	0.31	-	-	-
Misc. Equip.	49.72	3.8	-	-
Task Lights	-	-	-	-
Area Lights	56.97	-	-	-
<b>Total</b>	<b>531.33</b>	<b>3,828.9</b>	-	-

- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling




**Electricity**




**Natural Gas**

### Electric Consumption (kWh)



### Gas Consumption (Btu)



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling

#### Electric Consumption (kWh x000)


	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	0.64	1.21	1.76	3.98	10.03	12.74	12.97	11.29	16.06	7.18	2.99	0.93	81.78
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	40.24	32.36	24.75	14.30	3.40	1.40	0.88	1.35	1.35	6.59	15.60	35.26	177.50
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	8.10	8.75	7.19	8.81	13.55	12.79	10.15	8.91	15.49	12.45	8.73	5.37	120.31
Pumps & Aux.	13.58	11.76	12.40	8.95	6.35	5.49	4.99	5.31	5.49	6.95	9.84	13.29	104.39
Ext. Usage	0.66	0.51	0.56	0.54	0.39	0.38	0.39	0.63	0.61	0.63	0.64	0.66	6.60
Misc. Equip.	16.76	17.46	14.78	15.98	19.43	13.57	8.82	8.63	16.59	19.96	17.08	10.66	179.72
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	17.65	18.26	16.21	17.09	20.41	14.38	9.66	9.32	17.40	20.72	18.13	12.27	191.51
<b>Total</b>	<b>97.64</b>	<b>90.31</b>	<b>77.64</b>	<b>69.66</b>	<b>73.56</b>	<b>60.75</b>	<b>47.86</b>	<b>45.45</b>	<b>72.99</b>	<b>74.49</b>	<b>73.01</b>	<b>78.44</b>	<b>861.81</b>

#### Gas Consumption (Btu x000,000)


	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	36.9	21.9	-	-	-	-	-	-	-	-	2.3	3.4	64.4
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	114.4	120.9	101.7	109.1	120.2	81.6	53.1	49.3	87.2	108.7	98.7	70.2	1,115.0
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	23.4	24.7	19.5	22.1	27.3	13.0	0.1	0.1	20.8	28.5	23.4	13.1	216.0
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>174.7</b>	<b>167.5</b>	<b>121.2</b>	<b>131.2</b>	<b>147.4</b>	<b>94.6</b>	<b>53.1</b>	<b>49.4</b>	<b>108.0</b>	<b>137.3</b>	<b>124.3</b>	<b>86.7</b>	<b>1,395.4</b>

**Annual Energy Consumption by Enduse**

	Electricity kWh (x000)	Natural Gas MBtu	Steam Btu	Chilled Water Btu
Space Cool	81.78	-	-	-
Heat Reject.	-	-	-	-
Refrigeration	-	-	-	-
Space Heat	177.50	64.4	-	-
HP Supp.	-	-	-	-
Hot Water	-	1,115.0	-	-
Vent. Fans	120.31	-	-	-
Pumps & Aux.	104.39	-	-	-
Ext. Usage	6.60	-	-	-
Misc. Equip.	179.72	216.0	-	-
Task Lights	-	-	-	-
Area Lights	191.51	-	-	-
<b>Total</b>	<b>861.81</b>	<b>1,395.4</b>	<b>-</b>	<b>-</b>




**Electricity**



**Natural Gas**




**Monthly Utility Bills (\$)**




**Total Annual Bill Across All Rates: \$ 168,809**

**Electric Demand (kW)**



**Gas Demand (Btu/h)**



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling

**Electric Demand (kW)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	96.8	116.6	74.0	74.2	144.1	46.8	-	-	552.4
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	165.9	151.3	133.2	196.8	-	-	7.7	8.6	-	9.6	128.2	155.3	956.6
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	33.4	34.7	34.8	24.6	77.3	90.3	52.5	53.0	116.5	69.3	35.4	34.5	656.3
Pumps & Aux.	20.3	20.2	20.1	20.9	13.8	14.9	22.7	22.7	15.6	21.5	20.1	20.2	233.3
Ext. Usage	-	-	-	-	-	-	-	0.3	-	-	-	-	0.3
Misc. Equip.	57.9	57.9	49.9	22.2	73.8	77.8	24.3	24.3	79.7	76.8	49.9	49.9	644.5
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	59.2	59.2	53.8	24.2	59.2	59.2	29.1	27.1	59.2	59.2	53.8	53.8	597.0
<b>Total</b>	<b>336.7</b>	<b>323.3</b>	<b>291.7</b>	<b>288.8</b>	<b>320.9</b>	<b>358.9</b>	<b>210.3</b>	<b>210.3</b>	<b>415.2</b>	<b>283.2</b>	<b>287.4</b>	<b>313.8</b>	<b>3,640.5</b>


**Gas Demand (Btu/h x1000,000)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	3.00	2.96	-	-	-	-	-	-	-	-	2.29	2.42	10.67
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	0.23	0.24	0.48	0.47	0.43	0.40	0.18	0.17	0.36	0.37	0.20	0.22	3.75
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	0.00	0.00	0.38	0.38	0.38	0.38	-	-	0.38	0.38	0.00	0.00	2.29
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>3.23</b>	<b>3.20</b>	<b>0.86</b>	<b>0.85</b>	<b>0.81</b>	<b>0.78</b>	<b>0.18</b>	<b>0.17</b>	<b>0.74</b>	<b>0.75</b>	<b>2.49</b>	<b>2.64</b>	<b>16.70</b>


**Annual Peak Demand by Enduse**

	Electricity kW	Natural Gas Btu/h (x000)	Steam Btu/h	Chilled Water Btu/h
Space Cool	144.12	-	-	-
Heat Reject.	-	-	-	-
Refrigeration	-	-	-	-
Space Heat	-	2,997.4	-	-
HP Supp.	-	-	-	-
Hot Water	-	232.0	-	-
Vent. Fans	116.49	-	-	-
Pumps & Aux.	15.63	-	-	-
Ext. Usage	-	-	-	-
Misc. Equip.	79.71	3.8	-	-
Task Lights	-	-	-	-
Area Lights	59.19	-	-	-
<b>Total</b>	<b>415.16</b>	<b>3,233.2</b>	-	-

- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling




**Electricity**




**Natural Gas**

### Electric Consumption (kWh)



### Gas Consumption (Btu)



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling

#### Electric Consumption (kWh x000)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	7.8	6.4	6.8	4.7	8.0	15.5	21.0	18.1	17.6	5.6	5.1	7.3	123.8
Heat Reject.	0.0	0.0	0.0	0.0	0.4	1.1	1.5	1.4	1.1	0.2	0.0	0.0	5.9
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	-	-	-	-	-	-	-	-	-	-	-	-	-
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	30.3	25.9	24.0	16.1	11.7	12.8	13.6	12.2	13.7	12.7	18.1	26.4	217.4
Pumps & Aux.	16.2	14.7	15.6	12.3	9.3	9.4	9.5	9.1	9.6	10.7	13.7	15.6	145.7
Ext. Usage	0.8	0.6	0.7	0.6	0.5	0.4	0.5	0.7	0.7	0.7	0.8	0.8	7.8
Misc. Equip.	16.8	17.5	14.8	16.0	19.4	13.6	8.8	8.6	16.6	20.0	17.1	10.7	179.7
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	35.0	36.2	32.1	33.9	40.4	28.5	19.1	18.5	34.5	41.0	35.9	24.3	379.4
<b>Total</b>	<b>106.7</b>	<b>101.3</b>	<b>93.9</b>	<b>83.6</b>	<b>89.8</b>	<b>81.3</b>	<b>74.1</b>	<b>68.7</b>	<b>93.9</b>	<b>90.8</b>	<b>90.7</b>	<b>85.0</b>	<b>1,059.8</b>


#### Gas Consumption (Btu x000,000)

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	592.2	476.1	353.6	238.0	103.0	65.6	44.4	55.4	69.7	165.1	274.8	497.2	2,935.1
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	114.2	120.7	101.4	108.9	119.8	81.4	52.9	49.2	86.9	108.4	98.4	70.1	1,112.3
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	23.4	24.7	19.5	22.1	27.3	13.0	0.1	0.1	20.8	28.5	23.4	13.1	216.0
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>729.8</b>	<b>621.5</b>	<b>474.6</b>	<b>369.0</b>	<b>250.1</b>	<b>160.0</b>	<b>97.4</b>	<b>104.8</b>	<b>177.4</b>	<b>302.1</b>	<b>396.6</b>	<b>580.4</b>	<b>4,263.4</b>


**Annual Energy Consumption by Enduse**

	<b>Electricity kWh (x000)</b>	<b>Natural Gas MBtu</b>	<b>Steam Btu</b>	<b>Chilled Water Btu</b>
Space Cool	123.8	-	-	-
Heat Reject.	5.9	-	-	-
Refrigeration	-	-	-	-
Space Heat	-	2,935.1	-	-
HP Supp.	-	-	-	-
Hot Water	-	1,112.3	-	-
Vent. Fans	217.4	-	-	-
Pumps & Aux.	145.7	-	-	-
Ext. Usage	7.8	-	-	-
Misc. Equip.	179.7	216.0	-	-
Task Lights	-	-	-	-
Area Lights	379.4	-	-	-
<b>Total</b>	<b>1,059.8</b>	<b>4,263.4</b>	-	-

- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling




**Electricity**




**Natural Gas**

**Monthly Utility Bills (\$)**




**Total Annual Bill Across All Rates: \$ 226,426**

**Electric Demand (kW)**



**Gas Demand (Btu/h)**



- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling

**Electric Demand (kW)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	9.9	9.1	9.1	3.7	95.0	142.5	143.9	134.0	165.9	45.9	5.7	9.1	773.8
Heat Reject.	-	-	-	-	5.2	5.2	12.9	5.2	10.9	3.2	-	-	42.5
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	-	-	-	-	-	-	-	-	-	-	-	-	-
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	-	-	-	-	-	-	-	-	-	-	-	-	-
Vent. Fans	67.4	66.8	66.9	66.9	79.4	88.9	70.5	72.8	94.1	59.9	66.9	67.4	868.0
Pumps & Aux.	24.6	24.5	24.5	24.7	31.2	37.4	36.4	31.6	38.0	26.6	24.5	24.5	348.5
Ext. Usage	-	-	-	-	-	-	-	0.4	-	-	-	-	0.4
Misc. Equip.	80.8	80.8	80.8	79.7	64.4	64.4	24.3	24.3	79.7	76.8	79.7	80.8	816.4
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	117.3	117.3	117.3	117.3	117.3	117.3	57.7	57.7	117.3	117.3	117.3	117.3	1,288.3
<b>Total</b>	<b>300.0</b>	<b>298.6</b>	<b>298.6</b>	<b>292.2</b>	<b>392.5</b>	<b>455.7</b>	<b>345.8</b>	<b>326.0</b>	<b>505.9</b>	<b>329.6</b>	<b>294.1</b>	<b>299.1</b>	<b>4,137.8</b>


**Gas Demand (Btu/h x1000,000)**

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Total
Space Cool	-	-	-	-	-	-	-	-	-	-	-	-	-
Heat Reject.	-	-	-	-	-	-	-	-	-	-	-	-	-
Refrigeration	-	-	-	-	-	-	-	-	-	-	-	-	-
Space Heat	2.40	2.31	2.58	2.57	1.31	0.33	0.29	0.37	0.44	1.80	2.61	2.67	19.68
HP Supp.	-	-	-	-	-	-	-	-	-	-	-	-	-
Hot Water	0.46	0.48	0.24	0.23	0.22	0.40	0.15	0.15	0.36	0.19	0.20	0.22	3.29
Vent. Fans	-	-	-	-	-	-	-	-	-	-	-	-	-
Pumps & Aux.	-	-	-	-	-	-	-	-	-	-	-	-	-
Ext. Usage	-	-	-	-	-	-	-	-	-	-	-	-	-
Misc. Equip.	0.38	0.28	0.00	0.00	0.00	0.38	-	-	0.38	0.00	0.00	0.00	1.44
Task Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
Area Lights	-	-	-	-	-	-	-	-	-	-	-	-	-
<b>Total</b>	<b>3.24</b>	<b>3.07</b>	<b>2.82</b>	<b>2.81</b>	<b>1.53</b>	<b>1.11</b>	<b>0.45</b>	<b>0.52</b>	<b>1.18</b>	<b>1.99</b>	<b>2.82</b>	<b>2.89</b>	<b>24.41</b>


**Annual Peak Demand by Enduse**

	<b>Electricity kW</b>	<b>Natural Gas Btu/h (x000)</b>	<b>Steam Btu/h</b>	<b>Chilled Water Btu/h</b>
Space Cool	165.89	-	-	-
Heat Reject.	10.87	-	-	-
Refrigeration	-	-	-	-
Space Heat	-	2,395.6	-	-
HP Supp.	-	-	-	-
Hot Water	-	460.1	-	-
Vent. Fans	94.14	-	-	-
Pumps & Aux.	37.99	-	-	-
Ext. Usage	-	-	-	-
Misc. Equip.	79.71	379.5	-	-
Task Lights	-	-	-	-
Area Lights	117.27	-	-	-
<b>Total</b>	<b>505.87</b>	<b>3,235.2</b>	<b>-</b>	<b>-</b>

- Area Lighting
- Exterior Usage
- Water Heating
- Refrigeration
- Task Lighting
- Pumps & Aux.
- Ht Pump Supp.
- Heat Rejection
- Misc. Equipment
- Ventilation Fans
- Space Heating
- Space Cooling



**Electricity**



**Natural Gas**



## Appendix

### 3 Heat Gain and Loss Calculations HVAC



## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

**TABLE 1.1.A. Component Loads For Space "1214 OFFICE" In Zone "VAV-1-1"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
<b>SPACE LOADS</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	140 ft²	0	-	140 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	98 W	303	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	210 W	687	-	0	0	-
People	3	644	615	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	82	31	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1715</b>	<b>646</b>	-	<b>0</b>	<b>0</b>

**TABLE 1.1.B. Envelope Loads For Space "1214 OFFICE" In Zone "VAV-1-1"**

				COOLING	COOLING	HEATING
	Area	U-Value	Shade	TRANS	SOLAR	TRANS
	(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

**TABLE 2.1.A. Component Loads For Space "1215 OFFICE" In Zone "VAV-1-2"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	148 ft²	0	-	148 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	104 W	320	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	222 W	726	-	0	0	-
People	3	644	615	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	85	31	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1775</b>	<b>646</b>	-	<b>0</b>	<b>0</b>

**TABLE 2.1.B. Envelope Loads For Space "1215 OFFICE" In Zone "VAV-1-2"**

		COOLING		HEATING	
		COOLING	COOLING	COOLING	HEATING
		TRANS	SOLAR	TRANS	TRANS
Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 3.1.A. Component Loads For Space "1217 PRACTICE" In Zone "VAV-1-3"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	121 ft²	0	-	121 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	85 W	262	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	61 W	198	-	0	0	-
People	3	776	1365	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	62	68	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1297</b>	<b>1433</b>	-	<b>0</b>	<b>0</b>

TABLE 3.1.B. Envelope Loads For Space "1217 PRACTICE" In Zone "VAV-1-3"							
					COOLING	COOLING	HEATING
		Area	U-Value	Shade	TRANS	SOLAR	TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 4.1.A. Component Loads For Space "1218 PRACTICE" In Zone "VAV-1-4"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	104 ft²	0	-	104 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	73 W	225	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	52 W	170	-	0	0	-
People	3	776	1365	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	59	68	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1229</b>	<b>1433</b>	-	<b>0</b>	<b>0</b>

TABLE 4.1.B. Envelope Loads For Space "1218 PRACTICE" In Zone "VAV-1-4"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 5.1.A. Component Loads For Space "1219 ENSEMBLE" In Zone "VAV-1-5"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
SPACE LOADS	Details			Details		
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	160 ft²	0	-	160 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	112 W	346	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	80 W	262	-	0	0	-
People	5	1293	2275	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	95	114	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1996</b>	<b>2389</b>	-	<b>0</b>	<b>0</b>

TABLE 5.1.B. Envelope Loads For Space "1219 ENSEMBLE" In Zone "VAV-1-5"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

**TABLE 6.1.A. Component Loads For Space "1300 LOBBY" In Zone "VAV-1-6"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	188 ft²	210	-	188 ft²	311	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	862 ft²	0	-	862 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	603 W	1787	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	-	-	0	0
Safety Factor	5% / 5%	100	0	5%	16	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>2098</b>	<b>0</b>	-	<b>326</b>	<b>0</b>

**TABLE 6.1.B. Envelope Loads For Space "1300 LOBBY" In Zone "VAV-1-6"**

				COOLING		HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>H EXPOSURE</b>						
ROOF	188	0.027	-	210	-	311



## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 7.1.A. Component Loads For Space "1310 CORRIDOR" In Zone "VAV-1-7"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
<b>SPACE LOADS</b>	Details	(BTU/hr)	(BTU/hr)	Details	(BTU/hr)	(BTU/hr)
Window & Skylight Solar Loads	175 ft²	6965	-	175 ft²	-	-
Wall Transmission	110 ft²	159	-	110 ft²	422	-
Roof Transmission	605 ft²	747	-	605 ft²	1000	-
Window Transmission	90 ft²	437	-	90 ft²	2103	-
Skylight Transmission	85 ft²	260	-	85 ft²	1255	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	690 ft²	0	-	690 ft²	457	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	483 W	1399	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	134	135	-	531	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	505	7	5%	288	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>10606</b>	<b>142</b>	-	<b>6055</b>	<b>0</b>

TABLE 7.1.B. Envelope Loads For Space "1310 CORRIDOR" In Zone "VAV-1-7"						
	Area (ft²)	U-Value (BTU/(hr-ft²-°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>E EXPOSURE</b>						
WALL	110	0.062	-	159	-	422
WINDOW 1	90	0.380	0.333	437	1781	2103
<b>H EXPOSURE</b>						
ROOF	605	0.027	-	747	-	1000
SKYLIGHT	85	0.240	0.448	260	5185	1255

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 8.1.A. Component Loads For Space "1060A CORRIDOR (W)" In Zone "VAV-1-8"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1400 COOLING OA DB / WB 86.0 °F / 70.4 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	91 ft²	2845	-	91 ft²	-	-
Wall Transmission	259 ft²	407	-	259 ft²	993	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	91 ft²	286	-	91 ft²	2127	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	1473 ft²	0	-	1473 ft²	1184	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	1031 W	2986	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	167	168	-	929	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	335	8	5%	262	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>7026</b>	<b>177</b>	-	<b>5494</b>	<b>0</b>

TABLE 8.1.B. Envelope Loads For Space "1060A CORRIDOR (W)" In Zone "VAV-1-8"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>S EXPOSURE</b>						
WALL	259	0.062	-	407	-	993
WINDOW 1	91	0.380	0.333	286	2845	2127

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

**TABLE 9.1.A. Component Loads For Space "1220 BAND" In Zone "VAV-1-9"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 89.5 °F / 72.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
<b>SPACE LOADS</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>
Window & Skylight Solar Loads	151 ft²	1726	-	151 ft²	-	-
Wall Transmission	290 ft²	297	-	290 ft²	1111	-
Roof Transmission	6 ft²	6	-	6 ft²	10	-
Window Transmission	151 ft²	720	-	151 ft²	3529	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	846 ft²	0	-	846 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	592 W	1772	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	423 W	1364	-	0	0	-
People	31	5974	3720	0	0	0
Infiltration	-	275	302	-	1170	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	607	201	5%	291	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>12742</b>	<b>4223</b>	-	<b>6112</b>	<b>0</b>

**TABLE 9.1.B. Envelope Loads For Space "1220 BAND" In Zone "VAV-1-9"**

	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>N EXPOSURE</b>						
WALL	276	0.062	-	279	-	1058
WINDOW 1	151	0.380	0.437	720	1726	3529
<b>E EXPOSURE</b>						
WALL	14	0.062	-	19	-	54
<b>H EXPOSURE</b>						
ROOF	6	0.027	-	6	-	10

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 10.1.A. Component Loads For Space "1222A/B BAND/CHOR OFFICE" In Zone "VAV-1-10"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	98 ft²	0	-	98 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	69 W	212	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	147 W	481	-	0	0	-
People	2	429	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	56	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1178</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

TABLE 10.1.B. Envelope Loads For Space "1222A/B BAND/CHOR OFFICE" In Zone "VAV-1-10"						
		COOLING		COOLING		HEATING
		TRANS		SOLAR		TRANS
		Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

**TABLE 11.1.A. Component Loads For Space "1224 CHORUS" In Zone "VAV-1-11"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 82.1 °F / 70.5 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
<b>SPACE LOADS</b>	<b>Details</b>	<b>Sensible (BTU/hr)</b>	<b>Latent (BTU/hr)</b>	<b>Details</b>	<b>Sensible (BTU/hr)</b>	<b>Latent (BTU/hr)</b>
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	8 ft²	3	-	8 ft²	13	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	851 ft²	0	-	851 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	596 W	1842	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	426 W	1391	-	0	0	-
People	32	8274	14560	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	575	728	5%	1	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>12085</b>	<b>15288</b>	-	<b>14</b>	<b>0</b>

**TABLE 11.1.B. Envelope Loads For Space "1224 CHORUS" In Zone "VAV-1-11"**

		COOLING			HEATING	
		Area	U-Value	Shade	COOLING	COOLING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR
<b>H EXPOSURE</b>				(BTU/hr)	(BTU/hr)	(BTU/hr)
ROOF	8	0.027	-	3	-	13

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 12.1.A. Component Loads For Space "1230 DRAMA CLASSROOM" In Zone "VAV-1-12"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 2100 COOLING OA DB / WB 82.1 °F / 70.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	31 ft²	227	-	31 ft²	-	-
Wall Transmission	137 ft²	136	-	137 ft²	525	-
Roof Transmission	7 ft²	3	-	7 ft²	12	-
Window Transmission	31 ft²	92	-	31 ft²	724	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	837 ft²	0	-	837 ft²	490	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	586 W	1811	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	419 W	1368	-	0	0	-
People	26	5583	5330	0	0	0
Infiltration	-	52	112	-	446	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	464	272	5%	110	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>9735</b>	<b>5714</b>	-	<b>2307</b>	<b>0</b>

TABLE 12.1.B. Envelope Loads For Space "1230 DRAMA CLASSROOM" In Zone "VAV-1-12"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>N EXPOSURE</b>						
WALL	137	0.062	-	136	-	525
WINDOW 1	31	0.380	0.437	92	227	724
<b>H EXPOSURE</b>						
ROOF	7	0.027	-	3	-	12

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 13.1.A. Component Loads For Space "1232 ART WORKROOM" In Zone "VAV-1-13"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	98 ft²	0	-	98 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	69 W	212	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	147 W	481	-	0	0	-
People	2	433	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	56	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1181</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

TABLE 13.1.B. Envelope Loads For Space "1232 ART WORKROOM" In Zone "VAV-1-13"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING	COOLING	HEATING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR	TRANS
					(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 14.1.A. Component Loads For Space "1233 ART WORKROOM" In Zone "VAV-1-14"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	68 ft²	0	-	68 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	48 W	147	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	102 W	333	-	0	0	-
People	2	429	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	46	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>956</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

TABLE 14.1.B. Envelope Loads For Space "1233 ART WORKROOM" In Zone "VAV-1-14"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING	COOLING	HEATING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR	TRANS
					(BTU/hr)	(BTU/hr)	(BTU/hr)



## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

**TABLE 15.1.A. Component Loads For Space "1234 ART" In Zone "VAV-1-15"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 91.0 °F / 73.0 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
<b>SPACE LOADS</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>
Window & Skylight Solar Loads	284 ft²	3758	-	284 ft²	-	-
Wall Transmission	262 ft²	266	-	262 ft²	1004	-
Roof Transmission	255 ft²	308	-	255 ft²	422	-
Window Transmission	284 ft²	1431	-	284 ft²	6637	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	1173 ft²	0	-	1173 ft²	1135	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	821 W	2406	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	587 W	1875	-	0	0	-
People	26	5187	5330	0	0	0
Infiltration	-	377	367	-	1449	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	780	285	5%	532	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>16388</b>	<b>5982</b>	-	<b>11179</b>	<b>0</b>

**TABLE 15.1.B. Envelope Loads For Space "1234 ART" In Zone "VAV-1-15"**

	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>NNE EXPOSURE</b>						
WALL	150	0.062	-	145	-	575
WINDOW 1	284	0.380	0.437	1431	3758	6637
<b>WNW EXPOSURE</b>						
WALL	112	0.062	-	121	-	429
<b>H EXPOSURE</b>						
ROOF	255	0.027	-	308	-	422

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 16.1.A. Component Loads For Space "1059 LEARNING COMMONS" In Zone "VAV-1-16"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	1505 ft²	0	-	1505 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	1054 W	3257	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	753 W	2460	-	0	0	-
People	33	7087	6765	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	640	338	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>13444</b>	<b>7103</b>	-	<b>0</b>	<b>0</b>

TABLE 16.1.B. Envelope Loads For Space "1059 LEARNING COMMONS" In Zone "VAV-1-16"							
					COOLING	COOLING	HEATING
		Area	U-Value	Shade	TRANS	SOLAR	TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 17.1.A. Component Loads For Space "1068 BREAKOUT" In Zone "VAV-1-17"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	208 ft²	0	-	208 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	146 W	450	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	104 W	340	-	0	0	-
People	8	1718	1640	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	125	82	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>2633</b>	<b>1722</b>	-	<b>0</b>	<b>0</b>

TABLE 17.1.B. Envelope Loads For Space "1068 BREAKOUT" In Zone "VAV-1-17"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING	COOLING	HEATING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR	TRANS
			(BTU/hr)	(BTU/hr)	(BTU/hr)		

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 18.1.A. Component Loads For Space "2210 SCIENCE CLASSROOM" In Zone "VAV-1-18"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 89.5 °F / 72.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
<b>SPACE LOADS</b>	Details	(BTU/hr)	(BTU/hr)	Details	(BTU/hr)	(BTU/hr)
Window & Skylight Solar Loads	155 ft²	4754	-	155 ft²	-	-
Wall Transmission	466 ft²	845	-	466 ft²	1786	-
Roof Transmission	386 ft²	378	-	386 ft²	638	-
Window Transmission	155 ft²	740	-	155 ft²	3622	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	874 W	2613	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	624 W	2012	-	0	0	-
People	26	5338	5330	0	0	0
Infiltration	-	388	426	-	1648	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	853	288	5%	385	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>17922</b>	<b>6044</b>	-	<b>8079</b>	<b>0</b>

TABLE 18.1.B. Envelope Loads For Space "2210 SCIENCE CLASSROOM" In Zone "VAV-1-18"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>W EXPOSURE</b>						
WALL	466	0.062	-	845	-	1786
WINDOW 1	155	0.380	0.333	740	4754	3622
<b>H EXPOSURE</b>						
ROOF	386	0.027	-	378	-	638

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 19.1.A. Component Loads For Space "2211A SCIENCE-PREP" In Zone "VAV-1-19"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	57 W	175	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	41 W	132	-	0	0	-
People	2	429	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	37	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>774</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

TABLE 19.1.B. Envelope Loads For Space "2211A SCIENCE-PREP" In Zone "VAV-1-19"							
					COOLING	COOLING	HEATING
		Area	U-Value	Shade	TRANS	SOLAR	TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 19.2.A. Component Loads For Space "2211B SCIENCE-PREP" In Zone "VAV-1-19"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	56 W	173	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	40 W	131	-	0	0	-
People	2	429	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	37	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>770</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

TABLE 19.2.B. Envelope Loads For Space "2211B SCIENCE-PREP" In Zone "VAV-1-19"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING	COOLING	HEATING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR	TRANS
			(BTU/hr)	(BTU/hr)	(BTU/hr)		

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 20.1.A. Component Loads For Space "2212 SCIENCE-TP" In Zone "VAV-1-20"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	69 W	212	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	49 W	160	-	0	0	-
People	2	429	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	40	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>842</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

TABLE 20.1.B. Envelope Loads For Space "2212 SCIENCE-TP" In Zone "VAV-1-20"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 21.1.A. Component Loads For Space "2214 SCIENCE CLASSROOM" In Zone "VAV-1-21"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500 COOLING OA DB / WB 91.0 °F / 73.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	155 ft²	2928	-	155 ft²	-	-
Wall Transmission	55 ft²	77	-	55 ft²	211	-
Roof Transmission	377 ft²	455	-	377 ft²	623	-
Window Transmission	155 ft²	781	-	155 ft²	3622	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	873 W	2558	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	624 W	1993	-	0	0	-
People	26	5187	5330	0	0	0
Infiltration	-	145	136	-	557	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	706	273	5%	251	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>14830</b>	<b>5740</b>	-	<b>5264</b>	<b>0</b>

TABLE 21.1.B. Envelope Loads For Space "2214 SCIENCE CLASSROOM" In Zone "VAV-1-21"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>E EXPOSURE</b>						
WALL	55	0.062	-	77	-	211
WINDOW 1	155	0.380	0.333	781	2928	3622
<b>H EXPOSURE</b>						
ROOF	377	0.027	-	455	-	623



## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 22.1.A. Component Loads For Space "2222 CLASSROOM-TP" In Zone "VAV-1-22"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	90 ft²	0	-	90 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	67 W	208	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	48 W	157	-	0	0	-
People	2	429	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	40	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>834</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

TABLE 22.1.B. Envelope Loads For Space "2222 CLASSROOM-TP" In Zone "VAV-1-22"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING	COOLING	HEATING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR	TRANS
			(BTU/hr)	(BTU/hr)	(BTU/hr)		

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 23.1.A. Component Loads For Space "2224 CLASSROOM" In Zone "VAV-1-23"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	Details			Details		
Window & Skylight Solar Loads	175 ft²	2212	-	175 ft²	-	-
Wall Transmission	282 ft²	329	-	282 ft²	1081	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	175 ft²	873	-	175 ft²	4090	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	610 W	1806	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	436 W	1398	-	0	0	-
People	26	5265	5330	0	0	0
Infiltration	-	306	310	-	1213	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	610	282	5%	319	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>12800</b>	<b>5922</b>	-	<b>6703</b>	<b>0</b>

TABLE 23.1.B. Envelope Loads For Space "2224 CLASSROOM" In Zone "VAV-1-23"						
	Area (ft²)	U-Value (BTU/(hr-ft²-°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>NNE EXPOSURE</b>						
WALL	157	0.062	-	160	-	602
WINDOW 1	175	0.380	0.437	873	2212	4090
<b>E EXPOSURE</b>						
WALL	56	0.062	-	76	-	215
<b>WNW EXPOSURE</b>						
WALL	69	0.062	-	93	-	264

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 24.1.A. Component Loads For Space "2060A CORRIDOR (W)" In Zone "VAV-1-24"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1400 COOLING OA DB / WB 86.0 °F / 70.4 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	115 ft²	3596	-	115 ft²	-	-
Wall Transmission	185 ft²	291	-	185 ft²	709	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	115 ft²	361	-	115 ft²	2688	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	1018 W	2948	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	143	144	-	796	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	367	7	5%	210	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>7705</b>	<b>151</b>	-	<b>4402</b>	<b>0</b>

TABLE 24.1.B. Envelope Loads For Space "2060A CORRIDOR (W)" In Zone "VAV-1-24"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>S EXPOSURE</b>						
WALL	185	0.062	-	291	-	709
WINDOW 1	115	0.380	0.333	361	3596	2688

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 25.1.A. Component Loads For Space "2230 CLASSROOM-ELL" In Zone "VAV-1-25"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1700 COOLING OA DB / WB 86.5 °F / 70.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	190 ft²	2486	-	190 ft²	-	-
Wall Transmission	238 ft²	221	-	238 ft²	912	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	190 ft²	690	-	190 ft²	4440	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	610 W	1826	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	436 W	1406	-	0	0	-
People	26	5338	5330	0	0	0
Infiltration	-	212	216	-	1136	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	609	277	5%	324	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>12788</b>	<b>5823</b>	-	<b>6813</b>	<b>0</b>

TABLE 25.1.B. Envelope Loads For Space "2230 CLASSROOM-ELL" In Zone "VAV-1-25"						
	Area (ft²)	U-Value (BTU/(hr-ft²-°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>N EXPOSURE</b>						
WALL	161	0.062	-	137	-	617
WINDOW 1	190	0.380	0.437	690	2486	4440
<b>ENE EXPOSURE</b>						
WALL	56	0.062	-	61	-	215
<b>E EXPOSURE</b>						
WALL	21	0.062	-	24	-	80

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 26.1.A. Component Loads For Space "2232 CLASSROOM-TP" In Zone "VAV-1-26"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	90 ft²	0	-	90 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	69 W	212	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	49 W	160	-	0	0	-
People	2	429	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	40	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>842</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

TABLE 26.1.B. Envelope Loads For Space "2232 CLASSROOM-TP" In Zone "VAV-1-26"							
					COOLING	COOLING	HEATING
		Area	U-Value	Shade	TRANS	SOLAR	TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 27.1.A. Component Loads For Space "2234 CLASSROOM" In Zone "VAV-1-27"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500 COOLING OA DB / WB 91.0 °F / 73.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	Details			Details		
Window & Skylight Solar Loads	190 ft²	2514	-	190 ft²	-	-
Wall Transmission	267 ft²	289	-	267 ft²	1023	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	190 ft²	957	-	190 ft²	4440	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	613 W	1797	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	438 W	1400	-	0	0	-
People	26	5187	5330	0	0	0
Infiltration	-	316	309	-	1213	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	623	282	5%	334	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>13084</b>	<b>5921</b>	-	<b>7010</b>	<b>0</b>

TABLE 27.1.B. Envelope Loads For Space "2234 CLASSROOM" In Zone "VAV-1-27"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>NNE EXPOSURE</b>						
WALL	142	0.062	-	137	-	544
WINDOW 1	190	0.380	0.437	957	2514	4440
<b>E EXPOSURE</b>						
WALL	56	0.062	-	78	-	215
<b>WNW EXPOSURE</b>						
WALL	69	0.062	-	75	-	264

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 28.1.A. Component Loads For Space "2059 COHORT COMMON" In Zone "VAV-1-28"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	800 W	2474	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	572 W	1868	-	0	0	-
People	30	6442	6150	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	539	308	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>11323</b>	<b>6458</b>	-	<b>0</b>	<b>0</b>

TABLE 28.1.B. Envelope Loads For Space "2059 COHORT COMMON" In Zone "VAV-1-28"						
				COOLING	COOLING	HEATING
	Area	U-Value	Shade	TRANS	SOLAR	TRANS
	(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 29.1.A. Component Loads For Space "2056 BREAKOUT" In Zone "VAV-1-29"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
SPACE LOADS	Details			Details		
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	137 W	422	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	98 W	319	-	0	0	-
People	13	2792	2665	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	177	133	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>3709</b>	<b>2798</b>	-	<b>0</b>	<b>0</b>

TABLE 29.1.B. Envelope Loads For Space "2056 BREAKOUT" In Zone "VAV-1-29"						
				COOLING	COOLING	HEATING
	Area	U-Value	Shade	TRANS	SOLAR	TRANS
	(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)



## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 30.1.A. Component Loads For Space "3210 CLASSROOM" In Zone "VAV-1-30"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 89.5 °F / 72.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
<b>SPACE LOADS</b>	Details	(BTU/hr)	(BTU/hr)	Details	(BTU/hr)	(BTU/hr)
Window & Skylight Solar Loads	185 ft²	3661	-	185 ft²	-	-
Wall Transmission	635 ft²	963	-	635 ft²	2434	-
Roof Transmission	880 ft²	862	-	880 ft²	1455	-
Window Transmission	185 ft²	883	-	185 ft²	4323	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	616 W	1843	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	440 W	1419	-	0	0	-
People	26	5338	5330	0	0	0
Infiltration	-	512	564	-	2176	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	774	295	5%	519	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>16253</b>	<b>6189</b>	-	<b>10907</b>	<b>0</b>

TABLE 30.1.B. Envelope Loads For Space "3210 CLASSROOM" In Zone "VAV-1-30"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NNW EXPOSURE</b>						
WALL	201	0.062	-	227	-	770
WINDOW 1	185	0.380	0.437	883	3661	4323
<b>NE EXPOSURE</b>						
WALL	63	0.062	-	73	-	241
<b>W EXPOSURE</b>						
WALL	350	0.062	-	635	-	1341
<b>E EXPOSURE</b>						
WALL	21	0.062	-	28	-	80
<b>H EXPOSURE</b>						
ROOF	880	0.027	-	862	-	1455

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 31.1.A. Component Loads For Space "3212 CLASSROOM-TP" In Zone "VAV-1-31"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	96 ft²	107	-	96 ft²	159	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	67 W	199	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	48 W	154	-	0	0	-
People	2	405	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	43	21	5%	8	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>909</b>	<b>431</b>	-	<b>167</b>	<b>0</b>

TABLE 31.1.B. Envelope Loads For Space "3212 CLASSROOM-TP" In Zone "VAV-1-31"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>H EXPOSURE</b>						
ROOF	96	0.027	-	107	-	159

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 32.1.A. Component Loads For Space "3214 CLASSROOM" In Zone "VAV-1-32"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 89.5 °F / 72.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
SPACE LOADS	Details	(BTU/hr)	(BTU/hr)	Details	(BTU/hr)	(BTU/hr)
Window & Skylight Solar Loads	185 ft²	2115	-	185 ft²	-	-
Wall Transmission	340 ft²	402	-	340 ft²	1303	-
Roof Transmission	868 ft²	850	-	868 ft²	1435	-
Window Transmission	185 ft²	883	-	185 ft²	4323	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	608 W	1818	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	434 W	1399	-	0	0	-
People	26	5338	5330	0	0	0
Infiltration	-	328	360	-	1393	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	657	284	5%	423	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>13788</b>	<b>5974</b>	-	<b>8877</b>	<b>0</b>

TABLE 32.1.B. Envelope Loads For Space "3214 CLASSROOM" In Zone "VAV-1-32"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>N EXPOSURE</b>						
WALL	207	0.062	-	209	-	793
WINDOW 1	185	0.380	0.437	883	2115	4323
<b>ENE EXPOSURE</b>						
WALL	63	0.062	-	79	-	241
<b>WNW EXPOSURE</b>						
WALL	70	0.062	-	114	-	268
<b>H EXPOSURE</b>						
ROOF	868	0.027	-	850	-	1435

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 33.1.A. Component Loads For Space "3220 CLASSROOM" In Zone "VAV-1-33"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 89.5 °F / 72.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	144 ft²	1646	-	144 ft²	-	-
Wall Transmission	360 ft²	402	-	360 ft²	1380	-
Roof Transmission	869 ft²	851	-	869 ft²	1437	-
Window Transmission	144 ft²	687	-	144 ft²	3365	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	608 W	1820	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	435 W	1401	-	0	0	-
People	26	5338	5330	0	0	0
Infiltration	-	315	345	-	1338	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	623	284	5%	376	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>13082</b>	<b>5959</b>	-	<b>7895</b>	<b>0</b>

TABLE 33.1.B. Envelope Loads For Space "3220 CLASSROOM" In Zone "VAV-1-33"						
	Area (ft²)	U-Value (BTU/(hr-ft²-°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>N EXPOSURE</b>						
WALL	248	0.062	-	250	-	950
WINDOW 1	144	0.380	0.437	687	1646	3365
<b>NE EXPOSURE</b>						
WALL	63	0.062	-	73	-	241
<b>W EXPOSURE</b>						
WALL	28	0.062	-	51	-	107
<b>E EXPOSURE</b>						
WALL	21	0.062	-	28	-	80
<b>H EXPOSURE</b>						
ROOF	869	0.027	-	851	-	1437

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 34.1.A. Component Loads For Space "3222 CLASSROOM-TP" In Zone "VAV-1-34"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	98 ft²	110	-	98 ft²	162	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	69 W	203	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	49 W	157	-	0	0	-
People	2	405	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	44	21	5%	8	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>919</b>	<b>431</b>	-	<b>170</b>	<b>0</b>

TABLE 34.1.B. Envelope Loads For Space "3222 CLASSROOM-TP" In Zone "VAV-1-34"						
				COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>H EXPOSURE</b>						
ROOF	98	0.027	-	110	-	162

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 35.1.A. Component Loads For Space "3060A CORRIDOR (W)" In Zone "VAV-1-35"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	400 ft²	19690	-	400 ft²	-	-
Wall Transmission	439 ft²	581	-	439 ft²	1682	-
Roof Transmission	1155 ft²	1427	-	1155 ft²	1909	-
Window Transmission	107 ft²	519	-	107 ft²	2501	-
Skylight Transmission	293 ft²	898	-	293 ft²	4325	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	1014 W	2936	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	366	372	-	1449	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	1321	19	5%	593	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>27737</b>	<b>391</b>	-	<b>12459</b>	<b>0</b>

TABLE 35.1.B. Envelope Loads For Space "3060A CORRIDOR (W)" In Zone "VAV-1-35"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>S EXPOSURE</b>						
WALL	439	0.062	-	581	-	1682
WINDOW 1	107	0.380	0.333	519	1819	2501
<b>H EXPOSURE</b>						
ROOF	1155	0.027	-	1427	-	1909
SKYLIGHT	293	0.240	0.448	898	17872	4325

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 36.1.A. Component Loads For Space "3224 CLASSROOM" In Zone "VAV-1-36"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500 COOLING OA DB / WB 91.0 °F / 73.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	Details			Details		
Window & Skylight Solar Loads	185 ft²	2448	-	185 ft²	-	-
Wall Transmission	312 ft²	334	-	312 ft²	1196	-
Roof Transmission	874 ft²	1054	-	874 ft²	1445	-
Window Transmission	185 ft²	932	-	185 ft²	4323	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	612 W	1793	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	437 W	1397	-	0	0	-
People	26	5187	5330	0	0	0
Infiltration	-	343	338	-	1319	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	674	283	5%	414	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>14164</b>	<b>5952</b>	-	<b>8697</b>	<b>0</b>

TABLE 36.1.B. Envelope Loads For Space "3224 CLASSROOM" In Zone "VAV-1-36"						
	Area (ft²)	U-Value (BTU/(hr-ft²-°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>NNE EXPOSURE</b>						
WALL	207	0.062	-	200	-	793
WINDOW 1	185	0.380	0.437	932	2448	4323
<b>ENE EXPOSURE</b>						
WALL	63	0.062	-	80	-	241
<b>E EXPOSURE</b>						
WALL	21	0.062	-	29	-	80
<b>W EXPOSURE</b>						
WALL	21	0.062	-	26	-	80
<b>H EXPOSURE</b>						
ROOF	874	0.027	-	1054	-	1445

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 37.1.A. Component Loads For Space "3230 CLASSROOM" In Zone "VAV-1-37"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 89.5 °F / 72.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	185 ft²	2115	-	185 ft²	-	-
Wall Transmission	312 ft²	348	-	312 ft²	1196	-
Roof Transmission	876 ft²	858	-	876 ft²	1448	-
Window Transmission	185 ft²	883	-	185 ft²	4323	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	613 W	1834	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	438 W	1412	-	0	0	-
People	26	5338	5330	0	0	0
Infiltration	-	310	341	-	1319	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	655	284	5%	414	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>13752</b>	<b>5954</b>	-	<b>8701</b>	<b>0</b>

TABLE 37.1.B. Envelope Loads For Space "3230 CLASSROOM" In Zone "VAV-1-37"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>N EXPOSURE</b>						
WALL	207	0.062	-	209	-	793
WINDOW 1	185	0.380	0.437	883	2115	4323
<b>NE EXPOSURE</b>						
WALL	63	0.062	-	73	-	241
<b>W EXPOSURE</b>						
WALL	21	0.062	-	38	-	80
<b>E EXPOSURE</b>						
WALL	21	0.062	-	28	-	80
<b>H EXPOSURE</b>						
ROOF	876	0.027	-	858	-	1448



## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 38.1.A. Component Loads For Space "3232 CLASSROOM-TP" In Zone "VAV-1-38"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	94 ft²	105	-	94 ft²	155	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	66 W	195	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	47 W	151	-	0	0	-
People	2	405	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	43	21	5%	8	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>899</b>	<b>431</b>	-	<b>163</b>	<b>0</b>

TABLE 38.1.B. Envelope Loads For Space "3232 CLASSROOM-TP" In Zone "VAV-1-38"						
	Area (ft²)	U-Value	Shade Coeff.	COOLING	COOLING	HEATING
		(BTU/(hr-ft²·°F))		TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
	<b>H EXPOSURE</b>					
ROOF	94	0.027	-	105	-	155

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 39.1.A. Component Loads For Space "3234 CLASSROOM" In Zone "VAV-1-39"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500 COOLING OA DB / WB 91.0 °F / 73.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	185 ft²	2448	-	185 ft²	-	-
Wall Transmission	340 ft²	355	-	340 ft²	1303	-
Roof Transmission	872 ft²	1052	-	872 ft²	1442	-
Window Transmission	185 ft²	932	-	185 ft²	4323	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	610 W	1789	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	436 W	1394	-	0	0	-
People	26	5187	5330	0	0	0
Infiltration	-	362	358	-	1393	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	676	284	5%	423	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>14195</b>	<b>5972</b>	-	<b>8884</b>	<b>0</b>

TABLE 39.1.B. Envelope Loads For Space "3234 CLASSROOM" In Zone "VAV-1-39"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>NNE EXPOSURE</b>						
WALL	207	0.062	-	200	-	793
WINDOW 1	185	0.380	0.437	932	2448	4323
<b>ENE EXPOSURE</b>						
WALL	63	0.062	-	80	-	241
<b>WNW EXPOSURE</b>						
WALL	70	0.062	-	76	-	268
<b>H EXPOSURE</b>						
ROOF	872	0.027	-	1052	-	1442

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 40.1.A. Component Loads For Space "3068 BREAKOUT" In Zone "VAV-1-40"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1400 COOLING OA DB / WB 87.5 °F / 70.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	216 ft²	11930	-	216 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	20 ft²	24	-	20 ft²	33	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	216 ft²	506	-	216 ft²	3188	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	156 W	452	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	112 W	355	-	0	0	-
People	8	1571	1640	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	742	82	5%	161	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>15579</b>	<b>1722</b>	-	<b>3382</b>	<b>0</b>

TABLE 40.1.B. Envelope Loads For Space "3068 BREAKOUT" In Zone "VAV-1-40"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>H EXPOSURE</b>						
ROOF	20	0.027	-	24	-	33
<b>W EXPOSURE</b>						
SKYLIGHT	123	0.240	0.448	288	7269	1815
<b>E EXPOSURE</b>						
SKYLIGHT	93	0.240	0.448	218	4661	1373

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 41.1.A. Component Loads For Space "1166 STAFF LUNCH" In Zone "VAV-1-41"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 1600			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
<b>SPACE LOADS</b>	Details	(BTU/hr)	(BTU/hr)	Details	(BTU/hr)	(BTU/hr)
Window & Skylight Solar Loads	113 ft²	3323	-	113 ft²	-	-
Wall Transmission	384 ft²	491	-	384 ft²	1472	-
Roof Transmission	30 ft²	31	-	30 ft²	50	-
Window Transmission	113 ft²	564	-	113 ft²	2641	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	370 ft²	0	-	370 ft²	606	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	259 W	767	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	93 W	297	-	0	0	-
People	12	2430	2460	0	0	0
Infiltration	-	333	341	-	1319	0
Miscellaneous	-	400	0	-	0	0
Safety Factor	5% / 5%	432	140	5%	304	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>9067</b>	<b>2941</b>	-	<b>6391</b>	<b>0</b>

TABLE 41.1.B. Envelope Loads For Space "1166 STAFF LUNCH" In Zone "VAV-1-41"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NW EXPOSURE</b>						
WALL	266	0.062	-	281	-	1019
<b>SW EXPOSURE</b>						
WALL	62	0.062	-	111	-	238
WINDOW 1	113	0.380	0.333	564	3323	2641
<b>S EXPOSURE</b>						
WALL	56	0.062	-	98	-	215
<b>H EXPOSURE</b>						
ROOF	30	0.027	-	31	-	50

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 42.1.A. Component Loads For Space "1160 TECH/FAB LAB" In Zone "VAV-1-42"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1500 COOLING OA DB / WB 86.5 °F / 70.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	236 ft²	7816	-	236 ft²	-	-
Wall Transmission	475 ft²	556	-	475 ft²	1820	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	236 ft²	786	-	236 ft²	5515	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	1202 ft²	0	-	1202 ft²	1324	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	841 W	2465	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	601 W	1921	-	0	0	-
People	20	3990	4100	0	0	0
Infiltration	-	353	355	-	1887	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	894	223	5%	527	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>18782</b>	<b>4677</b>	-	<b>11074</b>	<b>0</b>

TABLE 42.1.B. Envelope Loads For Space "1160 TECH/FAB LAB" In Zone "VAV-1-42"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>NW EXPOSURE</b>						
WALL	133	0.062	-	68	-	510
<b>SW EXPOSURE</b>						
WALL	209	0.062	-	299	-	801
WINDOW 1	236	0.380	0.333	786	7816	5515
<b>SE EXPOSURE</b>						
WALL	133	0.062	-	189	-	510

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 43.1.A. Component Loads For Space "1000A CORRIDOR (W)" In Zone "VAV-1-43"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	1805 ft²	0	-	1805 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	1315 W	4066	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	203	0	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>4270</b>	<b>0</b>	-	<b>0</b>	<b>0</b>

TABLE 43.1.B. Envelope Loads For Space "1000A CORRIDOR (W)" In Zone "VAV-1-43"							
					COOLING	COOLING	HEATING
		Area	U-Value	Shade	TRANS	SOLAR	TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 43.2.A. Component Loads For Space "1150 TOILET (4 STALL)" In Zone "VAV-1-43"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 1600 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	31 ft²	912	-	31 ft²	-	-
Wall Transmission	117 ft²	210	-	117 ft²	448	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	31 ft²	155	-	31 ft²	724	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	240 ft²	0	-	240 ft²	268	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	168 W	498	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	99	121	-	393	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	94	6	5%	92	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1967</b>	<b>127</b>	-	<b>1926</b>	<b>0</b>

TABLE 43.2.B. Envelope Loads For Space "1150 TOILET (4 STALL)" In Zone "VAV-1-43"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>SW EXPOSURE</b>						
WALL	117	0.062	-	210	-	448
WINDOW 1	31	0.380	0.333	155	912	724

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 43.3.A. Component Loads For Space "1152 TOILET (1 STALL)" In Zone "VAV-1-43"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	54 ft²	0	-	54 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	38 W	117	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	6	0	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>123</b>	<b>0</b>	-	<b>0</b>	<b>0</b>

TABLE 43.3.B. Envelope Loads For Space "1152 TOILET (1 STALL)" In Zone "VAV-1-43"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING	COOLING	HEATING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR	TRANS
			(BTU/hr)	(BTU/hr)	(BTU/hr)		



## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 43.4.A. Component Loads For Space "1153 STOREROOM" In Zone "VAV-1-43"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 1800 COOLING OA DB / WB 87.8 °F / 72.1 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	84 ft²	172	-	84 ft²	322	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	150 ft²	0	-	150 ft²	160	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	105 W	317	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	46	69	-	223	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	27	3	5%	35	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>562</b>	<b>73</b>	-	<b>740</b>	<b>0</b>

TABLE 43.4.B. Envelope Loads For Space "1153 STOREROOM" In Zone "VAV-1-43"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>SW EXPOSURE</b>						
WALL	84	0.062	-	172	-	322

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 43.5.A. Component Loads For Space "1154 TOILET (1 STALL)" In Zone "VAV-1-43"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	54 ft²	0	-	54 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	38 W	117	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	6	0	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>123</b>	<b>0</b>	-	<b>0</b>	<b>0</b>

TABLE 43.5.B. Envelope Loads For Space "1154 TOILET (1 STALL)" In Zone "VAV-1-43"						
		COOLING		COOLING		HEATING
		TRANS		SOLAR		TRANS
		Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 43.6.A. Component Loads For Space "1156 TOILET (4 STALL)" In Zone "VAV-1-43"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 1600 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	31 ft²	912	-	31 ft²	-	-
Wall Transmission	109 ft²	196	-	109 ft²	418	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	31 ft²	155	-	31 ft²	724	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	229 ft²	0	-	229 ft²	256	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	160 W	475	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	94	115	-	372	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	92	6	5%	88	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1922</b>	<b>120</b>	-	<b>1858</b>	<b>0</b>

TABLE 43.6.B. Envelope Loads For Space "1156 TOILET (4 STALL)" In Zone "VAV-1-43"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>SW EXPOSURE</b>						
WALL	109	0.062	-	196	-	418
WINDOW 1	31	0.380	0.333	155	912	724

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 44.1.A. Component Loads For Space "1055A CAF/LEARN COMM" In Zone "VAV-1-44"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1400 COOLING OA DB / WB 87.5 °F / 70.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	1054 ft²	66795	-	1054 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	1284 ft²	1518	-	1284 ft²	2123	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	1054 ft²	2470	-	1054 ft²	15557	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	2338 ft²	0	-	2338 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	1637 W	4740	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	585 W	1860	-	0	0	-
People	216	39808	25920	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	5860	1296	5%	884	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>123051</b>	<b>27216</b>	-	<b>18564</b>	<b>0</b>

TABLE 44.1.B. Envelope Loads For Space "1055A CAF/LEARN COMM" In Zone "VAV-1-44"						
	Area (ft²)	U-Value (BTU/(hr-ft²-°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>H EXPOSURE</b>						
ROOF	1284	0.027	-	1518	-	2123
SKYLIGHT	1054	0.240	0.448	2470	66795	15557

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 45.1.A. Component Loads For Space "1008 CORRIDOR" In Zone "VAV-1-45"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1900 COOLING OA DB / WB 85.8 °F / 71.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	273 ft²	457	-	273 ft²	1046	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	334 ft²	0	-	334 ft²	430	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	234 W	712	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	127	190	-	725	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	65	10	5%	110	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1361</b>	<b>200</b>	-	<b>2311</b>	<b>0</b>

TABLE 45.1.B. Envelope Loads For Space "1008 CORRIDOR" In Zone "VAV-1-45"						
	Area (ft²)	U-Value (BTU/(hr-ft²-°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NW EXPOSURE</b>						
WALL	273	0.062	-	457	-	1046

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 45.2.A. Component Loads For Space "1010 RECEIVING" In Zone "VAV-1-45"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1900 COOLING OA DB / WB 85.8 °F / 71.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	207 ft²	347	-	207 ft²	793	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	312 ft²	0	-	312 ft²	363	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	218 W	665	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	2	507	910	0	0	0
Infiltration	-	96	144	-	549	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	81	53	5%	85	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1696</b>	<b>1107</b>	-	<b>1791</b>	<b>0</b>

TABLE 45.2.B. Envelope Loads For Space "1010 RECEIVING" In Zone "VAV-1-45"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NW EXPOSURE</b>						
WALL	207	0.062	-	347	-	793

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 45.3.A. Component Loads For Space "1011 CUSTODIAN WORKSHOP" In Zone "VAV-1-45"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	251 ft²	0	-	251 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	176 W	543	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	300 W	981	-	0	0	-
People	2	517	910	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	102	46	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>2143</b>	<b>956</b>	-	<b>0</b>	<b>0</b>

TABLE 45.3.B. Envelope Loads For Space "1011 CUSTODIAN WORKSHOP" In Zone "VAV-1-45"							
					COOLING	COOLING	HEATING
		Area	U-Value	Shade	TRANS	SOLAR	TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 45.4.A. Component Loads For Space "1011A CUSTODIAL STORAGE" In Zone "VAV-1-45"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	45 ft²	0	-	45 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	32 W	97	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	5	0	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>102</b>	<b>0</b>	-	<b>0</b>	<b>0</b>

TABLE 45.4.B. Envelope Loads For Space "1011A CUSTODIAL STORAGE" In Zone "VAV-1-45"							
					COOLING	COOLING	HEATING
		Area	U-Value	Shade	TRANS	SOLAR	TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)



## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 45.5.A. Component Loads For Space "1020 CORRIDOR" In Zone "VAV-1-45"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	91 ft²	138	-	91 ft²	349	-
Roof Transmission	250 ft²	309	-	250 ft²	413	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	219 ft²	0	-	219 ft²	199	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	153 W	444	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	61	64	-	242	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	48	3	5%	60	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1000</b>	<b>67</b>	-	<b>1263</b>	<b>0</b>

TABLE 45.5.B. Envelope Loads For Space "1020 CORRIDOR" In Zone "VAV-1-45"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>ESE EXPOSURE</b>						
WALL	91	0.062	-	138	-	349
<b>H EXPOSURE</b>						
ROOF	250	0.027	-	309	-	413

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 46.1.A. Component Loads For Space "1027 CUST OFFICE/BREAK" In Zone "VAV-1-46"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700 COOLING OA DB / WB 89.5 °F / 72.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	30 ft²	675	-	30 ft²	-	-
Wall Transmission	509 ft²	804	-	509 ft²	1951	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	30 ft²	143	-	30 ft²	701	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	328 ft²	0	-	328 ft²	561	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	230 W	687	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	492 W	1586	-	0	0	-
People	9	1848	1845	0	0	0
Infiltration	-	337	370	-	1430	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	304	111	5%	232	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>6384</b>	<b>2326</b>	-	<b>4875</b>	<b>0</b>

TABLE 46.1.B. Envelope Loads For Space "1027 CUST OFFICE/BREAK" In Zone "VAV-1-46"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NW EXPOSURE</b>						
WALL	194	0.062	-	269	-	744
WINDOW 1	30	0.380	0.333	143	675	701
<b>SSW EXPOSURE</b>						
WALL	315	0.062	-	535	-	1207

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 47.1.A. Component Loads For Space "1141 KITCHEN OFFICE" In Zone "VAV-1-47"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	75 ft²	0	-	75 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	53 W	162	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	113 W	368	-	0	0	-
People	2	429	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	48	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1008</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

TABLE 47.1.B. Envelope Loads For Space "1141 KITCHEN OFFICE" In Zone "VAV-1-47"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING	COOLING	HEATING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR	TRANS
			(BTU/hr)	(BTU/hr)	(BTU/hr)		

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 48.1.A. Component Loads For Space "2168B SPED-READING" In Zone "VAV-1-48"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1900 COOLING OA DB / WB 85.8 °F / 71.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	182 ft²	305	-	182 ft²	698	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	141 W	428	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	101 W	326	-	0	0	-
People	4	790	480	0	0	0
Infiltration	-	85	124	-	483	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	97	30	5%	59	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>2031</b>	<b>634</b>	-	<b>1240</b>	<b>0</b>

TABLE 48.1.B. Envelope Loads For Space "2168B SPED-READING" In Zone "VAV-1-48"						
		COOLING		COOLING		HEATING
		TRANS		SOLAR		TRANS
		Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	(BTU/hr)	(BTU/hr)
<b>NW EXPOSURE</b>						
WALL	182	0.062	-	305	-	698

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 49.1.A. Component Loads For Space "2168A SPED-READING" In Zone "VAV-1-49"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	95 W	292	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	68 W	221	-	0	0	-
People	4	806	480	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	66	24	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1385</b>	<b>504</b>	-	<b>0</b>	<b>0</b>

TABLE 49.1.B. Envelope Loads For Space "2168A SPED-READING" In Zone "VAV-1-49"						
				COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 50.1.A. Component Loads For Space "2168C SPED-RESOURCE" In Zone "VAV-1-50"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 1600			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
<b>SPACE LOADS</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>
Window & Skylight Solar Loads	63 ft²	1853	-	63 ft²	-	-
Wall Transmission	586 ft²	894	-	586 ft²	2246	-
Roof Transmission	16 ft²	17	-	16 ft²	27	-
Window Transmission	63 ft²	314	-	63 ft²	1472	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	351 W	1041	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	251 W	806	-	0	0	-
People	16	3240	3280	0	0	0
Infiltration	-	435	445	-	1722	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	430	186	5%	273	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>9030</b>	<b>3911</b>	-	<b>5741</b>	<b>0</b>

TABLE 50.1.B. Envelope Loads For Space "2168C SPED-RESOURCE" In Zone "VAV-1-50"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NW EXPOSURE</b>						
WALL	215	0.062	-	228	-	824
<b>SW EXPOSURE</b>						
WALL	371	0.062	-	667	-	1422
WINDOW 1	63	0.380	0.333	314	1853	1472
<b>H EXPOSURE</b>						
ROOF	16	0.027	-	17	-	27

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 51.1.A. Component Loads For Space "2166 GUIDANCE-OFFICE" In Zone "VAV-1-51"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	95 W	292	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	203 W	662	-	0	0	-
People	4	859	820	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	91	41	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1904</b>	<b>861</b>	-	<b>0</b>	<b>0</b>

TABLE 51.1.B. Envelope Loads For Space "2166 GUIDANCE-OFFICE" In Zone "VAV-1-51"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 52.1.A. Component Loads For Space "2165 GUIDANCE-OFFICE" In Zone "VAV-1-52"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1500 COOLING OA DB / WB 86.5 °F / 70.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	66 ft²	2132	-	66 ft²	-	-
Wall Transmission	195 ft²	176	-	195 ft²	747	-
Roof Transmission	135 ft²	111	-	135 ft²	223	-
Window Transmission	66 ft²	220	-	66 ft²	1542	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	107 W	314	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	230 W	734	-	0	0	-
People	2	399	410	0	0	0
Infiltration	-	130	130	-	693	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	211	27	5%	160	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>4425</b>	<b>568</b>	-	<b>3366</b>	<b>0</b>

TABLE 52.1.B. Envelope Loads For Space "2165 GUIDANCE-OFFICE" In Zone "VAV-1-52"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>NW EXPOSURE</b>						
WALL	127	0.062	-	65	-	487
<b>SSW EXPOSURE</b>						
WALL	68	0.062	-	111	-	261
WINDOW 1	66	0.380	0.333	220	2132	1542
<b>H EXPOSURE</b>						
ROOF	135	0.027	-	111	-	223



## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 53.1.A. Component Loads For Space "2164 OFFICE-DEPT" In Zone "VAV-1-53"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1500 COOLING OA DB / WB 86.5 °F / 70.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	90 ft²	2981	-	90 ft²	-	-
Wall Transmission	40 ft²	57	-	40 ft²	153	-
Roof Transmission	135 ft²	111	-	135 ft²	223	-
Window Transmission	90 ft²	300	-	90 ft²	2103	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	111 W	326	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	239 W	763	-	0	0	-
People	2	399	410	0	0	0
Infiltration	-	65	65	-	345	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	250	24	5%	141	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>5250</b>	<b>499</b>	-	<b>2966</b>	<b>0</b>

TABLE 53.1.B. Envelope Loads For Space "2164 OFFICE-DEPT" In Zone "VAV-1-53"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>SW EXPOSURE</b>						
WALL	40	0.062	-	57	-	153
WINDOW 1	90	0.380	0.333	300	2981	2103
<b>H EXPOSURE</b>						
ROOF	135	0.027	-	111	-	223

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 54.1.A. Component Loads For Space "2163 OFFICE-DEPT" In Zone "VAV-1-54"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1500 COOLING OA DB / WB 86.5 °F / 70.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	66 ft²	2186	-	66 ft²	-	-
Wall Transmission	185 ft²	263	-	185 ft²	709	-
Roof Transmission	81 ft²	66	-	81 ft²	133	-
Window Transmission	66 ft²	220	-	66 ft²	1542	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	111 W	324	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	237 W	758	-	0	0	-
People	2	399	410	0	0	0
Infiltration	-	125	126	-	666	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	217	27	5%	153	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>4557</b>	<b>562</b>	-	<b>3203</b>	<b>0</b>

TABLE 54.1.B. Envelope Loads For Space "2163 OFFICE-DEPT" In Zone "VAV-1-54"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>SW EXPOSURE</b>						
WALL	61	0.062	-	87	-	234
WINDOW 1	66	0.380	0.333	220	2186	1542
<b>SE EXPOSURE</b>						
WALL	124	0.062	-	176	-	475
<b>H EXPOSURE</b>						
ROOF	81	0.027	-	66	-	133

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 55.1.A. Component Loads For Space "2161 GUIDANCE-WAITING" In Zone "VAV-1-55"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	53 W	164	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	4	859	820	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	51	41	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1075</b>	<b>861</b>	-	<b>0</b>	<b>0</b>

TABLE 55.1.B. Envelope Loads For Space "2161 GUIDANCE-WAITING" In Zone "VAV-1-55"						
		COOLING			HEATING	
		Area	U-Value	Shade	COOLING	COOLING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR
			(BTU/hr)	(BTU/hr)	(BTU/hr)	

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 55.2.A. Component Loads For Space "2161A GUIDANCE-STORAGE" In Zone "VAV-1-55"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	9 W	28	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	1	0	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>30</b>	<b>0</b>	-	<b>0</b>	<b>0</b>

TABLE 55.2.B. Envelope Loads For Space "2161A GUIDANCE-STORAGE" In Zone "VAV-1-55"							
					COOLING	COOLING	HEATING
		Area	U-Value	Shade	TRANS	SOLAR	TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 55.3.A. Component Loads For Space "2161B CORRIDOR" In Zone "VAV-1-55"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	158 W	489	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	24	0	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>514</b>	<b>0</b>	-	<b>0</b>	<b>0</b>

TABLE 55.3.B. Envelope Loads For Space "2161B CORRIDOR" In Zone "VAV-1-55"							
					COOLING	COOLING	HEATING
		Area	U-Value	Shade	TRANS	SOLAR	TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 56.1.A. Component Loads For Space "2160 WORKROOM" In Zone "VAV-1-56"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	133 W	411	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	285 W	932	-	0	0	-
People	8	1718	1640	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	153	82	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>3214</b>	<b>1722</b>	-	<b>0</b>	<b>0</b>

TABLE 56.1.B. Envelope Loads For Space "2160 WORKROOM" In Zone "VAV-1-56"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 57.1.A. Component Loads For Space "2000A CORRIDOR (W)" In Zone "VAV-1-57"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700 COOLING OA DB / WB 89.5 °F / 72.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	109 ft²	3343	-	109 ft²	-	-
Wall Transmission	80 ft²	145	-	80 ft²	307	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	109 ft²	520	-	109 ft²	2547	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	1145 W	3426	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	118	130	-	502	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	378	6	5%	168	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>7930</b>	<b>136</b>	-	<b>3523</b>	<b>0</b>

TABLE 57.1.B. Envelope Loads For Space "2000A CORRIDOR (W)" In Zone "VAV-1-57"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>W EXPOSURE</b>						
WALL	80	0.062	-	145	-	307
WINDOW 1	109	0.380	0.333	520	3343	2547

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 57.2.A. Component Loads For Space "2150 TOILET (4 STALLS)" In Zone "VAV-1-57"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 1600			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	32 ft²	941	-	32 ft²	-	-
Wall Transmission	108 ft²	194	-	108 ft²	414	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	32 ft²	160	-	32 ft²	748	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	164 W	485	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	94	96	-	372	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	94	5	5%	77	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1967</b>	<b>101</b>	-	<b>1610</b>	<b>0</b>

TABLE 57.2.B. Envelope Loads For Space "2150 TOILET (4 STALLS)" In Zone "VAV-1-57"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>SW EXPOSURE</b>						
WALL	108	0.062	-	194	-	414
WINDOW 1	32	0.380	0.333	160	941	748



## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 57.3.A. Component Loads For Space "2152 TOILET (1 STALL)" In Zone "VAV-1-57"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	38 W	117	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	6	0	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>123</b>	<b>0</b>	-	<b>0</b>	<b>0</b>

TABLE 57.3.B. Envelope Loads For Space "2152 TOILET (1 STALL)" In Zone "VAV-1-57"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 57.4.A. Component Loads For Space "2153 STOREROOM" In Zone "VAV-1-57"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	69 W	212	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	11	0	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>223</b>	<b>0</b>	-	<b>0</b>	<b>0</b>

TABLE 57.4.B. Envelope Loads For Space "2153 STOREROOM" In Zone "VAV-1-57"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING	COOLING	HEATING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR	TRANS
			(BTU/hr)	(BTU/hr)	(BTU/hr)		

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 57.5.A. Component Loads For Space "2154 TOILET (1 STALL)" In Zone "VAV-1-57"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	38 W	117	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	6	0	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>123</b>	<b>0</b>	-	<b>0</b>	<b>0</b>

TABLE 57.5.B. Envelope Loads For Space "2154 TOILET (1 STALL)" In Zone "VAV-1-57"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

**TABLE 57.6.A. Component Loads For Space "2155 IDF" In Zone "VAV-1-57"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 1800 COOLING OA DB / WB 87.8 °F / 72.1 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	80 ft²	163	-	80 ft²	307	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	34 W	104	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	1000 W	3237	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	44	56	-	212	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	177	3	5%	26	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>3725</b>	<b>59</b>	-	<b>545</b>	<b>0</b>

**TABLE 57.6.B. Envelope Loads For Space "2155 IDF" In Zone "VAV-1-57"**

				COOLING		HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>SW EXPOSURE</b>						
WALL	80	0.062	-	163	-	307

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 57.7.A. Component Loads For Space "2156 TOILET (4 STALLS)" In Zone "VAV-1-57"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1500 COOLING OA DB / WB 86.5 °F / 70.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	32 ft²	1060	-	32 ft²	-	-
Wall Transmission	98 ft²	140	-	98 ft²	376	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	32 ft²	107	-	32 ft²	748	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	151 W	443	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	65	66	-	345	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	91	3	5%	73	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1905</b>	<b>70</b>	-	<b>1542</b>	<b>0</b>

TABLE 57.7.B. Envelope Loads For Space "2156 TOILET (4 STALLS)" In Zone "VAV-1-57"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>SW EXPOSURE</b>						
WALL	98	0.062	-	140	-	376
WINDOW 1	32	0.380	0.333	107	1060	748

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 58.1.A. Component Loads For Space "2058 BREAKOUT" In Zone "VAV-1-58"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
SPACE LOADS	Details			Details		
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	242 W	749	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	173 W	566	-	0	0	-
People	6	1288	1230	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	130	62	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>2733</b>	<b>1292</b>	-	<b>0</b>	<b>0</b>

TABLE 58.1.B. Envelope Loads For Space "2058 BREAKOUT" In Zone "VAV-1-58"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 59.1.A. Component Loads For Space "2040 MEDICAL OFFICE" In Zone "VAV-1-59"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	109 W	335	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	233 W	760	-	0	0	-
People	4	859	820	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	98	41	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>2052</b>	<b>861</b>	-	<b>0</b>	<b>0</b>

TABLE 59.1.B. Envelope Loads For Space "2040 MEDICAL OFFICE" In Zone "VAV-1-59"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING	COOLING	HEATING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR	TRANS
			(BTU/hr)	(BTU/hr)	(BTU/hr)		

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 59.2.A. Component Loads For Space "2046A EXAM" In Zone "VAV-1-59"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	72 W	223	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	155 W	505	-	0	0	-
People	1	202	120	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	46	6	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>976</b>	<b>126</b>	-	<b>0</b>	<b>0</b>

TABLE 59.2.B. Envelope Loads For Space "2046A EXAM" In Zone "VAV-1-59"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)



## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

**TABLE 59.3.A. Component Loads For Space "2046B EXAM" In Zone "VAV-1-59"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	70 W	216	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	150 W	490	-	0	0	-
People	1	202	120	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	45	6	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>954</b>	<b>126</b>	-	<b>0</b>	<b>0</b>

**TABLE 59.3.B. Envelope Loads For Space "2046B EXAM" In Zone "VAV-1-59"**

		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 59.4.A. Component Loads For Space "2046C EXAM" In Zone "VAV-1-59"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	67 W	206	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	143 W	466	-	0	0	-
People	1	202	120	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	44	6	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>917</b>	<b>126</b>	-	<b>0</b>	<b>0</b>

TABLE 59.4.B. Envelope Loads For Space "2046C EXAM" In Zone "VAV-1-59"							
					COOLING	COOLING	HEATING
		Area	U-Value	Shade	TRANS	SOLAR	TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 60.1.A. Component Loads For Space "2042 INTERVIEW" In Zone "VAV-1-60"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	77 W	238	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	165 W	539	-	0	0	-
People	2	403	240	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	59	12	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1240</b>	<b>252</b>	-	<b>0</b>	<b>0</b>

TABLE 60.1.B. Envelope Loads For Space "2042 INTERVIEW" In Zone "VAV-1-60"						
				COOLING	COOLING	HEATING
	Area	U-Value	Shade	TRANS	SOLAR	TRANS
	(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 61.1.A. Component Loads For Space "2026 CONFERENCE-SM" In Zone "VAV-1-61"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1700 COOLING OA DB / WB 86.5 °F / 70.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	147 ft²	3564	-	147 ft²	-	-
Wall Transmission	74 ft²	93	-	74 ft²	284	-
Roof Transmission	194 ft²	179	-	194 ft²	321	-
Window Transmission	147 ft²	534	-	147 ft²	3435	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	149 W	446	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	320 W	1030	-	0	0	-
People	6	1232	1230	0	0	0
Infiltration	-	109	113	-	587	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	359	67	5%	231	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>7547</b>	<b>1410</b>	-	<b>4858</b>	<b>0</b>

TABLE 61.1.B. Envelope Loads For Space "2026 CONFERENCE-SM" In Zone "VAV-1-61"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NW EXPOSURE</b>						
WALL	74	0.062	-	93	-	284
WINDOW 1	147	0.380	0.333	534	3564	3435
<b>H EXPOSURE</b>						
ROOF	194	0.027	-	179	-	321

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 62.1.A. Component Loads For Space "2027 RECORDS" In Zone "VAV-1-62"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500 COOLING OA DB / WB 91.0 °F / 73.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	124 ft²	150	-	124 ft²	205	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	146 W	427	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	-	-	0	0
Safety Factor	5% / 5%	29	0	5%	10	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>605</b>	<b>0</b>	-	<b>215</b>	<b>0</b>

TABLE 62.1.B. Envelope Loads For Space "2027 RECORDS" In Zone "VAV-1-62"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
	<b>H EXPOSURE</b>					
ROOF	124	0.027	-	150	-	205

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 63.1.A. Component Loads For Space "2025 WORKSPACE" In Zone "VAV-1-63"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 89.5 °F / 72.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
<b>SPACE LOADS</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>
Window & Skylight Solar Loads	89 ft²	2003	-	89 ft²	-	-
Wall Transmission	126 ft²	174	-	126 ft²	483	-
Roof Transmission	413 ft²	405	-	413 ft²	683	-
Window Transmission	89 ft²	425	-	89 ft²	2080	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	289 W	865	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	620 W	1998	-	0	0	-
People	10	2053	2050	0	0	0
Infiltration	-	134	148	-	571	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	403	110	5%	191	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>8458</b>	<b>2308</b>	-	<b>4007</b>	<b>0</b>

TABLE 63.1.B. Envelope Loads For Space "2025 WORKSPACE" In Zone "VAV-1-63"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NW EXPOSURE</b>						
WALL	126	0.062	-	174	-	483
WINDOW 1	89	0.380	0.333	425	2003	2080
<b>H EXPOSURE</b>						
ROOF	413	0.027	-	405	-	683

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 64.1.A. Component Loads For Space "2022 OFFICE-SPARE" In Zone "VAV-1-64"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1500 COOLING OA DB / WB 86.5 °F / 70.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	54 ft²	1745	-	54 ft²	-	-
Wall Transmission	281 ft²	229	-	281 ft²	1077	-
Roof Transmission	141 ft²	115	-	141 ft²	233	-
Window Transmission	54 ft²	180	-	54 ft²	1262	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	99 W	289	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	212 W	676	-	0	0	-
People	5	998	1025	0	0	0
Infiltration	-	166	168	-	889	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	220	60	5%	173	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>4618</b>	<b>1252</b>	-	<b>3634</b>	<b>0</b>

TABLE 64.1.B. Envelope Loads For Space "2022 OFFICE-SPARE" In Zone "VAV-1-64"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>NW EXPOSURE</b>						
WALL	205	0.062	-	105	-	786
<b>SSW EXPOSURE</b>						
WALL	76	0.062	-	124	-	291
WINDOW 1	54	0.380	0.333	180	1745	1262
<b>H EXPOSURE</b>						
ROOF	141	0.027	-	115	-	233

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 65.1.A. Component Loads For Space "2020 CONFERENCE" In Zone "VAV-1-65"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1500 COOLING OA DB / WB 86.5 °F / 70.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	54 ft²	1745	-	54 ft²	-	-
Wall Transmission	70 ft²	114	-	70 ft²	268	-
Roof Transmission	148 ft²	121	-	148 ft²	245	-
Window Transmission	54 ft²	180	-	54 ft²	1262	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	104 W	304	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	222 W	710	-	0	0	-
People	5	998	1025	0	0	0
Infiltration	-	62	62	-	329	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	212	54	5%	105	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>4443</b>	<b>1141</b>	-	<b>2209</b>	<b>0</b>

TABLE 65.1.B. Envelope Loads For Space "2020 CONFERENCE" In Zone "VAV-1-65"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>SSW EXPOSURE</b>						
WALL	70	0.062	-	114	-	268
WINDOW 1	54	0.380	0.333	180	1745	1262
<b>H EXPOSURE</b>						
ROOF	148	0.027	-	121	-	245



## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 66.1.A. Component Loads For Space "2018 OFFICE-ASST. PR." In Zone "VAV-1-66"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1500 COOLING OA DB / WB 86.5 °F / 70.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	54 ft²	1745	-	54 ft²	-	-
Wall Transmission	68 ft²	111	-	68 ft²	261	-
Roof Transmission	145 ft²	119	-	145 ft²	240	-
Window Transmission	54 ft²	180	-	54 ft²	1262	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	102 W	297	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	218 W	695	-	0	0	-
People	5	998	1025	0	0	0
Infiltration	-	61	61	-	324	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	210	54	5%	104	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>4415</b>	<b>1140</b>	-	<b>2190</b>	<b>0</b>

TABLE 66.1.B. Envelope Loads For Space "2018 OFFICE-ASST. PR." In Zone "VAV-1-66"						
	Area (ft²)	U-Value (BTU/(hr-ft²-°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>SSW EXPOSURE</b>						
WALL	68	0.062	-	111	-	261
WINDOW 1	54	0.380	0.333	180	1745	1262
<b>H EXPOSURE</b>						
ROOF	145	0.027	-	119	-	240

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 67.1.A. Component Loads For Space "2016 CONFERENCE-LG" In Zone "VAV-1-67"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1400 COOLING OA DB / WB 86.0 °F / 70.4 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	289 ft²	9544	-	289 ft²	-	-
Wall Transmission	185 ft²	164	-	185 ft²	709	-
Roof Transmission	327 ft²	253	-	327 ft²	541	-
Window Transmission	289 ft²	908	-	289 ft²	6754	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	229 W	663	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	491 W	1561	-	0	0	-
People	8	1571	1640	0	0	0
Infiltration	-	226	237	-	1258	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	744	94	5%	463	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>15633</b>	<b>1971</b>	-	<b>9725</b>	<b>0</b>

TABLE 67.1.B. Envelope Loads For Space "2016 CONFERENCE-LG" In Zone "VAV-1-67"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>SSW EXPOSURE</b>						
WALL	93	0.062	-	127	-	356
WINDOW 1	289	0.380	0.333	908	9544	6754
<b>NW EXPOSURE</b>						
WALL	92	0.062	-	37	-	353
<b>NNE EXPOSURE</b>						
ROOF	327	0.027	-	253	-	541

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 68.1.A. Component Loads For Space "2014 OFFICE-PRINCIPAL" In Zone "VAV-1-68"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	79 ft²	1606	-	79 ft²	-	-
Wall Transmission	283 ft²	430	-	283 ft²	1085	-
Roof Transmission	418 ft²	502	-	418 ft²	691	-
Window Transmission	79 ft²	383	-	79 ft²	1846	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	293 W	847	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	627 W	1995	-	0	0	-
People	9	1767	1845	0	0	0
Infiltration	-	243	246	-	961	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	389	105	5%	229	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>8163</b>	<b>2196</b>	-	<b>4812</b>	<b>0</b>

TABLE 68.1.B. Envelope Loads For Space "2014 OFFICE-PRINCIPAL" In Zone "VAV-1-68"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>ESE EXPOSURE</b>						
WALL	283	0.062	-	430	-	1085
WINDOW 1	79	0.380	0.333	383	1606	1846
<b>NNE EXPOSURE</b>						
ROOF	418	0.027	-	502	-	691

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 69.1.A. Component Loads For Space "2012 OFFICE-PR SECRETARY" In Zone "VAV-1-69"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 91.0 °F / 73.0 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	9 ft²	175	-	9 ft²	-	-
Wall Transmission	52 ft²	76	-	52 ft²	199	-
Roof Transmission	46 ft²	54	-	46 ft²	76	-
Window Transmission	9 ft²	45	-	9 ft²	210	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	92 W	271	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	198 W	633	-	0	0	-
People	2	399	410	0	0	0
Infiltration	-	42	40	-	162	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	85	23	5%	32	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1779</b>	<b>473</b>	-	<b>680</b>	<b>0</b>

TABLE 69.1.B. Envelope Loads For Space "2012 OFFICE-PR SECRETARY" In Zone "VAV-1-69"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>ESE EXPOSURE</b>						
WALL	52	0.062	-	76	-	199
WINDOW 1	9	0.380	0.333	45	175	210
<b>NNE EXPOSURE</b>						
ROOF	46	0.027	-	54	-	76

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 70.1.A. Component Loads For Space "2010 ADMIN-GENERAL" In Zone "Zone 70"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	272 W	842	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	584 W	1907	-	0	0	-
People	7	1503	1435	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	213	72	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>4465</b>	<b>1507</b>	-	<b>0</b>	<b>0</b>

TABLE 70.1.B. Envelope Loads For Space "2010 ADMIN-GENERAL" In Zone "Zone 70"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 70.2.A. Component Loads For Space "2010A COPY" In Zone "Zone 70"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	137 W	424	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	1000 W	3269	-	0	0	-
People	1	203	120	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	195	6	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>4091</b>	<b>126</b>	-	<b>0</b>	<b>0</b>

TABLE 70.2.B. Envelope Loads For Space "2010A COPY" In Zone "Zone 70"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 70.3.A. Component Loads For Space "2010B MAIL" In Zone "Zone 70"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500 COOLING OA DB / WB 91.0 °F / 73.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	68 ft²	79	-	68 ft²	112	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	72 W	211	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	1	200	205	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	24	10	5%	6	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>514</b>	<b>215</b>	-	<b>118</b>	<b>0</b>

TABLE 70.3.B. Envelope Loads For Space "2010B MAIL" In Zone "Zone 70"							
		DESIGN COOLING			DESIGN HEATING		
		Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING TRANS (BTU/hr)	COOLING SOLAR (BTU/hr)	HEATING TRANS (BTU/hr)
<b>NNE EXPOSURE</b>							
ROOF	68	0.027	-	79	-	112	

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 70.4.A. Component Loads For Space "1246 CORRIDOR" In Zone "Zone 70"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	238 ft²	294	-	238 ft²	393	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	186 W	539	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	42	0	5%	20	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>875</b>	<b>0</b>	-	<b>413</b>	<b>0</b>

TABLE 70.4.B. Envelope Loads For Space "1246 CORRIDOR" In Zone "Zone 70"						
	Area (ft²)	U-Value	Shade Coeff.	COOLING	COOLING	HEATING
		(BTU/(hr-ft²·°F))		TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
	<b>H EXPOSURE</b>					
ROOF	238	0.027	-	294	-	393



## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 70.5.A. Component Loads For Space "2025 WORKSPACE" In Zone "Zone 70"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 89.5 °F / 72.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
<b>SPACE LOADS</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>
Window & Skylight Solar Loads	89 ft²	2003	-	89 ft²	-	-
Wall Transmission	126 ft²	174	-	126 ft²	483	-
Roof Transmission	413 ft²	405	-	413 ft²	683	-
Window Transmission	89 ft²	425	-	89 ft²	2080	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	289 W	865	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	620 W	1998	-	0	0	-
People	10	2053	2050	0	0	0
Infiltration	-	134	144	-	571	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	403	110	5%	191	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>8458</b>	<b>2304</b>	-	<b>4007</b>	<b>0</b>

TABLE 70.5.B. Envelope Loads For Space "2025 WORKSPACE" In Zone "Zone 70"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NW EXPOSURE</b>						
WALL	126	0.062	-	174	-	483
WINDOW 1	89	0.380	0.333	425	2003	2080
<b>H EXPOSURE</b>						
ROOF	413	0.027	-	405	-	683

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 71.1.A. Component Loads For Space "3164 CLASSROOM-ELL" In Zone "Zone 71"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 1600 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
SPACE LOADS	Details			Details		
Window & Skylight Solar Loads	185 ft²	5440	-	185 ft²	-	-
Wall Transmission	785 ft²	1047	-	785 ft²	3009	-
Roof Transmission	882 ft²	897	-	882 ft²	1458	-
Window Transmission	185 ft²	923	-	185 ft²	4323	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	882 ft²	1158	-	882 ft²	5424	-
Partitions	124 ft²	0	-	124 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	617 W	1829	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	441 W	1416	-	0	0	-
People	26	5265	5330	0	0	0
Infiltration	-	651	667	-	2574	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	931	300	5%	839	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>19556</b>	<b>6297</b>	-	<b>17628</b>	<b>-1</b>

TABLE 71.1.B. Envelope Loads For Space "3164 CLASSROOM-ELL" In Zone "Zone 71"							
		Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
					TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>NW EXPOSURE</b>							
WALL		441	0.062	-	467	-	1690
<b>SW EXPOSURE</b>							
WALL		211	0.062	-	379	-	809
WINDOW 1		185	0.380	0.333	923	5440	4323
<b>W EXPOSURE</b>							
WALL		63	0.062	-	96	-	241
<b>SE EXPOSURE</b>							
WALL		70	0.062	-	106	-	268
<b>H EXPOSURE</b>							
ROOF		882	0.027	-	897	-	1458

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 72.1.A. Component Loads For Space "3160 CLASSROOM-ELL" In Zone "Zone 72"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1500 COOLING OA DB / WB 86.5 °F / 70.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	285 ft²	9439	-	285 ft²	-	-
Wall Transmission	258 ft²	298	-	258 ft²	989	-
Roof Transmission	883 ft²	723	-	883 ft²	1460	-
Window Transmission	285 ft²	949	-	285 ft²	6660	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	618 W	1811	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	442 W	1412	-	0	0	-
People	26	5187	5330	0	0	0
Infiltration	-	269	271	-	1441	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	1004	280	5%	528	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>21092</b>	<b>5881</b>	-	<b>11078</b>	<b>0</b>

TABLE 72.1.B. Envelope Loads For Space "3160 CLASSROOM-ELL" In Zone "Zone 72"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>SW EXPOSURE</b>						
WALL	107	0.062	-	153	-	410
WINDOW 1	285	0.380	0.333	949	9439	6660
<b>W EXPOSURE</b>						
WALL	98	0.062	-	88	-	376
<b>SE EXPOSURE</b>						
WALL	32	0.062	-	45	-	123
<b>NW EXPOSURE</b>						
WALL	21	0.062	-	11	-	80
<b>H EXPOSURE</b>						
ROOF	883	0.027	-	723	-	1460

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 73.1.A. Component Loads For Space "3000A CORRIDOR (W)" In Zone "Zone 73"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1500 COOLING OA DB / WB 88.0 °F / 71.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	456 ft²	22652	-	456 ft²	-	-
Wall Transmission	40 ft²	42	-	40 ft²	153	-
Roof Transmission	959 ft²	1104	-	959 ft²	1585	-
Window Transmission	163 ft²	635	-	163 ft²	3809	-
Skylight Transmission	293 ft²	721	-	293 ft²	4325	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	1031 W	3021	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	114	101	-	539	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	1415	5	5%	521	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>29705</b>	<b>106</b>	-	<b>10932</b>	<b>0</b>

TABLE 73.1.B. Envelope Loads For Space "3000A CORRIDOR (W)" In Zone "Zone 73"						
	Area (ft²)	U-Value (BTU/(hr-ft²-°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>W EXPOSURE</b>						
WALL	40	0.062	-	42	-	153
WINDOW 1	163	0.380	0.333	635	4652	3809
<b>H EXPOSURE</b>						
ROOF	959	0.027	-	1104	-	1585
SKYLIGHT	293	0.240	0.448	721	18000	4325

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 73.2.A. Component Loads For Space "3150 TOILET (4 STALLS)" In Zone "Zone 73"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 1600 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	26 ft²	765	-	26 ft²	-	-
Wall Transmission	133 ft²	239	-	133 ft²	510	-
Roof Transmission	193 ft²	196	-	193 ft²	319	-
Window Transmission	26 ft²	130	-	26 ft²	608	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	135 W	400	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	107	110	-	422	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	92	5	5%	93	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1928</b>	<b>115</b>	-	<b>1951</b>	<b>0</b>

TABLE 73.2.B. Envelope Loads For Space "3150 TOILET (4 STALLS)" In Zone "Zone 73"						
	Area (ft²)	U-Value (BTU/(hr-ft²-°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>SW EXPOSURE</b>						
WALL	133	0.062	-	239	-	510
WINDOW 1	26	0.380	0.333	130	765	608
<b>H EXPOSURE</b>						
ROOF	193	0.027	-	196	-	319

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 73.3.A. Component Loads For Space "3152 TOILET (1 STALL)" In Zone "Zone 73"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	54 ft²	67	-	54 ft²	89	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	38 W	109	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	-	-	0	0
Safety Factor	5% / 5%	9	0	5%	4	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>185</b>	<b>0</b>	-	<b>94</b>	<b>0</b>

TABLE 73.3.B. Envelope Loads For Space "3152 TOILET (1 STALL)" In Zone "Zone 73"						
	Area (ft²)	U-Value	Shade Coeff.	COOLING	COOLING	HEATING
		(BTU/(hr-ft²·°F))		TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
	<b>H EXPOSURE</b>					
ROOF	54	0.027	-	67	-	89

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 73.4.A. Component Loads For Space "3153 STOREROOM" In Zone "Zone 73"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	88 ft²	109	-	88 ft²	145	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	62 W	178	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	-	-	0	0
Safety Factor	5% / 5%	14	0	5%	7	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>301</b>	<b>0</b>	-	<b>153</b>	<b>0</b>

TABLE 73.4.B. Envelope Loads For Space "3153 STOREROOM" In Zone "Zone 73"						
				COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>H EXPOSURE</b>						
ROOF	88	0.027	-	109	-	145

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 73.5.A. Component Loads For Space "3154 TOILET (1 STALL)" In Zone "Zone 73"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	54 ft²	67	-	54 ft²	89	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	38 W	109	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	-	-	0	0
Safety Factor	5% / 5%	9	0	5%	4	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>185</b>	<b>0</b>	-	<b>94</b>	<b>0</b>

TABLE 73.5.B. Envelope Loads For Space "3154 TOILET (1 STALL)" In Zone "Zone 73"							
		Area	U-Value	Shade	COOLING	COOLING	HEATING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>H EXPOSURE</b>							
ROOF		54	0.027	-	67	-	89



## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 73.6.A. Component Loads For Space "3156 TOILET (4 STALLS)" In Zone "Zone 73"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 1600 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	26 ft²	765	-	26 ft²	-	-
Wall Transmission	113 ft²	203	-	113 ft²	433	-
Roof Transmission	182 ft²	185	-	182 ft²	301	-
Window Transmission	26 ft²	130	-	26 ft²	608	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	127 W	377	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	93	96	-	369	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	88	5	5%	86	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1841</b>	<b>101</b>	-	<b>1796</b>	<b>0</b>

TABLE 73.6.B. Envelope Loads For Space "3156 TOILET (4 STALLS)" In Zone "Zone 73"						
	Area (ft²)	U-Value (BTU/(hr-ft²-°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>SW EXPOSURE</b>						
WALL	113	0.062	-	203	-	433
WINDOW 1	26	0.380	0.333	130	765	608
<b>H EXPOSURE</b>						
ROOF	182	0.027	-	185	-	301

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 74.1.A. Component Loads For Space "3058 BREAKOUT" In Zone "Zone 74"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1400 COOLING OA DB / WB 87.5 °F / 70.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	222 ft²	11866	-	222 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	17 ft²	20	-	17 ft²	28	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	222 ft²	520	-	222 ft²	3277	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	167 W	485	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	120 W	380	-	0	0	-
People	8	1571	1640	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	742	82	5%	165	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>15584</b>	<b>1722</b>	-	<b>3470</b>	<b>0</b>

TABLE 74.1.B. Envelope Loads For Space "3058 BREAKOUT" In Zone "Zone 74"						
	Area (ft²)	U-Value (BTU/(hr-ft²-°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>H EXPOSURE</b>						
ROOF	17	0.027	-	20	-	28
<b>NW EXPOSURE</b>						
SKYLIGHT	118	0.240	0.448	277	5969	1742
<b>SE EXPOSURE</b>						
SKYLIGHT	104	0.240	0.448	244	5897	1535

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 75.1.A. Component Loads For Space "3144 CLASSROOM" In Zone "Zone 75"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 1600			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
<b>SPACE LOADS</b>	Details	(BTU/hr)	(BTU/hr)	Details	(BTU/hr)	(BTU/hr)
Window & Skylight Solar Loads	158 ft²	4646	-	158 ft²	-	-
Wall Transmission	367 ft²	622	-	367 ft²	1407	-
Roof Transmission	886 ft²	901	-	886 ft²	1465	-
Window Transmission	158 ft²	788	-	158 ft²	3692	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	620 W	1837	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	443 W	1423	-	0	0	-
People	26	5265	5330	0	0	0
Infiltration	-	352	360	-	1393	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	792	284	5%	398	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>16625</b>	<b>5974</b>	-	<b>8355</b>	<b>0</b>

TABLE 75.1.B. Envelope Loads For Space "3144 CLASSROOM" In Zone "Zone 75"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>W EXPOSURE</b>						
WALL	63	0.062	-	96	-	241
<b>SW EXPOSURE</b>						
WALL	234	0.062	-	420	-	897
WINDOW 1	158	0.380	0.333	788	4646	3692
<b>SE EXPOSURE</b>						
WALL	70	0.062	-	106	-	268
<b>H EXPOSURE</b>						
ROOF	886	0.027	-	901	-	1465

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 76.1.A. Component Loads For Space "3142 CLASSROOM-TP" In Zone "Zone 76"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	95 ft²	106	-	95 ft²	157	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	67 W	197	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	48 W	153	-	0	0	-
People	2	405	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	43	21	5%	8	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>904</b>	<b>431</b>	-	<b>165</b>	<b>0</b>

TABLE 76.1.B. Envelope Loads For Space "3142 CLASSROOM-TP" In Zone "Zone 76"						
				COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
H EXPOSURE	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.			
ROOF	95	0.027	-	106	-	157

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 77.1.A. Component Loads For Space "3140 CLASSROOM" In Zone "Zone 77"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1500 COOLING OA DB / WB 86.5 °F / 70.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	185 ft²	5977	-	185 ft²	-	-
Wall Transmission	319 ft²	478	-	319 ft²	1223	-
Roof Transmission	889 ft²	728	-	889 ft²	1470	-
Window Transmission	185 ft²	616	-	185 ft²	4323	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	622 W	1823	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	445 W	1421	-	0	0	-
People	26	5187	5330	0	0	0
Infiltration	-	250	250	-	1338	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	824	279	5%	418	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>17305</b>	<b>5859</b>	-	<b>8771</b>	<b>0</b>

TABLE 77.1.B. Envelope Loads For Space "3140 CLASSROOM" In Zone "Zone 77"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>SW EXPOSURE</b>						
WALL	63	0.062	-	90	-	241
<b>W EXPOSURE</b>						
WALL	21	0.062	-	19	-	80
<b>SSW EXPOSURE</b>						
WALL	207	0.062	-	337	-	793
WINDOW 1	185	0.380	0.333	616	5977	4323
<b>ESE EXPOSURE</b>						
WALL	28	0.062	-	33	-	107
<b>H EXPOSURE</b>						
ROOF	889	0.027	-	728	-	1470

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 78.1.A. Component Loads For Space "1140 KITCHEN" In Zone "Zone 78"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	1553 ft²	0	-	1553 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	1087 W	3361	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	1553 W	5077	-	0	0	-
People	8	2069	3640	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	525	182	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>11032</b>	<b>3822</b>	-	<b>0</b>	<b>0</b>

TABLE 78.1.B. Envelope Loads For Space "1140 KITCHEN" In Zone "Zone 78"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 78.2.A. Component Loads For Space "1142 KITCHEN TOILET" In Zone "Zone 78"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	49 ft²	0	-	49 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	34 W	106	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	5	0	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>111</b>	<b>0</b>	-	<b>0</b>	<b>0</b>

TABLE 78.2.B. Envelope Loads For Space "1142 KITCHEN TOILET" In Zone "Zone 78"							
					COOLING	COOLING	HEATING
		Area	U-Value	Shade	TRANS	SOLAR	TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-1&2

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:26PM

TABLE 78.3.A. Component Loads For Space "1147 KITCHEN STORAGE" In Zone "Zone 78"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	92 ft²	0	-	92 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	64 W	199	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	10	0	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>209</b>	<b>0</b>	-	<b>0</b>	<b>0</b>

TABLE 78.3.B. Envelope Loads For Space "1147 KITCHEN STORAGE" In Zone "Zone 78"							
					COOLING	COOLING	HEATING
		Area	U-Value	Shade	TRANS	SOLAR	TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)



## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

**TABLE 1.1.A. Component Loads For Space "1240 MEDIA CENTER" In Zone "1"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 91.0 °F / 73.0 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
		Sensible	Latent		Sensible	Latent
SPACE LOADS	Details	(BTU/hr)	(BTU/hr)	Details	(BTU/hr)	(BTU/hr)
Window & Skylight Solar Loads	543 ft²	7186	-	543 ft²	-	-
Wall Transmission	1795 ft²	2185	-	1795 ft²	6879	-
Roof Transmission	1107 ft²	1335	-	1107 ft²	1830	-
Window Transmission	543 ft²	2736	-	543 ft²	12690	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	1881 ft²	0	-	1881 ft²	2054	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	1317 W	3858	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	2822 W	9021	-	0	0	-
People	30	5985	6150	0	0	0
Infiltration	-	1614	1597	-	6205	-1
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	1696	387	5%	1483	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>35616</b>	<b>8135</b>	-	<b>31141</b>	<b>-1</b>

**TABLE 1.1.B. Envelope Loads For Space "1240 MEDIA CENTER" In Zone "1"**

	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>NNE EXPOSURE</b>						
WALL	395	0.062	-	381	-	1514
WINDOW 1	543	0.380	0.437	2736	7186	12690
<b>WNW EXPOSURE</b>						
WALL	686	0.062	-	741	-	2629
<b>SE EXPOSURE</b>						
WALL	714	0.062	-	1063	-	2736
<b>H EXPOSURE</b>						
ROOF	1107	0.027	-	1335	-	1830

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

**TABLE 2.1.A. Component Loads For Space "1242 MEDIA OFFICE" In Zone "2"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	98 ft²	0	-	98 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	69 W	212	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	147 W	481	-	0	0	-
People	2	429	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	56	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1178</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

**TABLE 2.1.B. Envelope Loads For Space "1242 MEDIA OFFICE" In Zone "2"**

		COOLING		HEATING	
		COOLING	COOLING	COOLING	HEATING
		TRANS	SOLAR	TRANS	TRANS
Area	U-Value	Shade	(BTU/hr)	(BTU/hr)	(BTU/hr)
(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 3.1.A. Component Loads For Space "1055B CAF/LEARN COMM" In Zone "3"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1400 COOLING OA DB / WB 87.5 °F / 70.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	1524 ft²	96581	-	1524 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	814 ft²	962	-	814 ft²	1346	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	1524 ft²	3571	-	1524 ft²	22494	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	2338 ft²	0	-	2338 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	1637 W	4740	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	585 W	1860	-	0	0	-
People	200	36859	24000	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	7229	1200	5%	1192	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>151802</b>	<b>25200</b>	-	<b>25032</b>	<b>0</b>

TABLE 3.1.B. Envelope Loads For Space "1055B CAF/LEARN COMM" In Zone "3"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING	COOLING	HEATING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>H EXPOSURE</b>							
ROOF	814	0.027	-	962	-	1346	
SKYLIGHT	1524	0.240	0.448	3571	96581	22494	

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

**TABLE 4.1.A. Component Loads For Space "1244 CLASSROOM" In Zone "4"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 91.0 °F / 73.0 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
<b>SPACE LOADS</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>
Window & Skylight Solar Loads	190 ft²	3373	-	190 ft²	-	-
Wall Transmission	272 ft²	315	-	272 ft²	1042	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	190 ft²	957	-	190 ft²	4440	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	904 ft²	0	-	904 ft²	949	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	633 W	1854	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	452 W	1445	-	0	0	-
People	26	5187	5330	0	0	0
Infiltration	-	319	310	-	1226	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	673	282	5%	383	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>14124</b>	<b>5922</b>	-	<b>8041</b>	<b>0</b>

**TABLE 4.1.B. Envelope Loads For Space "1244 CLASSROOM" In Zone "4"**

	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NE EXPOSURE</b>						
WALL	202	0.062	-	224	-	774
WINDOW 1	190	0.380	0.437	957	3373	4440
<b>E EXPOSURE</b>						
WALL	56	0.062	-	78	-	215
<b>NW EXPOSURE</b>						
WALL	14	0.062	-	13	-	54

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

**TABLE 5.1.A. Component Loads For Space "1060B CORRIDOR (E)" In Zone "5"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 0900 COOLING OA DB / WB 80.1 °F / 69.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	122 ft²	3428	-	122 ft²	-	-
Wall Transmission	81 ft²	94	-	81 ft²	310	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	122 ft²	243	-	122 ft²	2851	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	1473 ft²	0	-	1473 ft²	786	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	1031 W	2771	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	45	135	-	539	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	329	7	5%	224	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>6910</b>	<b>142</b>	-	<b>4710</b>	<b>0</b>

**TABLE 5.1.B. Envelope Loads For Space "1060B CORRIDOR (E)" In Zone "5"**

	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>E EXPOSURE</b>						
WALL	81	0.062	-	94	-	310
WINDOW 1	122	0.380	0.333	243	3428	2851

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 5.2.A. Component Loads For Space "1250 TOILET (4 STALLS)" In Zone "5"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	31 ft²	571	-	31 ft²	-	-
Wall Transmission	128 ft²	139	-	128 ft²	491	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	31 ft²	150	-	31 ft²	724	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	246 ft²	0	-	246 ft²	284	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	172 W	499	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	107	109	-	422	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	73	5	5%	96	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1539</b>	<b>114</b>	-	<b>2018</b>	<b>0</b>

TABLE 5.2.B. Envelope Loads For Space "1250 TOILET (4 STALLS)" In Zone "5"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>NE EXPOSURE</b>						
WALL	128	0.062	-	139	-	491
WINDOW 1	31	0.380	0.437	150	571	724

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 5.3.A. Component Loads For Space "1252 SPED TLT (1 STALL)" In Zone "5"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	101 ft²	0	-	101 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	71 W	219	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	11	0	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>230</b>	<b>0</b>	-	<b>0</b>	<b>0</b>

TABLE 5.3.B. Envelope Loads For Space "1252 SPED TLT (1 STALL)" In Zone "5"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

**TABLE 5.4.A. Component Loads For Space "1253 CUST STOR" In Zone "5"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 89.5 °F / 72.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
<b>SPACE LOADS</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	84 ft²	97	-	84 ft²	322	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	146 ft²	0	-	146 ft²	158	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	102 W	306	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	52	58	-	223	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	23	3	5%	35	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>478</b>	<b>61</b>	-	<b>738</b>	<b>0</b>

**TABLE 5.4.B. Envelope Loads For Space "1253 CUST STOR" In Zone "5"**

	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NE EXPOSURE</b>						
WALL	84	0.062	-	97	-	322



## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

**TABLE 5.5.A. Component Loads For Space "1254 EMERG. ELEC" In Zone "5"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	13 ft²	0	-	13 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	9 W	28	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	1	0	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>30</b>	<b>0</b>	-	<b>0</b>	<b>0</b>

**TABLE 5.5.B. Envelope Loads For Space "1254 EMERG. ELEC" In Zone "5"**

		COOLING		HEATING	
		COOLING	COOLING	COOLING	HEATING
		TRANS	SOLAR	TRANS	TRANS
Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 5.6.A. Component Loads For Space "1256 TOILET (4 STALLS)" In Zone "5"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	31 ft²	571	-	31 ft²	-	-
Wall Transmission	109 ft²	118	-	109 ft²	418	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	31 ft²	150	-	31 ft²	724	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	231 ft²	0	-	231 ft²	257	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	162 W	468	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	94	96	-	372	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	70	5	5%	89	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1472</b>	<b>101</b>	-	<b>1859</b>	<b>0</b>

TABLE 5.6.B. Envelope Loads For Space "1256 TOILET (4 STALLS)" In Zone "5"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NE EXPOSURE</b>						
WALL	109	0.062	-	118	-	418
WINDOW 1	31	0.380	0.437	150	571	724

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 6.1.A. Component Loads For Space "1260 SPED CLASSROOM" In Zone "6"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500 COOLING OA DB / WB 91.0 °F / 73.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	190 ft²	3373	-	190 ft²	-	-
Wall Transmission	300 ft²	353	-	300 ft²	1150	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	190 ft²	957	-	190 ft²	4440	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	866 ft²	0	-	866 ft²	964	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	606 W	1776	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	433 W	1384	-	0	0	-
People	26	4870	3120	0	0	0
Infiltration	-	338	329	-	1300	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	653	172	5%	393	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>13704</b>	<b>3622</b>	-	<b>8247</b>	<b>0</b>

TABLE 6.1.B. Envelope Loads For Space "1260 SPED CLASSROOM" In Zone "6"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>NE EXPOSURE</b>						
WALL	202	0.062	-	224	-	774
WINDOW 1	190	0.380	0.437	957	3373	4440
<b>E EXPOSURE</b>						
WALL	56	0.062	-	78	-	215
<b>ESE EXPOSURE</b>						
WALL	21	0.062	-	31	-	80
<b>NW EXPOSURE</b>						
WALL	21	0.062	-	20	-	80

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 7.1.A. Component Loads For Space "1262 SPED-TP" In Zone "7"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	98 ft²	0	-	98 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	69 W	212	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	250 W	817	-	0	0	-
People	2	429	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	73	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1532</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

TABLE 7.1.B. Envelope Loads For Space "1262 SPED-TP" In Zone "7"						
		COOLING			HEATING	
		Area	U-Value	Shade	COOLING	HEATING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR
			(BTU/hr)	(BTU/hr)	(BTU/hr)	

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 8.1.A. Component Loads For Space "1264 SPED CLASSROOM" In Zone "8"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500 COOLING OA DB / WB 91.0 °F / 73.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	190 ft²	3373	-	190 ft²	-	-
Wall Transmission	763 ft²	1016	-	763 ft²	2924	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	190 ft²	957	-	190 ft²	4440	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	870 ft²	0	-	870 ft²	1303	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	609 W	1784	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	435 W	1391	-	0	0	-
People	26	4870	3120	0	0	0
Infiltration	-	658	648	-	2529	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	702	188	5%	560	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>14752</b>	<b>3956</b>	-	<b>11757</b>	<b>0</b>

TABLE 8.1.B. Envelope Loads For Space "1264 SPED CLASSROOM" In Zone "8"						
	Area (ft²)	U-Value (BTU/(hr-ft²-°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>NE EXPOSURE</b>						
WALL	202	0.062	-	224	-	774
WINDOW 1	190	0.380	0.437	957	3373	4440
<b>E EXPOSURE</b>						
WALL	56	0.062	-	78	-	215
<b>NW EXPOSURE</b>						
WALL	71	0.062	-	68	-	272
<b>SE EXPOSURE</b>						
WALL	434	0.062	-	646	-	1663

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 9.1.A. Component Loads For Space "2242 CLASSROOM-TP" In Zone "9"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	67 W	208	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	48 W	157	-	0	0	-
People	2	429	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	40	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>834</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

TABLE 9.1.B. Envelope Loads For Space "2242 CLASSROOM-TP" In Zone "9"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 10.1.A. Component Loads For Space "2244 CLASSROOM" In Zone "10"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500 COOLING OA DB / WB 91.0 °F / 73.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	144 ft²	2556	-	144 ft²	-	-
Wall Transmission	289 ft²	336	-	289 ft²	1108	-
Roof Transmission	35 ft²	42	-	35 ft²	58	-
Window Transmission	144 ft²	726	-	144 ft²	3365	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	630 W	1846	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	450 W	1439	-	0	0	-
People	26	5187	5330	0	0	0
Infiltration	-	299	289	-	1149	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	622	281	5%	284	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>13053</b>	<b>5900</b>	-	<b>5964</b>	<b>0</b>

TABLE 10.1.B. Envelope Loads For Space "2244 CLASSROOM" In Zone "10"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NE EXPOSURE</b>						
WALL	233	0.062	-	258	-	893
WINDOW 1	144	0.380	0.437	726	2556	3365
<b>E EXPOSURE</b>						
WALL	56	0.062	-	78	-	215
<b>H EXPOSURE</b>						
ROOF	35	0.027	-	42	-	58

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 11.1.A. Component Loads For Space "2250 TOILET (4 STALLS)" In Zone "11"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	26 ft²	479	-	26 ft²	-	-
Wall Transmission	128 ft²	139	-	128 ft²	491	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	26 ft²	126	-	26 ft²	608	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	163 W	472	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	103	99	-	409	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	66	5	5%	75	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1386</b>	<b>104</b>	-	<b>1582</b>	<b>0</b>

TABLE 11.1.B. Envelope Loads For Space "2250 TOILET (4 STALLS)" In Zone "11"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NE EXPOSURE</b>						
WALL	128	0.062	-	139	-	491
WINDOW 1	26	0.380	0.437	126	479	608



## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 11.2.A. Component Loads For Space "2252 SPED-TLT (1 STALL)" In Zone "11"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	71 W	219	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	11	0	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>230</b>	<b>0</b>	-	<b>0</b>	<b>0</b>

TABLE 11.2.B. Envelope Loads For Space "2252 SPED-TLT (1 STALL)" In Zone "11"							
					COOLING	COOLING	HEATING
		Area	U-Value	Shade	TRANS	SOLAR	TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 11.3.A. Component Loads For Space "2253 CUSTODIAN STORAGE" In Zone "11"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	68 W	210	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	10	0	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>220</b>	<b>0</b>	-	<b>0</b>	<b>0</b>

TABLE 11.3.B. Envelope Loads For Space "2253 CUSTODIAN STORAGE" In Zone "11"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING	COOLING	HEATING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR	TRANS
			(BTU/hr)	(BTU/hr)	(BTU/hr)		

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 11.4.A. Component Loads For Space "2254 EMERG. ELECTRIC" In Zone "11"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	9 W	28	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	1	0	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>30</b>	<b>0</b>	-	<b>0</b>	<b>0</b>

TABLE 11.4.B. Envelope Loads For Space "2254 EMERG. ELECTRIC" In Zone "11"						
		COOLING			HEATING	
		Area	U-Value	Shade	COOLING	COOLING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR
			(BTU/hr)	(BTU/hr)	(BTU/hr)	

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

**TABLE 11.5.A. Component Loads For Space "2255 IDF" In Zone "11"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 2100 COOLING OA DB / WB 82.1 °F / 70.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	51 ft²	50	-	51 ft²	195	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	33 W	102	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	1000 W	3269	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	16	34	-	135	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	172	2	5%	17	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>3609</b>	<b>36</b>	-	<b>347</b>	<b>0</b>

**TABLE 11.5.B. Envelope Loads For Space "2255 IDF" In Zone "11"**

				COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NE EXPOSURE</b>	<b>Area</b> (ft²)	<b>U-Value</b> (BTU/(hr-ft²·°F))	<b>Shade</b> Coeff.			
WALL	51	0.062	-	50	-	195

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 11.6.A. Component Loads For Space "2256 TOILET (4 STALLS)" In Zone "11"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	26 ft²	479	-	26 ft²	-	-
Wall Transmission	128 ft²	139	-	128 ft²	491	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	26 ft²	126	-	26 ft²	608	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	160 W	462	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	103	99	-	409	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	65	5	5%	75	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1375</b>	<b>104</b>	-	<b>1582</b>	<b>0</b>

TABLE 11.6.B. Envelope Loads For Space "2256 TOILET (4 STALLS)" In Zone "11"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NE EXPOSURE</b>						
WALL	128	0.062	-	139	-	491
WINDOW 1	26	0.380	0.437	126	479	608

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 11.7.A. Component Loads For Space "2060B CORRIDOR (E)" In Zone "11"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 0900 COOLING OA DB / WB 80.1 °F / 69.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	139 ft²	3905	-	139 ft²	-	-
Wall Transmission	50 ft²	58	-	50 ft²	192	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	139 ft²	277	-	139 ft²	3248	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	1018 W	2735	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	42	117	-	502	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	351	6	5%	197	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>7369</b>	<b>123</b>	-	<b>4139</b>	<b>0</b>

TABLE 11.7.B. Envelope Loads For Space "2060B CORRIDOR (E)" In Zone "11"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING	COOLING	HEATING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR	TRANS
<b>E EXPOSURE</b>				(BTU/hr)	(BTU/hr)	(BTU/hr)	
WALL	50	0.062	-	58	-	192	
WINDOW 1	139	0.380	0.333	277	3905	3248	

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 12.1.A. Component Loads For Space "2260 SPED-CLASSROOM" In Zone "12"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500 COOLING OA DB / WB 91.0 °F / 73.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	190 ft²	3373	-	190 ft²	-	-
Wall Transmission	307 ft²	359	-	307 ft²	1177	-
Roof Transmission	20 ft²	24	-	20 ft²	33	-
Window Transmission	190 ft²	957	-	190 ft²	4440	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	606 W	1776	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	433 W	1384	-	0	0	-
People	26	5187	5330	0	0	0
Infiltration	-	343	335	-	1319	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	670	283	5%	348	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>14075</b>	<b>5948</b>	-	<b>7317</b>	<b>0</b>

TABLE 12.1.B. Envelope Loads For Space "2260 SPED-CLASSROOM" In Zone "12"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>NE EXPOSURE</b>						
WALL	202	0.062	-	224	-	774
WINDOW 1	190	0.380	0.437	957	3373	4440
<b>E EXPOSURE</b>						
WALL	56	0.062	-	78	-	215
<b>NW EXPOSURE</b>						
WALL	28	0.062	-	27	-	107
<b>ESE EXPOSURE</b>						
WALL	21	0.062	-	31	-	80
<b>H EXPOSURE</b>						
ROOF	20	0.027	-	24	-	33

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

**TABLE 13.1.A. Component Loads For Space "2262 SPED-TP" In Zone "13"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
<b>SPACE LOADS</b>	<b>Details</b>	<b>Sensible (BTU/hr)</b>	<b>Latent (BTU/hr)</b>	<b>Details</b>	<b>Sensible (BTU/hr)</b>	<b>Latent (BTU/hr)</b>
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	69 W	212	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	49 W	160	-	0	0	-
People	2	429	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	40	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>842</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

**TABLE 13.1.B. Envelope Loads For Space "2262 SPED-TP" In Zone "13"**

		COOLING		HEATING	
		COOLING	COOLING	COOLING	HEATING
		TRANS	SOLAR	TRANS	TRANS
Area	U-Value	Shade	(BTU/hr)	(BTU/hr)	(BTU/hr)
(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)



## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 14.1.A. Component Loads For Space "2264 SPED-CLASSROOM" In Zone "14"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500 COOLING OA DB / WB 91.0 °F / 73.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	190 ft²	3373	-	190 ft²	-	-
Wall Transmission	655 ft²	893	-	655 ft²	2510	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	190 ft²	957	-	190 ft²	4440	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	610 W	1787	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	436 W	1392	-	0	0	-
People	26	5187	5330	0	0	0
Infiltration	-	583	574	-	2243	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	709	295	5%	460	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>14881</b>	<b>6200</b>	-	<b>9653</b>	<b>0</b>

TABLE 14.1.B. Envelope Loads For Space "2264 SPED-CLASSROOM" In Zone "14"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NE EXPOSURE</b>							
WALL	202	0.062	-	224	-	774	
WINDOW 1	190	0.380	0.437	957	3373	4440	
<b>E EXPOSURE</b>							
WALL	56	0.062	-	78	-	215	
<b>SE EXPOSURE</b>							
WALL	397	0.062	-	591	-	1522	

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 15.1.A. Component Loads For Space "3240 CLASSROOM" In Zone "15"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500 COOLING OA DB / WB 91.0 °F / 73.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	185 ft²	2448	-	185 ft²	-	-
Wall Transmission	312 ft²	334	-	312 ft²	1196	-
Roof Transmission	869 ft²	1048	-	869 ft²	1437	-
Window Transmission	185 ft²	932	-	185 ft²	4323	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	608 W	1782	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	435 W	1389	-	0	0	-
People	26	5187	5330	0	0	0
Infiltration	-	343	339	-	1319	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	673	283	5%	414	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>14138</b>	<b>5952</b>	-	<b>8688</b>	<b>0</b>

TABLE 15.1.B. Envelope Loads For Space "3240 CLASSROOM" In Zone "15"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>NNE EXPOSURE</b>						
WALL	207	0.062	-	200	-	793
WINDOW 1	185	0.380	0.437	932	2448	4323
<b>ENE EXPOSURE</b>						
WALL	63	0.062	-	80	-	241
<b>W EXPOSURE</b>						
WALL	21	0.062	-	26	-	80
<b>E EXPOSURE</b>						
WALL	21	0.062	-	29	-	80
<b>H EXPOSURE</b>						
ROOF	869	0.027	-	1048	-	1437

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

**TABLE 16.1.A. Component Loads For Space "3054 BREAKOUT" In Zone "16"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1600 COOLING OA DB / WB 87.5 °F / 70.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	189 ft²	10441	-	189 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	9 ft²	10	-	9 ft²	15	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	189 ft²	459	-	189 ft²	2790	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	137 W	406	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	98 W	315	-	0	0	-
People	8	1620	1640	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	663	82	5%	140	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>13914</b>	<b>1722</b>	-	<b>2945</b>	<b>0</b>

**TABLE 16.1.B. Envelope Loads For Space "3054 BREAKOUT" In Zone "16"**

				COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>H EXPOSURE</b>	<b>Area</b>	<b>U-Value</b>	<b>Shade</b>			
	(ft²)	(BTU/(hr-ft²·°F))	Coeff.			
ROOF	9	0.027	-	10	-	15
<b>NW EXPOSURE</b>						
SKYLIGHT	107	0.240	0.448	260	5682	1579
<b>WNW EXPOSURE</b>						
SKYLIGHT	82	0.240	0.448	199	4759	1210

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 17.1.A. Component Loads For Space "3242 CLASSROOM-TP" In Zone "17"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	95 ft²	106	-	95 ft²	157	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	67 W	197	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	48 W	153	-	0	0	-
People	2	405	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	43	21	5%	8	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>904</b>	<b>431</b>	-	<b>165</b>	<b>0</b>

TABLE 17.1.B. Envelope Loads For Space "3242 CLASSROOM-TP" In Zone "17"						
		COOLING		COOLING		HEATING
		TRANS		SOLAR		TRANS
		Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	(BTU/hr)	(BTU/hr)
<b>H EXPOSURE</b>						
ROOF	95	0.027	-	106	-	157

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 18.1.A. Component Loads For Space "3244 CLASSROOM" In Zone "18"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500 COOLING OA DB / WB 91.0 °F / 73.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	Details			Details		
Window & Skylight Solar Loads	185 ft²	3284	-	185 ft²	-	-
Wall Transmission	340 ft²	393	-	340 ft²	1303	-
Roof Transmission	873 ft²	1053	-	873 ft²	1443	-
Window Transmission	185 ft²	932	-	185 ft²	4323	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	17 ft²	23	-	17 ft²	105	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	611 W	1791	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	437 W	1396	-	0	0	-
People	26	5187	5330	0	0	0
Infiltration	-	362	357	-	1393	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	721	284	5%	428	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>15142</b>	<b>5971</b>	-	<b>8997</b>	<b>0</b>

TABLE 18.1.B. Envelope Loads For Space "3244 CLASSROOM" In Zone "18"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NE EXPOSURE</b>						
WALL	207	0.062	-	229	-	793
WINDOW 1	185	0.380	0.437	932	3284	4323
<b>E EXPOSURE</b>						
WALL	63	0.062	-	88	-	241
<b>WNW EXPOSURE</b>						
WALL	70	0.062	-	76	-	268
<b>H EXPOSURE</b>						
ROOF	873	0.027	-	1053	-	1443

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 19.1.A. Component Loads For Space "3250 TOILET (4 STALLS)" In Zone "19"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	26 ft²	479	-	26 ft²	-	-
Wall Transmission	132 ft²	143	-	132 ft²	506	-
Roof Transmission	234 ft²	289	-	234 ft²	387	-
Window Transmission	26 ft²	126	-	26 ft²	608	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	164 W	474	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	106	106	-	419	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	81	5	5%	96	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1699</b>	<b>111</b>	-	<b>2016</b>	<b>0</b>

TABLE 19.1.B. Envelope Loads For Space "3250 TOILET (4 STALLS)" In Zone "19"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NE EXPOSURE</b>						
WALL	132	0.062	-	143	-	506
WINDOW 1	26	0.380	0.437	126	479	608
<b>H EXPOSURE</b>						
ROOF	234	0.027	-	289	-	387

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 19.2.A. Component Loads For Space "3252 SPED-TLT (1 STALL)" In Zone "19"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	101 ft²	125	-	101 ft²	167	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	71 W	205	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	-	-	0	0
Safety Factor	5% / 5%	16	0	5%	8	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>346</b>	<b>0</b>	-	<b>175</b>	<b>0</b>

TABLE 19.2.B. Envelope Loads For Space "3252 SPED-TLT (1 STALL)" In Zone "19"							
		COOLING			HEATING		
		Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING TRANS (BTU/hr)	COOLING SOLAR (BTU/hr)	HEATING TRANS (BTU/hr)
		<b>H EXPOSURE</b>					
ROOF	101	0.027	-	125	-	167	

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 19.3.A. Component Loads For Space "3253 CUST STOR" In Zone "19"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 91.0 °F / 73.0 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	84 ft²	93	-	84 ft²	322	-
Roof Transmission	149 ft²	180	-	149 ft²	246	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	104 W	306	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	58	57	-	223	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	32	3	5%	40	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>668</b>	<b>60</b>	-	<b>831</b>	<b>0</b>

TABLE 19.3.B. Envelope Loads For Space "3253 CUST STOR" In Zone "19"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NE EXPOSURE</b>						
WALL	84	0.062	-	93	-	322
<b>H EXPOSURE</b>						
ROOF	149	0.027	-	180	-	246



## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 19.4.A. Component Loads For Space "3254 EMERG. ELECTRIC" In Zone "19"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	13 ft²	16	-	13 ft²	21	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	9 W	26	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	2	0	5%	1	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>45</b>	<b>0</b>	-	<b>23</b>	<b>0</b>

TABLE 19.4.B. Envelope Loads For Space "3254 EMERG. ELECTRIC" In Zone "19"						
		COOLING			HEATING	
		Area	U-Value	Shade	COOLING	COOLING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR
H EXPOSURE				(BTU/hr)	(BTU/hr)	(BTU/hr)
ROOF	13	0.027	-	16	-	21

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 19.5.A. Component Loads For Space "3256 TOILET (4 STALLS)" In Zone "19"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
<b>SPACE LOADS</b>	Details	(BTU/hr)	(BTU/hr)	Details	(BTU/hr)	(BTU/hr)
Window & Skylight Solar Loads	26 ft²	479	-	26 ft²	-	-
Wall Transmission	121 ft²	131	-	121 ft²	464	-
Roof Transmission	232 ft²	287	-	232 ft²	384	-
Window Transmission	26 ft²	126	-	26 ft²	608	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	162 W	470	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	99	99	-	390	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	80	5	5%	92	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1672</b>	<b>103</b>	-	<b>1937</b>	<b>0</b>

TABLE 19.5.B. Envelope Loads For Space "3256 TOILET (4 STALLS)" In Zone "19"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NE EXPOSURE</b>						
WALL	121	0.062	-	131	-	464
WINDOW 1	26	0.380	0.437	126	479	608
<b>H EXPOSURE</b>						
ROOF	232	0.027	-	287	-	384

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 19.6.A. Component Loads For Space "3060B CORRIDOR (E)" In Zone "19"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1400 COOLING OA DB / WB 87.5 °F / 70.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	Details			Details		
Window & Skylight Solar Loads	412 ft²	20962	-	412 ft²	-	-
Wall Transmission	84 ft²	105	-	84 ft²	322	-
Roof Transmission	1254 ft²	1483	-	1254 ft²	2073	-
Window Transmission	119 ft²	442	-	119 ft²	2781	-
Skylight Transmission	293 ft²	687	-	293 ft²	4325	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	1014 W	2936	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	110	99	-	539	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	1336	5	5%	502	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>28060</b>	<b>104</b>	-	<b>10541</b>	<b>0</b>

TABLE 19.6.B. Envelope Loads For Space "3060B CORRIDOR (E)" In Zone "19"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>E EXPOSURE</b>						
WALL	84	0.062	-	105	-	322
WINDOW 1	119	0.380	0.333	442	2394	2781
<b>H EXPOSURE</b>						
ROOF	1254	0.027	-	1483	-	2073
SKYLIGHT	293	0.240	0.448	687	18568	4325

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 20.1.A. Component Loads For Space "3260B SPED-READING" In Zone "20"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500 COOLING OA DB / WB 91.0 °F / 73.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	199 ft²	240	-	199 ft²	329	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	139 W	408	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	100 W	318	-	0	0	-
People	4	749	480	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	86	24	5%	16	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1801</b>	<b>504</b>	-	<b>345</b>	<b>0</b>

TABLE 20.1.B. Envelope Loads For Space "3260B SPED-READING" In Zone "20"						
		COOLING		COOLING		HEATING
		TRANS		SOLAR		TRANS
		Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	(BTU/hr)	(BTU/hr)
<b>H EXPOSURE</b>						
ROOF	199	0.027	-	240	-	329

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 21.1.A. Component Loads For Space "3260A SPED-READING" In Zone "21"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	135 ft²	151	-	135 ft²	223	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	95 W	280	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	68 W	217	-	0	0	-
People	4	760	480	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	70	24	5%	11	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1479</b>	<b>504</b>	-	<b>234</b>	<b>0</b>

TABLE 21.1.B. Envelope Loads For Space "3260A SPED-READING" In Zone "21"						
		COOLING		COOLING		HEATING
		TRANS		SOLAR		TRANS
		Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	(BTU/hr)	(BTU/hr)
<b>H EXPOSURE</b>						
ROOF	135	0.027	-	151	-	223

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 22.1.A. Component Loads For Space "3260C SPED-RESOURCE" In Zone "22"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500 COOLING OA DB / WB 91.0 °F / 73.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	93 ft²	1651	-	93 ft²	-	-
Wall Transmission	327 ft²	362	-	327 ft²	1253	-
Roof Transmission	502 ft²	606	-	502 ft²	830	-
Window Transmission	93 ft²	469	-	93 ft²	2173	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	351 W	1030	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	251 W	802	-	0	0	-
People	16	2997	1920	0	0	0
Infiltration	-	290	286	-	1115	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	410	110	5%	269	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>8617</b>	<b>2316</b>	-	<b>5640</b>	<b>0</b>

TABLE 22.1.B. Envelope Loads For Space "3260C SPED-RESOURCE" In Zone "22"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NE EXPOSURE</b>						
WALL	327	0.062	-	362	-	1253
WINDOW 1	93	0.380	0.437	469	1651	2173
<b>H EXPOSURE</b>						
ROOF	502	0.027	-	606	-	830

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 23.1.A. Component Loads For Space "3262 CLASSROOM-TP" In Zone "23"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	96 ft²	107	-	96 ft²	159	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	67 W	199	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	48 W	154	-	0	0	-
People	2	405	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	43	21	5%	8	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>909</b>	<b>431</b>	-	<b>167</b>	<b>0</b>

TABLE 23.1.B. Envelope Loads For Space "3262 CLASSROOM-TP" In Zone "23"						
				COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
H EXPOSURE	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.			
ROOF	96	0.027	-	107	-	159

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 24.1.A. Component Loads For Space "3265 OFFICE-DEPT" In Zone "24"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	134 ft²	150	-	134 ft²	222	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	94 W	278	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	201 W	645	-	0	0	-
People	4	810	820	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	94	41	5%	11	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1977</b>	<b>861</b>	-	<b>233</b>	<b>0</b>

TABLE 24.1.B. Envelope Loads For Space "3265 OFFICE-DEPT" In Zone "24"							
		COOLING			HEATING		
		Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING TRANS (BTU/hr)	COOLING SOLAR (BTU/hr)	HEATING TRANS (BTU/hr)
		<b>H EXPOSURE</b>					
ROOF	134	0.027	-	150	-	222	



## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 25.1.A. Component Loads For Space "3266 OFFICE-DEPT" In Zone "25"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500 COOLING OA DB / WB 91.0 °F / 73.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	54 ft²	959	-	54 ft²	-	-
Wall Transmission	236 ft²	240	-	236 ft²	904	-
Roof Transmission	153 ft²	185	-	153 ft²	253	-
Window Transmission	54 ft²	272	-	54 ft²	1262	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	107 W	314	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	230 W	734	-	0	0	-
People	2	399	410	0	0	0
Infiltration	-	200	199	-	770	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	165	30	5%	159	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>3467</b>	<b>639</b>	-	<b>3348</b>	<b>0</b>

TABLE 25.1.B. Envelope Loads For Space "3266 OFFICE-DEPT" In Zone "25"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>NW EXPOSURE</b>						
WALL	144	0.062	-	138	-	552
<b>NE EXPOSURE</b>						
WALL	92	0.062	-	102	-	353
WINDOW 1	54	0.380	0.437	272	959	1262
<b>H EXPOSURE</b>						
ROOF	153	0.027	-	185	-	253

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

**TABLE 26.1.A. Component Loads For Space "3263B CORRIDOR" In Zone "26"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
<b>SPACE LOADS</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	225 ft²	278	-	225 ft²	372	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	158 W	456	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	-	-	0	0
Safety Factor	5% / 5%	37	0	5%	19	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>771</b>	<b>0</b>	-	<b>391</b>	<b>0</b>

**TABLE 26.1.B. Envelope Loads For Space "3263B CORRIDOR" In Zone "26"**

	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>H EXPOSURE</b>						
ROOF	225	0.027	-	278	-	372

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 26.2.A. Component Loads For Space "3263A GUIDANCE-STOREROOM" In Zone "26"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 1400 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	87 ft²	143	-	87 ft²	333	-
Roof Transmission	20 ft²	23	-	20 ft²	33	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	14 W	41	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	58	58	-	231	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	13	3	5%	30	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>279</b>	<b>61</b>	-	<b>627</b>	<b>0</b>

TABLE 26.2.B. Envelope Loads For Space "3263A GUIDANCE-STOREROOM" In Zone "26"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>SE EXPOSURE</b>						
WALL	87	0.062	-	143	-	333
<b>H EXPOSURE</b>						
ROOF	20	0.027	-	23	-	33

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 26.3.A. Component Loads For Space "3263 GUIDANCE-WAITING" In Zone "26"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700 COOLING OA DB / WB 89.5 °F / 72.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	76 ft²	74	-	76 ft²	126	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	53 W	159	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	114 W	368	-	0	0	-
People	4	771	480	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	69	24	5%	6	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1441</b>	<b>504</b>	-	<b>132</b>	<b>0</b>

TABLE 26.3.B. Envelope Loads For Space "3263 GUIDANCE-WAITING" In Zone "26"						
		COOLING		COOLING		HEATING
		TRANS		SOLAR		TRANS
		Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	(BTU/hr)	(BTU/hr)
<b>H EXPOSURE</b>						
ROOF	76	0.027	-	74	-	126

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 27.1.A. Component Loads For Space "3267 GUIDANCE-OFFICE" In Zone "27"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
<b>SPACE LOADS</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>
Window & Skylight Solar Loads	80 ft²	1475	-	80 ft²	-	-
Wall Transmission	72 ft²	78	-	72 ft²	276	-
Roof Transmission	159 ft²	196	-	159 ft²	263	-
Window Transmission	80 ft²	388	-	80 ft²	1870	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	111 W	322	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	239 W	759	-	0	0	-
People	2	393	410	0	0	0
Infiltration	-	102	104	-	403	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	186	26	5%	141	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>3899</b>	<b>539</b>	-	<b>2952</b>	<b>0</b>

TABLE 27.1.B. Envelope Loads For Space "3267 GUIDANCE-OFFICE" In Zone "27"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NE EXPOSURE</b>						
WALL	72	0.062	-	78	-	276
WINDOW 1	80	0.380	0.437	388	1475	1870
<b>H EXPOSURE</b>						
ROOF	159	0.027	-	196	-	263

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 28.1.A. Component Loads For Space "3268 GUIDANCE-OFFICE" In Zone "28"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	65 ft²	1198	-	65 ft²	-	-
Wall Transmission	292 ft²	415	-	292 ft²	1119	-
Roof Transmission	154 ft²	190	-	154 ft²	255	-
Window Transmission	65 ft²	315	-	65 ft²	1519	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	108 W	312	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	231 W	735	-	0	0	-
People	2	393	410	0	0	0
Infiltration	-	239	244	-	947	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	190	33	5%	192	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>3988</b>	<b>687</b>	-	<b>4032</b>	<b>0</b>

TABLE 28.1.B. Envelope Loads For Space "3268 GUIDANCE-OFFICE" In Zone "28"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NE EXPOSURE</b>						
WALL	72	0.062	-	78	-	276
WINDOW 1	65	0.380	0.437	315	1198	1519
<b>SE EXPOSURE</b>						
WALL	220	0.062	-	337	-	843
<b>H EXPOSURE</b>						
ROOF	154	0.027	-	190	-	255

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 29.1.A. Component Loads For Space "3269 WORKROOM" In Zone "29"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 1500			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 91.0 °F / 73.0 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	266 ft²	422	-	266 ft²	1019	-
Roof Transmission	196 ft²	218	-	196 ft²	324	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	137 W	402	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	294 W	940	-	0	0	-
People	8	1596	1640	0	0	0
Infiltration	-	184	182	-	706	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	188	91	5%	102	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>3950</b>	<b>1913</b>	-	<b>2152</b>	<b>0</b>

TABLE 29.1.B. Envelope Loads For Space "3269 WORKROOM" In Zone "29"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>SE EXPOSURE</b>						
WALL	266	0.062	-	422	-	1019
<b>H EXPOSURE</b>						
ROOF	196	0.027	-	218	-	324

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 30.1.A. Component Loads For Space "1134 MAKER SPACE" In Zone "30"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 1400 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	366 ft²	12563	-	366 ft²	-	-
Wall Transmission	551 ft²	761	-	551 ft²	2112	-
Roof Transmission	793 ft²	913	-	793 ft²	1311	-
Window Transmission	366 ft²	1936	-	366 ft²	9328	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	1955 ft²	0	-	1955 ft²	1908	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	1369 W	3964	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	2000 W	6364	-	0	0	-
People	26	5104	5330	0	0	0
Infiltration	-	615	625	-	2434	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	1611	298	5%	855	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>33830</b>	<b>6253</b>	-	<b>17947</b>	<b>0</b>

TABLE 30.1.B. Envelope Loads For Space "1134 MAKER SPACE" In Zone "30"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>E EXPOSURE</b>						
WALL	287	0.062	-	396	-	1100
WINDOW 2	105	0.500	1.000	670	5696	3229
<b>SSW EXPOSURE</b>						
WALL	264	0.062	-	365	-	1012
WINDOW 1	261	0.380	0.333	1266	6867	6100
<b>H EXPOSURE</b>						
ROOF	793	0.027	-	913	-	1311



## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 31.1.A. Component Loads For Space "1048 BREAKOUT" In Zone "31"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	310 ft²	0	-	310 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	217 W	671	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	155 W	507	-	0	0	-
People	8	1718	1640	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	145	82	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>3040</b>	<b>1722</b>	-	<b>0</b>	<b>0</b>

TABLE 31.1.B. Envelope Loads For Space "1048 BREAKOUT" In Zone "31"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING	COOLING	HEATING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR	TRANS
			(BTU/hr)	(BTU/hr)	(BTU/hr)		

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 32.1.A. Component Loads For Space "1132 CLASSROOM-TP" In Zone "32"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	98 ft²	0	-	98 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	69 W	212	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	49 W	160	-	0	0	-
People	2	429	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	40	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>842</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

TABLE 32.1.B. Envelope Loads For Space "1132 CLASSROOM-TP" In Zone "32"						
		COOLING		COOLING		HEATING
		TRANS		SOLAR		TRANS
		Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 33.1.A. Component Loads For Space "1000B CORRIDOR (E)" In Zone "33"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500 COOLING OA DB / WB 91.0 °F / 73.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	181 ft²	2395	-	181 ft²	-	-
Wall Transmission	358 ft²	345	-	358 ft²	1372	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	181 ft²	912	-	181 ft²	4230	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	1879 ft²	0	-	1879 ft²	1716	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	1315 W	3854	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	372	348	-	1430	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	394	17	5%	437	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>8272</b>	<b>365</b>	-	<b>9186</b>	<b>0</b>

TABLE 33.1.B. Envelope Loads For Space "1000B CORRIDOR (E)" In Zone "33"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NNE EXPOSURE</b>						
WALL	358	0.062	-	345	-	1372
WINDOW 1	181	0.380	0.437	912	2395	4230

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 34.1.A. Component Loads For Space "1130 CLASSROOM-ELL" In Zone "34"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1400 COOLING OA DB / WB 86.0 °F / 70.4 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	144 ft²	4502	-	144 ft²	-	-
Wall Transmission	262 ft²	364	-	262 ft²	1004	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	144 ft²	452	-	144 ft²	3365	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	867 ft²	0	-	867 ft²	902	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	607 W	1758	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	434 W	1379	-	0	0	-
People	26	5104	5330	0	0	0
Infiltration	-	193	196	-	1077	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	688	276	5%	317	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>14441</b>	<b>5803</b>	-	<b>6667</b>	<b>0</b>

TABLE 34.1.B. Envelope Loads For Space "1130 CLASSROOM-ELL" In Zone "34"						
	Area (ft²)	U-Value (BTU/(hr-ft²-°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>S EXPOSURE</b>						
WALL	185	0.062	-	291	-	709
WINDOW 1	144	0.380	0.333	452	4502	3365
<b>WSW EXPOSURE</b>						
WALL	56	0.062	-	47	-	215
<b>ESE EXPOSURE</b>						
WALL	21	0.062	-	26	-	80

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

**TABLE 35.1.A. Component Loads For Space "1038 BREAKOUT" In Zone "35"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	341 ft²	0	-	341 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	239 W	738	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	171 W	557	-	0	0	-
People	8	1718	1640	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	151	82	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>3164</b>	<b>1722</b>	-	<b>0</b>	<b>0</b>

**TABLE 35.1.B. Envelope Loads For Space "1038 BREAKOUT" In Zone "35"**

				COOLING	COOLING	HEATING
	Area	U-Value	Shade	TRANS	SOLAR	TRANS
	(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 36.1.A. Component Loads For Space "1128B SPED-READING" In Zone "36"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	199 ft²	0	-	199 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	139 W	431	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	100 W	325	-	0	0	-
People	4	806	480	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	78	24	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1640</b>	<b>504</b>	-	<b>0</b>	<b>0</b>

TABLE 36.1.B. Envelope Loads For Space "1128B SPED-READING" In Zone "36"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 37.1.A. Component Loads For Space "1128A SPED-READING" In Zone "37"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	137 ft²	0	-	137 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	96 W	296	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	69 W	224	-	0	0	-
People	4	806	480	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	66	24	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1393</b>	<b>504</b>	-	<b>0</b>	<b>0</b>

TABLE 37.1.B. Envelope Loads For Space "1128A SPED-READING" In Zone "37"						
				COOLING	COOLING	HEATING
	Area	U-Value	Shade	TRANS	SOLAR	TRANS
	(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 38.1.A. Component Loads For Space "1128C SPED-RESOURCE" In Zone "38"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1500 COOLING OA DB / WB 86.5 °F / 70.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	93 ft²	3005	-	93 ft²	-	-
Wall Transmission	327 ft²	532	-	327 ft²	1253	-
Roof Transmission	7 ft²	6	-	7 ft²	12	-
Window Transmission	93 ft²	310	-	93 ft²	2173	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	503 ft²	0	-	503 ft²	654	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	352 W	1032	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	252 W	804	-	0	0	-
People	16	2997	1920	0	0	0
Infiltration	-	208	208	-	1115	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	445	106	5%	260	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>9337</b>	<b>2235</b>	-	<b>5467</b>	<b>0</b>

TABLE 38.1.B. Envelope Loads For Space "1128C SPED-RESOURCE" In Zone "38"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>SSW EXPOSURE</b>						
WALL	327	0.062	-	532	-	1253
WINDOW 1	93	0.380	0.333	310	3005	2173
<b>H EXPOSURE</b>						
ROOF	7	0.027	-	6	-	12



## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 39.1.A. Component Loads For Space "1122 CLASSROOM-TP" In Zone "39"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	96 ft²	0	-	96 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	67 W	208	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	48 W	157	-	0	0	-
People	2	429	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	40	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>834</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

TABLE 39.1.B. Envelope Loads For Space "1122 CLASSROOM-TP" In Zone "39"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 40.1.A. Component Loads For Space "1009 COHORT COMMON" In Zone "40"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	1420 ft²	0	-	1420 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	994 W	3073	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	710 W	2321	-	0	0	-
People	30	6442	6150	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	592	308	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>12428</b>	<b>6458</b>	-	<b>0</b>	<b>0</b>

TABLE 40.1.B. Envelope Loads For Space "1009 COHORT COMMON" In Zone "40"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING	COOLING	HEATING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR	TRANS
					(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 41.1.A. Component Loads For Space "1126 GUIDANCE-OFFICE" In Zone "41"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	135 ft²	0	-	135 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	95 W	292	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	203 W	662	-	0	0	-
People	4	859	820	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	91	41	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1904</b>	<b>861</b>	-	<b>0</b>	<b>0</b>

TABLE 41.1.B. Envelope Loads For Space "1126 GUIDANCE-OFFICE" In Zone "41"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING	COOLING	HEATING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR	TRANS
					(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 42.1.A. Component Loads For Space "1121B GUIDANCE-WAITING" In Zone "42"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	76 ft²	0	-	76 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	53 W	164	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	4	806	480	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	49	24	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1019</b>	<b>504</b>	-	<b>0</b>	<b>0</b>

TABLE 42.1.B. Envelope Loads For Space "1121B GUIDANCE-WAITING" In Zone "42"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

**TABLE 42.2.A. Component Loads For Space "1121 CORRIDOR" In Zone "42"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	225 ft²	0	-	225 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	158 W	487	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	24	0	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>511</b>	<b>0</b>	-	<b>0</b>	<b>0</b>

**TABLE 42.2.B. Envelope Loads For Space "1121 CORRIDOR" In Zone "42"**

				COOLING	COOLING	HEATING
	Area	U-Value	Shade	TRANS	SOLAR	TRANS
	(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 42.3.A. Component Loads For Space "1121A GUIDANCE-STORAGE" In Zone "42"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
SPACE LOADS	Details			Details		
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	19 ft²	0	-	19 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	13 W	41	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	2	0	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>43</b>	<b>0</b>	-	<b>0</b>	<b>0</b>

TABLE 42.3.B. Envelope Loads For Space "1121A GUIDANCE-STORAGE" In Zone "42"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING	COOLING	HEATING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)	

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 43.1.A. Component Loads For Space "1125 GUIDANCE OFFICE" In Zone "43"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1400			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 86.0 °F / 70.4 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
<b>SPACE LOADS</b>	Details	(BTU/hr)	(BTU/hr)	Details	(BTU/hr)	(BTU/hr)
Window & Skylight Solar Loads	66 ft²	2064	-	66 ft²	-	-
Wall Transmission	211 ft²	204	-	211 ft²	809	-
Roof Transmission	108 ft²	94	-	108 ft²	179	-
Window Transmission	66 ft²	207	-	66 ft²	1542	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	157 ft²	0	-	157 ft²	280	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	110 W	318	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	236 W	749	-	0	0	-
People	2	393	410	0	0	0
Infiltration	-	132	138	-	735	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	208	27	5%	177	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>4369</b>	<b>575</b>	-	<b>3723</b>	<b>0</b>

TABLE 43.1.B. Envelope Loads For Space "1125 GUIDANCE OFFICE" In Zone "43"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>W EXPOSURE</b>						
WALL	133	0.062	-	81	-	510
<b>S EXPOSURE</b>						
WALL	78	0.062	-	123	-	299
WINDOW 1	66	0.380	0.333	207	2064	1542
<b>H EXPOSURE</b>						
ROOF	108	0.027	-	94	-	179

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 44.1.A. Component Loads For Space "1124 OFFICE-DEPT" In Zone "44"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1300 COOLING OA DB / WB 84.8 °F / 70.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	89 ft²	2884	-	89 ft²	-	-
Wall Transmission	55 ft²	74	-	55 ft²	211	-
Roof Transmission	96 ft²	83	-	96 ft²	159	-
Window Transmission	89 ft²	246	-	89 ft²	2080	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	159 ft²	0	-	159 ft²	214	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	111 W	318	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	239 W	755	-	0	0	-
People	2	386	410	0	0	0
Infiltration	-	61	71	-	382	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	240	24	5%	152	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>5047</b>	<b>506</b>	-	<b>3198</b>	<b>0</b>

TABLE 44.1.B. Envelope Loads For Space "1124 OFFICE-DEPT" In Zone "44"						
	Area (ft²)	U-Value (BTU/(hr-ft²-°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>S EXPOSURE</b>						
WALL	55	0.062	-	74	-	211
WINDOW 1	89	0.380	0.333	246	2884	2080
<b>H EXPOSURE</b>						
ROOF	96	0.027	-	83	-	159



## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

**TABLE 45.1.A. Component Loads For Space "1123 OFFICE-DEPT" In Zone "45"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1300			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 84.8 °F / 70.0 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
<b>SPACE LOADS</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>
Window & Skylight Solar Loads	65 ft²	2106	-	65 ft²	-	-
Wall Transmission	72 ft²	97	-	72 ft²	276	-
Roof Transmission	57 ft²	49	-	57 ft²	94	-
Window Transmission	65 ft²	179	-	65 ft²	1519	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	153 ft²	0	-	153 ft²	207	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	107 W	306	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	230 W	727	-	0	0	-
People	2	386	410	0	0	0
Infiltration	-	58	68	-	364	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	195	24	5%	123	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>4104</b>	<b>502</b>	-	<b>2583</b>	<b>0</b>

**TABLE 45.1.B. Envelope Loads For Space "1123 OFFICE-DEPT" In Zone "45"**

	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>S EXPOSURE</b>						
WALL	72	0.062	-	97	-	276
WINDOW 1	65	0.380	0.333	179	2106	1519
<b>H EXPOSURE</b>						
ROOF	57	0.027	-	49	-	94

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 46.1.A. Component Loads For Space "1120 WORKROOM" In Zone "46"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	194 ft²	0	-	194 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	136 W	420	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	291 W	951	-	0	0	-
People	8	1718	1640	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	154	82	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>3244</b>	<b>1722</b>	-	<b>0</b>	<b>0</b>

TABLE 46.1.B. Envelope Loads For Space "1120 WORKROOM" In Zone "46"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 47.1.A. Component Loads For Space "1114 SCIENCE CLASSROOM" In Zone "47"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1400 COOLING OA DB / WB 86.0 °F / 70.4 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	195 ft²	6097	-	195 ft²	-	-
Wall Transmission	253 ft²	398	-	253 ft²	970	-
Roof Transmission	265 ft²	231	-	265 ft²	438	-
Window Transmission	195 ft²	612	-	195 ft²	4557	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	1136 ft²	0	-	1136 ft²	1003	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	795 W	2303	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	568 W	1807	-	0	0	-
People	26	5104	5330	0	0	0
Infiltration	-	213	216	-	1189	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	838	277	5%	408	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>17604</b>	<b>5823</b>	-	<b>8564</b>	<b>0</b>

TABLE 47.1.B. Envelope Loads For Space "1114 SCIENCE CLASSROOM" In Zone "47"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>S EXPOSURE</b>						
WALL	253	0.062	-	398	-	970
WINDOW 1	195	0.380	0.333	612	6097	4557
<b>H EXPOSURE</b>						
ROOF	265	0.027	-	231	-	438

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 48.1.A. Component Loads For Space "1112 SCIENCE-TP" In Zone "48"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	98 ft²	0	-	98 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	69 W	212	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	49 W	160	-	0	0	-
People	2	429	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	40	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>842</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

TABLE 48.1.B. Envelope Loads For Space "1112 SCIENCE-TP" In Zone "48"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING	COOLING	HEATING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR	TRANS
					(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 49.1.A. Component Loads For Space "1111A SCIENCE PREP" In Zone "49"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	81 ft²	0	-	81 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	57 W	175	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	41 W	132	-	0	0	-
People	2	429	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	37	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>774</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

TABLE 49.1.B. Envelope Loads For Space "1111A SCIENCE PREP" In Zone "49"							
					COOLING	COOLING	HEATING
		Area	U-Value	Shade	TRANS	SOLAR	TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 49.2.A. Component Loads For Space "1111B SCIENCE PREP" In Zone "49"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	80 ft²	0	-	80 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	56 W	173	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	40 W	131	-	0	0	-
People	2	429	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	37	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>770</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

TABLE 49.2.B. Envelope Loads For Space "1111B SCIENCE PREP" In Zone "49"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 50.1.A. Component Loads For Space "1110 SCIENCE CLASSROOM" In Zone "50"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1200 COOLING OA DB / WB 83.0 °F / 69.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	261 ft²	8268	-	261 ft²	-	-
Wall Transmission	772 ft²	656	-	772 ft²	2959	-
Roof Transmission	274 ft²	216	-	274 ft²	453	-
Window Transmission	261 ft²	583	-	261 ft²	6100	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	1146 ft²	0	-	1146 ft²	1558	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	802 W	2263	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	573 W	1804	-	0	0	-
People	26	4920	5330	0	0	0
Infiltration	-	356	485	-	2742	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	953	291	5%	691	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>20019</b>	<b>6105</b>	-	<b>14501</b>	<b>0</b>

TABLE 50.1.B. Envelope Loads For Space "1110 SCIENCE CLASSROOM" In Zone "50"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>SSE EXPOSURE</b>						
WALL	187	0.062	-	246	-	717
WINDOW 1	261	0.380	0.333	583	8268	6100
<b>ENE EXPOSURE</b>						
WALL	585	0.062	-	410	-	2242
<b>H EXPOSURE</b>						
ROOF	274	0.027	-	216	-	453

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 51.1.A. Component Loads For Space "2134 CLASSROOM" In Zone "51"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1500 COOLING OA DB / WB 86.5 °F / 70.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	Details			Details		
Window & Skylight Solar Loads	190 ft²	6138	-	190 ft²	-	-
Wall Transmission	329 ft²	462	-	329 ft²	1261	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	190 ft²	632	-	190 ft²	4440	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	610 W	1789	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	436 W	1394	-	0	0	-
People	26	5187	5330	0	0	0
Infiltration	-	258	257	-	1377	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	793	279	5%	354	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>16653</b>	<b>5867</b>	-	<b>7433</b>	<b>0</b>

TABLE 51.1.B. Envelope Loads For Space "2134 CLASSROOM" In Zone "51"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>SSW EXPOSURE</b>						
WALL	202	0.062	-	328	-	774
WINDOW 1	190	0.380	0.333	632	6138	4440
<b>W EXPOSURE</b>						
WALL	56	0.062	-	50	-	215
<b>ESE EXPOSURE</b>						
WALL	71	0.062	-	83	-	272



## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 52.1.A. Component Loads For Space "2132 CLASSROOM-TP" In Zone "52"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	69 W	212	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	49 W	160	-	0	0	-
People	2	429	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	40	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>842</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

TABLE 52.1.B. Envelope Loads For Space "2132 CLASSROOM-TP" In Zone "52"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 53.1.A. Component Loads For Space "2130 CLASSROOM" In Zone "53"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1400			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 86.0 °F / 70.4 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	190 ft²	5941	-	190 ft²	-	-
Wall Transmission	293 ft²	399	-	293 ft²	1123	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	190 ft²	597	-	190 ft²	4440	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	612 W	1772	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	437 W	1391	-	0	0	-
People	26	5104	5330	0	0	0
Infiltration	-	230	236	-	1282	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	772	278	5%	342	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>16205</b>	<b>5845</b>	-	<b>7187</b>	<b>0</b>

TABLE 53.1.B. Envelope Loads For Space "2130 CLASSROOM" In Zone "53"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>S EXPOSURE</b>						
WALL	202	0.062	-	318	-	774
WINDOW 1	190	0.380	0.333	597	5941	4440
<b>WSW EXPOSURE</b>						
WALL	56	0.062	-	47	-	215
<b>ESE EXPOSURE</b>						
WALL	21	0.062	-	26	-	80
<b>W EXPOSURE</b>						
WALL	14	0.062	-	9	-	54

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 54.1.A. Component Loads For Space "2038 BREAKOUT" In Zone "54"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	262 W	809	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	187 W	611	-	0	0	-
People	8	1718	1640	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	157	82	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>3296</b>	<b>1722</b>	-	<b>0</b>	<b>0</b>

TABLE 54.1.B. Envelope Loads For Space "2038 BREAKOUT" In Zone "54"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 55.1.A. Component Loads For Space "2124 SPED-CLASSROOM" In Zone "55"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1500 COOLING OA DB / WB 86.5 °F / 70.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	190 ft²	6138	-	190 ft²	-	-
Wall Transmission	329 ft²	477	-	329 ft²	1261	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	190 ft²	632	-	190 ft²	4440	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	36 ft²	31	-	36 ft²	218	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	611 W	1791	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	437 W	1396	-	0	0	-
People	26	5187	5330	0	0	0
Infiltration	-	258	258	-	1377	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	796	279	5%	365	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>16706</b>	<b>5867</b>	-	<b>7662</b>	<b>0</b>

TABLE 55.1.B. Envelope Loads For Space "2124 SPED-CLASSROOM" In Zone "55"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>SSW EXPOSURE</b>						
WALL	202	0.062	-	328	-	774
WINDOW 1	190	0.380	0.333	632	6138	4440
<b>WSW EXPOSURE</b>						
WALL	56	0.062	-	66	-	215
<b>ESE EXPOSURE</b>						
WALL	71	0.062	-	83	-	272

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

**TABLE 56.1.A. Component Loads For Space "2122 SPED-TP" In Zone "56"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	69 W	212	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	49 W	160	-	0	0	-
People	2	429	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	40	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>842</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

**TABLE 56.1.B. Envelope Loads For Space "2122 SPED-TP" In Zone "56"**

		COOLING		HEATING	
		COOLING	COOLING	COOLING	HEATING
		TRANS	SOLAR	TRANS	TRANS
Area	U-Value	Shade	(BTU/hr)	(BTU/hr)	(BTU/hr)
(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 57.1.A. Component Loads For Space "2000B CORRIDOR (E)" In Zone "57"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1700			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 89.5 °F / 72.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	180 ft²	2057	-	180 ft²	-	-
Wall Transmission	318 ft²	321	-	318 ft²	1219	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	180 ft²	859	-	180 ft²	4207	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	1145 W	3426	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	311	336	-	1322	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	349	17	5%	337	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>7323</b>	<b>353</b>	-	<b>7084</b>	<b>0</b>

TABLE 57.1.B. Envelope Loads For Space "2000B CORRIDOR (E)" In Zone "57"						
				COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
N EXPOSURE	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.			
WALL	318	0.062	-	321	-	1219
WINDOW 1	180	0.380	0.437	859	2057	4207

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 58.1.A. Component Loads For Space "2120 SPED-CLASSROOM" In Zone "58"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1400 COOLING OA DB / WB 86.0 °F / 70.4 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	190 ft²	5941	-	190 ft²	-	-
Wall Transmission	293 ft²	393	-	293 ft²	1123	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	190 ft²	597	-	190 ft²	4440	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	612 W	1772	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	437 W	1391	-	0	0	-
People	26	5104	5330	0	0	0
Infiltration	-	230	236	-	1282	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	771	278	5%	342	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>16198</b>	<b>5845</b>	-	<b>7187</b>	<b>0</b>

TABLE 58.1.B. Envelope Loads For Space "2120 SPED-CLASSROOM" In Zone "58"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>S EXPOSURE</b>						
WALL	202	0.062	-	318	-	774
WINDOW 1	190	0.380	0.333	597	5941	4440
<b>E EXPOSURE</b>						
WALL	21	0.062	-	20	-	80
<b>WSW EXPOSURE</b>						
WALL	56	0.062	-	47	-	215
<b>W EXPOSURE</b>						
WALL	14	0.062	-	9	-	54

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 59.1.A. Component Loads For Space "2114 CLASSROOM" In Zone "59"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1400 COOLING OA DB / WB 86.0 °F / 70.4 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	190 ft²	5941	-	190 ft²	-	-
Wall Transmission	329 ft²	433	-	329 ft²	1261	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	190 ft²	597	-	190 ft²	4440	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	600 W	1738	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	429 W	1363	-	0	0	-
People	26	5104	5330	0	0	0
Infiltration	-	247	254	-	1377	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	771	279	5%	354	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>16194</b>	<b>5864</b>	-	<b>7433</b>	<b>0</b>

TABLE 59.1.B. Envelope Loads For Space "2114 CLASSROOM" In Zone "59"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>S EXPOSURE</b>						
WALL	202	0.062	-	318	-	774
WINDOW 1	190	0.380	0.333	597	5941	4440
<b>E EXPOSURE</b>						
WALL	71	0.062	-	68	-	272
<b>WSW EXPOSURE</b>						
WALL	56	0.062	-	47	-	215



## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 60.1.A. Component Loads For Space "2112 CLASSROOM-TP" In Zone "60"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	69 W	212	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	49 W	160	-	0	0	-
People	2	429	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	40	21	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>842</b>	<b>431</b>	-	<b>0</b>	<b>0</b>

TABLE 60.1.B. Envelope Loads For Space "2112 CLASSROOM-TP" In Zone "60"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 61.1.A. Component Loads For Space "2110 CLASSROOM-ELL" In Zone "61"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1200 COOLING OA DB / WB 83.0 °F / 69.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	190 ft²	6019	-	190 ft²	-	-
Wall Transmission	731 ft²	770	-	731 ft²	2802	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	190 ft²	424	-	190 ft²	4440	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	612 W	1726	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	437 W	1376	-	0	0	-
People	26	4920	5330	0	0	0
Infiltration	-	317	434	-	2444	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	778	288	5%	484	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>16329</b>	<b>6052</b>	-	<b>10170</b>	<b>0</b>

TABLE 61.1.B. Envelope Loads For Space "2110 CLASSROOM-ELL" In Zone "61"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>SSE EXPOSURE</b>						
WALL	202	0.062	-	266	-	774
WINDOW 1	190	0.380	0.333	424	6019	4440
<b>SW EXPOSURE</b>						
WALL	56	0.062	-	27	-	215
<b>WSW EXPOSURE</b>						
WALL	21	0.062	-	7	-	80
<b>E EXPOSURE</b>						
WALL	452	0.062	-	470	-	1732

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 62.1.A. Component Loads For Space "3134 CLASSROOM" In Zone "62"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1500 COOLING OA DB / WB 86.5 °F / 70.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	185 ft²	5977	-	185 ft²	-	-
Wall Transmission	364 ft²	504	-	364 ft²	1395	-
Roof Transmission	884 ft²	724	-	884 ft²	1461	-
Window Transmission	185 ft²	616	-	185 ft²	4323	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	619 W	1813	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	442 W	1413	-	0	0	-
People	26	5187	5330	0	0	0
Infiltration	-	272	273	-	1457	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	825	280	5%	432	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>17332</b>	<b>5883</b>	-	<b>9069</b>	<b>0</b>

TABLE 62.1.B. Envelope Loads For Space "3134 CLASSROOM" In Zone "62"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>SSW EXPOSURE</b>						
WALL	210	0.062	-	342	-	805
WINDOW 1	185	0.380	0.333	616	5977	4323
<b>W EXPOSURE</b>						
WALL	63	0.062	-	57	-	241
<b>ESE EXPOSURE</b>						
WALL	91	0.062	-	106	-	349
<b>H EXPOSURE</b>						
ROOF	884	0.027	-	724	-	1461

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 63.1.A. Component Loads For Space "3132 CLASSROOM-TP" In Zone "63"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	95 ft²	106	-	95 ft²	157	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	67 W	197	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	48 W	153	-	0	0	-
People	2	405	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	43	21	5%	8	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>904</b>	<b>431</b>	-	<b>165</b>	<b>0</b>

TABLE 63.1.B. Envelope Loads For Space "3132 CLASSROOM-TP" In Zone "63"						
		COOLING		COOLING		HEATING
		TRANS		SOLAR		TRANS
		Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	(BTU/hr)	(BTU/hr)
<b>H EXPOSURE</b>						
ROOF	95	0.027	-	106	-	157

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 64.1.A. Component Loads For Space "3130 CLASSROOM" In Zone "64"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1400 COOLING OA DB / WB 86.0 °F / 70.4 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	144 ft²	4502	-	144 ft²	-	-
Wall Transmission	367 ft²	485	-	367 ft²	1407	-
Roof Transmission	886 ft²	772	-	886 ft²	1465	-
Window Transmission	144 ft²	452	-	144 ft²	3365	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	620 W	1796	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	443 W	1410	-	0	0	-
People	26	5104	5330	0	0	0
Infiltration	-	243	250	-	1356	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	738	279	5%	380	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>15503</b>	<b>5859</b>	-	<b>7972</b>	<b>0</b>

TABLE 64.1.B. Envelope Loads For Space "3130 CLASSROOM" In Zone "64"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>S EXPOSURE</b>						
WALL	248	0.062	-	390	-	950
WINDOW 1	144	0.380	0.333	452	4502	3365
<b>WSW EXPOSURE</b>						
WALL	98	0.062	-	82	-	376
<b>W EXPOSURE</b>						
WALL	21	0.062	-	13	-	80
<b>H EXPOSURE</b>						
ROOF	886	0.027	-	772	-	1465

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 65.1.A. Component Loads For Space "3124 SCIENCE-CLASSROOM" In Zone "65"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1500 COOLING OA DB / WB 86.5 °F / 70.5 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	Details			Details		
Window & Skylight Solar Loads	172 ft²	5557	-	172 ft²	-	-
Wall Transmission	354 ft²	517	-	354 ft²	1357	-
Roof Transmission	1138 ft²	932	-	1138 ft²	1881	-
Window Transmission	172 ft²	573	-	172 ft²	4020	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	797 W	2334	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	569 W	1819	-	0	0	-
People	26	5187	5330	0	0	0
Infiltration	-	261	260	-	1396	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	859	279	5%	433	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>18039</b>	<b>5869</b>	-	<b>9086</b>	<b>0</b>

TABLE 65.1.B. Envelope Loads For Space "3124 SCIENCE-CLASSROOM" In Zone "65"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>SSW EXPOSURE</b>						
WALL	273	0.062	-	444	-	1046
WINDOW 1	172	0.380	0.333	573	5557	4020
<b>W EXPOSURE</b>						
WALL	81	0.062	-	73	-	310
<b>H EXPOSURE</b>						
ROOF	1138	0.027	-	932	-	1881

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 66.1.A. Component Loads For Space "3000B CORRIDOR (E)" In Zone "66"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jun 1400 COOLING OA DB / WB 87.5 °F / 70.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	425 ft²	20079	-	425 ft²	-	-
Wall Transmission	404 ft²	251	-	404 ft²	1548	-
Roof Transmission	1436 ft²	1698	-	1436 ft²	2374	-
Window Transmission	132 ft²	490	-	132 ft²	3085	-
Skylight Transmission	293 ft²	687	-	293 ft²	4325	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	1031 W	2986	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	290	258	-	1423	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	1324	13	5%	638	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>27805</b>	<b>271</b>	-	<b>13392</b>	<b>0</b>

TABLE 66.1.B. Envelope Loads For Space "3000B CORRIDOR (E)" In Zone "66"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>N EXPOSURE</b>						
WALL	404	0.062	-	251	-	1548
WINDOW 1	132	0.380	0.437	490	1511	3085
<b>H EXPOSURE</b>						
ROOF	1436	0.027	-	1698	-	2374
SKYLIGHT	293	0.240	0.448	687	18568	4325

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 66.2.A. Component Loads For Space "3050 COHORT COMMON" In Zone "66"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	1638 ft²	1772	-	1638 ft²	2707	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	1179 W	3491	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	842 W	2704	-	0	0	-
People	35	7088	7175	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	753	359	5%	135	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>15808</b>	<b>7534</b>	-	<b>2843</b>	<b>0</b>

TABLE 66.2.B. Envelope Loads For Space "3050 COHORT COMMON" In Zone "66"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>H EXPOSURE</b>						
ROOF	1488	0.027	-	1666	-	2459
<b>E EXPOSURE</b>						
ROOF	150	0.027	-	107	-	248



## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 67.1.A. Component Loads For Space "3122 SCIENCE-TP" In Zone "67"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	96 ft²	107	-	96 ft²	159	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	67 W	199	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	48 W	154	-	0	0	-
People	2	405	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	43	21	5%	8	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>909</b>	<b>431</b>	-	<b>167</b>	<b>0</b>

TABLE 67.1.B. Envelope Loads For Space "3122 SCIENCE-TP" In Zone "67"						
	Area (ft²)	U-Value	Shade Coeff.	COOLING	COOLING	HEATING
		(BTU/(hr-ft²·°F))		TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
	<b>H EXPOSURE</b>					
ROOF	96	0.027	-	107	-	159

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 68.1.A. Component Loads For Space "3121B SCIENCE-PREP" In Zone "68"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	79 ft²	88	-	79 ft²	131	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	55 W	164	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	40 W	127	-	0	0	-
People	2	405	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	39	21	5%	7	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>823</b>	<b>431</b>	-	<b>137</b>	<b>0</b>

TABLE 68.1.B. Envelope Loads For Space "3121B SCIENCE-PREP" In Zone "68"						
				COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
H EXPOSURE	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.			
ROOF	79	0.027	-	88	-	131

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 68.2.A. Component Loads For Space "3121A SCIENCE-PREP" In Zone "68"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	82 ft²	92	-	82 ft²	136	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	57 W	170	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	41 W	132	-	0	0	-
People	2	405	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	40	21	5%	7	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>838</b>	<b>431</b>	-	<b>142</b>	<b>0</b>

TABLE 68.2.B. Envelope Loads For Space "3121A SCIENCE-PREP" In Zone "68"						
				COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
H EXPOSURE	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.			
ROOF	82	0.027	-	92	-	136

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 69.1.A. Component Loads For Space "3120 SCIENCE-CLASSROOM" In Zone "69"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1400 COOLING OA DB / WB 86.0 °F / 70.4 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	182 ft²	5690	-	182 ft²	-	-
Wall Transmission	397 ft²	543	-	397 ft²	1522	-
Roof Transmission	1136 ft²	990	-	1136 ft²	1878	-
Window Transmission	182 ft²	572	-	182 ft²	4253	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	323 ft²	267	-	323 ft²	1987	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	795 W	2303	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	568 W	1807	-	0	0	-
People	26	5104	5330	0	0	0
Infiltration	-	276	282	-	1537	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	878	281	5%	559	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>18431</b>	<b>5893</b>	-	<b>11735</b>	<b>0</b>

TABLE 69.1.B. Envelope Loads For Space "3120 SCIENCE-CLASSROOM" In Zone "69"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>S EXPOSURE</b>						
WALL	264	0.062	-	415	-	1012
WINDOW 1	182	0.380	0.333	572	5690	4253
<b>E EXPOSURE</b>						
WALL	133	0.062	-	128	-	510
<b>H EXPOSURE</b>						
ROOF	1136	0.027	-	990	-	1878

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 70.1.A. Component Loads For Space "3114 CLASSROOM" In Zone "70"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1400 COOLING OA DB / WB 86.0 °F / 70.4 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	182 ft²	5690	-	182 ft²	-	-
Wall Transmission	403 ft²	482	-	403 ft²	1545	-
Roof Transmission	876 ft²	763	-	876 ft²	1448	-
Window Transmission	182 ft²	572	-	182 ft²	4253	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	613 W	1776	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	438 W	1394	-	0	0	-
People	26	5104	5330	0	0	0
Infiltration	-	279	288	-	1553	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	803	281	5%	440	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>16863</b>	<b>5899</b>	-	<b>9238</b>	<b>0</b>

TABLE 70.1.B. Envelope Loads For Space "3114 CLASSROOM" In Zone "70"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>S EXPOSURE</b>						
WALL	210	0.062	-	330	-	805
WINDOW 1	182	0.380	0.333	572	5690	4253
<b>W EXPOSURE</b>						
WALL	98	0.062	-	60	-	376
<b>E EXPOSURE</b>						
WALL	95	0.062	-	92	-	364
<b>H EXPOSURE</b>						
ROOF	876	0.027	-	763	-	1448

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 71.1.A. Component Loads For Space "3112 CLASSROOM-TP" In Zone "71"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	96 ft²	107	-	96 ft²	159	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	67 W	199	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	48 W	154	-	0	0	-
People	2	405	410	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	43	21	5%	8	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>909</b>	<b>431</b>	-	<b>167</b>	<b>0</b>

TABLE 71.1.B. Envelope Loads For Space "3112 CLASSROOM-TP" In Zone "71"						
		COOLING			HEATING	
		Area	U-Value	Shade	COOLING	COOLING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR
H EXPOSURE				(BTU/hr)	(BTU/hr)	(BTU/hr)
ROOF	96	0.027	-	107	-	159

## Space Design Load Summary for RTU-3&4

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/04/2019  
 02:48PM

TABLE 72.1.A. Component Loads For Space "3110 CLASSROOM" In Zone "72"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Sep 1300 COOLING OA DB / WB 84.8 °F / 70.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
		Sensible (BTU/hr)	Latent (BTU/hr)		Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>	<b>Details</b>			<b>Details</b>		
Window & Skylight Solar Loads	158 ft²	4658	-	158 ft²	-	-
Wall Transmission	836 ft²	927	-	836 ft²	3204	-
Roof Transmission	874 ft²	752	-	874 ft²	1445	-
Window Transmission	158 ft²	436	-	158 ft²	3692	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	0 ft²	0	-	0 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	612 W	1750	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	437 W	1383	-	0	0	-
People	26	5015	5330	0	0	0
Infiltration	-	421	479	-	2638	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	767	290	5%	549	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>16110</b>	<b>6100</b>	-	<b>11528</b>	<b>0</b>

TABLE 72.1.B. Envelope Loads For Space "3110 CLASSROOM" In Zone "72"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>SSE EXPOSURE</b>						
WALL	234	0.062	-	353	-	897
WINDOW 1	158	0.380	0.333	436	4658	3692
<b>WSW EXPOSURE</b>						
WALL	21	0.062	-	11	-	80
<b>SW EXPOSURE</b>						
WALL	98	0.062	-	75	-	376
<b>E EXPOSURE</b>						
WALL	483	0.062	-	487	-	1851
<b>H EXPOSURE</b>						
ROOF	874	0.027	-	752	-	1445





## Space Design Load Summary for RTU-5

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:34PM

**TABLE 1.1.A. Component Loads For Space "1320 GYM" In Zone "Gymnasium"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 2200			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 80.6 °F / 70.0 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
		Sensible	Latent		Sensible	Latent
SPACE LOADS	Details	(BTU/hr)	(BTU/hr)	Details	(BTU/hr)	(BTU/hr)
Window & Skylight Solar Loads	253 ft²	2818	-	253 ft²	-	-
Wall Transmission	2790 ft²	3280	-	2790 ft²	10694	-
Roof Transmission	2912 ft²	886	-	2912 ft²	4814	-
Window Transmission	253 ft²	644	-	253 ft²	5913	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	2912 ft²	0	-	2912 ft²	4049	-
Partitions	1589 ft²	0	-	1589 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	2038 W	6483	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	728 W	2409	-	0	0	-
People	725	155692	148625	0	0	0
Infiltration	-	735	-1650	-	8077	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	8647	7349	5%	1677	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>181595</b>	<b>154324</b>	-	<b>35224</b>	<b>0</b>

**TABLE 1.1.B. Envelope Loads For Space "1320 GYM" In Zone "Gymnasium"**

	Area (ft²)	U-Value (BTU/(hr-ft²-°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>N EXPOSURE</b>						
WALL	1125	0.062	-	1015	-	4313
WINDOW 1	101	0.380	0.437	257	690	2360
<b>W EXPOSURE</b>						
WALL	1303	0.062	-	1907	-	4992
WINDOW 1	101	0.380	0.333	257	1680	2360
<b>S EXPOSURE</b>						
WALL	121	0.062	-	121	-	462
WINDOW 1	51	0.380	0.333	130	449	1192
<b>E EXPOSURE</b>						
WALL	242	0.062	-	237	-	927
<b>E EXPOSURE</b>						
ROOF	2912	0.027	-	886	-	4814

## Space Design Load Summary for RTU-5

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:34PM

TABLE 1.2.A. Component Loads For Space "1320B GYM Play Area" In Zone "Gymnasium"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 2200 COOLING OA DB / WB 80.6 °F / 70.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	5355 ft²	1630	-	5355 ft²	8852	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	5355 ft²	0	-	5355 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	3749 W	11922	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	1339 W	4430	-	0	0	-
People	85	52898	92650	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	3544	4633	5%	443	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>74423</b>	<b>97283</b>	-	<b>9295</b>	<b>0</b>

TABLE 1.2.B. Envelope Loads For Space "1320B GYM Play Area" In Zone "Gymnasium"						
		COOLING		COOLING		HEATING
		TRANS		SOLAR		TRANS
		Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	(BTU/hr)	(BTU/hr)
<b>E EXPOSURE</b>						
ROOF	5355	0.027	-	1630	-	8852

## Space Design Load Summary for RTU-5

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:34PM

TABLE 1.3.A. Component Loads For Space "1325 GYM STORAGE" In Zone "Gymnasium"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1500			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 91.0 °F / 73.0 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
<b>SPACE LOADS</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>
Window & Skylight Solar Loads	51 ft²	514	-	51 ft²	-	-
Wall Transmission	292 ft²	282	-	292 ft²	1120	-
Roof Transmission	313 ft²	371	-	313 ft²	517	-
Window Transmission	51 ft²	257	-	51 ft²	1192	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	313 ft²	0	-	313 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	219 W	642	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	237	241	-	911	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	115	12	5%	187	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>2418</b>	<b>253</b>	-	<b>3927</b>	<b>0</b>

TABLE 1.3.B. Envelope Loads For Space "1325 GYM STORAGE" In Zone "Gymnasium"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>NNE EXPOSURE</b>						
WALL	292	0.062	-	282	-	1120
WINDOW 1	51	0.380	0.333	257	514	1192
<b>E EXPOSURE</b>						
ROOF	313	0.027	-	371	-	517



## Space Design Load Summary for RTU-6

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:34PM

TABLE 1.1.A. Component Loads For Space "1340 AUDITORIUM" In Zone "Auditorium"						
DESIGN COOLING				DESIGN HEATING		
COOLING DATA AT Jul 1700 COOLING OA DB / WB 89.5 °F / 72.6 °F OCCUPIED T-STAT 75.0 °F				HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	285 ft²	3257	-	285 ft²	-	-
Wall Transmission	5127 ft²	6291	-	5127 ft²	19649	-
Roof Transmission	4414 ft²	4318	-	4414 ft²	7297	-
Window Transmission	285 ft²	1360	-	285 ft²	6660	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	4414 ft²	0	-	4414 ft²	4252	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	3090 W	9538	-	0	0	-
Task Lighting	4000 W	12926	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	412	78323	49440	0	0	0
Infiltration	-	3379	2529	-	14363	-2
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>119392</b>	<b>51969</b>	-	<b>52222</b>	<b>-2</b>

TABLE 1.1.B. Envelope Loads For Space "1340 AUDITORIUM" In Zone "Auditorium"						
	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING TRANS (BTU/hr)	COOLING SOLAR (BTU/hr)	HEATING TRANS (BTU/hr)
<b>N EXPOSURE</b>						
WALL	2387	0.062	-	2410	-	9148
WINDOW 1	285	0.380	0.437	1360	3257	6660
<b>E EXPOSURE</b>						
WALL	2260	0.062	-	3011	-	8662
<b>W EXPOSURE</b>						
WALL	480	0.062	-	871	-	1840
<b>S EXPOSURE</b>						
ROOF	4414	0.027	-	4318	-	7297

## Space Design Load Summary for RTU-6

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:34PM

TABLE 1.2.A. Component Loads For Space "1341 STAGE" In Zone "Auditorium"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Aug 2200 COOLING OA DB / WB 80.6 °F / 70.0 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	609 ft²	654	-	609 ft²	2334	-
Roof Transmission	1560 ft²	449	-	1560 ft²	2579	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	1560 ft²	0	-	1560 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	1092 W	3473	-	0	0	-
Task Lighting	20000 W	65669	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	100	26734	54500	0	0	0
Infiltration	-	147	102	-	1616	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>97125</b>	<b>54602</b>	-	<b>6529</b>	<b>0</b>

TABLE 1.2.B. Envelope Loads For Space "1341 STAGE" In Zone "Auditorium"						
				COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>S EXPOSURE</b>	<b>Area</b>	<b>U-Value</b>	<b>Shade</b>			
	(ft²)	(BTU/(hr-ft²-°F))	Coeff.			
WALL	609	0.062	-	654	-	2334
<b>S EXPOSURE</b>						
ROOF	1560	0.027	-	449	-	2579

## Space Design Load Summary for RTU-6

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:34PM

TABLE 1.3.A. Component Loads For Space "1345 STORAGE" In Zone "Auditorium"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	171 ft²	212	-	171 ft²	283	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	171 ft²	0	-	171 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	120 W	347	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>558</b>	<b>0</b>	-	<b>283</b>	<b>0</b>

TABLE 1.3.B. Envelope Loads For Space "1345 STORAGE" In Zone "Auditorium"						
		COOLING		COOLING		HEATING
		TRANS		SOLAR		TRANS
		Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	(BTU/hr)	(BTU/hr)
<b>E EXPOSURE</b>						
ROOF	171	0.027	-	212	-	283

## Space Design Load Summary for RTU-6

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:34PM

TABLE 2.1.A. Component Loads For Space "1343 DRESSING" In Zone "Zone 2"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	170 ft²	194	-	170 ft²	281	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	170 ft²	0	-	170 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	119 W	352	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	255 W	819	-	0	0	-
People	4	760	480	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>2125</b>	<b>480</b>	-	<b>281</b>	<b>0</b>

TABLE 2.1.B. Envelope Loads For Space "1343 DRESSING" In Zone "Zone 2"							
		Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
					TRANS	SOLAR	TRANS
					(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>S EXPOSURE</b>							
ROOF		170	0.027	-	194	-	281



## Space Design Load Summary for RTU-6

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:34PM

**TABLE 3.1.A. Component Loads For Space "1344 AV" In Zone "Zone 3"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	66 ft²	75	-	66 ft²	109	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	66 ft²	0	-	66 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	46 W	137	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	99 W	322	-	0	0	-
People	2	375	240	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>909</b>	<b>240</b>	-	<b>109</b>	<b>0</b>

**TABLE 3.1.B. Envelope Loads For Space "1344 AV" In Zone "Zone 3"**

				COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>S EXPOSURE</b>						
ROOF	66	0.027	-	75	-	109

## Space Design Load Summary for RTU-6

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:34PM

TABLE 4.1.A. Component Loads For Space "1347 DRESSING" In Zone "Zone 4"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	170 ft²	194	-	170 ft²	281	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	170 ft²	0	-	170 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	119 W	352	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	255 W	819	-	0	0	-
People	4	760	480	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>2125</b>	<b>480</b>	-	<b>281</b>	<b>0</b>

TABLE 4.1.B. Envelope Loads For Space "1347 DRESSING" In Zone "Zone 4"						
				COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
S EXPOSURE	Area (ft²)	U-Value (BTU/(hr-ft²-°F))	Shade Coeff.			
ROOF	170	0.027	-	194	-	281

## Space Design Load Summary for RTU-6

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:34PM

**TABLE 5.1.A. Component Loads For Space "1348 AV" In Zone "Zone 5"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1600			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 90.5 °F / 72.9 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
<b>SPACE LOADS</b>	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	66 ft²	75	-	66 ft²	109	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	66 ft²	0	-	66 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	60 W	178	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	129 W	420	-	0	0	-
People	2	375	240	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1048</b>	<b>240</b>	-	<b>109</b>	<b>0</b>

**TABLE 5.1.B. Envelope Loads For Space "1348 AV" In Zone "Zone 5"**

		COOLING			HEATING	
		Area	U-Value	Shade	COOLING	COOLING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR
<b>S EXPOSURE</b>				(BTU/hr)	(BTU/hr)	(BTU/hr)
ROOF	66	0.027	-	75	-	109

## Space Design Load Summary for RTU-6

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:34PM

TABLE 6.1.A. Component Loads For Space "1339 VESTIBULE" In Zone "Zone 6"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	171 ft²	220	-	171 ft²	283	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	171 ft²	0	-	171 ft²	0	-
Partitions	155 ft²	0	-	155 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	120 W	347	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>566</b>	<b>0</b>	-	<b>283</b>	<b>0</b>

TABLE 6.1.B. Envelope Loads For Space "1339 VESTIBULE" In Zone "Zone 6"							
		COOLING			HEATING		
		Area (ft²)	U-Value (BTU/(hr-ft²-°F))	Shade Coeff.	COOLING TRANS (BTU/hr)	COOLING SOLAR (BTU/hr)	HEATING TRANS (BTU/hr)
		<b>S EXPOSURE</b>					
ROOF	171	0.027	-	220	-	283	

## Space Design Load Summary for RTU-6

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 03:34PM

TABLE 7.1.A. Component Loads For Space "1349 VESTIBULE" In Zone "Zone 7"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1400 COOLING OA DB / WB 90.5 °F / 72.9 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	392 ft²	565	-	392 ft²	1502	-
Roof Transmission	212 ft²	272	-	212 ft²	350	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	171 ft²	0	-	171 ft²	486	-
Partitions	155 ft²	0	-	155 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	148 W	430	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	263	186	-	1040	-1
Miscellaneous	-	0	0	-	0	0
Safety Factor	0% / 0%	0	0	0%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1530</b>	<b>186</b>	-	<b>3379</b>	<b>-1</b>

TABLE 7.1.B. Envelope Loads For Space "1349 VESTIBULE" In Zone "Zone 7"						
				COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
<b>E EXPOSURE</b>						
WALL	392	0.062	-	565	-	1502
<b>S EXPOSURE</b>						
ROOF	212	0.027	-	272	-	350



## Space Design Load Summary for RTU-7

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 02:55PM

**TABLE 1.1.A. Component Loads For Space "1324 LOCKER" In Zone "VAV-3-1"**

	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 87.8 °F / 72.1 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
		Sensible	Latent		Sensible	Latent
<b>SPACE LOADS</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>	<b>Details</b>	<b>(BTU/hr)</b>	<b>(BTU/hr)</b>
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	420 ft²	849	-	420 ft²	1610	-
Roof Transmission	76 ft²	60	-	76 ft²	125	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	418 ft²	0	-	418 ft²	590	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	293 W	883	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	232	408	-	1115	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	101	20	5%	172	0
<b>&gt;&gt; Total Zone Loads</b>	<b>-</b>	<b>2126</b>	<b>428</b>	<b>-</b>	<b>3611</b>	<b>0</b>

**TABLE 1.1.B. Envelope Loads For Space "1324 LOCKER" In Zone "VAV-3-1"**

	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.	COOLING	COOLING	HEATING
				TRANS (BTU/hr)	SOLAR (BTU/hr)	TRANS (BTU/hr)
<b>W EXPOSURE</b>						
WALL	420	0.062	-	849	-	1610
<b>H EXPOSURE</b>						
ROOF	76	0.027	-	60	-	125

## Space Design Load Summary for RTU-7

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 02:55PM

TABLE 2.1.A. Component Loads For Space "1321 LOCKER" In Zone "VAV-3-2"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100 COOLING OA DB / WB 43.1 °F / 42.6 °F OCCUPIED T-STAT 75.0 °F			HEATING DATA AT DES HTG HEATING OA DB / WB 8.5 °F / 4.9 °F OCCUPIED T-STAT 70.0 °F		
	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
<b>SPACE LOADS</b>						
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	387 ft²	0	-	387 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	271 W	838	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	42	0	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>879</b>	<b>0</b>	-	<b>0</b>	<b>0</b>

TABLE 2.1.B. Envelope Loads For Space "1321 LOCKER" In Zone "VAV-3-2"							
		DESIGN COOLING			DESIGN HEATING		
		Area	U-Value	Shade	COOLING TRANS	COOLING SOLAR	HEATING TRANS
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	(BTU/hr)	(BTU/hr)	(BTU/hr)



## Space Design Load Summary for RTU-7

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 02:55PM

TABLE 3.1.A. Component Loads For Space "1210 TOILET (3 STALLS)" In Zone "VAV-3-3"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jul 1800			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 87.8 °F / 72.1 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	238 ft²	481	-	238 ft²	912	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	196 ft²	0	-	196 ft²	299	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	137 W	414	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	131	213	-	632	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	51	11	5%	92	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>1078</b>	<b>224</b>	-	<b>1935</b>	<b>0</b>

TABLE 3.1.B. Envelope Loads For Space "1210 TOILET (3 STALLS)" In Zone "VAV-3-3"						
				COOLING	COOLING	HEATING
				TRANS	SOLAR	TRANS
				(BTU/hr)	(BTU/hr)	(BTU/hr)
W EXPOSURE	Area (ft²)	U-Value (BTU/(hr-ft²·°F))	Shade Coeff.			
WALL	238	0.062	-	481	-	912

## Space Design Load Summary for RTU-7

Project Name: FULLER SCHOOL  
 Prepared by: Garcia Galuska DeSousa consulting engineers

10/03/2019  
 02:55PM

TABLE 4.1.A. Component Loads For Space "1212 TOILET (3 STALLS)" In Zone "VAV-3-4"						
	DESIGN COOLING			DESIGN HEATING		
	COOLING DATA AT Jan 2100			HEATING DATA AT DES HTG		
	COOLING OA DB / WB 43.1 °F / 42.6 °F			HEATING OA DB / WB 8.5 °F / 4.9 °F		
OCCUPIED T-STAT 75.0 °F			OCCUPIED T-STAT 70.0 °F			
SPACE LOADS	Details	Sensible (BTU/hr)	Latent (BTU/hr)	Details	Sensible (BTU/hr)	Latent (BTU/hr)
Window & Skylight Solar Loads	0 ft²	0	-	0 ft²	-	-
Wall Transmission	0 ft²	0	-	0 ft²	0	-
Roof Transmission	0 ft²	0	-	0 ft²	0	-
Window Transmission	0 ft²	0	-	0 ft²	0	-
Skylight Transmission	0 ft²	0	-	0 ft²	0	-
Door Loads	0 ft²	0	-	0 ft²	0	-
Floor Transmission	164 ft²	0	-	164 ft²	0	-
Partitions	0 ft²	0	-	0 ft²	0	-
Ceiling	0 ft²	0	-	0 ft²	0	-
Overhead Lighting	115 W	355	-	0	0	-
Task Lighting	0 W	0	-	0	0	-
Electric Equipment	0 W	0	-	0	0	-
People	0	0	0	0	0	0
Infiltration	-	0	0	-	0	0
Miscellaneous	-	0	0	-	0	0
Safety Factor	5% / 5%	18	0	5%	0	0
<b>&gt;&gt; Total Zone Loads</b>	-	<b>373</b>	<b>0</b>	-	<b>0</b>	<b>0</b>

TABLE 4.1.B. Envelope Loads For Space "1212 TOILET (3 STALLS)" In Zone "VAV-3-4"							
		COOLING			HEATING		
		Area	U-Value	Shade	COOLING	COOLING	HEATING
		(ft²)	(BTU/(hr-ft²·°F))	Coeff.	TRANS	SOLAR	TRANS
			(BTU/hr)	(BTU/hr)	(BTU/hr)		

## Appendix

### 4 Draft CostEstimate

- Draft Estimate Comparison
- CMR draft estimate
- Designer draft estimate
- OPM draft estimate and comparison analysis



Dated 9/27/19 (updated 9/30/19)

	Consigli Final 60% CD Estimate 8/5/19	Consigli Draft 90% CD Estimate 9/27/19	Delta from Final 60% Estimate	Myakoda Draft 90% CD Estimate 9/30/19	Delta from Final 60% Estimate	Fogarty Draft 90% CD Estimate 9/26/19	Delta from Final 60% Estimate
SF	136,790	136,790		136,790		136,790	
Division 1 - General Requirements	\$ 75,000	\$ 75,000	\$ -	\$ -	\$ (75,000)	\$ -	\$ (75,000)
Division 2 - Existing Conditions	\$ 2,872,380	\$ 2,970,080	\$ 97,700	\$ 2,759,990	\$ (112,390)	\$ 2,764,490	\$ (107,890)
Division 3 - Concrete	\$ 2,772,478	\$ 32,850	\$ (2,739,628)	\$ 111,548	\$ (2,660,930)	\$ -	\$ (2,772,478)
Division 4 - Masonry	\$ 2,015,845	\$ 2,296,835	\$ 280,990	\$ 2,456,979	\$ 441,134	\$ 1,794,046	\$ (221,799)
Division 5 - Metals	\$ 5,438,115	\$ 873,350	\$ (4,564,765)	\$ 1,830,093	\$ (3,608,022)	\$ 1,765,905	\$ (3,672,210)
Division 6 - Wood, Plastics and Composites	\$ 2,101,375	\$ 2,106,225	\$ 4,850	\$ 1,242,083	\$ (859,292)	\$ 1,080,017	\$ (1,021,358)
Division 7 - Thermal and Moisture Protection	\$ 3,789,139	\$ 3,751,202	\$ (37,937)	\$ 3,927,436	\$ 138,297	\$ 4,342,706	\$ 553,567
Division 8 - Openings	\$ 4,382,132	\$ 4,329,350	\$ (52,782)	\$ 5,373,104	\$ 990,972	\$ 4,171,037	\$ (211,095)
Division 9 - Finishes	\$ 7,991,673	\$ 9,604,268	\$ 1,612,595	\$ 6,538,330	\$ (1,453,343)	\$ 8,319,458	\$ 327,785
Division 10 - Specialties	\$ 1,087,728	\$ 1,158,642	\$ 70,914	\$ 1,371,594	\$ 283,866	\$ 937,405	\$ (150,323)
Division 11 - Equipment	\$ 1,431,329	\$ 1,438,829	\$ 7,500	\$ 1,568,448	\$ 137,119	\$ 1,615,962	\$ 184,633
Division 12 - Furnishings	\$ 668,465	\$ 646,985	\$ (21,480)	\$ 1,138,179	\$ 469,714	\$ 1,785,278	\$ 1,116,813
Division 13 - Special Construction	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -	\$ -
Division 14 - Conveying Equipment	\$ 220,000	\$ 220,000	\$ -	\$ 205,000	\$ (15,000)	\$ 212,000	\$ (8,000)
Division 21 - Fire Suppression	\$ 791,653	\$ 914,839	\$ 123,186	\$ 863,994	\$ 72,341	\$ 853,485	\$ 61,832
Division 22 - Plumbing	\$ 2,195,545	\$ 1,935,182	\$ (260,363)	\$ 2,126,673	\$ (68,872)	\$ 2,148,401	\$ (47,144)
Division 23 - HVAC	\$ 7,967,908	\$ 7,946,076	\$ (21,832)	\$ 7,879,869	\$ (88,039)	\$ 8,281,591	\$ 313,683
Division 26 - Electrical	\$ 5,663,400	\$ 6,291,566	\$ 628,166	\$ 5,986,215	\$ 322,815	\$ 5,947,549	\$ 284,149
Division 31 - Earthwork	\$ -	\$ -	\$ -	\$ 272,455	\$ 272,455	\$ 464,732	\$ 464,732
Division 32 - Exterior Improvements	\$ 1,605,665	\$ 1,468,942	\$ (136,723)	\$ 1,828,819	\$ 223,154	\$ 918,067	\$ (687,598)
Division 33 - Utilities	\$ -	\$ 3,500	\$ 3,500	\$ -	\$ -	\$ 291,650	\$ 291,650
	\$ 53,069,830	\$ 48,063,721	\$ -5,006,109	\$ 47,480,809	\$ -5,589,021	\$ 47,693,779	\$ -5,376,051
<b>Total Trade Cost</b>	<b>\$ 53,069,830</b>	<b>\$ 48,063,721</b>	<b>-\$5,006,109</b>	<b>\$ 47,480,809</b>		<b>\$ 47,693,779</b>	
General Conditions	\$ 3,401,447	\$ 2,931,033	-\$470,414	\$ 2,931,033	-\$470,414	\$ 2,931,033	-\$470,414
General Requirements	\$ 2,652,482	\$ 2,289,380	-\$363,102	\$ 2,289,380	-\$363,102	\$ 2,389,380	-\$263,102
Insurance	\$ 668,571	\$ 576,109	-\$92,462	\$ 576,109	-\$92,462	\$ 576,109	-\$92,462
Bonds	\$ -	\$ -	\$ 0	\$ -	\$ 0	\$ -	\$ 0
Sub Bonds	\$ 742,977	\$ 672,892	-\$70,085	\$ 672,892	-\$70,085	\$ -	-\$742,977
Builders Risk	\$ -	\$ -	\$ 0	\$ -	\$ 0	\$ -	\$ 0
Permit	\$ -	\$ -	\$ 0	\$ -	\$ 0	\$ -	\$ 0
Fee	\$ 1,337,143	\$ 1,152,218	-\$184,925	\$ 1,152,218	-\$184,925	\$ 1,152,218	-\$184,925
Design Contingency	\$ 2,653,491	\$ 1,441,912	3% -\$1,211,579	\$ 1,424,424	3% -\$1,229,067	\$ 953,876	2% -\$1,699,615
GMP Contingency	\$ 1,432,554	\$ 1,266,839	-\$165,715	\$ 1,239,014	-\$193,540	\$ 1,216,191	-\$216,363
Escalation	\$ 835,850	\$ 495,056	1% -\$340,794	\$ 655,330	1% -\$180,520	\$ 498,638	1% -\$337,212
	\$ 13,724,515	\$ 10,825,439	-\$2,899,076	\$ 10,940,400	-\$2,784,115	\$ 9,717,445	-\$4,007,070
Early Site Package	\$ 10,957,843	\$ 10,957,843	\$ 0	\$ 10,957,843	\$ 0	\$ 10,956,907	-\$936
Early Concrete and Steel Package		\$ 8,716,894	\$ 8,716,894	\$ 8,738,800	\$ 8,738,800	\$ 8,738,801	\$ 8,738,801
Buy Savings		\$ (50,755)	-\$50,755	\$ (182,955)			
<b>Total Construction Cost</b>	<b>\$ 77,752,188</b>	<b>\$ 78,513,142</b>	<b>\$ 760,954</b>	<b>\$ 77,934,897</b>	<b>\$ 182,709</b>	<b>\$ 77,106,932</b>	<b>-\$645,256</b>
Post 60% VE **	\$ (487,000)						
<b>Adjusted Cost</b>	<b>\$ 77,265,188</b>	<b>\$ 78,513,142</b>	<b>\$ 1,247,954</b>	<b>\$ 77,934,897</b>	<b>\$ 669,709</b>	<b>\$ 77,106,932</b>	<b>-\$158,256</b>
<b>Construction Cost Budget</b>	<b>\$ 77,935,429</b>	<b>\$ 77,935,429</b>		<b>\$ 77,935,429</b>		<b>\$ 77,935,429</b>	
<b>Delta</b>	<b>\$ (670,241)</b>	<b>\$ 577,713</b>		<b>\$ (532)</b>		<b>\$ (828,497)</b>	

\*\*

Remove the raised traffic table on Flagg Drive – Deduct \$247,000  
 Remove the stepped terraces on the amphitheater – Deduct \$139,000  
 Change the Centralized pH Neutralization System to a point of use system – Deduct \$101,000



# 90% CD Estimate



## **Town of Framingham**

Fuller Middle School

Framingham, MA

September 27, 2019

## **SUBMITTED BY:**

Consigli Construction Co., Inc.

72 Sumner Street

Milford, MA 01757







CONSIGLI  
*Est. 1905*

# TABLE OF CONTENTS

Fuller Middle School



## The Right Choice

Consigli Construction Co., Inc. is a fourth-generation family owned organization that can offer the resources and experience of one of the strongest construction management firms in the Northeast with the creativity and flexibility of a start-up.

1. Uniformat Summary
2. Uniformat Detail
3. CSI Summary
4. CSI Detail
5. General Requirements
6. Assumptions & Qualifications





CONSIGLI  
*Est. 1905*





**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>A Substructure</b>			
<b>A10 Foundations</b>			
A1010 Standard Foundations	136,600 sf	/sf	
A1030 Slab on Grade	136,600 sf	/sf	
<b>A10 Foundations</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>A Substructure</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>B Shell</b>			
<b>B10 Superstructure</b>			
B1010 Floor Construction	136,600 sf	1.55 /sf	211,720
B1020 Roof Construction	136,600 sf	1.39 /sf	190,225
<b>B10 Superstructure</b>	<b>136,600 sf</b>	<b>2.94 /sf</b>	<b>401,945</b>
<b>B20 Exterior Enclosure</b>			
B2010 Exterior Walls	136,600 sf	36.67 /sf	5,008,543
B2020 Exterior Windows	136,600 sf	12.28 /sf	1,676,839
B2030 Exterior Doors	136,600 sf	1.23 /sf	167,968
<b>B20 Exterior Enclosure</b>	<b>136,600 sf</b>	<b>50.17 /sf</b>	<b>6,853,350</b>
<b>B30 Roofing</b>			
B3010 Roof Coverings	136,600 sf	13.55 /sf	1,850,807
B3020 Roof Openings	136,600 sf	5.07 /sf	693,000
<b>B30 Roofing</b>	<b>136,600 sf</b>	<b>18.62 /sf</b>	<b>2,543,807</b>
<b>B Shell</b>	<b>136,600 sf</b>	<b>71.74 /sf</b>	<b>9,799,101</b>
<b>C Interiors</b>			
<b>C10 Interior Construction</b>			
C1010 Partitions	136,600 sf	38.28 /sf	5,229,438
C1020 Interior Doors	136,600 sf	7.17 /sf	979,098
C1030 Specialties/Millwork	136,600 sf	7.07 /sf	966,182
<b>C10 Interior Construction</b>	<b>136,600 sf</b>	<b>52.52 /sf</b>	<b>7,174,718</b>
<b>C20 Stairs</b>			
C2010 Stair Construction	136,600 sf	2.50 /sf	342,000
C2020 Stair Finishes	136,600 sf	0.12 /sf	16,160
<b>C20 Stairs</b>	<b>136,600 sf</b>	<b>2.62 /sf</b>	<b>358,160</b>



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>C30 Interior Finishes</b>			
C3010 Wall Finishes	136,600 sf	11.33 /sf	1,547,373
C3020 Floor Finishes	136,600 sf	10.15 /sf	1,387,030
C3030 Ceiling Finishes	136,600 sf	17.78 /sf	2,428,588
<b>C30 Interior Finishes</b>	<b>136,600 sf</b>	<b>39.26 /sf</b>	<b>5,362,991</b>
<b>C Interiors</b>	<b>136,600 sf</b>	<b>94.41 /sf</b>	<b>12,895,869</b>
<b>D Services</b>			
<b>D10 Conveying Systems</b>			
D1010 Elevators & Lifts	136,600 sf	1.61 /sf	220,450
<b>D10 Conveying Systems</b>	<b>136,600 sf</b>	<b>1.61 /sf</b>	<b>220,450</b>
<b>D20 Plumbing</b>			
D2010 Plumbing	136,600 sf	3.05 /sf	416,156
D2020 Domestic Water Distribution	136,600 sf	3.96 /sf	540,525
D2030 Sanitary Waste	136,600 sf	2.51 /sf	343,448
D2040 Rain Water Drainage	136,600 sf	1.62 /sf	221,676
D2090 Other Plumbing Systems	136,600 sf	3.48 /sf	475,103
<b>D20 Plumbing</b>	<b>136,600 sf</b>	<b>14.62 /sf</b>	<b>1,996,907</b>
<b>D30 Heating, Ventilating, and Air Conditioning (HVAC)</b>			
D3010 Energy Supply	136,600 sf	9.29 /sf	1,268,916
D3020 HVAC	136,600 sf	1.20 /sf	163,945
D3030 Cooling Generating Systems	136,600 sf	2.85 /sf	389,905
D3040 HVAC Distribution	136,600 sf	17.06 /sf	2,329,778
D3050 Terminal & Package Units	136,600 sf	17.52 /sf	2,393,325
D3060 HVAC Instrumentation & Controls	136,600 sf	5.49 /sf	749,864
D3070 Testing, Adjusting & Balancing	136,600 sf	0.65 /sf	88,790
D3090 Other HVAC Systems & Equipment	136,600 sf	3.66 /sf	499,829
<b>D30 Heating, Ventilating, and Air Conditioning (HVAC)</b>	<b>136,600 sf</b>	<b>57.72 /sf</b>	<b>7,884,351</b>
<b>D40 Fire Protection Systems</b>			
D4010 Sprinklers	136,600 sf	6.32 /sf	863,266
D4020 Standpipes	136,600 sf	0.17 /sf	22,839
D4030 Fire Protection Specialties	136,600 sf	0.08 /sf	10,734
D4090 Other Fire Protection Systems	136,600 sf	0.13 /sf	18,000



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D40 Fire Protection Systems</b>	136,600 sf	6.70 /sf	914,839
<b>D50 Electrical Systems</b>			
D5010 Gear & Distribution	136,600 sf	8.18 /sf	1,117,861
D5020 Lighting & Branch Wiring	136,600 sf	17.61 /sf	2,405,966
D5030 Communications & Security	136,600 sf	12.09 /sf	1,652,074
D5090 Other Electrical Systems	136,600 sf	3.95 /sf	538,839
<b>D50 Electrical Systems</b>	136,600 sf	41.84 /sf	5,714,740
<b>D Services</b>	136,600 sf	122.48 /sf	16,731,287
<b>E Equipment &amp; Furnishings</b>			
<b>E10 Equipment</b>			
E1020 Institutional Equipment	136,600 sf	12.13 /sf	1,656,689
E1090 Other Equipment	136,600 sf	0.18 /sf	24,600
<b>E10 Equipment</b>	136,600 sf	12.31 /sf	1,681,288
<b>E20 Furnishings</b>			
E2010 Fixed Furnishings	136,600 sf	12.84 /sf	1,754,375
<b>E20 Furnishings</b>	136,600 sf	12.84 /sf	1,754,375
<b>E Equipment &amp; Furnishings</b>	136,600 sf	25.15 /sf	3,435,664
<b>F Special Construction &amp; Demolition</b>			
<b>F20 Demolition</b>			
F2010 Building Elements Demolition	194,500 sf	7.03 /sf	1,367,800
F2020 Hazardous Component Abatement	194,500 sf	8.24 /sf	1,602,280
<b>F20 Demolition</b>	194,500 sf	15.27 /sf	2,970,080
<b>F Special Construction &amp; Demolition</b>	194,500 sf	15.27 /sf	2,970,080
<b>G Sitework</b>			
<b>G10 Site Preparation</b>			
G1010 Site Clearing	136,600 sf	/sf	
G1020 Site Demolition & Relocations	136,600 sf	0.07 /sf	9,000
G1030 Site Earthwork	136,600 sf	3.01 /sf	410,790
<b>G10 Site Preparation</b>	136,600 sf	3.07 /sf	419,790
<b>G20 Site Improvements</b>			



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
G2010 Roadways	136,600 sf	/sf	
G2020 Parking Lots	136,600 sf	/sf	
G2030 Pedestrian Paving	136,600 sf	0.05 /sf	7,140
G2040 Site Development	136,600 sf	2.97 /sf	405,650
G2050 Landscaping	136,600 sf	6.02 /sf	822,312
<b>G20 Site Improvements</b>	<b>136,600 sf</b>	<b>9.04 /sf</b>	<b>1,235,102</b>
<b>G30 Site Civil/Mechanical Utilites</b>			
G3010 Water Supply	136,600 sf	/sf	
G3020 Sanitary Sewer	136,600 sf	/sf	
G3030 Storm Drainage	136,600 sf	/sf	
G3060 Fuel Distribution	136,600 sf	/sf	
<b>G30 Site Civil/Mechanical Utilites</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>G40 Site Electrical Utilities</b>			
G4010 Electrical Distribution	136,600 sf	1.22 /sf	166,498
G4020 Site Lighting	136,600 sf	2.57 /sf	350,530
G4030 Site Communications & Security	136,600 sf	0.44 /sf	59,799
<b>G40 Site Electrical Utilities</b>	<b>136,600 sf</b>	<b>4.22 /sf</b>	<b>576,826</b>
<b>G Sitework</b>	<b>136,600 sf</b>	<b>16.34 /sf</b>	<b>2,231,718</b>





90% CD Estimate

Estimate Totals

Description	Amount	Totals	Rate	Cost per Unit
Subtotal	<b>48,063,718</b>	<b>48,063,718</b>		<b>351.86 /sf</b>
Design/Estimate Contingency	1,441,912		3.000 %	10.56 /sf
Escalation	495,056		1.000 %	3.62 /sf
<b>Subtotal</b>	<b>1,936,968</b>	<b>50,000,686</b>		<b>366.04 /sf</b>
SDI (Non-Trade Contracts)	269,858		1.400 %	1.98 /sf
Sub Bonds (Trade Contracts)	403,034		1.400 %	2.95 /sf
Contractor's Contingency	1,266,839		2.500 %	9.27 /sf
General Conditions	2,931,033			21.46 /sf
General Requirements	2,289,380			16.76 /sf
<b>Subtotal</b>	<b>7,160,144</b>	<b>57,160,830</b>		<b>418.45 /sf</b>
Builder's Risk Insurance - BP1				
General Liability Insurance	576,109			4.22 /sf
Building Permit - NIC				
Performance & Payment Bond				
<b>Subtotal</b>	<b>576,109</b>	<b>57,736,939</b>		<b>422.67 /sf</b>
Fee	1,152,218			8.43 /sf
Amendment #1 - Sitework	10,957,843			80.22 /sf
Amendment #2 - Concrete & Steel	8,716,894			63.81 /sf
Amendment #2 - Buy Savings	(50,755)			(0.37) /sf
<b>Total</b>		<b>78,513,139</b>		<b>574.77 /sf</b>





CONSIGLI  
*Est. 1905*





Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>A Substructure</b>			
<b>A10 Foundations</b>			
<b>A1010 Standard Foundations</b>			
Lull, laborer for cleanup by Consigli (Concrete)	(1) ls	116,000.00 /ls	(116,000)
Trade support - lull, laborer for cleanup (Concrete)	1 ls	116,000.00 /ls	116,000
<i>Elevator pit</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>F3 spread footings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>F4 spread footings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>F5 spread footings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>F6 spread footings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>F7 spread footings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>F8 spread footings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>F9 spread footings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>F10 spread footings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>F11 spread footings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>F12 spread footings</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Continuous footings - 3'x12"</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Continuous footings - 4'x12"</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Continuous footings - 5'x12" @ Bandshell</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Foundation walls - 16"</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Foundation walls - 16" @ Bandshell</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Foundation walls - 21"</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Retaining walls - 16"</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Concrete walls @ Auditorium</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Piers - 24"x24"</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Grade beam 1</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Grade beam 2</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Foundation wall insulation</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Dampproofing at foundation wall</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Foundation wall waterproofing - membrane w/ drainage board</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Elevator pit waterproofing - cementitious</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Site cuts to site fills</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Excavation @ foundations</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Fill to subgrade @ building footprint - import (structural fill)</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Crushed stone base beneath column &amp; wall footings</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Excavate for elevator pits</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Dewatering</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Additional dewatering</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Site surcharge/rigid inclusion</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Rammed aggregate piers</i>	<i>BP#1</i>	<i>/BP#1</i>	
<i>Rigid inclusions Gym and Auditorium</i>	<i>BP#1</i>	<i>/BP#1</i>	



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
A1010 Standard Foundations	136,600 sf	/sf	
<b>A1030 Slab on Grade</b>			
Slab depressions	BP#2	/BP#2	
Slab on grade - 5"	BP#2	/BP#2	
Power trowel/seal concrete @ Auditorium	BP#2	/BP#2	
Underslab insulation (perimeter only)	BP#2	/BP#2	
Crushed stone base beneath S.O.G	BP#1	/BP#1	
Fine grade under building	BP#1	/BP#1	
Excavate/backfill utilities under SOG by machine	BP#1	/BP#1	
A1030 Slab on Grade	136,600 sf	/sf	
<b>A10 Foundations</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>A Substructure</b>	<b>136,600 sf</b>	<b>/sf</b>	

**B Shell**

**B10 Superstructure**

**B1010 Floor Construction**

Place & finish slabs - 3-1/4" on 3" deck @ floor (LW)	BP#2	/BP#2	
Topping slab @ Breakout LGMF floors	BP#2	/BP#2	
Moment connections @ floor	BP#2	/BP#2	
Steel @ floors	BP#2	/BP#2	
Steel hangers - AESS	BP#2	/BP#2	
Steel @ floors - VM-S05	BP#2	/BP#2	
Steel @ Canopy - AESS	BP#2	/BP#2	
Relieving angles @ brick veneer	BP#2	/BP#2	
Shoring @ Learning Commons	BP#2	/BP#2	
Metal floor decking - galvanized (3" 18g)	BP#2	/BP#2	
Metal floor decking @ Breakout room LGMF floors	BP#2	/BP#2	
Sprayed fireproofing - steel beams and columns @ floor structure	64,740 sf	3.00 /sf	194,220
Patch Sprayed fireproofing - floor structure	5 days	3,500.00 /days	17,500
<b>B1010 Floor Construction</b>	<b>136,600 sf</b>	<b>1.55 /sf</b>	<b>211,720</b>

**B1020 Roof Construction**

Place & finish slabs - 2-1/2" on 3" deck @ roof	BP#2	/BP#2	
Place & finish slabs - 3-1/4" on 3" deck @ roof	BP#2	/BP#2	
Moment connections @ roof	BP#2	/BP#2	
Steel @ screen wall - galvanized	BP#2	/BP#2	
Steel @ roof	BP#2	/BP#2	
Steel dunnage - RTU & chiller	BP#2	/BP#2	
Open web joists, bridging	BP#2	/BP#2	
Metal roof decking - acoustical (3" 18/16g)	BP#2	/BP#2	



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>B1020 Roof Construction</b>			
Metal roof decking - galvanized (1-1/2" 20g)	BP#2	/BP#2	
Metal roof decking - acoustical (1-1/2" 20g)	BP#2	/BP#2	
Metal roof decking - galvanized (3" 18g)	BP#2	/BP#2	
Sprayed fireproofing - steel beams and columns @ roof structure below 20'	33,575 sf	3.00 /sf	100,725
Patch Sprayed fireproofing - roof structure	5 days	3,500.00 /days	17,500
Intumescent fireproofing @ Learning Commons	1 ls	72,000.00 /ls	72,000
<i>B1020 Roof Construction</i>	<b>136,600 sf</b>	<b>1.39 /sf</b>	<b>190,225</b>
<b>B10 Superstructure</b>	<b>136,600 sf</b>	<b>2.94 /sf</b>	<b>401,945</b>
<b>B20 Exterior Enclosure</b>			
<b>B2010 Exterior Walls</b>			
Exterior wall mockup - Masonry, Allowance	1 allw	7,500.00 /allw	7,500
Exterior wall mockup - Steel, Allowance	BP#2	/BP#2	
Exterior wall mockup - Siding, Allowance	1 allw	10,000.00 /allw	10,000
Exterior wall mockup - Waterproofing, Allowance	1 allw	5,000.00 /allw	5,000
Exterior wall mockup - Roofing, Allowance	1 allw	2,500.00 /allw	2,500
Exterior wall mockup - Drywall, Allowance	1 allw	10,000.00 /allw	10,000
Temporary bracing of CMU @ Gym and Auditorium	1 ls	100,000.00 /ls	100,000
Exterior staging	40,145 sf	2.50 /sf	100,363
Masonry winter conditions/heat	12 wks	5,000.00 /wks	60,000
Lull, laborer for cleanup by Consigli (Masonry)	(1) ls	77,000.00 /ls	(77,000)
Lull, laborer for cleanup by Consigli (Waterproofing)	(1) ls	29,000.00 /ls	(29,000)
Lull, laborer for cleanup by Consigli (Siding)	(1) ls	48,000.00 /ls	(48,000)
Trade support - lull, laborer for cleanup (Masonry)	1 ls	77,000.00 /ls	77,000
Trade support - lull, laborer for cleanup (Waterproofing)	1 ls	29,000.00 /ls	29,000
Trade support - lull, laborer for cleanup (Siding)	1 ls	48,000.00 /ls	48,000
Precast planters	25 lf	750.00 /lf	18,750
Install loose lintels (< 8")	14 ea	150.00 /ea	2,100
4x4x12 iron spot brick veneer, scored	6,815 sf	36.00 /sf	245,340
4x8x8 iron spot brick veneer, scored	6,750 sf	36.00 /sf	243,000
Brick veneer, precast cap @ entry wall per A102A	25 lf	285.00 /lf	7,125
4x4x12 scored ground faced CMU veneer	2,970 sf	27.00 /sf	80,190
4x8x16 scored ground faced CMU veneer	23,615 sf	29.00 /sf	684,835
CMU - 12" exterior wall	15,795 sf	25.00 /sf	394,875
Loose lintels - Furnish	95 lf	25.00 /lf	2,375
Guardrails - 42" galvanized perforated @ exterior	105 lf	500.00 /lf	52,500
Guardrails - 42" galvanized perforated @ terrace	30 lf	500.00 /lf	15,000
Misc. caulking & sealants @ exterior	73,210 sf	0.75 /sf	54,908
Mineral wool insulation at brick/CMU veneer	40,145 sf	3.50 /sf	140,508



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>B2010 Exterior Walls</b>			
Air and vapor barrier @ exterior walls	56,650 sf	7.50 /sf	424,875
Air and vapor barrier @ soffits	1,245 sf	7.50 /sf	9,338
Air and vapor barrier @ phenolic fins per A102A, A315	380 sf	7.50 /sf	2,850
Corrugated, perforated metal siding @ screen walls	1,105 sf	45.00 /sf	49,725
Exposed fastener metal panel	6,065 sf	45.00 /sf	272,925
Composite metal panel siding	3,120 sf	75.00 /sf	234,000
Phenolic panel siding	7,705 sf	80.00 /sf	616,400
Metal louver	625 sf	85.00 /sf	53,125
Exterior walls - 10" studs, 1/2" sheathing, 5/8" GWB, insulation	44,220 sf	23.50 /sf	1,039,170
Framing @ phenolic fins per A102A, A315	380 sf	7.65 /sf	2,907
Exterior soffit framing, sheathing, insulation	1,245 sf	23.90 /sf	29,756
Misc. exterior painting	73,210 sf	0.50 /sf	36,605
<i>B2010 Exterior Walls</i>	<b>136,600 sf</b>	<b>36.67 /sf</b>	<b>5,008,543</b>
<b>B2020 Exterior Windows</b>			
Exterior wall mockup - Windows, Allowance	1 allw	20,000.00 /allw	20,000
Lull, laborer for cleanup by Consigli (Windows)	(1) ls	73,000.00 /ls	(73,000)
Trade support - lull, laborer for cleanup (Windows)	1 ls	73,000.00 /ls	73,000
Window blocking	7,425 lf	12.75 /lf	94,669
Door blocking - exterior	265 lf	13.85 /lf	3,671
Caulking @ storefront/curtainwall	7,425 lf	4.00 /lf	29,700
Window transitions	7,425 lf	10.00 /lf	74,250
Aluminum storefront/windows	11,555 sf	100.00 /sf	1,155,500
Aluminum storefront - School Guard	545 sf	140.00 /sf	76,300
Extruded aluminum perimeter angles	7,425 lf	30.00 /lf	222,750
<i>B2020 Exterior Windows</i>	<b>136,600 sf</b>	<b>12.28 /sf</b>	<b>1,676,839</b>
<b>B2030 Exterior Doors</b>			
Install exterior door, HW	14 ea	300.00 /ea	4,200
HM doors - exterior flush	23 lvs	625.00 /lvs	14,375
HM frames - exterior single	5 ea	255.00 /ea	1,275
HM frames - exterior double	9 ea	440.00 /ea	3,960
Overhead coiling door	1 ea	7,500.00 /ea	7,500
Aluminum entrance doors, HW - exterior	4 lvs	6,000.00 /lvs	24,000
Aluminum entrance doors, HW - exterior, School Guard	11 lvs	7,000.00 /lvs	77,000
Hardware sets - exterior door/panic	14 set	1,920.01 /set	26,880
Hardware sets - auto operators	1 set	4,500.00 /set	4,500
Install HM door frames - exterior single	5 ea	73.00 /ea	365
Install HM door frames - exterior double	9 ea	117.00 /ea	1,053
Paint HM doors - exterior	23 lvs	90.00 /lvs	2,070
Paint HM frames - exterior, single	5 ea	50.00 /ea	250





**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>B2030 Exterior Doors</b>			
Paint HM frames - exterior, double	9 ea	60.00 /ea	540
<i>B2030 Exterior Doors</i>	<u>136,600 sf</u>	<u>1.23 /sf</u>	<u>167,968</u>
<b>B20 Exterior Enclosure</b>	<b>136,600 sf</b>	<b>50.17 /sf</b>	<b>6,853,350</b>
<b>B30 Roofing</b>			
<b>B3010 Roof Coverings</b>			
Roof blocking	10,780 lf	32.00 /lf	344,960
PVC membrane roof w/insulation, underlayment, cover board, vapor barrier	63,155 sf	18.25 /sf	1,152,579
PVC membrane @ walls	2,740 sf	20.25 /sf	55,485
Reinforced walkway pads	715 sf	7.50 /sf	5,363
Pavers - terrace	295 sf	35.00 /sf	10,325
Pavers - main entrance	780 sf	35.00 /sf	27,300
Roof accessories	63,155 sf	0.35 /sf	22,104
Roof vents & hatches	1 ls	25,000.00 /ls	25,000
Metal roof fascia	2,695 lf	35.00 /lf	94,325
Additional flashing, scuppers	63,155 sf	0.75 /sf	47,366
Polycarbonate glazing @ canopy	440 sf	150.00 /sf	66,000
<i>B3010 Roof Coverings</i>	<u>136,600 sf</u>	<u>13.55 /sf</u>	<u>1,850,807</u>
<b>B3020 Roof Openings</b>			
Metal-framed skylights (8:12)	4,130 sf	150.00 /sf	619,500
Metal-framed skylights gable ends	490 sf	150.00 /sf	73,500
<i>B3020 Roof Openings</i>	<u>136,600 sf</u>	<u>5.07 /sf</u>	<u>693,000</u>
<b>B30 Roofing</b>	<b>136,600 sf</b>	<b>18.62 /sf</b>	<b>2,543,807</b>
<b>B Shell</b>	<b>136,600 sf</b>	<b>71.74 /sf</b>	<b>9,799,101</b>
<b>C Interiors</b>			
<b>C10 Interior Construction</b>			
<b>C1010 Partitions</b>			
Lull, laborer for cleanup by Consigli (Drywall)	(1) ls	188,000.00 /ls	(188,000)
Trade support - lull, laborer for cleanup (Drywall)	1 ls	188,000.00 /ls	188,000
CMU - 12" interior wall	6,890 sf	25.00 /sf	172,250
CMU - ground face block, premium	1 ls	35,000.00 /ls	35,000
CMU - acoustical block, premium	1 ls	5,000.00 /ls	5,000
Light gage metal framing @ Breakout floors	1,440 sf	60.00 /sf	86,400
Light gage metal framing @ Breakout walls	16,820 sf	25.00 /sf	420,500
Misc. metal fabrications	136,600 sf	1.00 /sf	136,600
Seismic clips - 4' OC, each side	270 ea	60.00 /ea	16,200
<i>Steel angles/stantions @ locker guardrail</i>	<i>BP#2</i>	<i>/BP#2</i>	



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>C1010 Partitions</b>			
Handrail @ steps/ramps	55 lf	295.00 /lf	16,225
Cane rails	120 lf	200.00 /lf	24,000
In-wall blocking	12,160 lf	12.75 /lf	155,040
Miscellaneous rough carpentry - Allowance	136,600 sf	0.65 /sf	88,790
Caulking & sealants @ interior	136,600 sf	0.90 /sf	122,940
Firestopping @ rated walls	5,630 lf	16.20 /lf	91,206
Miscellaneous firestopping	136,600 sf	0.10 /sf	13,660
Aluminum storefront - interior, School Guard	340 sf	140.00 /sf	47,600
Aluminum windows - interior, School Guard	2 ea	12,000.00 /ea	24,000
Misc. interior glass & glazing	136,600 sf	0.25 /sf	34,150
Glazed partition	4,700 sf	60.00 /sf	282,000
Glazed partition - double acoustic	625 sf	110.00 /sf	68,750
Glazed partition @ sidelights	1,165 sf	75.00 /sf	87,375
Glass walls @ Breakout	2,005 sf	120.00 /sf	240,600
Glass roof @ Breakout	70 sf	150.00 /sf	10,500
Graduated glass film	3,675 sf	5.00 /sf	18,375
3M Safety and Security Window Film @ glass walls	4,090 sf	15.00 /sf	61,350
3M Safety and Security Window Film @ doors	67 lvs	450.00 /lvs	30,150
Level 5 finish - Allowance	25,000 sf	2.55 /sf	63,750
Interior wall framing - 2-1/2"	3,370 sf	5.75 /sf	19,378
Interior wall framing - 3-5/8"/4"	96,355 sf	5.75 /sf	554,041
Interior wall framing - 6"	7,050 sf	7.65 /sf	53,933
Interior wall framing - 8"	21,965 sf	10.15 /sf	222,945
Interior wall framing - 10"	555 sf	12.10 /sf	6,716
GWB - 5/8", level 4	229,230 sf	4.15 /sf	951,305
GWB - 5/8", additional layer	96,320 sf	3.50 /sf	336,627
GWB - high impact	1 ls	50,000.00 /ls	50,000
Shaft liner - 1"	2,420 sf	4.15 /sf	10,043
Sound batt insulation	137,275 sf	1.60 /sf	219,640
Half height walls @ Auditorium	400 sf	22.90 /sf	9,160
LGMF framing @ locker guardrail	4,095 sf	5.10 /sf	20,885
GWB - 5/8", level 5 @ locker guardrail	4,095 sf	6.70 /sf	27,437
Curved walls - premium	5,205 sf	6.35 /sf	33,074
Patch GWB	136,600 sf	0.50 /sf	68,300
Operable partitions w/writeable surface on one side	325 sf	77.00 /sf	25,025
Operable partitions w/writeable surface on both sides	2,740 sf	98.00 /sf	268,520
<b>C1010 Partitions</b>	<b>136,600 sf</b>	<b>38.28 /sf</b>	<b>5,229,438</b>

**C1020 Interior Doors**

Door blocking - interior	4,965 lf	13.85 /lf	68,772
--------------------------	----------	-----------	--------



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>C1020 Interior Doors</b>			
Install interior door, HW	300 ea	300.00 /ea	90,000
HM doors - interior - flush	45 lvs	310.00 /lvs	13,950
HM frames - interior single	258 ea	310.00 /ea	79,980
HM frames - interior single, tandem	13 ea	360.00 /ea	4,680
HM frames - interior double	29 ea	385.00 /ea	11,165
Wood door - interior flush	297 lvs	390.00 /lvs	115,830
Fire rated wood doors - premium	44 lvs	390.00 /lvs	17,160
Acoustical doors (STC 45) - premium	1 ls	15,000.00 /ls	15,000
Access panels	1 ls	15,000.00 /ls	15,000
Coiling security screen - 4' high, manual	85 sf	70.00 /sf	5,950
Coiling security screen - 8' high, manual	690 sf	70.00 /sf	48,300
Custom security gate @ Learning Commons	2 lvs	6,000.00 /lvs	12,000
Aluminum entrance doors, HW - interior	1 lvs	6,000.00 /lvs	6,000
Aluminum entrance doors, HW - interior, School Guard	8 lvs	7,000.00 /lvs	56,000
Hardware sets - standard interior	287 set	1,015.00 /set	291,305
Hardware sets - interior, tandem	13 set	1,330.00 /set	17,290
Automatic operators	1 pair	4,400.00 /pair	4,400
Door glazing - full	159 ea	400.00 /ea	63,600
Door glazing - narrow	2 ea	100.00 /ea	200
Install HM door frames - interior single	271 ea	73.00 /ea	19,783
Install HM door frames - interior double	29 ea	117.00 /ea	3,393
Paint HM doors - interior	45 lvs	90.00 /lvs	4,050
Paint HM frames - interior, single	271 ea	50.00 /ea	13,550
Paint HM frames - interior, double	29 ea	60.00 /ea	1,740
<i>C1020 Interior Doors</i>	<b>136,600 sf</b>	<b>7.17 /sf</b>	<b>979,098</b>
<b>C1030 Specialties/Millwork</b>			
Guardrails @ Atrium	380 lf	500.00 /lf	190,000
Window sills - P-lam	1,100 lf	25.00 /lf	27,500
Wood louvered shades - Rulon panel grille	450 lf	150.00 /lf	67,500
Mirrors - unframed restroom	1,145 sf	35.00 /sf	40,075
Interior signage	136,600 sf	0.35 /sf	47,810
Toilet partition	23 ea	1,020.00 /ea	23,460
Toilet partition - handicap	16 ea	1,650.00 /ea	26,400
Urinal screens - wall-hung	15 ea	433.00 /ea	6,495
Cubicle curtains	45 lf	40.00 /lf	1,800
Cubicle curtain track	45 lf	11.50 /lf	518
Corner guards	1 ls	20,000.00 /ls	20,000
Toilet paper dispenser	54 ea	105.17 /ea	5,679
Grab bar	62 ea	141.38 /ea	8,765



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>C1030 Specialties/Millwork</b>			
Soap dispenser - surface mounted	59 ea	87.64 /ea	5,171
Paper towel dispenser - recessed	32 ea	136.79 /ea	4,377
Framed mirrors	15 ea	171.00 /ea	2,565
Sanitary napkin disposal	46 ea	274.00 /ea	12,604
Shower curtains, hooks & rod	3 ea	125.00 /ea	375
Shower seat	2 ea	668.00 /ea	1,336
Mop rack	3 ea	230.67 /ea	692
Fire extinguisher cabinet - fully recessed	27 ea	350.00 /ea	9,450
Student lockers - phenolic	660 ea	600.00 /ea	396,000
Athletic lockers	80 ea	350.00 /ea	28,000
Staff lockers	12 ea	400.00 /ea	4,800
Locker benches	12 lf	55.00 /lf	660
Misc. specialties - Allowance	136,600 sf	0.25 /sf	34,150
<i>C1030 Specialties/Millwork</i>	<b>136,600 sf</b>	<b>7.07 /sf</b>	<b>966,182</b>
<b>C10 Interior Construction</b>	<b>136,600 sf</b>	<b>52.52 /sf</b>	<b>7,174,718</b>

**C20 Stairs**

**C2010 Stair Construction**

<i>Place &amp; finish stair treads/landings</i>	<i>BP#2</i>	<i>/BP#2</i>	
Ornamental stairs 3 and 6 - excluding rails	2 flt	60,000.00 /flt	120,000
Egress stair	5 flt	20,000.00 /flt	100,000
<i>Ornamental stairs 4 and 5 - excluding rails</i>	<i>BP#2</i>	<i>/BP#2</i>	
Roof ladders	3 ea	1,500.00 /ea	4,500
Guardrails @ Atrium stairs	235 lf	500.00 /lf	117,500
<i>C2010 Stair Construction</i>	<b>136,600 sf</b>	<b>2.50 /sf</b>	<b>342,000</b>

**C2020 Stair Finishes**

Rubber flooring @ ornamental stairs	770 sf	8.00 /sf	6,160
Paint egress stairs	5 flt	2,000.00 /flt	10,000
<i>C2020 Stair Finishes</i>	<b>136,600 sf</b>	<b>0.12 /sf</b>	<b>16,160</b>

**C20 Stairs** **136,600 sf** **2.62 /sf** **358,160**

**C30 Interior Finishes**

**C3010 Wall Finishes**

Lull, laborer for cleanup by Consigli (Tile)	(1) ls	7,000.00 /ls	(7,000)
Trade support - lull, laborer for cleanup (Tile)	1 ls	7,000.00 /ls	7,000
<i>Brick veneer - interior - N/A</i>	-	/-	
Miscellaneous wood base/trim	136,600 sf	0.50 /sf	68,300
Trim @ Breakout D glass lights	320 sf	25.00 /sf	8,000
P-lam panel	1,440 sf	45.00 /sf	64,800



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>C3010 Wall Finishes</b>			
P-lam panel backsplash	120 sf	45.00 /sf	5,400
Marker tray - bamboo	2,485 lf	30.00 /lf	74,550
MDF bumper rail	3,715 lf	25.00 /lf	92,875
P-lam wall panels - sound reflecting @ Auditorium	2,925 sf	45.00 /sf	131,625
P-lam wall panels - vestibules	400 sf	45.00 /sf	18,000
P-lam projector enclosure @ Auditorium	1 ea	2,500.00 /ea	2,500
Ceramic wall tile	2,295 sf	18.00 /sf	41,310
Quarry tile base	280 lf	20.00 /lf	5,600
Linoleum tile base w/trim	19,260 lf	9.00 /lf	173,340
Rubber base	2,175 lf	3.50 /lf	7,613
Vented base @ Gym	370 lf	8.00 /lf	2,960
Fiberglass reinforced panels (FRP) - wall panels	2,240 sf	8.00 /sf	17,920
Fabric wrapped acoustical panels	12,275 sf	20.00 /sf	245,500
Tectum wall panels	5,535 sf	18.00 /sf	99,630
Mural panorama wall covering	1,485 sf	1.50 /sf	2,228
Paint GWB partitions	227,710 sf	0.80 /sf	182,168
Paint CMU - N/A	-	/-	
Epoxy wall paint	15,550 sf	2.30 /sf	35,765
Touchup	136,600 sf	0.50 /sf	68,300
Magnetic writeable wall covering	9,045 sf	22.00 /sf	198,990
<b>C3010 Wall Finishes</b>	<b>136,600 sf</b>	<b>11.33 /sf</b>	<b>1,547,373</b>
<b>C3020 Floor Finishes</b>			
Lull, laborer for cleanup by Consigli (Resilient)	(1) ls	48,000.00 /ls	(48,000)
Trade support - lull, laborer for cleanup (Resilient)	1 ls	48,000.00 /ls	48,000
Polished concrete @ Auditorium	3,650 sf	9.00 /sf	32,850
Wood base	100 lf	25.00 /lf	2,500
Porcelain floor tile	5,475 sf	25.00 /sf	136,875
Quarry floor tile	1,770 sf	20.00 /sf	35,400
Underlayment at 2nd and 3rd floor linoleum - Forbo NR99, exclude corridors	62,015 sf	4.00 /sf	248,060
Moisture mitigation - Excluded	-	/-	
Hardwood stage assembly	1,610 sf	25.00 /sf	40,250
Wood athletic flooring	8,570 sf	20.00 /sf	171,400
Linoleum tile	100,135 sf	6.00 /sf	600,810
Epoxy flooring/base	5,780 sf	14.00 /sf	80,920
Carpet @ Auditorium	135 sy	45.00 /sy	6,075
Seal concrete floor	7,245 sf	2.00 /sf	14,490
Entry mats - recessed	435 sf	40.00 /sf	17,400
<b>C3020 Floor Finishes</b>	<b>136,600 sf</b>	<b>10.15 /sf</b>	<b>1,387,030</b>



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>C3030 Ceiling Finishes</b>			
Dance floor at auditorium - multi-trade	1 ls	75,000.00 /ls	75,000
Lull, laborer for cleanup by Consigli (Finish Carpentry)	(1) ls	72,000.00 /ls	(72,000)
Lull, laborer for cleanup by Consigli (Ceilings)	(1) ls	49,000.00 /ls	(49,000)
Trade support - lull, laborer for cleanup (Finish Carpentry)	1 ls	72,000.00 /ls	72,000
Trade support - lull, laborer for cleanup (Ceilings)	1 ls	49,000.00 /ls	49,000
P-lam panel on Z-clips @ Breakout	325 sf	45.00 /sf	14,625
Suspended P-lam clouds @ Auditorium	100 ea	2,000.00 /ea	200,000
Gypsum board ceilings	21,010 sf	15.25 /sf	320,411
Gypsum board ceilings - 1 hr	655 sf	19.10 /sf	12,511
Gypsum board ceilings - 2 hr	80 sf	22.90 /sf	1,832
Gypsum board ceilings - resilient	5,350 sf	31.75 /sf	169,863
Stucco soffit	1,245 sf	11.35 /sf	14,131
Gypsum board soffits	28,335 sf	25.45 /sf	721,126
Gypsum board soffits @ Learning Commons	4,920 sf	25.45 /sf	125,214
Gypsum board soffits @ Skylights	1,915 sf	25.45 /sf	48,737
A1 - Armstrong Ultima #1911, random running bond pattern	21,400 sf	9.00 /sf	192,600
A1 - Armstrong Ultima #1911 @ Learning Commons corridors	9,980 sf	9.00 /sf	89,820
A2 - Armstrong Calla #2824	20,985 sf	8.00 /sf	167,880
A3 - USG Geometrix 3 Dimensional	3,815 sf	35.00 /sf	133,525
A4 - Armstrong Healthzone Ultima	1,760 sf	7.00 /sf	12,320
Paint GWB ceilings	21,735 sf	1.00 /sf	21,735
Paint GWB soffits	35,170 sf	1.00 /sf	35,170
Paint exposed ceilings	24,085 sf	1.50 /sf	36,128
Paint exposed ceilings @ Gym and Auditorium	14,385 sf	2.50 /sf	35,963
<i>C3030 Ceiling Finishes</i>	<b>136,600 sf</b>	<b>17.78 /sf</b>	<b>2,428,588</b>
<b>C30 Interior Finishes</b>	<b>136,600 sf</b>	<b>39.26 /sf</b>	<b>5,362,991</b>
<b>C Interiors</b>	<b>136,600 sf</b>	<b>94.41 /sf</b>	<b>12,895,869</b>

**D Services**

**D10 Conveying Systems**

**D1010 Elevators & Lifts**

Elevator pit ladders	1 ea	450.00 /ea	450
Passenger elevators - cab, equipment	1 ls	40,000.00 /ls	40,000
Passenger elevators - stops	4 stop	45,000.00 /stop	180,000
<i>D1010 Elevators &amp; Lifts</i>	<b>136,600 sf</b>	<b>1.61 /sf</b>	<b>220,450</b>

<b>D10 Conveying Systems</b>	<b>136,600 sf</b>	<b>1.61 /sf</b>	<b>220,450</b>
------------------------------	-------------------	-----------------	----------------

**D20 Plumbing**

**D2010 Plumbing**



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D2010 Plumbing</b>			
Lull, laborer for cleanup by Consigli (Plumbing)	(1) ls	83,000.00 /ls	(83,000)
Trade support - lull, laborer for cleanup (Plumbing)	1 ls	83,000.00 /ls	83,000
Water closet/wall mnt./carrier/flush valve	22 ea	1,330.12 /ea	29,263
Water closet/wall mnt./carrier/flush valve/ADA	32 ea	1,367.52 /ea	43,761
Urinal/wall mnt./carrier/flush valve	18 ea	1,202.85 /ea	21,651
Urinal/wall mnt./carrier/flush valve/ADA	5 ea	1,241.35 /ea	6,207
Lavatory/undermount/std 1-lever faucet	54 ea	523.24 /ea	28,255
Lavatory/undermount/std 1-lever faucet/ADA	10 ea	586.41 /ea	5,864
Lavatory/wall hung/std 1-lever faucet/carrier/ADA	15 ea	1,147.55 /ea	17,213
Mixing valve/single lav. (Leonard #170)	85 ea	348.84 /ea	29,651
P15 Sink/lay-in/1-bowl 20"x22"/std faucet/ADA	2 ea	1,560.75 /ea	3,121
P14 Sink/lay-in/1-bowl 20"x22"/std faucet/ADA Maker Space	2 ea	1,610.75 /ea	3,221
P7 Sink/lay-in/1-bowl 21"x15"/std faucet	36 ea	1,584.98 /ea	57,059
P9 Sink/lay-in/1-bowl 21"x15"/std faucet Art Room	3 ea	1,384.98 /ea	4,155
P9A Sink/lay-in/1-bowl 21"x15"/std faucet/ADA Art Room	1 ea	1,455.75 /ea	1,456
P7A Sink/lay-in/1-bowl 21"x15"/std faucet/ADA	3 ea	1,860.75 /ea	5,582
P8 Sink/lay-in/1-bowl/22"x16"/bubbler	5 ea	1,715.35 /ea	8,577
P-13 Sink/acid waste/undermount/std 2-lever faucet/ss - 21"x15"x10"D	3 ea	1,508.82 /ea	4,526
- Solids interceptors (Art Room sinks)	4 ea	552.64 /ea	2,211
Mop sink/floor mnt - 24"x24"	5 ea	1,349.01 /ea	6,745
P6 Shower stall/std valve & access./3'x3' fiberglass	1 ea	2,704.96 /ea	2,705
P6-A Shower stall/std valve & access./5'x3' fiberglass/ADA	2 ea	3,701.67 /ea	7,403
P13 Emergency eye wash station/mixing valve/sink mount	3 ea	1,106.71 /ea	3,320
Emergency shower/eye wash sta./mixing valve/cabinet mount	7 ea	3,540.35 /ea	24,782
Water cooler/bi-level/ADA	10 ea	4,418.42 /ea	44,184
- Plumbing fixtures offload & distribution	239 ea	103.07 /ea	24,634
- Plumbing fixtures rough-in	239 ea	128.07 /ea	30,609
<i>D2010 Plumbing</i>	<b>136,600 sf</b>	<b>3.05 /sf</b>	<b>416,156</b>

**D2020 Domestic Water Distribution**

Insulation/copper pipe/fiberglass	7,975 lf	8.44 /lf	67,307
Water meter w/remote readout - 4"	1 ea	2,285.75 /ea	2,286
Water sub-meter - avg. size	1 ea	1,561.84 /ea	1,562
Water sub-meter - 1.5 Circ	1 ea	1,261.84 /ea	1,262
Water sub-meter - 2" Domestic WH	1 ea	1,277.30 /ea	1,277
Backflow preventer/RPZ-BFP - dishwasher	1 ea	1,809.21 /ea	1,809
Backflow preventer/RPZ-BFP - 2" LW	2 ea	1,657.68 /ea	3,315
Backflow preventer/RPZ-BFP - 4"	1 ea	1,960.75 /ea	1,961
Pressure reducing valve/PRV - 1"	1 ea	1,159.21 /ea	1,159



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D2020 Domestic Water Distribution</b>			
Pressure reducing valve - 4"	1 ea	2,210.75 /ea	2,211
Recirculation pump/bronze/6.5 gpm - 1/8 hp (B&G Ecocirc)	1 ea	1,806.14 /ea	1,806
Recirculation pump/bronze/10 gpm - 1/6 hp (B&G #SSF-22)	2 ea	709.14 /ea	1,418
Expansion tank/ASME/potable - 9 gal (B&G #PTA-30V)	1 ea	1,250.61 /ea	1,251
TMV/master/hi-lo temp.	1 ea	2,759.21 /ea	2,759
Hose bibbs w/vac. breaker/encased - interior	19 ea	382.50 /ea	7,268
Hose bibbs/exterior/encased (Zurn #Z1320)	3 ea	452.07 /ea	1,356
Trap primers/electronic - 8 outlet (PPP #PT-8)	8 ea	1,359.91 /ea	10,879
Shock absorbers/12 - 33 fixture units (Shoktrol #200)	3 ea	269.77 /ea	809
Valve box/washing machine	1 ea	226.54 /ea	227
Valve box/ice machine	3 ea	176.54 /ea	530
Domestic water entrance UG/ductile iron - 4"	20 lf	306.14 /lf	6,123
Domestic water AG/type "L" copper/press fit ftgs. - avg. size	525 lf	23.31 /lf	12,235
Domestic water AG/type "L" copper/press fit - 1/2" TP	1,120 lf	13.02 /lf	14,577
Domestic water AG/type "L" copper/press fit - 1/2" NP	800 lf	13.02 /lf	10,412
Domestic water AG/type "L" copper/press fit - 1/2"	1,460 lf	13.02 /lf	19,002
Domestic water AG/type "L" copper/press fit - 3/4" NP	450 lf	15.76 /lf	7,091
Domestic water AG/type "L" copper/press fit - 3/4"	1,240 lf	15.76 /lf	19,539
Domestic water AG/type "L" copper/press fit - 1" NP	100 lf	20.56 /lf	2,056
Domestic water AG/type "L" copper/press fit - 1"	50 lf	20.57 /lf	1,028
Domestic water AG/type "L" copper/press fit - 1-1/4" NP	100 lf	25.23 /lf	2,523
Domestic water AG/type "L" copper/press fit - 1-1/4"	115 lf	25.23 /lf	2,902
Domestic water AG/type "L" copper/press fit - 1-1/2"	400 lf	30.31 /lf	12,125
Domestic water AG/type "L" copper/press fit - 2" NP	450 lf	41.16 /lf	18,523
Domestic water AG/type "L" copper/press fit - 2"	300 lf	41.16 /lf	12,349
Domestic water AG/type "L" copper/press fit - 2-1/2"	285 lf	66.38 /lf	18,919
Domestic water AG/type "L" copper/press fit - 3"	480 lf	84.91 /lf	40,759
Domestic water AG/type "L" copper/press fit - 4"	100 lf	116.00 /lf	11,600
Non-potable water AG/type "L" copper/solder - Hood Tie In	60 lf	22.94 /lf	1,377
- Domestic water piping accessories DOM	6,095 lf	2.78 /lf	16,917
- Domestic water piping accessories NP	1,900 lf	2.78 /lf	5,274
- Domestic water heat tracing/small bore piping All LHW	1,900 lf	25.97 /lf	49,340
- Domestic water pipe & equipment I.D. DOM	6,095 lf	1.61 /lf	9,817
- Domestic water pipe & equipment I.D. NP	1,900 lf	1.52 /lf	2,881
- Domestic water pressure gauges & thermometers	12 ea	120.61 /ea	1,447
- Domestic water support steel/additional to hangers & clamps	1 ls	1,074.56 /ls	1,075
- Layout Mech Room	1 ls	20,000.00 /ls	20,000
- Domestic water storage tank	1 ls	3.52 /ls	4
Domestic Boilers/gas fired/399 mbh (AO Smith #BTH-300A)	2 ea	15,618.42 /ea	31,237
Boiler Flues	1 ls	45,525.00 /ls	45,525





90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D2020 Domestic Water Distribution</b>			
Water Heater Flues	1 ls	24,000.00 /ls	24,000
HWH/indirect fed - 300 gal	1 ea	7,418.42 /ea	7,418
<i>D2020 Domestic Water Distribution</i>	<b>136,600 sf</b>	<b>3.96 /sf</b>	<b>540,525</b>
<b>D2030 Sanitary Waste</b>			
Floor drain - 3" (#ZN415-6B)	16 ea	294.07 /ea	4,705
Floor drain - 4" (#ZN415-8B)	4 ea	353.07 /ea	1,412
Floor sink/12x12 - 4" (#Z1900)	8 ea	2,581.14 /ea	20,649
Floor cleanouts - 4" (#ZN1400)	37 ea	291.07 /ea	10,770
Wall cleanouts - 4" (#Z1468)	10 ea	101.08 /ea	1,011
Grease interceptor/interior/size 800/75 gpm/150 gal.	2 ea	4,291.56 /ea	8,583
8000 Gallon Concrete Grease Trap	1 ea	17,649.12 /ea	17,649
Elevator sump pump/oil minder	1 ea	3,812.28 /ea	3,812
Grease interceptor flow control	1 ea	417.14 /ea	417
Sanitary UG/cast iron single hub pipe & ftgs. - 2"	220 lf	31.98 /lf	7,036
Sanitary UG/cast iron single hub pipe & ftgs. - 3"	236 lf	36.45 /lf	8,602
Sanitary UG/cast iron single hub pipe & ftgs. - 4"	610 lf	44.78 /lf	27,315
Sanitary UG/cast iron single hub pipe & ftgs. - 6"	275 lf	74.82 /lf	20,576
Sanitary AG/cast iron no hub pipe & ftgs. - avg. size Fixture Runouts	1,560 lf	47.33 /lf	73,828
Sanitary AG/cast iron no hub pipe & ftgs. - 1-1/2"	30 lf	33.82 /lf	1,015
Sanitary AG/cast iron no hub pipe & ftgs. - 2"	750 lf	34.83 /lf	26,119
Sanitary AG/cast iron no hub pipe & ftgs. - 3"	980 lf	44.36 /lf	43,468
Sanitary AG/cast iron no hub pipe & ftgs. - 4"	495 lf	52.52 /lf	25,999
Grease waste UG/cast iron single hub pipe & ftgs. - 2"	40 lf	31.98 /lf	1,279
Grease waste UG/cast iron single hub pipe & ftgs. - 3"	20 lf	36.45 /lf	729
Grease waste UG/cast iron single hub pipe & ftgs. - 4"	220 lf	44.78 /lf	9,851
Grease waste AG/cast iron no hub pipe & ftgs. - 2"	55 lf	34.83 /lf	1,915
Grease waste AG/cast iron no hub pipe & ftgs. - 3"	65 lf	44.36 /lf	2,883
Grease waste AG/cast iron no hub pipe & ftgs. - 4"	70 lf	52.52 /lf	3,677
- Sanitary waste & vent piping accessories	5,626 lf	1.77 /lf	9,976
- Sanitary piping & equipment I.D.	5,626 lf	1.81 /lf	10,171
<i>D2030 Sanitary Waste</i>	<b>136,600 sf</b>	<b>2.51 /sf</b>	<b>343,448</b>
<b>D2040 Rain Water Drainage</b>			
Insulation/rainleader pipe/fiberglass/PVC jacketed/horiz. & vert.	1,200 lf	40.61 /lf	48,737
Roof drain/#ZC100 - 4"	9 ea	298.07 /ea	2,683
Roof drain/#ZC100 - 5"	2 ea	387.84 /ea	776
Roof drain/#ZC100 - 6"	14 ea	387.84 /ea	5,430
Floor cleanouts - 4" (#ZN1400)	6 ea	291.07 /ea	1,746
Wall cleanouts - 4" (#Z1468)	12 ea	101.07 /ea	1,213
Rainleader UG/cast iron single hub pipe & ftgs. - 4"	90 lf	44.77 /lf	4,030



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D2040 Rain Water Drainage</b>			
Rainleader UG/cast iron single hub pipe & ftgs. - 6"	90 lf	74.82 /lf	6,734
Rainleader UG/cast iron single hub pipe & ftgs. - 8"	70 lf	103.25 /lf	7,228
Rainleader UG/cast iron single hub pipe & ftgs. - 10"	160 lf	141.04 /lf	22,566
Rainleader UG/cast iron single hub pipe & ftgs. - 12"	25 lf	186.99 /lf	4,675
Rainleader AG/cast iron no hub pipe & ftgs. - 4"	265 lf	52.53 /lf	13,919
Rainleader AG/cast iron no hub pipe & ftgs. - 6"	410 lf	81.16 /lf	33,274
Rainleader AG/cast iron no hub pipe & ftgs. - 8"	460 lf	133.84 /lf	61,565
Rainleader AG/cast iron no hub pipe & ftgs. - 10"	10 lf	198.47 /lf	1,985
- Rainleader piping accessories	1,580 lf	1.77 /lf	2,802
- Rainleader piping & equipment I.D.	1,580 lf	1.46 /lf	2,314
<i>D2040 Rain Water Drainage</i>	<b>136,600 sf</b>	<b>1.62 /sf</b>	<b>221,676</b>
<b>D2090 Other Plumbing Systems</b>			
General requirements (management, permits, as-builts, coring, fire stopping)	136,600 sf	0.75 /sf	102,450
3D/BIM coordination	1 ls	12,000.00 /ls	12,000
Core drilling	1 ls	10,000.00 /ls	10,000
Project management	1 ls	50,000.00 /ls	50,000
Kitchen Equipment Tie ins	1 ls	12,000.00 /ls	12,000
Commissioning support/day	5 day	824.56 /day	4,123
Gas Flow Meter - avg. size	1 ea	1,857.68 /ea	1,858
Emergency gas shut off/cabinet w/1" solenoid & UL ball valve 1114, 1111A	2 ea	3,968.42 /ea	7,937
Emergency gas shut off/cabinet w/1-1/2" solenoid & UL ball valve KIT	1 ea	5,093.42 /ea	5,093
- Remote panic buttons	2 ea	828.07 /ea	1,656
Gas turret/single	5 ea	212.07 /ea	1,060
Gas turret/double	5 ea	320.54 /ea	1,603
Gas piping/sch 40 black steel CW t&c - 1"	240 lf	28.68 /lf	6,882
Gas piping/sch 40 black steel CW t&c - 1-1/4"	120 lf	34.14 /lf	4,097
Gas piping/sch 40 black steel CW t&c - 1-1/2"	65 lf	37.25 /lf	2,421
Gas piping/sch 40 black steel CW t&c - 2"	10 lf	42.28 /lf	423
Gas piping/sch 40 blk stl ERW weld - 2-1/2"	30 lf	45.73 /lf	1,372
Gas piping/sch 40 blk stl ERW weld - 3"	75 lf	54.12 /lf	4,059
Gas piping/sch 40 blk stl ERW weld - 4"	60 lf	87.71 /lf	5,263
Gas piping/sch 40 blk stl ERW weld - 8"	25 lf	180.43 /lf	4,511
- Gas piping accessories	625 lf	2.52 /lf	1,577
- Gas piping link seals	1 ea	404.61 /ea	405
- Gas piping & equipment I.D.	625 lf	28.95 /lf	18,094
Acid neut. Tank/5 gallon - 1-sink (Orion style 5)	1 ea	622.14 /ea	622



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D2090 Other Plumbing Systems</b>			
Acid neut. tank/15 gallon - 3-sinks (Orion style 5)	3 ea	911.21 /ea	2,734
Acid neut. tank/55 gallon -	2 ea	1,912.28 /ea	3,825
- Limestone chips/50 lb. bag	24 ea	43.77 /ea	1,050
PH Monitoring (2) locations	2 ea	6,612.28 /ea	13,225
Floor drain - 6" (#ZN415-AA-8B)	3 ea	480.84 /ea	1,443
Floor cleanout/heavy duty - 4" (#ZN1400-K-AR)	5 ea	424.84 /ea	2,124
Wall cleanouts/#Z1468 - 4"	5 ea	101.07 /ea	505
Acid waste UG/sch 40 polypropylene fuseal & ftgs. - 3"	20 lf	58.29 /lf	1,166
Acid waste UG/sch 40 polypropylene fuseal & ftgs. - 4"	230 lf	68.91 /lf	15,849
Tie-ins to Lab Hoods acid waste & vent - A/G	3 ea	815.35 /ea	2,446
Acid waste AG/sch 40 polypropylene fuseal & ftgs. - 2"	800 lf	51.44 /lf	41,154
Acid waste AG/sch 40 polypropylene fuseal & ftgs. - 3"	400 lf	65.67 /lf	26,269
Acid waste AG/sch 40 polypropylene fuseal & ftgs. - 4"	360 lf	77.44 /lf	27,877
- Acid waste & vent piping accessories	1,790 lf	2.02 /lf	3,622
- Acid waste piping & equipment I.D.	1,790 lf	2.56 /lf	4,585
Wiring PH Monitor and Misc Control	1 ls	6,000.00 /ls	6,000
SM - Flue piping/double wall/stainless steel/6" pipe - linear foot	600 lf	97.98 /lf	58,786
DWH			
SM - Flue piping/double wall/stainless steel/6" fittings - each DWH	16 ea	122.47 /ea	1,960
SM - Flue piping/double wall/stainless steel/6" fittings - each DWH	8 lf	122.47 /lf	980
<i>D2090 Other Plumbing Systems</i>	<b>136,600 sf</b>	<b>3.48 /sf</b>	<b>475,103</b>
<b>D20 Plumbing</b>	<b>136,600 sf</b>	<b>14.62 /sf</b>	<b>1,996,907</b>

**D30 Heating, Ventilating, and Air Conditioning (HVAC)**

**D3010 Energy Supply**

Insulation/pipe/copper	14,483 lf	7.09 /lf	102,715
Insulation/pipe/weld	3,838 lf	12.50 /lf	47,975
Hot water s&r/type "L" copper solder - 3/4"	8,970 lf	20.16 /lf	180,835
Hot water s&r/type "L" copper solder - 1"	1,760 lf	25.01 /lf	44,018
Hot water s&r/type "L" copper solder - 1-1/4"	1,260 lf	28.57 /lf	35,998
Hot water s&r/type "L" copper solder - 1-1/2"	890 lf	32.82 /lf	29,210
Hot water s&r/type "L" copper solder - 2"	1,550 lf	41.25 /lf	63,937
Hot water s&r/sch 40 blk stl ERW weld - 2-1/2"	605 lf	50.55 /lf	30,583
Hot water s&r/sch 40 blk stl ERW weld - 3"	475 lf	59.42 /lf	28,225
Hot water s&r/sch 40 blk stl ERW weld - 4"	756 lf	82.30 /lf	62,219
Hot water s&r/sch 40 blk stl ERW weld - 6"	520 lf	134.07 /lf	69,716
Hot water s&r/sch 40 blk stl ERW weld - 8"	220 lf	167.74 /lf	36,903
Glycol water s&r/type "L" copper solder - 2"	53 lf	41.25 /lf	2,186
Glycol water s&r/sch 40 blk stl ERW weld - 2-1/2"	47 lf	50.55 /lf	2,376
Glycol water s&r/sch 40 blk stl ERW weld - 3"	90 lf	59.42 /lf	5,348



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D3010 Energy Supply</b>			
Glycol water s&r/sch 40 blk stl ERW weld - 4"	152 lf	82.30 /lf	12,510
Glycol water s&r/sch 40 blk stl ERW weld - 6"	910 lf	134.07 /lf	122,004
Glycol water s&r/sch 40 blk stl ERW weld - 8"	110 lf	167.74 /lf	18,451
- Hydronic piping accessories	18,368 lf	2.53 /lf	46,506
Pump/base mount/790 gpm (HW)	2 ea	8,167.68 /ea	16,335
Chilled water pump house (pumps & accesories, enclosure, piping, unit heater	1 ls	226,667.68 /ls	226,668
- Suction diffusers	2 ea	1,460.58 /ea	2,921
- Flex connector/HVAC pumps	4 ea	556.35 /ea	2,225
- Triple duty valves	2 ea	2,312.69 /ea	4,625
Air separators	1 ea	4,333.84 /ea	4,334
Expansion tanks/ASME	2 ea	7,167.68 /ea	14,335
Chemical treatment (lump sum)	1 ls	20,000.00 /ls	20,000
Glycol feed/50 gal. tank w/pump (Neptune #G-50-1)	2 ea	5,272.92 /ea	10,546
- Glycol solution/40% propylene	1,000 gal	25.21 /gal	25,212
<i>D3010 Energy Supply</i>	<b>136,600 sf</b>	<b>9.29 /sf</b>	<b>1,268,916</b>
<b>D3020 HVAC</b>			
Boiler/HW/gas/high eff. cond. - 4,000 mbh Riello AR 4000	2 ea	57,501.52 /ea	115,003
Boiler circulator pump	2 ea	1,708.46 /ea	3,417
Boiler combustion air/galvanized steel 10"	200 lf	38.00 /lf	7,600
Flue piping/double wall/stainless steel 10"	205 lf	185.00 /lf	37,925
<i>D3020 HVAC</i>	<b>136,600 sf</b>	<b>1.20 /sf</b>	<b>163,945</b>
<b>D3030 Cooling Generating Systems</b>			
Chiller/air cooled - 370 tons	1 ea	381,153.80 /ea	381,154
Buffer tanks/Lochinvar - 300 gals.	1 ea	8,750.76 /ea	8,751
<i>D3030 Cooling Generating Systems</i>	<b>136,600 sf</b>	<b>2.85 /sf</b>	<b>389,905</b>
<b>D3040 HVAC Distribution</b>			
Lull, laborer for cleanup by Consigli (HVAC)	(1) ls	343,000.00 /ls	(343,000)
Trade support - lull, laborer for cleanup (HVAC)	1 ls	343,000.00 /ls	343,000
Insulation/ductwork/blanket wrap	83,500 sf	3.55 /sf	296,088
Insulation/ductwork/weatherproof exposed	4,500 sf	12.89 /sf	57,986
Sheetmetal & accessories/galvanized	101,200 lb	11.04 /lb	1,117,248
Sheetmetal & accessories/galvanized (perforated)	790 lb	14.49 /lb	11,447
Sheetmetal & accessories/galvanized (smoke exhasut)	8,850 lb	11.04 /lb	97,704
Sheetmetal & accessories/stainless steel (dishwasher)	350 lb	22.28 /lb	7,798
Sheetmetal & accessories/welded stainless steel (kitchen exhaust)	1,060 lb	29.78 /lb	31,567
Sheetmetal & accessories/welded stainless steel (kiln exhaust)	500 lb	29.78 /lb	14,890
Sheetmetal & accessories/welded stainless steel (3 - fume hoods)	2,700 lb	29.78 /lb	80,406



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D3040 HVAC Distribution</b>			
Sheetmetal & accessories/fabric/1-row cable (DuctSox) - 20"	405 lf	76.50 /lf	30,982
Sheetmetal & accessories/fabric/1-row cable (DuctSox) - 24"	305 lf	81.29 /lf	24,792
Duct enclosure (roof)	1 ea	5,424.10 /ea	5,424
SM - Diffusers, registers & grilles	136,600 sf	0.20 /sf	27,320
SM - Linear slot diffusers (supply)	6 ea	465.39 /ea	2,792
SM - Linear slot diffusers (exhaust) - architectural	lf	/lf	
SM - Displ. Diffuser/Floor Mnt.	156 ea	1,289.88 /ea	201,221
SM - Combination fire/smoke dampers/louver type/UL	20 ea	776.53 /ea	15,530
SM - Motorized damper	14 ea	1,107.92 /ea	15,511
SM - Smoke detectors/duct mount	40 ea	747.47 /ea	29,899
SM - Sound attenuators/in-line/std. gauge	239,000 cfm	0.55 /cfm	131,341
SM - Kitchen exhaust hood/st. steel/install only (by KES)	1 ea	2,339.28 /ea	2,339
SM - Dishwasher exhaust hood/st. steel/install only (by KES)	1 ea	1,559.52 /ea	1,560
SEF-1-4	4 ea	17,339.28 /ea	69,357
EF-3&4 /centrifugal downblast/roof/direct drive - 500 cfm	2 ea	1,069.31 /ea	2,139
EF-1&2 /centrifugal downblast/roof/direct drive - 2,500 cfm	2 ea	1,771.24 /ea	3,542
KEF-1&2/centrifugal upblast/roof	2 ea	2,734.82 /ea	5,470
FEF-1,2,3,4,5 Lab exhaust fan/roof - 1,200 cfm	5 ea	9,084.82 /ea	45,424
<i>D3040 HVAC Distribution</i>	<b>136,600 sf</b>	<b>17.06 /sf</b>	<b>2,329,778</b>
<b>D3050 Terminal &amp; Package Units</b>			
Variable air volume box - small	12 ea	533.15 /ea	6,398
Variable air volume box - medium	143 ea	668.62 /ea	95,612
RTU-1-4 Classrooms (service enclosure, HW&CHW coils, energy recovery)	80,000 cfm	15.75 /cfm	1,260,000
RTU-5 Gymnasium (service enclosure, HW&CHW coils, energy recovery)	15,000 cfm	16.25 /cfm	243,750
RTU-6 Auditorium (service enclosure, HW&CHW coils, energy recovery)	12,000 cfm	16.25 /cfm	195,000
RTU-7 Lockers (service enclosure, HW&CHW coils, energy recovery)	2,000 cfm	18.25 /cfm	36,500
MAU-1 Make-up air unit/HW&CHW coil/	5,000 cfm	7.25 /cfm	36,250
Mini-split AC system/1-zone/wall mnt./cool only - 12 mbh	1 ea	2,072.92 /ea	2,073
Mini-split AC system/1-zone/wall mnt./cool only - 18 mbh	5 ea	2,681.66 /ea	13,408
Mini-split AC system/1-zone/wall mnt./cool only - 24 mbh	2 ea	2,956.03 /ea	5,912
Mini-split refrigeration line set/6-12 mbh - 50'	2 ea	584.88 /ea	1,170
Mini-split refrigeration line set/15-18 mbh - 50'	10 ea	599.88 /ea	5,999
Mini-split refrigeration line set/24-30 mbh - 50'	4 ea	614.88 /ea	2,460
Mini-split condensate drains/type "L" copper	450 lf	19.43 /lf	8,744
A/C cond. pump	8 ea	253.74 /ea	2,030
INS - Mini-split Insulation/copper pipe	450 lf	6.87 /lf	3,090



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D3050 Terminal &amp; Package Units</b>			
ATC - Mini-split condensing units (w/factory controls)	8 ea	879.76 /ea	7,038
ATC - Mini-split indoor units (w/factory controls)	8 ea	587.35 /ea	4,699
Radiant ceiling panels/24" wide - ft.	1,450 lf	120.00 /lf	174,000
FTR-2 Finned-tube radiation w/enclosure - 1 row	260 lf	194.24 /lf	50,502
FTR-1 Finned-tube radiation w/enclosure - 2 row	570 lf	259.37 /lf	147,841
FTR-3 Finned-tube radiation w/enclosure - 2 row	40 lf	297.49 /lf	11,900
Fin-tube radiation/electric - 2 kW	8 ea	739.88 /ea	5,919
Cabinet unit heater/hot water/wall mount/recessed - avg. size	4 ea	1,573.62 /ea	6,294
Cabinet unit heater/hot water/ceiling mount - avg. size	10 ea	1,749.51 /ea	17,495
Unit heater/hot water/horiz./propeller - avg. size	2 ea	1,092.41 /ea	2,185
Misc. VFD's	1 ls	35,000.00 /ls	35,000
VFD w/keypad/disconnect/bypass/NEMA 1 - HW pumps	2 ea	6,028.47 /ea	12,057
VFD w/keypad/disconnect/bypass/NEMA 1 - CHW pumps w/ pump house	ea	/ea	
<i>D3050 Terminal &amp; Package Units</i>	<b>136,600 sf</b>	<b>17.52 /sf</b>	<b>2,393,325</b>
<b>D3060 HVAC Instrumentation &amp; Controls</b>			
Automatic temperature controls/cost per sq. ft.	136,600 sf	0.25 /sf	34,150
ATC - Air valve/hood exhaust/HEX	3 ea	4,194.32 /ea	12,583
ATC - Air valves/no coil control wiring - 3 pts./fume hood	9 pnt	437.00 /pnt	3,933
ATC - RTU's/custom - 30 pts.	240 pnt	1,303.18 /pnt	312,763
ATC - MUA units - 10 pts.	10 pnt	759.44 /pnt	7,594
ATC - Exhaust fans - 3 pts.	18 pnt	711.10 /pnt	12,800
ATC - Life safty fans - 8 pts.	32 pnt	766.15 /pnt	24,517
ATC - Lab exhaust fans - 5 pts./fan	25 pnt	766.15 /pnt	19,154
ATC - Boilers/modular - 10 pts.	20 pnt	821.19 /pnt	16,424
ATC - Pumps - 4 pts.	16 pnt	766.15 /pnt	12,258
ATC - VFD wiring for pumps (remote mount) - 4 pts.	16 pnt	763.91 /pnt	12,223
ATC - Circulators - 2 pts.	4 pnt	488.68 /pnt	1,955
ATC - Chillers - 15 pts.	15 pnt	1,303.18 /pnt	19,548
ATC - VAV box/no coil (ATC furn./factory install controls) 2 pts.	310 pnt	408.36 /pnt	126,592
ATC - Fintube radiation zones - 2 pts.	20 pnt	381.96 /pnt	7,639
ATC - electric fintube radiation zones - 2 pts.	4 pnt	381.95 /pnt	1,528
ATC - Cabinet unit heaters - 3 pts.	42 pnt	381.96 /pnt	16,042
ATC - Unit heaters - 3 pts.	6 pnt	381.95 /pnt	2,292
ATC - Radiant ceiling panel zones - 2 pts.	246 pnt	381.96 /pnt	93,961
ATC - Plumbing points - 10 pts.	10 pnt	595.50 /pnt	5,955
ATC - Elctrical points - 10 pts.	10 pnt	595.50 /pnt	5,955
<i>D3060 HVAC Instrumentation &amp; Controls</i>	<b>136,600 sf</b>	<b>5.49 /sf</b>	<b>749,864</b>

D3070 Testing, Adjusting & Balancing



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D3070 Testing, Adjusting &amp; Balancing</b>			
Testing & balancing/cost per sq. ft.	136,600 sf	0.65 /sf	88,790
<i>D3070 Testing, Adjusting &amp; Balancing</i>	<u>136,600 sf</u>	<u>0.65 /sf</u>	<u>88,790</u>
<b>D3090 Other HVAC Systems &amp; Equipment</b>			
General requirements (sq. ft.)	136,600 sf	1.15 /sf	157,090
3D/BIM coordination	1 ls	100,000.00 /ls	100,000
Commissioning support/lump sum	1 ls	15,000.00 /ls	15,000
Dust collection system	1 ea	17,339.28 /ea	17,339
Kiln exhaust	1 ls	5,500.00 /ls	5,500
Equipment hoisting/rigging/setting/start-up	136,600 sf	1.50 /sf	204,900
<i>D3090 Other HVAC Systems &amp; Equipment</i>	<u>136,600 sf</u>	<u>3.66 /sf</u>	<u>499,829</u>
<b>D30 Heating, Ventilating, and Air Conditioning (HVAC)</b>	<b>136,600 sf</b>	<b>57.72 /sf</b>	<b>7,884,351</b>
<b>D40 Fire Protection Systems</b>			
<b>D4010 Sprinklers</b>			
Lull, laborer for cleanup by Consigli (Fire Protection)	(1) ls	31,000.00 /ls	(31,000)
Trade support - lull, laborer for cleanup (Fire Protection)	1 ls	31,000.00 /ls	31,000
General requirements (management/design, permits, as-builts, coring, fire stopping)	136,600 sf	0.80 /sf	109,280
Fire dept. inlet connection - 2-1/2" polished brass - 3-way	1 ea	1,863.93 /ea	1,864
Sprinkler head - wet - recessed pendant	903 ea	125.42 /ea	113,250
Sprinkler head - wet - pendant or upright	522 ea	77.23 /ea	40,313
Sprinkler head - wet - sidewall	151 ea	87.51 /ea	13,213
Sprinkler head - wet - window	34 ea	87.51 /ea	2,975
Sprinkler head - extended coverage pendant or upright	120 ea	127.23 /ea	15,267
Sprinkler head - dry - sidewall (wet system)	22 ea	293.06 /ea	6,447
Sprinkler branch piping black steel sch. 40 w/ fittings 1"	3,465 lf	23.99 /lf	83,116
Sprinkler branch piping black steel sch. 40 w/ fittings 1-1/4"	600 lf	27.93 /lf	16,757
Sprinkler branch piping black steel sch. 40 w/ fittings 1-1/2"	5,200 lf	30.66 /lf	159,417
Sprinkler branch piping black steel sch. 40 w/ fittings 2"	650 lf	34.57 /lf	22,468
Sprinkler main piping black steel sch. 40 w/ fittings (avg. size)	1,000 lf	62.18 /lf	62,184
Sprinkler main piping black steel sch. 10 w/ fittings 3"	450 lf	36.32 /lf	16,345
Sprinkler main piping black steel sch. 10 w/ fittings 4"	3,180 lf	39.66 /lf	126,127
Sprinkler main piping black steel sch. 10 w/ fittings 6"	500 lf	69.39 /lf	34,695
Wet alarm valve - 6"	1 ea	3,656.71 /ea	3,657
Double check valve (BFP) assembly - 6"	1 ea	8,244.56 /ea	8,245
Butterfly valve - 6"	2 ea	1,566.71 /ea	3,133
Zone flow control valve - 4"	7 ea	2,521.71 /ea	17,652
Waterflow switch	8 ea	421.96 /ea	3,376
Tamper switch	8 ea	356.96 /ea	2,856



### 90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D4010 Sprinklers</b>			
Water motor gong bell	1 ea	628.36 /ea	628
<i>D4010 Sprinklers</i>	<b>136,600 sf</b>	6.32 /sf	863,266
<b>D4020 Standpipes</b>			
Standpipe - sch 40 black steel piping w/ fittings - 6"	125 lf	99.13 /lf	12,391
Drain riser - sch 40 black steel piping w/ fittings - 3"	125 lf	49.66 /lf	6,208
Fire hose valve - 2-1/2"	12 ea	353.36 /ea	4,240
<i>D4020 Standpipes</i>	<b>136,600 sf</b>	0.17 /sf	22,839
<b>D4030 Fire Protection Specialties</b>			
Fire valve cabinet - steel - recessed	12 ea	894.50 /ea	10,734
<i>D4030 Fire Protection Specialties</i>	<b>136,600 sf</b>	0.08 /sf	10,734
<b>D4090 Other Fire Protection Systems</b>			
Hydraulic calculation & shop drawings	1 ls	8,000.00 /ls	8,000
3D/BIM coordination	1 ls	10,000.00 /ls	10,000
<i>D4090 Other Fire Protection Systems</i>	<b>136,600 sf</b>	0.13 /sf	18,000
<b>D40 Fire Protection Systems</b>	<b>136,600 sf</b>	<b>6.70 /sf</b>	<b>914,839</b>
<b>D50 Electrical Systems</b>			
<b>D5010 Gear &amp; Distribution</b>			
Feeder (MC) - 20A (kitchen equipment - x42)	3,150 lf	5.75 /lf	18,111
Feeder (MC) - 30A (kitchen equipment - x2)	200 lf	5.87 /lf	1,173
1" PVC - 30A (3#8 & #10G)	250 lf	10.29 /lf	2,573
Feeder (MC) - 40A (kitchen equipment - x1)	100 lf	7.01 /lf	701
Feeder (MC) - 60A (kitchen equipment - x2)	200 lf	10.55 /lf	2,110
Power for automatic temperature control panels (BMS)	12 ea	460.91 /ea	5,531
Electric heat trace power (cables, sensors, controllers by Div. 21 / 22)	1,900 lf	3.50 /lf	6,650
Service switch: 20A/3P, NEMA-1	1 ea	107.43 /ea	107
Fused Disco: 20A/3P, NEMA-1	7 ea	323.22 /ea	2,263
Fused Disco: 100A/3P, NEMA-1	2 ea	1,185.41 /ea	2,371
Fused Disco: 200A/3P, NEMA-1	3 ea	1,555.38 /ea	4,666
Fused Disco: 1000A/3P, NEMA-1	2 ea	7,290.94 /ea	14,582
Wire gymnasium equipment SMC control stations (furnished by others)	8 ea	1,058.23 /ea	8,466
Wire motors and controllers	15 ea	821.28 /ea	12,319
Kitchen equipment final connections (includes flexible whip)	47 ea	72.36 /ea	3,401
Mount & wire VFD's (furnished by Div. 23)	8 ea	646.55 /ea	5,172
MAU (5000cfm) - circuit / disconnect (3R) / connection	1 ea	2,503.41 /ea	2,503
RTU's - circuit / disconnect (3R) / connection (small)	3 ea	4,736.19 /ea	14,209





90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5010 Gear &amp; Distribution</b>			
RTU's - circuit / disconnect (3R) / connection (large)	4 ea	7,010.29 /ea	28,041
Mini-split systems (indoor/outdoor) - circuits / disconnects (3R) / connections	8 ea	3,225.23 /ea	25,802
Chiller (370T) - circuit / disconnect (3R) / connection	1 ea	25,825.56 /ea	25,826
Smoke exhaust fans - circuit / disconnect / connection (100A)	4 ea	2,400.01 /ea	9,600
Kitchen exhaust fans - circuit / disconnect / connection	2 ea	1,420.91 /ea	2,842
Kiln exhaust system - circuit / disconnect / connection	1 ea	2,655.30 /ea	2,655
Dust collection system - circuit / disconnect / connection	1 ea	3,579.00 /ea	3,579
Fume hood exhaust fans - circuit / disconnect / connection	5 ea	1,214.10 /ea	6,071
Exhaust fans - circuit / disconnect / connection	4 ea	1,214.11 /ea	4,856
Power to electronic trap primers - 120V	8 ea	100.19 /ea	801
Hot water pumps - circuit / disconnect / connection	2 ea	1,673.87 /ea	3,348
Boilers - circuit / disconnect / connection	2 ea	1,204.71 /ea	2,409
Chilled water pump house pumps & heaters - circuits / disconnects / connections	1 ls	6,158.00 /ls	6,158
Hot water heater - circuit / service switch / connection	1 ea	591.53 /ea	592
Cabinet unit heaters - circuit / service switch / connection	14 ea	868.28 /ea	12,156
Unit heaters - circuit / service switch / connection	2 ea	868.28 /ea	1,737
Elevator sump pump - circuit / disconnect (3R) / connection	1 ea	1,247.28 /ea	1,247
Domestic boilers - circuit / disconnect (3R) / connection	2 ea	1,247.28 /ea	2,495
Recirculation pumps - circuit / disconnect / connection	3 ea	997.87 /ea	2,994
Glycol feed pumps - circuit / disconnect / connection	2 ea	997.87 /ea	1,996
Boiler circulation pumps - circuit / disconnect / connection	2 ea	997.87 /ea	1,996
Fin-tube radiators (2kW) - circuit / disconnect / connection	8 ea	1,847.40 /ea	14,779
VAV's - circuit / disconnect / connection	155 ea	298.83 /ea	46,318
Acid neutralization tanks / PH monitoring - circuit / connection	2 ea	965.80 /ea	1,932
Circuit breaker - 20A/1P (panel)	1 ea	149.86 /ea	150
Switchboard: 3000A bus, 2500A rated MCB (100%), 480/277V, 3PH, 65kAIC	1 ea	45,417.04 /ea	45,417
Panelboard: 100A, 42-circuit	14 ea	2,550.41 /ea	35,706
Panelboard: 225A, 42-circuit	9 ea	3,420.66 /ea	30,786
Panelboard: 225A, 84-circuit	9 ea	4,338.66 /ea	39,048
Panelboard: 400A, 42-circuit	3 ea	5,435.74 /ea	16,307
Panelboard: 400A, 84-circuit	1 ea	10,724.46 /ea	10,724
Distribution panel: 600A	2 ea	9,886.92 /ea	19,774
Distribution panel: 800A	3 ea	12,443.25 /ea	37,330
Transformer: floor/wall - 75kVA, 480V:208V	1 ea	4,384.00 /ea	4,384
K-13 Transformer: floor - 225kVA, 480V:208V	3 ea	12,168.50 /ea	36,506
Engineered Services - Training (Manufacturer)	1 ea	4,165.70 /ea	4,166
Engineered Services - Start-Up Assistance (Manufacturer)	1 ea	3,519.08 /ea	3,519



### 90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5010 Gear &amp; Distribution</b>			
Feeder (EMT/CU) - 20A [BMS to utility meter]	200 lf	7.43 /lf	1,486
Feeder (EMT/CU) - 20A [EP1A to Elevator Controller]	125 lf	7.43 /lf	929
Feeder (EMT/CU) - 60A [MSB to SPD]	50 lf	14.69 /lf	735
Feeder (EMT/CU) - 60A [2DP1A to SPD]	50 lf	14.69 /lf	735
Feeder (EMT/CU) - 60A [2DP1B to SPD]	50 lf	14.69 /lf	735
Feeder (EMT/CU) - 60A [2DP1C to SPD]	50 lf	14.69 /lf	735
Feeder (EMT/CU) - 60A [4DP1B to SPD]	50 lf	14.69 /lf	735
Feeder (EMT/CU) - 90A [2DP1A to KPP1A]	42 lf	15.96 /lf	670
Feeder (EMT/CU) - 100A [MSB to LP1A]	40 lf	20.74 /lf	830
Feeder (EMT/CU) - 100A [4DP1B to LP1B]	50 lf	20.74 /lf	1,037
Feeder (EMT/CU) - 100A [4DP1C to LP1C]	27 lf	20.74 /lf	560
Feeder (EMT/CU) - 100A [4DP1B to LP2B]	50 lf	20.74 /lf	1,037
Feeder (EMT/CU) - 100A [2DP1A to LP2C]	190 lf	20.74 /lf	3,940
Feeder (EMT/CU) - 100A [4DP1B to LP3B]	150 lf	20.74 /lf	3,111
Feeder (EMT/CU) - 100A [4DP1C to LP3C]	165 lf	20.74 /lf	3,422
Feeder (EMT/CU) - 100A [MSB to LP1D]	150 lf	20.74 /lf	3,111
Feeder (EMT/CU) - 100A [EHP1A to Elevator Controller]	125 lf	20.74 /lf	2,592
Feeder (EMT/CU) - 100A [TEP1A to TEP2B]	200 lf	20.74 /lf	4,148
Feeder (EMT/CU) - 100A [TEP1A to TEP2C]	200 lf	20.74 /lf	4,148
Feeder (EMT/CU) - 100A [TEP1A to TEP1D]	200 lf	20.74 /lf	4,148
Feeder (EMT/CU) - 100A [TEP1A to UPS]	50 lf	20.74 /lf	1,037
Feeder (EMT/CU) - 100A [2DP1A to MP1A]	410 lf	20.74 /lf	8,503
Feeder (EMT/CU) - 125A [UPS to EP1A]	150 lf	20.99 /lf	3,149
Feeder (EMT/CU) - 150A [2DP1B to MP1B]	50 lf	26.82 /lf	1,341
Feeder (EMT/CU) - 150A [2DP1C to MSB]	200 lf	26.82 /lf	5,365
Feeder (EMT/CU) - 150A [2DP1C to MP3C]	250 lf	26.82 /lf	6,706
Feeder (EMT/CU) - 150A [2DP1B to PP2B]	60 lf	26.82 /lf	1,609
Feeder (EMT/CU) - 150A [2DP1C to PP2C]	100 lf	26.82 /lf	2,682
Feeder (EMT/CU) - 150A [2DP1B to PP1B]	50 lf	26.82 /lf	1,341
Feeder (EMT/CU) - 150A [2DP1C to MP1C]	40 lf	26.83 /lf	1,073
Feeder (EMT/CU) - 150A [2DP1C to PP2C]	125 lf	26.82 /lf	3,353
Feeder (EMT/CU) - 150A [2DP1C to PP3C]	150 lf	26.82 /lf	4,024
Feeder (EMT/CU) - 150A [4DP1C to PP3B]	165 lf	26.82 /lf	4,426
Feeder (EMT/CU) - 150A [2DP1C to PP1C]	50 lf	26.82 /lf	1,341
Feeder (EMT/CU) - 150A [2DP1A to PP1D]	100 lf	26.82 /lf	2,682
Feeder (EMT/CU) - 200A [MSB to ATS-LS]	100 lf	32.13 /lf	3,213
Feeder (EMT/CU) - 200A [ATS-LS to ELP1A]	40 lf	32.13 /lf	1,285
Feeder (EMT/CU) - 200A [2DP1A to PP1A]	50 lf	32.13 /lf	1,607
Feeder (EMT/CU) - 200A [Cam Lock Box to ATS-LS]	60 lf	32.13 /lf	1,928
Feeder (EMT/CU) - 225A [MSB to Dimming Rack HDP]	250 lf	46.72 /lf	11,679



### 90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5010 Gear &amp; Distribution</b>			
Feeder (EMT/CU) - 225A [2DP1A to Dimming Rack SDP]	200 lf	46.72 /lf	9,344
Feeder (EMT/CU) - 225A [EHP1A to EHP3C]	250 lf	46.72 /lf	11,679
Feeder (EMT/CU) - 225A [MP3C to PP3C]	45 lf	46.72 /lf	2,102
Feeder (EMT/CU) - 225A [2DP1B to MP3B]	100 lf	46.72 /lf	4,672
Feeder (EMT/CU) - 225A [4DP1C to MHP3C]	165 lf	49.70 /lf	8,200
Feeder (EMT/CU) - 225A [ATS-OS to EHP1A]	200 lf	49.70 /lf	9,940
Feeder (EMT/CU) - 225A [MSB to ATS-OS]	75 lf	49.70 /lf	3,727
Feeder (EMT/CU) - 400A [MSB to MHP1A]	50 lf	73.75 /lf	3,688
Feeder (EMT/CU) - 400A [EHP1C to EHP1A]	100 lf	73.75 /lf	7,375
Feeder (EMT/CU) - 400A [Generator to ATS-LR] (interior)	430 lf	73.75 /lf	31,713
Feeder (EMT/CU) - 400A [MSB to ATS-LR]	375 lf	78.46 /lf	29,422
Feeder (EMT/CU) - 400A [MHP-LR to ATS-LR]	10 lf	78.46 /lf	785
Feeder (EMT/CU) - 400A [ATS-LR to MHP-LR]	50 lf	73.75 /lf	3,688
Feeder (EMT/CU) - 600A [MSB to 4DP1B]	200 lf	108.91 /lf	21,782
Feeder (EMT/CU) - 600A [MSB to 2DP1A]	70 lf	108.91 /lf	7,624
Feeder (EMT/CU) - 800A [MSB to 2DP1C]	125 lf	138.78 /lf	17,348
Feeder (EMT/CU) - 800A [MSB to 4DP1C]	200 lf	138.78 /lf	27,757
Empty conduit (EMT) - 3/4" [utility meter to switchboard]	75 lf	6.28 /lf	471
Feeder (MC) - 125A [75kVA]	30 lf	12.82 /lf	385
Feeder (MC) - 225A [75kVA]	30 lf	35.43 /lf	1,063
Feeder (MC) - 400A [225kVA]	90 lf	59.32 /lf	5,339
Feeder (MC) - 800A [225kVA]	90 lf	111.65 /lf	10,048
M.I. Cable - 4-1/c #6 [ELP1B to ELP3B]	150 lf	36.15 /lf	5,422
M.I. Cable - 4-1/c #3 [EHP1A to EP3C]	165 lf	65.42 /lf	10,794
M.I. Cable - 4-1/c #3 [ELP1A to EDP]	125 lf	65.42 /lf	8,178
M.I. Cable - 4-1/c #3 [ELP1A to EP1C]	125 lf	65.42 /lf	8,178
M.I. Cable - 4-1/c #2 [EPL1A to ELP1B]	150 lf	72.60 /lf	10,890
M.I. Cable - 4-1/c #2 [ELP1A to ELP1D]	417 lf	77.24 /lf	32,208
Quick term kit - #6 4-1/c	2 ea	359.96 /ea	720
Quick term kit - #3 4-1/c	6 ea	710.21 /ea	4,261
Quick term kit - #2 4-1/c	4 ea	734.64 /ea	2,939
Brass plate (per hole)	12 ea	92.10 /ea	1,105
Empty conduit - sch 40 PVC: 1 x 2" [future Canopy PV]	280 lf	26.88 /lf	7,526
Empty conduit - sch 40 PVC: 2 x 2" [future PV]	1,250 lf	35.04 /lf	43,800
Empty conduit - sch 40 PVC: 2 x 4" [future Canopy PV]	160 lf	45.14 /lf	7,222
ATS-OS: 225A, 277/480V, 4P, no iso by-pass - open transition	1 ea	6,752.90 /ea	6,753
ATS-LS: 150A, 277/480V, 4P, w/ iso by-pass - open transition	1 ea	11,058.30 /ea	11,058
ATS-LR: 400A, 277/480V, 4P, w/ iso by-pass - open transition	1 ea	19,961.43 /ea	19,961
Power junction w/feed (EMT) - 20A	1 ea	337.91 /ea	338
Empty conduit (EMT) - 3/4"	2,000 lf	5.11 /lf	10,218



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<i>D5010 Gear &amp; Distribution</i>	<b>136,600 sf</b>	<i>8.18 /sf</i>	<b>1,117,861</b>
<b>D5020 Lighting &amp; Branch Wiring</b>			
Lull, laborer for cleanup by Consigli (Electrical)	(1) ls	230,000.00 /ls	(230,000)
Trade support - lull, laborer for cleanup (Electrical)	1 ls	230,000.00 /ls	230,000
Science Classrooms - CO system solenoid shutdown- 120V power & control wiring	2 ea	5,326.40 /ea	10,653
Kitchen - Ansul system - 120V power & control wiring	1 ea	10,237.00 /ea	10,237
Gym scoreboards and shot clocks - wiring only, F&I by Div. 11	2 ea	5,344.80 /ea	10,690
On-site programming & startup (manufacturer)	1 ls	3,913.41 /ls	3,913
Single pole switch (120/277V)	13 ea	65.04 /ea	845
Key op switch (120/277V)	2 ea	72.44 /ea	145
Three position momentary contact switch	1 ea	226.42 /ea	226
Ceiling PIR occupancy sensor (24VDC)	323 ea	247.23 /ea	79,854
Occupancy sensor power packs (120V)	200 ea	82.04 /ea	16,408
Wall dimmer switch (0-10V)	227 ea	131.04 /ea	29,746
Photocells (daylight harvesting)	84 ea	265.06 /ea	22,265
Universal dimming room controller, 1-channel	50 ea	536.88 /ea	26,844
ALCS master switching / dimming station	1 ea	821.83 /ea	822
Plug load controllers (20A/120V)	50 ea	300.80 /ea	15,040
Emergency lighting transfer (bypass relay) - non-dimming	30 ea	236.81 /ea	7,104
Astronomical time clock	1 ea	919.97 /ea	920
Rough in for Theater Lighting - Allowance	1 allw	9,400.01 /allw	9,400
Power for Theater Lighting - Allowance	1 allw	28,199.87 /allw	28,200
Sub lighting control panels	3 ea	2,394.56 /ea	7,184
Master lighting control panel	1 ea	4,383.41 /ea	4,383
Energy control unit	1 ea	2,157.58 /ea	2,158
System server unit	1 ea	1,316.75 /ea	1,317
Network Ethernet switch	1 ea	2,270.85 /ea	2,271
MC Cable (12/2) - 20A	12,500 lf	3.45 /lf	43,126
MC Cable (12/3) - 20A	3,500 lf	3.87 /lf	13,541
EMT (12/2) - 20A	2,000 lf	6.70 /lf	13,404
EMT (12/2) - 20A	50 lf	7.13 /lf	356
RJ45 Cable, 25LF (plenum-rated)	407 ea	72.10 /ea	29,344
RJ45 Cable, 50LF (plenum rated)	228 ea	111.05 /ea	25,318
MC Cable (12/2) - 20A	11,370 lf	3.45 /lf	39,227
MC Cable (10/2) - 20A [homeruns - x372]	24,180 lf	4.36 /lf	105,516
EMT (12/2) - 20A	2,000 lf	6.70 /lf	13,404
PVC (10/2) - 20A	450 lf	6.68 /lf	3,007
Duplex receptacle - 20A - tamper resistant	497 ea	78.60 /ea	39,065
Duplex receptacle - 20A - switched with IO module	14 ea	67.78 /ea	949



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5020 Lighting &amp; Branch Wiring</b>			
Simplex receptacle - 20A [scoreboard control]	2 ea	70.18 /ea	140
Duplex receptacle - 20A - GFCI	187 ea	92.44 /ea	17,286
Duplex receptacle - 20A - GFCI - W.P.	29 ea	129.27 /ea	3,749
Duplex receptacle - 20A [kitchen equipment] - circuitry in Equipment Wiring]	33 ea	67.79 /ea	2,237
Duplex receptacle - 20A [A/V]	9 ea	67.79 /ea	610
Duplex receptacle - 20A [CR]	8 ea	67.80 /ea	542
Exterior pedestal receptacle, GFI type, Wayne Tyler, Inc. #CB-BOX	5 ea	1,292.26 /ea	6,461
Quadruplex receptacle - 20A	325 ea	93.78 /ea	30,479
Quadruplex receptacle - 20A - switched with IO module	18 ea	93.79 /ea	1,688
Duplex receptacle - 20A - USB	14 ea	99.44 /ea	1,392
Specialty receptacle - 20A - L5-20R	11 ea	101.01 /ea	1,111
Specialty receptacle - 20A - L14-20R	1 ea	104.81 /ea	105
Specialty receptacle - 30A - L5-30R	23 ea	111.69 /ea	2,569
Quadruplex receptacle - 20A - GFCI	5 ea	143.12 /ea	716
Hardwired A/C junction (MC) - 20A [A/V]	2 ea	318.93 /ea	638
Hardwired A/C junction (MC) - 20A [fume hoods]	4 ea	318.93 /ea	1,276
Power junction w/feed (MC) - 20A [water coolers/bottle fillers]	11 ea	221.21 /ea	2,433
Power junction w/feed (MC) - 20A	28 ea	221.21 /ea	6,194
Trash compactor feed & connection	2 ea	2,243.92 /ea	4,488
Overhead door power & connection	3 ea	1,223.50 /ea	3,671
Dock leveler feed & connection	1 ea	3,532.90 /ea	3,533
Emergency power offs (EPO)	10 ea	295.11 /ea	2,951
Wiremold receptacles - G4	110 ea	31.05 /ea	3,416
G4000 dual-channel wiremold - 24" spacing	220 lf	63.39 /lf	13,945
LK24: 2'x2' lay-in fixture [O]	24 ea	198.57 /ea	4,766
SPFL: LED flood light [C]	20 ea	682.90 /ea	13,658
SPNF: LED flood light, narrow [C]	20 ea	682.90 /ea	13,658
LR2 (emerg): 2' linear 2" aperature recessed luminaire [O]	183 ea	300.48 /ea	54,987
LR2: 2' linear 2" aperature recessed luminaire [O]	912 ea	300.48 /ea	274,033
G4: 4' linear rugged low profile 360 deg adjustable flood luminaire [O]	80 ea	2,155.93 /ea	172,474
LS4: 4' utility fixtre with frosted acrylic diffuser [O]	20 ea	246.16 /ea	4,923
LS4 (emerg): 4' utility fixture with frosted acrylic diffuser [O]	14 ea	246.16 /ea	3,446
LS8: 8' utility fixtre with frosted acrylic diffuser [O]	11 ea	411.94 /ea	4,531
LS4A (emerg): 4' utility fixtre with frosted acrylic diffuser [O]	12 ea	494.94 /ea	5,939
LS4A: 4' utility fixture with frosted acrylic diffuser [O]	12 ea	494.94 /ea	5,939
LP8 (emerg): Axis 8' LED fixture [O]	9 ea	1,027.94 /ea	9,251
LS8 (emerg): 8' utility fixture with frosted acrylic diffuser [O]	10 ea	411.94 /ea	4,119
JB: utility fixture with frosted tempered glass globe & guard [O]	4 ea	245.95 /ea	984



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5020 Lighting &amp; Branch Wiring</b>			
PC3: 6" down light fixture with dead-front gasketed trim [O]	1 ea	298.16 /ea	298
LRW (emerg): 6" aperature LED linear recessed fixture / qty. of 18 [C]	114 lf	146.99 /lf	16,757
PC1: 4" down light fixture, 0-10V dimming capable [O]	24 ea	298.16 /ea	7,156
RC1: 6" down light fixture [O]	45 ea	271.54 /ea	12,219
RC1 (emerg): 6" down light fixture [O]	18 ea	271.54 /ea	4,888
LS2 (emerg): 2' utility fixture [O]	2 ea	177.98 /ea	356
LSV4: 4' linear utility fixture with prismatic polcarbonate lens [C]	4 ea	675.93 /ea	2,704
RC2: 4" down light fixture, 0-10V dimming [O]	8 ea	230.56 /ea	1,844
LR4: 4' linear 2" aperature recessed luminaire with frosted lens [O]	1 ea	410.45 /ea	410
LUL: LED tape light with AL channel [C]	1,840 lf	88.49 /lf	162,829
LC3: linear cove Xeleum lighting / qty. of 96 [O]	1,925 lf	121.99 /lf	234,826
LWW: LED tape light with AL channel [C]	1,408 lf	88.49 /lf	124,599
RSH: 6" down light fixture with dead-front gasketed trim [O]	1 ea	306.54 /ea	307
LC2: linear cove fixture with frosted diffuser / qty. of 10 [O]	76 lf	148.23 /lf	11,265
PC2: 6" down light fixture with dead-front gasketed trim [O]	28 ea	298.16 /ea	8,348
LCL: LED tape light with AL channel [C]	3,051 lf	88.49 /lf	269,994
LSL: LED strip mounted on edge of stage / qty. of 1	59 lf	305.95 /lf	18,051
Exit sign, ceiling mounted, double sided [O]	34 ea	196.16 /ea	6,669
Exit sign, ceiling mounted, single sided [O]	16 ea	183.16 /ea	2,931
Exit sign, wall mounted	18 ea	313.16 /ea	5,637
Exit sign, ceiling mounted, single sided - handicap [O]	2 ea	433.16 /ea	866
LRC (emerg): 6" aperature LED linear recessed fixture / qty. of 46 [C]	596 lf	161.70 /lf	96,373
MC Cable (12/2) - 20A (concealed branch)	12,068 lf	3.67 /lf	44,291
MC Cable (10/2) - 20A (concealed homeruns)	2,400 lf	4.64 /lf	11,142
EMT (12/2) - 20A (exposed branch)	4,023 lf	7.13 /lf	28,679
EMT (10/2) - 20A (exposed homeruns)	500 lf	8.58 /lf	4,290
SL4: LED egress / perimeter lighting fixture - custom color/finish [O]	40 ea	565.36 /ea	22,614
MC Cable (12/2) - 20A	1,200 lf	3.67 /lf	4,404
<i>D5020 Lighting &amp; Branch Wiring</i>	<b>136,600 sf</b>	<b>17.61 /sf</b>	<b>2,405,966</b>

**D5030 Communications & Security**

Externally mounted SPD's	6 ea	3,131.70 /ea	18,790
Tel/data J-hook system (plenum)	136,600 sf	0.19 /sf	25,681
Cable tray - 18"W (IDF/MDF only)	200 lf	75.55 /lf	15,109
Empty conduit (EMT) - 2"	650 lf	11.19 /lf	7,271
Copper ground bar w/isolators - 2"x1/4"	4 ea	280.03 /ea	1,120
Conduit sleeve w/ fireproofing - 4"	20 ea	201.11 /ea	4,022
Data outlet - (1) CAT-6A cable	20 ea	264.84 /ea	5,297
Data outlet - (1) CAT-6A cable [audio-visual]	12 ea	264.84 /ea	3,178



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5030 Communications &amp; Security</b>			
Data outlet - (2) CAT-6A cables	131 ea	466.16 /ea	61,067
Tel/data outlet - (3) CAT-6A cables	91 ea	652.82 /ea	59,407
Floor box tel/data outlet - (3) CAT-6A cables	2 ea	652.83 /ea	1,306
Voice outlet - (1) CAT-6A cable (WAP's by Owner)	79 ea	263.70 /ea	20,832
Wireless access point - (1) CAT-6A cable (WAP's by Owner)	138 ea	263.70 /ea	36,390
TVE - Video outlet	56 ea	838.75 /ea	46,970
TVC - Video outlet	2 ea	838.77 /ea	1,678
Double gang junction box with (4) 1" C	54 ea	482.68 /ea	26,065
FO - 12 strand SM	1,750 lf	5.27 /lf	9,225
FO - 12 strand MM	1,500 lf	7.10 /lf	10,642
4-Post Full Height Rack	10 ea	1,170.17 /ea	11,702
Vertical cable wire manager	20 ea	314.09 /ea	6,282
Horizontal cable wire manager	10 ea	80.25 /ea	803
Copper patch panel - 96 port	15 ea	1,244.28 /ea	18,664
Fiber optic patch panel - 24 port	6 ea	570.06 /ea	3,420
Fiber enclosure (rack mtd.)	6 ea	485.85 /ea	2,915
Network switch - 24 port	2 ea	5,390.24 /ea	10,780
S1: wall mounted loudspeaker - 1 gang metal box w/ cover	2 ea	228.33 /ea	457
S2: ceiling loud speaker - custom backbox	6 ea	308.23 /ea	1,849
S3: ceiling loud speaker - 4" SQ metal box w/ cover	16 ea	179.94 /ea	2,879
S4: ceiling loud speaker - 4" SQ metal box w/ cover	2 ea	251.94 /ea	504
S5: ceiling loud speaker - 4" SQ metal box w/ cover (New)	2 ea	245.27 /ea	491
D1: display back box, Chief PAC-526	3 ea	371.35 /ea	1,114
F1: floor box, FSR FL-500P-6 floor box w/ finished cover	1 ea	469.58 /ea	470
V1: wall mounted video projector - 1 gang metal box w/ cover	1 ea	179.47 /ea	179
R1: receptacle panel - 2 gang metal box w/ cover	3 ea	242.43 /ea	727
R2: receptacle panel - 12"x12"x4" NEMA-1 enclosure w/ oversized flush	2 ea	242.43 /ea	485
R3: receptacle panel - 3 gang metal box w/ cover	4 ea	311.69 /ea	1,247
R5: receptacle panel - 3 gang metal box w/ cover	1 ea	242.43 /ea	242
R6: receptacle panel - 12"x12"x4" NEMA-1 enclosure w/ oversized flush	2 ea	405.94 /ea	812
BP: wall mounted button panel - 1 gang metal box w/ cover	3 ea	221.77 /ea	665
J1: junction box - type 1 - 12"x12"x4" NEMA-1 enclosure w/ oversized flush	2 ea	723.57 /ea	1,447
J2: junction box - type 2 - 18"x18"x4" NEMA-1 enclosure w/ oversized flush	1 ea	844.78 /ea	845
J3: junction box - type 3 - same as Type 2	3 ea	844.78 /ea	2,534
A1: Wall mounted antenna - 1 gang deep metal box w/ cover	2 ea	159.74 /ea	319
A2: Wall mounted antenna - 1 gang deep metal box w/ cover	1 ea	159.74 /ea	160



### 90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5030 Communications &amp; Security</b>			
A3: Ceiling mounted antenna - 4" SQ metal box w/ cover	2 ea	138.32 /ea	277
A4: Ceiling mounted antenna - 4" SQ metal box w/ cover	1 ea	138.31 /ea	138
PS: Production communication speaker station - 4 gang deep metal box w/ cov	5 ea	385.28 /ea	1,926
PC: Production communication - 1 gang deep metal box w/ cover	1 ea	134.38 /ea	134
T1: Wall mounted touch panel - 3 gang metal box w/ cover	2 ea	249.04 /ea	498
VC: Wall mounted audio volume control - 1 gang deep metal box	2 ea	134.39 /ea	269
MC: Motor controller - 4" SQ metal box w/ cover	3 ea	86.46 /ea	259
C1: Wall mounted camera - 2 gang deep metal box w/ cover	1 ea	193.57 /ea	194
A/V Equipment Rack	2 ea	1,001.85 /ea	2,004
M1: Ceiling mounted microphone - 1 gang deep metal box w/ cover	1 ea	134.38 /ea	134
Intercom sub-stations	6 ea	1,009.28 /ea	6,056
Intercom master-stations	5 ea	3,327.13 /ea	16,636
Speaker - ceiling mouted	269 ea	405.93 /ea	109,194
Speaker - wall mounted	32 ea	611.85 /ea	19,579
Volume control	24 ea	177.96 /ea	4,271
Power supply (80) units - speakers 24V DC	4 ea	2,661.71 /ea	10,647
PA console	1 ea	14,251.90 /ea	14,252
PA equipment power connection - 120V	1 ea	256.53 /ea	257
AM/FM/CD/DVD tuner	1 ea	694.40 /ea	694
Speaker system testing	1 ea	1,986.71 /ea	1,987
Two way communication call box (recessed)	20 ea	799.75 /ea	15,995
Power supply w/battery back up	1 ea	1,714.28 /ea	1,714
Two way communication base station (28 zone)	1 ea	5,980.66 /ea	5,981
Tel/data outlet - (1) CAT-6A cable	20 ea	264.84 /ea	5,297
Tel/data outlet - (2) CAT-6A cables	1 ea	466.16 /ea	466
System testing	1 ea	1,016.70 /ea	1,017
Clock, wall mounted - 12" round	126 ea	283.06 /ea	35,665
Master clock w/ roof mounted antenna	1 ea	3,778.57 /ea	3,779
Wireless clock repeater	1 ea	647.06 /ea	647
Wireless clock transciever	1 ea	647.06 /ea	647
Program unit	1 ea	991.96 /ea	992
Speaker baffle, clock back box	74 ea	202.78 /ea	15,006
Wire guard	20 ea	57.70 /ea	1,154
Clock wiring (EMT)	700 lf	7.03 /lf	4,923
Clock wiring (RS-485 plenum)	500 lf	3.08 /lf	1,540
System testing	1 ls	33.83 /ls	34
Card readers	22 ea	1,163.83 /ea	25,604
Card readers - W.P.	3 ea	1,967.78 /ea	5,903
Electro-magnetic lock	6 ea	657.91 /ea	3,947





90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5030 Communications &amp; Security</b>			
Request to exit motion sensor	26 ea	322.33 /ea	8,380
Electric strike	40 ea	400.49 /ea	16,020
Thermal disconnecting means	20 ea	427.58 /ea	8,552
24V power supply	20 ea	295.11 /ea	5,902
Junction box - 6"x6"x4"	20 ea	130.61 /ea	2,612
Power transfer hinge	20 ea	377.68 /ea	7,554
Intrusion digital keypads	4 ea	984.97 /ea	3,940
Dual tech motion detectors	77 ea	595.80 /ea	45,876
Door contacts	63 ea	465.74 /ea	29,342
Access control panel	1 ea	8,222.56 /ea	8,223
Tie in to lighting control system	1 ea	402.23 /ea	402
Security wiring - cable	7,500 lf	3.80 /lf	28,527
Security wiring (EMT)	2,250 lf	8.53 /lf	19,181
Power junctions - 120V/20A	2 ea	193.20 /ea	386
Connect to CCTV system	1 ea	665.43 /ea	665
Proximity cards	250 ea	2.35 /ea	588
Software / licenses, programming, testing, startup (manufacturer)	1 ea	13,308.52 /ea	13,309
CCTV color monitors	2 ea	815.52 /ea	1,631
360-degree multi-sensor interior cameras	28 ea	1,659.85 /ea	46,476
Dome I.P. camera - exterior	19 ea	1,996.28 /ea	37,929
Dome I.P. camera - interior - fixed	27 ea	1,471.85 /ea	39,740
Camera monitoring station	1 ea	1,330.85 /ea	1,331
Video recorders	2 ea	3,131.71 /ea	6,263
Video switchers	2 ea	1,627.71 /ea	3,255
Camera wiring (EMT)	2,500 lf	8.76 /lf	21,899
Camera wiring - cable	7,400 lf	4.04 /lf	29,885
Power junction - 120V/20A	2 ea	193.20 /ea	386
Software / licenses, programming, testing, startup (manufacturer)	1 ea	13,308.52 /ea	13,309
<i>Temporary fire alarm heat detection coverage / stairwell pull stations / temp notification - N/A</i>	-	/-	
Fire alarm impairment plan (NFPA-101)	1 ls	10,000.00 /ls	10,000
Elevator fire alarm interfacing	1 ls	5,000.00 /ls	5,000
Manual pull stations	25 ea	202.12 /ea	5,053
Smoke detectors	82 ea	220.39 /ea	18,072
Smoke detector w/ elevator recall	3 ea	373.26 /ea	1,120
Smoke detectors (for Atrium)	89 ea	220.39 /ea	19,615
Smoke detectors w/ elevator recall (for Atrium)	3 ea	373.25 /ea	1,120
Carbon monoxide detector (w/ monitor module)	5 ea	367.16 /ea	1,836
Beam detector (receiver & transmitter)	5 ea	416.88 /ea	2,084
Duct smoke detector (furnish & wire)	40 ea	838.91 /ea	33,556



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5030 Communications &amp; Security</b>			
Remote test switch w/ indicating light	40 ea	194.88 /ea	7,795
Control modules	20 ea	265.75 /ea	5,315
Addressable monitor modules	30 ea	160.83 /ea	4,825
Tamper switch connection (via monitor module)	8 ea	560.06 /ea	4,480
Flow switch connection (via monitor module)	8 ea	403.67 /ea	3,229
Door hold device (magnetic)	5 ea	388.88 /ea	1,944
Wire motorized dampers (120V)	14 ea	407.48 /ea	5,705
Wire combination fire/smoke damper (120V & SLC)	20 ea	608.50 /ea	12,170
Strobe only	48 ea	175.36 /ea	8,417
Speaker/strobes	150 ea	246.56 /ea	36,983
Speaker/strobe - W.P.	1 ea	309.72 /ea	310
Horn/visual - wall mounted	52 ea	222.79 /ea	11,585
Exterior beacons (weatherproof)	4 ea	388.83 /ea	1,555
Fire alarm transponder panels	6 ea	928.51 /ea	5,571
Fire alarm annunciators w/ microphones	3 ea	2,107.39 /ea	6,322
FACP w/ 60-minute battery backup (Notifier NFS640)	1 ea	6,999.66 /ea	7,000
Masterbox (local energy)	1 ea	4,212.70 /ea	4,213
Key (Knox) box	2 ea	806.43 /ea	1,613
Smoke control panel	1 ea	19,502.56 /ea	19,503
Generator monitoring control panel	1 ea	571.80 /ea	572
Fire pump/jockey pump connection	1 ea	402.23 /ea	402
Fire alarm graphic maps	3 ea	1,454.56 /ea	4,364
Fire alarm comissioning	1 ea	6,158.00 /ea	6,158
Fire alarm testing (manufacturer)	6 ea	1,338.28 /ea	8,030
Fire alarm system programming	397 ea	20.79 /ea	8,254
FPLP cable (red) - #14-4/c	11,475 lf	2.23 /lf	25,589
FPLP cable (red) - #16-2/c	12,330 lf	1.83 /lf	22,564
EMT (red) - 3/4"C w/ #16-2/c (exposed)	2,500 lf	7.19 /lf	17,981
EMT (red) - 3/4"C w/ #14-4/c (exposed)	1,200 lf	7.95 /lf	9,535
Circuit integrity cabling (CIC)	1,500 lf	18.31 /lf	27,465
BDA system - parts & smarts (dual-frequency)	136,600 sf	0.47 /sf	64,202
BDA system - installation & minor material (dual-frequency)	136,600 sf	0.19 /sf	25,681
Directional couplers	20 ea	1,150.35 /ea	23,007
In-Line connectors	20 ea	249.01 /ea	4,980
Lightning protection units	5 ea	1,995.53 /ea	9,978
<i>D5030 Communications &amp; Security</i>	<b>136,600 sf</b>	<b>12.09 /sf</b>	<b>1,652,074</b>

**D5090 Other Electrical Systems**

LEED Silver - premium (T.B.D.)	1 ls	9,400.00 /ls	9,400
Temp light stringers & GFCI power	136,600 sf	0.35 /sf	47,810



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>D5090 Other Electrical Systems</b>			
Temp 480Y/277V electrical service (400A)	3 ea	18,226.22 /ea	54,679
Material handling / project mgmt.	250 mh	97.71 /mh	24,428
3D/BIM coordination	500 mh	97.71 /mh	48,856
Record drawings / as-builts	1 ea	5,318.52 /ea	5,319
Seismic & testing (panels, generator, lighting control, fire alarm)	1 ls	18,800.00 /ls	18,800
Coring - patching - firestopping	136,600 sf	0.09 /sf	12,840
Project phasing (re-mobilization)	1 ls	9,400.00 /ls	9,400
Hoisting & rigging (generator & switchboard)	2 ls	7,050.00 /ls	14,100
Building grounding & bonding	136,600 sf	0.11 /sf	15,408
SPD grounding (internal and external)	47 ea	120.29 /ea	5,653
Dry-type transformer grounding	4 ea	213.22 /ea	853
Copper ground bar - 2"x1/4" (ea.)	5 ea	280.03 /ea	1,400
Natural gas generator: 350kW / 437.5kVA	1 ea	133,322.25 /ea	133,322
Generator testing & start-up	1 ea	1,863.20 /ea	1,863
Generator annunciator panel	1 ea	1,447.40 /ea	1,447
Battery charger circuit (4#10 & 1#10G in 1"C)	140 lf	20.94 /lf	2,932
Jacket heater circuit	140 lf	34.49 /lf	4,828
Oil heater circuit	140 lf	53.66 /lf	7,512
Exterior W.P. sound attenuating enclosure (350kW)	1 ea	19,478.75 /ea	19,479
Remote status panel circuit	140 lf	9.64 /lf	1,349
Starting circuits - 2#14 MI cable	140 lf	12.76 /lf	1,787
Remote annunciator panel - 16#14 (EMT)	100 lf	15.81 /lf	1,581
Quick connect switch, ESL Storm Switch 3020	1 ea	3,668.10 /ea	3,668
UPS: 480-208/120V, 24kW (static ts,manual by-pass, 8min batt.BU)	2 ea	30,061.40 /ea	60,123
Lightning prevention system subcontractor	1 ls	30,000.00 /ls	30,000
<i>D5090 Other Electrical Systems</i>	<b>136,600 sf</b>	<b>3.95 /sf</b>	<b>538,839</b>
<b>D50 Electrical Systems</b>	<b>136,600 sf</b>	<b>41.84 /sf</b>	<b>5,714,740</b>
<b>D Services</b>	<b>136,600 sf</b>	<b>122.48 /sf</b>	<b>16,731,287</b>

E Equipment & Furnishings

E10 Equipment

E1020 Institutional Equipment

Loading dock equipment	1 ls	1,000.00 /ls	1,000
Misc. appliances	1 ls	10,000.00 /ls	10,000
Food service equipment - Allowance	1 ls	415,270.00 /ls	415,270
Vocational shop equipment	1 ls	25,000.00 /ls	25,000
- Welding booths - In Above	-	/-	
- Portable welding fumes extractor - In Above	-	/-	
- Paint spray hoods - In Above	-	/-	
- Portable wood working equipment dust collector - In HVAC	-	/-	



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>E1020 Institutional Equipment</b>			
Kiln	1 ls	12,000.00 /ls	12,000
Sound systems @ Auditorium - Allowance	1 allw	200,000.00 /allw	200,000
Sound systems @ Gym - Allowance	1 allw	120,000.00 /allw	120,000
Sound systems @ Cafeteria - Allowance	1 allw	50,000.00 /allw	50,000
Sound systems @ Band/Chorus - Allowance	2 allw	30,000.00 /allw	60,000
Sound systems @ Drama - Allowance	1 allw	20,000.00 /allw	20,000
Projection screen @ Gym, Cafeteria	2 ea	10,000.00 /ea	20,000
Projection screen	1 ea	5,000.00 /ea	5,000
<i>Orchestra enclosures - FFE</i>	-	/-	
Theatrical rigging - Allowance	1 ls	158,300.00 /ls	158,300
Theatrical draperies - Allowance	1 ls	33,854.00 /ls	33,854
Theatrical lighting instruments & accessories - Allowance	1 ls	129,018.00 /ls	129,018
Theatrical lighting controls - Allowance	1 ls	95,749.00 /ls	95,749
Basketball backstop - ceiling-hung	6 ea	6,500.00 /ea	39,000
Gym divider curtain - electric roll up	1,530 sf	20.00 /sf	30,600
Athletic wall padding	835 sf	12.50 /sf	10,438
Volleyball system	1 ls	5,000.00 /ls	5,000
Fixed audience seating	406 ea	285.00 /ea	115,710
Retractable Bleachers at Gym	650 seat	155.00 /seat	100,750
<i>E1020 Institutional Equipment</i>	<b>136,600 sf</b>	<b>12.13 /sf</b>	<b>1,656,689</b>
<b>E1090 Other Equipment</b>			
Refrigerator	7 ea	1,200.00 /ea	8,400
<i>Ice maker - None shown</i>	-	/-	
<i>Undercounter refrigerator - None shown</i>	-	/-	
Microwave oven	1 ea	450.00 /ea	450
Range hood	1 ea	650.00 /ea	650
Range	1 ea	900.00 /ea	900
Dishwasher	4 ea	925.00 /ea	3,700
Washer/dryer - stackable	2 ea	1,500.00 /ea	3,000
Scoreboards - basketball	1 ea	7,500.00 /ea	7,500
<i>E1090 Other Equipment</i>	<b>136,600 sf</b>	<b>0.18 /sf</b>	<b>24,600</b>
<b>E10 Equipment</b>	<b>136,600 sf</b>	<b>12.31 /sf</b>	<b>1,681,288</b>
<b>E20 Furnishings</b>			
<b>E2010 Fixed Furnishings</b>			
Hardwood trim @ locker guardrail per A650	3,300 lf	15.00 /lf	49,500
P-lam top panels @ locker guardrail per A650	1,025 lf	50.00 /lf	51,250
P-lam side panels @ locker guardrail per A650	450 lf	50.00 /lf	22,500
Casework for lockers (bank of 5) - including base	1,025 lf	250.00 /lf	256,250



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>E2010 Fixed Furnishings</b>			
P-lam base cabinet w/top	40 lf	450.00 /lf	18,000
P-lam workstation w/top	770 lf	250.00 /lf	192,500
Mobile storage	172 ea	550.00 /ea	94,600
P-lam valance for fin tube	570 lf	45.00 /lf	25,650
P-lam 3/4" lip at counter for fin tube	570 lf	4.00 /lf	2,280
P-lam wall cabinet	40 lf	325.00 /lf	13,000
P-lam full height cabinet	50 lf	700.00 /lf	35,000
Bathroom vanity w/top	210 lf	250.00 /lf	52,500
Reception cabinet	20 lf	1,000.00 /lf	20,000
P-lam circulation desk	10 lf	750.00 /lf	7,500
P-lam work counter @ Admin	10 lf	1,500.00 /lf	15,000
P-lam counter @ Servery	32 lf	200.00 /lf	6,400
P-lam end/filler panels @ Admin	10 lf	135.00 /lf	1,350
Mailboxes	18 lf	415.00 /lf	7,470
Storage shelving	380 lf	150.00 /lf	57,000
Storage shelving w/MDF	470 lf	200.00 /lf	94,000
P-lam bookcases	40 lf	500.00 /lf	20,000
Built-in benches	205 lf	600.00 /lf	123,000
Display cases	5 ea	4,500.00 /ea	22,500
Misc. casework - Allowance	136,600 sf	1.00 /sf	136,600
Misc. lab equipment - Allowance	1 ls	25,000.00 /ls	25,000
Fume hoods	3 ea	11,000.00 /ea	33,000
Roller shades	11,205 sf	10.00 /sf	112,050
Roller shades - interior	3,300 sf	10.00 /sf	33,000
Roller shades - doors	50 ea	150.00 /ea	7,500
Base cabinet w/epoxy top	30 lf	600.00 /lf	18,000
Epoxy countertop - open below	325 lf	375.00 /lf	121,875
Epoxy backsplash	635 lf	60.00 /lf	38,100
Wall cabinets	105 lf	400.00 /lf	42,000
<i>E2010 Fixed Furnishings</i>	<b>136,600 sf</b>	<b>12.84 /sf</b>	<b>1,754,375</b>
<b>E20 Furnishings</b>	<b>136,600 sf</b>	<b>12.84 /sf</b>	<b>1,754,375</b>
<b>E Equipment &amp; Furnishings</b>	<b>136,600 sf</b>	<b>25.15 /sf</b>	<b>3,435,664</b>

F Special Construction & Demolition

F20 Demolition

F2010 Building Elements Demolition

Building demolition	195,400 sf	7.00 /sf	1,367,800
<i>F2010 Building Elements Demolition</i>	<b>194,500 sf</b>	<b>7.03 /sf</b>	<b>1,367,800</b>

F2020 Hazardous Component Abatement



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>F2020 Hazardous Component Abatement</b>			
Asbestos abatement	195,400 sf	8.20 /sf	1,602,280
<i>F2020 Hazardous Component Abatement</i>	194,500 sf	8.24 /sf	1,602,280
<b>F20 Demolition</b>	<b>194,500 sf</b>	<b>15.27 /sf</b>	<b>2,970,080</b>
<b>F Special Construction &amp; Demolition</b>	<b>194,500 sf</b>	<b>15.27 /sf</b>	<b>2,970,080</b>

G Sitework

G10 Site Preparation

G1010 Site Clearing

Mobilizations	BP#1	/BP#1
Survey/layout	BP#1	/BP#1
Police details	BP#1	/BP#1
Precast Concrete Jersey Barriers for Temp. Parking Lot	BP#1	/BP#1
Temporary site signage	BP#1	/BP#1
As-built plan preparation	BP#1	/BP#1
Localized dewatering	BP#1	/BP#1
Clear & grub, vegetation removal	BP#1	/BP#1
Strip & stockpile topsoil/loam	BP#1	/BP#1
Construct Phase 2 Temp. Sediment Basins	BP#1	/BP#1
SWPPP (Prep of SWPPP by civil engineer)	BP#1	/BP#1
12"diameter Straw Wattles	BP#1	/BP#1
Silt sacks at catch basin	BP#1	/BP#1
Construction entrance	BP#1	/BP#1
Street sweeping	BP#1	/BP#1
Inspect / repair silt barrier weekly	BP#1	/BP#1
Remove erosion control measure at project completion	BP#1	/BP#1
Asphalt paving - Temp. Parking Layout	BP#1	/BP#1
Temporary roads and maintenance required during construction	BP#1	/BP#1
G1010 Site Clearing	136,600 sf	/sf

G1020 Site Demolition & Relocations

Demo hydrants	BP#1	/BP#1
Demo bituminous concrete paving	BP#1	/BP#1
Demo bituminous walk	BP#1	/BP#1
Demo Temporary Bituminous Parking & Access Pavement	BP#1	/BP#1
Demo concrete sidewalks/pads/ramps	BP#1	/BP#1
Demo curbing	BP#1	/BP#1
Cut & cap site utilities - water	BP#1	/BP#1
Cut & cap site utilities - sewer	BP#1	/BP#1
Demo utility piping - water	BP#1	/BP#1
Demo utility piping - sewer	BP#1	/BP#1



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>G1020 Site Demolition &amp; Relocations</b>			
Demo utility piping - electrical	BP#1	/BP#1	
Demo utility piping - drain	BP#1	/BP#1	
Demo utility piping - gas	BP#1	/BP#1	
Demo drain structures	BP#1	/BP#1	
Demo grease trap	BP#1	/BP#1	
Demo fencing/guardrail	BP#1	/BP#1	
Misc. site demolition	BP#1	/BP#1	
Demo utility poles	BP#1	/BP#1	
Flag pole	1 ea	9,000.00 /ea	9,000
G1020 Site Demolition & Relocations	136,600 sf	0.07 /sf	9,000
<b>G1030 Site Earthwork</b>			
Preconstruction survey and vibration monitoring & compliance	BP#1	/BP#1	
Rough grading	BP#1	/BP#1	
Fine grading - building SOG	BP#1	/BP#1	
Fine grading - paving	BP#1	/BP#1	
Fine grading - conc walks & site pads	BP#1	/BP#1	
Fine grading - bituminous walks	BP#1	/BP#1	
Cut to subgrade @ site	BP#1	/BP#1	
Fill to subgrade from cut @ site	BP#1	/BP#1	
Grind foundations for fill - In Demolition	-	/-	
Fill to subgrade @ site - import	BP#1	/BP#1	
Site cuts to stockpile for temporary parking & access layout	BP#1	/BP#1	
Site surcharge	BP#1	/BP#1	
Contaminated soil removal - unlined landfill	BP#1	/BP#1	
Rock removal - NIC	-	/-	
Import loam & spread (6") at Lawns, Athletic Fields & Native Meadows	5,594 cy	40.00 /cy	223,760
Ammend & spread (6") at Lawns, Athletic Fields & Native Meadows	6,030 cy	12.00 /cy	72,360
Import loam & spread (6") at Detention Basins	802 cy	40.00 /cy	32,080
Import loam & spread (12") at Plant Beds	375 cy	40.00 /cy	15,000
Landscape Metal Edging at Building Mow Strip	2,330 lf	15.00 /lf	34,950
Building Mowing Strip- (Peastone)	100 tn	50.00 /tn	5,000
Import loam & spread (6") at Sodded Amphlitheather Lawns	691 cy	40.00 /cy	27,640
G1030 Site Earthwork	136,600 sf	3.01 /sf	410,790
<b>G10 Site Preparation</b>	<b>136,600 sf</b>	<b>3.07 /sf</b>	<b>419,790</b>

G20 Site Improvements

G2010 Roadways

Street plates for protection	BP#1	/BP#1	
------------------------------	------	-------	--



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
G2010 Roadways	136,600 sf	/sf	
<b>G2020 Parking Lots</b>			
Gravel base course @ asphalt pavements	BP#1	/BP#1	
Gravel base course @ Raised Stamped asphalt pavement at Flagg Drive	BP#1	/BP#1	
1 1/2" crushed stone base course - concrete walks & site pads	BP#1	/BP#1	
Asphalt paving - (Parking Lots & Site Drives)	BP#1	/BP#1	
Asphalt paving - top course @ temporary to permanent	BP#1	/BP#1	
Precast concrete curbs	BP#1	/BP#1	
Vertical granite curbs	BP#1	/BP#1	
Handicapped ramps at curbing	BP#1	/BP#1	
Detectable Warning Plates at Handicapped Ramps	BP#1	/BP#1	
Speed bumps - bituminous	BP#1	/BP#1	
Pavement markings	BP#1	/BP#1	
Parking signage	BP#1	/BP#1	
G2020 Parking Lots	136,600 sf	/sf	
<b>G2030 Pedestrian Paving</b>			
Processed Aggregate base course - bituminous walks	BP#1	/BP#1	
Concrete pavement	BP#2	/BP#2	
Steps - premium	BP#2	/BP#2	
Dumpster pad	BP#2	/BP#2	
Concrete pavement with sawcut joints	BP#2	/BP#2	
Stamped pavement at Flagg Drive	BP#1	/BP#1	
Pavers - plaza paving	260 sf	25.00 /sf	6,500
Stone Dust at Raised Planter	32 sf	20.00 /sf	640
Bituminous sidewalks	BP#1	/BP#1	
G2030 Pedestrian Paving	136,600 sf	0.05 /sf	7,140
<b>G2040 Site Development</b>			
Retaining footing	BP#2	/BP#2	
Retaining wall	BP#2	/BP#2	
Concrete bench/seat wall	BP#2	/BP#2	
Steel @ Bandshell - AESS	BP#2	/BP#2	
Guardrails - exterior, colorgalv	240 lf	325.00 /lf	78,000
Phenolic bench per A102A	1 ea	4,200.00 /ea	4,200
Glass @ Bandshell (vertical) - 9/16" tempered, laminated	235 sf	150.00 /sf	35,250
Glass @ Bandshell (roof) - 9/16" tempered, laminated	300 sf	150.00 /sf	45,000
Prep/paint Bandshell	1 ls	10,000.00 /ls	10,000
Prep/paint main and West Admin egress canopies	1 ls	10,000.00 /ls	10,000
Exterior signage	BP#1	/BP#1	





90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>G2040 Site Development</b>			
Wood benches	20 lf	750.00 /lf	15,000
Bicycle Racks	20 ea	785.00 /ea	15,700
Basketball Poles & Hoops	2 ea	8,000.00 /ea	16,000
Miscellaneous site furnishings - Allowance	1 ls	30,000.00 /ls	30,000
Gravel base course - misc site amenities- (i.e.- curbing, swales,etc.)	BP#1	/BP#1	
Basketball Court Pavement- (3 1/2" Total Paving w/ Gravel Base) - BP#1	sf	/sf	
Basketball Court Pavement Markings	1 ls	2,000.00 /ls	2,000
Wooden Guardrailing	BP#1	/BP#1	
Fencing - N/A	-	/-	
24' wide Single Arm Gate	1 ea	3,500.00 /ea	3,500
Wooden Guardrailing - BP#1	lf	/lf	
Bollards - 6" steel w/concrete - BP#1	BP#1	/BP#1	
Bollards - 6" steel w/concrete - BP#1	ea	/ea	
Bollards - architectural - VM-C01	0 ea	/ea	
Segmental retaining wall	2,600 sf	50.00 /sf	130,000
Additional segmental retaining wall per PR #12	220 sf	50.00 /sf	11,000
G2040 Site Development	<b>136,600 sf</b>	<b>2.97 /sf</b>	<b>405,650</b>
<b>G2050 Landscaping</b>			
Landscaping maintenance	1 yr	8,000.00 /yr	8,000
Irrigation system @ south sports field - by others	-	/-	
Irrigation @ ampitheater - Allowance	23,435 sf	2.00 /sf	46,870
Irrigation system @ north sports field - Allowance	81,000 sf	2.00 /sf	162,000
Mulch at trees and planting beds (3")	240 cy	105.00 /cy	25,200
Fine grade & hydroseed lawn areas	119,420 sf	0.30 /sf	35,826
Fine grade & seed (Native Wildflower Meadow)	104,005 sf	0.25 /sf	26,001
Fine grade & seed (Detention Basin Mix- Hydroseed)	33,330 sf	0.25 /sf	8,333
Fine grade & seed (Natural Turf Fields)	259,269 sf	0.25 /sf	64,817
Sod (Amphiltheather Lawns)	28,719 sf	1.50 /sf	43,079
Watering for sod areas	1 ls	7,500.00 /ls	7,500
Sod (100'x170')	17,000 sf	1.50 /sf	25,500
Sod northeast - phase 3 play area	5,000 sf	1.50 /sf	7,500
Watering for sod areas	1 ls	7,500.00 /ls	7,500
Trees	118 ea	750.00 /ea	88,500
Shrubs (478 Total)	7,736 sf	8.50 /sf	65,756
Groundcover/perennials	1,966 ea	20.00 /ea	39,320
Planter Beds	7,786 sf	10.00 /sf	77,860
Rain garden	8,275 sf	10.00 /sf	82,750
G2050 Landscaping	<b>136,600 sf</b>	<b>6.02 /sf</b>	<b>822,312</b>



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>G20 Site Improvements</b>	<b>136,600 sf</b>	<b>9.04 /sf</b>	<b>1,235,102</b>
<b>G30 Site Civil/Mechanical Utilites</b>			
<b>G3010 Water Supply</b>			
Fire hydrants	BP#1	/BP#1	
Fire hydrant - relocate existing	BP#1	/BP#1	
Gate valves, tees, bends, thrust blocks, restraints	BP#1	/BP#1	
Water distribution connections to existing	BP#1	/BP#1	
Water line - domestic	BP#1	/BP#1	
Water line - hydrant & fire services	BP#1	/BP#1	
Pressure test & chlorinate	BP#1	/BP#1	
G3010 Water Supply	<u>136,600 sf</u>	/sf	
<b>G3020 Sanitary Sewer</b>			
Sanitary sewer piping	BP#1	/BP#1	
Sanitary sewer manholes	BP#1	/BP#1	
Connect to existing structures	BP#1	/BP#1	
Utility and sewer tie-in at trailer	BP#1	/BP#1	
Sanitary sewer testing - piping	BP#1	/BP#1	
Video inspect incoming sewer, etc.	BP#1	/BP#1	
Sanitary sewer testing - structures	BP#1	/BP#1	
Grease interceptor - In Plumbing	-	/-	
Acid Neutralization - In Plumbing	-	/-	
G3020 Sanitary Sewer	<u>136,600 sf</u>	/sf	
<b>G3030 Storm Drainage</b>			
Catch basins	BP#1	/BP#1	
Granite Curb Inlets	BP#1	/BP#1	
Storm drainage manholes	BP#1	/BP#1	
Outlet control structures	BP#1	/BP#1	
Storm headwalls	BP#1	/BP#1	
Stormceptors	BP#1	/BP#1	
Storm drainage piping	BP#1	/BP#1	
Rip Rap Splash Pads	BP#1	/BP#1	
Weir Overflows	BP#1	/BP#1	
Check dams	BP#1	/BP#1	
Foundation drainage piping	BP#1	/BP#1	
Infiltration system	BP#1	/BP#1	
G3030 Storm Drainage	<u>136,600 sf</u>	/sf	
<b>G3060 Fuel Distribution</b>			
Excavation / backfill for gas line	BP#1	/BP#1	



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
G3060 Fuel Distribution	136,600 sf	/sf	
<b>G30 Site Civil/Mechanical Utilites</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>G40 Site Electrical Utilities</b>			
<b>G4010 Electrical Distribution</b>			
Temp power for welders	2 ea	2,398.27 /ea	4,797
Temp power for trailers	4 ea	1,302.42 /ea	5,210
Temp internet connection for trailers	4 ea	1,854.17 /ea	7,417
Feeder (PVC/CU) - 150A [generator / LS]	135 lf	22.18 /lf	2,994
Feeder (PVC/CU) - 225A [generator / OS]	135 lf	33.46 /lf	4,517
Feeder (PVC/CU) - 400A [generator / LR] (exterior)	135 lf	56.93 /lf	7,685
Feeder (PVC/CU) - 2500A [secondary]	105 lf	414.00 /lf	43,470
Empty conduit - sch 40 PVC: 1 x 4" [generator]	135 lf	9.86 /lf	1,330
Empty conduit - sch 40 PVC: 1 x 4" [secondary / spare]	105 lf	9.86 /lf	1,035
Empty conduit - sch 40 PVC: 2 x 4" [primary]	250 lf	17.66 /lf	4,415
Magnetic warning tape - 1/8"	875 lf	4.37 /lf	3,826
Pole riser (GRC - 4"C)	2 ea	2,343.85 /ea	4,688
Electric manhole - 6'x12x7'	1 ea	6,773.56 /ea	6,774
Cast iron manhole frame/cover, 32"D x 6'H grade rings	1 ea	1,140.93 /ea	1,141
12" x 12" x 12"D ground mounted pullbox (Quazite #PC1212HG00 w/ Cover)	2 ea	752.15 /ea	1,504
Hand hole & cover - 4'x4'x4'	6 ea	1,937.11 /ea	11,623
17"x30"x12"D ground pullbox (Quazite #PC1730BA12 w/ cover)	11 ea	1,078.60 /ea	11,865
24" x 36" x 24"D ground mounted pullbox (Quazite #Pg2436BC-24 w/ Cover)	1 ea	1,718.39 /ea	1,718
Manhole / racking grounding & bonding	1 ea	701.05 /ea	701
Exterior (utility) transformer grounding & bonding	1 ea	1,066.05 /ea	1,066
Generator grounding & bonding	1 ea	1,066.05 /ea	1,066
Bare copper wire - #4/0 [duct bank]	875 lf	4.99 /lf	4,368
Electric vehicle charging station / dual pedestal / cable mgmt.	3 ea	10,512.40 /ea	31,537
Utility meter socket (meter by Util. Co.)	1 ea	289.66 /ea	290
CT meter enclosure for switchboard	1 ea	1,462.26 /ea	1,462
Excavation/backfill for Emergency Generator ductbank	BP#1	/BP#1	
Excavation/backfill for Primary Electric ductbank	BP#1	/BP#1	
Excavation/backfill for Fire Alarm ductbank	BP#1	/BP#1	
Excavation/backfill for Telcom ductbank	BP#1	/BP#1	
Excavation/backfill for U.G. ductbank	BP#1	/BP#1	
Excavation/backfill for 2"C Power Data ductbank (Amphitheather)	BP#1	/BP#1	
Excavation/backfill for 2"C to IDF ductbank	BP#1	/BP#1	
Concrete and rebar for electrical/telcom ductbanks	BP#1	/BP#1	



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>G4010 Electrical Distribution</b>			
6" Concrete Filled Steel Pipe Bollards at Generator & Transformer Pads	BP#1	/BP#1	
G4010 Electrical Distribution	136,600 sf	1.22 /sf	166,498
<b>G4020 Site Lighting</b>			
Remove existing exterior site light fixture	11 ea	672.85 /ea	7,401
Lighting contactor - 12 pole (exterior lighting)	1 ea	1,899.98 /ea	1,900
SL5: exterior ampitheater RGB projector, DMX capable, IP65 rated [O]	8 ea	3,626.85 /ea	29,015
SLS: LED recessed step light, 0-10V dimming capable [C]	7 ea	732.90 /ea	5,130
SL1: LED pole mounted luminaires mounted on a 20' pole [O]	35 ea	2,891.40 /ea	101,199
SL2A: exterior post top fixture with 15' round tapered alum pole [O]	13 ea	5,492.50 /ea	71,403
SL3: exterior bollard 43.3 cast illuminium [O]	9 ea	1,929.78 /ea	17,368
SL10: LED mini in-ground flood fixture capable of 0-10V dimming [O]	12 ea	978.60 /ea	11,743
EMT (12/2) - 20A	1,400 lf	7.13 /lf	9,981
1" PVC - 30A (3#8 & #10G)	6,900 lf	10.95 /lf	75,528
1" GRC - 90 Deg Sweep	114 ea	174.22 /ea	19,861
Emergency Call Box base	BP#1	/BP#1	
EV Parking Station bases	BP#1	/BP#1	
Light pole bases	BP#1	/BP#1	
G4020 Site Lighting	136,600 sf	2.57 /sf	350,530
<b>G4030 Site Communications &amp; Security</b>			
Relocate existing emergency call box (provide new concrete base)	1 ea	2,994.80 /ea	2,995
Empty conduit (PVC) - 1"	250 lf	8.07 /lf	2,016
Empty conduit (PVC) - 2"	700 lf	6.03 /lf	4,223
Empty conduit (sch 40 PVC) (4) 4"C (CATV, Telephone, Fiber, Spare)	220 lf	32.32 /lf	7,110
Three (3) 1.25" inner ducts for fiber	220 lf	15.50 /lf	3,411
Communications utility pole conduit riser (GRC - 4"C)	4 ea	2,343.84 /ea	9,375
Telecom manhole & cover - 4'x6'x7'	1 ea	3,920.36 /ea	3,920
360-degree multi-sensor exterior cameras mounted on poles	3 ea	4,509.56 /ea	13,529
Camera wiring (PVC)	600 lf	13.34 /lf	8,003
Ductbank w/ IMSA cable - 2" PVC	320 lf	16.30 /lf	5,217
Excavation/backfill for site lighting	BP#1	/BP#1	
G4030 Site Communications & Security	136,600 sf	0.44 /sf	59,799
<b>G40 Site Electrical Utilities</b>	<b>136,600 sf</b>	<b>4.22 /sf</b>	<b>576,826</b>
<b>G Sitework</b>	<b>136,600 sf</b>	<b>16.34 /sf</b>	<b>2,231,718</b>



CONSIGLI  
*Est. 1905*





### 90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
01-54 SCAFFOLDING	136,600 sf	0.55 /sf	75,000
02-20 SELECTIVE DEMOLITION	136,600 sf	10.01 /sf	1,367,800
02-82 HAZARDOUS MATERIAL ABATEMENT	136,600 sf	11.73 /sf	1,602,280
03-30 CONCRETE	136,600 sf	/sf	
03-45 POLISHED CONCRETE	136,600 sf	0.24 /sf	32,850
04-20 MASONRY (TS)	136,600 sf	16.81 /sf	2,296,835
05-12 STRUCTURAL STEEL	136,600 sf	/sf	
05-50 MISCELLANEOUS METALS (TS)	136,600 sf	6.39 /sf	873,350
06-25 FINISH CARPENTRY	136,600 sf	15.42 /sf	2,106,225
07-10 WATERPROOFING & JOINT SEALANTS (TS)	136,600 sf	5.30 /sf	723,860
07-42 METAL/COMPOSITE PANELS & SIDING	136,600 sf	8.66 /sf	1,183,050
07-50 MEMBRANE ROOFING (TS)	136,600 sf	10.56 /sf	1,442,347
07-81 FIREPROOFING	136,600 sf	2.94 /sf	401,945
08-10 DOORS, FRAMES & HARDWARE	136,600 sf	5.21 /sf	711,550
08-34 OVERHEAD DOORS & GRILLES	136,600 sf	0.55 /sf	74,750
08-41 ALUMINUM STOREFRONT & WINDOWS (TS)	136,600 sf	17.23 /sf	2,353,200
08-45 TRANSLUCENT PANEL SYSTEMS	136,600 sf	0.48 /sf	66,000
08-80 GLASS & GLAZING (TS)	136,600 sf	7.84 /sf	1,070,725
08-90 LOUVERS	136,600 sf	0.39 /sf	53,125
09-21 DRYWALL	136,600 sf	48.08 /sf	6,568,069
09-30 TILE (TS)	136,600 sf	1.61 /sf	219,185
09-51 ACOUSTICAL CEILINGS (TS)	136,600 sf	6.91 /sf	943,503
09-64 WOOD FLOORING	136,600 sf	1.55 /sf	211,650
09-65 RESILIENT FLOORING (TS)	136,600 sf	7.61 /sf	1,038,943
09-67 RESINOUS FLOORING	136,600 sf	0.59 /sf	80,920
09-68 CARPET	136,600 sf	0.17 /sf	23,475
09-90 PAINTING (TS)	136,600 sf	3.80 /sf	518,523
10-14 SIGNAGE	136,600 sf	0.35 /sf	47,810
10-24 OPERABLE PARTITIONS	136,600 sf	2.15 /sf	293,545
10-51 LOCKERS	136,600 sf	3.14 /sf	429,460
10-95 MISCELLANEOUS SPECIALTIES	136,600 sf	2.84 /sf	387,827
11-31 RESIDENTIAL APPLIANCES	136,600 sf	0.20 /sf	27,100



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
11-40 FOOD SERVICE EQUIPMENT	136,600 sf	3.04 /sf	415,270
11-51 AUDIO-VISUAL EQUIPMENT	136,600 sf	3.29 /sf	450,000
11-61 THEATER & STAGE EQUIPMENT	136,600 sf	3.05 /sf	416,921
11-65 ATHLETIC/RECREATIONAL EQUIPMENT	136,600 sf	0.68 /sf	92,538
11-95 VOCATIONAL SHOP EQUIPMENT	136,600 sf	0.27 /sf	37,000
12-20 WINDOW TREATMENTS	136,600 sf	1.12 /sf	152,550
12-35 LAB CASEWORK	136,600 sf	2.04 /sf	277,975
12-60 FIXED AUDITORIUM SEATING	136,600 sf	0.85 /sf	115,710
12-62 BLEACHERS	136,600 sf	0.74 /sf	100,750
14-20 ELEVATORS (TS)	136,600 sf	1.61 /sf	220,000
21-01 FIRE PROTECTION (TS)	136,600 sf	6.70 /sf	914,839
22-01 PLUMBING (TS)	136,600 sf	14.17 /sf	1,935,182
23-01 HVAC (TS)	136,600 sf	58.17 /sf	7,946,076
26-01 ELECTRICAL (TS)	136,600 sf	46.06 /sf	6,291,566
31-23 SITEWORK	136,600 sf	/sf	
32-10 LANDSCAPING & SITE IMPROVEMENTS	136,600 sf	10.75 /sf	1,468,942
32-31 FENCING	136,600 sf	0.03 /sf	3,500





**90% CD Estimate**

**Estimate Totals**

Description	Amount	Totals	Rate	Cost per Unit
Subtotal	<b>48,063,718</b>	<b>48,063,718</b>		<b>351.86 /sf</b>
Design/Estimate Contingency	1,441,912		3.000 %	10.56 /sf
Escalation	495,056		1.000 %	3.62 /sf
<b>Subtotal</b>	<b>1,936,968</b>	<b>50,000,686</b>		<b>366.04 /sf</b>
SDI (Non-Trade Contracts)	269,858		1.400 %	1.98 /sf
Sub Bonds (Trade Contracts)	403,034		1.400 %	2.95 /sf
Contractor's Contingency	1,266,839		2.500 %	9.27 /sf
General Conditions	2,931,033			21.46 /sf
General Requirements	2,289,380			16.76 /sf
<b>Subtotal</b>	<b>7,160,144</b>	<b>57,160,830</b>		<b>418.45 /sf</b>
Builder's Risk Insurance - BP1				
General Liability Insurance	576,109			4.22 /sf
Building Permit - NIC				
Performance & Payment Bond				
<b>Subtotal</b>	<b>576,109</b>	<b>57,736,939</b>		<b>422.67 /sf</b>
Fee	1,152,218			8.43 /sf
Amendment #1 - Sitework	10,957,843			80.22 /sf
Amendment #2 - Concrete & Steel	8,716,894			63.81 /sf
Amendment #2 - Buy Savings	(50,755)			(0.37) /sf
<b>Total</b>		<b>78,513,139</b>		<b>574.77 /sf</b>





CONSIGLI  
*Est. 1905*





Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>01-54 SCAFFOLDING</b>			
<b>01.54.23 Temporary Scaffolding &amp; Platforms</b>			
Dance floor at auditorium - multi-trade	1 ls	75,000.00 /ls	75,000
<b>Temporary Scaffolding &amp; Platforms</b>	<b>136,600 sf</b>	<b>0.55 /sf</b>	<b>75,000</b>
<b>01-54 SCAFFOLDING</b>	<b>136,600 sf</b>	<b>0.55 /sf</b>	<b>75,000</b>
<b>02-20 SELECTIVE DEMOLITION</b>			
<b>02.41.01 Demolition - General</b>			
Building demolition	195,400 sf	7.00 /sf	1,367,800
<b>Demolition - General</b>	<b>136,600 sf</b>	<b>10.01 /sf</b>	<b>1,367,800</b>
<b>02-20 SELECTIVE DEMOLITION</b>	<b>136,600 sf</b>	<b>10.01 /sf</b>	<b>1,367,800</b>
<b>02-82 HAZARDOUS MATERIAL ABATEMENT</b>			
<b>02.82.00 Asbestos Remediation</b>			
Asbestos abatement	195,400 sf	8.20 /sf	1,602,280
<b>Asbestos Remediation</b>	<b>136,600 sf</b>	<b>11.73 /sf</b>	<b>1,602,280</b>
<b>02-82 HAZARDOUS MATERIAL ABATEMENT</b>	<b>136,600 sf</b>	<b>11.73 /sf</b>	<b>1,602,280</b>
<b>03-30 CONCRETE</b>			
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Concrete)	(1) ls	116,000.00 /ls	(116,000)
Trade support - lull, laborer for cleanup (Concrete)	1 ls	116,000.00 /ls	116,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>03.11.50 Concrete Forming - Flatwork</b>			
Slab depressions	BP#2	/BP#2	
<b>Concrete Forming - Flatwork</b>	<b>135,589 sf</b>	<b>/sf</b>	
<b>03.11.75 Concrete Forming - Pits</b>			
Elevator pit	BP#2	/BP#2	
<b>Concrete Forming - Pits</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>03.31.10 Concrete Ready Mix - Site</b>			
Retaining footing	BP#2	/BP#2	
Retaining wall	BP#2	/BP#2	
Concrete bench/seat wall	BP#2	/BP#2	
<b>Concrete Ready Mix - Site</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>03.31.20 Concrete Ready Mix - Foundations</b>			



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>03.31.20 Concrete Ready Mix - Foundations</b>			
F3 spread footings	BP#2	/BP#2	
F4 spread footings	BP#2	/BP#2	
F5 spread footings	BP#2	/BP#2	
F6 spread footings	BP#2	/BP#2	
F7 spread footings	BP#2	/BP#2	
F8 spread footings	BP#2	/BP#2	
F9 spread footings	BP#2	/BP#2	
F10 spread footings	BP#2	/BP#2	
F11 spread footings	BP#2	/BP#2	
F12 spread footings	BP#2	/BP#2	
Continuous footings - 3'x12"	BP#2	/BP#2	
Continuous footings - 4'x12"	BP#2	/BP#2	
Continuous footings - 5'x12" @ Bandshell	BP#2	/BP#2	
Foundation walls - 16"	BP#2	/BP#2	
Foundation walls - 16" @ Bandshell	BP#2	/BP#2	
Foundation walls - 21"	BP#2	/BP#2	
Retaining walls - 16"	BP#2	/BP#2	
Concrete walls @ Auditorium	BP#2	/BP#2	
Piers - 24"x24"	BP#2	/BP#2	
Grade beam 1	BP#2	/BP#2	
Grade beam 2	BP#2	/BP#2	
<b>Concrete Ready Mix - Foundations</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>03.31.50 Concrete Ready Mix - Flatwork</b>			
Slab on grade - 5"	BP#2	/BP#2	
<b>Concrete Ready Mix - Flatwork</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>03.35.55 Concrete Finishing - Slabs-on-Grades</b>			
Power trowel/seal concrete @ Auditorium	BP#2	/BP#2	
<b>Concrete Finishing - Slabs-on-Grades</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>03.35.60 Concrete Finishing - Slabs-on-Decking</b>			
Place & finish slabs - 2-1/2" on 3" deck @ roof	BP#2	/BP#2	
Place & finish slabs - 3-1/4" on 3" deck @ floor (LW)	BP#2	/BP#2	
Topping slab @ Breakout LGMF floors	BP#2	/BP#2	
Place & finish slabs - 3-1/4" on 3" deck @ roof	BP#2	/BP#2	
<b>Concrete Finishing - Slabs-on-Decking</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>03.35.90 Concrete Finishing - Miscellaneous</b>			
Place & finish stair treads/landings	BP#2	/BP#2	



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Concrete Finishing - Miscellaneous</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>03.36.00 Miscellaneous Concrete Items</b>			
Underslab insulation (perimeter only)	BP#2	/BP#2	
Foundation wall insulation	BP#2	/BP#2	
<b>Miscellaneous Concrete Items</b>	<b>135,589 sf</b>	<b>/sf</b>	
<b>32.13.00 Rigid Paving</b>			
Concrete pavement	BP#2	/BP#2	
Steps - premium	BP#2	/BP#2	
Dumpster pad	BP#2	/BP#2	
Concrete pavement with sawcut joints	BP#2	/BP#2	
<b>Rigid Paving</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>03-30 CONCRETE</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>03-45 POLISHED CONCRETE</b>			
<b>03.36.00 Miscellaneous Concrete Items</b>			
Polished concrete @ Auditorium	3,650 sf	9.00 /sf	32,850
<b>Miscellaneous Concrete Items</b>	<b>136,600 sf</b>	<b>0.24 /sf</b>	<b>32,850</b>
<b>03-45 POLISHED CONCRETE</b>	<b>136,600 sf</b>	<b>0.24 /sf</b>	<b>32,850</b>
<b>04-20 MASONRY (TS)</b>			
<b>01.43.00 Quality Assurance</b>			
Exterior wall mockup - Masonry, Allowance	1 allw	7,500.00 /allw	7,500
<b>Quality Assurance</b>	<b>136,600 sf</b>	<b>0.06 /sf</b>	<b>7,500</b>
<b>01.54.23 Temporary Scaffolding &amp; Platforms</b>			
Temporary bracing of CMU @ Gym and Auditorium	1 ls	100,000.00 /ls	100,000
Exterior staging	40,145 sf	2.50 /sf	100,363
<b>Temporary Scaffolding &amp; Platforms</b>	<b>136,600 sf</b>	<b>1.47 /sf</b>	<b>200,363</b>
<b>01.56.50 Winter Conditions</b>			
Masonry winter conditions/heat	12 wks	5,000.00 /wks	60,000
<b>Winter Conditions</b>	<b>136,600 sf</b>	<b>0.44 /sf</b>	<b>60,000</b>
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Masonry)	(1) ls	77,000.00 /ls	(77,000)
Trade support - lull, laborer for cleanup (Masonry)	1 ls	77,000.00 /ls	77,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>03.45.00 Precast Architectural Concrete</b>			
Precast planters	25 lf	750.00 /lf	18,750
<b>Precast Architectural Concrete</b>	<b>136,600 sf</b>	<b>0.14 /sf</b>	<b>18,750</b>
<b>04.05.23 Masonry Accessories</b>			
Install loose lintels (< 8")	14 ea	150.00 /ea	2,100
<b>Masonry Accessories</b>	<b>136,600 sf</b>	<b>0.02 /sf</b>	<b>2,100</b>
<b>04.21.13 Brick Masonry - Veneer</b>			
4x4x12 iron spot brick veneer, scored	6,815 sf	36.00 /sf	245,340
4x8x8 iron spot brick veneer, scored	6,750 sf	36.00 /sf	243,000
Brick veneer - interior - N/A	-	/-	
Brick veneer, precast cap @ entry wall per A102A	25 lf	285.00 /lf	7,125
<b>Brick Masonry - Veneer</b>	<b>136,600 sf</b>	<b>3.63 /sf</b>	<b>495,465</b>
<b>04.22.00 Concrete Unit Masonry</b>			
4x4x12 scored ground faced CMU veneer	2,970 sf	27.00 /sf	80,190
4x8x16 scored ground faced CMU veneer	23,615 sf	29.00 /sf	684,835
CMU - 12" exterior wall	15,795 sf	25.00 /sf	394,875
CMU - 12" interior wall	6,890 sf	25.00 /sf	172,250
CMU - ground face block, premium	1 ls	35,000.00 /ls	35,000
CMU - acoustical block, premium	1 ls	5,000.00 /ls	5,000
<b>Concrete Unit Masonry</b>	<b>136,600 sf</b>	<b>10.05 /sf</b>	<b>1,372,150</b>
<b>07.21.00 Thermal Insulation</b>			
Mineral wool insulation at brick/CMU veneer	40,145 sf	3.50 /sf	140,508
<b>Thermal Insulation</b>	<b>136,600 sf</b>	<b>1.03 /sf</b>	<b>140,508</b>
<b>04-20 MASONRY (TS)</b>	<b>136,600 sf</b>	<b>16.81 /sf</b>	<b>2,296,835</b>
<b>05-12 STRUCTURAL STEEL</b>			
<b>01.43.00 Quality Assurance</b>			
Exterior wall mockup - Steel, Allowance	BP#2	/BP#2	
<b>Quality Assurance</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>05.05.23 Metal Fastenings</b>			
Moment connections @ floor	BP#2	/BP#2	
Moment connections @ roof	BP#2	/BP#2	
<b>Metal Fastenings</b>	<b>136,600 sf</b>	<b>/sf</b>	

**05.12.00 Structural Steel Framing**





90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>05.12.00 Structural Steel Framing</b>			
Steel @ floors	BP#2	/BP#2	
Steel hangers - AESS	BP#2	/BP#2	
Steel @ floors - VM-S05	BP#2	/BP#2	
Steel @ screen wall - galvanized	BP#2	/BP#2	
Steel @ Bandshell - AESS	BP#2	/BP#2	
Steel @ Canopy - AESS	BP#2	/BP#2	
Steel @ roof	BP#2	/BP#2	
Steel dunnage - RTU & chiller	BP#2	/BP#2	
Relieving angles @ brick veneer	BP#2	/BP#2	
Shoring @ Learning Commons	BP#2	/BP#2	
<b>Structural Steel Framing</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>05.20.00 Metal Joists</b>			
Open web joists, bridging	BP#2	/BP#2	
<b>Metal Joists</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>05.30.00 Metal Decking</b>			
Metal floor decking - galvanized (3" 18g)	BP#2	/BP#2	
Metal roof decking - acoustical (3" 18/16g)	BP#2	/BP#2	
Metal floor decking @ Breakout room LGMF floors	BP#2	/BP#2	
Metal roof decking - galvanized (1-1/2" 20g)	BP#2	/BP#2	
Metal roof decking - acoustical (1-1/2" 20g)	BP#2	/BP#2	
Metal roof decking - galvanized (3" 18g)	BP#2	/BP#2	
<b>Metal Decking</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>05.51.00 Metal Stairs</b>			
Ornamental stairs 4 and 5 - excluding rails	BP#2	/BP#2	
<b>Metal Stairs</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>05.52.00 Metal Railings</b>			
Steel angles/stantions @ locker guardrail	BP#2	/BP#2	
<b>Metal Railings</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>05-12 STRUCTURAL STEEL</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>05-50 MISCELLANEOUS METALS (TS)</b>			
<b>05.50.00 Metal Fabrications</b>			
Misc. metal fabrications	136,600 sf	1.00 /sf	136,600
Seismic clips - 4' OC, each side	270 ea	60.00 /ea	16,200
Loose lintels - Furnish	95 lf	25.00 /lf	2,375



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Metal Fabrications</b>	<b>136,600 sf</b>	<b>1.14 /sf</b>	<b>155,175</b>
<b>05.51.00 Metal Stairs</b>			
Ornamental stairs 3 and 6 - excluding rails	2 flt	60,000.00 /flt	120,000
Egress stair	5 flt	20,000.00 /flt	100,000
Roof ladders	3 ea	1,500.00 /ea	4,500
Elevator pit ladders	1 ea	450.00 /ea	450
<b>Metal Stairs</b>	<b>136,600 sf</b>	<b>1.65 /sf</b>	<b>224,950</b>
<b>05.52.00 Metal Railings</b>			
Handrail @ steps/ramps	55 lf	295.00 /lf	16,225
Cane rails	120 lf	200.00 /lf	24,000
Guardrails @ Atrium	380 lf	500.00 /lf	190,000
Guardrails @ Atrium stairs	235 lf	500.00 /lf	117,500
Guardrails - 42" galvanized perforated @ exterior	105 lf	500.00 /lf	52,500
Guardrails - 42" galvanized perforated @ terrace	30 lf	500.00 /lf	15,000
Guardrails - exterior, colorgalv	240 lf	325.00 /lf	78,000
<b>Metal Railings</b>	<b>136,600 sf</b>	<b>3.61 /sf</b>	<b>493,225</b>
<b>05-50 MISCELLANEOUS METALS (TS)</b>	<b>136,600 sf</b>	<b>6.39 /sf</b>	<b>873,350</b>
<b>06-25 FINISH CARPENTRY</b>			
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Finish Carpentry)	(1) ls	72,000.00 /ls	(72,000)
Trade support - lull, laborer for cleanup (Finish Carpentry)	1 ls	72,000.00 /ls	72,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>06.20.23 Interior Finish Carpentry</b>			
Wood base	100 lf	25.00 /lf	2,500
Miscellaneous wood base/trim	136,600 sf	0.50 /sf	68,300
Trim @ Breakout D glass lights	320 sf	25.00 /sf	8,000
Window sills - P-lam	1,100 lf	25.00 /lf	27,500
Hardwood trim @ locker guardrail per A650	3,300 lf	15.00 /lf	49,500
<b>Interior Finish Carpentry</b>	<b>136,600 sf</b>	<b>1.14 /sf</b>	<b>155,800</b>
<b>06.25.00 Prefinished Paneling</b>			
P-lam panel	1,440 sf	45.00 /sf	64,800
P-lam panel on Z-clips @ Breakout	325 sf	45.00 /sf	14,625
Suspended P-lam clouds @ Auditorium	100 ea	2,000.00 /ea	200,000
P-lam top panels @ locker guardrail per A650	1,025 lf	50.00 /lf	51,250
P-lam side panels @ locker guardrail per A650	450 lf	50.00 /lf	22,500



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>06.25.00 Prefinished Paneling</b>			
P-lam panel backsplash	120 sf	45.00 /sf	5,400
Marker tray - bamboo	2,485 lf	30.00 /lf	74,550
Casework for lockers (bank of 5) - including base	1,025 lf	250.00 /lf	256,250
MDF bumper rail	3,715 lf	25.00 /lf	92,875
P-lam wall panels - sound reflecting @ Auditorium	2,925 sf	45.00 /sf	131,625
P-lam wall panels - vestibules	400 sf	45.00 /sf	18,000
P-lam projector enclosure @ Auditorium	1 ea	2,500.00 /ea	2,500
<b>Prefinished Paneling</b>	<b>136,600 sf</b>	<b>6.84 /sf</b>	<b>934,375</b>
<b>06.41.00 Architectural Wood Casework</b>			
P-lam base cabinet w/top	40 lf	450.00 /lf	18,000
P-lam workstation w/top	770 lf	250.00 /lf	192,500
Mobile storage	172 ea	550.00 /ea	94,600
P-lam valance for fin tube	570 lf	45.00 /lf	25,650
P-lam 3/4" lip at counter for fin tube	570 lf	4.00 /lf	2,280
P-lam wall cabinet	40 lf	325.00 /lf	13,000
P-lam full height cabinet	50 lf	700.00 /lf	35,000
Bathroom vanity w/top	210 lf	250.00 /lf	52,500
Reception cabinet	20 lf	1,000.00 /lf	20,000
P-lam circulation desk	10 lf	750.00 /lf	7,500
P-lam work counter @ Admin	10 lf	1,500.00 /lf	15,000
P-lam counter @ Served	32 lf	200.00 /lf	6,400
P-lam end/filler panels @ Admin	10 lf	135.00 /lf	1,350
Mailboxes	18 lf	415.00 /lf	7,470
Storage shelving	380 lf	150.00 /lf	57,000
Storage shelving w/MDF	470 lf	200.00 /lf	94,000
P-lam bookcases	40 lf	500.00 /lf	20,000
Built-in benches	205 lf	600.00 /lf	123,000
Display cases	5 ea	4,500.00 /ea	22,500
Misc. casework - Allowance	136,600 sf	1.00 /sf	136,600
Phenolic bench per A102A	1 ea	4,200.00 /ea	4,200
Wood louvered shades - Rulon panel grille	450 lf	150.00 /lf	67,500
<b>Architectural Wood Casework</b>	<b>136,600 sf</b>	<b>7.44 /sf</b>	<b>1,016,050</b>
<b>06-25 FINISH CARPENTRY</b>	<b>136,600 sf</b>	<b>15.42 /sf</b>	<b>2,106,225</b>

07-10 WATERPROOFING & JOINT SEALANTS (TS)

01.43.00 Quality Assurance

Exterior wall mockup - Waterproofing, Allowance	1 allw	5,000.00 /allw	5,000
---	--------	----------------	-------



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Quality Assurance</b>	<b>136,600 sf</b>	<b>0.04 /sf</b>	<b>5,000</b>
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Waterproofing)	(1) ls	29,000.00 /ls	(29,000)
Trade support - lull, laborer for cleanup (Waterproofing)	1 ls	29,000.00 /ls	29,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>07.10.00 Dampproofing &amp; Waterproofing</b>			
Caulking @ storefront/curtainwall	7,425 lf	4.00 /lf	29,700
Caulking & sealants @ interior	136,600 sf	0.90 /sf	122,940
<i>Dampproofing at foundation wall</i>	<i>BP#2</i>	<i>/BP#2</i>	
Misc. caulking & sealants @ exterior	73,210 sf	0.75 /sf	54,908
<i>Foundation wall waterproofing - membrane w/ drainage board</i>	<i>BP#2</i>	<i>/BP#2</i>	
<i>Elevator pit waterproofing - cementitious</i>	<i>BP#2</i>	<i>/BP#2</i>	
<b>Dampproofing &amp; Waterproofing</b>	<b>136,600 sf</b>	<b>1.52 /sf</b>	<b>207,548</b>
<b>07.26.00 Vapor Retarders</b>			
Air and vapor barrier @ exterior walls	56,650 sf	7.50 /sf	424,875
Air and vapor barrier @ soffits	1,245 sf	7.50 /sf	9,338
Air and vapor barrier @ phenolic fins per A102A, A315	380 sf	7.50 /sf	2,850
Window transitions	7,425 lf	10.00 /lf	74,250
<b>Vapor Retarders</b>	<b>136,600 sf</b>	<b>3.74 /sf</b>	<b>511,313</b>
<b>07-10 WATERPROOFING &amp; JOINT SEALANTS (TS)</b>	<b>136,600 sf</b>	<b>5.30 /sf</b>	<b>723,860</b>
<b>07-42 METAL/COMPOSITE PANELS &amp; SIDING</b>			
<b>01.43.00 Quality Assurance</b>			
Exterior wall mockup - Siding, Allowance	1 allw	10,000.00 /allw	10,000
<b>Quality Assurance</b>	<b>136,600 sf</b>	<b>0.07 /sf</b>	<b>10,000</b>
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Siding)	(1) ls	48,000.00 /ls	(48,000)
Trade support - lull, laborer for cleanup (Siding)	1 ls	48,000.00 /ls	48,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>07.42.00 Wall Panels</b>			
Corrugated, perforated metal siding @ screen walls	1,105 sf	45.00 /sf	49,725
Exposed fastener metal panel	6,065 sf	45.00 /sf	272,925
Composite metal panel siding	3,120 sf	75.00 /sf	234,000
Phenolic panel siding	7,705 sf	80.00 /sf	616,400
<b>Wall Panels</b>	<b>136,600 sf</b>	<b>8.59 /sf</b>	<b>1,173,050</b>



### 90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>07-42 METAL/COMPOSITE PANELS &amp; SIDING</b>	<b>136,600 sf</b>	<b>8.66 /sf</b>	<b>1,183,050</b>
<b>07-50 MEMBRANE ROOFING (TS)</b>			
<b>01.43.00 Quality Assurance</b>			
Exterior wall mockup - Roofing, Allowance	1 allw	2,500.00 /allw	2,500
<b>Quality Assurance</b>	<b>136,600 sf</b>	<b>0.02 /sf</b>	<b>2,500</b>
<b>07.50.00 Membrane Roofing</b>			
PVC membrane roof w/insulation, underlayment, cover board, vapor barrier	63,155 sf	18.25 /sf	1,152,579
PVC membrane @ walls	2,740 sf	20.25 /sf	55,485
Reinforced walkway pads	715 sf	7.50 /sf	5,363
Pavers - terrace	295 sf	35.00 /sf	10,325
Pavers - main entrance	780 sf	35.00 /sf	27,300
<b>Membrane Roofing</b>	<b>136,600 sf</b>	<b>9.16 /sf</b>	<b>1,251,051</b>
<b>07.72.00 Roof Accessories</b>			
Roof accessories	63,155 sf	0.35 /sf	22,104
Roof vents & hatches	1 ls	25,000.00 /ls	25,000
Metal roof fascia	2,695 lf	35.00 /lf	94,325
Additional flashing, scuppers	63,155 sf	0.75 /sf	47,366
<b>Roof Accessories</b>	<b>136,600 sf</b>	<b>1.38 /sf</b>	<b>188,796</b>
<b>07-50 MEMBRANE ROOFING (TS)</b>	<b>136,600 sf</b>	<b>10.56 /sf</b>	<b>1,442,347</b>
<b>07-81 FIREPROOFING</b>			
<b>07.81.00 Applied Fireproofing</b>			
Sprayed fireproofing - steel beams and columns @ floor structure	64,740 sf	3.00 /sf	194,220
Sprayed fireproofing - steel beams and columns @ roof structure below 20'	33,575 sf	3.00 /sf	100,725
Patch Sprayed fireproofing - floor structure	5 days	3,500.00 /days	17,500
Patch Sprayed fireproofing - roof structure	5 days	3,500.00 /days	17,500
Intumescent fireproofing @ Learning Commons	1 ls	72,000.00 /ls	72,000
<b>Applied Fireproofing</b>	<b>136,600 sf</b>	<b>2.94 /sf</b>	<b>401,945</b>
<b>07-81 FIREPROOFING</b>	<b>136,600 sf</b>	<b>2.94 /sf</b>	<b>401,945</b>
<b>08-10 DOORS, FRAMES &amp; HARDWARE</b>			
<b>08.10.05 Doors &amp; Frames</b>			
Install exterior door, HW	14 ea	300.00 /ea	4,200
Install interior door, HW	300 ea	300.00 /ea	90,000



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Doors &amp; Frames</b>	<b>136,600 sf</b>	<b>0.69 /sf</b>	<b>94,200</b>
<b>08.11.13 Hollow Metal Doors &amp; Frames</b>			
HM doors - interior - flush	45 lvs	310.00 /lvs	13,950
HM doors - exterior flush	23 lvs	625.00 /lvs	14,375
HM frames - exterior single	5 ea	255.00 /ea	1,275
HM frames - exterior double	9 ea	440.00 /ea	3,960
HM frames - interior single	258 ea	310.00 /ea	79,980
HM frames - interior single, tandem	13 ea	360.00 /ea	4,680
HM frames - interior double	29 ea	385.00 /ea	11,165
<b>Hollow Metal Doors &amp; Frames</b>	<b>136,600 sf</b>	<b>0.95 /sf</b>	<b>129,385</b>
<b>08.14.00 Wood Doors</b>			
Wood door - interior flush	297 lvs	390.00 /lvs	115,830
Fire rated wood doors - premium	44 lvs	390.00 /lvs	17,160
Acoustical doors (STC 45) - premium	1 ls	15,000.00 /ls	15,000
<b>Wood Doors</b>	<b>136,600 sf</b>	<b>1.08 /sf</b>	<b>147,990</b>
<b>08.71.00 Door Hardware</b>			
Hardware sets - exterior door/panic	14 set	1,920.01 /set	26,880
Hardware sets - auto operators	1 set	4,500.00 /set	4,500
Hardware sets - standard interior	287 set	1,015.00 /set	291,305
Hardware sets - interior, tandem	13 set	1,330.00 /set	17,290
<b>Door Hardware</b>	<b>136,600 sf</b>	<b>2.49 /sf</b>	<b>339,975</b>
<b>08-10 DOORS, FRAMES &amp; HARDWARE</b>	<b>136,600 sf</b>	<b>5.21 /sf</b>	<b>711,550</b>
<b>08-34 OVERHEAD DOORS &amp; GRILLES</b>			
<b>08.33.00 Coiling Doors &amp; Grilles</b>			
Coiling security screen - 4' high, manual	85 sf	70.00 /sf	5,950
Coiling security screen - 8' high, manual	690 sf	70.00 /sf	48,300
Custom security gate @ Learning Commons	2 lvs	6,000.00 /lvs	12,000
<b>Coiling Doors &amp; Grilles</b>	<b>136,600 sf</b>	<b>0.49 /sf</b>	<b>66,250</b>
<b>08.36.00 Panel Doors</b>			
Overhead coiling door	1 ea	7,500.00 /ea	7,500
<b>Panel Doors</b>	<b>136,600 sf</b>	<b>0.06 /sf</b>	<b>7,500</b>
<b>11.13.00 Loading Dock Equipment</b>			
Loading dock equipment	1 ls	1,000.00 /ls	1,000
<b>Loading Dock Equipment</b>	<b>136,600 sf</b>	<b>0.01 /sf</b>	<b>1,000</b>



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>08-34 OVERHEAD DOORS &amp; GRILLES</b>	<b>136,600 sf</b>	<b>0.55 /sf</b>	<b>74,750</b>
<b>08-41 ALUMINUM STOREFRONT &amp; WINDOWS (TS)</b>			
<b>01.43.00 Quality Assurance</b>			
Exterior wall mockup - Windows, Allowance	1 allw	20,000.00 /allw	20,000
<b>Quality Assurance</b>	<b>136,600 sf</b>	<b>0.15 /sf</b>	<b>20,000</b>
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Windows)	(1) ls	73,000.00 /ls	(73,000)
Trade support - lull, laborer for cleanup (Windows)	1 ls	73,000.00 /ls	73,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>08.41.00 Entrances &amp; Storefronts</b>			
Aluminum storefront/windows	11,555 sf	100.00 /sf	1,155,500
Aluminum storefront - School Guard	545 sf	140.00 /sf	76,300
Extruded aluminum perimeter angles	7,425 lf	30.00 /lf	222,750
Aluminum entrance doors, HW - exterior	4 lvs	6,000.00 /lvs	24,000
Aluminum entrance doors, HW - exterior, School Guard	11 lvs	7,000.00 /lvs	77,000
<b>Entrances &amp; Storefronts</b>	<b>136,600 sf</b>	<b>11.39 /sf</b>	<b>1,555,550</b>
<b>08.63.00 Metal-Framed Skylights</b>			
Metal-framed skylights (8:12)	4,130 sf	150.00 /sf	619,500
Metal-framed skylights gable ends	490 sf	150.00 /sf	73,500
<b>Metal-Framed Skylights</b>		<b>/sf</b>	<b>693,000</b>
<b>08.71.00 Door Hardware</b>			
Automatic operators	1 pair	4,400.00 /pair	4,400
<b>Door Hardware</b>	<b>136,600 sf</b>	<b>0.03 /sf</b>	<b>4,400</b>
<b>08.80.00 Glazing</b>			
Glass @ Bandshell (vertical) - 9/16" tempered, laminated	235 sf	150.00 /sf	35,250
Glass @ Bandshell (roof) - 9/16" tempered, laminated	300 sf	150.00 /sf	45,000
<b>Glazing</b>	<b>135,589 sf</b>	<b>0.59 /sf</b>	<b>80,250</b>
<b>08-41 ALUMINUM STOREFRONT &amp; WINDOWS (TS)</b>	<b>136,600 sf</b>	<b>17.23 /sf</b>	<b>2,353,200</b>
<b>08-45 TRANSLUCENT PANEL SYSTEMS</b>			
<b>08.45.00 Translucent Wall &amp; Roof Assemblies</b>			
Polycarbonate glazing @ canopy	440 sf	150.00 /sf	66,000
<b>Translucent Wall &amp; Roof Assemblies</b>	<b>136,600 sf</b>	<b>0.48 /sf</b>	<b>66,000</b>
<b>08-45 TRANSLUCENT PANEL SYSTEMS</b>	<b>136,600 sf</b>	<b>0.48 /sf</b>	<b>66,000</b>



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>08-80 GLASS &amp; GLAZING (TS)</b>			
<b>08.41.00 Entrances &amp; Storefronts</b>			
Aluminum storefront - interior, School Guard	340 sf	140.00 /sf	47,600
Aluminum windows - interior, School Guard	2 ea	12,000.00 /ea	24,000
Aluminum entrance doors, HW - interior	1 lvs	6,000.00 /lvs	6,000
Aluminum entrance doors, HW - interior, School Guard	8 lvs	7,000.00 /lvs	56,000
<b>Entrances &amp; Storefronts</b>	<b>136,600 sf</b>	<b>0.98 /sf</b>	<b>133,600</b>
<b>08.80.00 Glazing</b>			
Misc. interior glass & glazing	136,600 sf	0.25 /sf	34,150
Glazed partition	4,700 sf	60.00 /sf	282,000
Glazed partition - double acoustic	625 sf	110.00 /sf	68,750
Glazed partition @ sidelights	1,165 sf	75.00 /sf	87,375
Glass walls @ Breakout	2,005 sf	120.00 /sf	240,600
Glass roof @ Breakout	70 sf	150.00 /sf	10,500
Door glazing - full	159 ea	400.00 /ea	63,600
Door glazing - narrow	2 ea	100.00 /ea	200
Mirrors - unframed restroom	1,145 sf	35.00 /sf	40,075
<b>Glazing</b>	<b>136,600 sf</b>	<b>6.06 /sf</b>	<b>827,250</b>
<b>08.88.00 Glazing Surface Films</b>			
Graduated glass film	3,675 sf	5.00 /sf	18,375
3M Safety and Security Window Film @ glass walls	4,090 sf	15.00 /sf	61,350
3M Safety and Security Window Film @ doors	67 lvs	450.00 /lvs	30,150
<b>Glazing Surface Films</b>	<b>136,600 sf</b>	<b>0.80 /sf</b>	<b>109,875</b>
<b>08-80 GLASS &amp; GLAZING (TS)</b>	<b>136,600 sf</b>	<b>7.84 /sf</b>	<b>1,070,725</b>
<b>08-90 LOUVERS</b>			
<b>08.90.00 Louvers &amp; Vents</b>			
Metal louver	625 sf	85.00 /sf	53,125
<b>Louvers &amp; Vents</b>	<b>136,600 sf</b>	<b>0.39 /sf</b>	<b>53,125</b>
<b>08-90 LOUVERS</b>	<b>136,600 sf</b>	<b>0.39 /sf</b>	<b>53,125</b>
<b>09-21 DRYWALL</b>			
<b>01.43.00 Quality Assurance</b>			
Exterior wall mockup - Drywall, Allowance	1 allw	10,000.00 /allw	10,000
<b>Quality Assurance</b>	<b>136,600 sf</b>	<b>0.07 /sf</b>	<b>10,000</b>
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Drywall)	(1) ls	188,000.00 /ls	(188,000)





### 90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Trade support - lull, laborer for cleanup (Drywall)	1 ls	188,000.00 /ls	188,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>05.40.00 Cold-Formed Metal Framing</b>			
Light gage metal framing @ Breakout floors	1,440 sf	60.00 /sf	86,400
Light gage metal framing @ Breakout walls	16,820 sf	25.00 /sf	420,500
<b>Cold-Formed Metal Framing</b>	<b>136,600 sf</b>	<b>3.71 /sf</b>	<b>506,900</b>
<b>06.10.00 Rough Carpentry</b>			
Roof blocking	10,780 lf	32.00 /lf	344,960
Window blocking	7,425 lf	12.75 /lf	94,669
Door blocking - exterior	265 lf	13.85 /lf	3,671
Door blocking - interior	4,965 lf	13.85 /lf	68,772
In-wall blocking	12,160 lf	12.75 /lf	155,040
Miscellaneous rough carpentry - Allowance	136,600 sf	0.65 /sf	88,790
<b>Rough Carpentry</b>	<b>136,600 sf</b>	<b>5.53 /sf</b>	<b>755,902</b>
<b>07.84.00 Firestopping</b>			
Firestopping @ rated walls	5,630 lf	16.20 /lf	91,206
Miscellaneous firestopping	136,600 sf	0.10 /sf	13,660
<b>Firestopping</b>	<b>136,600 sf</b>	<b>0.77 /sf</b>	<b>104,866</b>
<b>08.31.00 Access Doors &amp; Panels</b>			
Access panels	1 ls	15,000.00 /ls	15,000
<b>Access Doors &amp; Panels</b>	<b>136,600 sf</b>	<b>0.11 /sf</b>	<b>15,000</b>
<b>09.21.13 Gypsum Board Assemblies - Walls</b>			
Level 5 finish - Allowance	25,000 sf	2.55 /sf	63,750
Interior wall framing - 2-1/2"	3,370 sf	5.75 /sf	19,378
Interior wall framing - 3-5/8"/4"	96,355 sf	5.75 /sf	554,041
Interior wall framing - 6"	7,050 sf	7.65 /sf	53,933
Interior wall framing - 8"	21,965 sf	10.15 /sf	222,945
Interior wall framing - 10"	555 sf	12.10 /sf	6,716
GWB - 5/8", level 4	229,230 sf	4.15 /sf	951,305
GWB - 5/8", additional layer	96,320 sf	3.50 /sf	336,627
GWB - high impact	1 ls	50,000.00 /ls	50,000
Shaft liner - 1"	2,420 sf	4.15 /sf	10,043
Sound batt insulation	137,275 sf	1.60 /sf	219,640
Half height walls @ Auditorium	400 sf	22.90 /sf	9,160
LGMF framing @ locker guardrail	4,095 sf	5.10 /sf	20,885



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>09.21.13 Gypsum Board Assemblies - Walls</b>			
GWB - 5/8", level 5 @ locker guardrail	4,095 sf	6.70 /sf	27,437
Curved walls - premium	5,205 sf	6.35 /sf	33,074
Exterior walls - 10" studs, 1/2" sheathing, 5/8" GWB, insulation	44,220 sf	23.50 /sf	1,039,170
Framing @ phenolic fins per A102A, A315	380 sf	7.65 /sf	2,907
Install HM door frames - exterior single	5 ea	73.00 /ea	365
Install HM door frames - interior single	271 ea	73.00 /ea	19,783
Install HM door frames - exterior double	9 ea	117.00 /ea	1,053
Install HM door frames - interior double	29 ea	117.00 /ea	3,393
<b>Gypsum Board Assemblies - Walls</b>	<b>136,600 sf</b>	<b>26.69 /sf</b>	<b>3,645,602</b>
<b>09.21.16 Gypsum Board Assemblies - Ceilings &amp; Soffits</b>			
Gypsum board ceilings	21,010 sf	15.25 /sf	320,411
Gypsum board ceilings - 1 hr	655 sf	19.10 /sf	12,511
Gypsum board ceilings - 2 hr	80 sf	22.90 /sf	1,832
Gypsum board ceilings - resilient	5,350 sf	31.75 /sf	169,863
Stucco soffit	1,245 sf	11.35 /sf	14,131
Exterior soffit framing, sheathing, insulation	1,245 sf	23.90 /sf	29,756
Gypsum board soffits	28,335 sf	25.45 /sf	721,126
Gypsum board soffits @ Learning Commons	4,920 sf	25.45 /sf	125,214
Gypsum board soffits @ Skylights	1,915 sf	25.45 /sf	48,737
<b>Gypsum Board Assemblies - Ceilings &amp; Soffits</b>	<b>136,600 sf</b>	<b>10.57 /sf</b>	<b>1,443,579</b>
<b>09.21.25 Gypsum Board Assemblies - Patching/Infills</b>			
Patch GWB	136,600 sf	0.50 /sf	68,300
<b>Gypsum Board Assemblies - Patching/Infills</b>	<b>136,600 sf</b>	<b>0.50 /sf</b>	<b>68,300</b>
<b>09.77.33 Fiberglass Reinforced Panels</b>			
Fiberglass reinforced panels (FRP) - wall panels	2,240 sf	8.00 /sf	17,920
<b>Fiberglass Reinforced Panels</b>	<b>136,600 sf</b>	<b>0.13 /sf</b>	<b>17,920</b>
<b>09-21 DRYWALL</b>	<b>136,600 sf</b>	<b>48.08 /sf</b>	<b>6,568,069</b>
<b>09-30 TILE (TS)</b>			
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Tile)	(1) ls	7,000.00 /ls	(7,000)
Trade support - lull, laborer for cleanup (Tile)	1 ls	7,000.00 /ls	7,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>09.30.00 Tiling</b>			
Ceramic wall tile	2,295 sf	18.00 /sf	41,310
Porcelain floor tile	5,475 sf	25.00 /sf	136,875



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>09.30.00 Tiling</b>			
Quarry floor tile	1,770 sf	20.00 /sf	35,400
Quarry tile base	280 lf	20.00 /lf	5,600
<b>Tiling</b>	<b>136,600 sf</b>	<b>1.61 /sf</b>	<b>219,185</b>
<b>09-30 TILE (TS)</b>	<b>136,600 sf</b>	<b>1.61 /sf</b>	<b>219,185</b>
<b>09-51 ACOUSTICAL CEILINGS (TS)</b>			
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Ceilings)	(1) ls	49,000.00 /ls	(49,000)
Trade support - lull, laborer for cleanup (Ceilings)	1 ls	49,000.00 /ls	49,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>09.51.00 Acoustical Ceilings</b>			
A1 - Armstrong Ultima #1911, random running bond pattern	21,400 sf	9.00 /sf	192,600
A1 - Armstrong Ultima #1911 @ Learning Commons corridors	9,980 sf	9.00 /sf	89,820
A2 - Armstrong Calla #2824	20,985 sf	8.00 /sf	167,880
A3 - USG Geometrix 3 Dimensional	3,815 sf	35.00 /sf	133,525
A4 - Armstrong Healthzone Ultima	1,760 sf	7.00 /sf	12,320
<b>Acoustical Ceilings</b>	<b>136,600 sf</b>	<b>4.36 /sf</b>	<b>596,145</b>
<b>09.80.00 Acoustical Treatment</b>			
Fabric wrapped acoustical panels	12,275 sf	20.00 /sf	245,500
Tectum wall panels	5,535 sf	18.00 /sf	99,630
Mural panorama wall covering	1,485 sf	1.50 /sf	2,228
<b>Acoustical Treatment</b>	<b>136,600 sf</b>	<b>2.54 /sf</b>	<b>347,358</b>
<b>09-51 ACOUSTICAL CEILINGS (TS)</b>	<b>136,600 sf</b>	<b>6.91 /sf</b>	<b>943,503</b>
<b>09-64 WOOD FLOORING</b>			
<b>09.64.00 Wood Flooring</b>			
Hardwood stage assembly	1,610 sf	25.00 /sf	40,250
Wood athletic flooring	8,570 sf	20.00 /sf	171,400
<b>Wood Flooring</b>	<b>136,600 sf</b>	<b>1.55 /sf</b>	<b>211,650</b>
<b>09-64 WOOD FLOORING</b>	<b>136,600 sf</b>	<b>1.55 /sf</b>	<b>211,650</b>
<b>09-65 RESILIENT FLOORING (TS)</b>			
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Resilient)	(1) ls	48,000.00 /ls	(48,000)
Trade support - lull, laborer for cleanup (Resilient)	1 ls	48,000.00 /ls	48,000



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>09.61.00 Flooring Treatment</b>			
Underlayment at 2nd and 3rd floor linoleum - Forbo NR99, exclude corridors	62,015 sf	4.00 /sf	248,060
<i>Moisture mitigation - Excluded</i>	-	/-	
<b>Flooring Treatment</b>	<b>136,600 sf</b>	<b>1.82 /sf</b>	<b>248,060</b>
<b>09.65.00 Resilient Flooring</b>			
Linoleum tile	100,135 sf	6.00 /sf	600,810
Linoleum tile base w/trim	19,260 lf	9.00 /lf	173,340
Rubber base	2,175 lf	3.50 /lf	7,613
Vented base @ Gym	370 lf	8.00 /lf	2,960
Rubber flooring @ ornamental stairs	770 sf	8.00 /sf	6,160
<b>Resilient Flooring</b>	<b>136,600 sf</b>	<b>5.79 /sf</b>	<b>790,883</b>
<b>09-65 RESILIENT FLOORING (TS)</b>	<b>136,600 sf</b>	<b>7.61 /sf</b>	<b>1,038,943</b>
<b>09-67 RESINOUS FLOORING</b>			
<b>09.67.00 Fluid-Applied Flooring</b>			
Epoxy flooring/base	5,780 sf	14.00 /sf	80,920
<b>Fluid-Applied Flooring</b>	<b>136,600 sf</b>	<b>0.59 /sf</b>	<b>80,920</b>
<b>09-67 RESINOUS FLOORING</b>	<b>136,600 sf</b>	<b>0.59 /sf</b>	<b>80,920</b>
<b>09-68 CARPET</b>			
<b>09.68.00 Carpeting</b>			
Carpet @ Auditorium	135 sy	45.00 /sy	6,075
<b>Carpeting</b>	<b>136,600 sf</b>	<b>0.04 /sf</b>	<b>6,075</b>
<b>12.48.13 Entrance Floor Mats &amp; Frames</b>			
Entry mats - recessed	435 sf	40.00 /sf	17,400
<b>Entrance Floor Mats &amp; Frames</b>	<b>136,600 sf</b>	<b>0.13 /sf</b>	<b>17,400</b>
<b>09-68 CARPET</b>	<b>136,600 sf</b>	<b>0.17 /sf</b>	<b>23,475</b>
<b>09-90 PAINTING (TS)</b>			
<b>09.90.00 Painting &amp; Coating</b>			
Paint GWB partitions	227,710 sf	0.80 /sf	182,168
<i>Paint CMU - N/A</i>	-	/-	
Epoxy wall paint	15,550 sf	2.30 /sf	35,765
Prep/paint Bandshell	1 ls	10,000.00 /ls	10,000



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>09.90.00 Painting &amp; Coating</b>			
Prep/paint main and West Admin egress canopies	1 ls	10,000.00 /ls	10,000
Paint GWB ceilings	21,735 sf	1.00 /sf	21,735
Paint GWB soffits	35,170 sf	1.00 /sf	35,170
Paint HM doors - exterior	23 lvs	90.00 /lvs	2,070
Paint HM doors - interior	45 lvs	90.00 /lvs	4,050
Paint HM frames - exterior, single	5 ea	50.00 /ea	250
Paint HM frames - interior, single	271 ea	50.00 /ea	13,550
Paint HM frames - exterior, double	9 ea	60.00 /ea	540
Paint HM frames - interior, double	29 ea	60.00 /ea	1,740
Paint egress stairs	5 flt	2,000.00 /flt	10,000
Paint exposed ceilings	24,085 sf	1.50 /sf	36,128
Paint exposed ceilings @ Gym and Auditorium	14,385 sf	2.50 /sf	35,963
Seal concrete floor	7,245 sf	2.00 /sf	14,490
Misc. exterior painting	73,210 sf	0.50 /sf	36,605
Touchup	136,600 sf	0.50 /sf	68,300
<b>Painting &amp; Coating</b>	<b>136,600 sf</b>	<b>3.80 /sf</b>	<b>518,523</b>
<b>09-90 PAINTING (TS)</b>	<b>136,600 sf</b>	<b>3.80 /sf</b>	<b>518,523</b>
<b>10-14 SIGNAGE</b>			
<b>10.14.00 Signage</b>			
Interior signage	136,600 sf	0.35 /sf	47,810
Exterior signage	BP#1	/BP#1	
<b>Signage</b>	<b>136,600 sf</b>	<b>0.35 /sf</b>	<b>47,810</b>
<b>10-14 SIGNAGE</b>	<b>136,600 sf</b>	<b>0.35 /sf</b>	<b>47,810</b>
<b>10-24 OPERABLE PARTITIONS</b>			
<b>10.22.00 Partitions</b>			
Operable partitions w/writeable surface on one side	325 sf	77.00 /sf	25,025
Operable partitions w/writeable surface on both sides	2,740 sf	98.00 /sf	268,520
<b>Partitions</b>	<b>136,600 sf</b>	<b>2.15 /sf</b>	<b>293,545</b>
<b>10-24 OPERABLE PARTITIONS</b>	<b>136,600 sf</b>	<b>2.15 /sf</b>	<b>293,545</b>
<b>10-51 LOCKERS</b>			
<b>10.51.00 Lockers</b>			
Student lockers - phenolic	660 ea	600.00 /ea	396,000
Athletic lockers	80 ea	350.00 /ea	28,000
Staff lockers	12 ea	400.00 /ea	4,800
Locker benches	12 lf	55.00 /lf	660



### 90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Lockers</b>	<b>136,600 sf</b>	<b>3.14 /sf</b>	<b>429,460</b>
<b>10-51 LOCKERS</b>	<b>136,600 sf</b>	<b>3.14 /sf</b>	<b>429,460</b>
<b>10-95 MISCELLANEOUS SPECIALTIES</b>			
<b>10.11.00 Visual Display Units</b>			
Magnetic writeable wall covering	9,045 sf	22.00 /sf	198,990
<b>Visual Display Units</b>	<b>136,600 sf</b>	<b>1.46 /sf</b>	<b>198,990</b>
<b>10.21.00 Compartments &amp; Cubicles</b>			
Toilet partition	23 ea	1,020.00 /ea	23,460
Toilet partition - handicap	16 ea	1,650.00 /ea	26,400
Urinal screens - wall-hung	15 ea	433.00 /ea	6,495
Cubicle curtains	45 lf	40.00 /lf	1,800
Cubicle curtain track	45 lf	11.50 /lf	518
<b>Compartments &amp; Cubicles</b>	<b>136,600 sf</b>	<b>0.43 /sf</b>	<b>58,673</b>
<b>10.26.00 Wall &amp; Door Protection</b>			
Corner guards	1 ls	20,000.00 /ls	20,000
<b>Wall &amp; Door Protection</b>	<b>136,600 sf</b>	<b>0.15 /sf</b>	<b>20,000</b>
<b>10.28.00 Toilet, Bath, &amp; Laundry Accessories</b>			
Toilet paper dispenser	54 ea	105.17 /ea	5,679
Grab bar	62 ea	141.38 /ea	8,765
Soap dispenser - surface mounted	59 ea	87.64 /ea	5,171
Paper towel dispenser - recessed	32 ea	136.79 /ea	4,377
Framed mirrors	15 ea	171.00 /ea	2,565
Sanitary napkin disposal	46 ea	274.00 /ea	12,604
Shower curtains, hooks & rod	3 ea	125.00 /ea	375
Shower seat	2 ea	668.00 /ea	1,336
Mop rack	3 ea	230.67 /ea	692
<b>Toilet, Bath, &amp; Laundry Accessories</b>	<b>136,600 sf</b>	<b>0.30 /sf</b>	<b>41,564</b>
<b>10.40.00 Safety Specialties</b>			
Fire extinguisher cabinet - fully recessed	27 ea	350.00 /ea	9,450
<b>Safety Specialties</b>	<b>136,600 sf</b>	<b>0.07 /sf</b>	<b>9,450</b>
<b>10.80.00 Other Specialties</b>			
Misc. specialties - Allowance	136,600 sf	0.25 /sf	34,150
<b>Other Specialties</b>	<b>136,600 sf</b>	<b>0.25 /sf</b>	<b>34,150</b>
<b>11.52.00 Audio-Visual Equipment</b>			
Projection screen @ Gym, Cafeteria	2 ea	10,000.00 /ea	20,000



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>11.52.00 Audio-Visual Equipment</b>			
Projection screen	1 ea	5,000.00 /ea	5,000
<b>Audio-Visual Equipment</b>	<b>136,600 sf</b>	<b>0.18 /sf</b>	<b>25,000</b>
<b>10-95 MISCELLANEOUS SPECIALTIES</b>	<b>136,600 sf</b>	<b>2.84 /sf</b>	<b>387,827</b>
<b>11-31 RESIDENTIAL APPLIANCES</b>			
<b>11.31.00 Residential Appliances</b>			
Misc. appliances	1 ls	10,000.00 /ls	10,000
Refrigerator	7 ea	1,200.00 /ea	8,400
<i>Ice maker - None shown</i>	-	/-	
<i>Undercounter refrigerator - None shown</i>	-	/-	
Microwave oven	1 ea	450.00 /ea	450
Range hood	1 ea	650.00 /ea	650
Range	1 ea	900.00 /ea	900
Dishwasher	4 ea	925.00 /ea	3,700
Washer/dryer - stackable	2 ea	1,500.00 /ea	3,000
<b>Residential Appliances</b>	<b>136,600 sf</b>	<b>0.20 /sf</b>	<b>27,100</b>
<b>11-31 RESIDENTIAL APPLIANCES</b>	<b>136,600 sf</b>	<b>0.20 /sf</b>	<b>27,100</b>
<b>11-40 FOOD SERVICE EQUIPMENT</b>			
<b>11.40.00 Foodservice Equipment</b>			
Food service equipment - Allowance	1 ls	415,270.00 /ls	415,270
<b>Foodservice Equipment</b>	<b>136,600 sf</b>	<b>3.04 /sf</b>	<b>415,270</b>
<b>11-40 FOOD SERVICE EQUIPMENT</b>	<b>136,600 sf</b>	<b>3.04 /sf</b>	<b>415,270</b>
<b>11-51 AUDIO-VISUAL EQUIPMENT</b>			
<b>11.52.00 Audio-Visual Equipment</b>			
Sound systems @ Auditorium - Allowance	1 allw	200,000.00 /allw	200,000
Sound systems @ Gym - Allowance	1 allw	120,000.00 /allw	120,000
Sound systems @ Cafeteria - Allowance	1 allw	50,000.00 /allw	50,000
Sound systems @ Band/Chorus - Allowance	2 allw	30,000.00 /allw	60,000
Sound systems @ Drama - Allowance	1 allw	20,000.00 /allw	20,000
<b>Audio-Visual Equipment</b>	<b>136,600 sf</b>	<b>3.29 /sf</b>	<b>450,000</b>
<b>11-51 AUDIO-VISUAL EQUIPMENT</b>	<b>136,600 sf</b>	<b>3.29 /sf</b>	<b>450,000</b>
<b>11-61 THEATER &amp; STAGE EQUIPMENT</b>			
<b>11.61.00 Theater &amp; Stage Equipment</b>			
<i>Orchestra enclosures - FFE</i>	-	/-	
Theatrical rigging - Allowance	1 ls	158,300.00 /ls	158,300



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>11.61.00 Theater &amp; Stage Equipment</b>			
Theatrical draperies - Allowance	1 ls	33,854.00 /ls	33,854
Theatrical lighting instruments & accessories - Allowance	1 ls	129,018.00 /ls	129,018
Theatrical lighting controls - Allowance	1 ls	95,749.00 /ls	95,749
<b>Theater &amp; Stage Equipment</b>	<b>136,600 sf</b>	<b>3.05 /sf</b>	<b>416,921</b>
<b>11-61 THEATER &amp; STAGE EQUIPMENT</b>	<b>136,600 sf</b>	<b>3.05 /sf</b>	<b>416,921</b>
<b>11-65 ATHLETIC/RECREATIONAL EQUIPMENT</b>			
<b>11.65.00 Athletic &amp; Recreational Equipment</b>			
Basketball backstop - ceiling-hung	6 ea	6,500.00 /ea	39,000
Gym divider curtain - electric roll up	1,530 sf	20.00 /sf	30,600
Athletic wall padding	835 sf	12.50 /sf	10,438
Volleyball system	1 ls	5,000.00 /ls	5,000
Scoreboards - basketball	1 ea	7,500.00 /ea	7,500
<b>Athletic &amp; Recreational Equipment</b>	<b>136,600 sf</b>	<b>0.68 /sf</b>	<b>92,538</b>
<b>11-65 ATHLETIC/RECREATIONAL EQUIPMENT</b>	<b>136,600 sf</b>	<b>0.68 /sf</b>	<b>92,538</b>
<b>11-95 VOCATIONAL SHOP EQUIPMENT</b>			
<b>11.51.00 Vocational Shop Equipment</b>			
Vocational shop equipment	1 ls	25,000.00 /ls	25,000
- Welding booths - In Above	-	/-	
- Portable welding fumes extractor - In Above	-	/-	
- Paint spray hoods - In Above	-	/-	
- Portable wood working equipment dust collector - In HVAC	-	/-	
Kiln	1 ls	12,000.00 /ls	12,000
<b>Vocational Shop Equipment</b>	<b>136,600 sf</b>	<b>0.27 /sf</b>	<b>37,000</b>
<b>11-95 VOCATIONAL SHOP EQUIPMENT</b>	<b>136,600 sf</b>	<b>0.27 /sf</b>	<b>37,000</b>
<b>12-20 WINDOW TREATMENTS</b>			
<b>12.20.00 Window Treatments</b>			
Roller shades	11,205 sf	10.00 /sf	112,050
Roller shades - interior	3,300 sf	10.00 /sf	33,000
Roller shades - doors	50 ea	150.00 /ea	7,500
<b>Window Treatments</b>	<b>136,600 sf</b>	<b>1.12 /sf</b>	<b>152,550</b>
<b>12-20 WINDOW TREATMENTS</b>	<b>136,600 sf</b>	<b>1.12 /sf</b>	<b>152,550</b>
<b>12-35 LAB CASEWORK</b>			
<b>11.53.00 Laboratory Equipment</b>			
Misc. lab equipment - Allowance	1 ls	25,000.00 /ls	25,000





**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>11.53.00 Laboratory Equipment</b>			
Fume hoods	3 ea	11,000.00 /ea	33,000
<b>Laboratory Equipment</b>	<b>136,600 sf</b>	<b>0.43 /sf</b>	<b>58,000</b>
<b>12.35.53 Laboratory Casework</b>			
Base cabinet w/epoxy top	30 lf	600.00 /lf	18,000
Epoxy countertop - open below	325 lf	375.00 /lf	121,875
Epoxy backsplash	635 lf	60.00 /lf	38,100
Wall cabinets	105 lf	400.00 /lf	42,000
<b>Laboratory Casework</b>	<b>136,600 sf</b>	<b>1.61 /sf</b>	<b>219,975</b>
<b>12-35 LAB CASEWORK</b>	<b>136,600 sf</b>	<b>2.04 /sf</b>	<b>277,975</b>
<b>12-60 FIXED AUDITORIUM SEATING</b>			
<b>12.60.00 Multiple Seating</b>			
Fixed audience seating	406 ea	285.00 /ea	115,710
<b>Multiple Seating</b>	<b>136,600 sf</b>	<b>0.85 /sf</b>	<b>115,710</b>
<b>12-60 FIXED AUDITORIUM SEATING</b>	<b>136,600 sf</b>	<b>0.85 /sf</b>	<b>115,710</b>
<b>12-62 BLEACHERS</b>			
<b>12.60.00 Multiple Seating</b>			
Retractable Bleachers at Gym	650 seat	155.00 /seat	100,750
<b>Multiple Seating</b>	<b>136,600 sf</b>	<b>0.74 /sf</b>	<b>100,750</b>
<b>12-62 BLEACHERS</b>	<b>136,600 sf</b>	<b>0.74 /sf</b>	<b>100,750</b>
<b>14-20 ELEVATORS (TS)</b>			
<b>14.20.00 Elevators</b>			
Passenger elevators - cab, equipment	1 ls	40,000.00 /ls	40,000
Passenger elevators - stops	4 stop	45,000.00 /stop	180,000
<b>Elevators</b>	<b>136,600 sf</b>	<b>1.61 /sf</b>	<b>220,000</b>
<b>14-20 ELEVATORS (TS)</b>	<b>136,600 sf</b>	<b>1.61 /sf</b>	<b>220,000</b>
<b>21-01 FIRE PROTECTION (TS)</b>			
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Fire Protection)	(1) ls	31,000.00 /ls	(31,000)
Trade support - lull, laborer for cleanup (Fire Protection)	1 ls	31,000.00 /ls	31,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	

**21.01.00 Fire Suppression General Requirements**



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>21.01.00 Fire Suppression General Requirements</b>			
General requirements (management/design, permits, as-builts, coring, fire stopping)	136,600 sf	0.80 /sf	109,280
Hydraulic calculation & shop drawings	1 ls	8,000.00 /ls	8,000
3D/BIM coordination	1 ls	10,000.00 /ls	10,000
<b>Fire Suppression General Requirements</b>	<b>136,600 sf</b>	<b>0.93 /sf</b>	<b>127,280</b>
<b>21.11.00 Fire Suppression - Water-Service Piping</b>			
Fire dept. inlet connection - 2-1/2" polished brass - 3 -way	1 ea	1,863.93 /ea	1,864
<b>Fire Suppression - Water-Service Piping</b>	<b>136,600 sf</b>	<b>0.01 /sf</b>	<b>1,864</b>
<b>21.12.00 Fire-Suppression Standpipes</b>			
Standpipe - sch 40 black steel piping w/ fittings - 6"	125 lf	99.13 /lf	12,391
Drain riser - sch 40 black steel piping w/ fittings - 3"	125 lf	49.66 /lf	6,208
Fire hose valve - 2-1/2"	12 ea	353.36 /ea	4,240
Fire valve cabinet - steel - recessed	12 ea	894.50 /ea	10,734
<b>Fire-Suppression Standpipes</b>	<b>136,600 sf</b>	<b>0.25 /sf</b>	<b>33,573</b>
<b>21.13.13 Fire Suppression Wet-Pipe Sprinkler System</b>			
Sprinkler head - wet - recessed pendant	903 ea	125.42 /ea	113,250
Sprinkler head - wet - pendant or upright	522 ea	77.23 /ea	40,313
Sprinkler head - wet - sidewall	151 ea	87.51 /ea	13,213
Sprinkler head - wet - window	34 ea	87.51 /ea	2,975
Sprinkler head - extended coverage pendant or upright	120 ea	127.23 /ea	15,267
Sprinkler head - dry - sidewall (wet system)	22 ea	293.06 /ea	6,447
Sprinkler branch piping black steel sch. 40 w/ fittings 1"	3,465 lf	23.99 /lf	83,116
Sprinkler branch piping black steel sch. 40 w/ fittings 1-1/4"	600 lf	27.93 /lf	16,757
Sprinkler branch piping black steel sch. 40 w/ fittings 1-1/2"	5,200 lf	30.66 /lf	159,417
Sprinkler branch piping black steel sch. 40 w/ fittings 2"	650 lf	34.57 /lf	22,468
Sprinkler main piping black steel sch. 40 w/ fittings (avg. size)	1,000 lf	62.18 /lf	62,184
Sprinkler main piping black steel sch. 10 w/ fittings 3"	450 lf	36.32 /lf	16,345
Sprinkler main piping black steel sch. 10 w/ fittings 4"	3,180 lf	39.66 /lf	126,127
Sprinkler main piping black steel sch. 10 w/ fittings 6"	500 lf	69.39 /lf	34,695
Wet alarm valve - 6"	1 ea	3,656.71 /ea	3,657
Double check valve (BFP) assembly - 6"	1 ea	8,244.56 /ea	8,245
Butterfly valve - 6"	2 ea	1,566.71 /ea	3,133
Zone flow control valve - 4"	7 ea	2,521.71 /ea	17,652
Waterflow switch	8 ea	421.96 /ea	3,376
Tamper switch	8 ea	356.96 /ea	2,856
Water motor gong bell	1 ea	628.36 /ea	628



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Fire Suppression Wet-Pipe Sprinkler System</b>	<b>136,600 sf</b>	<b>5.51 /sf</b>	<b>752,122</b>
<b>21-01 FIRE PROTECTION (TS)</b>	<b>136,600 sf</b>	<b>6.70 /sf</b>	<b>914,839</b>
<b>22-01 PLUMBING (TS)</b>			
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Plumbing)	(1) ls	83,000.00 /ls	(83,000)
Trade support - lull, laborer for cleanup (Plumbing)	1 ls	83,000.00 /ls	83,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>22.00.05 PLUMBING - General Requirements</b>			
General requirements (management, permits, as-builts, coring, fire stopping)	136,600 sf	0.75 /sf	102,450
3D/BIM coordination	1 ls	12,000.00 /ls	12,000
Core drilling	1 ls	10,000.00 /ls	10,000
Project management	1 ls	50,000.00 /ls	50,000
Kitchen Equipment Tie ins	1 ls	12,000.00 /ls	12,000
<b>PLUMBING - General Requirements</b>	<b>136,600 sf</b>	<b>1.37 /sf</b>	<b>186,450</b>
<b>22.07.00 PLUMBING - Insulation</b>			
Insulation/copper pipe/fiberglass	7,975 lf	8.44 /lf	67,307
Insulation/rainleader pipe/fiberglass/PVC jacketed/horiz. & vert.	1,200 lf	40.61 /lf	48,737
<b>PLUMBING - Insulation</b>	<b>136,600 sf</b>	<b>0.85 /sf</b>	<b>116,044</b>
<b>22.08.00 Plumbing Commissioning Support</b>			
Commissioning support/day	5 day	824.56 /day	4,123
<b>Plumbing Commissioning Support</b>	<b>136,600 sf</b>	<b>0.03 /sf</b>	<b>4,123</b>
<b>22.10.00 Plumbing Facility Water Distribution</b>			
Water meter w/remote readout - 4"	1 ea	2,285.75 /ea	2,286
Water sub-meter - avg. size	1 ea	1,561.84 /ea	1,562
Water sub-meter - 1.5 Circ	1 ea	1,261.84 /ea	1,262
Water sub-meter - 2" Domestic WH	1 ea	1,277.30 /ea	1,277
Backflow preventer/RPZ-BFP - dishwasher	1 ea	1,809.21 /ea	1,809
Backflow preventer/RPZ-BFP - 2" LW	2 ea	1,657.68 /ea	3,315
Backflow preventer/RPZ-BFP - 4"	1 ea	1,960.75 /ea	1,961
Pressure reducing valve/PRV - 1"	1 ea	1,159.21 /ea	1,159
Pressure reducing valve - 4"	1 ea	2,210.75 /ea	2,211
Recirculation pump/bronze/6.5 gpm - 1/8 hp (B&G Ecocirc)	1 ea	1,806.14 /ea	1,806
Recirculation pump/bronze/10 gpm - 1/6 hp (B&G #SSF-22)	2 ea	709.14 /ea	1,418
Expansion tank/ASME/potable - 9 gal (B&G #PTA-30V)	1 ea	1,250.61 /ea	1,251
TMV/master/hi-lo temp.	1 ea	2,759.21 /ea	2,759
Hose bibbs w/vac. breaker/encased - interior	19 ea	382.50 /ea	7,268



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>22.10.00 Plumbing Facility Water Distribution</b>			
Hose bibbs/exterior/encased (Zurn #Z1320)	3 ea	452.07 /ea	1,356
Trap primers/electronic - 8 outlet (PPP #PT-8)	8 ea	1,359.91 /ea	10,879
Shock absorbers/12 - 33 fixture units (Shoktrol #200)	3 ea	269.77 /ea	809
Valve box/washing machine	1 ea	226.54 /ea	227
Valve box/ice machine	3 ea	176.54 /ea	530
Domestic water entrance UG/ductile iron - 4"	20 lf	306.14 /lf	6,123
Domestic water AG/type "L" copper/press fit ftgs. - avg. size	525 lf	23.31 /lf	12,235
Domestic water AG/type "L" copper/press fit - 1/2" TP	1,120 lf	13.02 /lf	14,577
Domestic water AG/type "L" copper/press fit - 1/2" NP	800 lf	13.02 /lf	10,412
Domestic water AG/type "L" copper/press fit - 1/2"	1,460 lf	13.02 /lf	19,002
Domestic water AG/type "L" copper/press fit - 3/4" NP	450 lf	15.76 /lf	7,091
Domestic water AG/type "L" copper/press fit - 3/4"	1,240 lf	15.76 /lf	19,539
Domestic water AG/type "L" copper/press fit - 1" NP	100 lf	20.56 /lf	2,056
Domestic water AG/type "L" copper/press fit - 1"	50 lf	20.57 /lf	1,028
Domestic water AG/type "L" copper/press fit - 1-1/4" NP	100 lf	25.23 /lf	2,523
Domestic water AG/type "L" copper/press fit - 1-1/4"	115 lf	25.23 /lf	2,902
Domestic water AG/type "L" copper/press fit - 1-1/2"	400 lf	30.31 /lf	12,125
Domestic water AG/type "L" copper/press fit - 2" NP	450 lf	41.16 /lf	18,523
Domestic water AG/type "L" copper/press fit - 2"	300 lf	41.16 /lf	12,349
Domestic water AG/type "L" copper/press fit - 2-1/2"	285 lf	66.38 /lf	18,919
Domestic water AG/type "L" copper/press fit - 3"	480 lf	84.91 /lf	40,759
Domestic water AG/type "L" copper/press fit - 4"	100 lf	116.00 /lf	11,600
Non-potable water AG/type "L" copper/solder - Hood Tie In	60 lf	22.94 /lf	1,377
- Domestic water piping accessories DOM	6,095 lf	2.78 /lf	16,917
- Domestic water piping accessories NP	1,900 lf	2.78 /lf	5,274
- Domestic water heat tracing/small bore piping All LHW	1,900 lf	25.97 /lf	49,340
- Domestic water pipe & equipment I.D. DOM	6,095 lf	1.61 /lf	9,817
- Domestic water pipe & equipment I.D. NP	1,900 lf	1.52 /lf	2,881
- Domestic water pressure gauges & thermometers	12 ea	120.61 /ea	1,447
- Domestic water support steel/additional to hangers & clamps	1 ls	1,074.56 /ls	1,075
- Layout Mech Room	1 ls	20,000.00 /ls	20,000
- Domestic water storage tank	1 ls	3.52 /ls	4
<b>Plumbing Facility Water Distribution</b>	<b>136,600 sf</b>	<b>2.67 /sf</b>	<b>365,038</b>

22.13.00 PLUMBING - Sanitary, Waste & Vent Piping

Floor drain - 3" (#ZN415-6B)	16 ea	294.07 /ea	4,705
Floor drain - 4" (#ZN415-8B)	4 ea	353.07 /ea	1,412
Floor sink/12x12 - 4" (#Z1900)	8 ea	2,581.14 /ea	20,649
Floor cleanouts - 4" (#ZN1400)	37 ea	291.07 /ea	10,770
Wall cleanouts - 4" (#Z1468)	10 ea	101.08 /ea	1,011



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>22.13.00 PLUMBING - Sanitary, Waste &amp; Vent Piping</b>			
Grease interceptor/interior/size 800/75 gpm/150 gal.	2 ea	4,291.56 /ea	8,583
8000 Gallon Concrete Grease Trap	1 ea	17,649.12 /ea	17,649
Elevator sump pump/oil minder	1 ea	3,812.28 /ea	3,812
Grease interceptor flow control	1 ea	417.14 /ea	417
Sanitary UG/cast iron single hub pipe & ftgs. - 2"	220 lf	31.98 /lf	7,036
Sanitary UG/cast iron single hub pipe & ftgs. - 3"	236 lf	36.45 /lf	8,602
Sanitary UG/cast iron single hub pipe & ftgs. - 4"	610 lf	44.78 /lf	27,315
Sanitary UG/cast iron single hub pipe & ftgs. - 6"	275 lf	74.82 /lf	20,576
Sanitary AG/cast iron no hub pipe & ftgs. - avg. size Fixture Runouts	1,560 lf	47.33 /lf	73,828
Sanitary AG/cast iron no hub pipe & ftgs. - 1-1/2"	30 lf	33.82 /lf	1,015
Sanitary AG/cast iron no hub pipe & ftgs. - 2"	750 lf	34.83 /lf	26,119
Sanitary AG/cast iron no hub pipe & ftgs. - 3"	980 lf	44.36 /lf	43,468
Sanitary AG/cast iron no hub pipe & ftgs. - 4"	495 lf	52.52 /lf	25,999
Grease waste UG/cast iron single hub pipe & ftgs. - 2"	40 lf	31.98 /lf	1,279
Grease waste UG/cast iron single hub pipe & ftgs. - 3"	20 lf	36.45 /lf	729
Grease waste UG/cast iron single hub pipe & ftgs. - 4"	220 lf	44.78 /lf	9,851
Grease waste AG/cast iron no hub pipe & ftgs. - 2"	55 lf	34.83 /lf	1,915
Grease waste AG/cast iron no hub pipe & ftgs. - 3"	65 lf	44.36 /lf	2,883
Grease waste AG/cast iron no hub pipe & ftgs. - 4"	70 lf	52.52 /lf	3,677
- Sanitary waste & vent piping accessories	5,626 lf	1.77 /lf	9,976
- Sanitary piping & equipment I.D.	5,626 lf	1.81 /lf	10,171
<b>PLUMBING - Sanitary, Waste &amp; Vent Piping</b>	<b>136,600 sf</b>	<b>2.51 /sf</b>	<b>343,448</b>
<b>22.14.00 PLUMBING - Rainleader Piping</b>			
Roof drain/#ZC100 - 4"	9 ea	298.07 /ea	2,683
Roof drain/#ZC100 - 5"	2 ea	387.84 /ea	776
Roof drain/#ZC100 - 6"	14 ea	387.84 /ea	5,430
Floor cleanouts - 4" (#ZN1400)	6 ea	291.07 /ea	1,746
Wall cleanouts - 4" (#Z1468)	12 ea	101.07 /ea	1,213
Rainleader UG/cast iron single hub pipe & ftgs. - 4"	90 lf	44.77 /lf	4,030
Rainleader UG/cast iron single hub pipe & ftgs. - 6"	90 lf	74.82 /lf	6,734
Rainleader UG/cast iron single hub pipe & ftgs. - 8"	70 lf	103.25 /lf	7,228
Rainleader UG/cast iron single hub pipe & ftgs. - 10"	160 lf	141.04 /lf	22,566
Rainleader UG/cast iron single hub pipe & ftgs. - 12"	25 lf	186.99 /lf	4,675
Rainleader AG/cast iron no hub pipe & ftgs. - 4"	265 lf	52.53 /lf	13,919
Rainleader AG/cast iron no hub pipe & ftgs. - 6"	410 lf	81.16 /lf	33,274
Rainleader AG/cast iron no hub pipe & ftgs. - 8"	460 lf	133.84 /lf	61,565
Rainleader AG/cast iron no hub pipe & ftgs. - 10"	10 lf	198.47 /lf	1,985
- Rainleader piping accessories	1,580 lf	1.77 /lf	2,802
- Rainleader piping & equipment I.D.	1,580 lf	1.46 /lf	2,314



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>PLUMBING - Rainleader Piping</b>	<b>136,600 sf</b>	<b>1.27 /sf</b>	<b>172,939</b>
<b>22.20.00 Plumbing Facility Gas Piping - Natural &amp; LP Gas</b>			
Gas Flow Meter - avg. size	1 ea	1,857.68 /ea	1,858
Emergency gas shut off/cabinet w/1" solenoid & UL ball valve 1114, 1111A	2 ea	3,968.42 /ea	7,937
Emergency gas shut off/cabinet w/1-1/2" solenoid & UL ball valve KIT	1 ea	5,093.42 /ea	5,093
- Remote panic buttons	2 ea	828.07 /ea	1,656
Gas turret/single	5 ea	212.07 /ea	1,060
Gas turret/double	5 ea	320.54 /ea	1,603
Gas piping/sch 40 black steel CW t&c - 1"	240 lf	28.68 /lf	6,882
Gas piping/sch 40 black steel CW t&c - 1-1/4"	120 lf	34.14 /lf	4,097
Gas piping/sch 40 black steel CW t&c - 1-1/2"	65 lf	37.25 /lf	2,421
Gas piping/sch 40 black steel CW t&c - 2"	10 lf	42.28 /lf	423
Gas piping/sch 40 blk stl ERW weld - 2-1/2"	30 lf	45.73 /lf	1,372
Gas piping/sch 40 blk stl ERW weld - 3"	75 lf	54.12 /lf	4,059
Gas piping/sch 40 blk stl ERW weld - 4"	60 lf	87.71 /lf	5,263
Gas piping/sch 40 blk stl ERW weld - 8"	25 lf	180.43 /lf	4,511
- Gas piping accessories	625 lf	2.52 /lf	1,577
- Gas piping link seals	1 ea	404.61 /ea	405
- Gas piping & equipment I.D.	625 lf	28.95 /lf	18,094
<b>Plumbing Facility Gas Piping - Natural &amp; LP Gas</b>	<b>136,600 sf</b>	<b>0.50 /sf</b>	<b>68,310</b>
<b>22.30.00 PLUMBING - Equipment</b>			
Domestic Boilers/gas fired/399 mbh (AO Smith #BTH-300A)	2 ea	15,618.42 /ea	31,237
Boiler Flues	1 ls	45,525.00 /ls	45,525
Water Heater Flues	1 ls	24,000.00 /ls	24,000
HWH/indirect fed - 300 gal	1 ea	7,418.42 /ea	7,418
<b>PLUMBING - Equipment</b>	<b>136,600 sf</b>	<b>0.79 /sf</b>	<b>108,180</b>
<b>22.40.00 PLUMBING - Fixtures</b>			
Water closet/wall mnt./carrier/flush valve	22 ea	1,330.12 /ea	29,263
Water closet/wall mnt./carrier/flush valve/ADA	32 ea	1,367.52 /ea	43,761
Urinal/wall mnt./carrier/flush valve	18 ea	1,202.85 /ea	21,651
Urinal/wall mnt./carrier/flush valve/ADA	5 ea	1,241.35 /ea	6,207
Lavatory/undermount/std 1-lever faucet	54 ea	523.24 /ea	28,255
Lavatory/undermount/std 1-lever faucet/ADA	10 ea	586.41 /ea	5,864
Lavatory/wall hung/std 1-lever faucet/carrier/ADA	15 ea	1,147.55 /ea	17,213
Mixing valve/single lav. (Leonard #170)	85 ea	348.84 /ea	29,651
P15 Sink/lay-in/1-bowl 20"x22"/std faucet/ADA	2 ea	1,560.75 /ea	3,121
P14 Sink/lay-in/1-bowl 20"x22"/std faucet/ADA Maker Space	2 ea	1,610.75 /ea	3,221



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>22.40.00 PLUMBING - Fixtures</b>			
P7 Sink/lay-in/1-bowl 21"x15"/std faucet	36 ea	1,584.98 /ea	57,059
P9 Sink/lay-in/1-bowl 21"x15"/std faucet Art Room	3 ea	1,384.98 /ea	4,155
P9A Sink/lay-in/1-bowl 21"x15"/std faucet/ADA Art Room	1 ea	1,455.75 /ea	1,456
P7A Sink/lay-in/1-bowl 21"x15"/std faucet/ADA	3 ea	1,860.75 /ea	5,582
P8 Sink/lay-in/1-bowl/22"x16"/bubbler	5 ea	1,715.35 /ea	8,577
P-13 Sink/acid waste/undermount/std 2-lever faucet/ss - 21"x15"x10"D	3 ea	1,508.82 /ea	4,526
- Solids interceptors (Art Room sinks)	4 ea	552.64 /ea	2,211
Mop sink/floor mnt - 24"x24"	5 ea	1,349.01 /ea	6,745
P6 Shower stall/std valve & access./3'x3' fiberglass	1 ea	2,704.96 /ea	2,705
P6-A Shower stall/std valve & access./5'x3' fiberglass/ADA	2 ea	3,701.67 /ea	7,403
P13 Emergency eye wash station/mixing valve/sink mount	3 ea	1,106.71 /ea	3,320
Emergency shower/eye wash sta./mixing valve/cabinet mount	7 ea	3,540.35 /ea	24,782
Water cooler/bi-level/ADA	10 ea	4,418.42 /ea	44,184
- Plumbing fixtures offload & distribution	239 ea	103.07 /ea	24,634
- Plumbing fixtures rough-in	239 ea	128.07 /ea	30,609
<b>PLUMBING - Fixtures</b>	<b>136,600 sf</b>	<b>3.05 /sf</b>	<b>416,156</b>
<b>22.66.00 Plumbing Acid Neutrillization System</b>			
Acid neut. Tank/5 gallon - 1-sink (Orion style 5)	1 ea	622.14 /ea	622
Acid neut. tank/15 gallon - 3-sinks (Orion style 5)	3 ea	911.21 /ea	2,734
Acid neut. tank/55 gallon -	2 ea	1,912.28 /ea	3,825
- Limestone chips/50 lb. bag	24 ea	43.77 /ea	1,050
PH Monitoring (2) locations	2 ea	6,612.28 /ea	13,225
Floor drain - 6" (#ZN415-AA-8B)	3 ea	480.84 /ea	1,443
Floor cleanout/heavy duty - 4" (#ZN1400-K-AR)	5 ea	424.84 /ea	2,124
Wall cleanouts/#Z1468 - 4"	5 ea	101.07 /ea	505
Acid waste UG/sch 40 polypropylene fuseal & ftgs. - 3"	20 lf	58.29 /lf	1,166
Acid waste UG/sch 40 polypropylene fuseal & ftgs. - 4"	230 lf	68.91 /lf	15,849
Tie-ins to Lab Hoods acid waste & vent - A/G	3 ea	815.35 /ea	2,446
Acid waste AG/sch 40 polypropylene fuseal & ftgs. - 2"	800 lf	51.44 /lf	41,154
Acid waste AG/sch 40 polypropylene fuseal & ftgs. - 3"	400 lf	65.67 /lf	26,269
Acid waste AG/sch 40 polypropylene fuseal & ftgs. - 4"	360 lf	77.44 /lf	27,877
- Acid waste & vent piping accessories	1,790 lf	2.02 /lf	3,622
- Acid waste piping & equipment I.D.	1,790 lf	2.56 /lf	4,585
<b>Plumbing Acid Neutrillization System</b>	<b>136,600 sf</b>	<b>1.09 /sf</b>	<b>148,495</b>
<b>22.90.00 Plumbing - Other</b>			
Wiring PH Monitor and Misc Control	1 ls	6,000.00 /ls	6,000



Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Plumbing - Other</b>	<b>136,600 sf</b>	<b>0.04 /sf</b>	<b>6,000</b>
<b>22-01 PLUMBING (TS)</b>	<b>136,600 sf</b>	<b>14.17 /sf</b>	<b>1,935,182</b>
<b>23-01 HVAC (TS)</b>			
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (HVAC)	(1) ls	343,000.00 /ls	(343,000)
Trade support - lull, laborer for cleanup (HVAC)	1 ls	343,000.00 /ls	343,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>23.00.05 HVAC - General Requirements</b>			
General requirements (sq. ft.)	136,600 sf	1.15 /sf	157,090
3D/BIM coordination	1 ls	100,000.00 /ls	100,000
<b>HVAC - General Requirements</b>	<b>136,600 sf</b>	<b>1.88 /sf</b>	<b>257,090</b>
<b>23.05.93 HVAC Testing Adjusting &amp; Balancing (TAB)</b>			
Testing & balancing/cost per sq. ft.	136,600 sf	0.65 /sf	88,790
<b>HVAC Testing Adjusting &amp; Balancing (TAB)</b>	<b>136,600 sf</b>	<b>0.65 /sf</b>	<b>88,790</b>
<b>23.07.00 HVAC - Insulation</b>			
Insulation/ductwork/blanket wrap	83,500 sf	3.55 /sf	296,088
Insulation/ductwork/weatherproof exposed	4,500 sf	12.89 /sf	57,986
Insulation/pipe/copper	14,483 lf	7.09 /lf	102,715
Insulation/pipe/weld	3,838 lf	12.50 /lf	47,975
<b>HVAC - Insulation</b>	<b>136,600 sf</b>	<b>3.70 /sf</b>	<b>504,764</b>
<b>23.08.00 HVAC - Commissioning Support</b>			
Commissioning support/lump sum	1 ls	15,000.00 /ls	15,000
<b>HVAC - Commissioning Support</b>	<b>136,600 sf</b>	<b>0.11 /sf</b>	<b>15,000</b>
<b>23.09.00 HVAC - Automatic Temperature Controls</b>			
Automatic temperature controls/cost per sq. ft.	136,600 sf	0.25 /sf	34,150
ATC - Air valve/hood exhaust/HEX	3 ea	4,194.32 /ea	12,583
ATC - Air valves/no coil control wiring - 3 pts./fume hood	9 pnt	437.00 /pnt	3,933
ATC - RTU's/custom - 30 pts.	240 pnt	1,303.18 /pnt	312,763
ATC - MUA units - 10 pts.	10 pnt	759.44 /pnt	7,594
ATC - Exhaust fans - 3 pts.	18 pnt	711.10 /pnt	12,800
ATC - Life safty fans - 8 pts.	32 pnt	766.15 /pnt	24,517
ATC - Lab exhaust fans - 5 pts./fan	25 pnt	766.15 /pnt	19,154
ATC - Boilers/modular - 10 pts.	20 pnt	821.19 /pnt	16,424
ATC - Pumps - 4 pts.	16 pnt	766.15 /pnt	12,258
ATC - VFD wiring for pumps (remote mount) - 4 pts.	16 pnt	763.91 /pnt	12,223
ATC - Circulators - 2 pts.	4 pnt	488.68 /pnt	1,955





90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>23.09.00 HVAC - Automatic Temperature Controls</b>			
ATC - Chillers - 15 pts.	15 pnt	1,303.18 /pnt	19,548
ATC - VAV box/no coil (ATC furn./factory install controls) 2 pts.	310 pnt	408.36 /pnt	126,592
ATC - Fintube radiation zones - 2 pts.	20 pnt	381.96 /pnt	7,639
ATC - electric fintube radiation zones - 2 pts.	4 pnt	381.95 /pnt	1,528
ATC - Cabinet unit heaters - 3 pts.	42 pnt	381.96 /pnt	16,042
ATC - Unit heaters - 3 pts.	6 pnt	381.95 /pnt	2,292
ATC - Radiant ceiling panel zones - 2 pts.	246 pnt	381.96 /pnt	93,961
ATC - Plumbing points - 10 pts.	10 pnt	595.50 /pnt	5,955
ATC - Elctrical points - 10 pts.	10 pnt	595.50 /pnt	5,955
<b>HVAC - Automatic Temperature Controls</b>	<b>136,600 sf</b>	<b>5.49 /sf</b>	<b>749,864</b>
<b>23.21.13 Hydronic Piping</b>			
Hot water s&r/type "L" copper solder - 3/4"	8,970 lf	20.16 /lf	180,835
Hot water s&r/type "L" copper solder - 1"	1,760 lf	25.01 /lf	44,018
Hot water s&r/type "L" copper solder - 1-1/4"	1,260 lf	28.57 /lf	35,998
Hot water s&r/type "L" copper solder - 1-1/2"	890 lf	32.82 /lf	29,210
Hot water s&r/type "L" copper solder - 2"	1,550 lf	41.25 /lf	63,937
Hot water s&r/sch 40 blk stl ERW weld - 2-1/2"	605 lf	50.55 /lf	30,583
Hot water s&r/sch 40 blk stl ERW weld - 3"	475 lf	59.42 /lf	28,225
Hot water s&r/sch 40 blk stl ERW weld - 4"	756 lf	82.30 /lf	62,219
Hot water s&r/sch 40 blk stl ERW weld - 6"	520 lf	134.07 /lf	69,716
Hot water s&r/sch 40 blk stl ERW weld - 8"	220 lf	167.74 /lf	36,903
Glycol water s&r/type "L" copper solder - 2"	53 lf	41.25 /lf	2,186
Glycol water s&r/sch 40 blk stl ERW weld - 2-1/2"	47 lf	50.55 /lf	2,376
Glycol water s&r/sch 40 blk stl ERW weld - 3"	90 lf	59.42 /lf	5,348
Glycol water s&r/sch 40 blk stl ERW weld - 4"	152 lf	82.30 /lf	12,510
Glycol water s&r/sch 40 blk stl ERW weld - 6"	910 lf	134.07 /lf	122,004
Glycol water s&r/sch 40 blk stl ERW weld - 8"	110 lf	167.74 /lf	18,451
- Hydronic piping accessories	18,368 lf	2.53 /lf	46,506
<b>Hydronic Piping</b>	<b>136,600 sf</b>	<b>5.79 /sf</b>	<b>791,024</b>
<b>23.21.23 Hydronic Pumps &amp; Accessories</b>			
Pump/base mount/790 gpm (HW)	2 ea	8,167.68 /ea	16,335
Chilled water pump house (pumps & accesories, enclosure, piping, unit heater	1 ls	226,667.68 /ls	226,668
- Suction diffusers	2 ea	1,460.58 /ea	2,921
- Flex connector/HVAC pumps	4 ea	556.35 /ea	2,225
- Triple duty valves	2 ea	2,312.69 /ea	4,625
Air separators	1 ea	4,333.84 /ea	4,334
Expansion tanks/ASME	2 ea	7,167.68 /ea	14,335



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Hydronic Pumps &amp; Accessories</b>	<b>136,600 sf</b>	<b>1.99 /sf</b>	<b>271,444</b>
<b>23.25.00 HVAC Water Treatment</b>			
Chemical treatment (lump sum)	1 ls	20,000.00 /ls	20,000
Glycol feed/50 gal. tank w/pump (Neptune #G-50-1)	2 ea	5,272.92 /ea	10,546
- Glycol solution/40% propylene	1,000 gal	25.21 /gal	25,212
<b>HVAC Water Treatment</b>	<b>136,600 sf</b>	<b>0.41 /sf</b>	<b>55,757</b>
<b>23.30.00 HVAC - Sheetmetal &amp; Fans</b>			
Sheetmetal & accessories/galvanized	101,200 lb	11.04 /lb	1,117,248
Sheetmetal & accessories/galvanized (perforated)	790 lb	14.49 /lb	11,447
Sheetmetal & accessories/galvanized (smoke exhasut)	8,850 lb	11.04 /lb	97,704
Sheetmetal & accessories/stainless steel (dishwasher)	350 lb	22.28 /lb	7,798
Sheetmetal & accessories/welded stainless steel (kitchen exhaust)	1,060 lb	29.78 /lb	31,567
Sheetmetal & accessories/welded stainless steel (kiln exhaust)	500 lb	29.78 /lb	14,890
Sheetmetal & accessories/welded stainless steel (3 - fume hoods)	2,700 lb	29.78 /lb	80,406
Sheetmetal & accessories/fabric/1-row cable (DuctSox) - 20"	405 lf	76.50 /lf	30,982
Sheetmetal & accessories/fabric/1-row cable (DuctSox) - 24"	305 lf	81.29 /lf	24,792
Duct enclosure (roof)	1 ea	5,424.10 /ea	5,424
SM - Flue piping/double wall/stainless steel/6" pipe - linear foot DWH	600 lf	97.98 /lf	58,786
SM - Flue piping/double wall/stainless steel/6" fittings - each DWH	16 ea	122.47 /ea	1,960
SM - Flue piping/double wall/stainless steel/6" fittings - each DWH	8 lf	122.47 /lf	980
SM - Diffusers, registers & grilles	136,600 sf	0.20 /sf	27,320
SM - Linear slot diffusers (supply)	6 ea	465.39 /ea	2,792
SM - Linear slot diffusers (exhaust) - architectural	lf	/lf	
SM - Displ. Diffuser/Floor Mnt.	156 ea	1,289.88 /ea	201,221
SM - Combination fire/smoke dampers/louver type/UL	20 ea	776.53 /ea	15,530
SM - Motorized damper	14 ea	1,107.92 /ea	15,511
SM - Smoke detectors/duct mount	40 ea	747.47 /ea	29,899
SM - Sound attenuators/in-line/std. gauge	239,000 cfm	0.55 /cfm	131,341
SM - Kitchen exhaust hood/st. steel/install only (by KES)	1 ea	2,339.28 /ea	2,339
SM - Dishwasher exhaust hood/st. steel/install only (by KES)	1 ea	1,559.52 /ea	1,560
<b>HVAC - Sheetmetal &amp; Fans</b>	<b>136,600 sf</b>	<b>13.99 /sf</b>	<b>1,911,497</b>
<b>23.34.00 HVAC Fans - Exhaust &amp; Supply</b>			
SEF-1-4	4 ea	17,339.28 /ea	69,357
EF-3&4 /centrifugal downblast/roof/direct drive - 500 cfm	2 ea	1,069.31 /ea	2,139
EF-1&2 /centrifugal downblast/roof/direct drive - 2,500 cfm	2 ea	1,771.24 /ea	3,542
KEF-1&2/centrifugal upblast/roof	2 ea	2,734.82 /ea	5,470
FEF-1,2,3,4,5 Lab exhaust fan/roof - 1,200 cfm	5 ea	9,084.82 /ea	45,424



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>HVAC Fans - Exhaust &amp; Supply</b>	<b>136,600 sf</b>	<b>0.92 /sf</b>	<b>125,932</b>
<b>23.35.00 Specialty Exhaust Systems</b>			
Dust collection system	1 ea	17,339.28 /ea	17,339
Kiln exhaust	1 ls	5,500.00 /ls	5,500
<b>Specialty Exhaust Systems</b>	<b>136,600 sf</b>	<b>0.17 /sf</b>	<b>22,839</b>
<b>23.36.00 Air Terminal Units - VAV's, CAV's &amp;FPB's</b>			
Variable air volume box - small	12 ea	533.15 /ea	6,398
Variable air volume box - medium	143 ea	668.62 /ea	95,612
<b>Air Terminal Units - VAV's, CAV's &amp;FPB's</b>	<b>136,600 sf</b>	<b>0.75 /sf</b>	<b>102,010</b>
<b>23.50.00 HVAC - Central Heating Equipment</b>			
Boiler/HW/gas/high eff. cond. - 4,000 mbh Riello AR 4000	2 ea	57,501.52 /ea	115,003
Boiler circulator pump	2 ea	1,708.46 /ea	3,417
Boiler combustion air/galvanized steel 10"	200 lf	38.00 /lf	7,600
Flue piping/double wall/stainless steel 10"	205 lf	185.00 /lf	37,925
<b>HVAC - Central Heating Equipment</b>	<b>136,600 sf</b>	<b>1.20 /sf</b>	<b>163,945</b>
<b>23.60.00 HVAC - Central Cooling Equipment</b>			
Chiller/air cooled - 370 tons	1 ea	381,153.80 /ea	381,154
Buffer tanks/Lochinvar - 300 gals.	1 ea	8,750.76 /ea	8,751
<b>HVAC - Central Cooling Equipment</b>	<b>136,600 sf</b>	<b>2.85 /sf</b>	<b>389,905</b>
<b>23.70.00 HVAC - Central Air Handling Equipment</b>			
RTU-1-4 Classrooms (service enclosure, HW&CHW coils, energy recovery)	80,000 cfm	15.75 /cfm	1,260,000
RTU-5 Gymnasium (service enclosure, HW&CHW coils, energy recovery)	15,000 cfm	16.25 /cfm	243,750
RTU-6 Auditorium (service enclosure, HW&CHW coils, energy recovery)	12,000 cfm	16.25 /cfm	195,000
RTU-7 Lockers (service enclosure, HW&CHW coils, energy recovery)	2,000 cfm	18.25 /cfm	36,500
MAU-1 Make-up air unit/HW&CHW coil/	5,000 cfm	7.25 /cfm	36,250
<b>HVAC - Central Air Handling Equipment</b>	<b>136,600 sf</b>	<b>12.97 /sf</b>	<b>1,771,500</b>
<b>23.80.20 Mini-Split AC &amp; Heat Pump Systems</b>			
Mini-split AC system/1-zone/wall mnt./cool only - 12 mbh	1 ea	2,072.92 /ea	2,073
Mini-split AC system/1-zone/wall mnt./cool only - 18 mbh	5 ea	2,681.66 /ea	13,408
Mini-split AC system/1-zone/wall mnt./cool only - 24 mbh	2 ea	2,956.03 /ea	5,912
Mini-split refrigeration line set/6-12 mbh - 50'	2 ea	584.88 /ea	1,170
Mini-split refrigeration line set/15-18 mbh - 50'	10 ea	599.88 /ea	5,999



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>23.80.20 Mini-Split AC &amp; Heat Pump Systems</b>			
Mini-split refrigeration line set/24-30 mbh - 50'	4 ea	614.88 /ea	2,460
Mini-split condensate drains/type"L" copper	450 lf	19.43 /lf	8,744
A/C cond. pump	8 ea	253.74 /ea	2,030
INS - Mini-split Insulation/copper pipe	450 lf	6.87 /lf	3,090
ATC - Mini-split condensing units (w/factory controls)	8 ea	879.76 /ea	7,038
ATC - Mini-split indoor units (w/factory controls)	8 ea	587.35 /ea	4,699
<b>Mini-Split AC &amp; Heat Pump Systems</b>	<b>136,600 sf</b>	<b>0.42 /sf</b>	<b>56,622</b>
<b>23.82.00 Heating &amp; Cooling Terminal Equipment</b>			
Radiant ceiling panels/24" wide - ft.	1,450 lf	120.00 /lf	174,000
FTR-2 Finned-tube radiation w/enclosure - 1 row	260 lf	194.24 /lf	50,502
FTR-1 Finned-tube radiation w/enclosure - 2 row	570 lf	259.37 /lf	147,841
FTR-3 Finned-tube radiation w/enclosure - 2 row	40 lf	297.49 /lf	11,900
Fin-tube radiation/electric - 2 kW	8 ea	739.88 /ea	5,919
Cabinet unit heater/hot water/wall mount/recessed - avg. size	4 ea	1,573.62 /ea	6,294
Cabinet unit heater/hot water/ceiling mount - avg. size	10 ea	1,749.51 /ea	17,495
Unit heater/hot water/horiz./propeller - avg. size	2 ea	1,092.41 /ea	2,185
<b>Heating &amp; Cooling Terminal Equipment</b>	<b>136,600 sf</b>	<b>3.05 /sf</b>	<b>416,136</b>
<b>23.85.00 HVAC Equipment VFD's</b>			
Misc. VFD's	1 ls	35,000.00 /ls	35,000
VFD w/keypad/disconnect/bypass/NEMA 1 - HW pumps	2 ea	6,028.47 /ea	12,057
VFD w/keypad/disconnect/bypass/NEMA 1 - CHW pumps w/ pump house	ea	/ea	
<b>HVAC Equipment VFD's</b>	<b>136,600 sf</b>	<b>0.34 /sf</b>	<b>47,057</b>
<b>23.90.00 HVAC Equipment Rigging/Setting/Start Up</b>			
Equipment hoisting/rigging/setting/start-up	136,600 sf	1.50 /sf	204,900
<b>HVAC Equipment Rigging/Setting/Start Up</b>	<b>136,600 sf</b>	<b>1.50 /sf</b>	<b>204,900</b>
<b>23-01 HVAC (TS)</b>	<b>136,600 sf</b>	<b>58.17 /sf</b>	<b>7,946,076</b>
<b>26-01 ELECTRICAL (TS)</b>			
<b>01.74.00 Cleaning &amp; Waste Management</b>			
Lull, laborer for cleanup by Consigli (Electrical)	(1) ls	230,000.00 /ls	(230,000)
Trade support - lull, laborer for cleanup (Electrical)	1 ls	230,000.00 /ls	230,000
<b>Cleaning &amp; Waste Management</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>26.00.05 Electrical General Requirements</b>			
LEED Silver - premium (T.B.D.)	1 ls	9,400.00 /ls	9,400
Temp light stringers & GFCI power	136,600 sf	0.35 /sf	47,810



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>26.00.05 Electrical General Requirements</b>			
Temp 480Y/277V electrical service (400A)	3 ea	18,226.22 /ea	54,679
Temp power for welders	2 ea	2,398.27 /ea	4,797
Temp power for trailers	4 ea	1,302.42 /ea	5,210
Temp internet connection for trailers	4 ea	1,854.17 /ea	7,417
Material handling / project mgmt.	250 mh	97.71 /mh	24,428
3D/BIM coordination	500 mh	97.71 /mh	48,856
Record drawings / as-builts	1 ea	5,318.52 /ea	5,319
Seismic & testing (panels, generator, lighting control, fire alarm)	1 ls	18,800.00 /ls	18,800
Coring - patching - firestopping	136,600 sf	0.09 /sf	12,840
Project phasing (re-mobilization)	1 ls	9,400.00 /ls	9,400
Hoisting & rigging (generator & switchboard)	2 ls	7,050.00 /ls	14,100
<b>Electrical General Requirements</b>	<b>136,600 sf</b>	<b>1.93 /sf</b>	<b>263,055</b>
<b>26.05.05 Demolition for Electrical</b>			
Relocate existing emergency call box (provide new concrete base)	1 ea	2,994.80 /ea	2,995
Remove existing exterior site light fixture	11 ea	672.85 /ea	7,401
<b>Demolition for Electrical</b>	<b>136,600 sf</b>	<b>0.08 /sf</b>	<b>10,396</b>
<b>26.05.08 Electrical Distribution</b>			
Feeder (PVC/CU) - 150A [generator / LS]	135 lf	22.18 /lf	2,994
Feeder (PVC/CU) - 225A [generator / OS]	135 lf	33.46 /lf	4,517
Feeder (PVC/CU) - 400A [generator / LR] (exterior)	135 lf	56.93 /lf	7,685
Feeder (PVC/CU) - 2500A [secondary]	105 lf	414.00 /lf	43,470
Empty conduit - sch 40 PVC: 1 x 4" [generator]	135 lf	9.86 /lf	1,330
Empty conduit - sch 40 PVC: 1 x 4" [secondary / spare]	105 lf	9.86 /lf	1,035
Empty conduit - sch 40 PVC: 2 x 4" [primary]	250 lf	17.66 /lf	4,415
Magnetic warning tape - 1/8"	875 lf	4.37 /lf	3,826
Pole riser (GRC - 4"C)	2 ea	2,343.85 /ea	4,688
Electric manhole - 6'x12x7'	1 ea	6,773.56 /ea	6,774
Cast iron manhole frame/cover, 32"D x 6'H grade rings	1 ea	1,140.93 /ea	1,141
12" x 12" x 12"D ground mounted pullbox (Quazite #PC1212HG00 w/ Cover)	2 ea	752.15 /ea	1,504
Hand hole & cover - 4'x4'x4'	6 ea	1,937.11 /ea	11,623
17"x30"x12"D ground pullbox (Quazite #PC1730BA12 w/ cover)	11 ea	1,078.60 /ea	11,865
24" x 36" x 24"D ground mounted pullbox (Quazite #Pg2436BC-24 w/ Cover)	1 ea	1,718.39 /ea	1,718
<b>Electrical Distribution</b>	<b>136,600 sf</b>	<b>0.80 /sf</b>	<b>108,584</b>
<b>26.05.26 Grounding &amp; Bonding for Electrical Systems</b>			
Building grounding & bonding	136,600 sf	0.11 /sf	15,408



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>26.05.26 Grounding &amp; Bonding for Electrical Systems</b>			
Manhole / racking grounding & bonding	1 ea	701.05 /ea	701
Exterior (utility) transformer grounding & bonding	1 ea	1,066.05 /ea	1,066
Generator grounding & bonding	1 ea	1,066.05 /ea	1,066
SPD grounding (internal and external)	47 ea	120.29 /ea	5,653
Dry-type transformer grounding	4 ea	213.22 /ea	853
Copper ground bar - 2"x1/4" (ea.)	5 ea	280.03 /ea	1,400
Bare copper wire - #4/0 [duct bank]	875 lf	4.99 /lf	4,368
<b>Grounding &amp; Bonding for Electrical Systems</b>	<b>136,600 sf</b>	<b>0.22 /sf</b>	<b>30,516</b>
<b>26.05.83 Equipment Wiring</b>			
Science Classrooms - CO system solenoid shutdown- 120V power & control wiring	2 ea	5,326.40 /ea	10,653
Kitchen - Ansul system - 120V power & control wiring	1 ea	10,237.00 /ea	10,237
Gym scoreboards and shot clocks - wiring only, F&I by Div. 11	2 ea	5,344.80 /ea	10,690
Feeder (MC) - 20A (kitchen equipment - x42)	3,150 lf	5.75 /lf	18,111
Feeder (MC) - 30A (kitchen equipment - x2)	200 lf	5.87 /lf	1,173
1" PVC - 30A (3#8 & #10G)	250 lf	10.29 /lf	2,573
Feeder (MC) - 40A (kitchen equipment - x1)	100 lf	7.01 /lf	701
Feeder (MC) - 60A (kitchen equipment - x2)	200 lf	10.55 /lf	2,110
Power for automatic temperature control panels (BMS)	12 ea	460.91 /ea	5,531
Electric heat trace power (cables, sensors, controllers by Div. 21 / 22)	1,900 lf	3.50 /lf	6,650
Service switch: 20A/3P, NEMA-1	1 ea	107.43 /ea	107
Fused Disco: 20A/3P, NEMA-1	7 ea	323.22 /ea	2,263
Fused Disco: 100A/3P, NEMA-1	2 ea	1,185.41 /ea	2,371
Fused Disco: 200A/3P, NEMA-1	3 ea	1,555.38 /ea	4,666
Fused Disco: 1000A/3P, NEMA-1	2 ea	7,290.94 /ea	14,582
Wire gymnasium equipment SMC control stations (furnished by others)	8 ea	1,058.23 /ea	8,466
Electric vehicle charging station / dual pedestal / cable mgmt.	3 ea	10,512.40 /ea	31,537
Wire motors and controllers	15 ea	821.28 /ea	12,319
Kitchen equipment final connections (includes flexible whip)	47 ea	72.36 /ea	3,401
Mount & wire VFD's (furnished by Div. 23)	8 ea	646.55 /ea	5,172
MAU (5000cfm) - circuit / disconnect (3R) / connection	1 ea	2,503.41 /ea	2,503
RTU's - circuit / disconnect (3R) / connection (small)	3 ea	4,736.19 /ea	14,209
RTU's - circuit / disconnect (3R) / connection (large)	4 ea	7,010.29 /ea	28,041
Mini-split systems (indoor/outdoor) - circuits / disconnects (3R) / connections	8 ea	3,225.23 /ea	25,802
Chiller (370T) - circuit / disconnect (3R) / connection	1 ea	25,825.56 /ea	25,826
Smoke exhaust fans - circuit / disconnect / connection (100A)	4 ea	2,400.01 /ea	9,600
Kitchen exhaust fans - circuit / disconnect / connection	2 ea	1,420.91 /ea	2,842
Kiln exhaust system - circuit / disconnect / connection	1 ea	2,655.30 /ea	2,655



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>26.05.83 Equipment Wiring</b>			
Dust collection system - circuit / disconnect / connection	1 ea	3,579.00 /ea	3,579
Fume hood exhaust fans - circuit / disconnect / connection	5 ea	1,214.10 /ea	6,071
Exhaust fans - circuit / disconnect / connection	4 ea	1,214.11 /ea	4,856
Power to electronic trap primers - 120V	8 ea	100.19 /ea	801
Hot water pumps - circuit / disconnect / connection	2 ea	1,673.87 /ea	3,348
Boilers - circuit / disconnect / connection	2 ea	1,204.71 /ea	2,409
Chilled water pump house pumps & heaters - circuits / disconnects / connections	1 ls	6,158.00 /ls	6,158
Hot water heater - circuit / service switch / connection	1 ea	591.53 /ea	592
Cabinet unit heaters - circuit / service switch / connection	14 ea	868.28 /ea	12,156
Unit heaters - circuit / service switch / connection	2 ea	868.28 /ea	1,737
Elevator sump pump - circuit / disconnect (3R) / connection	1 ea	1,247.28 /ea	1,247
Domestic boilers - circuit / disconnect (3R) / connection	2 ea	1,247.28 /ea	2,495
Recirculation pumps - circuit / disconnect / connection	3 ea	997.87 /ea	2,994
Glycol feed pumps - circuit / disconnect / connection	2 ea	997.87 /ea	1,996
Boiler circulation pumps - circuit / disconnect / connection	2 ea	997.87 /ea	1,996
Fin-tube radiators (2kW) - circuit / disconnect / connection	8 ea	1,847.40 /ea	14,779
VAV's - circuit / disconnect / connection	155 ea	298.83 /ea	46,318
Acid neutralization tanks / PH monitoring - circuit / connection	2 ea	965.80 /ea	1,932
<b>Equipment Wiring</b>	<b>136,600 sf</b>	<b>2.78 /sf</b>	<b>380,253</b>
<b>26.09.23 Lighting Control Devices</b>			
On-site programming & startup (manufacturer)	1 ls	3,913.41 /ls	3,913
Single pole switch (120/277V)	13 ea	65.04 /ea	845
Key op switch (120/277V)	2 ea	72.44 /ea	145
Three position momentary contact switch	1 ea	226.42 /ea	226
Ceiling PIR occupancy sensor (24VDC)	323 ea	247.23 /ea	79,854
Occupancy sensor power packs (120V)	200 ea	82.04 /ea	16,408
Wall dimmer switch (0-10V)	227 ea	131.04 /ea	29,746
Photocells (daylight harvesting)	84 ea	265.06 /ea	22,265
Universal dimming room controller, 1-channel	50 ea	536.88 /ea	26,844
ALCS master switching / dimming station	1 ea	821.83 /ea	822
Plug load controllers (20A/120V)	50 ea	300.80 /ea	15,040
Emergency lighting transfer (bypass relay) - non-dimming	30 ea	236.81 /ea	7,104
Lighting contactor - 12 pole (exterior lighting)	1 ea	1,899.98 /ea	1,900
Astronomical time clock	1 ea	919.97 /ea	920
Rough in for Theater Lighting - Allowance	1 allw	9,400.01 /allw	9,400
Power for Theater Lighting - Allowance	1 allw	28,199.87 /allw	28,200
Sub lighting control panels	3 ea	2,394.56 /ea	7,184
Master lighting control panel	1 ea	4,383.41 /ea	4,383



### 90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>26.09.23 Lighting Control Devices</b>			
Energy control unit	1 ea	2,157.58 /ea	2,158
System server unit	1 ea	1,316.75 /ea	1,317
Network Ethernet switch	1 ea	2,270.85 /ea	2,271
MC Cable (12/2) - 20A	12,500 lf	3.45 /lf	43,126
MC Cable (12/3) - 20A	3,500 lf	3.87 /lf	13,541
EMT (12/2) - 20A	2,000 lf	6.70 /lf	13,404
EMT (12/2) - 20A	50 lf	7.13 /lf	356
RJ45 Cable, 25LF (plenum-rated)	407 ea	72.10 /ea	29,344
RJ45 Cable, 50LF (plenum rated)	228 ea	111.05 /ea	25,318
<b>Lighting Control Devices</b>	<b>136,600 sf</b>	<b>2.83 /sf</b>	<b>386,033</b>
<b>26.10.00 Medium Voltage Electrical Distribution</b>			
Utility meter socket (meter by Util. Co.)	1 ea	289.66 /ea	290
CT meter enclosure for switchboard	1 ea	1,462.26 /ea	1,462
<b>Medium Voltage Electrical Distribution</b>	<b>136,600 sf</b>	<b>0.01 /sf</b>	<b>1,752</b>
<b>26.27.00 Low-Voltage Distribution Equipment</b>			
Circuit breaker - 20A/1P (panel)	1 ea	149.86 /ea	150
Switchboard: 3000A bus, 2500A rated MCB (100%), 480/277V, 3PH, 65kAIC	1 ea	45,417.04 /ea	45,417
Externally mounted SPD's	6 ea	3,131.70 /ea	18,790
Panelboard: 100A, 42-circuit	14 ea	2,550.41 /ea	35,706
Panelboard: 225A, 42-circuit	9 ea	3,420.66 /ea	30,786
Panelboard: 225A, 84-circuit	9 ea	4,338.66 /ea	39,048
Panelboard: 400A, 42-circuit	3 ea	5,435.74 /ea	16,307
Panelboard: 400A, 84-circuit	1 ea	10,724.46 /ea	10,724
Distribution panel: 600A	2 ea	9,886.92 /ea	19,774
Distribution panel: 800A	3 ea	12,443.25 /ea	37,330
Transformer: floor/wall - 75kVA, 480V:208V	1 ea	4,384.00 /ea	4,384
K-13 Transformer: floor - 225kVA, 480V:208V	3 ea	12,168.50 /ea	36,506
Engineered Services - Training (Manufacturer)	1 ea	4,165.70 /ea	4,166
Engineered Services - Start-Up Assistance (Manufacturer)	1 ea	3,519.08 /ea	3,519
<b>Low-Voltage Distribution Equipment</b>	<b>136,600 sf</b>	<b>2.22 /sf</b>	<b>302,606</b>
<b>26.27.05 Low-Voltage Distribution Feeders</b>			
Feeder (EMT/CU) - 20A [BMS to utility meter]	200 lf	7.43 /lf	1,486
Feeder (EMT/CU) - 20A [EP1A to Elevator Controller]	125 lf	7.43 /lf	929
Feeder (EMT/CU) - 60A [MSB to SPD]	50 lf	14.69 /lf	735
Feeder (EMT/CU) - 60A [2DP1A to SPD]	50 lf	14.69 /lf	735
Feeder (EMT/CU) - 60A [2DP1B to SPD]	50 lf	14.69 /lf	735





90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>26.27.05 Low-Voltage Distribution Feeders</b>			
Feeder (EMT/CU) - 60A [2DP1C to SPD]	50 lf	14.69 /lf	735
Feeder (EMT/CU) - 60A [4DP1B to SPD]	50 lf	14.69 /lf	735
Feeder (EMT/CU) - 90A [2DP1A to KPP1A]	42 lf	15.96 /lf	670
Feeder (EMT/CU) - 100A [MSB to LP1A]	40 lf	20.74 /lf	830
Feeder (EMT/CU) - 100A [4DP1B to LP1B]	50 lf	20.74 /lf	1,037
Feeder (EMT/CU) - 100A [4DP1C to LP1C]	27 lf	20.74 /lf	560
Feeder (EMT/CU) - 100A [4DP1B to LP2B]	50 lf	20.74 /lf	1,037
Feeder (EMT/CU) - 100A [2DP1A to LP2C]	190 lf	20.74 /lf	3,940
Feeder (EMT/CU) - 100A [4DP1B to LP3B]	150 lf	20.74 /lf	3,111
Feeder (EMT/CU) - 100A [4DP1C to LP3C]	165 lf	20.74 /lf	3,422
Feeder (EMT/CU) - 100A [MSB to LP1D]	150 lf	20.74 /lf	3,111
Feeder (EMT/CU) - 100A [EHP1A to Elevator Controller]	125 lf	20.74 /lf	2,592
Feeder (EMT/CU) - 100A [TEP1A to TEP2B]	200 lf	20.74 /lf	4,148
Feeder (EMT/CU) - 100A [TEP1A to TEP2C]	200 lf	20.74 /lf	4,148
Feeder (EMT/CU) - 100A [TEP1A to TEP1D]	200 lf	20.74 /lf	4,148
Feeder (EMT/CU) - 100A [TEP1A to UPS]	50 lf	20.74 /lf	1,037
Feeder (EMT/CU) - 100A [2DP1A to MP1A]	410 lf	20.74 /lf	8,503
Feeder (EMT/CU) - 125A [UPS to EP1A]	150 lf	20.99 /lf	3,149
Feeder (EMT/CU) - 150A [2DP1B to MP1B]	50 lf	26.82 /lf	1,341
Feeder (EMT/CU) - 150A [2DP1C to MSB]	200 lf	26.82 /lf	5,365
Feeder (EMT/CU) - 150A [2DP1C to MP3C]	250 lf	26.82 /lf	6,706
Feeder (EMT/CU) - 150A [2DP1B to PP2B]	60 lf	26.82 /lf	1,609
Feeder (EMT/CU) - 150A [2DP1C to PP2C]	100 lf	26.82 /lf	2,682
Feeder (EMT/CU) - 150A [2DP1B to PP1B]	50 lf	26.82 /lf	1,341
Feeder (EMT/CU) - 150A [2DP1C to MP1C]	40 lf	26.83 /lf	1,073
Feeder (EMT/CU) - 150A [2DP1C to PP2C]	125 lf	26.82 /lf	3,353
Feeder (EMT/CU) - 150A [2DP1C to PP3C]	150 lf	26.82 /lf	4,024
Feeder (EMT/CU) - 150A [4DP1C to PP3B]	165 lf	26.82 /lf	4,426
Feeder (EMT/CU) - 150A [2DP1C to PP1C]	50 lf	26.82 /lf	1,341
Feeder (EMT/CU) - 150A [2DP1A to PP1D]	100 lf	26.82 /lf	2,682
Feeder (EMT/CU) - 200A [MSB to ATS-LS]	100 lf	32.13 /lf	3,213
Feeder (EMT/CU) - 200A [ATS-LS to ELP1A]	40 lf	32.13 /lf	1,285
Feeder (EMT/CU) - 200A [2DP1A to PP1A]	50 lf	32.13 /lf	1,607
Feeder (EMT/CU) - 200A [Cam Lock Box to ATS-LS]	60 lf	32.13 /lf	1,928
Feeder (EMT/CU) - 225A [MSB to Dimming Rack HDP]	250 lf	46.72 /lf	11,679
Feeder (EMT/CU) - 225A [2DP1A to Dimming Rack SDP]	200 lf	46.72 /lf	9,344
Feeder (EMT/CU) - 225A [EHP1A to EHP3C]	250 lf	46.72 /lf	11,679
Feeder (EMT/CU) - 225A [MP3C to PP3C]	45 lf	46.72 /lf	2,102
Feeder (EMT/CU) - 225A [2DP1B to MP3B]	100 lf	46.72 /lf	4,672
Feeder (EMT/CU) - 225A [4DP1C to MHP3C]	165 lf	49.70 /lf	8,200



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>26.27.05 Low-Voltage Distribution Feeders</b>			
Feeder (EMT/CU) - 225A [ATS-OS to EHP1A]	200 lf	49.70 /lf	9,940
Feeder (EMT/CU) - 225A [MSB to ATS-OS]	75 lf	49.70 /lf	3,727
Feeder (EMT/CU) - 400A [MSB to MHP1A]	50 lf	73.75 /lf	3,688
Feeder (EMT/CU) - 400A [EHP1C to EHP1A]	100 lf	73.75 /lf	7,375
Feeder (EMT/CU) - 400A [Generator to ATS-LR] (interior)	430 lf	73.75 /lf	31,713
Feeder (EMT/CU) - 400A [MSB to ATS-LR]	375 lf	78.46 /lf	29,422
Feeder (EMT/CU) - 400A [MHP-LR to ATS-LR]	10 lf	78.46 /lf	785
Feeder (EMT/CU) - 400A [ATS-LR to MHP-LR]	50 lf	73.75 /lf	3,688
Feeder (EMT/CU) - 600A [MSB to 4DP1B]	200 lf	108.91 /lf	21,782
Feeder (EMT/CU) - 600A [MSB to 2DP1A]	70 lf	108.91 /lf	7,624
Feeder (EMT/CU) - 800A [MSB to 2DP1C]	125 lf	138.78 /lf	17,348
Feeder (EMT/CU) - 800A [MSB to 4DP1C]	200 lf	138.78 /lf	27,757
Empty conduit (EMT) - 3/4" [utility meter to switchboard]	75 lf	6.28 /lf	471
Feeder (MC) - 125A [75kVA]	30 lf	12.82 /lf	385
Feeder (MC) - 225A [75kVA]	30 lf	35.43 /lf	1,063
Feeder (MC) - 400A [225kVA]	90 lf	59.32 /lf	5,339
Feeder (MC) - 800A [225kVA]	90 lf	111.65 /lf	10,048
M.I. Cable - 4-1/c #6 [ELP1B to ELP3B]	150 lf	36.15 /lf	5,422
M.I. Cable - 4-1/c #3 [EHP1A to EP3C]	165 lf	65.42 /lf	10,794
M.I. Cable - 4-1/c #3 [ELP1A to EDP]	125 lf	65.42 /lf	8,178
M.I. Cable - 4-1/c #3 [ELP1A to EP1C]	125 lf	65.42 /lf	8,178
M.I. Cable - 4-1/c #2 [EPL1A to ELP1B]	150 lf	72.60 /lf	10,890
M.I. Cable - 4-1/c #2 [ELP1A to ELP1D]	417 lf	77.24 /lf	32,208
Quick term kit - #6 4-1/c	2 ea	359.96 /ea	720
Quick term kit - #3 4-1/c	6 ea	710.21 /ea	4,261
Quick term kit - #2 4-1/c	4 ea	734.64 /ea	2,939
Brass plate (per hole)	12 ea	92.10 /ea	1,105
<b>Low-Voltage Distribution Feeders</b>	<b>136,600 sf</b>	<b>3.00 /sf</b>	<b>410,031</b>
<b>26.27.26 Wiring Devices</b>			
MC Cable (12/2) - 20A	11,370 lf	3.45 /lf	39,227
MC Cable (10/2) - 20A [homeruns - x372]	24,180 lf	4.36 /lf	105,516
EMT (12/2) - 20A	2,000 lf	6.70 /lf	13,404
PVC (10/2) - 20A	450 lf	6.68 /lf	3,007
Duplex receptacle - 20A - tamper resistant	497 ea	78.60 /ea	39,065
Duplex receptacle - 20A - switched with IO module	14 ea	67.78 /ea	949
Simplex receptacle - 20A [scoreboard control]	2 ea	70.18 /ea	140
Duplex receptacle - 20A - GFCI	187 ea	92.44 /ea	17,286
Duplex receptacle - 20A - GFCI - W.P.	29 ea	129.27 /ea	3,749



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>26.27.26 Wiring Devices</b>			
Duplex receptacle - 20A [kitchen equipment] - circuitry in Equipment Wiring]	33 ea	67.79 /ea	2,237
Duplex receptacle - 20A [A/V]	9 ea	67.79 /ea	610
Duplex receptacle - 20A [CR]	8 ea	67.80 /ea	542
Exterior pedestal receptacle, GFI type, Wayne Tyler, Inc. #CB-BOX	5 ea	1,292.26 /ea	6,461
Quadruplex receptacle - 20A	325 ea	93.78 /ea	30,479
Quadruplex receptacle - 20A - switched with IO module	18 ea	93.79 /ea	1,688
Duplex receptacle - 20A - USB	14 ea	99.44 /ea	1,392
Specialty receptacle - 20A - L5-20R	11 ea	101.01 /ea	1,111
Specialty receptacle - 20A - L14-20R	1 ea	104.81 /ea	105
Specialty receptacle - 30A - L5-30R	23 ea	111.69 /ea	2,569
Quadruplex receptacle - 20A - GFCI	5 ea	143.12 /ea	716
Hardwired A/C junction (MC) - 20A [A/V]	2 ea	318.93 /ea	638
Hardwired A/C junction (MC) - 20A [fume hoods]	4 ea	318.93 /ea	1,276
Power junction w/feed (MC) - 20A [water coolers/bottle fillers]	11 ea	221.21 /ea	2,433
Power junction w/feed (MC) - 20A	28 ea	221.21 /ea	6,194
Trash compactor feed & connection	2 ea	2,243.92 /ea	4,488
Overhead door power & connection	3 ea	1,223.50 /ea	3,671
Dock leveler feed & connection	1 ea	3,532.90 /ea	3,533
Emergency power offs (EPO)	10 ea	295.11 /ea	2,951
Wiremold receptacles - G4	110 ea	31.05 /ea	3,416
G4000 dual-channel wiremold - 24" spacing	220 lf	63.39 /lf	13,945
<b>Wiring Devices</b>	<b>136,600 sf</b>	<b>2.29 /sf</b>	<b>312,797</b>
<b>26.31.00 Provisions for Future Photovoltaic</b>			
Empty conduit - sch 40 PVC: 1 x 2" [future Canopy PV]	280 lf	26.88 /lf	7,526
Empty conduit - sch 40 PVC: 2 x 2" [future PV]	1,250 lf	35.04 /lf	43,800
Empty conduit - sch 40 PVC: 2 x 4" [future Canopy PV]	160 lf	45.14 /lf	7,222
<b>Provisions for Future Photovoltaic</b>	<b>136,600 sf</b>	<b>0.43 /sf</b>	<b>58,549</b>
<b>26.32.00 Packaged Generator Assemblies</b>			
Natural gas generator: 350kW / 437.5kVA	1 ea	133,322.25 /ea	133,322
Generator testing & start-up	1 ea	1,863.20 /ea	1,863
Generator annunciator panel	1 ea	1,447.40 /ea	1,447
Battery charger circuit (4#10 & 1#10G in 1"C)	140 lf	20.94 /lf	2,932
Jacket heater circuit	140 lf	34.49 /lf	4,828
Oil heater circuit	140 lf	53.66 /lf	7,512
Exterior W.P. sound attenuating enclosure (350kW)	1 ea	19,478.75 /ea	19,479
Remote status panel circuit	140 lf	9.64 /lf	1,349
Starting circuits - 2#14 MI cable	140 lf	12.76 /lf	1,787



## 90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>26.32.00 Packaged Generator Assemblies</b>			
Remote annunciator panel - 16#14 (EMT)	100 lf	15.81 /lf	1,581
Quick connect switch, ESL Storm Switch 3020	1 ea	3,668.10 /ea	3,668
<b>Packaged Generator Assemblies</b>	<b>136,600 sf</b>	<b>1.32 /sf</b>	<b>179,769</b>
<b>26.33.00 Battery Equipment</b>			
UPS: 480-208/120V, 24kW (static ts,manual by-pass, 8min batt.BU)	2 ea	30,061.40 /ea	60,123
<b>Battery Equipment</b>	<b>136,600 sf</b>	<b>0.44 /sf</b>	<b>60,123</b>
<b>26.36.00 Transfer Switches</b>			
ATS-OS: 225A, 277/480V, 4P, no iso by-pass - open transition	1 ea	6,752.90 /ea	6,753
ATS-LS: 150A, 277/480V, 4P, w/ iso by-pass - open transition	1 ea	11,058.30 /ea	11,058
ATS-LR: 400A, 277/480V, 4P, w/ iso by-pass - open transition	1 ea	19,961.43 /ea	19,961
<b>Transfer Switches</b>	<b>136,600 sf</b>	<b>0.28 /sf</b>	<b>37,773</b>
<b>26.40.00 Electrical &amp; Cathodic Protection</b>			
Lightning prevention system subcontractor	1 ls	30,000.00 /ls	30,000
<b>Electrical &amp; Cathodic Protection</b>	<b>136,600 sf</b>	<b>0.22 /sf</b>	<b>30,000</b>
<b>26.50.00 Lighting</b>			
LK24: 2'x2' lay-in fixture [O]	24 ea	198.57 /ea	4,766
SPFL: LED flood light [C]	20 ea	682.90 /ea	13,658
SPNF: LED flood light, narrow [C]	20 ea	682.90 /ea	13,658
LR2 (emerg): 2' linear 2" aperature recessed luminaire [O]	183 ea	300.48 /ea	54,987
LR2: 2' linear 2" aperature recessed luminaire [O]	912 ea	300.48 /ea	274,033
G4: 4' linear rugged low profile 360 deg adjustable flood luminaire [O]	80 ea	2,155.93 /ea	172,474
LS4: 4' utility fixtre with frosted acrylic diffuser [O]	20 ea	246.16 /ea	4,923
LS4 (emerg): 4' utility fixture with frosted acrylic diffuser [O]	14 ea	246.16 /ea	3,446
LS8: 8' utility fixtre with frosted acrylic diffuser [O]	11 ea	411.94 /ea	4,531
LS4A (emerg): 4' utility fixtre with frosted acrylic diffuser [O]	12 ea	494.94 /ea	5,939
LS4A: 4' utility fixture with frosted acrylic diffuser [O]	12 ea	494.94 /ea	5,939
LP8 (emerg): Axis 8' LED fixture [O]	9 ea	1,027.94 /ea	9,251
LS8 (emerg): 8' utility fixture with frosted acrylic diffuser [O]	10 ea	411.94 /ea	4,119
JB: utility fixture with frosted tempered glass globe & guard [O]	4 ea	245.95 /ea	984
PC3: 6" down light fixture with dead-front gasketed trim [O]	1 ea	298.16 /ea	298
LRW (emerg): 6" aperature LED linear recessed fixture / qty. of 18 [C]	114 lf	146.99 /lf	16,757
PC1: 4" down light fixture, 0-10V dimming capable [O]	24 ea	298.16 /ea	7,156
RC1: 6" down light fixture [O]	45 ea	271.54 /ea	12,219
RC1 (emerg): 6" down light fixture [O]	18 ea	271.54 /ea	4,888
LS2 (emerg): 2' utility fixture [O]	2 ea	177.98 /ea	356
LSV4: 4' linear utility fixture with prismatic polcarbonate lens [C]	4 ea	675.93 /ea	2,704



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>26.50.00 Lighting</b>			
RC2: 4" down light fixture, 0-10V dimming [O]	8 ea	230.56 /ea	1,844
LR4: 4' linear 2" aperature recessed luminaire with frosted lens [O]	1 ea	410.45 /ea	410
LUL: LED tape light with AL channel [C]	1,840 lf	88.49 /lf	162,829
LC3: linear cove Xeleum lighting / qty. of 96 [O]	1,925 lf	121.99 /lf	234,826
LWW: LED tape light with AL channel [C]	1,408 lf	88.49 /lf	124,599
RSH: 6" down light fixture with dead-front gasketed trim [O]	1 ea	306.54 /ea	307
LC2: linear cove fixture with frosted diffuser / qty. of 10 [O]	76 lf	148.23 /lf	11,265
PC2: 6" down light fixture with dead-front gasketed trim [O]	28 ea	298.16 /ea	8,348
LCL: LED tape light with AL channel [C]	3,051 lf	88.49 /lf	269,994
LSL: LED strip mounted on edge of stage / qty. of 1	59 lf	305.95 /lf	18,051
Exit sign, ceiling mounted, double sided [O]	34 ea	196.16 /ea	6,669
Exit sign, ceiling mounted, single sided [O]	16 ea	183.16 /ea	2,931
Exit sign, wall mounted	18 ea	313.16 /ea	5,637
Exit sign, ceiling mounted, single sided - handicap [O]	2 ea	433.16 /ea	866
LRC (emerg): 6" aperature LED linear recessed fixture / qty. of 46 [C]	596 lf	161.70 /lf	96,373
MC Cable (12/2) - 20A (concealed branch)	12,068 lf	3.67 /lf	44,291
MC Cable (10/2) - 20A (concealed homeruns)	2,400 lf	4.64 /lf	11,142
EMT (12/2) - 20A (exposed branch)	4,023 lf	7.13 /lf	28,679
EMT (10/2) - 20A (exposed homeruns)	500 lf	8.58 /lf	4,290
<b>Lighting</b>	<b>136,600 sf</b>	<b>12.08 /sf</b>	<b>1,650,438</b>
<b>26.56.00 Exterior Lighting</b>			
SL4: LED egress / perimeter lighting fixture - custom color/finish [O]	40 ea	565.36 /ea	22,614
SL5: exterior ampitheater RGB projector, DMX capable, IP65 rated [O]	8 ea	3,626.85 /ea	29,015
SLS: LED recessed step light, 0-10V dimming capable [C]	7 ea	732.90 /ea	5,130
SL1: LED pole mounted luminaires mounted on a 20' pole [O]	35 ea	2,891.40 /ea	101,199
SL2A: exterior post top fixture with 15' round tapered alum pole [O]	13 ea	5,492.50 /ea	71,403
SL3: exterior bollard 43.3 cast illuminum [O]	9 ea	1,929.78 /ea	17,368
SL10: LED mini in-ground flood fixture capable of 0-10V dimming [O]	12 ea	978.60 /ea	11,743
MC Cable (12/2) - 20A	1,200 lf	3.67 /lf	4,404
EMT (12/2) - 20A	1,400 lf	7.13 /lf	9,981
1" PVC - 30A (3#8 & #10G)	6,900 lf	10.95 /lf	75,528
1" GRC - 90 Deg Sweep	114 ea	174.22 /ea	19,861
<b>Exterior Lighting</b>	<b>136,600 sf</b>	<b>2.70 /sf</b>	<b>368,247</b>
<b>27.00.01 Data/Voice/Audio-Video Communications</b>			
Tel/data J-hook system (plenum)	136,600 sf	0.19 /sf	25,681
Cable tray - 18"W (IDF/MDF only)	200 lf	75.55 /lf	15,109
Empty conduit (PVC) - 1"	250 lf	8.07 /lf	2,016
Empty conduit (EMT) - 2"	650 lf	11.19 /lf	7,271



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>27.00.01 Data/Voice/Audio-Video Communications</b>			
Empty conduit (PVC) - 2"	700 lf	6.03 /lf	4,223
Empty conduit (sch 40 PVC) (4) 4"C (CATV, Telephone, Fiber, Spare)	220 lf	32.32 /lf	7,110
Three (3) 1.25" inner ducts for fiber	220 lf	15.50 /lf	3,411
Communications utility pole conduit riser (GRC - 4"C)	4 ea	2,343.84 /ea	9,375
Copper ground bar w/isolators - 2"x1/4"	4 ea	280.03 /ea	1,120
Conduit sleeve w/ fireproofing - 4"	20 ea	201.11 /ea	4,022
Data outlet - (1) CAT-6A cable	20 ea	264.84 /ea	5,297
Data outlet - (1) CAT-6A cable [audio-visual]	12 ea	264.84 /ea	3,178
Data outlet - (2) CAT-6A cables	131 ea	466.16 /ea	61,067
Tel/data outlet - (3) CAT-6A cables	91 ea	652.82 /ea	59,407
Floor box tel/data outlet - (3) CAT-6A cables	2 ea	652.83 /ea	1,306
Voice outlet - (1) CAT-6A cable (WAP's by Owner)	79 ea	263.70 /ea	20,832
Wireless access point - (1) CAT-6A cable (WAP's by Owner)	138 ea	263.70 /ea	36,390
TVE - Video outlet	56 ea	838.75 /ea	46,970
TVC - Video outlet	2 ea	838.77 /ea	1,678
Double gang junction box with (4) 1" C	54 ea	482.68 /ea	26,065
FO - 12 strand SM	1,750 lf	5.27 /lf	9,225
FO - 12 strand MM	1,500 lf	7.10 /lf	10,642
4-Post Full Height Rack	10 ea	1,170.17 /ea	11,702
Vertical cable wire manager	20 ea	314.09 /ea	6,282
Horizontal cable wire manager	10 ea	80.25 /ea	803
Copper patch panel - 96 port	15 ea	1,244.28 /ea	18,664
Fiber optic patch panel - 24 port	6 ea	570.06 /ea	3,420
Fiber enclosure (rack mtd.)	6 ea	485.85 /ea	2,915
Network switch - 24 port	2 ea	5,390.24 /ea	10,780
Telecom manhole & cover - 4'x6'x7'	1 ea	3,920.36 /ea	3,920
<b>Data/Voice/Audio-Video Communications</b>	<b>136,600 sf</b>	<b>3.07 /sf</b>	<b>419,882</b>
<b>27.40.00 Audio-Video Communications</b>			
S1: wall mounted loudspeaker - 1 gang metal box w/ cover	2 ea	228.33 /ea	457
S2: ceiling loud speaker - custom backbox	6 ea	308.23 /ea	1,849
S3: ceiling loud speaker - 4" SQ metal box w/ cover	16 ea	179.94 /ea	2,879
S4: ceiling loud speaker - 4" SQ metal box w/ cover	2 ea	251.94 /ea	504
S5: ceiling loud speaker - 4" SQ metal box w/ cover (New)	2 ea	245.27 /ea	491
D1: display back box, Chief PAC-526	3 ea	371.35 /ea	1,114
F1: floor box, FSR FL-500P-6 floor box w/ finished cover	1 ea	469.58 /ea	470
V1: wall mounted video projector - 1 gang metal box w/ cover	1 ea	179.47 /ea	179
R1: receptacle panel - 2 gang metal box w/ cover	3 ea	242.43 /ea	727
R2: receptacle panel - 12"x12"x4" NEMA-1 enclosure w/ oversized flush	2 ea	242.43 /ea	485



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>27.40.00 Audio-Video Communications</b>			
R3: receptacle panel - 3 gang metal box w/ cover	4 ea	311.69 /ea	1,247
R5: receptacle panel - 3 gang metal box w/ cover	1 ea	242.43 /ea	242
R6: receptacle panel - 12"x12"x4" NEMA-1 enclosure w/ oversized flush	2 ea	405.94 /ea	812
BP: wall mounted button panel - 1 gang metal box w/ cover	3 ea	221.77 /ea	665
J1: junction box - type 1 - 12"x12"x4" NEMA-1 enclosure w/ oversized flush	2 ea	723.57 /ea	1,447
J2: junction box - type 2 - 18"x18"x4" NEMA-1 enclosure w/ oversized flush	1 ea	844.78 /ea	845
J3: junction box - type 3 - same as Type 2	3 ea	844.78 /ea	2,534
A1: Wall mounted antenna - 1 gang deep metal box w/ cover	2 ea	159.74 /ea	319
A2: Wall mounted antenna - 1 gang deep metal box w/ cover	1 ea	159.74 /ea	160
A3: Ceiling mounted antenna - 4" SQ metal box w/ cover	2 ea	138.32 /ea	277
A4: Ceiling mounted antenna - 4" SQ metal box w/ cover	1 ea	138.31 /ea	138
PS: Production communication speaker station - 4 gang deep metal box w/ cov	5 ea	385.28 /ea	1,926
PC: Production communication - 1 gang deep metal box w/ cover	1 ea	134.38 /ea	134
T1: Wall mounted touch panel - 3 gang metal box w/ cover	2 ea	249.04 /ea	498
VC: Wall mounted audio volume control - 1 gang deep metal box	2 ea	134.39 /ea	269
MC: Motor controller - 4" SQ metal box w/ cover	3 ea	86.46 /ea	259
C1: Wall mounted camera - 2 gang deep metal box w/ cover	1 ea	193.57 /ea	194
A/V Equipment Rack	2 ea	1,001.85 /ea	2,004
M1: Ceiling mounted microphone - 1 gang deep metal box w/ cover	1 ea	134.38 /ea	134
<b>Audio-Video Communications</b>	<b>136,600 sf</b>	<b>0.17 /sf</b>	<b>23,260</b>
<b>27.50.00 Distributed Communications &amp; Monitoring Systems</b>			
Intercom sub-stations	6 ea	1,009.28 /ea	6,056
Intercom master-stations	5 ea	3,327.13 /ea	16,636
<b>Distributed Communications &amp; Monitoring Systems</b>	<b>136,600 sf</b>	<b>0.17 /sf</b>	<b>22,691</b>
<b>27.51.19 Ceiling Speaker System</b>			
Speaker - ceiling mouted	269 ea	405.93 /ea	109,194
Speaker - wall mounted	32 ea	611.85 /ea	19,579
Volume control	24 ea	177.96 /ea	4,271
Power supply (80) units - speakers 24V DC	4 ea	2,661.71 /ea	10,647
PA console	1 ea	14,251.90 /ea	14,252
PA equipment power connection - 120V	1 ea	256.53 /ea	257
AM/FM/CD/DVD tuner	1 ea	694.40 /ea	694
Speaker system testing	1 ea	1,986.71 /ea	1,987



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Ceiling Speaker System</b>	<b>136,600 sf</b>	<b>1.18 /sf</b>	<b>160,880</b>
<b>27.51.29 Emergency Communications Systems</b>			
Two way communication call box (recessed)	20 ea	799.75 /ea	15,995
Power supply w/battery back up	1 ea	1,714.28 /ea	1,714
Two way communication base station (28 zone)	1 ea	5,980.66 /ea	5,981
Power junction w/feed (EMT) - 20A	1 ea	337.91 /ea	338
Tel/data outlet - (1) CAT-6A cable	20 ea	264.84 /ea	5,297
Tel/data outlet - (2) CAT-6A cables	1 ea	466.16 /ea	466
Empty conduit (EMT) - 3/4"	2,000 lf	5.11 /lf	10,218
System testing	1 ea	1,016.70 /ea	1,017
<b>Emergency Communications Systems</b>	<b>136,600 sf</b>	<b>0.30 /sf</b>	<b>41,026</b>
<b>27.53.00 Clock System</b>			
Clock, wall mounted - 12" round	126 ea	283.06 /ea	35,665
Master clock w/ roof mounted antenna	1 ea	3,778.57 /ea	3,779
Wireless clock repeater	1 ea	647.06 /ea	647
Wireless clock transceiver	1 ea	647.06 /ea	647
Program unit	1 ea	991.96 /ea	992
Speaker baffle, clock back box	74 ea	202.78 /ea	15,006
Wire guard	20 ea	57.70 /ea	1,154
Clock wiring (EMT)	700 lf	7.03 /lf	4,923
Clock wiring (RS-485 plenum)	500 lf	3.08 /lf	1,540
System testing	1 ls	33.83 /ls	34
<b>Clock System</b>	<b>136,600 sf</b>	<b>0.47 /sf</b>	<b>64,387</b>
<b>28.10.00 Electronic Access Control &amp; Intrusion Detection</b>			
Card readers	22 ea	1,163.83 /ea	25,604
Card readers - W.P.	3 ea	1,967.78 /ea	5,903
Electro-magnetic lock	6 ea	657.91 /ea	3,947
Request to exit motion sensor	26 ea	322.33 /ea	8,380
Electric strike	40 ea	400.49 /ea	16,020
Thermal disconnecting means	20 ea	427.58 /ea	8,552
24V power supply	20 ea	295.11 /ea	5,902
Junction box - 6"x6"x4"	20 ea	130.61 /ea	2,612
Power transfer hinge	20 ea	377.68 /ea	7,554
Intrusion digital keypads	4 ea	984.97 /ea	3,940
Dual tech motion detectors	77 ea	595.80 /ea	45,876
Door contacts	63 ea	465.74 /ea	29,342
Access control panel	1 ea	8,222.56 /ea	8,223
Tie in to lighting control system	1 ea	402.23 /ea	402





90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>28.10.00 Electronic Access Control &amp; Intrusion Detection</b>			
Security wiring - cable	7,500 lf	3.80 /lf	28,527
Security wiring (EMT)	2,250 lf	8.53 /lf	19,181
Power junctions - 120V/20A	2 ea	193.20 /ea	386
Connect to CCTV system	1 ea	665.43 /ea	665
Proximity cards	250 ea	2.35 /ea	588
Software / licenses, programming, testing, startup (manufacturer)	1 ea	13,308.52 /ea	13,309
<b>Electronic Access Control &amp; Intrusion Detection</b>	<b>136,600 sf</b>	<b>1.72 /sf</b>	<b>234,913</b>
<b>28.20.00 Video Surveillance</b>			
CCTV color monitors	2 ea	815.52 /ea	1,631
360-degree multi-sensor interior cameras	28 ea	1,659.85 /ea	46,476
Dome I.P. camera - exterior	19 ea	1,996.28 /ea	37,929
Dome I.P. camera - interior - fixed	27 ea	1,471.85 /ea	39,740
360-degree multi-sensor exterior cameras mounted on poles	3 ea	4,509.56 /ea	13,529
Camera monitoring station	1 ea	1,330.85 /ea	1,331
Video recorders	2 ea	3,131.71 /ea	6,263
Video switchers	2 ea	1,627.71 /ea	3,255
Camera wiring (EMT)	2,500 lf	8.76 /lf	21,899
Camera wiring (PVC)	600 lf	13.34 /lf	8,003
Camera wiring - cable	7,400 lf	4.04 /lf	29,885
Power junction - 120V/20A	2 ea	193.20 /ea	386
Software / licenses, programming, testing, startup (manufacturer)	1 ea	13,308.52 /ea	13,309
<b>Video Surveillance</b>	<b>136,600 sf</b>	<b>1.64 /sf</b>	<b>223,638</b>
<b>28.46.00 Temporary Fire Alarm</b>			
<i>Temporary fire alarm heat detection coverage / stairwell pull stations / temp notification - N/A</i>	-	/-	
Fire alarm impairment plan (NFPA-101)	1 ls	10,000.00 /ls	10,000
<b>Temporary Fire Alarm</b>	<b>136,600 sf</b>	<b>0.07 /sf</b>	<b>10,000</b>
<b>28.46.20 Fire Detection and Alarm</b>			
Elevator fire alarm interfacing	1 ls	5,000.00 /ls	5,000
Manual pull stations	25 ea	202.12 /ea	5,053
Smoke detectors	82 ea	220.39 /ea	18,072
Smoke detector w/ elevator recall	3 ea	373.26 /ea	1,120
Smoke detectors (for Atrium)	89 ea	220.39 /ea	19,615
Smoke detectors w/ elevator recall (for Atrium)	3 ea	373.25 /ea	1,120
Carbon monoxide detector (w/ monitor module)	5 ea	367.16 /ea	1,836
Beam detector (receiver & transmitter)	5 ea	416.88 /ea	2,084
Duct smoke detector (furnish & wire)	40 ea	838.91 /ea	33,556



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>28.46.20 Fire Detection and Alarm</b>			
Remote test switch w/ indicating light	40 ea	194.88 /ea	7,795
Control modules	20 ea	265.75 /ea	5,315
Addressable monitor modules	30 ea	160.83 /ea	4,825
Tamper switch connection (via monitor module)	8 ea	560.06 /ea	4,480
Flow switch connection (via monitor module)	8 ea	403.67 /ea	3,229
Door hold device (magnetic)	5 ea	388.88 /ea	1,944
Wire motorized dampers (120V)	14 ea	407.48 /ea	5,705
Wire combination fire/smoke damper (120V & SLC)	20 ea	608.50 /ea	12,170
Strobe only	48 ea	175.36 /ea	8,417
Speaker/strobes	150 ea	246.56 /ea	36,983
Speaker/strobe - W.P.	1 ea	309.72 /ea	310
Horn/visual - wall mounted	52 ea	222.79 /ea	11,585
Exterior beacons (weatherproof)	4 ea	388.83 /ea	1,555
Fire alarm transponder panels	6 ea	928.51 /ea	5,571
Fire alarm annunciators w/ microphones	3 ea	2,107.39 /ea	6,322
FACP w/ 60-minute battery backup (Notifier NFS640)	1 ea	6,999.66 /ea	7,000
Masterbox (local energy)	1 ea	4,212.70 /ea	4,213
Key (Knox) box	2 ea	806.43 /ea	1,613
Smoke control panel	1 ea	19,502.56 /ea	19,503
Generator monitoring control panel	1 ea	571.80 /ea	572
Fire pump/jockey pump connection	1 ea	402.23 /ea	402
Fire alarm graphic maps	3 ea	1,454.56 /ea	4,364
Fire alarm comissioning	1 ea	6,158.00 /ea	6,158
Fire alarm testing (manufacturer)	6 ea	1,338.28 /ea	8,030
Fire alarm system programming	397 ea	20.79 /ea	8,254
FPLP cable (red) - #14-4/c	11,475 lf	2.23 /lf	25,589
FPLP cable (red) - #16-2/c	12,330 lf	1.83 /lf	22,564
EMT (red) - 3/4"C w/ #16-2/c (exposed)	2,500 lf	7.19 /lf	17,981
EMT (red) - 3/4"C w/ #14-4/c (exposed)	1,200 lf	7.95 /lf	9,535
Circuit integrity cabling (CIC)	1,500 lf	18.31 /lf	27,465
Ductbank w/ IMSA cable - 2" PVC	320 lf	16.30 /lf	5,217
<b>Fire Detection and Alarm</b>	<b>136,600 sf</b>	<b>2.72 /sf</b>	<b>372,120</b>
<b>28.46.24 Distributed Antenna System (DAS)</b>			
BDA system - parts & smarts (dual-frequency)	136,600 sf	0.47 /sf	64,202
BDA system - installation & minor material (dual-frequency)	136,600 sf	0.19 /sf	25,681
Directional couplers	20 ea	1,150.35 /ea	23,007
In-Line connectors	20 ea	249.01 /ea	4,980
Lightning protection units	5 ea	1,995.53 /ea	9,978



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Distributed Antenna System (DAS)</b>	<b>136,600 sf</b>	<b>0.94 /sf</b>	<b>127,848</b>
<b>26-01 ELECTRICAL (TS)</b>	<b>136,600 sf</b>	<b>46.06 /sf</b>	<b>6,291,566</b>
<b>31-23 SITEWORK</b>			
<b>02.41.13 Demolition - Site</b>			
Demo hydrants	BP#1	/BP#1	
Demo bituminous concrete paving	BP#1	/BP#1	
Demo bituminous walk	BP#1	/BP#1	
Demo Temporary Bituminous Parking & Access Pavement	BP#1	/BP#1	
Demo concrete sidewalks/pads/ramps	BP#1	/BP#1	
Demo curbing	BP#1	/BP#1	
Cut & cap site utilities - water	BP#1	/BP#1	
Cut & cap site utilities - sewer	BP#1	/BP#1	
Demo utility piping - water	BP#1	/BP#1	
Demo utility piping - sewer	BP#1	/BP#1	
Demo utility piping - electrical	BP#1	/BP#1	
Demo utility piping - drain	BP#1	/BP#1	
Demo utility piping - gas	BP#1	/BP#1	
Demo drain structures	BP#1	/BP#1	
Demo grease trap	BP#1	/BP#1	
Demo fencing/guardrail	BP#1	/BP#1	
Misc. site demolition	BP#1	/BP#1	
Demo utility poles	BP#1	/BP#1	
<b>Demolition - Site</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>31.00.05 General Requirements</b>			
Mobilizations	BP#1	/BP#1	
Survey/layout	BP#1	/BP#1	
Preconstruction survey and vibration monitoring & compliance	BP#1	/BP#1	
Street plates for protection	BP#1	/BP#1	
Police details	BP#1	/BP#1	
Precast Concrete Jersey Barriers for Temp. Parking Lot	BP#1	/BP#1	
Temporary site signage	BP#1	/BP#1	
As-built plan preparation	BP#1	/BP#1	
Localized dewatering	BP#1	/BP#1	
<b>General Requirements</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>31.10.00 Site Clearing</b>			
Clear & grub, vegetation removal	BP#1	/BP#1	
Strip & stockpile topsoil/loam	BP#1	/BP#1	
<b>Site Clearing</b>	<b>136,600 sf</b>	<b>/sf</b>	



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>31.22.00 Grading</b>			
Rough grading	BP#1	/BP#1	
Fine grading - building SOG	BP#1	/BP#1	
Fine grading - paving	BP#1	/BP#1	
Fine grading - conc walks & site pads	BP#1	/BP#1	
Fine grading - bituminous walks	BP#1	/BP#1	
<b>Grading</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>31.23.00 Excavation &amp; Fill - Overall Site</b>			
Cut to subgrade @ site	BP#1	/BP#1	
Fill to subgrade from cut @ site	BP#1	/BP#1	
Grind foundations for fill - In Demolition	-	/-	
Fill to subgrade @ site - import	BP#1	/BP#1	
Site cuts to stockpile for temporary parking & access layout	BP#1	/BP#1	
Site surcharge	BP#1	/BP#1	
Site cuts to site fills	BP#1	/BP#1	
Excavation @ foundations	BP#1	/BP#1	
Fill to subgrade @ building footprint - import (structural fill)	BP#1	/BP#1	
Contaminated soil removal - unlined landfill	BP#1	/BP#1	
Crushed stone base beneath S.O.G	BP#1	/BP#1	
Crushed stone base beneath column & wall footings	BP#1	/BP#1	
<b>Excavation &amp; Fill - Overall Site</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>31.23.01 Excavation &amp; Fill - Foundations</b>			
Excavate for elevator pits	BP#1	/BP#1	
Fine grade under building	BP#1	/BP#1	
<b>Excavation &amp; Fill - Foundations</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>31.23.02 Excavation &amp; Fill - Utilities</b>			
Excavate/backfill utilities under SOG by machine	BP#1	/BP#1	
<b>Excavation &amp; Fill - Utilities</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>31.23.16 Rock Removal</b>			
Rock removal - NIC	-	/-	
<b>Rock Removal</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>31.23.19 Dewatering</b>			
Dewatering	BP#1	/BP#1	
Construct Phase 2 Temp. Sediment Basins	BP#1	/BP#1	
Additional dewatering	BP#1	/BP#1	



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Dewatering</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>31.25.00 Erosion &amp; Sedimentation Control</b>			
SWPPP (Prep of SWPPP by civil engineer)	BP#1	/BP#1	
12" diameter Straw Wattles	BP#1	/BP#1	
Silt sacks at catch basin	BP#1	/BP#1	
Construction entrance	BP#1	/BP#1	
Street sweeping	BP#1	/BP#1	
Inspect / repair silt barrier weekly	BP#1	/BP#1	
Remove erosion control measure at project completion	BP#1	/BP#1	
<b>Erosion &amp; Sedimentation Control</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>31.62.00 Ground Improvement</b>			
Site surcharge/rigid inclusion	BP#1	/BP#1	
Rammed aggregate piers	BP#1	/BP#1	
Rigid inclusions Gym and Auditorium	BP#1	/BP#1	
<b>Ground Improvement</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>32.11.00 Base Courses</b>			
Gravel base course @ asphalt pavements	BP#1	/BP#1	
Gravel base course @ Raised Stamped asphalt pavement at Flagg Drive	BP#1	/BP#1	
Processed Aggregate base course - bituminous walks	BP#1	/BP#1	
1 1/2" crushed stone base course - concrete walks & site pads	BP#1	/BP#1	
Gravel base course - misc site amenities- (i.e.- curbing, swales,etc.)	BP#1	/BP#1	
<b>Base Courses</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>32.12.00 Flexible Paving</b>			
Asphalt paving - (Parking Lots & Site Drives)	BP#1	/BP#1	
Asphalt paving - Temp. Parking Layout	BP#1	/BP#1	
Temporary roads and maintenance required during construction	BP#1	/BP#1	
Asphalt paving - top course @ temporary to permanent	BP#1	/BP#1	
<b>Flexible Paving</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>32.13.00 Rigid Paving</b>			
Stamped pavement at Flagg Drive	BP#1	/BP#1	
<b>Rigid Paving</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>32.16.13 Curbs &amp; Gutters</b>			
Precast concrete curbs	BP#1	/BP#1	
Vertical granite curbs	BP#1	/BP#1	



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>32.16.13 Curbs &amp; Gutters</b>			
Handicapped ramps at curbing	BP#1	/BP#1	
Detectable Warning Plates at Handicapped Ramps	BP#1	/BP#1	
<b>Curbs &amp; Gutters</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>32.16.23 Sidewalks</b>			
Bituminous sidewalks	BP#1	/BP#1	
<b>Sidewalks</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>32.17.00 Paving Specialties</b>			
Speed bumps - bituminous	BP#1	/BP#1	
Pavement markings	BP#1	/BP#1	
Parking signage	BP#1	/BP#1	
<b>Paving Specialties</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>33.10.00 Water Utilities</b>			
Fire hydrants	BP#1	/BP#1	
Fire hydrant - relocate existing	BP#1	/BP#1	
Gate valves, tees, bends, thrust blocks, restraints	BP#1	/BP#1	
Water distribution connections to existing	BP#1	/BP#1	
Water line - domestic	BP#1	/BP#1	
Water line - hydrant & fire services	BP#1	/BP#1	
Pressure test & chlorinate	BP#1	/BP#1	
<b>Water Utilities</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>33.30.00 Sanitary Sewerage Utilities</b>			
Sanitary sewer piping	BP#1	/BP#1	
Sanitary sewer manholes	BP#1	/BP#1	
Connect to existing structures	BP#1	/BP#1	
Utility and sewer tie-in at trailer	BP#1	/BP#1	
Sanitary sewer testing - piping	BP#1	/BP#1	
Video inspect incoming sewer, etc.	BP#1	/BP#1	
Sanitary sewer testing - structures	BP#1	/BP#1	
<b>Sanitary Sewerage Utilities</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>33.36.00 Utility Septic Tanks</b>			
Grease interceptor - In Plumbing	-	/-	
Acid Neutralization - In Plumbing	-	/-	
<b>Utility Septic Tanks</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>33.40.00 Storm Drainage Utilities</b>			



90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>33.40.00 Storm Drainage Utilities</b>			
Catch basins	BP#1	/BP#1	
Granite Curb Inlets	BP#1	/BP#1	
Storm drainage manholes	BP#1	/BP#1	
Outlet control structures	BP#1	/BP#1	
Storm headwalls	BP#1	/BP#1	
Stormceptors	BP#1	/BP#1	
Storm drainage piping	BP#1	/BP#1	
Rip Rap Splash Pads	BP#1	/BP#1	
Weir Overflows	BP#1	/BP#1	
Check dams	BP#1	/BP#1	
<b>Storm Drainage Utilities</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>33.46.00 Subdrainage</b>			
Foundation drainage piping	BP#1	/BP#1	
<b>Subdrainage</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>33.47.00 Infiltration Systems</b>			
Infiltration system	BP#1	/BP#1	
<b>Infiltration Systems</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>33.50.00 Fuel Distribution Utilities</b>			
Excavation / backfill for gas line	BP#1	/BP#1	
<b>Fuel Distribution Utilities</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>33.70.00 Electrical Utilities</b>			
Excavation/backfill for Emergency Generator ductbank	BP#1	/BP#1	
Excavation/backfill for Primary Electric ductbank	BP#1	/BP#1	
Excavation/backfill for Fire Alarm ductbank	BP#1	/BP#1	
Excavation/backfill for Telcom ductbank	BP#1	/BP#1	
Excavation/backfill for U.G. ductbank	BP#1	/BP#1	
Excavation/backfill for 2"C Power Data ductbank (Amphitheather)	BP#1	/BP#1	
Excavation/backfill for 2"C to IDF ductbank	BP#1	/BP#1	
Concrete and rebar for electrical/telcom ductbanks	BP#1	/BP#1	
Excavation/backfill for site lighting	BP#1	/BP#1	
Emergency Call Box base	BP#1	/BP#1	
EV Parking Station bases	BP#1	/BP#1	
Light pole bases	BP#1	/BP#1	
6" Concrete Filled Steel Pipe Bollards at Generator & Transformer Pads	BP#1	/BP#1	
<b>Electrical Utilities</b>	<b>136,600 sf</b>	<b>/sf</b>	



### 90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>31-23 SITEWORK</b>	<b>136,600 sf</b>	<b>/sf</b>	
<b>32-10 LANDSCAPING &amp; SITE IMPROVEMENTS</b>			
<b>12.93.00 Site Furnishings</b>			
Wood benches	20 lf	750.00 /lf	15,000
Bicycle Racks	20 ea	785.00 /ea	15,700
Basketball Poles & Hoops	2 ea	8,000.00 /ea	16,000
Miscellaneous site furnishings - Allowance	1 ls	30,000.00 /ls	30,000
<b>Site Furnishings</b>	<b>136,600 sf</b>	<b>0.56 /sf</b>	<b>76,700</b>
<b>32.01.90 Plant Maintenance</b>			
Landscaping maintenance	1 yr	8,000.00 /yr	8,000
<b>Plant Maintenance</b>	<b>136,600 sf</b>	<b>0.06 /sf</b>	<b>8,000</b>
<b>32.14.00 Unit Paving</b>			
Pavers - plaza paving	260 sf	25.00 /sf	6,500
Stone Dust at Raised Planter	32 sf	20.00 /sf	640
<b>Unit Paving</b>	<b>136,600 sf</b>	<b>0.05 /sf</b>	<b>7,140</b>
<b>32.18.00 Athletic &amp; Recreational Surfacing</b>			
Basketball Court Pavement- (3 1/2" Total Paving w/ Gravel Base) - BP#1	sf	/sf	
Basketball Court Pavement Markings	1 ls	2,000.00 /ls	2,000
<b>Athletic &amp; Recreational Surfacing</b>	<b>136,790 sf</b>	<b>0.02 /sf</b>	<b>2,000</b>
<b>32.31.50 Walk / Road / Parking Appurtenances</b>			
Flag pole	1 ea	9,000.00 /ea	9,000
Bollards - 6" steel w/concrete - BP#1	BP#1	/BP#1	
Bollards - 6" steel w/concrete - BP#1	ea	/ea	
Bollards - architectural - VM-C01	0 ea	/ea	
<b>Walk / Road / Parking Appurtenances</b>	<b>136,600 sf</b>	<b>0.07 /sf</b>	<b>9,000</b>
<b>32.32.00 Retaining Walls</b>			
Segmental retaining wall	2,600 sf	50.00 /sf	130,000
Additional segmental retaining wall per PR #12	220 sf	50.00 /sf	11,000
<b>Retaining Walls</b>	<b>136,600 sf</b>	<b>1.03 /sf</b>	<b>141,000</b>
<b>32.80.00 Irrigation</b>			
Irrigation system @ south sports field - by others	-	/-	
Irrigation @ ampitheater - Allowance	23,435 sf	2.00 /sf	46,870
Irrigation system @ north sports field - Allowance	81,000 sf	2.00 /sf	162,000





90% CD Estimate

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>Irrigation</b>	<b>136,600 sf</b>	<b>1.53 /sf</b>	<b>208,870</b>
<b>32.91.00 Planting Preparation</b>			
Mulch at trees and planting beds (3")	240 cy	105.00 /cy	25,200
Import loam & spread (6") at Lawns, Athletic Fields & Native Meadows	5,594 cy	40.00 /cy	223,760
Ammend & spread (6") at Lawns, Athletic Fields & Native Meadows	6,030 cy	12.00 /cy	72,360
Import loam & spread (6") at Detention Basins	802 cy	40.00 /cy	32,080
Import loam & spread (12") at Plant Beds	375 cy	40.00 /cy	15,000
Landscape Metal Edging at Building Mow Strip	2,330 lf	15.00 /lf	34,950
Building Mowing Strip- (Peastone)	100 tn	50.00 /tn	5,000
Import loam & spread (6") at Sodded Amphitheater Lawns	691 cy	40.00 /cy	27,640
<b>Planting Preparation</b>	<b>136,600 sf</b>	<b>3.19 /sf</b>	<b>435,990</b>
<b>32.92.00 Turf &amp; Grasses</b>			
Fine grade & hydroseed lawn areas	119,420 sf	0.30 /sf	35,826
Fine grade & seed (Native Wildflower Meadow)	104,005 sf	0.25 /sf	26,001
Fine grade & seed (Detention Basin Mix- Hydroseed)	33,330 sf	0.25 /sf	8,333
Fine grade & seed (Natural Turf Fields)	259,269 sf	0.25 /sf	64,817
Sod (Amphitheater Lawns)	28,719 sf	1.50 /sf	43,079
Watering for sod areas	1 ls	7,500.00 /ls	7,500
Sod (100'x170')	17,000 sf	1.50 /sf	25,500
Sod northeast - phase 3 play area	5,000 sf	1.50 /sf	7,500
Watering for sod areas	1 ls	7,500.00 /ls	7,500
<b>Turf &amp; Grasses</b>	<b>136,600 sf</b>	<b>1.66 /sf</b>	<b>226,056</b>
<b>32.93.00 Plants</b>			
Trees	118 ea	750.00 /ea	88,500
Shrubs (478 Total)	7,736 sf	8.50 /sf	65,756
Groundcover/perennials	1,966 ea	20.00 /ea	39,320
Planter Beds	7,786 sf	10.00 /sf	77,860
Rain garden	8,275 sf	10.00 /sf	82,750
<b>Plants</b>	<b>136,600 sf</b>	<b>2.59 /sf</b>	<b>354,186</b>
<b>32-10 LANDSCAPING &amp; SITE IMPROVEMENTS</b>	<b>136,600 sf</b>	<b>10.75 /sf</b>	<b>1,468,942</b>
<b>32-31 FENCING</b>			
<b>32.31.00 Fences &amp; Gates</b>			
Wooden Guardrailing	BP#1	/BP#1	
Fencing - N/A	-	/-	
24' wide Single Arm Gate	1 ea	3,500.00 /ea	3,500



**90% CD Estimate**

Description	Takeoff Quantity	Total Cost/Unit	Total Amount
<b>32.31.00 Fences &amp; Gates</b>			
<i>Wooden Guardrailing - BP#1</i>	<i>lf</i>	<i>/lf</i>	
<b>Fences &amp; Gates</b>	<b>136,600 sf</b>	<b>0.03 /sf</b>	<b>3,500</b>
<b>32-31 FENCING</b>	<b>136,600 sf</b>	<b>0.03 /sf</b>	<b>3,500</b>



CONSIGLI  
*Est. 1905*



Job #:	<b>2043</b>
Project:	<b>Fuller Middle School</b>
Location:	<b>Framingham, MA</b>
Date:	<b>9/9/2019</b>
Proposal:	<b>General Requirements</b>
Gross Area (SF):	<b>157,000</b>

DESCRIPTION	Fuller Proposed GR	Steel & Concrete Package		Remaining
		Early Site		
Temp Power - Allowance	\$ 125,000.00	\$ 5,000.00	\$ 5,000.00	\$ 115,000
Temp Heating - Allowance	\$ 80,000.00	\$ 5,000.00	\$ 20,000.00	\$ 55,000
Temp Heating Fuel - Allowance	\$ 50,000.00	\$ 3,000.00	\$ 17,000.00	\$ 30,000
Staging (Auditorium)	\$ 81,000.00			\$ 81,000
Dumpster - Allowance	\$ 125,000.00	\$ 15,000.00	\$ 15,000.00	\$ 95,000
Temp Toilets	\$ 20,000.00	\$ 5,000.00	\$ 6,000.00	\$ 9,000
Project Identification	\$ 10,000.00	\$ 10,000.00	\$ -	\$ -
Temporary Barriers	\$ 40,000.00	\$ 4,000.00		\$ 36,000
Temp Fencing	\$ 248,520.00	\$ 106,792.00	\$ 57,688.00	\$ 84,040
Police Details - Allowance	\$ 30,000.00	\$ 5,000.00	\$ 10,000.00	\$ 15,000
Weather Protection - Allowance	\$ 170,000.00	\$ 10,000.00	\$ 50,000.00	\$ 110,000
Winter Conditions - Allowance	\$ 140,000.00	\$ 5,000.00	\$ 40,000.00	\$ 95,000
Carpenter Foreman	\$ 658,908.00	\$ 85,866.00	\$ 21,255.00	\$ 551,787
Labor Foreman	\$ 594,074.00	\$ 87,362.00	\$ 35,159.00	\$ 471,553
Temp Power - Allowance	\$ 20,000.00	\$ 5,000.00	\$ 2,500.00	\$ 12,500
Safety & First Aid	\$ 60,000.00	\$ 14,000.00	\$ 21,000.00	\$ 25,000
Temp. Fire Extinguishers	\$ 10,000.00	\$ 1,000.00	\$ 1,500.00	\$ 7,500
Temp Stair Towers	\$ 120,000.00		\$ 12,000.00	\$ 108,000
Roof Edge Protection	\$ 50,000.00			\$ 50,000
Pest Control	\$ 10,000.00	\$ 10,000.00		\$ -
Building Layout	\$ 115,000.00	\$ 21,000.00	\$ 30,000.00	\$ 64,000
Final Cleaning - Interior	\$ 157,000.00			\$ 157,000
Final Cleaning - Glass - Interior	\$ 43,000.00			\$ 43,000
Final Cleaning - Glass - Exterior	\$ 43,000.00			\$ 43,000
Project and Site Traffic Signage (Temp)	\$ 20,000.00	\$ 9,000.00	\$ 11,000.00	\$ -
Time Lapse Camera	\$ 17,000.00	\$ 17,000.00		\$ -
Storage	\$ 15,000.00	\$ 3,000.00	\$ 3,000.00	\$ 9,000
Security	\$ 17,000.00	\$ 5,000.00	\$ 5,000.00	\$ 7,000
Air Quality Control	\$ 15,000.00			\$ 15,000
<b>TOTAL GENERAL REQUIREMENT COSTS</b>	<b>\$ 3,084,502.00</b>	<b>\$ 432,020.00</b>	<b>\$ 363,102.00</b>	<b>\$ 2,289,380.00</b>





CONSIGLI  
*Est. 1905*







---

## ASSUMPTIONS & QUALIFICATIONS

### FULLER MIDDLE SCHOOL

90% CONSTRUCTION DOCUMENT ESTIMATE

SEPTEMBER 27, 2019

---

#### GENERAL

1. Pricing is based on the following:
  - 90% Construction Document Pricing Drawings by Jonathan Levi Architects, dated September 9, 2019.
  - 90% Construction Document Pricing Drawings by Jonathan Levi Architects, dated September 9, 2019.
2. Testing and/or inspections are not included.
3. Builders Risk Insurance is included in the Amendment #1 GMP value.
4. Building permit cost is not included.
5. A Payment and Performance Bond is included in the Amendment #1 GMP value.
6. Sales tax is not included as this project is assumed to be tax exempt.
7. Subcontractor insurances are included per Consigli standard subcontract.
8. Utility company back charges, user fees, etc. (temporary electric, water, gas, etc.) are excluded.
9. Work hours are assumed to be normal business hours (7:00AM to 3:00PM) Monday to Friday. Overtime, phasing, or off-hours work costs are not included.
10. Breakouts provided are for informational/accounting purposes only. We reserve the right to reprice our estimate if changes are made to the scope of the project.
11. Site Security costs or provisions are not included.
12. Uniform Fire watch is not included.
13. An exterior mockup is included as an allowance.
14. All design is by the Owner's Designer. Delegated design is excluded.

---

#### TRADE SPECIFIC

15. Hazardous material testing is not included.
16. Removal and/or relocation of furniture is not included.
17. Barrier-1 or similar concrete additives are not included.
18. The concrete floor at the Auditorium is included as polished per sheet A141D.
19. Exterior masonry work includes staging.
20. Interior brick veneer is not shown and therefore not included.
21. Fluid applied moisture mitigation is not included.
22. Resilient tile base is included as surface applied.
23. The Learning Commons stairs are included with rubber treads, risers, and landings.
24. CMU walls are not painted.
25. (3) fume hoods are included.
26. We have not included any costs or provisions for FF & E items and assume this will be by the Owner.
27. The orchestra enclosures are not included. These will be FF & E by the Owner.
28. Elevator operator costs are included.
29. Hydrant flow tests are not included and are assumed to have been previously completed to inform the fire protection design.



## ASSUMPTIONS & QUALIFICATIONS

### FULLER MIDDLE SCHOOL

90% CONSTRUCTION DOCUMENT ESTIMATE

SEPTEMBER 27, 2019

30. A Fire pump is not included.
31. A Domestic Booster pump is not included.
32. A Compressed Air System is not included.
33. Two (2) Gas Fired Domestic water heaters are included.
34. One (1) Domestic Storage tank is included.
35. Laboratory Hot Water piping is wrapped with heat maintenance cable.
36. Gas piping is included to (2) science labs 111A and 1114.
37. Ten (10) Gas Turrets are included.
38. Two (2) interior kitchen grease traps are included.
39. One (1) Exterior 8000 Gallon precast concrete grease trap is included.
40. Radon venting is not included.
41. Primary roof drains and storm piping is included.
42. Overflow secondary roof drains and piping is not included.
43. Interior under-slab drainage is not included.
44. A rainwater reclaim system is not included.
45. Six (6) Acid Neutralization local Chip Tanks are included.
46. Two (2) PH Monitoring panels and sensors are included.
47. Central Acid Neutralization and exterior pump stations are not included.
48. Rectangular, single-walled ductwork is included for supply air medium distribution.
49. VAV's do not include hot water re-heat coils.
50. Electrical and fire alarm permit fee costs are excluded (assumed waived by City of Framingham).
51. Primary cable, primary terminations, and exterior pad mount transformer by Utility Co.
52. Concealed lighting, power, and fire alarm branch circuitry is routed in MC Cable (per NEC Article 330).
53. Distribution feeders are routed in EMT and copper wire (where not required to be MI Cable).
54. Power, switch stations, and LV cable for twenty-five (25) motorized window treatment locations are included.
55. VFD's, motor starters, and motor controllers furnished by Division 23, installed and wired by Division 26.
56. Provisions for a future roof mounted photovoltaic (PV) system are included.
57. Two (2) central uninterruptible power supplies (UPS's) - 480V: 208/120V, 24kW (8 min. backup) - are included.
58. ATS's provided as open transition, with bypass isolation functionality included for legal-required and life-safety.
59. Cable tray is included for MDF and IDF's (200LF total); all other horizontal cabling routed across j-hooks.
60. Audio-visual devices, jacks, cabling, head end equipment, monitors, terminations and labor by Owner's Vendor.
61. Assistive classroom listening systems are not included.
62. Emergency pull-cord or call-for-aid systems are not included.
63. Motorized window treatment power and/or controls are excluded; none are shown on the electrical drawings.
64. Electrical floor boxes and poke-thru devices are not shown on power plans, and none are included in estimate.
65. Theatrical light fixtures, theatrical rigging, and theatrical lighting controls are included with theater equipment.
66. Electrical heat trace cabling system or power connections are not included.
67. Exterior site and building mounted lighting are included as shown on drawings E003-1 and E003-2.



---

## ASSUMPTIONS & QUALIFICATIONS

### FULLER MIDDLE SCHOOL

90% CONSTRUCTION DOCUMENT ESTIMATE

SEPTEMBER 27, 2019

- 68. Addressable fire alarm Notifier system shall be capable of voice evacuation via speaker/strobe appliances; a stand-alone mass notification system is not included.
- 69. Play field equipment is not included.
- 70. Fencing is not shown and therefore not included.

### ALLOWANCES

---

71. Exterior wall mockup (excluding Concrete and Steel).	\$55,000
72. Miscellaneous casework.	\$136,600
73. Miscellaneous rough carpentry.	\$88,790
74. Level 5 finish.	\$63,750
75. Miscellaneous specialties.	\$34,150
76. Food service equipment.	\$415,270
77. Sound systems.	\$450,000
78. Theater and stage equipment.	\$416,921
79. Miscellaneous lab equipment.	\$25,000
80. Theater lighting power and rough in.	\$37,600
81. Miscellaneous site furnishings.	\$30,000
82. Irrigation.	\$208,870



***Fuller Middle School***

Framingham, MA

**September 30, 2019**

**90% Construction Documents Estimate**

**Owner's Project Manager**

SMMA

1000 Massachusetts Ave.

Cambridge, MA

**Architect:**

Jonathan Levi Architects

266 Beacon Street

Boston, MA 02116

**Estimator:**

Miyakoda Consulting

PO Box 47

Raynham, MA 02767

(617) 799-5832

## **Fuller Middle School**

Fuller Middle School

### **INTRODUCTION**

#### **Description:**

- 1** Construction of the Framingham Middle School
- 2** The scope of the work includes all related sitework, hardscape/landscape, and underground utilities

#### **Particulars:**

- 1** 90% CD Drawings and Specifications dated September 9, 2019, received from Jonathan Levi Architects
- 2** Detailed quantity takeoff from these documents where possible
- 3** Experience with similar projects of this nature with JLA

#### **Assumptions:**

- 1** The project will be constructed by a Construction Manager
- 2** Our costs assume that there will be at least three subcontractors submitting unrestricted bids in each sub-trade
- 3** Unit rates are based on current dollars
- 4** General Conditions and Requirements value covers Sub-Contractor's bond, site office overheads, and building permit applications
- 5** Fee markup is calculated on a percentage basis of direct construction costs. The value covers Contractor's bond, insurance and profit
- 6** Design and Pricing Contingency markup is an allowance for unforeseen design issues, design detail development and specification clarifications
- 7** Escalation has been included to midpoint of construction. The construction start date is June 2020.

#### **Exclusions:**

- 1** Design fees and other soft costs
- 2** Owner's project administration
- 3** Construction of temporary facilities
- 4** Relocation expenses
- 5** Printing and advertising
- 6** Existing condition surveys and investigations
- 7** Work beyond the boundary of the site
- 8** Testing
- 9** Specialties, loose furnishings, fixtures and equipment beyond those noted
- 10** Preconstruction Fee
- 12** Traffic Improvements

**Fuller Middle School**

Fuller Middle School

137,385 GSF

**MAIN SUMMARY - NEW CONSTRUCTION**

<b><u>DESCRIPTION</u></b>			<b><u>TOTAL</u></b>	<b><u>COST/SF</u></b>
<b>Direct Trade Costs With Site</b>				
New Construction	137,385	GSF	\$42,156,411	\$306.85
Site Development			\$2,564,406	\$18.67
<b>Direct Trade Cost SubTotal</b>			<b>\$44,720,817</b>	<b>\$325.51</b>
Demolish Existing Building	195,400	GSF	\$1,465,500	\$10.67
Hazardous Waste Abatement (Budget provided)			\$1,294,490	\$9.42
<b>Building Cost Subtotal</b>			<b>\$47,480,807</b>	<b>\$345.60</b>
Design and Pricing Contingency	3.00%	\$47,480,807	\$1,424,424	\$10.37
<b>Building Cost Total</b>			<b>\$48,905,231</b>	<b>\$355.97</b>
Escal. to Midpoint of Construction (Consigli %)	1.3%	\$48,905,231	\$655,330	\$4.77
<b>Trade Cost SubTotal</b>			<b>\$49,560,561</b>	<b>\$360.74</b>
General Conditions			\$2,931,033	\$21.33
General Requirements			\$2,289,380	\$16.66
SDI (Non-Trade Contracts)			\$269,858	\$1.96
Sub Bonds (Trade Contracts)			\$403,034	\$2.93
General Liability Insurance			\$576,109	\$4.19
Construction Contingency	2.50%	\$49,560,561	\$1,239,014	\$9.02
CM Fee			\$1,152,218	\$8.39
BP#1			\$10,957,843	\$79.76
BP#2			\$8,738,800	\$63.61
BP#2 Buy Savings			(\$182,955)	(\$1.33)
<b>Estimated Construction Cost Total</b>			<b>\$77,934,895</b>	<b>\$567.27</b>

**Fuller Middle School**

Fuller Middle School

**DIRECT COST SUMMARY - NEW CONSTRUCTION**

<b><u>DIV. ELEMENTS</u></b>	<b><u>90%CD TOTAL</u></b>	<b><u>60%CD TOTAL</u></b>	<b><u>DIFFERENCE</u></b>	<b><u>% DIFF</u></b>
	137,385 GSF	136,600 GSF	785 GSF	0.57%
<b>A-G <u>BUILDING</u></b>				
<b><u>A SUBSTRUCTURES</u></b>				
A10 FOUNDATIONS				
Foundations	\$25,488	\$1,119,012	(\$1,093,524)	-97.72%
Slab on Grade	\$0	\$594,006	(\$594,006)	-100.00%
FOUNDATIONS TOTAL	<b>\$25,488</b>	<b>\$1,713,019</b>	<b>(\$1,687,530)</b>	<b>-98.51%</b>
A20 BASEMENT CONSTRUCTION				
<b>A SUBSTRUCTURES TOTAL</b>	<b>\$25,488</b>	<b>\$1,713,019</b>	<b>(\$1,687,530)</b>	<b>-98.51%</b>
<b><u>B SHELL</u></b>				
B10 STRUCTURE				
Upper Floor Construction	\$41,216	\$2,721,067	(\$2,679,851)	-98.49%
Roof Construction	\$357,300	\$2,333,165	(\$1,975,865)	-84.69%
STRUCTURE TOTAL	<b>\$398,516</b>	<b>\$5,054,232</b>	<b>(\$4,655,716)</b>	<b>-92.12%</b>
B20 EXTERIOR CLOSURE				
Exterior walls	\$5,096,693	\$4,646,002	\$450,691	9.70%
Exterior windows	\$1,965,316	\$1,942,628	\$22,688	1.17%
Exterior Doors	\$232,200	\$213,200	\$19,000	8.91%
EXTERIOR CLOSURE TOTAL	<b>\$7,294,209</b>	<b>\$6,801,830</b>	<b>\$492,379</b>	<b>7.24%</b>
B30 ROOFING				
Roof Coverngs	\$2,582,461	\$2,265,314	\$317,147	14.00%
ROOFING TOTAL	<b>\$2,582,461</b>	<b>\$2,265,314</b>	<b>\$317,147</b>	<b>14.00%</b>
<b>B SHELL TOTAL</b>	<b>\$10,275,185</b>	<b>\$14,121,376</b>	<b>(\$3,846,190)</b>	<b>-27.24%</b>
<b><u>C INTERIORS</u></b>				
C10 INTERIOR CONSTRUCTION				
Partitions	\$4,770,736	\$4,412,924	\$357,812	8.11%
Interior Doors, frames & Hardware	\$969,468	\$895,898	\$73,570	8.21%
Fittings	\$1,081,325	\$915,361	\$165,964	18.13%
INTERIOR CONSTRUCTION TOTAL	<b>\$6,821,528</b>	<b>\$6,224,182</b>	<b>\$597,346</b>	<b>9.60%</b>



**Fuller Middle School**  
Fuller Middle School

**DIRECT COST SUMMARY - NEW CONSTRUCTION**

<b><u>DIV. ELEMENTS</u></b>	<b><u>90%CD</u></b> <b><u>TOTAL</u></b>	<b><u>60%CD</u></b> <b><u>TOTAL</u></b>	<b><u>DIFFERENCE</u></b>	<b><u>% DIFF</u></b>
	137,385 GSF	136,600 GSF	785 GSF	0.57%
<b>C20 STAIRCASES</b>				
Staircases	\$469,770	\$590,570	(\$120,800)	-20.45%
<b>STAIRCASES TOTAL</b>	<b>\$469,770</b>	<b>\$590,570</b>	<b>(\$120,800)</b>	<b>-20.45%</b>
<b>C30 INTERIOR FINISHES</b>				
Wall finishes	\$1,776,276	\$1,767,241	\$9,035	0.51%
Floor finishes	\$1,301,453	\$1,288,200	\$13,253	1.03%
Ceiling finishes	\$1,927,926	\$1,858,543	\$69,383	3.73%
<b>INTERIOR FINISHES TOTAL</b>	<b>\$5,005,654</b>	<b>\$4,913,983</b>	<b>\$91,671</b>	<b>1.87%</b>
<b>C INTERIORS TOTAL</b>	<b>\$12,296,952</b>	<b>\$11,728,735</b>	<b>\$568,217</b>	<b>4.84%</b>
<b><u>D SERVICES</u></b>				
<b>D10 VERTICAL MOVEMENT</b>				
Conveying System	\$213,400	\$213,400	\$0	0.00%
<b>VERTICAL MOVEMENT TOTAL</b>	<b>\$213,400</b>	<b>\$213,400</b>	<b>\$0</b>	<b>0.00%</b>
<b>D20 PLUMBING</b>				
Plumbing	\$2,126,673	\$2,126,673	\$0	0.00%
<b>PLUMBING TOTAL</b>	<b>\$2,126,673</b>	<b>\$2,126,673</b>	<b>\$0</b>	<b>0.00%</b>
<b>D30 HVAC</b>				
HVAC	\$7,879,869	\$7,842,369	\$37,500	0.48%
<b>HVAC TOTAL</b>	<b>\$7,879,869</b>	<b>\$7,842,369</b>	<b>\$37,500</b>	<b>0.48%</b>
<b>D40 FIRE PROTECTION</b>				
Fire Protection	\$863,994	\$852,994	\$11,000	1.29%
<b>FIRE PROTECTION TOTAL</b>	<b>\$863,994</b>	<b>\$852,994</b>	<b>\$11,000</b>	<b>1.29%</b>
<b>D50 ELECTRICAL</b>				
Service and distribution	\$5,523,083	\$5,110,258	\$412,825	8.08%
<b>ELECTRICAL TOTAL</b>	<b>\$5,523,083</b>	<b>\$5,110,258</b>	<b>\$412,825</b>	<b>8.08%</b>
<b>D SERVICES TOTAL</b>	<b>\$16,607,018</b>	<b>\$16,145,693</b>	<b>\$461,325</b>	<b>2.86%</b>
<b><u>E EQUIPMENT AND FURNISHINGS</u></b>				

**Fuller Middle School**  
Fuller Middle School

**DIRECT COST SUMMARY - NEW CONSTRUCTION**

<b><u>DIV. ELEMENTS</u></b>	<b><u>90%CD</u></b> <b><u>TOTAL</u></b>	<b><u>60%CD</u></b> <b><u>TOTAL</u></b>	<b><u>DIFFERENCE</u></b>	<b><u>% DIFF</u></b>
	137,385 GSF	136,600 GSF	785 GSF	0.57%
<b>E10 EQUIPMENT</b>				
Institutional Equipment	\$1,644,448	\$1,644,448	\$0	0.00%
<b>EQUIPMENT TOTAL</b>	<b>\$1,644,448</b>	<b>\$1,644,448</b>	<b>\$0</b>	<b>0.00%</b>
<b>E20 FURNISHINGS</b>				
Specialties / Millwork	\$1,307,320	\$1,609,546	(\$302,226)	-18.78%
<b>FURNISHINGS TOTAL</b>	<b>\$1,307,320</b>	<b>\$1,609,546</b>	<b>(\$302,226)</b>	<b>-18.78%</b>
<b>D EQUIPMENT AND FURNISHINGS TOTAL</b>	<b>\$2,951,768</b>	<b>\$3,253,994</b>	<b>(\$302,226)</b>	<b>-9.29%</b>
<b><u>F SPECIAL CONSTRUCTION &amp; DEMO</u></b>				
<b>F10 SPECIAL CONSTRUCTION</b>				
Special construction	\$0	\$0	\$0	0.00%
<b>SPECIAL CONSTRUCTION TOTAL</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>0.00%</b>
<b>F20 SELECTIVE DEMOLITION</b>				
Selectice Demolition	\$0	\$0	\$0	0.00%
<b>SELECTIVE DEMOLITION TOTAL</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>0.00%</b>
<b>D SPECIAL CONSTRUCTION &amp; DEMO TOTAL</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>
<b>G EQUIPMENT AND FURNISHINGS TOTAL</b>	<b>\$4,427,652</b>	<b>\$4,880,991</b>	<b>(\$453,339)</b>	<b>-9.29%</b>
<b>A-G BUILDING TOTAL</b>	<b>\$42,156,411</b>	<b>\$46,962,817</b>	<b>(\$4,806,405)</b>	<b>-10.23%</b>
<b><u>G BUILDING SITEWORK</u></b>				
<b>G10 G10 SITE PREPARATION</b>				
G1010 Site Clearing	\$0	\$0	\$0	#DIV/0!
G1020 Site Demolition and Relocation	\$0	\$0	\$0	#DIV/0!
G1030 Site Earthwork	\$272,455	\$281,158	(\$8,703)	-3.10%
<b>G10 SITE PREPARATION TOTAL</b>	<b>\$272,455</b>	<b>\$281,158</b>	<b>(\$8,703)</b>	<b>-3.10%</b>
<b>G20 G20 SITE IMPROVEMENTS</b>				
G2020 Roadways	\$0	\$0	\$0	#DIV/0!
G2030 Pedestrian Paving	\$194,530	\$227,154	(\$32,624)	-14.36%
G2040 Site Development	\$771,744	\$975,872	(\$204,128)	-20.92%

**Fuller Middle School**  
Fuller Middle School

**DIRECT COST SUMMARY - NEW CONSTRUCTION**

<b><u>DIV. ELEMENTS</u></b>	<b><u>90%CD</u></b> <b><u>TOTAL</u></b>	<b><u>60%CD</u></b> <b><u>TOTAL</u></b>	<b><u>DIFFERENCE</u></b>	<b><u>% DIFF</u></b>
	137,385 GSF	136,600 GSF	785 GSF	0.57%
G2050 Landscaping	\$862,545	\$826,078		100.00%
<b>G20 SITE IMPROVEMENTS TOTAL</b>	<b>\$1,828,819</b>	<b>\$2,029,104</b>	<b>(\$236,752)</b>	<b>-11.67%</b>
<b>G30 G30 SITE CIVIL/MECHANICAL UTILITIES</b>				
G3010 Water Supply	\$0	\$0	\$0	#DIV/0!
G3020 Sanitary Sewer	\$0	\$0	\$0	100.00%
G3030 Storm Sewer	\$0	\$0	\$0	#DIV/0!
G3040 Heating Distribution	\$0	\$0	\$0	#DIV/0!
<b>G30 SITE CIVIL/MECHANICAL UTILITIES TOTAL</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>#DIV/0!</b>
<b>G40 G40 SITE ELECTRICAL UTILITIES</b>				
G4010 Site Electrical Utilities	\$463,132	\$476,743	(\$13,611)	-2.85%
<b>G40 SITE ELECTRICAL UTILITIES TOTAL</b>	<b>\$463,132</b>	<b>\$476,743</b>	<b>(\$13,611)</b>	<b>-2.85%</b>
<b>BP BID PACKAGES</b>				
BP#1 (Main Summary)	\$0	INCLUDED	\$0	100.00%
BP#2 (Main Summary)	\$0			
<b>BID PACKAGES TOTAL</b>	<b>\$0</b>			<b>100.00%</b>
<b>G BUILDING SITEWORK TOTAL</b>	<b>\$2,564,406</b>	<b>\$2,787,005</b>	<b>(\$259,066)</b>	<b>-9.30%</b>
<b>CONSTRUCTION TRADE TOTAL</b>	<b>\$44,720,817</b>	<b>\$49,749,822</b>	<b>(\$5,065,471)</b>	<b>-10.18%</b>
Demolish Existing Building	\$1,465,500	\$1,465,500	\$0	0.00%
Hazardous Waste Abatement (Budget provided)	\$1,294,490	\$1,384,630	(\$90,140)	-6.51%
Design and Pricing Contingency	\$1,424,424	\$2,629,998	(\$1,205,574)	-45.84%
<b>Building Cost</b>	<b>\$48,905,231</b>	<b>\$55,229,950</b>	<b>(\$3,544,176)</b>	<b>-6.42%</b>
Escal. to Midpoint of Construction (June 2020 Start)	\$655,330	\$828,449	(\$173,119)	-20.90%
<b>Trade Cost SubTotal</b>	<b>\$49,560,561</b>	<b>\$56,058,399</b>	<b>(\$5,182,383)</b>	<b>-9.24%</b>
General Conditions	\$2,931,033	\$3,401,447	(\$470,414)	-13.83%
General Requirements	\$2,289,380	\$2,652,483	(\$363,103)	-13.69%
Builder's Risk	\$0	\$0	\$0	
Traffic mitigation	\$0	\$0	\$0	
SDI	\$269,858	\$360,000	(\$90,142)	-25.04%
Sub Bonds	\$403,034	\$410,000	(\$6,966)	-1.70%
General Liability Insurance	\$576,109	\$668,571	(\$92,462)	-13.83%
Performance & Payment Bond	\$0	\$0	\$0	

**Fuller Middle School**  
Fuller Middle School

**DIRECT COST SUMMARY - NEW CONSTRUCTION**

<b><u>DIV. ELEMENTS</u></b>	<b><u>90%CD</u></b> <b><u>TOTAL</u></b>	<b><u>60%CD</u></b> <b><u>TOTAL</u></b>	<b><u>DIFFERENCE</u></b>	<b><u>% DIFF</u></b>
	137,385 GSF	136,600 GSF	785 GSF	0.57%
Construction Contingency	\$1,239,014	\$1,401,460	(\$162,446)	-11.59%
CM Fee	\$1,152,218	\$1,337,143	(\$184,925)	-13.83%
		\$10,957,843		
<b>Estimated Construction Cost Total</b>	<b>\$77,934,895</b>	<b>\$77,247,346</b>	<b>\$687,549</b>	<b>0.89%</b>



Noriko Hall &lt;norikohall@gmail.com&gt;

---

## Fuller - 90% CD Estimate Indirect Costs

1 message

**Lyons, Kristy** <klyons@consigli.com>

Thu, Sep 26, 2019 at 4:30 PM

To: Peter Timothy &lt;ptim@amfogarty.com&gt;, Noriko Hall &lt;norikohall@gmail.com&gt;, "Ericson, Timothy" &lt;tericson@consigli.com&gt;

Cc: Joel Seeley &lt;jseeley@smma.com&gt;, "Smith, Robert" &lt;rsmith@smma.com&gt;, Philip Gray &lt;pgray@leviarc.com&gt;, Elizabeth Bugbee &lt;ebugbee@leviarc.com&gt;, "Riordan, Christian" &lt;CRiordan@consigli.com&gt;, "Batista, Matteo" &lt;mbatista@consigli.com&gt;, "Traniello, Sarah" &lt;straniello@smma.com&gt;

Pete and Noriko,

The total value for Bid Package #1, including our indirect costs, is \$10,957,843.

The total value for Bid Package #2, including our indirect costs, is \$8,738,800.

The total buy-savings for Bid Package #2 is (\$182,955)

We are including these values at the bottom line of our estimate so that indirect adders are not factoring on the already bought scope. We recommend you do the same to streamline reconciliation.

Prorated values of indirect Lump Sum costs to include in your 90% CD estimate:

Balance of GCs: \$2,931,033

Balance of GRs: \$2,389,380

Balance of General Liability: \$576,109

Balance of Fee: \$1,152,218

Builders Risk and Payment &amp; Performance bond for entire project are included in the BP#1 value.

See attached BP#1 &amp; BP#2 GMP summaries for reference.

Bid Package #2 includes the steel at the locker guardrails and stairs 4&amp;5. All other stairs should be included as Misc. Metals.



Any questions, please let us know. Thanks,



**Kristy Lyons**  
**Preconstruction Manager**  
t: 508.458.0290 | m: 781.910.9565  
    [consigli.com](http://consigli.com)

---

**2 attachments**

-  **1.1 Fuller Middle School - Bid Package #1 06.17.19.pdf**  
611K
-  **ECSP GMP #2 Summary\_Consigli\_Fuller.pdf**  
121K

**Fuller Middle School**

Fuller Middle School

137,385 GSF

**DIRECT COST SUMMARY - NEW CONSTRUCTION**

<b><u>DIV.</u></b>	<b><u>ELEMENTS</u></b>	<b><u>SITWORK</u></b>	<b><u>BUILDING</u></b>	<b><u>TOTAL</u></b>	<b><u>\$/GSF</u></b>
<b><u>A SUBSTRUCTURES</u></b>					
A10	FOUNDATIONS				
	Foundations		\$25,488	\$25,488	\$0.19 /GSF
	Slab on Grade		\$0	\$0	\$0.00 /GSF
	FOUNDATIONS TOTAL		<b>\$25,488</b>	<b>\$25,488</b>	<b>\$0.19 /GSF</b>
A20	BASEMENT CONSTRUCTION		\$0	\$0	
<b>A</b>	<b>SUBSTRUCTURES TOTAL</b>		<b>\$25,488</b>	<b>\$25,488</b>	<b>\$0.19 /GSF</b>
<b><u>B SHELL</u></b>					
B10	STRUCTURE				
	Upper Floor Construction		\$41,216	\$41,216	\$0.30 /GSF
	Roof Construction		\$357,300	\$357,300	\$2.60 /GSF
	STRUCTURE TOTAL		<b>\$398,516</b>	<b>\$398,516</b>	<b>\$2.90 /GSF</b>
B20	EXTERIOR CLOSURE				
	Exterior walls		\$5,096,693	\$5,096,693	\$37.10 /GSF
	Exterior windows		\$1,965,316	\$1,965,316	\$14.31 /GSF
	Exterior Doors		\$232,200	\$232,200	\$1.69 /GSF
	EXTERIOR CLOSURE TOTAL		<b>\$7,294,209</b>	<b>\$7,294,209</b>	<b>\$53.09 /GSF</b>
B30	ROOFING				
	Roof Coverngs		\$2,582,461	\$2,582,461	\$18.80 /GSF
	ROOFING TOTAL		<b>\$2,582,461</b>	<b>\$2,582,461</b>	<b>\$18.80 /GSF</b>
<b>B</b>	<b>SHELL TOTAL</b>		<b>\$10,275,185</b>	<b>\$10,275,185</b>	<b>\$74.79 /GSF</b>
<b><u>C INTERIORS</u></b>					
C10	INTERIOR CONSTRUCTION				
	Partitions		\$4,770,736	\$4,770,736	\$34.73 /GSF
	Interior Doors, frames & Hardware		\$969,468	\$969,468	\$7.06 /GSF
	Fittings		\$1,081,325	\$1,081,325	\$7.87 /GSF
	INTERIOR CONSTRUCTION TOTAL		<b>\$6,821,528</b>	<b>\$6,821,528</b>	<b>\$49.65 /GSF</b>
C20	STAIRCASES				
	Staircases		\$469,770	\$469,770	\$3.42 /GSF

**Fuller Middle School**

Fuller Middle School

137,385 GSF

**DIRECT COST SUMMARY - NEW CONSTRUCTION**

<b><u>DIV.</u></b>	<b><u>ELEMENTS</u></b>	<b><u>SITWORK</u></b>	<b><u>BUILDING</u></b>	<b><u>TOTAL</u></b>	<b><u>\$/GSF</u></b>
	STAIRCASES TOTAL		<b>\$469,770</b>	<b>\$469,770</b>	<b>\$3.42 /GSF</b>
C30	INTERIOR FINISHES				
	Wall finishes		\$1,776,276	\$1,776,276	\$12.93 /GSF
	Floor finishes		\$1,301,453	\$1,301,453	\$9.47 /GSF
	Ceiling finishes		\$1,927,926	\$1,927,926	\$14.03 /GSF
	INTERIOR FINISHES TOTAL		<b>\$5,005,654</b>	<b>\$5,005,654</b>	<b>\$36.44 /GSF</b>
<b>C</b>	<b>INTERIORS TOTAL</b>		<b>\$12,296,952</b>	<b>\$12,296,952</b>	<b>\$89.51 /GSF</b>
<b>D</b>	<b><u>SERVICES</u></b>				
D10	VERTICAL MOVEMENT				
	Conveying System		\$213,400	\$213,400	\$1.55 /GSF
	VERTICAL MOVEMENT TOTAL		<b>\$213,400</b>	<b>\$213,400</b>	<b>\$1.55 /GSF</b>
D20	PLUMBING				
	Plumbing		\$2,126,673	\$2,126,673	\$15.48 /GSF
	PLUMBING TOTAL		<b>\$2,126,673</b>	<b>\$2,126,673</b>	<b>\$15.48 /GSF</b>
D30	HVAC				
	HVAC		\$7,879,869	\$7,879,869	\$57.36 /GSF
	HVAC TOTAL		<b>\$7,879,869</b>	<b>\$7,879,869</b>	<b>\$57.36 /GSF</b>
D40	FIRE PROTECTION				
	Fire Protection		\$863,994	\$863,994	\$6.29 /GSF
	FIRE PROTECTION TOTAL		<b>\$863,994</b>	<b>\$863,994</b>	<b>\$6.29 /GSF</b>
D50	ELECTRICAL				
	Service and distribution		\$5,523,083	\$5,523,083	\$40.20 /GSF
	ELECTRICAL TOTAL		<b>\$5,523,083</b>	<b>\$5,523,083</b>	<b>\$40.20 /GSF</b>
<b>D</b>	<b>SERVICES TOTAL</b>		<b>\$16,607,018</b>	<b>\$16,607,018</b>	<b>\$120.88 /GSF</b>
<b>E</b>	<b><u>EQUIPMENT AND FURNISHINGS</u></b>				
E10	EQUIPMENT				
	Institutional Equipment		\$1,644,448	\$1,644,448	\$11.97 /GSF
	EQUIPMENT TOTAL		<b>\$1,644,448</b>	<b>\$1,644,448</b>	<b>\$11.97 /GSF</b>



**Fuller Middle School**

Fuller Middle School

137,385 GSF

**DIRECT COST SUMMARY - NEW CONSTRUCTION**

<b><u>DIV. ELEMENTS</u></b>	<b><u>SITWORK</u></b>	<b><u>BUILDING</u></b>	<b><u>TOTAL</u></b>	<b><u>\$/GSF</u></b>
E20 FURNISHINGS				
Specialties / Millwork		\$1,307,320	\$1,307,320	\$9.52 /GSF
FURNISHINGS TOTAL		<b>\$1,307,320</b>	<b>\$1,307,320</b>	<b>\$9.52 /GSF</b>
<b>D EQUIPMENT AND FURNISHINGS TOTAL</b>		<b>\$2,951,768</b>	<b>\$2,951,768</b>	<b>\$21.49 /GSF</b>
<b><u>F SPECIAL CONSTRUCTION &amp; DEMOLITION</u></b>				
F10 SPECIAL CONSTRUCTION				
Special construction		\$0	\$0	\$0.00 /GSF
SPECIAL CONSTRUCTION TOTAL		<b>\$0</b>	<b>\$0</b>	<b>\$0.00 /GSF</b>
F20 SELECTIVE DEMOLITION				
Selectice Demolition		\$0	\$0	\$0.00 /GSF
SELECTIVE DEMOLITION TOTAL		<b>\$0</b>	<b>\$0</b>	<b>\$0.00 /GSF</b>
<b>D SPECIAL CONSTRUCTION &amp; DEMOLITION TOTAL</b>		<b>\$0</b>	<b>\$0</b>	<b>\$0.00 /GSF</b>
<b><u>G BUILDING SITEWORK</u></b>				
G10 G10 SITE PREPARATION				
G1010 Site Clearing	\$0		\$0	\$0.00 /GSF
G1020 Site Demolition and Relocation	\$0		\$0	\$0.00 /GSF
G1030 Site Earthwork	\$272,455		\$272,455	\$1.98 /GSF
G10 SITE PREPARATION TOTAL	<b>\$272,455</b>		<b>\$272,455</b>	<b>\$1.98 /GSF</b>
G20 G20 SITE IMPROVEMENTS				
G2020 Roadways	\$0		\$0	\$0.00 /GSF
G2030 Pedestrian Paving	\$194,530		\$194,530	\$1.42 /GSF
G2040 Site Development	\$771,744		\$771,744	\$5.62 /GSF
G2050 Landscaping	\$862,545		\$862,545	\$6.28 /GSF
G20 SITE IMPROVEMENTS TOTAL	<b>\$1,828,819</b>		<b>\$1,828,819</b>	<b>\$13.31 /GSF</b>
G30 G30 SITE CIVIL/MECHANICAL UTILITIES				
G3010 Water Supply	\$0		\$0	\$0.00 /GSF
G3020 Sanitary Sewer	\$0		\$0	\$0.00 /GSF
G3030 Storm Sewer	\$0		\$0	\$0.00 /GSF
G3040 Heating Distribution	\$0		\$0	\$0.00 /GSF
G30 SITE CIVIL/MECHANICAL UTILITIES TOTAL	<b>\$0</b>		<b>\$0</b>	<b>\$0.00 /GSF</b>

**Fuller Middle School**

Fuller Middle School

137,385 GSF

**DIRECT COST SUMMARY - NEW CONSTRUCTION**

<b><u>DIV. ELEMENTS</u></b>	<b><u>SITWORK</u></b>	<b><u>BUILDING</u></b>	<b><u>TOTAL</u></b>	<b><u>\$/GSF</u></b>
G40 G40 SITE ELECTRICAL UTILITIES				
G4010 Site Electrical Utilities	\$463,132		\$463,132	\$3.37 /GSF
G40 SITE ELECTRICAL UTILITIES TOTAL	<b>\$463,132</b>		<b>\$463,132</b>	<b>\$3.37 /GSF</b>
BP BID PACKAGES				
BP#1 (Main Summary)			\$0	\$0.00 /GSF
BP#2 (Main Summary)			\$0	\$0.00 /GSF
BID PACKAGES TOTAL	<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0.00 /GSF</b>
<b>G BUILDING SITEWORK TOTAL</b>	<b>\$2,564,406</b>	<b>\$0</b>	<b>\$2,564,406</b>	<b>\$18.67 /GSF</b>
<b>CONSTRUCTION TRADE TOTAL</b>	<b>\$2,564,406</b>	<b>\$42,156,411</b>	<b>\$44,720,817</b>	<b>\$325.51 /GSF</b>

**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>10 A10 FOUNDATIONS</b>				
<b>11</b>				
<b>12 A1010 FOUNDATIONS</b>				
<b>13 Earthwork</b>				
<b>14</b> Slab-on-Grade platform preparation in Sitework Tab	<b>66,213</b>	SF		
<b>15</b> Continuous footing w/foundation wall	<b>2,049</b>	LF		
<b>16</b> Excavation	<b>4,905</b>	CY	\$12.00	See below
<b>17</b> Backfill from import	<b>4,215</b>	CY	\$22.00	See below
<b>18</b> Spread footings	<b>133</b>	EA		
<b>19</b> Excavation	<b>977</b>	CY	\$12.00	See below
<b>20</b> Backfill from import		CY	\$22.00	See below
<b>21</b> Elevator pit	<b>1</b>	EA		
<b>22</b> Excavation	<b>47</b>	CY	\$12.00	See below
<b>23</b> Backfill from import	<b>18</b>	CY	\$22.00	See below
<b>24</b> Disposal				
<b>25</b> Cast to off-site waste	<b>1,696</b>	CY	\$22.00	See below
<b>26</b> Grade & compact	<b>66,213</b>	SF	\$1.00	See below
<b>27</b> 12" base course sand & gravel below slab on grade	<b>2,452</b>	CY	\$35.00	See below
<b>28</b>				
<b>29</b> Building overexcavation:				
<b>30</b> Over-excavation to remove topsoil	<b>12,262</b>	CY	\$9.00	
<b>31</b> Over-excavation	<b>11,649</b>	CY	\$8.50	
<b>32</b> Dispose materials	<b>6,131</b>	CY	\$18.00	
<b>33</b> Structural fill	<b>5,242</b>	CY	\$25.00	
<b>34</b>				
<b>35</b> Building Area				
<b>36</b> Cut and fill for building	<b>2,452.33</b>	CY	\$8.00	
<b>37</b> 1' Gravel base to building	<b>2,452</b>	CY	\$35.00	
<b>38</b>				
<b>39</b> Concrete				
<b>40</b> Continuous footings; 3' x 1' 0" typ.	<b>2,049</b>	LF		
<b>41</b> 4' x 1' 0"				
<b>42</b> 5' x 1' 0"				
<b>43</b> Concrete; material	<b>247</b>	CY	\$135.00	BP#2
<b>44</b> Concrete; place (combination of pumping/trucking)	<b>247</b>	CY	\$95.00	BP#2
<b>45</b> Reinforcement w/ftn wall dowels (10#/lf)	<b>20,490</b>	LB	\$1.15	BP#2
<b>46</b> Formwork	<b>8,196</b>	SF	\$12.00	BP#2
<b>47</b> Spread footings	<b>133</b>	EA		
<b>48</b> Concrete; material	<b>465</b>	CY	\$135.00	BP#2
<b>49</b> Concrete; place	<b>465</b>	CY	\$95.00	BP#2
<b>50</b> Reinforcement (100#/cy)	<b>46,500</b>	LB	\$1.15	BP#2
<b>51</b> Formwork	<b>6,406</b>	SF	\$12.00	BP#2
<b>52</b> Pilasters	<b>133</b>	EA	\$1,100.00	BP#2
<b>53</b> Grade beam GB-1, GB-2	<b>288</b>	LF		



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>54</b> Concrete; material	57	CY	\$135.00	BP#2
<b>55</b> Concrete; place (combination of pumping/trucking)	57	CY	\$95.00	BP#2
<b>56</b> Reinforcement (125#/cy)	7,125	LB	\$1.15	BP#2
<b>57</b> Formwork	1,940	SF	\$12.00	BP#2
<b>58</b> <i>Foundation and frost walls; 16" thick x 4' 0" high typ.</i>	8,551	SF		
<b>59</b> Concrete; material	443	CY	\$135.00	BP#2
<b>60</b> Concrete; place	443	CY	\$95.00	BP#2
<b>61</b> Reinforcement (150#/cy)	66,450	LB	\$1.15	BP#2
<b>62</b> Formwork	17,212	SF	\$8.00	BP#2
<b>63</b> <i>Foundation walls; 21" thick x 4' 0" high typ.</i>	1,645	SF		
<b>64</b> Concrete; material	112	CY	\$135.00	BP#2
<b>65</b> Concrete; place	112	CY	\$95.00	BP#2
<b>66</b> Reinforcement (150#/cy)	16,800	LB	\$1.15	BP#2
<b>67</b> Formwork	3,289	SF	\$8.00	BP#2
<b>68</b> Brick shelf	2,049	LF	\$5.00	BP#2
<b>69</b> Elevator pit; slab and walls	1	EA	\$5,000.00	BP#2
<b>70</b> Anchor bolts	532	SET	\$35.00	BP#2
<b>71</b> 6" Ø hole through wall, backfill w/crushed stone	4	EA	\$500.00	BP#2
<b>72</b>				
<b>73</b> <i>Bandshell</i>				
<b>74</b> Footing	46	lf		
<b>75</b> Concrete; material	7	CY	\$135.00	BP#2
<b>76</b> Concrete; place	7	CY	\$95.00	BP#2
<b>77</b> Reinforcing	455	LBS	\$1.15	BP#2
<b>78</b> Formwork	96	SF	\$9.00	BP#2
<b>79</b> Wall	182	sf		
<b>80</b> Concrete	10	CY	\$135.00	BP#2
<b>81</b> Placing	10	CY	\$95.00	BP#2
<b>82</b> Reinforcing	1,500	LBS	\$1.15	BP#2
<b>83</b> Formwork	382	SF	\$8.00	BP#2
<b>84</b> Concrete steps	556	LFR	\$150.00	BP#2
<b>85</b> Concrete steps , amphitheatre steps	385	LFR	\$125.00	BP#2
<b>86</b> Miscellaneous concrete				\$0
<b>87</b> Ground improvements				BP#1
<b>88</b>				
<b>89</b> <i>Special Foundation Conditions</i>				
<b>90</b> Dewatering during excavation				BP#1
<b>91</b>				
<b>92</b> <i>Thermal &amp; Moisture Protection</i>				
<b>93</b> 2" rigid insulation at foundation walls	10,195	SF	\$2.50	\$25,488
<b>94</b> Waterproofing elevator pit	225	SF	\$18.00	BP#2
<b>95</b> Damp proofing to foundation walls	10,195	SF	\$4.50	BP#2
<b>96</b> <b>A1010 FOUNDATIONS TOTAL</b>				<b>\$25,488</b>



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>97</b>				
<b>98 A1030 SLAB ON GRADE</b>				
<b>99 Concrete</b>				
<b>100 Slab on grade, 5" thick, WWF, top of slab 314' 0"</b>	<b>66,213</b>	<b>SF</b>		
<b>101 Concrete; material</b>	<b>1,030</b>	<b>CY</b>	\$135.00	BP#2
<b>102 Concrete; place &amp; finish</b>	<b>66,213</b>	<b>SF</b>	\$2.85	BP#2
<b>103 Reinforcement (6x6 mesh)</b>	<b>76,145</b>	<b>SF</b>	\$1.00	BP#2
<b>104 Slab depressions</b>	<b>1,243</b>	<b>LF</b>	\$65.00	BP#2
<b>105 Slab thickening at stair 5'x2'x1' deep</b>	<b>6</b>	<b>LOC</b>	\$2,500.00	BP#2
<b>106 Slab on grade at loading dock, 6" thick, #4 bars</b>	<b>350</b>	<b>SF</b>		
<b>107 Concrete; material</b>	<b>6</b>	<b>CY</b>	\$135.00	BP#2
<b>108 Concrete; place &amp; finish</b>	<b>350</b>	<b>SF</b>	\$2.85	BP#2
<b>109 Reinforcement; #4@12"bew</b>	<b>469</b>	<b>LBS</b>	\$1.45	BP#2
<b>110 Miscellaneous</b>				
<b>111 Concrete ramp @ Auditorium</b>	<b>2,440</b>	<b>SF</b>	\$18.00	BP#2
<b>112 Sloped walkway @ Cohort/Learning Common/Stage</b>	<b>320</b>	<b>SF</b>	\$20.00	BP#2
<b>113 Housekeeping &amp; mechanical equipment pads</b>	<b>1</b>	<b>LS</b>	\$5,000.00	BP#2
<b>114 Miscellaneous concrete</b>	<b>1</b>	<b>LS</b>	\$0.00	BP#2
<b>115</b>				
<b>116 Thermal &amp; Moisture Protection</b>				
<b>117 2" rigid insulation to perimeter of slab</b>	<b>6,392</b>	<b>SF</b>	\$2.65	BP#2
<b>118 Vapor retarder under slab</b>	<b>76,145</b>	<b>SF</b>	\$1.00	BP#2
<b>119 A1030 SLAB ON GRADE TOTAL</b>				<b>\$0</b>
<b>120</b>				
<b>121 A10 FOUNDATIONS TOTAL</b>				<b>\$25,488</b>
<b>122</b>				
<b>123</b>				
<b>124 A20 BASEMENT</b>				
<b>125</b>				
<b>126 No anticipated work</b>				
<b>127</b>				
<b>128 TOTAL SYSTEM A20 BASEMENT</b>				<b>\$0</b>
<b>129</b>				
<b>130</b>				
<b>131 B10 STRUCTURE</b>				
<b>132</b>				
<b>133 B1010 UPPER FLOOR CONSTRUCTION</b>				
<b>134 Concrete</b>				
<b>135 Slab on deck topping, 3 1/4" light weight, WWF</b>	<b>69,572</b>	<b>SF</b>		
<b>136 Concrete; material</b>	<b>966</b>	<b>CY</b>	\$135.00	BP#2
<b>137 Reinforcement (6x6 mesh)</b>	<b>76,529</b>	<b>SF</b>	\$1.00	BP#2
<b>138 Rebar at corners and openings</b>	<b>3,826</b>	<b>LBS</b>	\$1.15	BP#2
<b>139 Concrete; place &amp; finish</b>	<b>69,572</b>	<b>SF</b>	\$5.00	BP#2



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>140</b> Beam pocket	23	EA	\$750.00	BP#2
<b>141</b>				
<b>142</b> Concrete				
<b>143</b> Slab on deck topping, 3 1/4" light weight, WWF	1,600	SF		
<b>144</b> Concrete; material	22	CY	\$135.00	BP#2
<b>145</b> Reinforcement (6x6 mesh)	1,760	SF	\$1.00	BP#2
<b>146</b> Rebar at corners and openings	88	LBS	\$1.15	BP#2
<b>147</b> Concrete; place & finish	1,600	SF	\$5.00	BP#2
<b>148</b>				
<b>149</b> Structural Steel Framing	793	TNS		
<b>150</b> Steel floor framing				
<b>151</b> Wide flange beams	243	TNS	\$3,700.00	BP#2
<b>152</b> Wide flange beams > 100	36	TNS	\$3,950.00	BP#2
<b>153</b> HSS-shapes	47	TNS	\$4,150.00	BP#2
<b>154</b> W-shapes ; columns	14	TNS	\$3,950.00	BP#2
<b>155</b> HSS-shapes; columns	101	TNS	\$4,150.00	BP#2
<b>156</b> HSS brace frames	40	TNS	\$4,250.00	BP#2
<b>157</b> Remainder of steel framing; beams, columns, bridging	26	TNS	\$4,150.00	BP#2
<b>158</b> Plates, bent plates and angles	133	EA	\$75.00	BP#2
<b>159</b> Moment connections	157	EA	\$750.00	BP#2
<b>160</b> Shear studs	10,170	EA	\$5.50	BP#2
<b>161</b> 3" deep x 18ga galv composite floor deck	71,172	SF	\$4.25	BP#2
<b>162</b> Thermal & Moisture Protection				
<b>163</b> Firestopping	137,385	GSF	\$0.30	\$41,216
<b>164</b> Intumescent fireproofing				See Roof
<b>165</b> B1010 UPPER FLOOR CONSTRUCTION TOTAL				<u>\$41,216</u>
<b>166</b>				
<b>167</b> B1020 ROOF CONSTRUCTION				
<b>168</b> Structural steel roof framing	286	TNS		
<b>169</b> Wide flange beams	124	TNS	\$3,650.00	BP#2
<b>170</b> Wide flange beams > 100	87	TNS	\$3,900.00	BP#2
<b>171</b> HSS-shape	18	TNS	\$4,100.00	BP#2
<b>172</b> Support post HSS7.625x0.375; RTU screen	2	TNS	\$4,100.00	BP#2
<b>173</b> L- ledger; L4x4x1/4 anchored to CMU, roof	1	TNS	\$3,550.00	BP#2
<b>174</b> Roof steel framing incl's hanger support beam, 52DLH17, HSS trusses, 1"x10" 50KSI steel plate, etc.	42	TNS	\$4,100.00	BP#2
<b>175</b> Add reinforcement 7#/sf hot dip galv steel @ RTU	12	TNS	\$4,100.00	BP#2
<b>176</b> Moment connections	241	EA	\$750.00	BP#2
<b>177</b> Roof hanger @ main roof	47	EA	\$1,500.00	BP#2
<b>178</b> 3/4" rod hanger @ Gym and Auditorium roof	11	EA	\$1,500.00	BP#2
<b>179</b> Other misc plates, connections	65,518	SF	\$4.50	BP#2
<b>180</b> Premium for galv steel framing	14	TNS	\$500.00	BP#2
<b>181</b> 3" deep x 18ga galv comp roof deck (w/conc topping)	40,338	SF	\$4.25	BP#2



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>182</b> R3; 3" 18 ga roof deck above Learning Commons	<b>8,610</b>	SF	\$4.25 BP#2	
<b>183</b> R3C; 3" Cellular 18/16 ga roof deck, galv at Auditorium	<b>7,615</b>	SF	\$4.25 BP#2	
<b>184</b> R1.5; 1.5" 20 ga roof deck, Gym equipment storage	<b>835</b>	SF	\$6.00 BP#2	
<b>185</b> R1.5A; 1.5" Cellular acoustic 20 ga roof deck, galv at Gym	<b>8,120</b>	SF	\$6.50 BP#2	
<b>186</b> 1 hr spray fireproofing @ raised roof area over Learning Commons	<b>8,610</b>	SF	\$5.00	\$43,050
<b>187</b> Intumescent fireproofing	<b>1</b>	LS	\$65,000.00	\$65,000
<b>188</b> Rough blocking to roof				Div B3010
<b>189</b> Roof dunnage (SS)	<b>7</b>	TNS	\$7,500.00	\$52,500
<b>190</b> Roof screen, galv; HSS shapes	<b>15</b>	TNS	\$3,950.00	\$59,250
<b>191</b> Galvanized bar grating	<b>1,000</b>	SF	\$55.00	\$55,000
<b>192</b> Roof soffit/fascia framing	<b>500</b>	LF	\$165.00	\$82,500
<b>193</b> <b>B1020 ROOF CONSTRUCTION TOTAL</b>				<b>\$357,300</b>
<b>194</b>				
<b>195</b> <b>TOTAL SYSTEM B10 SUPERSTRUCTURE</b>				<b>\$398,516</b>
<b>196</b>				
<b>197</b>				
<b>198</b> <b>B20 EXTERIOR CLOSURE</b>	<b>70,150</b>	SF		
<b>199</b>				
<b>200</b> <b>B2010 EXTERIOR WALLS</b>	<b>57,695</b>			
<b>201</b>				
<b>202</b> Exterior brick wall; scored brick veneer, "modular" 8x8x4 , and "utility" 4x12x4, iron spot finish	<b>17,333</b>	SF	\$35.00	\$606,655
<b>203</b> 3" Faced rigid cellular polyiso insulation	<b>17,333</b>	SF	\$4.00	\$69,332
<b>204</b> Fluid applied air vapor barrier	<b>17,333</b>	SF	\$5.50	\$95,332
<b>205</b> Exterior CMU wall; scored ground face CMU, 8x12x16 , 4x8x16, and "utility" 4x12x4	<b>24,140</b>	SF	\$36.00	\$869,040
<b>206</b> 3" Faced rigid cellular polyiso insulation	<b>24,140</b>	SF	\$4.00	\$96,560
<b>207</b> Fluid applied air vapor barrier	<b>24,140</b>	SF	\$5.50	\$132,770
<b>208</b> ½" Fiberglass faced gypsum sheathing	<b>26,668</b>	SF	\$2.00	\$53,336
<b>209</b> 10" Cold formed metal framing	<b>26,668</b>	SF	\$12.00	\$320,016
<b>210</b> ⅝" GWB interior of exterior wall	<b>26,668</b>	SF	\$2.50	\$66,670
<b>211</b> 12" Reinforced ground face CMU wall backup @ Auditorium & Gym	<b>14,805</b>	SF	\$28.00	\$414,540
<b>212</b> Caulking and sealants at brick & CMU	<b>41,473</b>	SF	\$0.65	\$26,957
<b>213</b> 4" Utility brick, both sides @ parapet wall, Main Entrance	<b>175</b>	SF	\$32.00	\$5,600
<b>214</b> Precast colored coping on top of parapet wall	<b>26</b>	LF	\$150.00	\$3,900
<b>215</b> Premium for custom brick and CMU @ lintels & shelves	<b>1,128</b>	LF	\$50.00	\$56,400
<b>216</b> Corrugated metal panel w/exposed fasteners	<b>4,578</b>	SF	\$60.00	\$274,680
<b>217</b> 5" Fiberglass thermal Z-furring	<b>4,578</b>	SF	\$3.50	\$16,023
<b>218</b> 4" Mineral fiber insulation	<b>4,578</b>	SF	\$4.50	\$20,601
<b>219</b> Fluid applied air vapor barrier	<b>4,578</b>	SF	\$5.50	\$25,179
<b>220</b> ½" Fiberglass faced gypsum sheathing	<b>4,578</b>	SF	\$2.00	\$9,156



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>221</b> 10" Cold formed metal framing	<b>4,578</b>	SF	\$12.00	\$54,936
<b>222</b> 5/8" GWB interior of exterior wall	<b>4,578</b>	SF	\$2.50	\$11,445
<b>223</b> Caulking and sealants at corrugated metal panel	<b>4,578</b>	SF	\$0.65	\$2,976
<b>224</b> Composite metal panel w/exposed fasteners	<b>3,638</b>	SF	\$75.00	\$272,850
<b>225</b> 5" Fiberglass thermal Z-furring	<b>3,638</b>	SF	\$3.50	\$12,733
<b>226</b> 4" Mineral fiber insulation	<b>3,638</b>	SF	\$4.50	\$16,371
<b>227</b> Fluid applied air vapor barrier	<b>3,638</b>	SF	\$5.50	\$20,009
<b>228</b> 1/2" Fiberglass faced gypsum sheathing	<b>3,638</b>	SF	\$2.00	\$7,276
<b>229</b> 10" Cold formed metal framing	<b>3,638</b>	SF	\$12.00	\$43,656
<b>230</b> 5/8" GWB interior of exterior wall	<b>3,638</b>	SF	\$2.50	\$9,095
<b>231</b> Caulking and sealants at composite metal panel	<b>3,638</b>	SF	\$0.65	\$2,365
<b>232</b> Wood grain phenolic panel - Trespa @ ext wall incl's projections/window bay	<b>6,581</b>	SF	\$82.00	\$539,642
<b>233</b> 5" Fiberglass thermal Z-furring	<b>6,581</b>	SF	\$3.50	\$23,034
<b>234</b> 4" Mineral fiber insulation at Trespa cladding -	<b>6,581</b>	SF	\$4.50	\$29,615
<b>235</b> Fluid applied air vapor barrier	<b>6,581</b>	SF	\$5.50	\$36,196
<b>236</b> 1/2" Fiberglass faced gypsum sheathing	<b>6,581</b>	SF	\$2.00	\$13,162
<b>237</b> 10" Cold formed metal framing	<b>6,581</b>	SF	\$12.00	\$78,972
<b>238</b> 5/8" GWB interior of exterior wall	<b>6,581</b>	SF	\$2.50	\$16,453
<b>239</b> Caulking and sealants at Trespa cladding	<b>6,581</b>	SF	\$0.65	\$4,278
<b>240</b>				
<b>241</b> Phenolic panel; Ext soffit at projection/window bay	<b>1,250</b>	SF	\$82.00	\$102,500
<b>242</b> Furring	<b>1,250</b>	SF	\$4.25	\$5,313
<b>243</b> 4" mineral fiber insulation at Trespa cladding - Exterior soffit	<b>1,250</b>	SF	\$4.00	\$5,000
<b>244</b> Air vapor barrier at Trespa cladding - Exterior soffit	<b>1,250</b>	SF	\$5.50	\$6,875
<b>245</b> 1/2" sheathing at Trespa cladding - Exterior soffit	<b>1,250</b>	SF	\$2.00	\$2,500
<b>246</b> 6" Metal stud at Trespa cladding - Exterior soffit	<b>1,250</b>	SF	\$9.50	\$11,875
<b>247</b> 5/8 GWB at Trespa cladding - Exterior soffit	<b>1,250</b>	SF	\$2.50	\$3,125
<b>248</b> Caulking and sealants at Trespa cladding - Ext. soffit	<b>1,250</b>	SF	\$0.65	\$813
<b>249</b>				
<b>250</b> <i>Miscellaneous</i>				
<b>251</b> Sand blasted cast in place concrete walls	<b>1</b>	LS	\$50,000.00	\$50,000
<b>252</b> Precast concrete at planter w/galv steel connection & cross bracing	<b>212</b>	SF	\$75.00	\$15,900
<b>253</b> Precast planter	<b>50</b>	LF	\$750.00	\$37,500
<b>254</b> Cont galv relieving angle at masonry wall	<b>1,038</b>	LF	\$100.00	\$103,800
<b>255</b> Loose lintel @ exterior wall openings	<b>90</b>	LF	\$200.00	\$18,000
<b>256</b> Miscellaneous metals in exterior closure	<b>57,520</b>	SF	\$1.50	\$86,280
<b>257</b> Window caulking				Div B2020
<b>258</b> Through wall sheet metal flashing	<b>1,424</b>	LF	\$25.00	\$35,600
<b>259</b> Corrugated perforated metal; mechanical RTU screen	<b>1,678</b>	SF	\$60.00	\$100,680
<b>260</b> Metal louver	<b>625</b>	SF	\$85.00	\$53,125
<b>261</b> Exterior mockup	<b>1</b>	LS	\$50,000.00	\$50,000
<b>262</b> Temporary enclosures	<b>1</b>	LS	\$50,000.00	\$50,000





**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>263 B2010 EXTERIOR WALLS TOTAL</b>				<b>\$5,096,693</b>
<b>264</b>				
<b>265 B2020 EXTERIOR WINDOWS</b>	<b>12,630</b>	<b>SF</b>		
<b>266</b> <i>Aluminum storefronts, double glazed w/security insul glazing, school guard glass, laminated interior glass</i>	919	SF		
<b>267</b> Type 10A; 24'-8 1/4" x 12'-0"	1	EA	\$34,300.00	\$34,300
<b>268</b> Type 11A; 9'-6 1/4" x 12'-0"	1	EA	\$13,200.00	\$13,200
<b>269</b> Type 12A; 9'-7 1/2" x 12'-0"	2	EA	\$11,600.00	\$23,200
<b>270</b> Type 13A; 7'-6" x 12'-0"	1	EA	\$10,400.00	\$10,400
<b>271</b> Type 16A; 12'-0" x 13'-0 1/2"	1	EA	\$17,900.00	\$17,900
<b>272</b> <i>Bay windows</i>	2,912	SF		
<b>273</b> Type 1; 9'-3" x 12'-0"	10	EA	\$13,300.00	\$133,000
<b>274</b> Type 2; 9'-3" x 12'-0"	11	EA	\$13,300.00	\$146,300
<b>275</b> Type 2A; 9'-3" x 11'-0 1/4"	2	EA	\$12,700.00	\$25,400
<b>276</b> Type 3; 9'-3" x 11'-6"	9	EA	\$12,700.00	\$114,300
<b>277</b> Type 3C; 7'-0" x 12'-0"	1	EA	\$10,100.00	\$10,100
<b>278</b> <i>Curtain wall/Windows</i>	8,799	SF		
<b>279</b> Type 4; 3'-0" x 10'-1"	57	EA	\$3,500.00	\$199,500
<b>280</b> Type 5A; 3'-11" x 12'-0"	6	EA	\$5,800.00	\$34,800
<b>281</b> Type 5B; 3'-11" x 11'-6"	22	EA	\$5,800.00	\$127,600
<b>282</b> Type A1; 1'-4" x 3'-0"	1	EA	\$500.00	\$500
<b>283</b> Type A2; 2'-0" x 4'-0"	1	EA	\$1,000.00	\$1,000
<b>284</b> Type A3; 2'-0" x 12'-0"	27	EA	\$2,600.00	\$70,200
<b>285</b> Type B1; 3'-4" x 12'-0"	10	EA	\$4,400.00	\$44,000
<b>286</b> Type B1A; 3'-4" x 5'-10"	2	EA	\$1,800.00	\$3,600
<b>287</b> Type B3; 3'-4" x 7'-0"	1	EA	\$2,800.00	\$2,800
<b>288</b> Type B4; 3'-4" x 12'-0"	9	EA	\$4,400.00	\$39,600
<b>289</b> Type C1; 3'-4" x 12'-0"	14	EA	\$4,400.00	\$61,600
<b>290</b> Type D1; 5'-4" x 6'-2"	2	EA	\$3,900.00	\$7,800
<b>291</b> Type D3; 5'-4" x 12'-0"	12	EA	\$7,000.00	\$84,000
<b>292</b> Type E1; 5'-4" x 10'-0"	3	EA	\$7,000.00	\$21,000
<b>293</b> Type E2; 5'-4" x 12'-0"	6	EA	\$7,000.00	\$42,000
<b>294</b> Type F1; 7'-4" x 6'-2"	1	EA	\$5,400.00	\$5,400
<b>295</b> Type F2; 7'-4" x 10'-0"	3	EA	\$9,200.00	\$27,600
<b>296</b> Type F3; 7'-4" x 12'-0"	7	EA	\$9,600.00	\$67,200
<b>297</b> Type G1; 7'-4" x 12'-0"	11	EA	\$9,600.00	\$105,600
<b>298</b> Type H1; 9'-4" x 6'-0"	1	EA	\$7,000.00	\$7,000
<b>299</b> Type H2; 9'-4" x 10'-0"	1	EA	\$12,200.00	\$12,200
<b>300</b> Type H3; 9'-4" x 12'-0"	1	EA	\$14,000.00	\$14,000
<b>301</b> Type I1; 9'-4" x 6'-0"	1	EA	\$7,000.00	\$7,000
<b>302</b> Type I2; 9'-4" x 10'-0"	1	EA	\$12,200.00	\$12,200
<b>303</b> Type I3; 9'-4" x 12'-0"	1	EA	\$12,200.00	\$12,200
<b>304</b> Type K1; 11'-4" x 12'-0"	2	EA	\$17,000.00	\$34,000



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>305</b> Type L1; 13'-4" x 12'-0"	1	EA	\$17,500.00	\$17,500
<b>306</b> Type M1; 10'-4" x 6'-2"	1	EA	\$8,000.00	\$8,000
<b>307</b> Type N1; 6'-4" x 4'-4"	2	EA	\$3,400.00	\$6,800
<b>308</b> Type N2; 6'-4" x 5'-10"	2	EA	\$4,400.00	\$8,800
<b>309</b> Type O1; 6'-4" x 12'-0"	2	EA	\$9,500.00	\$19,000
<b>310</b> Type Q1; 4'-4" x 7'-0"	1	EA	\$3,600.00	\$3,600
<b>311</b> Type R1; 3'-4" x 6'-11" irregular shape	1	EA	\$2,900.00	\$2,900
<b>312</b> Horizontal aluminum sun shades attached to CW/windows @ south elevation; allow	1,755	LF	\$175.00	NIC
<b>313</b> Blocking for openings	7,906	LF	\$8.00	\$63,248
<b>314</b> Window caulking	7,906	LF	\$3.00	\$23,718
<b>315</b> Add premium cost for translucent	360	SF	\$25.00	\$9,000
<b>316</b> Allow for premium cost for security glazing	614	SF	\$375.00	\$230,250
<b>317 B2020 EXTERIOR WINDOWS TOTAL</b>				<b>\$1,965,316</b>
<b>318</b>				
<b>319 B2030 EXTERIOR DOORS</b>				
<b>320</b> OH door, 12'-0" x 10'-6" motor operated @ Makerspace	1	EA	\$8,000.00	\$8,000
<b>321</b> Exterior HM doors; complete	45	LEAF		
<b>322</b> Type A, single	1	LEAF	\$1,800.00	\$1,800
<b>323</b> Type B1, single	5	LEAF	\$1,800.00	\$9,000
<b>324</b> Type B2, pair	9	PR	\$3,600.00	\$32,400
<b>325</b> Type B2, 10'-0" x 8'-6" @ Receiving	1	PR	\$5,000.00	\$5,000
<b>326</b> Aluminum entry doors including hardware	17	LEAF		
<b>327</b> Type SF1, single	7	LEAF	\$3,500.00	\$24,500
<b>328</b> Type SF2, pair	5	PR	\$7,000.00	\$35,000
<b>329</b> School guard premium	5	LVS	\$10,000.00	\$50,000
<b>330</b> Card reader	3	EA	\$3,500.00	\$10,500
<b>331</b> RDL; Remote door un/lock	16	EA	\$3,500.00	\$56,000
<b>332 B2030 EXTERIOR DOORS TOTAL</b>				<b>\$232,200</b>
<b>333</b>				
<b>334 TOTAL SYSTEM B20 EXTERIOR CLOSURE</b>				<b>\$7,294,209</b>
<b>335</b>				
<b>336</b>				
<b>337 B30 ROOFING</b>				
<b>338</b>				
<b>339 B3010 ROOF COVERINGS</b>				
<b>340</b>				
<b>341</b> Roofing				
<b>342</b> Rough carpentry/wood blocking to roof	5,138	LF	\$13.50	\$69,363
<b>343</b> Single-ply PVC membrane roofing system	65,518	SF		
<b>344</b> Type 1; Main roof, lower roof	36,386	SF	\$13.50	\$491,211
<b>345</b> Type 2; Gym	8,955	SF	\$13.50	\$120,893
<b>346</b> Type 3; Raised roof above Learning Commons	8,610	SF	\$13.50	\$116,235



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>347</b> Type 4; Entry walkway & Terrace	<b>1,216</b>	SF	\$13.50	\$16,409
<b>348</b> Type 5; Auditorium	<b>7,615</b>	SF	\$13.50	\$102,803
<b>349</b> Vertical roof membrane, 5'-6" h at raised roof	<b>2,736</b>	SF	\$14.50	\$39,672
<b>350</b> ½" roof cover board	<b>65,518</b>	SF	\$2.25	\$147,414
<b>351</b> 6" insulation	<b>65,518</b>	SF	\$2.50	\$163,794
<b>352</b> Vapor retarder	<b>65,518</b>	SF	\$1.50	\$98,276
<b>353</b> Add ½" fire rated roof board @ Auditorium, Gym & raised roof area over Learning Commons	<b>17,565</b>	SF	\$2.75	\$48,304
<b>354</b> Add 2 layers ½" fiber cement roof board @ Auditorium	<b>7,615</b>	SF	\$5.00	\$38,075
<b>355</b> Add acoustic insulation in flutes @ Auditorium & Gym roof deck	<b>16,570</b>	SF	\$1.50	\$24,855
<b>356</b> Precast concrete pavers over adjustable deck pedestal system @ roof type 4	<b>1,216</b>	SF	\$45.00	\$54,698
<b>357</b> Polycarbonate entrance canopy	<b>420</b>	SF	\$185.00	\$77,700
<b>358</b> Prefinished aluminum fascia/roof edge	<b>3,054</b>	LF	\$65.00	\$198,510
<b>359</b> Roof expansion joint	<b>1</b>	AL	\$25,000.00	\$25,000
<b>360</b>				
<b>361</b> <i>Roofing Accessories</i>				
<b>362</b> Miscellaneous roof accessories	<b>1</b>	LS	\$22,000.00	\$22,000
<b>363</b> Roof hatch	<b>2</b>	EA	\$3,000.00	\$6,000
<b>364</b> Paver walkway	<b>745</b>	SF	\$25.00	\$18,625
<b>365</b>				
<b>366</b> <i>Roof openings</i>				
<b>367</b> Glazed aluminum-framed skylight	<b>4,015</b>	SF	\$175.00	\$702,625
<b>368</b> <b>B3010 ROOF COVERINGS TOTAL</b>				<b>\$2,582,461</b>
<b>369</b>				
<b>370</b> <b>TOTAL SYSTEM B30 ROOFING</b>				<b>\$2,582,461</b>
<b>371</b>				
<b>372</b>				
<b>373</b> <b>C10 INTERIOR CONSTRUCTION</b>				
<b>374</b>				
<b>375</b> <b>C1010 PARTITIONS</b>				
<b>376</b> <u>04.00.00 Masonry</u>				
<b>377</b> 12" CMU wall reinforced; Gym & Auditorium, double hgt	<b>7,942</b>	SF	\$32.00	\$254,144
<b>378</b> 8" CMU wall, load bearing wall @ Auditorium	<b>1,284</b>	SF	\$24.00	\$30,816
<b>379</b> Stairs/elevator CMU wall	<b>3,266</b>	SF	\$24.00	\$78,384
<b>380</b>				
<b>381</b> <i>Gypsum board partitions</i>	<b>114,616</b>	SF		
<b>382</b> Type B3; 3 5/8" metal stud, 5/8" GWB	<b>203</b>	SF	\$7.20	\$1,462
<b>383</b> Type B4; same as type B3, add batt insulation	<b>5,145</b>	SF	\$8.70	\$44,762
<b>384</b> Type C2; 3 5/8" metal stud, 2x 5/8" GWB	<b>5,600</b>	SF	\$9.40	\$52,640
<b>385</b> Type C3; 3 5/8" metal stud, 2x 5/8" GWB, batt insulation	<b>6,483</b>	SF	\$10.90	\$70,665
<b>386</b> Type C4; same as type C3, add 1hr fire rated	<b>3,165</b>	SF	\$11.40	\$36,081



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>387</b> Type C6; 6" metal stud, 2x 5/8" GWB, batt insulation	<b>2,468</b>	SF	\$12.90	\$31,837
<b>388</b> Type C7; same as type C6, add 1hr fire rated	<b>5,507</b>	SF	\$13.40	\$73,794
<b>389</b> Type C8; 8" metal stud, 2x 5/8" GWB, batt insulation	<b>172</b>	SF	\$14.90	\$2,563
<b>390</b> Type C10; 10" metal stud, 2x 5/8" GWB, batt insulation	<b>222</b>	SF	\$16.90	\$3,752
<b>391</b> Type D3; 3 5/8" metal stud, 2x 5/8" GWB, batt insulation	<b>1,526</b>	SF	\$10.90	\$16,633
<b>392</b> Type D6; 6" metal stud, 2x 5/8" GWB, batt insulation	<b>1,266</b>	SF	\$12.90	\$16,331
<b>393</b> Type E3; 3 5/8" metal stud, 3x 5/8" GWB, batt insulation	<b>23,327</b>	SF	\$13.10	\$305,584
<b>394</b> Type E4; same as type E3, add 1hr fire rated	<b>780</b>	SF	\$13.60	\$10,608
<b>395</b> Type E6; 6" metal stud, 3x 5/8" GWB, batt insulation	<b>1,158</b>	SF	\$15.30	\$17,717
<b>396</b> Type E7; 10" metal stud, 3x 5/8" GWB, batt insulation	<b>1,022</b>	SF	\$19.30	\$19,725
<b>397</b> Type E8; 8" metal stud, 3x 5/8" GWB, batt insulation	<b>18,060</b>	SF	\$17.30	\$312,438
<b>398</b> Type E9; same as type E8, add 1hr fire rated	<b>2,710</b>	SF	\$17.80	\$48,238
<b>399</b> Type F1; 3 5/8" metal stud, 4x 5/8" GWB, batt insulation	<b>4,988</b>	SF	\$15.30	\$76,316
<b>400</b> Type F2; same as type F1, add 1hr fire rated	<b>1,834</b>	SF	\$15.80	\$28,977
<b>401</b> Type F6; 6" metal stud, 4x 5/8" GWB, batt insulation	<b>9,646</b>	SF	\$17.30	\$166,876
<b>402</b> Type F7; 8" metal stud, 4x 5/8" GWB, batt insulation	<b>227</b>	SF	\$19.30	\$4,381
<b>403</b> Type F8; same as type F7, add 1hr fire rated	<b>1,065</b>	SF	\$19.80	\$21,087
<b>404</b> Type H4; 4" metal C-H stud, 3x 5/8" GWB, batt insulation, 2hr rated	<b>67</b>	SF	\$15.10	\$1,012
<b>405</b> Type H6; 6" metal C-H stud, 3x 5/8" GWB, batt insulation, 2hr rated @ Elevator	<b>1,561</b>	SF	\$17.10	\$26,693
<b>406</b> Type J1; 2 x (3 5/8" metal stud, 5/8" GWB, batt insulation)	<b>6,552</b>	SF	\$17.40	\$114,005
<b>407</b> Type J2; same as type J1	<b>1,157</b>	SF	\$17.40	\$20,132
<b>408</b> Type K1; 2 x (3 5/8" metal stud, 2x5/8" GWB, batt insulation)	<b>6,245</b>	SF	\$21.80	\$136,141
<b>409</b> Type K2; same as type K1, add 1hr fire rated	<b>2,460</b>	SF	\$22.30	\$54,858
<b>410</b> High Impact GWB premium	<b>51,577</b>	SF	\$1.00	\$51,577
<b>411</b> Rough carpentry internal partitions and ceilings	<b>137,385</b>	GSF	\$1.25	\$171,731
<b>412</b> Misc metals for interior construction	<b>137,385</b>	GSF	\$1.25	\$171,731
<b>413</b>				
<b>414</b> Operable partition				
<b>415</b> Operable partitions	<b>5,440</b>	SF	\$90.00	\$489,600
<b>416</b> Operable partition framing support beam	<b>633</b>	LF	\$175.00	\$110,775
<b>417</b>				
<b>418</b> Interior windows				
<b>419</b> Interior	<b>5,215</b>	SF	\$55.00	\$286,825
<b>420</b> Glazed film	<b>4,332</b>	SF	\$60.00	\$259,920
<b>421</b> Ballistic glass sliding window @ Admin	<b>1</b>	EA	\$2,500.00	\$2,500
<b>422</b> Mirror frameless	<b>1,454</b>	SF	\$45.00	\$65,430
<b>423</b> Graduated glass; premium	<b>2,359</b>	SF	\$65.00	\$153,335
<b>424</b> Acoustical glass premium	<b>505</b>	SF	\$300.00	\$151,500
<b>425</b> Interior storefront				
<b>426</b> Storefront @ vestibule	<b>3,115</b>	SF	\$85.00	\$264,775
<b>427</b> Breakout Space-A, B & C; Glazed partition/wood panel closure	<b>3</b>	EA	\$125,000.00	\$375,000



**Fuller Middle School**

Framingham, MA  
137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>428</b> Interior penetration firestopping				
<b>429</b> Interior caulking	<b>137,385</b>	GSF	\$0.50	BP#2
<b>430</b> Top-of-partition firestopping	<b>137,385</b>	GSF	\$1.00	
<b>431</b> <b>C1010 PARTITIONS TOTAL</b>				<b>\$137,385</b>
<b>432</b>				<b>\$4,770,736</b>
<b>433</b> <b>C1020 INTERIOR DOORS, FRAMES &amp; HARDWARE</b>				
<b>434</b> <i>08 10 00 Hollow Metal Doors and Frames:</i>				
<b>435</b> Security gate 7'-0" x 7'-10", steel @ 1st Floor Corridors	<b>2</b>	EA	\$975.00	\$1,950
<b>436</b> <i>Hollow Metal Doors:</i>				
<b>437</b> type B1, single	<b>41</b>	EA	\$325.00	\$13,325
<b>438</b> type B2, pair	<b>6</b>	EA	\$650.00	\$3,900
<b>439</b> HM frames	<b>260</b>	EA	\$225.00	\$58,500
<b>440</b> HM frames for pair doors	<b>29</b>	EA	\$275.00	\$7,975
<b>441</b> <i>Wood Doors:</i>				
<b>442</b> type B1, single, wood	<b>91</b>	EA	\$325.00	\$29,575
<b>443</b> same as above w/applied surface both sides	<b>13</b>	EA	\$775.00	\$10,075
<b>444</b> type B1, 5'-0" x 26'-0" swinging panel @ AV rooms	<b>2</b>	EA	\$25,000.00	\$50,000
<b>445</b> type B2, pair, wood	<b>13</b>	EA	\$650.00	\$8,450
<b>446</b> type C1, single, wood w/full height glass	<b>111</b>	EA	\$400.00	\$44,400
<b>447</b> type C2, pair, w/full height glass	<b>9</b>	EA	\$800.00	\$7,200
<b>448</b> type C3, pair, w/vision panel 0'-5" x 6'-0"	<b>1</b>	EA	\$800.00	\$800
<b>449</b> Premium cost for acoustical doors	<b>40</b>	LOC	\$250.00	\$10,000
<b>450</b>				
<b>451</b> <i>Coiling drapery, security screen</i>				
<b>452</b> Cafeteria/Learning Commons; 21'-0" x 8'-0" (2 ea)	<b>336</b>	SF	\$55.00	\$18,480
<b>453</b> Kitchen; 40'-0" x 8'-0" (1 ea)	<b>320</b>	SF	\$55.00	\$17,600
<b>454</b> Admin area; 21'-0" x 5'-6" (1 ea)	<b>116</b>	SF	\$55.00	\$6,353
<b>455</b>				
<b>456</b> <i>Aluminum-Framed Entrances and Storefronts, interior</i>				
<b>457</b> type SF1, single, aluminum/glass	<b>3</b>	EA	\$2,500.00	\$7,500
<b>458</b> type SF2, pair, aluminum/glass	<b>2</b>	PR	\$5,000.00	\$10,000
<b>459</b> School guard doors, premium	<b>5</b>	LVS	\$10,000.00	\$50,000
<b>460</b>				
<b>461</b> <i>Access Doors and Frames</i>				
<b>462</b> Access doors	<b>100</b>	EA	\$300.00	\$30,000
<b>463</b>				
<b>464</b> Door sidelights	<b>900</b>	SF	\$55.00	\$49,500
<b>465</b> Glazing to doors	<b>1,554</b>	SF	\$55.00	\$85,470
<b>466</b>				
<b>467</b> Hardware	<b>318</b>	SET	\$750.00	\$238,500
<b>468</b> Powered door openers	<b>4</b>	LOC	\$3,500.00	\$14,000
<b>469</b> CR; Card reader	<b>15</b>	EA	\$3,000.00	\$45,000
<b>470</b> RDL; Remote door un/lock	<b>14</b>	EA	\$3,000.00	\$42,000



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>471</b> Paint door frames	<b>318</b>	EA	\$85.00	\$27,030
<b>472</b> Paint door	<b>318</b>	EA	\$65.00	\$20,670
<b>473</b>				
<b>474</b> Blocking at doors	<b>5,406</b>	LF	\$2.50	\$13,515
<b>475</b> Door Installation	<b>318</b>	EA	\$150.00	\$47,700
<b>476</b> <b>C1020 INTERIOR DOORS, FRAMES &amp; HARDWARE TOTAL</b>				<b>\$969,468</b>
<b>477</b>				
<b>478</b> <b>C1030 FITTINGS</b>				
<b>479</b> Miscellaneous metals for fittings	<b>137,385</b>	GSF	\$1.25	\$171,731
<b>480</b>				
<b>481</b> Tackboards	<b>2,688</b>	SF	\$18.00	\$48,384
<b>482</b> Markerboards	<b>5,376</b>	SF	\$25.00	\$134,400
<b>483</b> Tackable wall; allow	<b>3,000</b>	SF	\$18.00	\$54,000
<b>484</b>				
<b>485</b> Window stools - Solid surfacing material	<b>1,250</b>	LF	\$50.00	\$62,500
<b>486</b> Toilets				
<b>487</b> Vanity counter; Toilets	<b>319</b>	LF	\$200.00	\$63,800
<b>488</b> Vanity counter; Dressing	<b>33</b>	LF	\$200.00	\$6,600
<b>489</b> Folding panel shutter w/w/magnetic writable surface both side:	<b>40</b>	EA	\$1,000.00	\$40,000
<b>490</b>				
<b>491</b> <i>Signage</i>				
<b>492</b> Commemorative plaque	<b>2</b>	LOC	\$1,500.00	\$3,000
<b>493</b> Dimensional characters; School name	<b>1</b>	AL	\$5,000.00	\$5,000
<b>494</b> Plastic panel signs for room identification, way finding, hazard identification	<b>1</b>	AL	\$7,500.00	\$7,500
<b>495</b> Framed paper signs	<b>1</b>	AL	\$2,180.00	\$2,180
<b>496</b> Miscellaneous signage	<b>137,385</b>	GSF	\$0.50	\$68,693
<b>497</b>				
<b>498</b> <i>Wall &amp; corner guards</i>				
<b>499</b> Stainless steel corner guards	<b>1</b>	LS	\$10,000.00	\$10,000
<b>500</b>				
<b>501</b> <i>Toilet compartments (plastic laminate)</i>				
<b>502</b> Toilet compartments	<b>20</b>	EA	\$1,200.00	\$24,000
<b>503</b> Toilet compartments - ADA	<b>14</b>	EA	\$1,400.00	\$19,600
<b>504</b> Urinal screen	<b>20</b>	EA	\$800.00	\$16,000
<b>505</b>				
<b>506</b> <i>Lockers</i>				
<b>507</b> Athletic / PE lockers: metal 2-tier 30"h. x 15"w x 15"d	<b>50</b>	EA	\$250.00	\$12,500
<b>508</b> Kitchen staff lockers, single tier, 12" x 12" x 6' high	<b>6</b>	EA	\$250.00	\$1,500
<b>509</b> Student lockers 15"x12"x36" w/angled top, phenolic w/plam finish and wd veneer sides and back	<b>660</b>	EA	\$385.00	\$254,100
<b>510</b> Angles at lockers	<b>825</b>	LF	\$35.00	\$28,875
<b>511</b> <i>Toilet accessories</i>				



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>512</b> Combination PTD/WR unit	8	EA	\$150.00	\$1,200
<b>513</b> Towel dispenser/waste receptacle	45	EA	\$100.00	\$4,500
<b>514</b> Soap dispensers	45	EA	\$35.00	\$1,575
<b>515</b> Toilet paper dispensers	48	EA	\$65.00	\$3,120
<b>516</b> Sanitary napkin disposal units	21	EA	\$250.00	\$5,250
<b>517</b> Robe hook	15	EA	\$25.00	\$375
<b>518</b> Fold-down shower seat	1	EA	\$200.00	\$200
<b>519</b> Grab bars	28	PR	\$160.00	\$4,480
<b>520</b> Mirrors - in private bathrooms	14	EA	\$150.00	\$2,100
<b>521</b> Mop holder w/shelf (Janitors)	6	EA	\$180.00	\$1,080
<b>522</b>				
<b>523</b> <i>Fire extinguisher cabinets</i>				
<b>524</b> Fully recessed/non-rated	14	EA	\$450.00	\$6,182
<b>525</b> Semi-recessed/non-rated	6	EA	\$300.00	\$1,800
<b>526</b>				
<b>527</b> <i>Other fittings</i>				
<b>528</b> Wood cantilevered benches at classroom glazed partitions	42	EA	\$350.00	\$14,700
<b>529</b> Curtain track, carriers and curtains	2	EA	\$200.00	\$400
<b>530</b> <b>C1030 FITTINGS TOTAL</b>				<b>\$1,081,325</b>
<b>531</b>				
<b>532</b> <b>TOTAL SYSTEM C10 INTERIOR CONSTRUCTION</b>				<b>\$6,821,528</b>
<b>533</b>				
<b>534</b>				
<b>535</b> <b>C20 STAIRCASES</b>				
<b>536</b>				
<b>537</b> <b>C2010 STAIRCASES</b>				
<b>538</b> <i>Interior stairs</i>				
<b>539</b> Egress stairs	6	FLT	\$25,000.00	\$150,000
<b>540</b> Monumental/open stairs #4 & #5				BP#2
<b>541</b> Monumental/open stairs #3	1	FLT	\$65,000.00	\$65,000
<b>542</b>				
<b>543</b> <i>Stair finishes</i>				
<b>544</b> Railings	1	LS	\$150,000.00	\$150,000
<b>545</b> Linoleum treads & risers with rubber nosing	828	LFR	\$15.50	\$12,834
<b>546</b> Linoleum tile at landings	1,717	SF	\$8.00	\$13,736
<b>547</b> Monumental/open stairs	920	LFR	\$85.00	\$78,200
<b>548</b> <b>C2010 STAIRCASES TOTAL</b>				<b>\$469,770</b>
<b>549</b>				
<b>550</b> <b>TOTAL C20 STAIRCASES</b>				<b>\$469,770</b>
<b>551</b>				
<b>552</b>				
<b>553</b> <b>C30 INTERIOR FINISHES</b>				
<b>554</b>				



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>555 C3010 WALL FINISHES</b>				
<b>556 Auditorium walls:</b>				
<b>557</b> Plam wall panel to auditorium	<b>2,900</b>	SF	\$42.00	\$121,800
<b>558</b> FRP; fiber reinforced panels in Kitchen	<b>1,921</b>	SF	\$15.00	\$28,815
<b>559</b> Epoxy paint wainscot @ Locker/Toilet	<b>8,234</b>	SF	\$2.00	\$16,468
<b>560</b> Solid epoxy backsplash	<b>650</b>	SF	\$18.00	\$11,700
<b>561</b> Linoleum base	<b>12,630</b>	LF	\$7.00	\$88,410
<b>562</b> Metal trim detail	<b>12,630</b>	LF	\$8.00	\$101,040
<b>563</b> Vented rubber wall base	<b>375</b>	LF	\$3.00	\$1,125
<b>564</b> Metal trim detail	<b>375</b>	LF	\$5.00	\$1,875
<b>565</b> Exposed column covers; allowance	<b>1</b>	LS	\$35,000.00	\$35,000
<b>566</b> P.lam panel wall cover	<b>330</b>	SF	\$25.00	\$8,250
<b>567 Academic areas:</b>				
<b>568</b> Magnetic writing surface	<b>6,400</b>	SF	\$25.00	\$160,000
<b>569</b> Plam bumper w/HD wood marker tray	<b>2,915</b>	LF	\$90.00	\$262,350
<b>570</b> Maple rail	<b>1,600</b>	LF	\$30.00	\$48,000
<b>571</b> over curved gwb partition at curved wall	<b>3,156</b>	SF	\$27.50	\$86,790
<b>572</b> Fabric wrapped acoustic wall panels @ Music areas	<b>1,443</b>	SF	\$22.00	\$31,746
<b>573</b> sloped fabric wrapped acoustic panel	<b>8,359</b>	SF	\$24.50	\$204,796
<b>574</b> Cementitious wood fiber acoustical wall panel @ Gym	<b>6,255</b>	SF	\$15.00	\$93,825
<b>575</b> Mural panorama wall cover; angeled @ Media, Admin Install	<b>1,575</b>	SF	\$1.50	\$2,363
<b>576</b> Wall pads with cutout for MEH units; allow	<b>1</b>	AL	\$1,500.00	\$1,500
<b>577</b> Cafeteria fixed sound absorbing panel, wood fiber; allow	<b>2,000</b>	SF	\$25.00	\$50,000
<b>578</b> Wall panels at auditorium	<b>1,500</b>	SF	\$85.00	\$127,500
<b>579</b> Wall epoxy	<b>1,100</b>	SF	\$18.00	\$19,800
<b>580</b> Paint CMU wall	<b>12,492</b>	SF	\$1.10	\$13,741
<b>581</b> Paint drywall partitions	<b>273,034</b>	SF	\$0.95	\$259,382
<b>582 C3010 WALL FINISHES TOTAL</b>				<b>\$1,776,276</b>
<b>583</b>				
<b>584 C3020 FLOOR FINISHES</b>	<b>124,516</b>	<b>SF</b>		
<b>585</b> EP; epoxy flooring at Toilets	<b>7,940</b>	SF	\$15.00	\$119,100
<b>586</b> Quarry tile at Kitchen	<b>1,705</b>	SF	\$25.00	\$42,625
<b>587</b>				
<b>588 Flooring</b>				
<b>589</b> Acoustic underlayment under resilient flooring	<b>52,962</b>	SF	\$2.75	\$145,646
<b>590</b> LT; Linoleum tile flooring, 13" x 13"	<b>93,064</b>	SF	\$7.00	\$651,448
<b>591</b> LP; Plank linoleum flooring	<b>1,100</b>	SF	\$10.00	\$11,000
<b>592</b> Wood athletic flooring at Gym	<b>8,405</b>	SF	\$25.00	\$210,125
<b>593</b> Stage wood flooring: 4" hardboard assembly- recessed:	<b>1,590</b>	SF	\$30.50	\$48,495
<b>594</b> 1/4" double tempered smooth both sides hardboard				
<b>595</b> (2) layers 3/4" plywood on sleepers with insulation				
<b>596 Auditorium:</b>				
<b>597</b> slab on grade power troweled concrete at seats	<b>2,240</b>	SF	\$9.00	\$20,160





**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>598</b> carpet at aisles	<b>2,770</b>	SF	\$12.00	\$33,240
<b>599</b> PC; power troweled concrete @ Makerspace, Auditorium, AV	<b>2,018</b>	SF	\$9.00	BP#2
<b>600</b> <i>Painting</i>				
<b>601</b> SC; sealed concrete at back of house	<b>3,288</b>	SF	\$1.75	\$5,754
<b>602</b> <i>Entrance mats</i>				
<b>603</b> RG; Vestibule	<b>396</b>	SF	\$35.00	\$13,860
<b>604</b> <b>C3020 FLOOR FINISHES TOTAL</b>				<b>\$1,301,453</b>
<b>605</b>				
<b>606</b> <b>C3030 CEILING FINISHES</b>	<b>116,094</b>	SF		
<b>607</b> ACT ceilings at Corridors, Public, Admin areas, Teacher Pl	<b>50,004</b>	SF	\$5.00	\$250,020
<b>608</b> ACT ceiling, washable in kitchen	<b>1,705</b>	SF	\$5.25	\$8,951
<b>609</b> <i>Academic areas: classrooms, science, media, art, music, etc</i>				
<b>610</b> E1; Exposed deck, painted @ Classrooms	<b>24,380</b>	SF	\$1.50	\$36,570
<b>611</b> Circulation Corridors ceiling	<b>13,581</b>	SF	\$32.00	\$434,592
<b>612</b> GWB soffit, light cove	<b>1,320</b>	LF	\$35.00	\$46,200
<b>613</b> GWB ceiling/soffit in classrooms	<b>16,127</b>	SF	\$32.00	\$516,064
<b>614</b> A1; ACT - MR ceiling at Toilets	<b>6,869</b>	SF	\$5.75	\$39,498
<b>615</b> Sloped GWB soffit @ Art.	<b>175</b>	SF	\$18.00	\$3,150
<b>616</b> Lay in ACT ceiling at band/chorus	<b>4,550</b>	SF	\$5.00	\$22,750
<b>617</b> Auditorium ceiling; painted exposed metal deck	<b>6,600</b>	SF	\$2.50	\$16,500
<b>618</b> Suspended plam clouds	<b>4,950</b>	SF	\$55.00	\$272,250
<b>619</b> Gym ceiling; suspended lay in pre painted tegular edge tectum plank	<b>2,101</b>	SF	\$15.00	\$31,519
<b>620</b> B1; GWB ceiling @ Atrium	<b>6,402</b>	SF	\$15.00	\$96,030
<b>621</b> Gym exposed deck, painted	<b>8,405</b>	SF	\$2.00	\$16,810
<b>622</b> Paint	<b>137,385</b>	GSF	\$0.75	\$103,039
<b>623</b> Paint GWB ceilings w/high performance coating at Toilets	<b>30,893</b>	SF	\$1.10	\$33,983
<b>624</b> <b>C3030 CEILING FINISHES TOTAL</b>				<b>\$1,927,926</b>
<b>625</b>				
<b>626</b> <b>TOTAL SYSTEM C30 INTERIOR FINISHES</b>				<b>\$5,005,654</b>
<b>627</b>				
<b>628</b>				
<b>629</b> <b>D10 CONVEYING SYSTEMS</b>				
<b>630</b>				
<b>631</b> <b>D1010 CONVEYING SYSTEMS</b>				
<b>632</b> Elevators; 3,500#, 4 stops	<b>1</b>	EA	\$205,000.00	\$205,000
<b>633</b> Elevator pit ladder	<b>1</b>	EA	\$1,500.00	\$1,500
<b>634</b> Elevator vent	<b>1</b>	EA	\$1,200.00	\$1,200
<b>635</b> Sill angles	<b>4</b>	EA	\$175.00	\$700
<b>636</b> Hoist beam	<b>1</b>	EA	\$5,000.00	\$5,000
<b>637</b> <b>D1010 CONVEYING SYSTEMS TOTAL</b>				<b>\$213,400</b>
<b>638</b>				
<b>639</b> <b>TOTAL SYSTEM D10 CONVEYING SYSTEMS</b>				<b>\$213,400</b>



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b><u>DESCRIPTION</u></b>	<b><u>QUANTITY</u></b>	<b><u>UNIT</u></b>	<b><u>RATE/UNIT</u></b>	<b><u>TOTAL</u></b>
<b>640</b>				
<b>641</b>				
<b>642 D15 MECHANICAL</b>				
<b>643</b>				
<b>644 D20 PLUMBING</b>				
<b>645</b> 6" Water Service w/ sub metera	1	EA	\$9,500.00	\$9,500
<b>646</b> Hot Water Heater & Storage				
<b>647</b> - WH-1	1	EA	\$65,000.00	\$65,000
<b>648</b> - WH-2	1	EA	\$5,500.00	\$5,500
<b>649</b> Mixing Valves	1	EA	\$2,450.00	\$2,450
<b>650</b> Circulating Pumps	2	EA	\$1,050.00	\$2,100
<b>651</b> Expansion Tank	1	EA	\$2,200.00	\$2,200
<b>652</b> 4" Backflow Preventers	1	EA	\$5,560.00	\$5,560
<b>653</b> Pressure Reducing Station	1	EA	\$3,650.00	\$3,650
<b>654</b> 1" Backflow Preventers	2	EA	\$1,850.00	\$3,700
<b>655</b> Grease Interceptor System 8,000 gal	1	EA	\$48,500.00	\$48,500
<b>656</b> Grease Trap	1	EA	\$3,850.00	\$3,850
<b>657</b> Oily Water Separator	1	EA	\$4,580.00	\$4,580
<b>658</b> Acid Neutralization Tank	2	EA	By Others	\$0
<b>659</b> Condensate Pump:				
<b>660</b> - CP-1 5 GPH	1	EA	\$950.00	\$950
<b>661</b> Heat Tracing	1	LS	\$5,000.00	\$5,000
<b>662</b> Elevator Sump Pump:				
<b>663</b> - SP-1	1	EA	\$1,850.00	\$1,850
<b>664</b> Reducer Pressure Backflow Preventer:				
<b>665</b> - RBP-1	1	EA	\$2,500.00	\$2,500
<b>666</b> Emergency Gas Shut Off Valve	2	EA	\$1,250.00	\$2,500
<b>667</b> Fixtures				
<b>668</b> Water Closet P-1	20	EA	\$2,455.00	\$49,100
<b>669</b> Water Closet P-1A	31	EA	\$2,455.00	\$76,105
<b>670</b> Urinal P-2	17	EA	\$2,510.00	\$42,670
<b>671</b> Urinal P-2A	8	EA	\$2,510.00	\$20,080
<b>672</b> Lavatory P-3	49	EA	\$2,365.00	\$115,885
<b>673</b> Lavatory P-3A	28	EA	\$2,365.00	\$66,220
<b>674</b> Drinking Fountain P-4	11	EA	\$3,250.00	\$35,750
<b>675</b> Mop Sink P-5	5	EA	\$2,850.00	\$14,250
<b>676</b> Shower P-6	2	EA	\$3,850.00	\$7,700
<b>677</b> Science Room Sink P-7	40	EA	\$3,650.00	\$146,000
<b>678</b> Science Room Sink P-7A	2	EA	\$3,650.00	\$7,300
<b>679</b> Classroom Sink P-8	7	EA	\$2,565.00	\$17,955
<b>680</b> Art Sink P-9	3	EA	\$3,250.00	\$9,750
<b>681</b> Art Sink P-9A	1	EA	\$3,250.00	\$3,250
<b>682</b> Eyewash/Shower P-10	5	EA	\$2,250.00	\$11,250



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b><u>DESCRIPTION</u></b>	<b><u>QUANTITY</u></b>	<b><u>UNIT</u></b>	<b><u>RATE/UNIT</u></b>	<b><u>TOTAL</u></b>
<b>683</b> Fume Hood	3	EA	\$5,000.00	\$15,000
<b>684</b> Lab Equipment	1	LS	\$25,000.00	\$25,000
<b>685</b> labs & Consumer Science)	36	LS	\$385.00	\$13,860
<b>686</b> Floor Clean Outs:				
<b>687</b> - FCO-1	54	EA	\$725.00	\$39,150
<b>688</b> Floor Drains:				
<b>689</b> - 3" FD-A	14	EA	\$1,050.00	\$14,700
<b>690</b> - 3" FD-B	8	EA	\$1,065.00	\$8,520
<b>691</b> - 4" FD-B	5	EA	\$1,165.00	\$5,825
<b>692</b> Trap Primers	16	EA	\$1,250.00	\$20,000
<b>693</b> Roof Drain:				
<b>694</b> - 8 RD-0	2	EA	\$1,650.00	\$3,300
<b>695</b> - 6" RD-1	12	EA	\$1,410.00	\$16,920
<b>696</b> - 5" RD-2	4	EA	\$1,220.00	\$4,880
<b>697</b> - 4" RD-3	8	EA	\$1,010.00	\$8,080
<b>698</b> Cup Sinks	8	EA	\$1,850.00	\$14,800
<b>699</b> Wall Hydrant				
<b>700</b> - WHYD-1	18	EA	\$375.00	\$6,750
<b>701</b> Hose Bibbs:				
<b>702</b> - HB-1	12	EA	\$285.00	\$3,420
<b>703</b> VTR	9	EA	\$650.00	\$5,850
<b>704</b>				
<b>705</b> Storm piping, below grade:				
<b>706</b> - 12"	120	LF	\$125.00	\$15,000
<b>707</b> - 8"	50	LF	\$85.25	\$4,263
<b>708</b> - 6"	110	LF	\$62.55	\$6,881
<b>709</b> - 4"	40	LF	\$43.75	\$1,750
<b>710</b> Storm piping, above grade:				
<b>711</b> - 10"	155	LF	\$110.00	\$17,050
<b>712</b> - 8"	510	LF	\$92.35	\$47,099
<b>713</b> - 6"	1,010	LF	\$65.05	\$65,701
<b>714</b> - 4"	165	LF	\$45.10	\$7,442
<b>715</b> Waste and vent piping, below grade:				
<b>716</b> - 5"	650	LF	\$59.61	\$38,747
<b>717</b> - 4"	560	LF	\$43.75	\$24,500
<b>718</b> - 3"	265	LF	\$32.25	\$8,546
<b>719</b> - 2"	110	LF	\$26.85	\$2,954
<b>720</b> Waste and vent piping, above grade:				
<b>721</b> - 4"	685	LF	\$43.10	\$29,524
<b>722</b> - 3"	785	LF	\$31.55	\$24,767
<b>723</b> - 2"	850	LF	\$26.25	\$22,313
<b>724</b> Kitchen Waste Below grade:				
<b>725</b> - 4"	510	LF	\$32.00	\$16,320



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b><u>DESCRIPTION</u></b>	<b><u>QUANTITY</u></b>	<b><u>UNIT</u></b>	<b><u>RATE/UNIT</u></b>	<b><u>TOTAL</u></b>
<b>726</b> - 3"	<b>40</b>	LF	\$28.95	\$1,158
<b>727</b> - 2"	<b>290</b>	LF	\$22.50	\$6,525
<b>728</b> Acid Waste below grade:				
<b>729</b> - 4"	<b>425</b>	LF	\$32.00	\$13,600
<b>730</b> - 2"	<b>290</b>	LF	\$18.00	\$5,220
<b>731</b> Acid Waste below grade:				
<b>732</b> - 4"	<b>295</b>	LF	\$32.00	\$9,440
<b>733</b> - 3"	<b>210</b>	LF	\$28.25	\$5,933
<b>734</b> - 2"	<b>265</b>	LF	\$18.00	\$4,770
<b>735</b> Potable Water Piping:				
<b>736</b> - 2-1/2"	<b>620</b>	LF	\$48.95	\$30,349
<b>737</b> - 2"	<b>780</b>	LF	\$35.75	\$27,885
<b>738</b> - 1-1/2"	<b>550</b>	LF	\$30.45	\$16,748
<b>739</b> - 1-1/4"	<b>475</b>	LF	\$28.35	\$13,466
<b>740</b> - Branch	<b>8,500</b>	LF	\$25.75	\$218,875
<b>741</b> Insulate Potable Water Piping:				
<b>742</b> - 2-1/2"	<b>620</b>	LF	\$16.40	\$10,168
<b>743</b> - 2"	<b>780</b>	LF	\$15.65	\$12,207
<b>744</b> - 1-1/2"	<b>550</b>	LF	\$14.75	\$8,113
<b>745</b> - 1-1/4"	<b>475</b>	LF	\$14.05	\$6,674
<b>746</b> - Branch	<b>8,500</b>	LF	\$13.75	\$116,875
<b>747</b> Gas Piping				
<b>748</b> - 6"	<b>50</b>	LF	\$56.25	\$2,813
<b>749</b> - 4"	<b>80</b>	LF	\$48.95	\$3,916
<b>750</b> - 3"	<b>120</b>	LF	\$42.25	\$5,070
<b>751</b> - Branch	<b>980</b>	LF	\$29.65	\$29,057
<b>752</b> Gas Hook-ups	<b>4</b>	EA	\$850.00	\$3,400
<b>753</b> Master Gas Valves	<b>2</b>	EA	\$2,850.00	\$5,700
<b>754</b> Pump	<b>1</b>	LS	\$25,000.00	\$25,000
<b>755</b> Flues to water heater	<b>120</b>	LF	\$65.00	\$7,800
<b>756</b> Generator Gas Connection	<b>1</b>	EA	\$5,000.00	\$5,000
<b>757</b> Kitchen	<b>1</b>	LS	\$50,000.00	\$50,000
<b>758</b> Storm Piping Insulation	<b>1</b>	LS	\$25,000.00	\$25,000
<b>759</b> Seismic Restraints	<b>1</b>	LS	\$10,500.00	\$10,500
<b>760</b> Lift & Hoisting	<b>1</b>	LS	\$18,500.00	\$18,500
<b>761</b> General Requirements				
<b>762</b> Coring, cutting and sleeves	<b>1</b>	LS	\$15,000.00	\$15,000
<b>763</b> Commissioning	<b>1</b>	LS	\$25,000.00	\$25,000
<b>764</b> Valves and specialties	<b>1</b>	LS	\$12,500.00	\$12,500
<b>765</b> Permits & Fees	<b>1</b>	LS	\$7,850.00	\$7,850
<b>766</b> Test and sterilize	<b>1</b>	LS	\$18,500.00	\$18,500
<b>767</b> Shop drawings	<b>1</b>	LS	\$16,500.00	\$16,500
<b>768 D20 PLUMBING TOTAL</b>				<b>\$2,126,673</b>



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b><u>DESCRIPTION</u></b>	<b><u>QUANTITY</u></b>	<b><u>UNIT</u></b>	<b><u>RATE/UNIT</u></b>	<b><u>TOTAL</u></b>
<b>769</b>				
<b>770 D30 HVAC</b>				
<b>771 Boilers:</b>				
<b>772 - B-1 &amp; 2 3,844 MBH</b>	2	EA	\$84,568.00	\$169,136
<b>773 Expantion Tank:</b>				
<b>774 - ET-1 Thru 3</b>	3	EA	\$2,150.00	\$6,450
<b>775 Air Separator:</b>				
<b>776 - AS-1 &amp; 2 8"</b>	2	EA	\$3,950.00	\$7,900
<b>777 Buffer Tank:</b>				
<b>778 - BT-1</b>	1	EA	\$2,500.00	\$2,500
<b>779 Pumps:</b>				
<b>780 - P-1 &amp; 2 HP 790 GPM</b>	2	EA	\$12,500.00	\$25,000
<b>781 - P-3 &amp; 4 HP 800 GPM</b>	2	EA		Pump House
<b>782 - BP-1</b>	2	EA	\$2,500.00	\$5,000
<b>783 - CP-1 5 GPH</b>	5	EA	\$450.00	\$2,250
<b>784 Pumps House</b>	1	EA	\$185,000.00	\$185,000
<b>785</b>				
<b>786 Chillers:</b>				
<b>787 - CH-1 350 Ton</b>	1	EA	\$367,500.00	\$367,500
<b>788 Rooftop Units:</b>				
<b>789 - RTU-1 22,000 CFM</b>	1	EA	\$264,000.00	\$264,000
<b>790 - RTU-2 22,000 CFM</b>	1	EA	\$264,000.00	\$264,000
<b>791 - RTU-3 22,000 CFM</b>	1	EA	\$264,000.00	\$264,000
<b>792 - RTU-4 22,000 CFM</b>	1	EA	\$264,000.00	\$264,000
<b>793 - RTU-5 15,000 CFM</b>	1	EA	\$180,000.00	\$180,000
<b>794 - RTU-6 12,000 CFM</b>	1	EA	\$144,000.00	\$144,000
<b>795 - RTU-7 2,000 CFM</b>	1	EA	\$28,000.00	\$28,000
<b>796 Make Up Units:</b>				
<b>797 - MAU-1 5,000 CFM</b>	1	EA	\$32,500.00	\$32,500
<b>798 Exhaust Fans:</b>				
<b>799 - EF-1 2,500 CFM</b>	1	EA	\$3,250.00	\$3,250
<b>800 - EF-2 2,500 CFM</b>	1	EA	\$3,250.00	\$3,250
<b>801 - EF-3 500 CFM</b>	1	EA	\$980.00	\$980
<b>802 - EF-4 500 CFM</b>	1	EA	\$980.00	\$980
<b>803 - EF-5 250 CFM</b>	1	EA	\$685.00	\$685
<b>804 - EF-6 250 CFM</b>	1	EA	\$685.00	\$685
<b>805 - SEF-1 50,000 CFM</b>	1	EA	\$32,500.00	\$32,500
<b>806 - SEF-2 50,000 CFM</b>	1	EA	\$32,500.00	\$32,500
<b>807 - SEF-3 50,000 CFM</b>	1	EA	\$32,500.00	\$32,500
<b>808 - SEF-4 50,000 CFM</b>	1	EA	\$32,500.00	\$32,500
<b>809 - KEF-1 4,170 CFM</b>	1	EA	\$4,500.00	\$4,500
<b>810 - FEF-1 1,200 CFM</b>	1	EA	\$2,100.00	\$2,100
<b>811 - FEF-2 1,200 CFM</b>	1	EA	\$2,100.00	\$2,100



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>812</b> - FEF-3 1,200 CFM	1	EA	\$2,100.00	\$2,100
<b>813</b> VAV Boxes:				
<b>814</b> - VAV-8	150	EA	\$1,050.00	\$157,500
<b>815</b> Radiant Heat Panels:				
<b>816</b> - R1	2,525	LF	\$135.00	\$340,875
<b>817</b> Fin-Tube Radiators:				
<b>818</b> - FT-1	100	LF	\$90.00	\$9,000
<b>819</b> Cabinet & Unit Heaters:				
<b>820</b> - CUH-1,2, 7 thru 16 350 MBH	12	EA	\$895.00	\$10,740
<b>821</b> - CUH-3 1050 MBH	1	EA	\$1,150.00	\$1,150
<b>822</b> - CUH-4 thru 6 450 MBH	3	EA	\$925.00	\$2,775
<b>823</b> Ductless Split Units:				
<b>824</b> - DCUe-1 1 Ton	1	EA	\$2,950.00	\$2,950
<b>825</b> - DCUe-2 2 Ton	1	EA	\$4,425.00	\$4,425
<b>826</b> - DCUe-3 2 Ton	1	EA	\$4,425.00	\$4,425
<b>827</b> - DCUe-4 1.5 Ton	1	EA	\$3,850.00	\$3,850
<b>828</b> - DCUe-5 1.5 Ton	1	EA	\$3,850.00	\$3,850
<b>829</b> - DCUe-6 1.5 Ton	1	EA	\$3,850.00	\$3,850
<b>830</b> - DCUe-7 1.5 Ton	1	EA	\$3,850.00	\$3,850
<b>831</b> Register & Diffusers:				
<b>832</b> - DD-1	22	EA	\$985.00	\$21,670
<b>833</b> - DD-2	18	EA	\$985.00	\$17,730
<b>834</b> - DD-3	16	EA	\$985.00	\$15,760
<b>835</b> - DD-4	1	EA	\$985.00	\$985
<b>836</b> - DD-5	42	EA	\$985.00	\$41,370
<b>837</b> - DD-6	2	EA	\$985.00	\$1,970
<b>838</b> - DD-7	4	EA	\$985.00	\$3,940
<b>839</b> - Slot	750	LF	\$45.00	\$33,750
<b>840</b> - E	80	EA	\$225.00	\$18,000
<b>841</b> Misc Diffusers, grills and registers	1	LS	\$5,000.00	\$5,000
<b>842</b> Fire & Motor Dampers	30	LS	\$1,850.00	\$55,500
<b>843</b> Volume Dampers	1	EA	\$40,000.00	\$40,000
<b>844</b> Flex Duct	1	LS	\$30,000.00	\$30,000
<b>845</b> Misc. Duct Accessories	1	LS	\$25,000.00	\$25,000
<b>846</b> Double Wall Galvanized Duct (Auditorium)	8,500	LBS	\$20.25	\$172,125
<b>847</b> Galvanized Duct	130,000	LBS	\$12.50	\$1,625,000
<b>848</b> Ductsox	680	LF	\$45.00	\$30,600
<b>849</b> Duct Insulation	45,000	SF	\$4.65	\$209,250
<b>850</b> Duct Insulation @ Kitchen area	1	LS	\$35,000.00	\$35,000
<b>851</b> Black iron at kitchen	2,125	LBS	\$18.50	\$39,313
<b>852</b> Duct S/S	5,000	LBS	\$20.20	\$101,000
<b>853</b> Seal Ductwork	7,500	LF	\$1.60	\$12,000
<b>854</b> Dust Collection System	1	LS	\$25,000.00	\$25,000



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b><u>DESCRIPTION</u></b>	<b><u>QUANTITY</u></b>	<b><u>UNIT</u></b>	<b><u>RATE/UNIT</u></b>	<b><u>TOTAL</u></b>
<b>855</b> Sound Attenuators				
<b>856</b> - SA-1S	1	EA	\$6,500.00	\$6,500
<b>857</b> - SA-1R	1	EA	\$6,500.00	\$6,500
<b>858</b> - SA-2S	1	EA	\$6,500.00	\$6,500
<b>859</b> - SA-2R	1	EA	\$6,500.00	\$6,500
<b>860</b> - SA-3S	1	EA	\$6,500.00	\$6,500
<b>861</b> - SA-3R	1	EA	\$6,500.00	\$6,500
<b>862</b> - SA-4S	1	EA	\$6,500.00	\$6,500
<b>863</b> - SA-4R	1	EA	\$6,500.00	\$6,500
<b>864</b> - SA-5S	1	EA	\$6,500.00	\$6,500
<b>865</b> - SA-5R	1	EA	\$6,500.00	\$6,500
<b>866</b> - SA-6S	1	EA	\$7,800.00	\$7,800
<b>867</b> - SA-6R	1	EA	\$6,200.00	\$6,200
<b>868</b> - SA-7S	1	EA	\$3,850.00	\$3,850
<b>869</b> - SA-7R	1	EA	\$3,850.00	\$3,850
<b>870</b> - SA-8	1	EA	\$4,250.00	\$4,250
<b>871</b> Hot & Chilles Water Piping				
<b>872</b> - Large Bore	9,000	LF	\$40.00	\$360,000
<b>873</b> - Small Bore	10,500	LF	\$28.00	\$294,000
<b>874</b> Insulate Hot Water Piping				
<b>875</b> - Large Bore	9,000	LF	\$16.95	\$152,550
<b>876</b> - Small Bore	10,500	LF	\$12.50	\$131,250
<b>877</b> Equipment Hook-Ups:				
<b>878</b> - 4" Boilers	2	EA	\$8,950.00	\$17,900
<b>879</b> - 8" Pump		EA		Pump House
<b>880</b> - 4" Pump	3	EA	\$2,100.00	\$6,300
<b>881</b> - 8" Chiller	1	EA	\$14,500.00	\$14,500
<b>882</b> - RCP	95	EA	\$1,075.00	\$102,125
<b>883</b> - CUH	12	EA	\$1,025.00	\$12,300
<b>884</b> - FT	2	EA	\$1,075.00	\$2,150
<b>885</b> - DD	105	EA	\$285.00	\$29,925
<b>886</b> - VAV	140	EA	\$1,105.00	\$154,700
<b>887</b> - 4" RTU Coils	6	EA	\$6,500.00	\$39,000
<b>888</b> - 2" RTU Coils	3	EA	\$2,650.00	\$7,950
<b>889</b> VFD	1	LS	\$20,000.00	\$20,000
<b>890</b> Glycol:				
<b>891</b> - GF-1 & 2	2	EA	\$6,500.00	\$13,000
<b>892</b> Combustion	1	LS	\$30,000.00	\$30,000
<b>893</b> Flues S/S boiler	380	LF	\$120.00	\$45,600
<b>894</b> Seismic Restraints	1	LS	\$10,500.00	\$10,500
<b>895</b> Misc. Valves & specialties	1	LS	\$15,000.00	\$15,000
<b>896</b> Commissioning support	1	LS	\$32,000.00	\$32,000
<b>897</b> Controls	1	LS	\$755,000.00	\$755,000



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>898</b> Testing & Balancing	1	LS	\$35,600.00	\$35,600
<b>899</b> Rigging & Lifting	1	LS	\$12,500.00	\$12,500
<b>900</b> Permits & Fees	1	LS	\$8,500.00	\$8,500
<b>901</b> Shop Drawing	1	LS	\$15,500.00	\$15,500
<b>902</b> <b>D30 HVAC TOTAL</b>				<b>\$7,879,869</b>
<b>903</b>				
<b>904</b> <b>D40 FIRE PROTECTION</b>				
<b>905</b> Upright Sprinkler Heads	260	EA	\$390.00	\$101,400
<b>906</b> Pendent Sprinkler Heads	817	EA	\$415.00	\$339,055
<b>907</b> Pendent/Upright Sprinkler Heads	120	EA	\$510.00	\$61,200
<b>908</b> Upright Sprinkler Heads ( Gym)	70	EA	\$425.00	\$29,750
<b>909</b> Upright Sprinkler Heads ( Auditorium)	40	EA	\$425.00	\$17,000
<b>910</b> Upright Sprinkler Heads ( Skylights)	16	EA	\$440.00	\$7,040
<b>911</b> Sidewall Sprinkler Heads	121	EA	\$514.00	\$62,194
<b>912</b> Window Sprinkler Heads	22	EA	\$650.00	\$14,300
<b>913</b> Dry Sprinkler Heads	16	EA	\$495.00	\$7,920
<b>914</b> 8" Water Service	1	EA	\$6,250.00	\$6,250
<b>915</b> 6" Alarm Valves w/ trim	1	EA	\$5,560.00	\$5,560
<b>916</b> 6" Backflow Preventer	1	EA	\$8,500.00	\$8,500
<b>917</b> Zone control w/ standpipe (SCVA)	14	EA	\$3,650.00	\$51,100
<b>918</b> 6" Riser Valves	2	EA	\$950.00	\$1,900
<b>919</b> 6" FSP W/ Standpipe	5	EA	\$2,250.00	\$11,250
<b>920</b> 4" FSP W/ Standpipe	3	EA	\$2,045.00	\$6,135
<b>921</b> Fire Dept. Connections	1	EA	\$2,650.00	\$2,650
<b>922</b> Riser Valve w/ tamper switch	2	EA	\$750.00	\$1,500
<b>923</b> Main piping:				
<b>924</b> - 6"	1,108	LF	\$80.00	\$88,640
<b>925</b> Misc. Valves	1	LS	\$4,500.00	\$4,500
<b>926</b> Commissioning	1	LS	\$1,250.00	\$1,250
<b>927</b> Lifting	1	LS	\$3,800.00	\$3,800
<b>928</b> Testing	1	LS	\$3,650.00	\$3,650
<b>929</b> Coordination	1	LS	\$8,100.00	\$8,100
<b>930</b> Coring, Sleeves & sleeves	1	LS	\$5,450.00	\$5,450
<b>931</b> Seismic Restraints	1	LS	\$5,900.00	\$5,900
<b>932</b> Shop drawings/hydraulic calculations	1	LS	\$8,000.00	\$8,000
<b>933</b> <b>D40 FIRE PROTECTION TOTAL</b>				<b>\$863,994</b>
<b>934</b>				
<b>935</b> <b>TOTAL SYSTEM D15 MECHANICAL</b>				<b>\$10,870,535</b>
<b>936</b>				
<b>937</b>				
<b>938</b> <b>D50 ELECTRICAL</b>				
<b>939</b>				
<b>940</b> <b>D5011 SERVICE &amp; DISTRIBUTION</b>				





**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>941</b> <i>Switchgear, Panelboards, Transformers</i>				
<b>942</b> 3000/2500 Amp Main Switchboard	1	LS	\$110,739.20	\$110,739
<b>943</b> Meter Pan	1	EA	\$738.10	\$738
<b>944</b> SPD @ Swbd	1	EA	\$2,855.60	\$2,856
<b>945</b> SPD @ Panelboard	46	EA	\$1,113.20	\$51,207
<b>946</b> 100 Amp Panel Board	14	EA	\$4,048.66	\$56,681
<b>947</b> 225 Amp Panel Board	9	EA	\$6,749.38	\$60,744
<b>948</b> 225 Amp Panel Board, 2-Section	9	EA	\$11,521.62	\$103,695
<b>949</b> 400 Amp Panel Board	4	EA	\$9,571.10	\$38,284
<b>950</b> 400 Amp Panel Board, 2-Section	1	EA	\$16,443.90	\$16,444
<b>951</b> 600 Amp Panel Board	2	EA	\$13,013.55	\$26,027
<b>952</b> 800 Amp Panel Board	2	EA	\$16,577.00	\$33,154
<b>953</b> 75 Kva Transformer	1	EA	\$7,550.40	\$7,550
<b>954</b> 225 Kva Transformer K13	3	EA	\$42,713.00	\$128,139
<b>955</b> 800 Amp Disconnect @ Xfmr	2	EA	\$7,381.00	\$14,762
<b>956</b> Emergency Generator, UPS				
<b>957</b> 350 Kw Emergency Generator, WP/Sound	1	LS	\$147,862.00	\$147,862
<b>958</b> Autotransfer Sw 150A	1	EA	\$7,148.08	\$7,148
<b>959</b> Autotransfer Sw 225A	1	EA	\$10,145.85	\$10,146
<b>960</b> Autotransfer Sw 400A	1	EA	\$12,541.65	\$12,542
<b>961</b> 150 Amp EG Quick Connect	1	EA	\$3,049.20	\$3,049
<b>962</b> 200/150 Amp Encl Ckt Brkr	1	EA	\$1,923.90	\$1,924
<b>963</b> 225 Amp Encl Ckt Brkr	1	EA	\$3,693.53	\$3,694
<b>964</b> 400 Amp Encl Ckt Brkr	1	EA	\$4,283.40	\$4,283
<b>965</b> 24KW/30Kva UPS, batteries	2	LS	\$47,432.00	\$94,864
<b>966</b> 200 Amp Disconnect @ UPS	2	EA	\$1,923.90	\$3,848
<b>967</b> Generator Annunciator	1	EA	\$1,621.40	\$1,621
<b>968</b> Motors:				
<b>969</b> Cond Pump Conn	12	EA	\$157.30	\$1,888
<b>970</b> Install Limit Switch FBO	3	EA	\$121.00	\$363
<b>971</b> Install Misc Gym CP FBO	8	EA	\$465.85	\$3,727
<b>972</b> Motor Backbd Conn's, Switch	8	EA	\$779.24	\$6,234
<b>973</b> Scoreboard Conn's, Switch	1	EA	\$779.24	\$779
<b>974</b> Bleach Motor 20/3A Conn, Switch	7	EA	\$779.24	\$5,455
<b>975</b> Manual Snap Switch Starter WP	5	EA	\$338.80	\$1,694
<b>976</b> 20/2 Amp Disconnect	19	EA	\$444.07	\$8,437
<b>977</b> 30/1 Amp Disconnect, Elev Cab	1	EA	\$444.07	\$444
<b>978</b> 30/2 Amp Disconnect, mech	8	EA	\$584.43	\$4,675
<b>979</b> 30 Amp Disconnect, mech,kit	16	EA	\$779.24	\$12,468
<b>980</b> 60 Amp Disconnect, mech, kit	5	EA	\$1,333.42	\$6,667
<b>981</b> 100 Amp Disconnect	6	EA	\$1,452.00	\$8,712
<b>982</b> 200 Amp Disconnect, Elev	1	EA	\$2,214.30	\$2,214
<b>983</b> 200/125 Amp Disconnect WP	4	EA	\$2,214.30	\$8,857
<b>984</b> 200/175 Amp Disconnect WP	4	EA	\$2,214.30	\$8,857
<b>985</b> 800 Amp Disconnect CH, WP	1	EA	\$8,845.10	\$8,845
<b>986</b> Junc Box, mech controls by others	13	EA	\$66.55	\$865



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>987</b> Install Nema 0 Motor Starter FBO	<b>11</b>	EA	\$356.95	\$3,926
<b>988</b> Install Nema 1 Motor Starter FBO	<b>2</b>	EA	\$471.90	\$944
<b>989</b> Install <=10HP VFD FBO	<b>5</b>	EA	\$1,367.30	\$6,837
<b>990</b> Install 20HP VFD FBO	<b>2</b>	EA	\$2,081.20	\$4,162
<b>991</b> Install 25HP VFD FBO	<b>2</b>	EA	\$2,734.60	\$5,469
<b>992</b> Install 50HP VFD FBO	<b>4</b>	EA	\$3,448.50	\$13,794
<b>993</b> Chiller CP Conn's	<b>1</b>	EA	\$3,726.80	\$3,727
<b>994</b>				
<b>995</b> Power Circuitry				
<b>996</b> 3/4" Emt, empty	<b>520</b>	LF	\$10.61	\$5,518
<b>997</b> 3/4" Emt, 4#12	<b>4,760</b>	LF	\$13.85	\$65,924
<b>998</b> 3/4" Emt, 4#10	<b>2,880</b>	LF	\$14.98	\$43,149
<b>999</b> 1" Emt, 4#8	<b>600</b>	LF	\$21.47	\$12,879
<b>1000</b> 1 1/4" Emt, 4#4	<b>200</b>	LF	\$29.05	\$5,810
<b>1001</b> 1 1/4" Emt, 4#2	<b>2,790</b>	LF	\$32.34	\$90,238
<b>1002</b> 1 1/2" Emt, 4#1	<b>850</b>	LF	\$38.81	\$32,990
<b>1003</b> 2" Emt, 4 1/0	<b>930</b>	LF	\$44.39	\$41,287
<b>1004</b> 2" Emt, 4 2/0	<b>800</b>	LF	\$48.07	\$38,459
<b>1005</b> 2" Emt, 4 3/0	<b>200</b>	LF	\$53.49	\$10,699
<b>1006</b> 2 1/2" Emt, 4 4/0	<b>80</b>	LF	\$62.02	\$4,962
<b>1007</b> 2 1/2" Emt, 4 250Mcm	<b>60</b>	LF	\$66.48	\$3,989
<b>1008</b> 3" Emt, 4 350Mcm	<b>420</b>	LF	\$81.49	\$34,227
<b>1009</b> 3 1/2" Emt, 4 500 Mcm	<b>1,820</b>	LF	\$105.02	\$191,129
<b>1010</b> 4#6 MI Cable	<b>50</b>	LF	\$41.27	\$2,064
<b>1011</b> 4#2 MI Cable	<b>200</b>	LF	\$83.99	\$16,797
<b>1012</b>				
<b>1013</b> Service Grounding	<b>1</b>	LS	\$5,033.60	\$5,034
<b>1014</b> Lightning Protection System (Preventor)	<b>1</b>	LS	\$34,485.00	\$34,485
<b>1015</b>				
<b>1016</b> Light Fixtures				
<b>1017</b> Type G4	<b>80</b>	EA	\$886.93	\$70,954
<b>1018</b> Type LK24	<b>24</b>	EA	\$474.32	\$11,384
<b>1019</b> Type LP8	<b>9</b>	EA	\$1,185.80	\$10,672
<b>1020</b> Type LR2	<b>1,173</b>	EA	\$411.40	\$482,572
<b>1021</b> Type LS2	<b>1</b>	EA	\$411.40	\$411
<b>1022</b> Type LS4	<b>41</b>	EA	\$310.97	\$12,750
<b>1023</b> Type LS4A	<b>22</b>	EA	\$310.97	\$6,841
<b>1024</b> Type LS8	<b>21</b>	EA	\$621.94	\$13,061
<b>1025</b> Type LUL	<b>61</b>	EA	\$310.97	\$18,969
<b>1026</b> Type PC1	<b>24</b>	EA	\$381.15	\$9,148
<b>1027</b> Type PC2	<b>29</b>	EA	\$381.15	\$11,053
<b>1028</b> Type PC3	<b>186</b>	EA	\$381.15	\$70,894
<b>1029</b> Type RC1	<b>88</b>	EA	\$381.15	\$33,541
<b>1030</b> Type RC2	<b>56</b>	EA	\$381.15	\$21,344
<b>1031</b> Type RSH	<b>1</b>	EA	\$393.25	\$393
<b>1032</b> Type SP1	<b>83</b>	EA	\$617.10	\$51,219



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>1033</b> Type SL4 Exterior Wallpack	17	EA	\$701.80	\$11,931
<b>1034</b> Type Exit	71	EA	\$332.75	\$23,625
<b>1035</b> Type LC2	72	LF	\$114.35	\$8,233
<b>1036</b> Type LC3	3,090	LF	\$114.35	\$353,326
<b>1037</b> Type LWS	624	LF	\$124.03	\$77,392
<b>1038</b> Type LSL	60	LF	\$130.08	\$7,805
<b>1039</b>				
<b>1040</b> Branch Circuitry				
<b>1041</b> 3/4" Emt, 4#12	15,624	LF	\$12.65	\$197,635
<b>1042</b> MC Cable	46,871	LF	\$5.18	\$242,733
<b>1043</b> 3/4" Emt, 4#10	880	LF	\$16.66	\$14,662
<b>1044</b> 1" Emt, 4#8	60	LF	\$21.47	\$1,288
<b>1045</b> 1" Emt, 4#6	160	LF	\$22.87	\$3,659
<b>1046</b> Plenum Cable	9,930	LF	\$1.59	\$15,740
<b>1047</b>				
<b>1048</b> Wiring Devices				
<b>1049</b> Switches	11	EA	\$78.65	\$865
<b>1050</b> Momentary Contact Switches	9	EA	\$124.03	\$1,116
<b>1051</b> OS, PS Power Pack	145	EA	\$181.50	\$26,318
<b>1052</b> Local Switch/Dimming Station L	226	EA	\$151.25	\$34,183
<b>1053</b> Occupancy Sensor	322	EA	\$202.68	\$65,261
<b>1054</b> Photo Sensor	114	EA	\$202.68	\$23,105
<b>1055</b> Receptacles	512	EA	\$78.65	\$40,269
<b>1056</b> Junc Boxes, Misc	5	EA	\$64.13	\$321
<b>1057</b> Receptacles GFI	217	EA	\$96.80	\$21,006
<b>1058</b> Receptacles Quad	317	EA	\$129.47	\$41,042
<b>1059</b> Receptacles GFI Quad	5	EA	\$159.72	\$799
<b>1060</b> Receptacles GFI WP	24	EA	\$177.87	\$4,269
<b>1061</b> Receptacles w/ I/O Module	28	EA	\$96.80	\$2,710
<b>1062</b> Receptacles Quad w/ I/O Modules	3	EA	\$181.50	\$545
<b>1063</b> Receptacle USB	13	EA	\$102.85	\$1,337
<b>1064</b> Cord Reel Receptacle	7	EA	\$580.80	\$4,066
<b>1065</b> Cond Pump Conn	12	EA	\$133.10	\$1,597
<b>1066</b> Install Leak Det FBO	12	EA	\$121.00	\$1,452
<b>1067</b> Sol Valve Conn	2	EA	\$121.00	\$242
<b>1068</b> FS Conn	7	EA	\$121.00	\$847
<b>1069</b> GSM Conn	7	EA	\$121.00	\$847
<b>1070</b> Floor Power Outlet	2	EA	\$399.30	\$799
<b>1071</b> 4-Pole Lighting Contactor	1	EA	\$635.25	\$635
<b>1072</b> 12-Pole Lighting Contactor	1	EA	\$1,500.40	\$1,500
<b>1073</b> EPO Pushbutton	3	EA	\$229.90	\$690
<b>1074</b> Fume Hood Conn	3	EA	\$157.30	\$472
<b>1075</b> Manual Snap Switch Starter VRF, VAV,misc	177	EA	\$181.50	\$32,126
<b>1076</b> 20/1 Amp Receptacle L5-20	11	EA	\$84.70	\$932
<b>1077</b> 20/1 Amp Eqpt Conn	12	EA	\$66.55	\$799
<b>1078</b> 30/1 Amp Receptacle L5-30	11	EA	\$117.98	\$1,298



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>1079</b> 30 Amp Receptacle	3	EA	\$130.08	\$390
<b>1080</b> 30 Amp Stage Receptacle / strip conn	8	EA	\$798.60	\$6,389
<b>1081</b> 50 Amp Receptacle	1	EA	\$193.60	\$194
<b>1082</b> 60 Amp Receptacle, weld	2	EA	\$205.70	\$411
<b>1083</b>				
<b>1084</b> Fire Alarm				
<b>1085</b> Teflon Cable	33,345	LF	\$2.34	\$78,113
<b>1086</b> 3" Rigid, Riser Cables	60	LF	\$114.95	\$6,897
<b>1087</b> Pull Station	24	EA	\$229.90	\$5,518
<b>1088</b> Audible/Visual	205	EA	\$347.88	\$71,314
<b>1089</b> Audible/Visual WP	1	EA	\$405.35	\$405
<b>1090</b> Smoke Detector	158	EA	\$387.20	\$61,178
<b>1091</b> CO Detector	5	EA	\$350.90	\$1,755
<b>1092</b> Beam-Type Smoke Detector	11	EA	\$1,052.70	\$11,580
<b>1093</b> Strobe	51	EA	\$229.90	\$11,725
<b>1094</b> WP Beacon	2	EA	\$287.38	\$575
<b>1095</b> Duct Detector	40	EA	\$889.35	\$35,574
<b>1096</b> Central Equipment, testing, Voice Command	1	LS	\$66,477.40	\$66,477
<b>1097</b> Radio Box, Antenna, wiring	1	EA	\$4,549.60	\$4,550
<b>1098</b> Fused Disc	1	EA	\$738.10	\$738
<b>1099</b> Door Release DH	6	EA	\$459.80	\$2,759
<b>1100</b> Ansul Conn's	1	LS	\$895.40	\$895
<b>1101</b> Remote Mic EVAC	1	EA	\$580.80	\$581
<b>1102</b> Annunciator Panel	3	EA	\$2,323.20	\$6,970
<b>1103</b> Misc Connections, Relays	25	EA	\$272.25	\$6,806
<b>1104</b> Knox Box	1	EA	\$520.30	\$520
<b>1105</b>				
<b>1106</b> Communications System				
<b>1107</b> MDF Rack, PP's, Terms	1	EA	\$14,762.00	\$14,762
<b>1108</b> IDF Rack, PP's, Terms	3	EA	\$7,381.00	\$22,143
<b>1109</b> 4" Floor Sleeves	16	EA	\$229.90	\$3,678
<b>1110</b> 4" Wall Sleeves	16	EA	\$229.90	\$3,678
<b>1111</b> Main Ground Bar	1	EA	\$1,476.20	\$1,476
<b>1112</b> Tel Ground Bar	3	EA	\$738.10	\$2,214
<b>1113</b> #3/0G Wire	600	LF	\$9.19	\$5,511
<b>1114</b> Cable Tray 24" Alum	1,570	LF	\$41.62	\$65,350
<b>1115</b> 12 Strand Multi-Mode Fiber	600	LF	\$6.18	\$3,710
<b>1116</b> 6 Strand Multi-Mode Fiber	600	LF	\$4.30	\$2,577
<b>1117</b> Cu Distr Cable	600	LF	\$10.29	\$6,171
<b>1118</b> 1" EMT CDT	172	LF	\$14.40	\$2,477
<b>1119</b> 2" EMT CDT	1,040	LF	\$22.90	\$23,819
<b>1120</b> 4" EMT Cdt	200	LF	\$34.64	\$6,928
<b>1121</b> Cat 6 Cable	103,500	LF	\$1.59	\$164,058
<b>1122</b> WAP Outlet AN 2c	14	EA	\$89.54	\$1,254
<b>1123</b> Tel Outlet	60	EA	\$72.60	\$4,356



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b><u>DESCRIPTION</u></b>	<b><u>QUANTITY</u></b>	<b><u>UNIT</u></b>	<b><u>RATE/UNIT</u></b>	<b><u>TOTAL</u></b>
<b>1124</b> Data Outlet	2	EA	\$72.60	\$145
<b>1125</b> Data Duplex Outlet 2c	78	EA	\$89.54	\$6,984
<b>1126</b> Tel/Data Outlet 3c	76	EA	\$111.93	\$8,506
<b>1127</b> Floor Tel/Data Outlet 3c	6	EA	\$399.30	\$2,396
<b>1128</b> Tel/Data Outlet T 2c	47	EA	\$89.54	\$4,208
<b>1129</b> TVE 2c	50	EA	\$169.40	\$8,470
<b>1130</b> TVC 2c	2	EA	\$169.40	\$339
<b>1131</b>				
<b>1132</b> Clock/ Public Address System:				
<b>1133</b> 2 1/2" Emt, Riser Cables	50	LF	\$66.74	\$3,337
<b>1134</b> 3/4" EMT Cdt	2,730	LF	\$11.93	\$32,571
<b>1135</b> 1" EMT Cdt	2,530	LF	\$14.40	\$36,429
<b>1136</b> Comm Cable	14,100	LF	\$1.59	\$22,350
<b>1137</b> Main Sound Rack	1	LS	\$48,884.00	\$48,884
<b>1138</b> Local Sound System Rack	2	EA	\$7,792.40	\$15,585
<b>1139</b> Outlet S Speaker	232	EA	\$254.10	\$58,951
<b>1140</b> Outlet S Speaker WP	19	EA	\$344.85	\$6,552
<b>1141</b> Volume Control	26	EA	\$181.50	\$4,719
<b>1142</b> Master Clock GPS	1	EA	\$5,493.40	\$5,493
<b>1143</b> Clock Antenna	1	EA	\$1,863.40	\$1,863
<b>1144</b> Wireless Clock Transceiver	1	EA	\$2,855.60	\$2,856
<b>1145</b> Wireless Clock Repeater	4	EA	\$1,427.80	\$5,711
<b>1146</b> Clock, wireless	73	EA	\$254.10	\$18,549
<b>1147</b>				
<b>1148</b> A/V System:				
<b>1149</b> 1" EMT Cdt	1,600	LF	\$14.40	\$23,038
<b>1150</b> BP Button Panel	41	EA	\$99.83	\$4,093
<b>1151</b> R1 Receptacle Panel	41	EA	\$99.83	\$4,093
<b>1152</b> V1 Video Projector	41	EA	\$99.83	\$4,093
<b>1153</b> S1 Speaker	82	EA	\$99.83	\$8,186
<b>1154</b> AV Eqpt, Inst, LV Wiring - Proj/Assist List	41	RM	\$0.00	\$0
<b>1155</b> J1	2	EA	\$99.83	\$200
<b>1156</b> Data Outlet P Projector	1	EA	\$99.83	\$100
<b>1157</b> Screen	1	EA	\$99.83	\$100
<b>1158</b> R2 Receptacle Panel	4	EA	\$169.40	\$678
<b>1159</b> R3 Receptacle Panel	4	EA	\$169.40	\$678
<b>1160</b> Speaker S1 Backbox	4	EA	\$99.83	\$399
<b>1161</b> Speaker S2 Backbox	4	EA	\$99.83	\$399
<b>1162</b> Speaker S3 Backbox	14	EA	\$99.83	\$1,398
<b>1163</b> AV Rack Enclosure	1	EA	\$459.80	\$460
<b>1164</b> AV Eqpt, Installation, LV Wiring - ALLOW	1	LS	\$0.00	\$0
<b>1165</b> Gym Sound System Mat'l Package	1	LS	\$45,000.00	\$45,000
<b>1166</b> Auditorium AV Roughin	1	LS	\$45,000.00	\$45,000
<b>1167</b> )				
<b>1168</b> Theater Lighting & Control System:ALLOW (Eqpt in "Equipment Section")				
<b>1169</b> Lighting and Controls included in "Equipment Section"				



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>1170</b> Theat Lighting & Power Roughin	1	LS	\$30,000.74	\$30,001
<b>1171</b> Theat Lighting Controls Roughin	1	LS	\$10,000.25	\$10,000
<b>1172</b>				
<b>1173</b> Security Intrusion Alarm System:				
<b>1174</b> Power Supply Junc Box, 120v	1	EA	\$459.80	\$460
<b>1175</b> Central Eqpt	1	EA	\$14,713.60	\$14,714
<b>1176</b> 3/4" Emt, 4#12	40	LF	\$13.85	\$554
<b>1177</b> Plenum Cables	4,800	LF	\$1.59	\$7,608
<b>1178</b> 3/4" Emt	720	LF	\$11.93	\$8,590
<b>1179</b> CR Card Reader	9	EA	\$810.70	\$7,296
<b>1180</b> K Keypad	2	EA	\$810.70	\$1,621
<b>1181</b> EL Electric Lock	5	EA	\$490.05	\$2,450
<b>1182</b> EH Electric Hinge	30	EA	\$490.05	\$14,702
<b>1183</b> Intercom	2	EA	\$520.30	\$1,041
<b>1184</b> PT Install Power Transfer Hinge FBO	16	EA	\$411.40	\$6,582
<b>1185</b> REX Req to Exit	21	EA	\$290.40	\$6,098
<b>1186</b> DC Door Position Sw	54	EA	\$199.65	\$10,781
<b>1187</b> M Motion Sensor	71	EA	\$411.40	\$29,209
<b>1188</b> TS Door Switch	16	EA	\$181.50	\$2,904
<b>1189</b> DJ Door Junc Box	16	EA	\$139.15	\$2,226
<b>1190</b>				
<b>1191</b> CCTV System:				
<b>1192</b> 3/4" EMT Cdt	870	LF	\$11.41	\$9,927
<b>1193</b> Signal Cables	11,400	LF	\$1.59	\$18,070
<b>1194</b> Monitoring/Recording Eqpt	1	LS	\$33,577.50	\$33,578
<b>1195</b> Viewing Console	2	EA	\$1,161.60	\$2,323
<b>1196</b> Data Outlet CAM, Camera	55	EA	\$1,294.70	\$71,209
<b>1197</b> Data Outlet CAM, Camera WP	15	EA	\$1,996.50	\$29,948
<b>1198</b>				
<b>1199</b> BDA System	1	LS	\$136,000.00	\$136,000
<b>1200</b> Area of Rescue Assistance	1	LS	\$20,000.00	\$20,000
<b>1201</b>				
<b>1202</b> Temp Power and Lighting	1	LS	\$89,540.00	\$89,540
<b>1203</b> <b>D5011 SERVICE &amp; DISTRIBUTION TOTAL</b>				<b>\$5,523,083</b>
<b>1204</b>				
<b>1205</b> <b>TOTAL SYSTEM D50 ELECTRICAL</b>				<b>\$5,523,083</b>
<b>1206</b>				
<b>1207</b>				
<b>1208</b> <b>E10 EQUIPMENT</b>				
<b>1209</b>				
<b>1210</b> <b>E1020 INSTITUTIONAL EQUIPMENT</b>				
<b>1211</b> <i>Projection Screens</i>				
<b>1212</b> Motorized projection screen; Auditorium	1	EA	\$17,000.00	\$17,000
<b>1213</b> Projection screen - Media Center, room 1250	2	EA	\$3,000.00	\$6,000
<b>1214</b> <i>Residential Appliances</i>				



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>1215</b> Refrigerator/Freezer, microwave oven	5	RMS	\$1,700.00	\$8,500
<b>1216</b> Dishwasher	1	EA	\$1,200.00	\$1,200
<b>1217</b> Undercounter refrigerator @ Nurse	1	EA	\$1,200.00	\$1,200
<b>1218</b> <i>Food service equipment</i>				
<b>1219</b> Dining & Food Service (Budget provided, July 19, 2019)	1	AL	\$415,270.00	\$415,270
<b>1220</b> <i>Auditorium/Theatre Equipment</i>				
<b>1221</b> AV	1	AL	\$200,000.00	\$200,000
<b>1222</b> Lighting	1	AL	\$129,018.00	\$129,018
<b>1223</b> Dimming	1	AL	\$95,749.00	\$95,749
<b>1224</b> Rigging	1	AL	\$158,300.00	\$158,300
<b>1225</b> Curtains	1	AL	\$33,854.00	\$33,854
<b>1226</b> Orchestra	1	AL	\$175,000.00	FF&E
<b>1227</b> Gym AV sound system	1	AL	\$120,000.00	\$120,000
<b>1228</b> Cafeteria AV	1	AL	\$50,000.00	\$50,000
<b>1229</b> Band and chorus AV	1	AL	\$60,000.00	\$60,000
<b>1230</b> Aud. seating; stacked (48), fixed (321), removeable (46)	1	AL	\$106,445.00	\$106,445
<b>1231</b> <i>Science Room Equipment</i>				
<b>1232</b> Fume hoods	6	EA	\$10,000.00	NIC
<b>1233</b> <i>Gymnasium equipment</i>				
<b>1234</b> Electronic scoreboard	1	EA	\$7,500.00	\$7,500
<b>1235</b> Shot clock/shot timer	1	EA	\$1,250.00	\$1,250
<b>1236</b> Pull up bar	1	EA	\$850.00	\$850
<b>1237</b> Stall bar	1	EA	\$850.00	\$850
<b>1238</b> Vertical ladder	1	EA	\$550.00	\$550
<b>1239</b> Rope hoist	1	EA	\$500.00	\$500
<b>1240</b> Overhead mounted folding backstops w/glass backboards	6	EA	\$6,500.00	\$39,000
<b>1241</b> Gym motorized divider curtains	1	EA	\$20,000.00	\$20,000
<b>1242</b> Sleeves & floor plates for badminton & volleyball uprights; allow	2	SETS	\$4,000.00	\$8,000
<b>1243</b> Gym equipment controls-power touch	1	LS	\$5,000.00	\$5,000
<b>1244</b> Gym wall safety pads to be 8'-8" high	2,634	SF	\$18.00	\$47,412
<b>1245</b> Motorized telescoping bleachers, motorized	760	SEAT	\$100.00	\$76,000
<b>1246</b> Shop equipment	1	LS	\$25,000.00	\$25,000
<b>1247</b> Loading dock equipment	1	LS	\$10,000.00	\$10,000
<b>1248</b> <b>E1020 INSTITUTIONAL EQUIPMENT TOTAL</b>				<b>\$1,644,448</b>
<b>1249</b>				
<b>1250</b> <b>TOTAL SYSTEM E10 FITTINGS &amp; EQUIPMENT</b>				<b>\$1,644,448</b>
<b>1251</b>				
<b>1252</b>				
<b>1253</b> <b>E20 FURNISHINGS</b>				
<b>1254</b>				
<b>1255</b> <b>E2020 SPECIALTIES / MILLWORK</b>				
<b>1256</b> <i>Interior guardrails</i>				
<b>1257</b> Handrailing	150	LF	\$200.00	\$30,000



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b>DESCRIPTION</b>	<b>QUANTITY</b>	<b>UNIT</b>	<b>RATE/UNIT</b>	<b>TOTAL</b>
<b>1258</b> Guardrail in Common areas	<b>365</b>	LF	\$103.00	\$37,595
<b>1259</b> Guardrails at lockers	<b>1,000</b>	LF	\$550.00	BP#2
<b>1260</b> Railings in auditorium	<b>1</b>	LS	\$35,000.00	\$35,000
<b>1261</b> Vertical duct enclosure	<b>4,200</b>	LF	\$90.00	NIC
<b>1262</b>				
<b>1263</b> <i>Miscellaneous metals</i>				
<b>1264</b> Furnishings; miscellaneous metals	<b>137,385</b>	GSF	\$0.35	\$48,085
<b>1265</b>				
<b>1266</b> Furnishings; miscellaneous wood blocking	<b>137,385</b>	GSF	\$0.25	\$34,346
<b>1267</b>				
<b>1268</b> <i>Academic areas: classrooms, science, media, music, vocational, sped</i>				
<b>1269</b> Bench; wood veneer cantilevered w/ptd supports	<b>69</b>	LF	\$350.00	\$24,150
<b>1270</b> Epoxy counter 24" wide	<b>325</b>	LF	\$325.00	\$105,625
<b>1271</b> Plam admin desk, curved @ Admin	<b>20</b>	LF	\$500.00	\$10,000
<b>1272</b> Plam base cabinet	<b>35</b>	LF	\$205.00	\$7,175
<b>1273</b> Plam base cabinet; mobile on casters	<b>175</b>	EA	\$550.00	\$96,250
<b>1274</b> Plam counter 24" wide	<b>1,425</b>	LF	\$200.00	\$285,000
<b>1275</b> Plam tall cabinets	<b>4</b>	EA	\$1,000.00	\$4,000
<b>1276</b> Plam tall cabinets w/tackable surface	<b>3</b>	EA	\$1,250.00	\$3,750
<b>1277</b> Plam upper cabinet	<b>197</b>	LF	\$175.00	\$34,475
<b>1278</b> Plam work counter oval @ Admin	<b>10</b>	LF	\$350.00	\$3,500
<b>1279</b> Shadow relief	<b>125</b>	LF	\$1,200.00	\$150,000
<b>1280</b> <i>Administration areas, Offices, Medical:</i>				
<b>1281</b> plam custom base & upper cabinets w/solid surface counter	<b>20</b>	LF	\$715.00	\$14,300
<b>1282</b> tackable surface backsplash	<b>160</b>	SF	\$24.00	\$3,840
<b>1283</b> Interior panel grille	<b>450</b>	LF	\$150.00	\$67,500
<b>1284</b> (4) Adj shelves 12" wide melamine	<b>602</b>	LF	\$140.00	\$84,280
<b>1285</b> (6) Adj shelves 12" wide melamine @ Media	<b>56</b>	LF	\$210.00	\$11,760
<b>1286</b> <i>Other areas:</i>				
<b>1287</b> Mail slots, melamine	<b>16</b>	LF	\$250.00	\$4,000
<b>1288</b> Window treatment, manually operated roller shades	<b>10,288</b>	SF	\$6.00	\$61,728
<b>1289</b> motorized roller shades @ exterior CW and SF	<b>1,456</b>	SF	\$10.00	\$14,560
<b>1290</b> motorized shade units at skylights	<b>4,015</b>	SF	\$10.00	\$40,150
<b>1291</b> roller shade at interior doors w/lites & glazed partitions	<b>5,569</b>	SF	\$4.00	\$22,276
<b>1292</b> Perforated arch grille curved @ Classrooms 1' h	<b>1,345</b>	LF	\$55.00	\$73,975
<b>1293</b> <b>E2020 SPECIALTIES / MILLWORK TOTAL</b>				<b>\$1,307,320</b>
<b>1294</b>				
<b>1295</b> <b>TOTAL SYSTEM E20 FURNISHINGS</b>				<b>\$1,307,320</b>
<b>1296</b>				
<b>1297</b>				
<b>1298</b> <b>F10 SPECIAL CONSTRUCTION</b>				
<b>1299</b>				
<b>1300</b> <b>F1010 SPECIAL CONSTRUCTION</b>				



**Fuller Middle School**

Framingham, MA

137,385 GSF

**DETAILED ESTIMATE - NEW CONSTRUCTION**

<b><u>DESCRIPTION</u></b>	<b><u>QUANTITY</u></b>	<b><u>UNIT</u></b>	<b><u>RATE/UNIT</u></b>	<b><u>TOTAL</u></b>
<b>1301</b> No work in this section				
<b>1302</b> <b>F1010 SPECIAL CONSTRUCTION TOTAL</b>				<b>\$0</b>
<b>1303</b>				
<b>1304</b> <b>TOTAL SYSTEM F10 SPECIAL CONSTRUCTION</b>				<b>\$0</b>
<b>1305</b>				
<b>1306</b>				
<b>1307</b> <b>F20 SELECTIVE DEMOLITION</b>				
<b>1308</b>				
<b>1309</b> <b>F2020 SELECTIVE DEMOLITION</b>				
<b>1310</b> Demolition of existing building allowance	<b>195,400</b>	SF		
<b>1311</b> Haz mat removal allowance				
<b>1312</b> <b>F2020 SELECTIVE DEMOLITION TOTAL</b>				<b>\$0</b>
<b>1313</b>				
<b>1314</b> <b>TOTAL SYSTEM F20 DEMOLITION</b>				<b>\$0</b>
<b>1315</b>				
<b>1316</b>				
<b>1317</b>				
			<b>TOTAL BUILDING SUMMARY</b>	<b>\$42,156,411</b>



**Fuller Middle School**

Framingham, MA

137,385 GSF

**SITWORK: NEW CONSTRUCTION**

<b><u>DESCRIPTION</u></b>	<b><u>QUANTITY</u></b>	<b><u>UNIT</u></b>	<b><u>UNIT COST</u></b>	<b><u>TOTAL</u></b>
<b>10 G10 SITE PREPARATION</b>				
<b>11</b>				
<b>12 G1010 Site Clearing</b>				
<b>13 31 10 00 Site Clearing</b>				
<b>14</b> Site clearing	7.3	ACRE	\$5,000.00	BP#1
<b>15</b> Safety barricade	1	AL	\$60,000.00	BP#1
<b>16</b> Construction fence, install, maintain, remove & reinstall; for all phases	11,344	LF	\$12.00	BP#1
<b>17</b> Double construction gate	2	PR	\$2,500.00	BP#1
<b>18</b> Temporary construction entrance	2	LOC	\$7,000.00	BP#1
<b>19</b> Add premium for moving and reinstalling for 3 phases	1	LS	\$37,385.00	BP#1
<b>20</b> Temporary Jersey Barriers; purchase and install	3,145	LF	\$65.00	BP#1
<b>21</b> Temp signs	1	LS	\$3,000.00	BP#1
<b>22</b> Wash down/re-fueling/parking allowance	3,000	SF	\$2.00	BP#1
<b>23 31 23 19 Dewatering and Drainage</b>				
<b>24</b> Dewatering for sitework excavation; allow	1	LS	\$100,000.00	BP#1
<b>25 31 25 00 Erosion and Sedimentation Controls</b>				
<b>26</b> Erosion control barrier	1,206	LF	\$14.00	BP#1
<b>27</b> Stockpile area (all phases), qty provided	35,000	CY	\$2.50	BP#1
<b>28</b> FM; discharge temp basin to existing DMH	271	LF	\$75.00	BP#1
<b>29</b> Stormwater basin	3,547	SF	\$2.50	BP#1
<b>30</b> Temporary pavement	47,106	SF	\$3.00	BP#1
<b>31</b> Temporary sedimentation and runoff basin	7,348	SF	\$2.00	BP#1
<b>32 G1010 Site Clearing Total</b>				<b>\$0</b>
<b>33</b>				
<b>34 G1020 Site Demolition and Relocation</b>				
<b>35 02 41 00 Demolition</b>				
<b>36</b> BP#1				BP#1
<b>37 <u>G1020.01 Building Demolition</u></b>				
<b>38 02 30 00 Building Demolition</b>				
<b>39</b> Building demolition				See Main Summary
<b>40 G1020 Site Demolition and Relocation Total</b>				<b>\$0</b>
<b>41</b>				
<b>42 G1030 Site Earthwork</b>				
<b>43 32 18 00 Athletic and Recreational Surfacing</b>				
<b>44</b> Site prep	258,370	SF	\$1.00	\$258,370
<b>243</b> Trench and backfill only	313	LF	\$45.00	\$14,085
<b>45</b> Baseball field				Existing to Remain
<b>58 G1030 Site Earthwork Total</b>				<b>\$272,455</b>
<b>59</b>				
<b>60 G10 SITE PREPARATION TOTAL</b>				<b>\$272,455</b>
<b>61</b>				



**Fuller Middle School**

Framingham, MA

137,385 GSF

**SITWORK: NEW CONSTRUCTION**

<b><u>DESCRIPTION</u></b>	<b><u>QUANTITY</u></b>	<b><u>UNIT</u></b>	<b><u>UNIT COST</u></b>	<b><u>TOTAL</u></b>
<b>62</b>				
<b>63 <u>G20 SITE IMPROVEMENTS</u></b>				
<b>64</b>				
<b>65 G2020 Roadways</b>				
<b>66 32 12 00 Flexible Paving</b>				
<b>67 Existing public roadway 'Flagg Drive' to remain</b>		SF		ETR
<b>68 Vehicular asphalt pavement, incl's temporary pavement</b>	<b>202,060</b>	SF	\$3.00	BP#1
<b>69 Raised bituminous pavement (stamped)</b>	<b>11,716</b>	SF	\$15.00	BP#1
<b>70 Gravel base to roadway &amp; parking lot</b>	<b>9,445</b>	CY	\$35.00	BP#1
<b>71 32 16 00 Curbs and Gutters</b>				BP#1
<b>72 VGC; vertical granite curb</b>	<b>3,965</b>	LF	\$42.00	BP#1
<b>73 SGC; sloped granite curb</b>	<b>191</b>	LF	\$43.50	BP#1
<b>74 PCC; precast concrete curb</b>	<b>8,105</b>	LF	\$25.00	BP#1
<b>75 Bit. berm curb</b>	<b>1,336</b>	LF	\$5.00	BP#1
<b>76 32 17 00 Paving Specialties</b>				BP#1
<b>77 Crosswalk</b>	<b>2,350</b>	SF	\$2.50	BP#1
<b>78 Parking stall painting</b>	<b>302</b>	EA	\$15.00	BP#1
<b>79 Parking stall painting; HC</b>	<b>12</b>	EA	\$75.00	BP#1
<b>80 Crosswalk striping, temporary</b>	<b>2,440</b>	SF	\$2.50	BP#1
<b>81 Temporary parking spaces, incl's HC bus</b>	<b>162</b>	EA	\$75.00	BP#1
<b>82 Jersey barrier between vehicle parking, temporary</b>	<b>745</b>	LF	\$10.00	BP#1
<b>83 Misc. marking other than above</b>	<b>1</b>	LS	\$50,000.00	BP#1
<b>84 G2020 Roadways Total</b>				<b>\$0</b>
<b>85</b>				
<b>86 G2030 Pedestrian Paving</b>				
<b>87 32 13 10 Rigid Paving</b>				
<b>88 Concrete paving/Conc sidewalk</b>	<b>17,115</b>	SF	\$9.00	\$154,035
<b>89 Bituminous conc sidewalk</b>	<b>26,443</b>	SF	\$2.25	BP#1
<b>90 Gravel base to concrete pavement</b>	<b>807</b>	CY	\$35.00	\$28,245
<b>90 Peastone drip edge around building; 1'-6" wide</b>	<b>50</b>	CY	\$75.00	\$3,750
<b>90 Stonedust paving</b>	<b>1</b>	LS	\$1,750.00	\$1,750
<b>91 Curb cut</b>	<b>15</b>	EA	\$450.00	\$6,750
<b>92 Concrete pad</b>	<b>1</b>	AL	\$24,000.00	BP#1
<b>93 Handicap ramp</b>	<b>402</b>	SF	\$20.00	BP#1
<b>94 Temporary modular handicap ramp</b>	<b>138</b>	SF	\$20.00	BP#1
<b>95 G2030 Pedestrian Paving Total</b>				<b>\$194,530</b>
<b>96</b>				
<b>97 G2040 Site Development</b>				
<b>98 <u>G2040.01 Fences and Gates</u></b>				
<b>99 32 31 00 Fences and Gates</b>				
<b>100 Vehicular guardrail</b>	<b>271</b>	LF	\$250.00	\$67,750
<b>127 Wooden guardrail det 7/L3.0</b>	<b>992</b>	LF	\$75.00	\$74,400



**Fuller Middle School**

Framingham, MA

137,385 GSF

**SITWORK: NEW CONSTRUCTION**

<b><u>DESCRIPTION</u></b>	<b><u>QUANTITY</u></b>	<b><u>UNIT</u></b>	<b><u>UNIT COST</u></b>	<b><u>TOTAL</u></b>
<b>127</b> gates	2	EA	\$2,500.00	\$5,000
<b>127</b> Galvanized handrails @ ramps and steps	219	LF	\$250.00	\$54,750
<b>102</b> <u>Unit block retaining wall</u>				
<b>103</b> Footing	361	lf		
<b>104</b> Concrete	28	CY	\$135.00	\$3,780
<b>105</b> Concrete; place	28	CY	\$85.00	\$2,380
<b>106</b> Reinforcing	1,820	LBS	\$1.10	\$2,002
<b>107</b> Formwork	2,166	SF	\$12.00	\$25,992
<b>108</b> Wall	1,264	sf		
<b>109</b> Concrete material	42	CY	\$135.00	\$5,670
<b>110</b> Concrete; place	42	CY	\$85.00	\$3,570
<b>111</b> Reinforcing	6,300	LBS	\$1.10	\$6,930
<b>112</b> Formwork	2,166	SF	\$12.00	\$25,992
<b>113</b> Wall	1,264	SF	\$28.00	\$35,378
<b>127</b> Concrete bench w/wooden top	20	LF	\$275.00	\$5,500
<b>127</b>				
<b>127</b> Flagpole	2	EA	\$7,500.00	\$15,000
<b>127</b> Bandshell	1	AL	\$200,000.00	\$200,000
<b>128</b> Traffic signs	1	AL	\$10,000.00	BP#1
<b>129</b> Bollards	103	EA	\$800.00	\$82,400
<b>130</b> Premium for architectural featured bollards	1	LS	\$75,000.00	\$75,000
<b>131</b> Signage	1	AL	\$15,000.00	BP#1
<b>132</b> Bicycle racks	20	EA	\$950.00	\$19,000
<b>132</b> Basketball pavement				BP#1
<b>133</b> Basketball court; fence, gate, court marking	1,750	SF	\$35.00	\$61,250
<b>134</b> <b>G2040 Site Development Total</b>				<b>\$771,744</b>
<b>135</b>				
<b>136</b> <b>G2050 Landscaping</b>				
<b>137</b> <u>G2050.02 Lawns and Grasses</u>				
<b>138</b> 32 92 00 Turfs and Grasses				
<b>139</b> Topsoil for planting beds, shrubs and perennials	276	CY	\$25.00	\$6,900
<b>149</b> Sports field mix (seed)	258,370	SF	\$0.35	\$90,430
<b>140</b> Native wildflower meadow	104,342	SF	\$0.50	\$52,171
<b>141</b> Lawn (seed)	121,052	SF	\$0.35	\$42,368
<b>142</b> Sod at ampitheater	25,902	SF	\$1.50	\$38,853
<b>143</b> Sod at play areas	24,038	SF	\$1.50	\$36,057
<b>144</b> Plant bed	7,900	SF	\$10.00	\$79,000
<b>145</b> Mulch	1	LS	\$30,000.00	\$30,000
<b>147</b> Remove and install new irrigation System	82,000	SF	\$1.25	\$102,500
<b>147</b> South Sports Field				By Others
<b>148</b> Irrigation in front of Ampitheater	25,902	SF	\$2.00	\$51,804
<b>148</b> Irrigation at play areas	24,038	SF	\$2.00	\$48,076



**Fuller Middle School**

Framingham, MA

137,385 GSF

**SITework: NEW CONSTRUCTION**

<b><u>DESCRIPTION</u></b>	<b><u>QUANTITY</u></b>	<b><u>UNIT</u></b>	<b><u>UNIT COST</u></b>	<b><u>TOTAL</u></b>
<b>150</b> Fine grading	<b>121,052</b>	SF	\$0.75	\$90,789
<b>152</b>				
<b>153</b> <u>G2050.03 Trees, Plants and Ground Covers</u>				
<b>154</b> 32 93 00 Plants				
<b>155</b> Trees				
<b>156</b> AL; Allegheny Serviceberry 2½ - 3" Cal	<b>12</b>	EA	\$900.00	\$10,800
<b>157</b> AC; Shadblow Serviceberry 2½ - 3" Cal	<b>1</b>	EA	\$900.00	\$900
<b>158</b> AR; Red Maple 3 - 3½" Cal	<b>6</b>	EA	\$850.00	\$5,100
<b>159</b> CK; American Yellowwood 3 - 3½" Cal	<b>24</b>	EA	\$800.00	\$19,200
<b>160</b> FG; American Beech 3 - 3½" Cal	<b>11</b>	EA	\$850.00	\$9,350
<b>161</b> LT; Tulip Tree 3 - 3½" Cal	<b>8</b>	EA	\$900.00	\$7,200
<b>162</b> NS; Black Tupelo 3 - 3½" Cal	<b>15</b>	EA	\$850.00	\$12,750
<b>163</b> OA; Sourwood 2½-3" Cal	<b>3</b>	EA	\$750.00	\$2,250
<b>164</b> PA; London Plain Tree 3 - 3½" Cal	<b>24</b>	EA	\$850.00	\$20,400
<b>165</b> QP; Pin Oak 3 - 3½" Cal	<b>7</b>	EA	\$900.00	\$6,300
<b>166</b> QR; Red Oak 3 - 3½" Cal	<b>7</b>	EA	\$950.00	\$6,650
<b>167</b> Shrubs				
<b>168</b> CA; Sweet Pepperbush 3½ - 4' HT	<b>28</b>	EA	\$95.00	\$2,660
<b>169</b> HQ; Oak-leaf Hydrangea 3 - 3½' HT	<b>49</b>	EA	\$95.00	\$4,655
<b>170</b> HV; Witch Hazel 7- 8' B+B	<b>3</b>	EA	\$350.00	\$1,050
<b>171</b> IG; Compact Incberry 2½ - 3' HT	<b>33</b>	EA	\$125.00	\$4,125
<b>172</b> IV; Winterberry 2 - 2½ HT	<b>61</b>	EA	\$95.00	\$5,795
<b>173</b> JC; Common Juniper 24" SPD	<b>0</b>	EA	\$75.00	\$0
<b>174</b> JH; Creeping Juniper 15-24" SPD	<b>68</b>	EA	\$75.00	\$5,100
<b>175</b> JV; Eastern Red Cedar 7- 8' HT	<b>26</b>	EA	\$205.00	\$5,330
<b>176</b> MG; Sweetgale 3½ - 4' HT	<b>38</b>	EA	\$95.00	\$3,610
<b>177</b> PF; Pink Beauty Potentilla 24" SPD	<b>22</b>	EA	\$75.00	\$1,650
<b>178</b> RA; Grow Low Sumac 2 - 2½' SPD	<b>47</b>	EA	\$115.00	\$5,405
<b>179</b> RT; Staghorn Sumac 3 Gal	<b>13</b>	EA	\$115.00	\$1,495
<b>180</b> RV; Virginia Rose 2½ - 3' SPD	<b>0</b>	EA	\$75.00	\$0
<b>181</b> VA; Lowbush Blueberry 15-24" SPD	<b>53</b>	EA	\$75.00	\$3,975
<b>182</b> VD; Arrowwood 4 - 4½' HT	<b>31</b>	EA	\$150.00	\$4,650
<b>183</b> VT; Dwarf Cranberry Bush 3 - 3½' HT	<b>12</b>	EA	\$115.00	\$1,380
<b>184</b> Groundcover				
<b>185</b> CP; Sweet Fern 1 Gal	<b>1,966</b>	EA	\$15.00	\$29,490
<b>186</b> Grass at temporary parking area	<b>6,650</b>	SF	\$0.35	\$2,328
<b>187</b> Maintenance of landscaping	<b>1</b>	LS	\$10,000.00	\$10,000
<b>188</b> <b>G2050 Landscaping Total</b>				<b>\$862,545</b>
<b>189</b>				
<b>190</b> <b>G20 SITE IMPROVEMENTS TOTAL</b>				<b>\$1,828,819</b>
<b>191</b>				
<b>192</b>				



**Fuller Middle School**

Framingham, MA

137,385 GSF

**SITWORK: NEW CONSTRUCTION**

<b><u>DESCRIPTION</u></b>	<b><u>QUANTITY</u></b>	<b><u>UNIT</u></b>	<b><u>UNIT COST</u></b>	<b><u>TOTAL</u></b>
<b>193</b> <b><u>G30 SITE CIVIL/MECHANICAL UTILITIES</u></b>				Early Bid package
<b>194</b>				
<b>195</b> <b>G3010 Water Supply</b>				
<b>196</b> <i>33 10 00 Water Distribution</i>				
<b>197</b> 2" Domestic water service	120	LF	\$60.00	BP#1
<b>198</b> 6" Fire water service	170	LF	\$70.00	BP#1
<b>199</b> Water service; not sized	680	LF	\$95.00	BP#1
<b>200</b> Hydrant	5	EA	\$4,500.00	BP#1
<b>201</b> Miscellaneous gates, valves, etc. (gate valve 8x8x6)	1	LS	\$10,000.00	BP#1
<b>202</b> <b>G3010 Water Supply Total</b>				<b>\$0</b>
<b>203</b>				
<b>204</b> <b>G3020 Sanitary Sewer</b>				
<b>205</b> <i>33 31 00 Sanitary Sewerage</i>				
<b>206</b> All incl. trench and backfill				
<b>207</b> 6" DI	78	LF	\$70.00	BP#1
<b>208</b> 6" PVC	42	LF	\$70.00	BP#1
<b>209</b> 8" PVC	472	LF	\$75.00	BP#1
<b>210</b> SMH; Sewer manhole	4	EA	\$4,500.00	BP#1
<b>211</b> CO; Cleanout	1	EA	\$600.00	BP#1
<b>212</b> Connect to existing	1	EA	\$3,500.00	BP#1
<b>213</b> Acid neutralization tank	2	EA	\$7,500.00	BP#1
<b>214</b> Grease trap	1	EA	\$15,000.00	BP#1
<b>215</b> <b>G3020 Sanitary Sewer Total</b>				<b>\$0</b>
<b>216</b>				
<b>217</b> <b>G3030 Storm Sewer</b>				
<b>218</b> <i>33 41 00 Storm Utility Drainage</i>				
<b>219</b> All incl. trench and backfill				
<b>220</b> 6" PVC	47	LF	\$35.00	BP#1
<b>221</b> 12" HDPE	2,435	LF	\$42.00	BP#1
<b>222</b> 15" HDPE	635	LF	\$45.00	BP#1
<b>223</b> 18" HDPE	548	LF	\$48.00	BP#1
<b>224</b> 24" HDPE	371	LF	\$50.00	BP#1
<b>225</b> 30" HDPE	547	LF	\$60.00	BP#1
<b>226</b> DMH; Manhole	9	EA	\$3,500.00	BP#1
<b>227</b> CB; catch basin	19	EA	\$4,500.00	BP#1
<b>228</b> Temporary CB, convert to DMH	3	EA	\$4,500.00	BP#1
<b>229</b> Headwall @ 24" HDPE end	2	EA	\$1,500.00	BP#1
<b>230</b> Allowances for:				BP#1
<b>231</b> Water quality structures	4	EA	\$15,000.00	BP#1
<b>232</b> Gravel and sod buffer for pretreatment	1	LS	\$10,000.00	BP#1
<b>233</b> Stormceptors:				BP#1
<b>234</b> 450i	2	EA	\$10,000.00	BP#1



**Fuller Middle School**

Framingham, MA

137,385 GSF

**SITWORK: NEW CONSTRUCTION**

<b><u>DESCRIPTION</u></b>	<b><u>QUANTITY</u></b>	<b><u>UNIT</u></b>	<b><u>UNIT COST</u></b>	<b><u>TOTAL</u></b>
<b>235</b> 3600	1	EA	\$35,000.00	BP#1
<b>236</b> 6000	1	EA	\$60,000.00	BP#1
<b>237</b> Outlet structure	1	EA	\$5,000.00	BP#1
<b>238</b> Perimeter drainage				Bldg Tab
<b>239 G3030 Storm Sewer Total</b>				<b>\$0</b>
<b>240</b>				
<b>241 G3040 Heating Distribution</b>				
<b>242</b> 33 50 00 Gas Service				
<b>244</b> Connection to existing gas main				By Other
<b>245</b> Gas line piping, incl's valves (2)				By Other
<b>246 G3040 Heating Distribution Total</b>				<b>\$0</b>
<b>247</b>				
<b>248 G30 SITE CIVIL/MECHANICAL UTILITIES TOTAL</b>				<b>\$0</b>
<b>249</b>				
<b>250</b>				
<b>251 G40 SITE ELECTRICAL UTILITIES</b>				
<b>252</b>				
<b>253 G4010 Site Electrical Utilities</b>				
<b>253</b>				
<b>254</b> 33 70 00 Electrical Utilities				
<b>255</b> Site Lighting, Site Eqpt				
<b>256</b> Type SL1, 1-Fixt, 30' pole	45	EA	\$4,767.40	BP#1
<b>257</b> Type SL1A, 1-Fixt, 30' pole	0	EA	\$4,767.40	BP#1
<b>258</b> Type SL3, Wallpack	4	EA	\$701.80	\$2,807
<b>259</b> Type SL3 Pedestrian Light Pole	42	EA	\$3,242.80	\$136,198
<b>260</b> WP Signage w/ Lights, FBO	1	EA	\$1,113.20	\$1,113
<b>261</b> Type SL10 Plant uplight	12	EA	\$520.30	\$6,244
<b>262</b> Receptacle WP GFI	5	EA	\$284.35	\$1,422
<b>263</b> CCTV Camera, Pole Mtd	3	EA	\$1,863.40	\$5,590
<b>264</b> Elect Vehicle Charging Station	3	EA	\$1,645.60	\$4,937
<b>265</b> Relocate Exist EM Call Box	2	EA	\$1,113.20	\$2,226
<b>266</b> Time Clock	1	EA	\$1,004.30	\$1,004
<b>267</b>				
<b>268</b> Branch Circuitry:				
<b>269</b> 3/4" Emt, 4#10	280	LF	\$14.98	BP#1
<b>270</b> 1" PVC CDT UG	7,110	LF	\$5.41	BP#1
<b>271</b> 2" PVC CDT UG	900	LF	\$7.70	BP#1
<b>272</b> 2 1/2" PVC CDT UG	3,600	LF	\$10.31	BP#1
<b>273</b> 17x30x12" Site Pullbox	16	EA	\$2,323.20	\$37,171
<b>274</b> Handhole	6	EA	\$2,323.20	\$13,939
<b>275</b> #10 Wire	12,400	LF	\$1.25	\$15,535
<b>276</b> #8 Wire	16,050	LF	\$1.76	\$28,261
<b>277</b> #6 Wire	2,700	LF	\$2.11	\$5,707



**Fuller Middle School**

Framingham, MA

137,385 GSF

**SITWORK: NEW CONSTRUCTION**

<b><u>DESCRIPTION</u></b>	<b><u>QUANTITY</u></b>	<b><u>UNIT</u></b>	<b><u>UNIT COST</u></b>	<b><u>TOTAL</u></b>
<b>278</b> Signal Cable	<b>1,250</b>	LF	\$1.82	\$2,269
<b>279</b>				
<b>280</b> Site Power, EG Feeders, Utilities:				
<b>282</b> 4" PVC (Primary, empty) UG	<b>460</b>	LF	\$16.95	\$7,797
<b>283</b> 4" PVC CDT, 4 600 Mcm, UG (service)	<b>600</b>	LF	\$104.70	\$62,819
<b>284</b> 4" PVC CDT UG (spare)	<b>100</b>	LF	\$16.95	\$1,695
<b>285</b> 4" PVC CDT, 4 500 Mcm, UG (EG)	<b>100</b>	LF	\$87.18	\$8,718
<b>286</b> 2" PVC, 4#1/0 UG (EG)	<b>100</b>	LF	\$29.19	\$2,919
<b>287</b> 2 1/2" PVC, 4#4/0 UG (EG)	<b>100</b>	LF	\$38.87	\$3,887
<b>288</b> 1" PVC, EG Controls, Misc UG	<b>200</b>	LF	\$10.44	\$2,088
<b>281</b> Utility Pole Riser	<b>1</b>	LF	\$4,767.40	\$4,767
<b>289</b> Utility Transformer Pad	<b>1</b>	LS	\$4,162.40	\$4,162
<b>290</b> Manhole	<b>2</b>	EA	\$11,616.00	\$23,232
<b>292</b> Trenching, Concrete, Backfill	<b>1</b>	LS	\$100,000.00	BP#1
<b>293</b>				
<b>294</b> Miscellaneous:				
<b>295</b> 4" PVC CDT UG (Comm)	<b>800</b>	LF	\$16.95	\$13,560
<b>296</b> Innerduct	<b>600</b>	LF	\$3.99	\$2,396
<b>297</b> Tel Utility Pole Riser	<b>1</b>	LS	\$3,121.80	\$3,122
<b>298</b> 3'x3' Comm Handhole	<b>1</b>	EA	\$6,243.60	\$6,244
<b>299</b>				
<b>300</b> Misc Site Demo	<b>1</b>	LS	\$10,890.00	BP#1
<b>301</b> Site Security Lighting	<b>1</b>	LS	\$12,584.00	\$12,584
<b>302</b> Temp Power and Lighting	<b>1</b>	LS	\$31,460.00	\$31,460
<b>303</b> Eqpt Rentals	<b>1</b>	LS	\$7,260.00	\$7,260
<b>304</b> <b>G4010 Site Electrical Utilities Total</b>				<b>\$463,132</b>
<b>305</b>				
<b>306</b> <b>G40 SITE ELECTRICAL UTILITIES TOTAL</b>				<b>\$463,132</b>
<b>307</b>				
<b>308</b>				
<b>309</b>				
			<b>TOTAL SITWORK SUMMARY</b>	<b>\$2,564,406</b>





**Fuller Middle School**

Fuller Middle School

137,385 GSF

**MAIN SUMMARY - NEW CONSTRUCTION**

<b><u>DESCRIPTION</u></b>			<b><u>TOTAL</u></b>	<b><u>COST/SF</u></b>
<b>Direct Trade Costs With Site</b>				
New Construction	137,385	GSF	\$42,156,411	\$306.85
Site Development			\$2,564,406	\$18.67
<b>Direct Trade Cost SubTotal</b>			<b>\$44,720,817</b>	<b>\$325.51</b>
Demolish Existing Building	195,400	GSF	\$1,465,500	\$10.67
Hazardous Waste Abatement (Budget provided)			\$1,294,490	\$9.42
<b>Building Cost Subtotal</b>			<b>\$47,480,807</b>	<b>\$345.60</b>
Design and Pricing Contingency	3.00%	\$47,480,807	\$1,424,424	\$10.37
<b>Building Cost Total</b>			<b>\$48,905,231</b>	<b>\$355.97</b>
Escal. to Midpoint of Construction (Consigli %)	1.34%	\$48,905,231	\$655,330	\$4.77
<b>Trade Cost SubTotal</b>			<b>\$49,560,561</b>	<b>\$360.74</b>
General Conditions			\$2,931,033	\$21.33
General Requirements			\$2,289,380	\$16.66
SDI			\$269,858	\$1.96
Sub Bonds			\$403,034	\$2.93
General Liability Insurance			\$576,109	\$4.19
Construction Contingency	2.50%	\$49,560,561	\$1,239,014	\$9.02
CM Fee			\$1,152,218	\$8.39
<b>BP#1</b>			\$10,957,843	\$79.76
<b>BP#2</b>			\$8,738,800	\$63.61
<b>BP#2 Savings</b>			(\$182,955)	
<b>Estimated Construction Cost Total</b>			<b>\$77,934,895</b>	<b>\$567.27</b>

# Fuller Middle School

Framingham, MA

## DIRECT TRADE COSTS SUMMARY - CSI

137,385 GSF

<u>Element</u>	<u>Filed Sub Bid</u>	<u>SITEWORK</u>	<u>BUILDING</u>	<u>TOTAL</u>	<u>\$/GSF</u>
02 30 00 Building Demolition				\$0	\$0.00
02 41 00 Demolition		\$0		\$0	\$0.00
02 60 00 Hazardous Waste Remediation			\$0	\$0	\$0.00
<b>02-EXISTING CONDITIONS</b>		<b>\$0</b>	<b>\$0</b>	<b>\$0</b>	<b>\$0.00</b>
03 30 00 Cast-In-Place Concrete			\$111,548	\$111,548	\$0.81
<b>03-CONCRETE</b>		<b>\$0</b>	<b>\$111,548</b>	<b>\$111,548</b>	<b>\$0.81</b>
04 20 00 Unit Masonry	\$2,456,979		\$2,456,979	\$2,456,979	\$17.88
<b>04-MASONRY</b>		<b>\$0</b>	<b>\$2,456,979</b>	<b>\$2,456,979</b>	<b>\$17.88</b>
05 12 00 Structural Steel Framing			\$59,250	\$59,250	\$0.43
05 31 00 Steel Decking			\$0	\$0	\$0.00
05 40 00 Cold-Formed Metal Framing			\$0	\$0	\$0.00
05 50 00* Miscellaneous and Ornamental Iron	\$1,770,843		\$1,770,843	\$1,770,843	\$12.89
<b>05-METALS</b>		<b>\$0</b>	<b>\$1,830,093</b>	<b>\$1,830,093</b>	<b>\$13.32</b>
06 10 00 Rough Carpentry			\$267,293	\$267,293	\$1.95
06 16 50 Gypsum Sheathing			\$0	\$0	\$0.00
06 20 00 Finish Carpentry			\$886,115	\$886,115	\$6.45
06 40 00 Architectural Woodwork			\$88,675	\$88,675	\$0.65
<b>06-WOOD, PLASTICS &amp; COMPOSITES</b>			<b>\$1,242,083</b>	<b>\$1,242,083</b>	<b>\$9.04</b>
07 00 01* Waterproofing, Dampproofing & Caulking	\$36,576		\$36,576	\$36,576	\$0.27
07 21 00 Thermal Insulation			\$541,964	\$541,964	\$3.94
07 00 02* Roofing & Flashing	\$1,810,473		\$1,810,473	\$1,810,473	\$13.18
07 42 00 Wall Panels			\$1,251,774	\$1,251,774	\$9.11
07 81 00 Applied Fireproofing			\$108,050	\$108,050	\$0.79
07 84 10 Penetration Firestopping			\$178,601	\$178,601	\$1.30
<b>07-THERMAL AND MOISTURE PROTECTION</b>			<b>\$3,927,436</b>	<b>\$3,927,436</b>	<b>\$28.59</b>
08 11 10 Hollow Metal Doors and Frames			\$284,350	\$284,350	\$2.07
08 14 00 Flush Wood Doors			\$10,000	\$10,000	\$0.07
08 31 10 Access Doors & Frames			\$30,000	\$30,000	\$0.22
08 33 10 Overhead Coiling Doors			\$50,433	\$50,433	\$0.37
08 00 01* Metal Windows			\$2,142,316	\$2,142,316	\$15.59
08 63 00 Metal-Framed Skylights			\$702,625	\$702,625	\$5.11
08 71 00 Door Hardware			\$406,000	\$406,000	\$2.96
08 00 02* Glass and Glazing	\$1,694,255		\$1,694,255	\$1,694,255	\$12.33
08 90 00 Louvers and Vents			\$53,125	\$53,125	\$0.39
<b>08-OPENINGS</b>			<b>\$5,373,104</b>	<b>\$5,373,104</b>	<b>\$39.11</b>
09 29 00 Gypsum Drywall			\$3,433,769	\$3,433,769	\$24.99

# Fuller Middle School

Framingham, MA

## DIRECT TRADE COSTS SUMMARY - CSI

137,385 GSF

<u>Element</u>	<u>Filed Sub Bid</u>	<u>SITWORK</u>	<u>BUILDING</u>	<u>TOTAL</u>	<u>\$/GSF</u>
09 30 00* Tiling	\$42,625		\$42,625	\$42,625	\$0.31
09 50 01* Acoustical Ceilings	\$755,811		\$755,811	\$755,811	\$5.50
09 60 01* Resilient Flooring	\$924,199		\$924,199	\$924,199	\$6.73
09 64 00 Wood Flooring			\$48,495	\$48,495	\$0.35
09 64 40 Wood Athletic Flooring			\$210,125	\$210,125	\$1.53
09 67 23 Resinous Flooring			\$119,100	\$119,100	\$0.87
09 68 00 Carpeting			\$33,240	\$33,240	\$0.24
09 72 00 Wall Coverings			\$421,019	\$421,019	\$3.06
09 91 00* Painting	\$549,947		\$549,947	\$549,947	\$4.00
<b>09-FINISHES</b>			<b>\$6,538,330</b>	<b>\$6,538,330</b>	<b>\$47.59</b>
10 00 01 Specialties			\$489,600	\$489,600	\$3.56
10 11 00 Visual Display Boards			\$396,784	\$396,784	\$2.89
10 14 23 Signage			\$86,373	\$86,373	\$0.63
10 21 13 Plastic Toilet Compartments			\$59,600	\$59,600	\$0.43
10 21 23 Cubicle Curtains, Tracks & Hardware			\$400	\$400	\$0.00
10 26 00 Wall Protection			\$10,000	\$10,000	\$0.07
10 28 13 Toilet Accessories			\$23,880	\$23,880	\$0.17
10 44 13 Fire Protection Specialties			\$7,982	\$7,982	\$0.06
10 51 24 Phenolic-Core Lockers			\$296,975	\$296,975	\$2.16
<b>10-SPECIALTIES</b>			<b>\$1,371,594</b>	<b>\$1,371,594</b>	<b>\$9.98</b>
11 00 00 Equipment			\$35,000	\$35,000	\$0.25
11 31 00 Appliances			\$10,900	\$10,900	\$0.08
11 40 00 Food Service Equipment			\$415,270	\$415,270	\$3.02
11 52 13 Projection Screens			\$23,000	\$23,000	\$0.17
11 61 00 Theater and Stage Equipment			\$953,366	\$953,366	\$6.94
11 66 23 Gymnasium Equipment			\$103,412	\$103,412	\$0.75
11 66 53 Gymnasium Dividers			\$20,000	\$20,000	\$0.15
11 66 80 Scoreboards			\$7,500	\$7,500	\$0.05
<b>11-EQUIPMENT</b>			<b>\$1,568,448</b>	<b>\$1,568,448</b>	<b>\$11.42</b>
12 24 12 Roller Shades			\$138,714	\$138,714	\$1.01
12 35 53 Caswork			\$909,605	\$909,605	\$6.62
12 48 13 Entrance Mats & Frames			\$13,860	\$13,860	\$0.10
12 66 00 Telescoping Stands			\$76,000	\$76,000	\$0.55
<b>12-FURNISHING</b>			<b>\$1,138,179</b>	<b>\$1,138,179</b>	<b>\$8.28</b>
13 00 00 Special Construction			\$0	\$0	\$0.00
<b>13-SPECIAL CONSTRUCTION</b>			<b>\$0</b>	<b>\$0</b>	<b>\$0.00</b>
14 24 00* Hydraulic Elevators	\$205,000		\$205,000	\$205,000	\$1.49
<b>14-CONVEYING EQUIPMENT</b>			<b>\$205,000</b>	<b>\$205,000</b>	<b>\$1.49</b>

# Fuller Middle School

Framingham, MA

## DIRECT TRADE COSTS SUMMARY - CSI

137,385 GSF

<u>Element</u>	<u>Filed Sub Bid</u>	<u>SITEWORK</u>	<u>BUILDING</u>	<u>TOTAL</u>	<u>\$/GSF</u>
21 00 00* Fire Protection	\$863,994		\$863,994	\$863,994	\$6.29
22 00 00* Plumbing	\$2,126,673		\$2,126,673	\$2,126,673	\$15.48
23 00 00* HVAC	\$7,879,869		\$7,879,869	\$7,879,869	\$57.36
<b>21 - 23-MECHANICAL</b>			<b>\$10,870,536</b>	<b>\$10,870,536</b>	<b>\$79.12</b>
26 00 00* Electrical	\$5,986,215	\$463,132	\$5,523,083	\$5,986,215	\$40.20
<b>26,27,28-ELECTRICAL, COMMUNICATION, SECURITY</b>		<b>\$463,132</b>	<b>\$5,523,083</b>	<b>\$5,986,215</b>	<b>\$40.20</b>
31 00 00 Earthwork		\$272,455	\$0	\$272,455	\$1.98
31 10 00 Site Clearing		\$0		\$0	\$0.00
31 23 19 Dewatering and Drainage		\$0		\$0	\$0.00
31 25 00 Erosion and Sedimentation Controls		\$0		\$0	\$0.00
<b>31-EARTHWORK</b>		<b>\$272,455</b>	<b>\$0</b>	<b>\$272,455</b>	<b>\$0.00</b>
32 12 00 Flexible Paving		\$0		\$0	\$0.00
32 13 10 Rigid Paving		\$0		\$0	\$0.00
32 14 00 Unit Paving		\$154,035		\$154,035	\$1.12
32 16 00 Curbs and Gutters		\$0		\$0	\$0.00
32 17 00 Paving Specialties		\$40,495		\$40,495	\$0.29
32 30 00 Site Improvements		\$569,844		\$569,844	\$4.15
32 31 00 Fences and Gates		\$201,900		\$201,900	\$1.47
32 32 00 Retaining Walls		\$0		\$0	\$0.00
32 80 00 Irrigation		\$0		\$0	\$0.00
32 92 00 Turfs and Grasses		\$668,947		\$668,947	\$4.87
32 93 00 Plants		\$193,598		\$193,598	\$1.41
<b>32-EXTERIOR IMPROVEMENTS</b>		<b>\$1,828,819</b>		<b>\$1,828,819</b>	<b>\$13.31</b>
33 10 00 Water Distribution		\$0		\$0	\$0.00
33 31 00 Sanitary Sewerage		\$0		\$0	\$0.00
33 41 00 Storm Utility Drainage		\$0		\$0	\$0.00
33 50 00 Gas Service		\$0		\$0	\$0.00
<b>33-UTILITIES</b>		<b>\$0</b>		<b>\$0</b>	<b>\$0.00</b>
<b>Direct Trade Costs Subtotal</b>	<b>\$27,103,458</b>	<b>\$2,564,406</b>	<b>\$42,156,411</b>	<b>\$44,720,817</b>	<b>\$325.51</b>

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>10 02-EXISTING CONDITIONS</b>				
<b>11</b>				
<b>12 02 60 00 Hazardous Waste Remediation</b>				
<b>13</b> Removal and disposal of hazardous materials				<u>Main Summary</u>
<b>14 02 60 00 Hazardous Waste RemediationTotal</b>				
<b>15</b>				
<b>16</b>				
<b>17 03-CONCRETE</b>				
<b>18</b>				
<b>19 03 30 00 Cast-In-Place Concrete</b>				
<b>20</b> A1010 FOUNDATIONS				
<b>21</b> Concrete				
<b>22</b> Continuous footings; 3' x 1' 0" typ.	2,049	LF		
<b>23</b> 4' x 1' 0"				
<b>24</b> 5' x 1' 0"				
<b>25</b> Concrete; material	247	CY	\$135.00	BP#2
<b>26</b> Concrete; place (combination of pumping/trucking)	247	CY	\$95.00	BP#2
<b>27</b> Reinforcement w/ftn wall dowels (10#/lf)	20,490	LB	\$1.15	BP#2
<b>28</b> Formwork	8,196	SF	\$12.00	BP#2
<b>29</b> Spread footings	133	EA		
<b>30</b> Concrete; material	465	CY	\$135.00	BP#2
<b>31</b> Concrete; place	465	CY	\$95.00	BP#2
<b>32</b> Reinforcement (100#/cy)	46,500	LB	\$1.15	BP#2
<b>33</b> Formwork	6,406	SF	\$12.00	BP#2
<b>34</b> Pilasters	133	EA	\$1,100.00	BP#2
<b>35</b> Grade beam GB-1, GB-2	288	LF		
<b>36</b> Concrete; material	57	CY	\$135.00	BP#2
<b>37</b> Concrete; place (combination of pumping/trucking)	57	CY	\$95.00	BP#2
<b>38</b> Reinforcement (125#/cy)	7,125	LB	\$1.15	BP#2
<b>39</b> Formwork	1,940	SF	\$12.00	BP#2
<b>40</b> Foundation and frost walls; 16" thick x 4' 0" high typ.	8,551	SF		
<b>41</b> Concrete; material	443	CY	\$135.00	BP#2
<b>42</b> Concrete; place	443	CY	\$95.00	BP#2
<b>43</b> Reinforcement (150#/cy)	66,450	LB	\$1.15	BP#2
<b>44</b> Formwork	17,212	SF	\$8.00	BP#2
<b>45</b> Foundation walls; 21" thick x 4' 0" high typ.	1,645	SF		
<b>46</b> Concrete; material	112	CY	\$135.00	BP#2
<b>47</b> Concrete; place	112	CY	\$95.00	BP#2
<b>48</b> Reinforcement (150#/cy)	16,800	LB	\$1.15	BP#2
<b>49</b> Formwork	3,289	SF	\$8.00	BP#2
<b>50</b> Brick shelf	2,049	LF	\$5.00	BP#2
<b>51</b> Elevator pit; slab and walls	1	EA	\$5,000.00	BP#2

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
52 Anchor bolts	532	SET	\$35.00	BP#2
53 6" Ø hole through wall, backfill w/crushed stone	4	EA	\$500.00	BP#2
54				
55 Bandshell				
56 Footing	46	lf		
57 Concrete; material	7	CY	\$135.00	BP#2
58 Concrete; place	7	CY	\$95.00	BP#2
59 Reinforcing	455	LBS	\$1.15	BP#2
60 Formwork	96	SF	\$9.00	BP#2
61 Wall	182	sf		
62 Concrete	10	CY	\$135.00	BP#2
63 Placing	10	CY	\$95.00	BP#2
64 Reinforcing	1,500	LBS	\$1.15	BP#2
65 Formwork	382	SF	\$8.00	BP#2
66 Concrete steps	556	LFR	\$150.00	BP#2
67 Concrete steps , amphitheatre steps	385	LFR	\$125.00	BP#2
68 Miscellaneous concrete				
69 Ground improvements				BP#1
70				
71 Special Foundation Conditions				
72 Dewatering during excavation				BP#1
73				
74 Thermal & Moisture Protection				
75 2" rigid insulation at foundation walls	10,195	SF	\$2.50	\$25,488
76				
77				
78				
79 A1030 SLAB ON GRADE				
80 Concrete				
81 Slab on grade, 5" thick, WWF, top of slab 314' 0"	66,213	SF		
82 Concrete; material	1,030	CY	\$135.00	BP#2
83 Concrete; place & finish	66,213	SF	\$2.85	BP#2
84 Reinforcement (6x6 mesh)	76,145	SF	\$1.00	BP#2
85 Slab depressions	1,243	LF	\$65.00	BP#2
86 Slab thickening at stair 5'x2'x1' deep	6	LOC	\$2,500.00	BP#2
87 Slab on grade at loading dock, 6" thick, #4 bars	350	SF		
88 Concrete; material	6	CY	\$135.00	BP#2
89 Concrete; place & finish	350	SF	\$2.85	BP#2
90 Reinforcement; #4@12"bew	469	LBS	\$1.45	BP#2
91 Miscellaneous				
92 Concrete ramp @ Auditorium	2,440	SF	\$18.00	BP#2
93 Sloped walkway @ Cohort/Learning Common/Stage	320	SF	\$20.00	BP#2

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
94 Housekeeping & mechanical equipment pads	1	LS	\$5,000.00	BP#2
95 Miscellaneous concrete	1	LS		BP#2
96				
97 Thermal & Moisture Protection				
98 2" rigid insulation to perimeter of slab	6,392	SF	\$2.65	BP#2
99 Vapor retarder under slab	76,145	SF	\$1.00	BP#2
100				
101 B1010 UPPER FLOOR CONSTRUCTION				
102 Concrete				
103 Slab on deck topping, 3¼" light weight, WWF	69,572	SF		
104 Concrete; material	966	CY	\$135.00	BP#2
105 Reinforcement (6x6 mesh)	76,529	SF	\$1.00	BP#2
106 Rebar at corners and openings	3,826	LBS	\$1.15	BP#2
107 Concrete; place & finish	69,572	SF	\$5.00	BP#2
108 Beam pocket	23	EA	\$750.00	BP#2
109				
110 Concrete				
111 Slab on deck topping, 3¼" light weight, WWF	1,600	SF		
112 Concrete; material	22	CY	\$135.00	BP#2
113 Reinforcement (6x6 mesh)	1,760	SF	\$1.00	BP#2
114 Rebar at corners and openings	88	LBS	\$1.15	BP#2
115 Concrete; place & finish	1,600	SF	\$5.00	BP#2
116				
117 Miscellaneous				
118 Sand blasted cast in place concrete walls	1	LS	\$50,000.00	\$50,000
119 Precast concrete at planter w/galv steel connection & cross bracing	212	SF	\$75.00	\$15,900
120 slab on grade power troweled concrete at seats	2,240	SF	\$9.00	\$20,160
121				
122 PC; power troweled concrete @ Makerspace, Auditorium, AV	2,018	SF	\$9.00	BP#2
123				
124 <b>03 30 00 Cast-In-Place Concrete Total</b>				<b>\$111,548</b>
125				
126				
127 <b>04-MASONRY</b>				
128				
129 <b>04 20 00 Unit Masonry</b>				
130 12" CMU wall reinforced; Gym & Auditorium, double hgt	7,942	SF	\$32.00	\$254,144
131 8" CMU wall, load bearing wall @ Auditorium	1,284	SF	\$24.00	\$30,816
132 Stairs/elevator CMU wall	3,266	SF	\$24.00	\$78,384
133				
134 Exterior brick wall; scored brick veneer, "modular" 8x8x4 , and "ut	17,333	SF	\$35.00	\$606,655
135 Exterior CMU wall; scored ground face CMU, 8x12x16 , 4x8x16, and	24,140	SF	\$36.00	\$869,040

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>136</b> 12" Reinforced ground face CMU wall backup @ Auditorium & Gyr	<b>14,805</b>	SF	\$28.00	\$414,540
<b>137</b>				
<b>138</b> 4" Utility brick, both sides @ parapet wall, Main Entrance	<b>175</b>	SF	\$32.00	\$5,600
<b>139</b> Precast colored coping on top of parapet wall	<b>26</b>	LF	\$150.00	\$3,900
<b>140</b> Premium for custom brick and CMU @ lintels & shelves	<b>1,128</b>	LF	\$50.00	\$56,400
<b>141</b> Precast planter	<b>50</b>	LF	\$750.00	\$37,500
<b>142</b>				
<b>143</b> Exterior mockup	<b>1</b>	LS	\$50,000.00	\$50,000
<b>144</b> Temporary enclosures	<b>1</b>	LS	\$50,000.00	\$50,000
<b>145</b> <b>04 20 00 Unit Masonry Total</b>				<b>\$2,456,979</b>
<b>146</b>				
<b>147</b>				
<b>148</b> <b>05-METALS</b>				
<b>149</b>				
<b>150</b> <b>05 12 00 Structural Steel Framing</b>				
<b>151</b> Structural Steel Framing	<b>793</b>	TNS		
<b>152</b> Steel floor framing				
<b>153</b> Wide flange beams	<b>243</b>	TNS	\$3,700.00	BP#2
<b>154</b> Wide flange beams > 100	<b>36</b>	TNS	\$3,950.00	BP#2
<b>155</b> HSS-shapes	<b>47</b>	TNS	\$4,150.00	BP#2
<b>156</b> W-shapes ; columns	<b>14</b>	TNS	\$3,950.00	BP#2
<b>157</b> HSS-shapes; columns	<b>101</b>	TNS	\$4,150.00	BP#2
<b>158</b> HSS brace frames	<b>40</b>	TNS	\$4,250.00	BP#2
<b>159</b> Remainder of steel framing; beams, columns, bridging	<b>26</b>	TNS	\$4,150.00	BP#2
<b>160</b> Plates, bent plates and angles	<b>133</b>	EA	\$75.00	BP#2
<b>161</b> Moment connections	<b>157</b>	EA	\$750.00	BP#2
<b>162</b> Shear studs	<b>10,170</b>	EA	\$5.50	BP#2
<b>163</b> 3" deep x 18ga galv composite floor deck	<b>71,172</b>	SF	\$4.25	BP#2
<b>164</b>				
<b>165</b> Structural steel roof framing	<b>286</b>	TNS		
<b>166</b> Wide flange beams	<b>124</b>	TNS	\$3,650.00	BP#2
<b>167</b> Wide flange beams > 100	<b>87</b>	TNS	\$3,900.00	BP#2
<b>168</b> HSS-shape	<b>18</b>	TNS	\$4,100.00	BP#2
<b>169</b> Support post HSS7.625x0.375; RTU screen	<b>2</b>	TNS	\$4,100.00	BP#2
<b>170</b> L- ledger; L4x4x1/4 anchored to CMU, roof	<b>1</b>	TNS	\$3,550.00	BP#2
<b>171</b> Roof steel framing incl's hanger support beam, 52DLH17, HSS trus	<b>42</b>	TNS	\$4,100.00	BP#2
<b>172</b> Add reinforcement 7#/sf hot dip galv steel @ RTU	<b>12</b>	TNS	\$4,100.00	BP#2
<b>173</b> Moment connections	<b>241</b>	EA	\$750.00	BP#2
<b>174</b> Roof hanger @ main roof	<b>47</b>	EA	\$1,500.00	BP#2
<b>175</b> 3/4" rod hanger @ Gym and Auditorium roof	<b>11</b>	EA	\$1,500.00	BP#2
<b>176</b> Other misc plates, connections	<b>65,518</b>	SF	\$4.50	BP#2



# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
177 Premium for galv steel framing	14	TNS	\$500.00	BP#2
178 3" deep x 18ga galv comp roof deck (w/conc topping)	40,338	SF	\$4.25	BP#2
179 R3; 3" 18 ga roof deck above Learning Commons	8,610	SF	\$4.25	BP#2
180 R3C; 3" Cellular 18/16 ga roof deck, galv at Auditorium	7,615	SF	\$4.25	BP#2
181 R1.5; 1.5" 20 ga roof deck, Gym equipment storage	835	SF	\$6.00	BP#2
182 R1.5A; 1.5" Cellular acoustic 20 ga roof deck, galv at Gym	8,120	SF	\$6.50	BP#2
183				
184 Roof screen, galv; HSS shapes	15	TNS	\$3,950.00	\$59,250
185 <b>05 12 00 Structural Steel Framing Total</b>				<b>\$59,250</b>
186				
187 <b>05 31 00 Steel Decking</b>				
188 With Structural Steel				
189 <b>05 31 00 Steel Decking Total</b>				
190				
191 <b>05 40 00 Cold-Formed Metal Framing</b>				
192 Light gage metal framing				Div 09
193 <b>05 40 00 Cold-Formed Metal Framing Total</b>				
194				
195 <b>05 50 00* Miscellaneous and Ornamental Iron</b>				
196 Interior guardrails				
197 Handrailing	150	LF	\$200.00	\$30,000
198 Guardrail in Common areas	365	LF	\$103.00	\$37,595
199 Guardrails at lockers	1,000	LF	\$550.00	BP#2
200 Railings in auditorium	1	LS	\$35,000.00	\$35,000
201 Vertical duct enclosure	4,200	LF	\$90.00	NIC
202				
203 Miscellaneous metals				
204 Furnishings; miscellaneous metals	137,385	GSF	\$0.35	\$48,085
205				
206 Elevator pit ladder	1	EA	\$1,500.00	\$1,500
207 Elevator vent	1	EA	\$1,200.00	\$1,200
208 Sill angles	4	EA	\$175.00	\$700
209 Hoist beam	1	EA	\$5,000.00	\$5,000
210				
211 Interior stairs				
212 Egress stairs	6	FLT	\$25,000.00	\$150,000
213 Monumental/open stairs #4 & #5				BP#2
214 Monumental/open stairs #3	1	FLT	\$65,000.00	\$65,000
215				
216 Stair finishes				
217 Railings	1	LS	\$150,000.00	\$150,000
218				

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
219 Miscellaneous metals for fittings	137,385	GSF	\$1.25	\$171,731
220 Misc metals for interior construction	137,385	GSF	\$1.25	\$171,731
222 Roof dunnage (SS)	7	TNS	\$7,500.00	\$52,500
223				
224 Galvanized bar grating	1,000	SF	\$55.00	\$55,000
225 Roof soffit/fascia framing	500	LF	\$165.00	\$82,500
226				
227 Cont galv relieving angle at masonry wall	1,038	LF	\$100.00	\$103,800
228 Loose lintel @ exterior wall openings	90	LF	\$200.00	\$18,000
229 Miscellaneous metals in exterior closure	57,520	SF	\$1.50	\$86,280
230				
231 Through wall sheet metal flashing	1,424	LF	\$25.00	\$35,600
232 Corrugated perforated metal; mechanical RTU screen	1,678	SF	\$60.00	\$100,680
233				
234 Operable partition framing support beam	633	LF	\$175.00	\$110,775
235 Monumental/open stairs	920	LFR	\$85.00	\$78,200
236				
237 Metal trim detail	12,630	LF	\$8.00	\$101,040
238				
239 Metal trim detail	375	LF	\$5.00	\$1,875
240 <b>05 50 00* Miscellaneous and Ornamental Iron Total</b>				<b>\$1,770,843</b>
241				
242				
243 <b>06-WOOD, PLASTICS &amp; COMPOSITES</b>				
244				
245 <b>06 10 00 Rough Carpentry</b>				
246 Furnishings; miscellaneous wood blocking	137,385	GSF	\$0.25	\$34,346
247 Blocking at doors	5,406	LF	\$2.50	\$13,515
248 Door Installation	318	EA	\$150.00	\$47,700
249 Rough carpentry internal partitions and ceilings	137,385	GSF	\$1.25	\$171,731
250 <b>06 10 00 Rough Carpentry Total</b>				<b>\$267,293</b>
251				
252 <b>06 16 50 Gypsum Sheathing</b>				
253 Included				
254 <b>06 16 50 Gypsum Sheathing Total</b>				
255				
256 <b>06 20 00 Finish Carpentry</b>				
257 Window stools - Solid surfacing material	1,250	LF	\$50.00	\$62,500
258 Toilets				
259 Vanity counter; Toilets	319	LF	\$200.00	\$63,800
260 Vanity counter; Dressing	33	LF	\$200.00	\$6,600
261 Folding panel shutter w/w/magnetic writable surface both sides &	40	EA	\$1,000.00	\$40,000

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
262				
263 Auditorium walls:				
264 Plam wall panel to auditorium	2,900	SF	\$42.00	\$121,800
265 FRP; fiber reinforced panels in Kitchen	1,921	SF	\$15.00	\$28,815
266				
267 Solid epoxy backsplash	650	SF	\$18.00	\$11,700
268				
269 Exposed column covers; allowance	1	LS	\$35,000.00	\$35,000
270 P.lam panel wall cover	330	SF	\$25.00	\$8,250
271				
272 Plam bumper w/HD wood marker tray	2,915	LF	\$90.00	\$262,350
273 Maple rail	1,600	LF	\$30.00	\$48,000
274				
275 Cafeteria fixed sound absorbing panel, wood fiber; allow	2,000	SF	\$25.00	\$50,000
276 Wall panels at auditorium	1,500	SF	\$85.00	\$127,500
277 Wall epoxy	1,100	SF	\$18.00	\$19,800
278 <b>06 20 00 Finish Carpentry Total</b>				<b>\$886,115</b>
279				
280 <b>06 40 00 Architectural Woodwork</b>				
281 Perforated arch grille curved @ Classrooms 1' h	1,345	LF	\$55.00	\$73,975
282 Wood cantelevered benches at classroom glazed partitions	42	EA	\$350.00	\$14,700
283 <b>06 40 00 Architectural Woodwork Total</b>				<b>\$88,675</b>
284				
285				
286 <b>07-THERMAL AND MOISTURE PROTECTION</b>				
287				
288 <b>07 00 01* Waterproofing, Dampproofing &amp; Caulking</b>				
289 <b>07 11 00 Bituminous Dampproofing</b>				
290 <b>07 13 00 Self-Adhering Waterproofing</b>				
291 <b>07 16 00 Cementitious Waterproofing</b>				
292 <b>07 27 00 Air Barrier</b>				
293 <b>07 92 00 Joint Sealants</b>				
294 Caulking and sealants at corrugated metal panel	4,578	SF	\$0.65	\$2,976
295 Caulking and sealants at composite metal panel	3,638	SF	\$0.65	\$2,365
296 Caulking and sealants at Trespa cladding	6,581	SF	\$0.65	\$4,278
297 Caulking and sealants at brick & CMU	41,473	SF	\$0.65	\$26,957
298 Waterproofing elevator pit	225	SF	\$18.00	BP#2
299 Damp proofing to foundation walls	10,195	SF	\$4.50	BP#2
300 <b>07 00 01* Waterproofing, Dampproofing &amp; Caulking Total</b>				<b>\$36,576</b>
301				
302 <b>07 21 00 Thermal Insulation</b>				
303 <b>07 26 00 Vapor Retarder</b>				

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
304 3" Faced rigid cellular polyiso insulation	17,333	SF	\$4.00	\$69,332
305 Fluid applied air vapor barrier	17,333	SF	\$5.50	\$95,332
306				
307 3" Faced rigid cellular polyiso insulation	24,140	SF	\$4.00	\$96,560
308 Fluid applied air vapor barrier	24,140	SF	\$5.50	\$132,770
309				
310 4" Mineral fiber insulation	4,578	SF	\$4.50	\$20,601
311 Fluid applied air vapor barrier	4,578	SF	\$5.50	\$25,179
312				
313 4" Mineral fiber insulation	3,638	SF	\$4.50	\$16,371
314 Fluid applied air vapor barrier	3,638	SF	\$5.50	\$20,009
315				
316 4" Mineral fiber insulation at Trespa cladding -	6,581	SF	\$4.50	\$29,615
317 Fluid applied air vapor barrier	6,581	SF	\$5.50	\$36,196
318 <b>07 21 00 Thermal Insulation Total</b>				<b>\$541,964</b>
319				
320 <b>07 00 02* Roofing &amp; Flashing</b>				
321 <b>07 54 00 Thermoplastic Membrane Roofing</b>				
322 <b>07 62 00 Sheet Metal Flashing and Trim</b>				
323 <b>07 72 00 Roof Accessories</b>				
324 Single-ply PVC membrane roofing system	65,518	SF		
325 Type 1; Main roof, lower roof	36,386	SF	\$13.50	\$491,211
326 Type 2; Gym	8,955	SF	\$13.50	\$120,893
327 Type 3; Raised roof above Learning Commons	8,610	SF	\$13.50	\$116,235
328 Type 4; Entry walkway & Terrace	1,216	SF	\$13.50	\$16,409
329 Type 5; Auditorium	7,615	SF	\$13.50	\$102,803
330 Vertical roof membrane, 5'-6" h at raised roof	2,736	SF	\$14.50	\$39,672
331 ½" roof cover board	65,518	SF	\$2.25	\$147,414
332 6" insulation	65,518	SF	\$2.50	\$163,794
333 Vapor retarder	65,518	SF	\$1.50	\$98,276
334 Add ½" fire rated roof board @ Auditorium, Gym & raised roof area	17,565	SF	\$2.75	\$48,304
335 Add 2 layers ½" fiber cement roof board @ Auditorium	7,615	SF	\$5.00	\$38,075
336 Add acoustic insulation in flutes @ Auditorium & Gym roof deck	16,570	SF	\$1.50	\$24,855
337 Precast concrete pavers over adjustable deck pedestal system @ rc	1,216	SF	\$45.00	\$54,698
338 Polycarbonate entrance canopy	420	SF	\$185.00	\$77,700
339 Prefinished aluminum fascia/roof edge	3,054	LF	\$65.00	\$198,510
340 Roof expansion joint	1	AL	\$25,000.00	\$25,000
341				
342 Roofing Accessories				
343 Miscellaneous roof accessories	1	LS	\$22,000.00	\$22,000
344 Roof hatch	2	EA	\$3,000.00	\$6,000

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
345 Paver walkway	745	SF	\$25.00	\$18,625
346 <b>07 00 02* Roofing &amp; Flashing Total</b>				<b>\$1,810,473</b>
347				
348 <b>07 42 00 Wall Panels</b>				
349 <b>07 42 10 Aluminum Composite Metal Panels</b>				
350 Corrugated metal panel w/exposed fasteners	4,578	SF	\$60.00	\$274,680
351 5" Fiberglass thermal Z-furring	4,578	SF	\$3.50	\$16,023
352				
353 Composite metal panel w/exposed fasteners	3,638	SF	\$75.00	\$272,850
354 5" Fiberglass thermal Z-furring	3,638	SF	\$3.50	\$12,733
355				
356 Wood grain phenolic panel - Trespa @ ext wall incl's projections/	6,581	SF	\$82.00	\$539,642
357 5" Fiberglass thermal Z-furring	6,581	SF	\$3.50	\$23,034
358				
359 Phenolic panel; Ext soffit at projection/window bay	1,250	SF	\$82.00	\$102,500
360 Furring	1,250	SF	\$4.25	\$5,313
361 4" mineral fiber insulation at Trespa cladding - Exterior soffit	1,250	SF	\$4.00	\$5,000
362 <b>07 42 00 Wall Panels Total</b>				<b>\$1,251,774</b>
363				
364 <b>07 81 00 Applied Fireproofing</b>				
365 Intumescent fireproofing @ raised roof area over Learning Commons	8,610	SF	\$5.00	\$43,050
366 Intumescent fireproofing	1	LS	\$65,000.00	\$65,000
367 <b>07 81 00 Applied Fireproofing Total</b>				<b>\$108,050</b>
368				
369 <b>07 84 10 Penetration Firestopping</b>				
370 Firestopping	137,385	GSF	\$0.30	\$41,216
371 Interior penetration firestopping				
372 Top-of-partition firestopping	137,385	GSF	\$1.00	\$137,385
373 <b>07 84 10 Penetration Firestopping Total</b>				<b>\$178,601</b>
374				
375				
376 <b>08-OPENINGS</b>				
377				
378 <b>08 11 10 Hollow Metal Doors and Frames</b>				
379 Security gate 7'-0" x 7'-10", steel @ 1st Floor Corridors	2	EA	\$975.00	\$1,950
380 Hollow Metal Doors:				
381 type B1, single	41	EA	\$325.00	\$13,325
382 type B2, pair	6	EA	\$650.00	\$3,900
383 HM frames	260	EA	\$225.00	\$58,500
384 HM frames for pair doors	29	EA	\$275.00	\$7,975
385 Wood Doors:				
386 type B1, single, wood	91	EA	\$325.00	\$29,575

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
387 same as above w/applied surface both sides	13	EA	\$775.00	\$10,075
388 type B1, 5'-0" x 26'-0" swinging panel @ AV rooms	2	EA	\$25,000.00	\$50,000
389 type B2, pair, wood	13	EA	\$650.00	\$8,450
390 type C1, single, wood w/full height glass	111	EA	\$400.00	\$44,400
391 type C2, pair, w/full height glass	9	EA	\$800.00	\$7,200
392 type C3, pair, w/vision panel 0'-5" x 6'-0"	1	EA	\$800.00	\$800
393				
394 Exterior HM doors; complete	45	LEAF		
395 Type A, single	1	LEAF	\$1,800.00	\$1,800
396 Type B1, single	5	LEAF	\$1,800.00	\$9,000
397 Type B2, pair	9	PR	\$3,600.00	\$32,400
398 Type B2, 10'-0" x 8'-6" @ Receiving	1	PR	\$5,000.00	\$5,000
399 <b>08 11 10 Hollow Metal Doors and Frames Total</b>				<b>\$284,350</b>
400				
401 <b>08 14 00 Flush Wood Doors</b>				
402 <b>08 34 70 Interior Sound Control Door Assemblies</b>				
403 Premium cost for acoustical doors	40	LOC	\$250.00	\$10,000
404 <b>08 14 00 Flush Wood Doors Total</b>				<b>\$10,000</b>
405				
406 <b>08 31 10 Access Doors &amp; Frames</b>				
407 Access doors	100	EA	\$300.00	\$30,000
408 <b>08 31 10 Access Doors &amp; Frames Total</b>				<b>\$30,000</b>
409				
410 <b>08 33 10 Overhead Coiling Doors</b>				
411 <b>08 33 10 Overhead Coiling Grilles</b>				
412 Coiling drapery, security screen				
413 Cafeteria/Learning Commons; 21'-0" x 8'-0" (2 ea)	336	SF	\$55.00	\$18,480
414 Kitchen; 40'-0" x 8'-0" (1 ea)	320	SF	\$55.00	\$17,600
415 Admin area; 21'-0" x 5'-6" (1 ea)	116	SF	\$55.00	\$6,353
416				
417 OH door, 12'-0" x 10'-6" motor operated @ Makerspace	1	EA	\$8,000.00	\$8,000
418 <b>08 33 10 Overhead Coiling Doors Total</b>				<b>\$50,433</b>
419				
420 <b>08 00 01* Metal Windows</b>				
421 <b>08 41 10 Aluminum-Framed Entrances and Storefronts</b>				
422 <b>08 44 10 Glazed Aluminum Curtain Walls</b>				
423 <b>08 45 23 Fiberglass-Sandwich-Panel Assemblies</b>				
424 <b>08 51 10 Aluminum Windows</b>				
425 Aluminum entry doors including hardware	17	LEAF		
426 Type SF1, single	7	LEAF	\$3,500.00	\$24,500
427 Type SF2, pair	5	PR	\$7,000.00	\$35,000
428 School guard premium	5	LVS	\$10,000.00	\$50,000

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>429</b>				
<b>430</b>				
<b>431</b> Aluminum-Framed Entrances and Storefronts, interior				
<b>432</b> type SF1, single, aluminum/glass	3	EA	\$2,500.00	\$7,500
<b>433</b> type SF2, pair, aluminum/glass	2	PR	\$5,000.00	\$10,000
<b>434</b> School guard doors, premium	5	LVS	\$10,000.00	\$50,000
<b>435</b>				
<b>436</b> Aluminum storefronts, double glazed w/security insul glazing, sch	919	SF		
<b>437</b> Type 10A; 24'-8 1/4" x 12'-0"	1	EA	\$34,300.00	\$34,300
<b>438</b> Type 11A; 9'-6 1/4" x 12'-0"	1	EA	\$13,200.00	\$13,200
<b>439</b> Type 12A; 9'-7 1/2" x 12'-0"	2	EA	\$11,600.00	\$23,200
<b>440</b> Type 13A; 7'-6" x 12'-0"	1	EA	\$10,400.00	\$10,400
<b>441</b> Type 16A; 12'-0" x 13'-0 1/2"	1	EA	\$17,900.00	\$17,900
<b>442</b> Bay windows	2,912	SF		
<b>443</b> Type 1; 9'-3" x 12'-0"	10	EA	\$13,300.00	\$133,000
<b>444</b> Type 2; 9'-3" x 12'-0"	11	EA	\$13,300.00	\$146,300
<b>445</b> Type 2A; 9'-3" x 11'-0 1/4"	2	EA	\$12,700.00	\$25,400
<b>446</b> Type 3; 9'-3" x 11'-6"	9	EA	\$12,700.00	\$114,300
<b>447</b> Type 3C; 7'-0" x 12'-0"	1	EA	\$10,100.00	\$10,100
<b>448</b> Curtain wall/Windows	8,799	SF		
<b>449</b> Type 4; 3'-0" x 10'-1"	57	EA	\$3,500.00	\$199,500
<b>450</b> Type 5A; 3'-11" x 12'-0"	6	EA	\$5,800.00	\$34,800
<b>451</b> Type 5B; 3'-11" x 11'-6"	22	EA	\$5,800.00	\$127,600
<b>452</b> Type A1; 1'-4" x 3'-0"	1	EA	\$500.00	\$500
<b>453</b> Type A2; 2'-0" x 4'-0"	1	EA	\$1,000.00	\$1,000
<b>454</b> Type A3; 2'-0" x 12'-0"	27	EA	\$2,600.00	\$70,200
<b>455</b> Type B1; 3'-4" x 12'-0"	10	EA	\$4,400.00	\$44,000
<b>456</b> Type B1A; 3'-4" x 5'-10"	2	EA	\$1,800.00	\$3,600
<b>457</b> Type B3; 3'-4" x 7'-0"	1	EA	\$2,800.00	\$2,800
<b>458</b> Type B4; 3'-4" x 12'-0"	9	EA	\$4,400.00	\$39,600
<b>459</b> Type C1; 3'-4" x 12'-0"	14	EA	\$4,400.00	\$61,600
<b>460</b> Type D1; 5'-4" x 6'-2"	2	EA	\$3,900.00	\$7,800
<b>461</b> Type D3; 5'-4" x 12'-0"	12	EA	\$7,000.00	\$84,000
<b>462</b> Type E1; 5'-4" x 10'-0"	3	EA	\$7,000.00	\$21,000
<b>463</b> Type E2; 5'-4" x 12'-0"	6	EA	\$7,000.00	\$42,000
<b>464</b> Type F1; 7'-4" x 6'-2"	1	EA	\$5,400.00	\$5,400
<b>465</b> Type F2; 7'-4" x 10'-0"	3	EA	\$9,200.00	\$27,600
<b>466</b> Type F3; 7'-4" x 12'-0"	7	EA	\$9,600.00	\$67,200
<b>467</b> Type G1; 7'-4" x 12'-0"	11	EA	\$9,600.00	\$105,600
<b>468</b> Type H1; 9'-4" x 6'-0"	1	EA	\$7,000.00	\$7,000
<b>469</b> Type H2; 9'-4" x 10'-0"	1	EA	\$12,200.00	\$12,200
<b>470</b> Type H3; 9'-4" x 12'-0"	1	EA	\$14,000.00	\$14,000

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
471 Type I1; 9'-4" x 6'-0"	1	EA	\$7,000.00	\$7,000
472 Type I2; 9'-4" x 10'-0"	1	EA	\$12,200.00	\$12,200
473 Type I3; 9'-4" x 12'-0"	1	EA	\$12,200.00	\$12,200
474 Type K1; 11'-4" x 12'-0"	2	EA	\$17,000.00	\$34,000
475 Type L1; 13'-4" x 12'-0"	1	EA	\$17,500.00	\$17,500
476 Type M1; 10'-4" x 6'-2"	1	EA	\$8,000.00	\$8,000
477 Type N1; 6'-4" x 4'-4"	2	EA	\$3,400.00	\$6,800
478 Type N2; 6'-4" x 5'-10"	2	EA	\$4,400.00	\$8,800
479 Type O1; 6'-4" x 12'-0"	2	EA	\$9,500.00	\$19,000
480 Type Q1; 4'-4" x 7'-0"	1	EA	\$3,600.00	\$3,600
481 Type R1; 3'-4" x 6'-11" irregular shape	1	EA	\$2,900.00	\$2,900
482 Horizontal aluminum sun shades attached to CW/windows @ sout	1,755	LF	\$175.00	NIC
483 Blocking for openings	7,906	LF	\$8.00	\$63,248
484 Window caulking	7,906	LF	\$3.00	\$23,718
485 Add premium cost for translucent	360	SF	\$25.00	\$9,000
486 Allow for premium cost for security glazing	614	SF	\$375.00	\$230,250
487 <b>08 00 01* Metal Windows Total</b>				<b>\$2,142,316</b>
488				
489 <b>08 63 00 Metal-Framed Skylights</b>				
490 Glazed aluminum-framed skylight	4,015	SF	\$175.00	\$702,625
491 <b>08 63 00 Metal-Framed Skylights Total</b>				<b>\$702,625</b>
492				
493 <b>08 71 00 Door Hardware</b>				
494 <i>Interior:</i>				
495 Hardware	318	SET	\$750.00	\$238,500
496 Powered door openers	4	LOC	\$3,500.00	\$14,000
497 CR; Card reader	15	EA	\$3,000.00	\$45,000
498 RDL; Remote door un/lock	14	EA	\$3,000.00	\$42,000
499				
500 <i>Exterior:</i>				
501 Card reader	3	EA	\$3,500.00	\$10,500
502 RDL; Remote door un/lock	16	EA	\$3,500.00	\$56,000
503 <b>08 71 00 Door Hardware Total</b>				<b>\$406,000</b>
504				
505 <b>08 00 02* Glass and Glazing</b>				
506 <b>08 80 00 Glazing</b>				
507 Door sidelights	900	SF	\$55.00	\$49,500
508 Glazing to doors	1,554	SF	\$55.00	\$85,470
509				
510 Interior windows				
511 Interior	5,215	SF	\$55.00	\$286,825
512 Glazed film	4,332	SF	\$60.00	\$259,920



# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
513 Ballistic glass sliding window @ Admin	1	EA	\$2,500.00	\$2,500
514 Mirror frameless	1,454	SF	\$45.00	\$65,430
515 Graduated glass; premium	2,359	SF	\$65.00	\$153,335
516 Acoustical glass premium	505	SF	\$300.00	\$151,500
517 Interior storefront				
518 Storefront @ vestibule	3,115	SF	\$85.00	\$264,775
519 Breakout Space-A, B & C; Glazed partition/wood panel closure	3	EA	\$125,000.00	\$375,000
520 <b>08 00 02* Glass and Glazing Total</b>				<b>\$1,694,255</b>
521				
522 <b>08 90 00 Louvers and Vents</b>				
523 Metal louver	625	SF	\$85.00	\$53,125
524 <b>08 90 00 Louvers and Vents Total</b>				<b>\$53,125</b>
525				
526				
527 <b>09-FINISHES</b>				
528				
529 <b>09 29 00 Gypsum Drywall</b>				
530 Gypsum board partitions	114,616	SF		
531 Type B3; 3 5/8" metal stud, 5/8" GWB	203	SF	\$7.20	\$1,462
532 Type B4; same as type B3, add batt insulation	5,145	SF	\$8.70	\$44,762
533 Type C2; 3 5/8" metal stud, 2x 5/8" GWB	5,600	SF	\$9.40	\$52,640
534 Type C3; 3 5/8" metal stud, 2x 5/8" GWB, batt insulation	6,483	SF	\$10.90	\$70,665
535 Type C4; same as type C3, add 1hr fire rated	3,165	SF	\$11.40	\$36,081
536 Type C6; 6" metal stud, 2x 5/8" GWB, batt insulation	2,468	SF	\$12.90	\$31,837
537 Type C7; same as type C6, add 1hr fire rated	5,507	SF	\$13.40	\$73,794
538 Type C8; 8" metal stud, 2x 5/8" GWB, batt insulation	172	SF	\$14.90	\$2,563
539 Type C10; 10" metal stud, 2x 5/8" GWB, batt insulation	222	SF	\$16.90	\$3,752
540 Type D3; 3 5/8" metal stud, 2x 5/8" GWB, batt insulation	1,526	SF	\$10.90	\$16,633
541 Type D6; 6" metal stud, 2x 5/8" GWB, batt insulation	1,266	SF	\$12.90	\$16,331
542 Type E3; 3 5/8" metal stud, 3x 5/8" GWB, batt insulation	23,327	SF	\$13.10	\$305,584
543 Type E4; same as type E3, add 1hr fire rated	780	SF	\$13.60	\$10,608
544 Type E6; 6" metal stud, 3x 5/8" GWB, batt insulation	1,158	SF	\$15.30	\$17,717
545 Type E7; 10" metal stud, 3x 5/8" GWB, batt insulation	1,022	SF	\$19.30	\$19,725
546 Type E8; 8" metal stud, 3x 5/8" GWB, batt insulation	18,060	SF	\$17.30	\$312,438
547 Type E9; same as type E8, add 1hr fire rated	2,710	SF	\$17.80	\$48,238
548 Type F1; 3 5/8" metal stud, 4x 5/8" GWB, batt insulation	4,988	SF	\$15.30	\$76,316
549 Type F2; same as type F1, add 1hr fire rated	1,834	SF	\$15.80	\$28,977
550 Type F6; 6" metal stud, 4x 5/8" GWB, batt insulation	9,646	SF	\$17.30	\$166,876
551 Type F7; 8" metal stud, 4x 5/8" GWB, batt insulation	227	SF	\$19.30	\$4,381
552 Type F8; same as type F7, add 1hr fire rated	1,065	SF	\$19.80	\$21,087
553 Type H4; 4" metal C-H stud, 3x 5/8" GWB, batt insulation, 2hr rate	67	SF	\$15.10	\$1,012
554 Type H6; 6" metal C-H stud, 3x 5/8" GWB, batt insulation, 2hr rate	1,561	SF	\$17.10	\$26,693

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
555 Type J1; 2 x (3 5/8" metal stud, 5/8" GWB, batt insulation)	6,552	SF	\$17.40	\$114,005
556 Type J2; same as type J1	1,157	SF	\$17.40	\$20,132
557 Type K1; 2 x (3 5/8" metal stud, 2x5/8" GWB, batt insulation)	6,245	SF	\$21.80	\$136,141
558 Type K2; same as typeK1, add 1hr fire rated	2,460	SF	\$22.30	\$54,858
559 High Impact GWB premium	51,577	SF	\$1.00	\$51,577
560				
561 1/2" Fiberglass faced gypsum sheathing	26,668	SF	\$2.00	\$53,336
562 10" Cold formed metal framing	26,668	SF	\$12.00	\$320,016
563 5/8" GWB interior of exterior wall	26,668	SF	\$2.50	\$66,670
564				
565 1/2" Fiberglass faced gypsum sheathing	4,578	SF	\$2.00	\$9,156
566 10" Cold formed metal framing	4,578	SF	\$12.00	\$54,936
567 5/8" GWB interior of exterior wall	4,578	SF	\$2.50	\$11,445
568				
569 1/2" Fiberglass faced gypsum sheathing	3,638	SF	\$2.00	\$7,276
570 10" Cold formed metal framing	3,638	SF	\$12.00	\$43,656
571 5/8" GWB interior of exterior wall	3,638	SF	\$2.50	\$9,095
572				
573 1/2" Fiberglass faced gypsum sheathing	6,581	SF	\$2.00	\$13,162
574 10" Cold formed metal framing	6,581	SF	\$12.00	\$78,972
575 5/8" GWB interior of exterior wall	6,581	SF	\$2.50	\$16,453
576				
577 1/2" sheathing at Trespa cladding - Exterior soffit	1,250	SF	\$2.00	\$2,500
578 6" Metal stud at Trespa cladding - Exterior soffit	1,250	SF	\$9.50	\$11,875
579 5/8" GWB at Trespa cladding - Exterior soffit	1,250	SF	\$2.50	\$3,125
580				
581 GWB soffit, light cove	1,320	LF	\$35.00	\$46,200
582 GWB ceiling/soffit in classrooms	16,127	SF	\$32.00	\$516,064
583 Sloped GWB soffit @ Art.	175	SF	\$18.00	\$3,150
584 Suspended plam clouds	4,950	SF	\$55.00	\$272,250
585 Gym ceiling; suspended lay in pre painted tegular edge tectum plar	2,101	SF	\$15.00	\$31,519
586 B1; GWB ceiling @ Atrium	6,402	SF	\$15.00	\$96,030
587 <b>09 29 00 Gypsum Drywall Total</b>				<b>\$3,433,769</b>
588				
589 <b>09 30 00* Tiling</b>				
590 Quarry tile at Kitchen	1,705	SF	\$25.00	\$42,625
591 <b>09 30 00* Tiling Total</b>				<b>\$42,625</b>
592				
593 <b>09 50 01* Acoustical Ceilings</b>				
594 <b>09 51 10 Cementitious Wood Fiber Ceiling Panel</b>				
595 <b>09 51 13 Acoustical Panel Ceilings</b>				
596 <b>09 51 33 Metal Ceiling System</b>				

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
597 ACT ceilings at Corridors, Public, Admin areas, Teacher Pl	50,004	SF	\$5.00	\$250,020
598 ACT ceiling, washable in kitchen	1,705	SF	\$5.25	\$8,951
599 Circulation Corridors ceiling	13,581	SF	\$32.00	\$434,592
600 A1; ACT - MR ceiling at Toilets	6,869	SF	\$5.75	\$39,498
601 Lay in ACT ceiling at band/chorus	4,550	SF	\$5.00	\$22,750
602 <b>09 50 01* Acoustical Ceilings Total</b>				<b>\$755,811</b>
603				
604 <b>09 60 01* Resilient Flooring</b>				
605 <b>09 65 00 Resilient Floor Tile</b>				
606 <b>09 65 13 Resilient Wall Base &amp; Accessories</b>				
607 <b>09 65 66 Resilient Athletic Flooring</b>				
608 Linoleum treads & risers with rubber nosing	828	LFR	\$15.50	\$12,834
609 Linoleum tile at landings	1,717	SF	\$8.00	\$13,736
610 Acoustic underlayment under resilient flooring	52,962	SF	\$2.75	\$145,646
611 LT; Linoleum tile flooring, 13" x 13"	93,064	SF	\$7.00	\$651,448
612 LP; Plank linoleum flooring	1,100	SF	\$10.00	\$11,000
613				
614 Linoleum base	12,630	LF	\$7.00	\$88,410
615				
616 Vented rubber wall base	375	LF	\$3.00	\$1,125
617 <b>09 60 01* Resilient Flooring Total</b>				<b>\$924,199</b>
618				
619 <b>09 64 00 Wood Flooring</b>				
620 Stage wood flooring: 4" hardboard assembly- recessed:	1,590	SF	\$30.50	\$48,495
621 1/4" double tempered smooth both sides hardboard				
622 (2) layers 3/4" plywood on sleepers with insulation				
623 <b>09 64 00 Wood Flooring Total</b>				<b>\$48,495</b>
624				
625 <b>09 64 40 Wood Athletic Flooring</b>				
626 Wood athletic flooring at Gym	8,405	SF	\$25.00	\$210,125
627 <b>09 64 40 Wood Athletic Flooring Total</b>				<b>\$210,125</b>
628				
629 <b>09 67 23 Resinous Flooring</b>				
630 EP; epoxy flooring at Toilets	7,940	SF	\$15.00	\$119,100
631 <b>09 67 23 Resinous Flooring Total</b>				<b>\$119,100</b>
632				
633 <b>09 68 00 Carpeting</b>				
634 carpet at aisles	2,770	SF	\$12.00	\$33,240
635 <b>09 68 00 Carpeting Total</b>				<b>\$33,240</b>
636				
637 <b>09 72 00 Wall Coverings</b>				
638 over curved gwb partition at curved wall	3,156	SF	\$27.50	\$86,790

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
639 Fabric wrapped acoustic wall panels @ Music areas	1,443	SF	\$22.00	\$31,746
640 sloped fabric wrapped acoustic panel	8,359	SF	\$24.50	\$204,796
641 Cementitious wood fiber acoustical wall panel @ Gym	6,255	SF	\$15.00	\$93,825
642 Mural panorama wall cover; angeled @ Media, Admin Install	1,575	SF	\$1.50	\$2,363
643 Wall pads with cutout for MEH units; allow	1	AL	\$1,500.00	\$1,500
644 <b>09 72 00 Wall Coverings Total</b>				<b>\$421,019</b>
645				
646 <b>09 91 00* Painting</b>				
647 Painting				
648 SC; sealed concrete at back of house	3,288	SF	\$1.75	\$5,754
649 E1; Exposed deck, painted @ Classrooms	24,380	SF	\$1.50	\$36,570
650 Gym exposed deck, painted	8,405	SF	\$2.00	\$16,810
651 Paint	137,385	GSF	\$0.75	\$103,039
652 Paint GWB ceilings w/high performance coating at Toilets	30,893	SF	\$1.10	\$33,983
653 Auditorium ceiling; painted exposed metal deck	6,600	SF	\$2.50	\$16,500
654 Epoxy paint wainscot @ Locker/Toilet	8,234	SF	\$2.00	\$16,468
655 Paint CMU wall	12,492	SF	\$1.10	\$13,741
656 Paint drywall partitions	273,034	SF	\$0.95	\$259,382
657 Paint door frames	318	EA	\$85.00	\$27,030
658 Paint door	318	EA	\$65.00	\$20,670
659 <b>09 91 00* Painting Total</b>				<b>\$549,947</b>
660				
661				
662 <b>10-SPECIALTIES</b>				
663				
664				
665 <b>10 00 01 Specialties</b>				
666 Operable partitions	5,440	SF	\$90.00	\$489,600
667 <b>10 00 01 Specialties Total</b>				<b>\$489,600</b>
668				
669 <b>10 11 00 Visual Display Boards</b>				
670 Tackboards	2,688	SF	\$18.00	\$48,384
671 Markerboards	5,376	SF	\$25.00	\$134,400
672 Tackable wall; allow	3,000	SF	\$18.00	\$54,000
673				
674 Academic areas:				
675 Magnetic writing surface	6,400	SF	\$25.00	\$160,000
676 <b>10 11 00 Visual Display Boards Total</b>				<b>\$396,784</b>
677				
678 <b>10 14 23 Signage</b>				
679 Signage				
680 Commerative plaque	2	LOC	\$1,500.00	\$3,000

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
681 Dimensional characters; School name	1	AL	\$5,000.00	\$5,000
682 Plastic panel signs for room identification, way finding, hazard identification	1	AL	\$7,500.00	\$7,500
683 Framed paper signs	1	AL	\$2,180.00	\$2,180
684 Miscellaneous signage	137,385	GSF	\$0.50	\$68,693
685 <b>10 14 23 Signage Total</b>				<b>\$86,373</b>
686				
687 <b>10 21 13 Plastic Toilet Compartments</b>				
688 Toilet compartments (plastic laminate)				
689 Toilet compartments	20	EA	\$1,200.00	\$24,000
690 Toilet compartments - ADA	14	EA	\$1,400.00	\$19,600
691 Urinal screen	20	EA	\$800.00	\$16,000
692 <b>10 21 13 Plastic Toilet Compartments Total</b>				<b>\$59,600</b>
693				
694 <b>10 21 23 Cubicle Curtains, Tracks &amp; Hardware</b>				
695 Curtain track, carriers and curtains	2	EA	\$200.00	\$400
696 <b>10 21 23 Cubicle Curtains, Tracks &amp; Hardware Total</b>				<b>\$400</b>
697				
698 <b>10 26 00 Wall Protection</b>				
699 Wall & corner guards				
700 Stainless steel corner guards	1	LS	\$10,000.00	\$10,000
701 <b>10 26 00 Wall Protection Total</b>				<b>\$10,000</b>
702				
703 <b>10 28 13 Toilet Accessories</b>				
704 Toilet accessories				
705 Combination PTD/WR unit	8	EA	\$150.00	\$1,200
706 Towel dispenser/waste receptacle	45	EA	\$100.00	\$4,500
707 Soap dispensers	45	EA	\$35.00	\$1,575
708 Toilet paper dispensers	48	EA	\$65.00	\$3,120
709 Sanitary napkin disposal units	21	EA	\$250.00	\$5,250
710 Robe hook	15	EA	\$25.00	\$375
711 Fold-down shower seat	1	EA	\$200.00	\$200
712 Grab bars	28	PR	\$160.00	\$4,480
713 Mirrors - in private bathrooms	14	EA	\$150.00	\$2,100
714 Mop holder w/shelf (Janitors)	6	EA	\$180.00	\$1,080
715 <b>10 28 13 Toilet Accessories Total</b>				<b>\$23,880</b>
716				
717 <b>10 44 13 Fire Protection Specialties</b>				
718 Fire extinguisher cabinets				
719 Fully recessed/non-rated	14	EA	\$450.00	\$6,182
720 Semi-recessed/non-rated	6	EA	\$300.00	\$1,800
721 <b>10 44 13 Fire Protection Specialties Total</b>				<b>\$7,982</b>
722				

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>723 10 51 24 Phenolic-Core Lockers</b>				
724 Lockers				
725 Athletic / PE lockers: metal 2-tier 30"h. x 15"w x 15"d	50	EA	\$250.00	\$12,500
726 Kitchen staff lockers, single tier, 12" x 12" x 6' high	6	EA	\$250.00	\$1,500
727 Student lockers 15"x12"x36" w/angled top, phenolic w/plam finisl	660	EA	\$385.00	\$254,100
728 Angles at lockers	825	LF	\$35.00	\$28,875
<b>729 10 51 24 Phenolic-Core Lockers Total</b>				<b>\$296,975</b>
730				
731				
<b>732 11-EQUIPMENT</b>				
733				
<b>734 11 00 00 Equipment</b>				
735 Shop equipment	1	LS	\$25,000.00	\$25,000
736 Loading dock equipment	1	LS	\$10,000.00	\$10,000
<b>737 11 00 00 Equipment Total</b>				<b>\$35,000</b>
738				
<b>739 11 31 00 Appliances</b>				
740 Residential Appliances				
741 Refrigerator/Freezer, microwave oven	5	RMS	\$1,700.00	\$8,500
742 Dishwasher	1	EA	\$1,200.00	\$1,200
743 Undercounter refrigerator @ Nurse	1	EA	\$1,200.00	\$1,200
<b>744 11 31 00 Appliances Total</b>				<b>\$10,900</b>
745				
<b>746 11 40 00 Food Service Equipment</b>				
747 Food service equipment				
748 Dining & Food Service (Budget provided, July 19, 2019)	1	AL	\$415,270.00	\$415,270
<b>749 11 40 00 Food Service Equipment Total</b>				<b>\$415,270</b>
750				
<b>751 11 52 13 Projection Screens</b>				
752 Projection Screens				
753 Motorized projection screen; Auditorium	1	EA	\$17,000.00	\$17,000
754 Projection screen - Media Center, room 1250	2	EA	\$3,000.00	\$6,000
<b>755 11 52 13 Projection Screens Total</b>				<b>\$23,000</b>
756				
<b>757 11 61 00 Theater and Stage Equipment</b>				
758 Auditorium/Theatre Equipment				
759 AV	1	AL	\$200,000.00	\$200,000
760 Lighting	1	AL	\$129,018.00	\$129,018
761 Dimming	1	AL	\$95,749.00	\$95,749
762 Rigging	1	AL	\$158,300.00	\$158,300
763 Curtains	1	AL	\$33,854.00	\$33,854
764 Orchestra	1	AL	\$175,000.00	FF&E

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
765 Gym AV sound system	1	AL	\$120,000.00	\$120,000
766 Cafeteria AV	1	AL	\$50,000.00	\$50,000
767 Band and chorus AV	1	AL	\$60,000.00	\$60,000
768 Aud. seating; stacked (48), fixed (321), removeable (46)	1	AL	\$106,445.00	\$106,445
769 <b>11 61 00 Theater and Stage Equipment Total</b>				<b>\$953,366</b>
770				
771 <b>11 66 23 Gymnasium Equipment</b>				
772 Gymnasium equipment				
773 Shot clock/shot timer	1	EA	\$1,250.00	\$1,250
774 Pull up bar	1	EA	\$850.00	\$850
775 Stall bar	1	EA	\$850.00	\$850
776 Vertical ladder	1	EA	\$550.00	\$550
777 Rope hoist	1	EA	\$500.00	\$500
778 Overhead mounted folding backstops w/glass backboards	6	EA	\$6,500.00	\$39,000
779 Sleeves & floor plates for badminton & volleyball uprights; allow	2	SETS	\$4,000.00	\$8,000
780 Gym equipment controls-power touch	1	LS	\$5,000.00	\$5,000
781 Gym wall safety pads to be 8'-8" high	2,634	SF	\$18.00	\$47,412
782 <b>11 66 23 Gymnasium Equipment Total</b>				<b>\$103,412</b>
783				
784 <b>11 66 53 Gymnasium Dividers</b>				
785 Gym motorized divider curtains	1	EA	\$20,000.00	\$20,000
786 <b>11 66 53 Gymnasium Dividers Total</b>				<b>\$20,000</b>
787				
788 <b>11 66 80 Scoreboards</b>				
789 Electronic scoreboard	1	EA	\$7,500.00	\$7,500
790 <b>11 66 80 Scoreboards Total</b>				<b>\$7,500</b>
791				
792				
793 <b>12-FURNISHING</b>				
794				
795 <b>12 24 12 Roller Shades</b>				
796 Window treatment, manually operated roller shades	10,288	SF	\$6.00	\$61,728
797 motorized roller shades @ exterior CW and SF	1,456	SF	\$10.00	\$14,560
798 motorized shade units at skylights	4,015	SF	\$10.00	\$40,150
799 roller shade at interior doors w/lites & glazed partitions	5,569	SF	\$4.00	\$22,276
800 <b>12 24 12 Roller Shades Total</b>				<b>\$138,714</b>
801				
802 <b>12 35 53 Caswork</b>				
803 Academic areas: classrooms, science, media, music, vocational, spe				
804 Bench; wood veneer cantilevered w/ptd supports	69	LF	\$350.00	\$24,150
805 Epoxy counter 24" wide	325	LF	\$325.00	\$105,625
806 Plam admin desk, curved @ Admin	20	LF	\$500.00	\$10,000

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
807 Plam base cabinet	35	LF	\$205.00	\$7,175
808 Plam base cabinet; mobile on casters	175	EA	\$550.00	\$96,250
809 Plam counter 24" wide	1,425	LF	\$200.00	\$285,000
810 Plam tall cabinets	4	EA	\$1,000.00	\$4,000
811 Plam tall cabinets w/tackable surface	3	EA	\$1,250.00	\$3,750
812 Plam upper cabinet	197	LF	\$175.00	\$34,475
813 Plam work counter oval @ Admin	10	LF	\$350.00	\$3,500
814 Shadow relief	125	LF	\$1,200.00	\$150,000
815 Administration areas, Offices, Medical:				
816 plam custom base & upper cabinets w/solid surface counter	20	LF	\$715.00	\$14,300
817 tackable surface backsplash	160	SF	\$24.00	\$3,840
818 Interior panel grille	450	LF	\$150.00	\$67,500
819 (4) Adj shelves 12" wide melamine	602	LF	\$140.00	\$84,280
820 (6) Adj shelves 12" wide melamine @ Media	56	LF	\$210.00	\$11,760
821 Other areas:				
822 Mail slots, melamine	16	LF	\$250.00	\$4,000
823 <b>12 35 53 Caswork Total</b>				<b>\$909,605</b>
824				
825 <b>12 48 13 Entrance Mats &amp; Frames</b>				
826 <i>Entrance mats</i>				
827 RG; Vestibule	396	SF	\$35.00	\$13,860
828 <b>12 48 13 Entrance Mats &amp; Frames Total</b>				<b>\$13,860</b>
829				
830 <b>12 66 00 Telescoping Stands</b>				
831 Motorized telescoping bleachers, motorized	760	SEAT	\$100.00	\$76,000
832 <b>12 66 00 Telescoping Stands Total</b>				<b>\$76,000</b>
833				
834				
835 <b>13-SPECIAL CONSTRUCTION</b>				
836				
837 <b>13 00 00 Special Construction</b>				
838 <i>No work in this section</i>				
839 <b>13 00 00 Special Construction Total</b>				
840				
841				
842 <b>14-CONVEYING EQUIPMENT</b>				
843				
844 <b>14 24 00* Hydraulic Elevators</b>				
845 Elevators; 3,500#, 4 stops	1	EA	\$205,000.00	\$205,000
846 <b>14 24 00* Hydraulic Elevators Total</b>				<b>\$205,000</b>
847				
848				



# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>849 21 - 23-MECHANICAL</b>				
<b>850</b>				
<b>851 21 00 00* Fire Protection</b>				
<b>852</b> Upright Sprinkler Heads	260	EA	\$390.00	\$101,400
<b>853</b> Pendent Sprinkler Heads	817	EA	\$415.00	\$339,055
<b>854</b> Pendent/Upright Sprinkler Heads	120	EA	\$510.00	\$61,200
<b>855</b> Upright Sprinkler Heads ( Gym)	70	EA	\$425.00	\$29,750
<b>856</b> Upright Sprinkler Heads ( Auditorium)	40	EA	\$425.00	\$17,000
<b>857</b> Upright Sprinkler Heads ( Skylights)	16	EA	\$440.00	\$7,040
<b>858</b> Sidewall Sprinkler Heads	121	EA	\$514.00	\$62,194
<b>859</b> Window Sprinkler Heads	22	EA	\$650.00	\$14,300
<b>860</b> Dry Sprinkler Heads	16	EA	\$495.00	\$7,920
<b>861</b> 8" Water Service	1	EA	\$6,250.00	\$6,250
<b>862</b> 6" Alarm Valves w/ trim	1	EA	\$5,560.00	\$5,560
<b>863</b> 6" Backflow Preventer	1	EA	\$8,500.00	\$8,500
<b>864</b> Zone control w/ standpipe (SCVA)	14	EA	\$3,650.00	\$51,100
<b>865</b> 6" Riser Valves	2	EA	\$950.00	\$1,900
<b>866</b> 6" FSP W/ Standpipe	5	EA	\$2,250.00	\$11,250
<b>867</b> 4" FSP W/ Standpipe	3	EA	\$2,045.00	\$6,135
<b>868</b> Fire Dept. Connections	1	EA	\$2,650.00	\$2,650
<b>869</b> Riser Valve w/ tamper switch	2	EA	\$750.00	\$1,500
<b>870</b> Main piping:				
<b>871</b> - 6"	1,108	LF	\$80.00	\$88,640
<b>872</b> Misc. Valves	1	LS	\$4,500.00	\$4,500
<b>873</b> Commissioning	1	LS	\$1,250.00	\$1,250
<b>874</b> Lifting	1	LS	\$3,800.00	\$3,800
<b>875</b> Testing	1	LS	\$3,650.00	\$3,650
<b>876</b> Coordination	1	LS	\$8,100.00	\$8,100
<b>877</b> Coring, Sleeves & sleeves	1	LS	\$5,450.00	\$5,450
<b>878</b> Seismic Restraints	1	LS	\$5,900.00	\$5,900
<b>879</b> Shop drawings/hydraulic calculations	1	LS	\$8,000.00	\$8,000
<b>880 21 00 00* Fire Protection Total</b>				<b>\$863,994</b>
<b>881</b>				
<b>882 22 00 00* Plumbing</b>				
<b>883</b> 6" Water Service w/ sub metera	1	EA	\$9,500.00	\$9,500
<b>884</b> Hot Water Heater & Storage				
<b>885</b> - WH-1	1	EA	\$65,000.00	\$65,000
<b>886</b> - WH-2	1	EA	\$5,500.00	\$5,500
<b>887</b> Mixing Valves	1	EA	\$2,450.00	\$2,450
<b>888</b> Circulating Pumps	2	EA	\$1,050.00	\$2,100
<b>889</b> Expansion Tank	1	EA	\$2,200.00	\$2,200
<b>890</b> 4" Backflow Preventers	1	EA	\$5,560.00	\$5,560

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
891 Pressure Reducing Station	1	EA	\$3,650.00	\$3,650
892 1" Backflow Preventers	2	EA	\$1,850.00	\$3,700
893 Grease Interceptor System 8,000 gal	1	EA	\$48,500.00	\$48,500
894 Grease Trap	1	EA	\$3,850.00	\$3,850
895 Oily Water Separator	1	EA	\$4,580.00	\$4,580
896 Acid Neutralization Tank	2	EA	By Others	
897 Condensate Pump:				
898 - CP-1 5 GPH	1	EA	\$950.00	\$950
899 Heat Tracing	1	LS	\$5,000.00	\$5,000
900 Elevator Sump Pump:				
901 - SP-1	1	EA	\$1,850.00	\$1,850
902 Reducer Pressure Backflow Preventer:				
903 - RBP-1	1	EA	\$2,500.00	\$2,500
904 Emergency Gas Shut Off Valve	2	EA	\$1,250.00	\$2,500
905 Fixtures				
906 Water Closet P-1	20	EA	\$2,455.00	\$49,100
907 Water Closet P-1A	31	EA	\$2,455.00	\$76,105
908 Urinal P-2	17	EA	\$2,510.00	\$42,670
909 Urinal P-2A	8	EA	\$2,510.00	\$20,080
910 Lavatory P-3	49	EA	\$2,365.00	\$115,885
911 Lavatory P-3A	28	EA	\$2,365.00	\$66,220
912 Drinking Fountain P-4	11	EA	\$3,250.00	\$35,750
913 Mop Sink P-5	5	EA	\$2,850.00	\$14,250
914 Shower P-6	2	EA	\$3,850.00	\$7,700
915 Science Room Sink P-7	40	EA	\$3,650.00	\$146,000
916 Science Room Sink P-7A	2	EA	\$3,650.00	\$7,300
917 Classroom Sink P-8	7	EA	\$2,565.00	\$17,955
918 Art Sink P-9	3	EA	\$3,250.00	\$9,750
919 Art Sink P-9A	1	EA	\$3,250.00	\$3,250
920 Eyewash/Shower P-10	5	EA	\$2,250.00	\$11,250
921 Fume Hood	3	EA	\$5,000.00	\$15,000
922 Lab Equipment	1	LS	\$25,000.00	\$25,000
923 labs & Consumer Science)	36	LS	\$385.00	\$13,860
924 Floor Clean Outs:				
925 - FCO-1	54	EA	\$725.00	\$39,150
926 Floor Drains:				
927 - 3" FD-A	14	EA	\$1,050.00	\$14,700
928 - 3" FD-B	8	EA	\$1,065.00	\$8,520
929 - 4" FD-B	5	EA	\$1,165.00	\$5,825
930 Trap Primers	16	EA	\$1,250.00	\$20,000
931 Roof Drain:				
932 - 8 RD-0	2	EA	\$1,650.00	\$3,300

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
933 - 6" RD-1	12	EA	\$1,410.00	\$16,920
934 - 5" RD-2	4	EA	\$1,220.00	\$4,880
935 - 4" RD-3	8	EA	\$1,010.00	\$8,080
936 Cup Sinks	8	EA	\$1,850.00	\$14,800
937 Wall Hydrant				
938 - WHYD-1	18	EA	\$375.00	\$6,750
939 Hose Bibbs:				
940 - HB-1	12	EA	\$285.00	\$3,420
941 VTR	9	EA	\$650.00	\$5,850
942				
943 Storm piping, below grade:				
944 - 12"	120	LF	\$125.00	\$15,000
945 - 8"	50	LF	\$85.25	\$4,263
946 - 6"	110	LF	\$62.55	\$6,881
947 - 4"	40	LF	\$43.75	\$1,750
948 Storm piping, above grade:				
949 - 10"	155	LF	\$110.00	\$17,050
950 - 8"	510	LF	\$92.35	\$47,099
951 - 6"	1,010	LF	\$65.05	\$65,701
952 - 4"	165	LF	\$45.10	\$7,442
953 Waste and vent piping, below grade:				
954 - 5"	650	LF	\$59.61	\$38,747
955 - 4"	560	LF	\$43.75	\$24,500
956 - 3"	265	LF	\$32.25	\$8,546
957 - 2"	110	LF	\$26.85	\$2,954
958 Waste and vent piping, above grade:				
959 - 4"	685	LF	\$43.10	\$29,524
960 - 3"	785	LF	\$31.55	\$24,767
961 - 2"	850	LF	\$26.25	\$22,313
962 Kitchen Waste Below grade:				
963 - 4"	510	LF	\$32.00	\$16,320
964 - 3"	40	LF	\$28.95	\$1,158
965 - 2"	290	LF	\$22.50	\$6,525
966 Acid Waste below grade:				
967 - 4"	425	LF	\$32.00	\$13,600
968 - 2"	290	LF	\$18.00	\$5,220
969 Acid Waste below grade:				
970 - 4"	295	LF	\$32.00	\$9,440
971 - 3"	210	LF	\$28.25	\$5,933
972 - 2"	265	LF	\$18.00	\$4,770
973 Potable Water Piping:				
974 - 2-1/2"	620	LF	\$48.95	\$30,349

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
975 - 2"	780	LF	\$35.75	\$27,885
976 - 1-1/2"	550	LF	\$30.45	\$16,748
977 - 1-1/4"	475	LF	\$28.35	\$13,466
978 - Branch	8,500	LF	\$25.75	\$218,875
979 Insulate Potable Water Piping:				
980 - 2-1/2"	620	LF	\$16.40	\$10,168
981 - 2"	780	LF	\$15.65	\$12,207
982 - 1-1/2"	550	LF	\$14.75	\$8,113
983 - 1-1/4"	475	LF	\$14.05	\$6,674
984 - Branch	8,500	LF	\$13.75	\$116,875
985 Gas Piping				
986 - 6"	50	LF	\$56.25	\$2,813
987 - 4"	80	LF	\$48.95	\$3,916
988 - 3"	120	LF	\$42.25	\$5,070
989 - Branch	980	LF	\$29.65	\$29,057
990 Gas Hook-ups	4	EA	\$850.00	\$3,400
991 Master Gas Valves	2	EA	\$2,850.00	\$5,700
992 Pump	1	LS	\$25,000.00	\$25,000
993 Flues to water heater	120	LF	\$65.00	\$7,800
994 Generator Gas Connection	1	EA	\$5,000.00	\$5,000
995 Kitchen	1	LS	\$50,000.00	\$50,000
996 Storm Piping Insulation	1	LS	\$25,000.00	\$25,000
997 Seismic Restraints	1	LS	\$10,500.00	\$10,500
998 Lift & Hoisting	1	LS	\$18,500.00	\$18,500
999 General Requirements				
1000 Coring, cutting and sleeves	1	LS	\$15,000.00	\$15,000
1001 Commissioning	1	LS	\$25,000.00	\$25,000
1002 Valves and specialties	1	LS	\$12,500.00	\$12,500
1003 Permits & Fees	1	LS	\$7,850.00	\$7,850
1004 Test and sterilize	1	LS	\$18,500.00	\$18,500
1005 Shop drawings	1	LS	\$16,500.00	\$16,500
1006 22 00 00* Plumbing Total				<b>\$2,126,673</b>
1007				
1008 23 00 00* HVAC				
1009 Boilers:				
1010 - B-1 & 2 3,844 MBH	2	EA	\$84,568.00	\$169,136
1011 Expantion Tank:				
1012 - ET-1 Thru 3	3	EA	\$2,150.00	\$6,450
1013 Air Separator:				
1014 - AS-1 & 2 8"	2	EA	\$3,950.00	\$7,900
1015 Buffer Tank:				
1016 - BT-1	1	EA	\$2,500.00	\$2,500

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>1017</b> Pumps:				
<b>1018</b> - P-1 & 2 HP 790 GPM	2	EA	\$12,500.00	\$25,000
<b>1019</b> - P-3 & 4 HP 800 GPM	2	EA		Pump House
<b>1020</b> - BP-1	2	EA	\$2,500.00	\$5,000
<b>1021</b> - CP-1 5 GPH	5	EA	\$450.00	\$2,250
<b>1022</b> Pumps House	1	EA	\$185,000.00	\$185,000
<b>1023</b>				
<b>1024</b> Chillers:				
<b>1025</b> - CH-1 350 Ton	1	EA	\$367,500.00	\$367,500
<b>1026</b> Rooftop Units:				
<b>1027</b> - RTU-1 22,000 CFM	1	EA	\$264,000.00	\$264,000
<b>1028</b> - RTU-2 22,000 CFM	1	EA	\$264,000.00	\$264,000
<b>1029</b> - RTU-3 22,000 CFM	1	EA	\$264,000.00	\$264,000
<b>1030</b> - RTU-4 22,000 CFM	1	EA	\$264,000.00	\$264,000
<b>1031</b> - RTU-5 15,000 CFM	1	EA	\$180,000.00	\$180,000
<b>1032</b> - RTU-6 12,000 CFM	1	EA	\$144,000.00	\$144,000
<b>1033</b> - RTU-7 2,000 CFM	1	EA	\$28,000.00	\$28,000
<b>1034</b> Make Up Units:				
<b>1035</b> - MAU-1 5,000 CFM	1	EA	\$32,500.00	\$32,500
<b>1036</b> Exhaust Fans:				
<b>1037</b> - EF-1 2,500 CFM	1	EA	\$3,250.00	\$3,250
<b>1038</b> - EF-2 2,500 CFM	1	EA	\$3,250.00	\$3,250
<b>1039</b> - EF-3 500 CFM	1	EA	\$980.00	\$980
<b>1040</b> - EF-4 500 CFM	1	EA	\$980.00	\$980
<b>1041</b> - EF-5 250 CFM	1	EA	\$685.00	\$685
<b>1042</b> - EF-6 250 CFM	1	EA	\$685.00	\$685
<b>1043</b> - SEF-1 50,000 CFM	1	EA	\$32,500.00	\$32,500
<b>1044</b> - SEF-2 50,000 CFM	1	EA	\$32,500.00	\$32,500
<b>1045</b> - SEF-3 50,000 CFM	1	EA	\$32,500.00	\$32,500
<b>1046</b> - SEF-4 50,000 CFM	1	EA	\$32,500.00	\$32,500
<b>1047</b> - KEF-1 4,170 CFM	1	EA	\$4,500.00	\$4,500
<b>1048</b> - FEF-1 1,200 CFM	1	EA	\$2,100.00	\$2,100
<b>1049</b> - FEF-2 1,200 CFM	1	EA	\$2,100.00	\$2,100
<b>1050</b> - FEF-3 1,200 CFM	1	EA	\$2,100.00	\$2,100
<b>1051</b> VAV Boxes:				
<b>1052</b> - VAV-8	150	EA	\$1,050.00	\$157,500
<b>1053</b> Radiant Heat Panels:				
<b>1054</b> - R1	2,525	LF	\$135.00	\$340,875
<b>1055</b> Fin-Tube Radiators:				
<b>1056</b> - FT-1	100	LF	\$90.00	\$9,000
<b>1057</b> Cabinet & Unit Heaters:				
<b>1058</b> - CUH-1,2, 7 thru 16 350 MBH	12	EA	\$895.00	\$10,740

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
1059 - CUH-3 1050 MBH	1	EA	\$1,150.00	\$1,150
1060 - CUH-4 thru 6 450 MBH	3	EA	\$925.00	\$2,775
1061 Ductless Split Units:				
1062 - DCUe-1 1 Ton	1	EA	\$2,950.00	\$2,950
1063 - DCUe-2 2 Ton	1	EA	\$4,425.00	\$4,425
1064 - DCUe-3 2 Ton	1	EA	\$4,425.00	\$4,425
1065 - DCUe-4 1.5 Ton	1	EA	\$3,850.00	\$3,850
1066 - DCUe-5 1.5 Ton	1	EA	\$3,850.00	\$3,850
1067 - DCUe-6 1.5 Ton	1	EA	\$3,850.00	\$3,850
1068 - DCUe-7 1.5 Ton	1	EA	\$3,850.00	\$3,850
1069 Register & Diffusers:				
1070 - DD-1	22	EA	\$985.00	\$21,670
1071 - DD-2	18	EA	\$985.00	\$17,730
1072 - DD-3	16	EA	\$985.00	\$15,760
1073 - DD-4	1	EA	\$985.00	\$985
1074 - DD-5	42	EA	\$985.00	\$41,370
1075 - DD-6	2	EA	\$985.00	\$1,970
1076 - DD-7	4	EA	\$985.00	\$3,940
1077 - Slot	750	LF	\$45.00	\$33,750
1078 - E	80	EA	\$225.00	\$18,000
1079 Misc Diffusers, grills and registers	1	LS	\$5,000.00	\$5,000
1080 Fire & Motor Dampers	30	LS	\$1,850.00	\$55,500
1081 Volume Dampers	1	EA	\$40,000.00	\$40,000
1082 Flex Duct	1	LS	\$30,000.00	\$30,000
1083 Misc. Duct Accessories	1	LS	\$25,000.00	\$25,000
1084 Double Wall Galvanized Duct (Auditorium)	8,500	LBS	\$20.25	\$172,125
1085 Galvanized Duct	130,000	LBS	\$12.50	\$1,625,000
1086 Ductsox	680	LF	\$45.00	\$30,600
1087 Duct Insulation	45,000	SF	\$4.65	\$209,250
1088 Duct Insulation @ Kitchen area	1	LS	\$35,000.00	\$35,000
1089 Black iron at kitchen	2,125	LBS	\$18.50	\$39,313
1090 Duct S/S	5,000	LBS	\$20.20	\$101,000
1091 Seal Ductwork	7,500	LF	\$1.60	\$12,000
1092 Dust Collection System	1	LS	\$25,000.00	\$25,000
1093 Sound Attenuators				
1094 - SA-1S	1	EA	\$6,500.00	\$6,500
1095 - SA-1R	1	EA	\$6,500.00	\$6,500
1096 - SA-2S	1	EA	\$6,500.00	\$6,500
1097 - SA-2R	1	EA	\$6,500.00	\$6,500
1098 - SA-3S	1	EA	\$6,500.00	\$6,500
1099 - SA-3R	1	EA	\$6,500.00	\$6,500
1100 - SA-4S	1	EA	\$6,500.00	\$6,500

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
1101 - SA-4R	1	EA	\$6,500.00	\$6,500
1102 - SA-5S	1	EA	\$6,500.00	\$6,500
1103 - SA-5R	1	EA	\$6,500.00	\$6,500
1104 - SA-6S	1	EA	\$7,800.00	\$7,800
1105 - SA-6R	1	EA	\$6,200.00	\$6,200
1106 - SA-7S	1	EA	\$3,850.00	\$3,850
1107 - SA-7R	1	EA	\$3,850.00	\$3,850
1108 - SA-8	1	EA	\$4,250.00	\$4,250
1109 Hot & Chilles Water Piping				
1110 - Large Bore	9,000	LF	\$40.00	\$360,000
1111 - Small Bore	10,500	LF	\$28.00	\$294,000
1112 Insulate Hot Water Piping				
1113 - Large Bore	9,000	LF	\$16.95	\$152,550
1114 - Small Bore	10,500	LF	\$12.50	\$131,250
1115 Equipment Hook-Ups:				
1116 - 4" Boilers	2	EA	\$8,950.00	\$17,900
1117 - 8" Pump		EA		Pump House
1118 - 4" Pump	3	EA	\$2,100.00	\$6,300
1119 - 8" Chiller	1	EA	\$14,500.00	\$14,500
1120 - RCP	95	EA	\$1,075.00	\$102,125
1121 - CUH	12	EA	\$1,025.00	\$12,300
1122 - FT	2	EA	\$1,075.00	\$2,150
1123 - DD	105	EA	\$285.00	\$29,925
1124 - VAV	140	EA	\$1,105.00	\$154,700
1125 - 4" RTU Coils	6	EA	\$6,500.00	\$39,000
1126 - 2" RTU Coils	3	EA	\$2,650.00	\$7,950
1127 VFD	1	LS	\$20,000.00	\$20,000
1128 Glycol:				
1129 - GF-1 & 2	2	EA	\$6,500.00	\$13,000
1130 Combustion	1	LS	\$30,000.00	\$30,000
1131 Flues S/S boiler	380	LF	\$120.00	\$45,600
1132 Seismic Restraints	1	LS	\$10,500.00	\$10,500
1133 Misc. Valves & specialties	1	LS	\$15,000.00	\$15,000
1134 Commissioning support	1	LS	\$32,000.00	\$32,000
1135 Controls	1	LS	\$755,000.00	\$755,000
1136 Testing & Balancing	1	LS	\$35,600.00	\$35,600
1137 Rigging & Lifting	1	LS	\$12,500.00	\$12,500
1138 Permits & Fees	1	LS	\$8,500.00	\$8,500
1139 Shop Drawing	1	LS	\$15,500.00	\$15,500
1140 23 00 00* HVAC Total				<b>\$7,879,869</b>
1141				
1142				

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>1143 26,27,28-ELECTRICAL, COMMUNICATION, SECURITY</b>				
<b>1144</b>				
<b>1145 26 00 00* Electrical</b>				
<b>1146 27 00 00 Technology</b>				
<b>1147 28 00 00 Integrated Electronic Security System</b>				
<b>1148</b> Switchgear, Panelboards, Transformers				
<b>1149</b> 3000/2500 Amp Main Switchboard	1	LS	\$110,739.20	\$110,739
<b>1150</b> Meter Pan	1	EA	\$738.10	\$738
<b>1151</b> SPD @ Swbd	1	EA	\$2,855.60	\$2,856
<b>1152</b> SPD @ Panelboard	46	EA	\$1,113.20	\$51,207
<b>1153</b> 100 Amp Panel Board	14	EA	\$4,048.66	\$56,681
<b>1154</b> 225 Amp Panel Board	9	EA	\$6,749.38	\$60,744
<b>1155</b> 225 Amp Panel Board, 2-Section	9	EA	\$11,521.62	\$103,695
<b>1156</b> 400 Amp Panel Board	4	EA	\$9,571.10	\$38,284
<b>1157</b> 400 Amp Panel Board, 2-Section	1	EA	\$16,443.90	\$16,444
<b>1158</b> 600 Amp Panel Board	2	EA	\$13,013.55	\$26,027
<b>1159</b> 800 Amp Panel Board	2	EA	\$16,577.00	\$33,154
<b>1160</b> 75 Kva Transformer	1	EA	\$7,550.40	\$7,550
<b>1161</b> 225 Kva Transformer K13	3	EA	\$42,713.00	\$128,139
<b>1162</b> 800 Amp Disconnect @ Xfmr	2	EA	\$7,381.00	\$14,762
<b>1163</b> Emergency Generator, UPS				
<b>1164</b> 350 Kw Emergency Generator, WP/Sound	1	LS	\$147,862.00	\$147,862
<b>1165</b> Autotransfer Sw 150A	1	EA	\$7,148.08	\$7,148
<b>1166</b> Autotransfer Sw 225A	1	EA	\$10,145.85	\$10,146
<b>1167</b> Autotransfer Sw 400A	1	EA	\$12,541.65	\$12,542
<b>1168</b> 150 Amp EG Quick Connect	1	EA	\$3,049.20	\$3,049
<b>1169</b> 200/150 Amp Encl Ckt Brkr	1	EA	\$1,923.90	\$1,924
<b>1170</b> 225 Amp Encl Ckt Brkr	1	EA	\$3,693.53	\$3,694
<b>1171</b> 400 Amp Encl Ckt Brkr	1	EA	\$4,283.40	\$4,283
<b>1172</b> 24KW/30Kva UPS, batteries	2	LS	\$47,432.00	\$94,864
<b>1173</b> 200 Amp Disconnect @ UPS	2	EA	\$1,923.90	\$3,848
<b>1174</b> Generator Annunciator	1	EA	\$1,621.40	\$1,621
<b>1175</b> Motors:				
<b>1176</b> Cond Pump Conn	12	EA	\$157.30	\$1,888
<b>1177</b> Install Limit Switch FBO	3	EA	\$121.00	\$363
<b>1178</b> Install Misc Gym CP FBO	8	EA	\$465.85	\$3,727
<b>1179</b> Motor Backbd Conn's, Switch	8	EA	\$779.24	\$6,234
<b>1180</b> Scoreboard Conn's, Switch	1	EA	\$779.24	\$779
<b>1181</b> Bleach Motor 20/3A Conn, Switch	7	EA	\$779.24	\$5,455
<b>1182</b> Manual Snap Switch Starter WP	5	EA	\$338.80	\$1,694
<b>1183</b> 20/2 Amp Disconnect	19	EA	\$444.07	\$8,437
<b>1184</b> 30/1 Amp Disconnect, Elev Cab	1	EA	\$444.07	\$444
<b>1185</b> 30/2 Amp Disconnect, mech	8	EA	\$584.43	\$4,675
<b>1186</b> 30 Amp Disconnect, mech,kit	16	EA	\$779.24	\$12,468



# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
1187 60 Amp Disconnect, mech, kit	5	EA	\$1,333.42	\$6,667
1188 100 Amp Disconnect	6	EA	\$1,452.00	\$8,712
1189 200 Amp Disconnect, Elev	1	EA	\$2,214.30	\$2,214
1190 200/125 Amp Disconnect WP	4	EA	\$2,214.30	\$8,857
1191 200/175 Amp Disconnect WP	4	EA	\$2,214.30	\$8,857
1192 800 Amp Disconnect CH, WP	1	EA	\$8,845.10	\$8,845
1193 Junc Box, mech controls by others	13	EA	\$66.55	\$865
1194 Install Nema 0 Motor Starter FBO	11	EA	\$356.95	\$3,926
1195 Install Nema 1 Motor Starter FBO	2	EA	\$471.90	\$944
1196 Install <=10HP VFD FBO	5	EA	\$1,367.30	\$6,837
1197 Install 20HP VFD FBO	2	EA	\$2,081.20	\$4,162
1198 Install 25HP VFD FBO	2	EA	\$2,734.60	\$5,469
1199 Install 50HP VFD FBO	4	EA	\$3,448.50	\$13,794
1200 Chiller CP Conn's	1	EA	\$3,726.80	\$3,727
1201				
1202 Power Circuitry				
1203 3/4" Emt, empty	520	LF	\$10.61	\$5,518
1204 3/4" Emt, 4#12	4,760	LF	\$13.85	\$65,924
1205 3/4" Emt, 4#10	2,880	LF	\$14.98	\$43,149
1206 1" Emt, 4#8	600	LF	\$21.47	\$12,879
1207 1 1/4" Emt, 4#4	200	LF	\$29.05	\$5,810
1208 1 1/4" Emt, 4#2	2,790	LF	\$32.34	\$90,238
1209 1 1/2" Emt, 4#1	850	LF	\$38.81	\$32,990
1210 2" Emt, 4 1/0	930	LF	\$44.39	\$41,287
1211 2" Emt, 4 2/0	800	LF	\$48.07	\$38,459
1212 2" Emt, 4 3/0	200	LF	\$53.49	\$10,699
1213 2 1/2" Emt, 4 4/0	80	LF	\$62.02	\$4,962
1214 2 1/2" Emt, 4 250Mcm	60	LF	\$66.48	\$3,989
1215 3" Emt, 4 350Mcm	420	LF	\$81.49	\$34,227
1216 3 1/2" Emt, 4 500 Mcm	1,820	LF	\$105.02	\$191,129
1217 4#6 MI Cable	50	LF	\$41.27	\$2,064
1218 4#2 MI Cable	200	LF	\$83.99	\$16,797
1219				
1220 Service Grounding	1	LS	\$5,033.60	\$5,034
1221 Lightning Protection System (Preventor)	1	LS	\$34,485.00	\$34,485
1222				
1223 Light Fixtures				
1224 Type G4	80	EA	\$886.93	\$70,954
1225 Type LK24	24	EA	\$474.32	\$11,384
1226 Type LP8	9	EA	\$1,185.80	\$10,672
1227 Type LR2	1,173	EA	\$411.40	\$482,572
1228 Type LS2	1	EA	\$411.40	\$411
1229 Type LS4	41	EA	\$310.97	\$12,750
1230 Type LS4A	22	EA	\$310.97	\$6,841
1231 Type LS8	21	EA	\$621.94	\$13,061

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
1232 Type LUL	61	EA	\$310.97	\$18,969
1233 Type PC1	24	EA	\$381.15	\$9,148
1234 Type PC2	29	EA	\$381.15	\$11,053
1235 Type PC3	186	EA	\$381.15	\$70,894
1236 Type RC1	88	EA	\$381.15	\$33,541
1237 Type RC2	56	EA	\$381.15	\$21,344
1238 Type RSH	1	EA	\$393.25	\$393
1239 Type SP1	83	EA	\$617.10	\$51,219
1240 Type SL4 Exterior Wallpack	17	EA	\$701.80	\$11,931
1241 Type Exit	71	EA	\$332.75	\$23,625
1242 Type LC2	72	LF	\$114.35	\$8,233
1243 Type LC3	3,090	LF	\$114.35	\$353,326
1244 Type LWS	624	LF	\$124.03	\$77,392
1245 Type LSL	60	LF	\$130.08	\$7,805
1246				
1247 Branch Circuitry				
1248 3/4" Emt, 4#12	15,624	LF	\$12.65	\$197,635
1249 MC Cable	46,871	LF	\$5.18	\$242,733
1250 3/4" Emt, 4#10	880	LF	\$16.66	\$14,662
1251 1" Emt, 4#8	60	LF	\$21.47	\$1,288
1252 1" Emt, 4#6	160	LF	\$22.87	\$3,659
1253 Plenum Cable	9,930	LF	\$1.59	\$15,740
1254				
1255 Wiring Devices				
1256 Switches	11	EA	\$78.65	\$865
1257 Momentary Contact Switches	9	EA	\$124.03	\$1,116
1258 OS, PS Power Pack	145	EA	\$181.50	\$26,318
1259 Local Switch/Dimming Station L	226	EA	\$151.25	\$34,183
1260 Occupancy Sensor	322	EA	\$202.68	\$65,261
1261 Photo Sensor	114	EA	\$202.68	\$23,105
1262 Receptacles	512	EA	\$78.65	\$40,269
1263 Junc Boxes, Misc	5	EA	\$64.13	\$321
1264 Receptacles GFI	217	EA	\$96.80	\$21,006
1265 Receptacles Quad	317	EA	\$129.47	\$41,042
1266 Receptacles GFI Quad	5	EA	\$159.72	\$799
1267 Receptacles GFI WP	24	EA	\$177.87	\$4,269
1268 Receptacles w/ I/O Module	28	EA	\$96.80	\$2,710
1269 Receptacles Quad w/ I/O Modules	3	EA	\$181.50	\$545
1270 Receptacle USB	13	EA	\$102.85	\$1,337
1271 Cord Reel Receptacle	7	EA	\$580.80	\$4,066
1272 Cond Pump Conn	12	EA	\$133.10	\$1,597
1273 Install Leak Det FBO	12	EA	\$121.00	\$1,452
1274 Sol Valve Conn	2	EA	\$121.00	\$242
1275 FS Conn	7	EA	\$121.00	\$847
1276 GSM Conn	7	EA	\$121.00	\$847

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
1277 Floor Power Outlet	2	EA	\$399.30	\$799
1278 4-Pole Lighting Contactor	1	EA	\$635.25	\$635
1279 12-Pole Lighting Contactor	1	EA	\$1,500.40	\$1,500
1280 EPO Pushbutton	3	EA	\$229.90	\$690
1281 Fume Hood Conn	3	EA	\$157.30	\$472
1282 Manual Snap Switch Starter VRF, VAV,misc	177	EA	\$181.50	\$32,126
1283 20/1 Amp Receptacle L5-20	11	EA	\$84.70	\$932
1284 20/1 Amp Eqpt Conn	12	EA	\$66.55	\$799
1285 30/1 Amp Receptacle L5-30	11	EA	\$117.98	\$1,298
1286 30 Amp Receptacle	3	EA	\$130.08	\$390
1287 30 Amp Stage Receptacle / strip conn	8	EA	\$798.60	\$6,389
1288 50 Amp Receptacle	1	EA	\$193.60	\$194
1289 60 Amp Receptacle, weld	2	EA	\$205.70	\$411
1290				
1291 Fire Alarm				
1292 Teflon Cable	33,345	LF	\$2.34	\$78,113
1293 3" Rigid, Riser Cables	60	LF	\$114.95	\$6,897
1294 Pull Station	24	EA	\$229.90	\$5,518
1295 Audible/Visual	205	EA	\$347.88	\$71,314
1296 Audible/Visual WP	1	EA	\$405.35	\$405
1297 Smoke Detector	158	EA	\$387.20	\$61,178
1298 CO Detector	5	EA	\$350.90	\$1,755
1299 Beam-Type Smoke Detector	11	EA	\$1,052.70	\$11,580
1300 Strobe	51	EA	\$229.90	\$11,725
1301 WP Beacon	2	EA	\$287.38	\$575
1302 Duct Detector	40	EA	\$889.35	\$35,574
1303 Central Equipment, testing, Voice Command	1	LS	\$66,477.40	\$66,477
1304 Radio Box, Antenna, wiring	1	EA	\$4,549.60	\$4,550
1305 Fused Disc	1	EA	\$738.10	\$738
1306 Door Release DH	6	EA	\$459.80	\$2,759
1307 Ansul Conn's	1	LS	\$895.40	\$895
1308 Remote Mic EVAC	1	EA	\$580.80	\$581
1309 Annunciator Panel	3	EA	\$2,323.20	\$6,970
1310 Misc Connections, Relays	25	EA	\$272.25	\$6,806
1311 Knox Box	1	EA	\$520.30	\$520
1312				
1313 Communications System				
1314 MDF Rack, PP's, Terms	1	EA	\$14,762.00	\$14,762
1315 IDF Rack, PP's, Terms	3	EA	\$7,381.00	\$22,143
1316 4" Floor Sleeves	16	EA	\$229.90	\$3,678
1317 4" Wall Sleeves	16	EA	\$229.90	\$3,678
1318 Main Ground Bar	1	EA	\$1,476.20	\$1,476
1319 Tel Ground Bar	3	EA	\$738.10	\$2,214
1320 #3/0G Wire	600	LF	\$9.19	\$5,511
1321 Cable Tray 24" Alum	1,570	LF	\$41.62	\$65,350

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
1322 12 Strand Multi-Mode Fiber	600	LF	\$6.18	\$3,710
1323 6 Strand Multi-Mode Fiber	600	LF	\$4.30	\$2,577
1324 Cu Distr Cable	600	LF	\$10.29	\$6,171
1325 1" EMT CDT	172	LF	\$14.40	\$2,477
1326 2" EMT CDT	1,040	LF	\$22.90	\$23,819
1327 4" EMT Cdt	200	LF	\$34.64	\$6,928
1328 Cat 6 Cable	103,500	LF	\$1.59	\$164,058
1329 WAP Outlet AN 2c	14	EA	\$89.54	\$1,254
1330 Tel Outlet	60	EA	\$72.60	\$4,356
1331 Data Outlet	2	EA	\$72.60	\$145
1332 Data Duplex Outlet 2c	78	EA	\$89.54	\$6,984
1333 Tel/Data Outlet 3c	76	EA	\$111.93	\$8,506
1334 Floor Tel/Data Outlet 3c	6	EA	\$399.30	\$2,396
1335 Tel/Data Outlet T 2c	47	EA	\$89.54	\$4,208
1336 TVE 2c	50	EA	\$169.40	\$8,470
1337 TVC 2c	2	EA	\$169.40	\$339
1338				
1339 Clock/ Public Address System:				
1340 2 1/2" Emt, Riser Cables	50	LF	\$66.74	\$3,337
1341 3/4" EMT Cdt	2,730	LF	\$11.93	\$32,571
1342 1" EMT Cdt	2,530	LF	\$14.40	\$36,429
1343 Comm Cable	14,100	LF	\$1.59	\$22,350
1344 Main Sound Rack	1	LS	\$48,884.00	\$48,884
1345 Local Sound System Rack	2	EA	\$7,792.40	\$15,585
1346 Outlet S Speaker	232	EA	\$254.10	\$58,951
1347 Outlet S Speaker WP	19	EA	\$344.85	\$6,552
1348 Volume Control	26	EA	\$181.50	\$4,719
1349 Master Clock GPS	1	EA	\$5,493.40	\$5,493
1350 Clock Antenna	1	EA	\$1,863.40	\$1,863
1351 Wireless Clock Transceiver	1	EA	\$2,855.60	\$2,856
1352 Wireless Clock Repeater	4	EA	\$1,427.80	\$5,711
1353 Clock, wireless	73	EA	\$254.10	\$18,549
1354				
1355 A/V System:				
1356 1" EMT Cdt	1,600	LF	\$14.40	\$23,038
1357 BP Button Panel	41	EA	\$99.83	\$4,093
1358 R1 Receptacle Panel	41	EA	\$99.83	\$4,093
1359 V1 Video Projector	41	EA	\$99.83	\$4,093
1360 S1 Speaker	82	EA	\$99.83	\$8,186
1361 AV Eqpt, Inst, LV Wiring - Proj/Assist List	41	RM		
1362 J1	2	EA	\$99.83	\$200
1363 Data Outlet P Projector	1	EA	\$99.83	\$100
1364 Screen	1	EA	\$99.83	\$100
1365 R2 Receptacle Panel	4	EA	\$169.40	\$678
1366 R3 Receptacle Panel	4	EA	\$169.40	\$678

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
1367 Speaker S1 Backbox	4	EA	\$99.83	\$399
1368 Speaker S2 Backbox	4	EA	\$99.83	\$399
1369 Speaker S3 Backbox	14	EA	\$99.83	\$1,398
1370 AV Rack Enclosure	1	EA	\$459.80	\$460
1371 AV Eqpt, Installation, LV Wiring - ALLOW	1	LS		
1372 Gym Sound System Mat'l Package	1	LS	\$45,000.00	\$45,000
1373 Auditorium AV Roughin	1	LS	\$45,000.00	\$45,000
1374 )				
1375 Theater Lighting & Control System:ALLOW (Eqpt in "Equipment Sec				
1376 Lighting and Controls included in "Equipment Section"				
1377 Theat Lighting & Power Roughin	1	LS	\$30,000.74	\$30,001
1378 Theat Lighting Controls Roughin	1	LS	\$10,000.25	\$10,000
1379				
1380 Security Intrusion Alarm System:				
1381 Power Supply Junc Box, 120v	1	EA	\$459.80	\$460
1382 Central Eqpt	1	EA	\$14,713.60	\$14,714
1383 3/4" Emt, 4#12	40	LF	\$13.85	\$554
1384 Plenum Cables	4,800	LF	\$1.59	\$7,608
1385 3/4" Emt	720	LF	\$11.93	\$8,590
1386 CR Card Reader	9	EA	\$810.70	\$7,296
1387 K Keypad	2	EA	\$810.70	\$1,621
1388 EL Electric Lock	5	EA	\$490.05	\$2,450
1389 EH Electric Hinge	30	EA	\$490.05	\$14,702
1390 Intercom	2	EA	\$520.30	\$1,041
1391 PT Install Power Transfer Hinge FBO	16	EA	\$411.40	\$6,582
1392 REX Req to Exit	21	EA	\$290.40	\$6,098
1393 DC Door Position Sw	54	EA	\$199.65	\$10,781
1394 M Motion Sensor	71	EA	\$411.40	\$29,209
1395 TS Door Switch	16	EA	\$181.50	\$2,904
1396 DJ Door Junc Box	16	EA	\$139.15	\$2,226
1397				
1398 CCTV System:				
1399 3/4" EMT Cdt	870	LF	\$11.41	\$9,927
1400 Signal Cables	11,400	LF	\$1.59	\$18,070
1401 Monitoring/Recording Eqpt	1	LS	\$33,577.50	\$33,578
1402 Viewing Console	2	EA	\$1,161.60	\$2,323
1403 Data Outlet CAM, Camera	55	EA	\$1,294.70	\$71,209
1404 Data Outlet CAM, Camera WP	15	EA	\$1,996.50	\$29,948
1405				
1406 BDA System	1	LS	\$136,000.00	\$136,000
1407 Area of Rescue Assistance	1	LS	\$20,000.00	\$20,000
1408				
1409 Temp Power and Lighting	1	LS	\$89,540.00	\$89,540
1410 <b>26,27,28-ELECTRICAL, COMMUNICATION, SECURITY TOTAL</b>				<b>\$5,523,083</b>
1411				

# Fuller Middle School

Framingham, MA

137,385 GSF

## BUILDING DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
1412				
1413 <b>31-EARTHWORK</b>				
1414				
1415 <b>31 00 00 Earthwork</b>				
1416 See Sitework				
1417 <b>31 00 00 Earthwork Total</b>				<hr/>
1418				
1419				
1420				
1421				
1422				
1423				
1424				
1425				
1426				
1427				
1428				
1429				
1430				

# Fuller Middle School

Framingham, MA

## SITWORK DIRECT TRADE COST DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>9 02-EXISTING CONDITIONS</b>				
<b>10</b>				
<b>11 02 41 00 Demolition</b>				
12 BP#1				BP#1
13 G1020.01 Building Demolition				\$0
14 02 30 00 Building Demolition				\$0
15 Building demoltion				See Main Summ:
<b>16 02 41 00 Demolition Total</b>				<u>\$0</u>
<b>17</b>				
<b>18</b>				
<b>19 31-EARTHWORK</b>				
<b>20</b>				
<b>21 31 00 00 Earthwork</b>				
22 Site prep	258,370	SF	\$1.00	\$258,370
23 Trench and backfill only	313	LF	\$45.00	\$14,085
24 Baseball field	0	0	\$0.00	Existing to Remo
<b>25 31 00 00 Earthwork Total</b>				<u>\$272,455</u>
<b>26</b>				
<b>27 31 10 00 Site Clearing</b>				
28 Site clearing	7	ACRE	\$5,000.00	BP#1
29 Safety barricade	1	AL	\$60,000.00	BP#1
30 Construction fence, install, maintain, remove & reinstall; f	11,344	LF	\$12.00	BP#1
31 Double construction gate	2	PR	\$2,500.00	BP#1
32 Temporary construction entrance	2	LOC	\$7,000.00	BP#1
33 Add premium for moving and reinstalling for 3 phases	1	LS	\$37,385.00	BP#1
34 Temporary Jersey Barriers; purchase and install	3,145	LF	\$65.00	BP#1
35 Temp signs	1	LS	\$3,000.00	BP#1
36 Wash down/re-fueling/parking allowance	3,000	SF	\$2.00	BP#1
37 Temporary pavement	47,106	SF	\$3.00	BP#1
38 Temporary sedimentation and runoff basin	7,348	SF	\$2.00	BP#1
<b>39 31 10 00 Site Clearing Total</b>				<u>\$0</u>
<b>40</b>				
<b>41 31 23 19 Dewatering and Drainage</b>				
42 Dewatering for sitework excavation; allow	1	LS	\$100,000.00	BP#1
<b>43 31 23 19 Dewatering and Drainage Total</b>				<u>\$0</u>
<b>44</b>				
<b>45 31 25 00 Erosion and Sedimentation Controls</b>				
46 Erosion control barrier	1,206	LF	\$14.00	BP#1
47 Stockpile area (all phases), qty provided	35,000	CY	\$2.50	BP#1
48 FM; discharge temp basin to existing DMH	271	LF	\$75.00	BP#1
49 Stormwater basin	3,547	SF	\$2.50	BP#1
<b>50 31 25 00 Erosion and Sedimentation Controls Total</b>				<u>\$0</u>
<b>51</b>				

# Fuller Middle School

Framingham, MA

## SITWORK DIRECT TRADE COST DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>52 32-EXTERIOR IMPROVEMENTS</b>				
<b>53</b>				
<b>54 32 12 00 Flexible Paving</b>				
<b>55</b> Existing public roadway 'Flagg Drive' to remain	0	SF	\$0.00	ETR
<b>56</b> Vehicular asphalt pavement, incl's temporary pavement	202,060	SF	\$3.00	BP#1
<b>57</b> Raised bituminous pavement (stamped)	11,716	SF	\$15.00	BP#1
<b>58</b> Gravel base to roadway & parking lot	9,445	CY	\$35.00	BP#1
<b>59</b> 32 17 00 Paving Specialties	0	0	\$0.00	BP#1
<b>60</b> Crosswalk	2,350	SF	\$2.50	BP#1
<b>61</b> Parking stall painting	302	EA	\$15.00	BP#1
<b>62</b> Parking stall painting; HC	12	EA	\$75.00	BP#1
<b>63</b> Crosswalk striping, temporary	2,440	SF	\$2.50	BP#1
<b>64</b> Temporary parking spaces, incl's HC bus	162	EA	\$75.00	BP#1
<b>65</b> Jersey barrier between vehicle parking, temporary	745	LF	\$10.00	BP#1
<b>66</b> Misc. marking other than above	1	LS	\$50,000.00	BP#1
<b>67 32 12 00 Flexible Paving Total</b>				<b>\$0</b>
<b>68</b>				
<b>69 32 13 10 Rigid Paving</b>				
<b>70</b>				\$0
<b>71</b>				\$0
<b>72</b>				\$0
<b>73</b>				\$0
<b>74</b>				\$0
<b>75</b>				\$0
<b>76</b>				\$0
<b>77 32 13 10 Rigid Paving Total</b>				<b>\$0</b>
<b>78</b>				
<b>79 32 14 00 Unit Paving</b>				
<b>80</b> Concrete paving/Conc sidewalk	17,115	SF	\$10.00	\$154,035
<b>81</b>				\$0
<b>82</b>				See Earthwork
<b>83</b>				See Earthwork
<b>84 32 14 00 Unit Paving Total</b>				<b>\$154,035</b>
<b>85</b>				
<b>86 32 16 00 Curbs and Gutters</b>				
<b>87</b> VGC; vertical granite curb	3,965	LF	\$42.00	BP#1
<b>88</b> SGC; sloped granite curb	191	LF	\$43.50	BP#1
<b>89</b> PCC; precast concrete curb	8,105	LF	\$25.00	BP#1
<b>90</b> Bit. berm curb	1,336	LF	\$5.00	BP#1
<b>91 32 16 00 Curbs and Gutters Total</b>				<b>\$0</b>
<b>92</b>				
<b>93 32 17 00 Paving Specialties</b>				
<b>94</b> Bituminous conc sidewalk	26,443	SF	\$2.25	BP#1



# Fuller Middle School

Framingham, MA

## SITWORK DIRECT TRADE COST DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
95 Gravel base to concrete pavement	807	CY	\$35.00	\$28,245
96 Peastone drip edge around building; 1'-6" wide	50	CY	\$75.00	\$3,750
97 Stonedust paving	1	LS	\$1,750.00	\$1,750
98 Curb cut	15	EA	\$450.00	\$6,750
99 Concrete pad	1	AL	\$24,000.00	BP#1
100 Handicap ramp	402	SF	\$20.00	BP#1
101 Temporary modular handicap ramp	138	SF	\$20.00	BP#1
<b>102 32 17 00 Paving Specialties Total</b>				<b>\$40,495</b>
103				
<b>104 32 30 00 Site Improvements</b>				
105 Unit block retaining wall	0	0	\$0.00	\$0
106 Footing	361	lf	\$0.00	\$0
107 Concrete	28	CY	\$135.00	\$3,780
108 Concrete; place	28	CY	\$85.00	\$2,380
109 Reinforcing	1,820	LBS	\$1.10	\$2,002
110 Formwork	2,166	SF	\$12.00	\$25,992
111 Wall	1,264	sf	\$0.00	\$0
112 Concrete material	42	CY	\$135.00	\$5,670
113 Concrete; place	42	CY	\$85.00	\$3,570
114 Reinforcing	6,300	LBS	\$1.10	\$6,930
115 Formwork	2,166	SF	\$12.00	\$25,992
116 Wall	1,264	SF	\$28.00	\$35,378
117 Concrete bench w/wooden top	20	LF	\$275.00	\$5,500
118	0	0	\$0.00	\$0
119 Flagpole	2	EA	\$7,500.00	\$15,000
120 Bandshell	1	AL	\$200,000.00	\$200,000
121 Traffic signs	1	AL	\$10,000.00	BP#1
122 Bollards	103	EA	\$800.00	\$82,400
123 Premium for architectural featured bollards	1	LS	\$75,000.00	\$75,000
124 Signage	1	AL	\$15,000.00	BP#1
125 Bicycle racks	20	EA	\$950.00	\$19,000
126 Basketball pavement	0	0	\$0.00	BP#1
127 Basketball court; fence, gate, court marking	1,750	SF	\$35.00	\$61,250
<b>128 32 30 00 Site Improvements Total</b>				<b>\$569,844</b>
129				
<b>130 32 31 00 Fences and Gates</b>				
131 Vehicular guardrail	271	LF	\$250.00	\$67,750
132 Wooden guardrail det 7/L3.0	992	LF	\$75.00	\$74,400
133 gates	2	EA	\$2,500.00	\$5,000
134 Galvanized handrails @ ramps and steps	219	LF	\$250.00	\$54,750
<b>135 32 31 00 Fences and Gates Total</b>				<b>\$201,900</b>
136				

# Fuller Middle School

Framingham, MA

## SITWORK DIRECT TRADE COST DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
<b>137 32 80 00 Irrigation</b>				
138 See the field				\$0
<b>139 32 80 00 Irrigation Total</b>				<b>\$0</b>
<b>140</b>				
<b>141 32 92 00 Turfs and Grasses</b>				
142 Topsoil for planting beds, shrubs and perennials	276	CY	\$25.00	\$6,900
143 Sports field mix (seed)	258,370	SF	\$0.35	\$90,430
144 Native wildflower meadow	104,342	SF	\$0.50	\$52,171
145 Lawn (seed)	121,052	SF	\$0.35	\$42,368
146 Sod at ampitheater	25,902	SF	\$1.50	\$38,853
147 Sod at play areas	24,038	SF	\$1.50	\$36,057
148 Plant bed	7,900	SF	\$10.00	\$79,000
149 Mulch	1	LS	\$30,000.00	\$30,000
150 Remove and install new irrigation System	82,000	SF	\$1.25	\$102,500
151 South Sports Field	0	0	\$0.00	By Others
152 Irrigation in front of Ampitheater	25,902	SF	\$2.00	\$51,804
153 Irrigation at play areas	24,038	SF	\$2.00	\$48,076
154 Fine grading	121,052	SF	\$0.75	\$90,789
<b>155 32 92 00 Turfs and Grasses Total</b>				<b>\$668,947</b>
<b>156</b>				
<b>157 32 93 00 Plants</b>				
158 Trees	0	0	\$0.00	\$0
159 AL; Allegheny Serviceberry 2½ - 3" Cal	12	EA	\$900.00	\$10,800
160 AC; Shadblow Serviceberry 2½ - 3" Cal	1	EA	\$900.00	\$900
161 AR; Red Maple 3 - 3½" Cal	6	EA	\$850.00	\$5,100
162 CK; American Yellowwood 3 - 3½" Cal	24	EA	\$800.00	\$19,200
163 FG; American Beech 3 - 3½" Cal	11	EA	\$850.00	\$9,350
164 LT; Tulip Tree 3 - 3½" Cal	8	EA	\$900.00	\$7,200
165 NS; Black Tupelo 3 - 3½" Cal	15	EA	\$850.00	\$12,750
166 OA; Sourwood 2½-3" Cal	3	EA	\$750.00	\$2,250
167 PA; London Plain Tree 3 - 3½" Cal	24	EA	\$850.00	\$20,400
168 QP; Pin Oak 3 - 3½" Cal	7	EA	\$900.00	\$6,300
169 QR; Red Oak 3 - 3½" Cal	7	EA	\$950.00	\$6,650
170 Shrubs	0	0	\$0.00	\$0
171 CA; Sweet Pepperbush 3½ - 4' HT	28	EA	\$95.00	\$2,660
172 HQ; Oak-leaf Hydrangea 3 - 3½' HT	49	EA	\$95.00	\$4,655
173 HV; Witch Hazel 7- 8' B+B	3	EA	\$350.00	\$1,050
174 IG; Compact Incberry 2½ - 3' HT	33	EA	\$125.00	\$4,125
175 IV; Winterberry 2 - 2½ HT	61	EA	\$95.00	\$5,795
176 JC; Common Juniper 24" SPD	0	EA	\$75.00	\$0
177 JH; Creeping Juniper 15-24" SPD	68	EA	\$75.00	\$5,100
178 JV; Eastern Red Cedar 7- 8' HT	26	EA	\$205.00	\$5,330
179 MG; Sweetgale 3½ - 4' HT	38	EA	\$95.00	\$3,610

# Fuller Middle School

Framingham, MA

## SITWORK DIRECT TRADE COST DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
180 PF; Pink Beauty Potentilla 24" SPD	22	EA	\$75.00	\$1,650
181 RA; Grow Low Sumac 2 - 2½' SPD	47	EA	\$115.00	\$5,405
182 RT; Staghorn Sumac 3 Gal	13	EA	\$115.00	\$1,495
183 RV; Virginia Rose 2½ - 3' SPD	0	EA	\$75.00	\$0
184 VA; Lowbush Blueberry 15-24" SPD	53	EA	\$75.00	\$3,975
185 VD; Arrowwood 4 - 4½' HT	31	EA	\$150.00	\$4,650
186 VT; Dwarf Cranberry Bush 3 - 3½' HT	12	EA	\$115.00	\$1,380
187 Groundcover	0	0	\$0.00	\$0
188 CP; Sweet Fern 1 Gal	1,966	EA	\$15.00	\$29,490
189 Grass at temporary parking area	6,650	SF	\$0.35	\$2,328
190 Maintenance of landscaping	1	LS	\$10,000.00	\$10,000
<b>191 32 93 00 Plants Total</b>				<b>\$193,598</b>
192				
193				
<b>194 33-UTILITIES</b>				
195				
<b>196 33 10 00 Water Distribution</b>				
197 2" Domestic water service	120	LF	\$60.00	BP#1
198 6" Fire water service	170	LF	\$70.00	BP#1
199 Water service; not sized	680	LF	\$95.00	BP#1
200 Hydrant	5	EA	\$4,500.00	BP#1
201 Miscellaneous gates, valves, etc. (gate valve 8x8x6)	1	LS	\$10,000.00	BP#1
<b>202 33 10 00 Water Distribution Total</b>				<b>\$0</b>
203				
<b>204 33 31 00 Sanitary Sewerage</b>				
205 6" DI	78	LF	\$70.00	BP#1
206 6" PVC	42	LF	\$70.00	BP#1
207 8" PVC	472	LF	\$75.00	BP#1
208 SMH; Sewer manhole	4	EA	\$4,500.00	BP#1
209 CO; Cleanout	1	EA	\$600.00	BP#1
210 Connect to existing	1	EA	\$3,500.00	BP#1
211 Acid neutralization tank	2	EA	\$7,500.00	BP#1
212 Grease trap	1	EA	\$15,000.00	BP#1
<b>213 33 31 00 Sanitary Sewerage Total</b>				<b>\$0</b>
214				
<b>215 33 41 00 Storm Utility Drainage</b>				
216 All incl. trench and backfill	0	0	\$0.00	\$0
217 6" PVC	47	LF	\$35.00	BP#1
218 12" HDPE	2,435	LF	\$42.00	BP#1
219 15" HDPE	635	LF	\$45.00	BP#1
220 18" HDPE	548	LF	\$48.00	BP#1
221 24" HDPE	371	LF	\$50.00	BP#1
222 30" HDPE	547	LF	\$60.00	BP#1

# Fuller Middle School

Framingham, MA

## SITWORK DIRECT TRADE COST DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
223 DMH; Manhole	9	EA	\$3,500.00	BP#1
224 CB; catch basin	19	EA	\$4,500.00	BP#1
225 Temporary CB, convert to DMH	3	EA	\$4,500.00	BP#1
226 Headwall @ 24" HDPE end	2	EA	\$1,500.00	BP#1
227 Allowances for:	0	0	\$0.00	BP#1
228 Water quality structures	4	EA	\$15,000.00	BP#1
229 Gravel and sod buffer for pretreatment	1	LS	\$10,000.00	BP#1
230 Stormceptors:	0	0	\$0.00	BP#1
231 450i	2	EA	\$10,000.00	BP#1
232	3600	1	EA \$35,000.00	BP#1
233	6000	1	EA \$60,000.00	BP#1
234 Outlet structure	1	EA	\$5,000.00	BP#1
235 Perimeter drainage	0	0	\$0.00	Bldg Tab
<b>236 33 41 00 Storm Utility Drainage Total</b>				<b>\$0</b>
237				
<b>238 33 50 00 Gas Service</b>				
239 33 50 00 Gas Service	0	0	\$0.00	\$0
240 Connection to existing gas main	0	0	\$0.00	By Other
241 Gas line piping, incl's valves (2)	0	0	\$0.00	By Other
<b>242 33 50 00 Gas Service Total</b>				<b>\$0</b>
243				
<b>244 33 70 00 Electrical Utilities</b>				
245 Site Lighting, Site Eqpt	0	0	\$0.00	\$0
246 Type SL1, 1-Fixt, 30' pole	45	EA	\$4,767.40	BP#1
247 Type SL1A, 1-Fixt, 30' pole	0	EA	\$4,767.40	BP#1
248 Type SL3, Wallpack	4	EA	\$701.80	\$2,807
249 Type SL3 Pedestrian Light Pole	42	EA	\$3,242.80	\$136,198
250 WP Signage w/ Lights, FBO	1	EA	\$1,113.20	\$1,113
251 Type SL10 Plant uplight	12	EA	\$520.30	\$6,244
252 Receptacle WP GFI	5	EA	\$284.35	\$1,422
253 CCTV Camera, Pole Mtd	3	EA	\$1,863.40	\$5,590
254 Elect Vehicle Charging Station	3	EA	\$1,645.60	\$4,937
255 Relocate Exist EM Call Box	2	EA	\$1,113.20	\$2,226
256 Time Clock	1	EA	\$1,004.30	\$1,004
257	0	0	\$0.00	\$0
258 Branch Circuitry:	0	0	\$0.00	\$0
259 3/4" Emt, 4#10	280	LF	\$14.98	BP#1
260 1" PVC CDT UG	7,110	LF	\$5.41	BP#1
261 2" PVC CDT UG	900	LF	\$7.70	BP#1
262 2 1/2" PVC CDT UG	3,600	LF	\$10.31	BP#1
263 17x30x12" Site Pullbox	16	EA	\$2,323.20	\$37,171
264 Handhole	6	EA	\$2,323.20	\$13,939
265 #10 Wire	12,400	LF	\$1.25	\$15,535
266 #8 Wire	16,050	LF	\$1.76	\$28,261

# Fuller Middle School

Framingham, MA

## SITWORK DIRECT TRADE COST DETAILS - CSI

<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Rate</u>	<u>Total</u>
267 #6 Wire	2,700	LF	\$2.11	\$5,707
268 Signal Cable	1,250	LF	\$1.82	\$2,269
269	0	0	\$0.00	\$0
270 Site Power, EG Feeders, Utilities:	0	0	\$0.00	\$0
271 4" PVC (Primary, empty) UG	460	LF	\$16.95	\$7,797
272 4" PVC CDT, 4 600 Mcm, UG (service)	600	LF	\$104.70	\$62,819
273 4" PVC CDT UG (spare)	100	LF	\$16.95	\$1,695
274 4" PVC CDT, 4 500 Mcm, UG (EG)	100	LF	\$87.18	\$8,718
275 2" PVC, 4#1/0 UG (EG)	100	LF	\$29.19	\$2,919
276 2 1/2" PVC, 4#4/0 UG (EG)	100	LF	\$38.87	\$3,887
277 1" PVC, EG Controls, Misc UG	200	LF	\$10.44	\$2,088
278 Utility Pole Riser	1	LF	\$4,767.40	\$4,767
279 Utility Transformer Pad	1	LS	\$4,162.40	\$4,162
280 Manhole	2	EA	\$11,616.00	\$23,232
281 Trenching, Concrete, Backfill	1	LS	\$100,000.00	BP#1
282	0	0	\$0.00	\$0
283 Miscellaneous:	0	0	\$0.00	\$0
284 4" PVC CDT UG (Comm)	800	LF	\$16.95	\$13,560
285 Innerduct	600	LF	\$3.99	\$2,396
286 Tel Utility Pole Riser	1	LS	\$3,121.80	\$3,122
287 3'x3' Comm Handhole	1	EA	\$6,243.60	\$6,244
288	0	0	\$0.00	\$0
289 Misc Site Demo	1	LS	\$10,890.00	BP#1
290 Site Security Lighting	1	LS	\$12,584.00	\$12,584
291 Temp Power and Lighting	1	LS	\$31,460.00	\$31,460
292 Eqpt Rentals	1	LS	\$7,260.00	\$7,260
293 <b>33 70 00 Electrical Utilities Total</b>				<b>\$463,132</b>
294				
295				
			<b>SITWORK SUBTOTAL</b>	<b>\$2,564,406</b>



**90% Construction Documents  
Fuller Middle School  
Framingham, MA**

26-Sep-19

BUILDING AND SITEWORK	\$57,411,224
EARLY SITE PACKAGE #1	\$10,956,907
EARLY SITE PACKAGE #2	\$8,738,801
	-----
TOTAL CONSTRUCTION COST	\$77,106,932

**90% Construction Documents**  
**Fuller Middle School**  
**Framingham, MA**

**26-Sep-19**

NEW BUILDING				\$43,254,839
SITWORK				\$1,674,449
BUILDING DEMOLITION	196,000	GSF	\$7.50	\$1,470,000
ASBESTOS REMOVAL ( cdw 9/19/19 )				\$1,171,440
OTHER HAZARDOUS MATERIAL ( cdw 9/19/19 )				\$123,050
				-----
TOTAL DIRECT COST ( estimated to the mid-point of construction )				\$47,693,778
Chapter 149 a:				
DESIGN CONTINGENCY		2%		\$953,876
CM CONTINGENCY		2.5%		\$1,216,191
ESCALATION ( bid 12/19 )		1.0%		\$498,638
SDI				\$0
SUB BOND				\$0
GENERAL REQUIREMENTS				\$2,389,380
GENERAL CONDITIONS				\$2,931,033
TRAFFIC MITIGATION				\$0
BUILDING PERMIT			waived	
GENERAL LIABILITY INSURANCE				\$576,109
FEE				\$1,152,218
				-----
				TOTAL CONSTRUCTION COST
				\$57,411,224
				COST PER S.F.
				\$420.29



EARLY SITE PACKAGE #1		\$8,710,136
		-----
TOTAL DIRECT COST ( estimated to the mid-point of construction )		\$8,710,136
Chapter 149 a:		
SDI		\$120,894
CM CONTINGENCY	2.5%	\$220,776
ESCALATION ( bid 12/19 )	2%	\$0
GENERAL REQUIREMENTS		\$432,020
GENERAL CONDITIONS		\$586,777
BUILDERS RISK		\$115,218
GENERAL LIABILITY INSURANCE		\$111,429
P&P BOND		\$436,800
FEE		\$222,857
		-----
	TOTAL CONSTRUCTION COST	\$10,956,907

EARLY SITE PACKAGE #2		\$7,339,465
		-----
TOTAL DIRECT COST ( estimated to the mid-point of construction )		\$7,339,465
Chapter 149 a:		
SDI		\$102,386
CM CONTINGENCY	2.5%	\$186,046
ESCALATION ( bid 12/19 )	2%	\$0
GENERAL REQUIREMENTS		\$363,102
GENERAL CONDITIONS		\$470,414
BUILDERS RISK	IN BP #1	\$0
GENERAL LIABILITY INSURANCE		\$92,462
P&P BOND	IN BP #1	\$0
FEE		\$184,925
		-----
	TOTAL CONSTRUCTION COST	\$8,738,801

PROJECT: Fuller Middle School  
 LOCATION: Framingham, MA  
 CLIENT: SMMA Architects  
 DATE: 26-Sep-19

NO. OF SQ. FT.: 136,600  
 COST PER SQ. FT.: \$328.91

SUMMARY

No.: 18020

	DIVISION TOTAL	PERCENT OF PROJECT	COST PER SF
<b>DIVISION 02 - EXISTING CONDITIONS</b>			
024117 BUILDING DEMOLITION	0	0%	0.00
024180 ASBESTOS ABATEMENT	0	0%	0.00
<b>DIVISION 03 - CONCRETE</b>			
033000 CAST IN PLACE CONCRETE	0	0%	0.00
<b>DIVISION 04 - MASONRY</b>			
042000 UNIT MASONRY*	1,794,046	4%	13.13
<b>DIVISION 05 - METALS</b>			
051200 STRUCTURAL STEEL FRAMING	0	0%	0.00
053000 METAL DECKING	0	0%	0.00
054000 COLD FORMED METAL FRAMING	0	0%	0.00
055000 METAL FABRICATIONS*	1,765,905	4%	12.93
<b>DIVISION 06 - WOOD, PLASTICS &amp; COMPOSITES</b>			
061000 ROUGH CARPENTRY	233,306	1%	1.71
062000 FINISH CARPENTRY	846,711	2%	6.20
<b>DIVISION 07 - THERMAL &amp; MOISTURE PROTECTION</b>			
071000 DAMPPROOF., WATERPROOF. & CAULKING*	702,224	2%	5.14
070002 ROOFING AND FLASHING*	1,724,581	4%	12.63
072100 THERMAL INSULATION	312,444	1%	2.29
072600 VAPOR RETARDERS	0	0%	0.00
074214 EXTERIOR WALL PANELS	1,168,460	3%	8.55
078100 FIREPROOFING	306,208	1%	2.24
078400 FIRESTOPPING	88,790	0%	0.65
079513 EXPANSION JOINTS (NO SPEC)	40,000	0%	0.29

	DIVISION TOTAL	PERCENT OF PROJECT	COST PER SF
<b>DIVISION 08 - OPENINGS</b>			
080001 METAL WINDOWS*	1,790,508	4%	13.11
080002 GLASS AND GLAZING*	794,147	2%	5.81
081113 HOLLOW METAL DOORS & FRAMES	136,485	0%	1.00
081416 FLUSH WOOD DOORS	159,225	0%	1.17
083100 ACCESS DOORS AND PANELS	30,000	0%	0.22
083323 SPECIAL DOORS	80,793	0%	0.59
084513 STRUCT-POLYCARBONATE PNL ASSEMB. & SKYLIG	729,120	2%	5.34
087100 DOOR HARDWARE	366,760	1%	2.68
089000 LOUVERS & VENTS	84,000	0%	0.61
<b>DIVISION 09 - FINISHES</b>			
090003 TILE*	308,119	1%	2.26
090006 RESILIENT FLOORING*	840,714	2%	6.15
090009 PAINTING*	622,406	1%	4.56
092116 GYPSUM WALLBOARD ASSEMBLIES	5,073,206	11%	37.14
095100 ACOUSTICAL CEILINGS*	427,380	1%	3.13
096446 WOOD & ATHLETIC FLOORING	225,065	1%	1.65
096712 RESINOUS FLOORING	109,314	0%	0.80
096800 CARPET	8,456	0%	0.06
097217 DIGITAL IMAGE WALL COVERINGS	23,500	0%	0.17
097233 DRY-ERASE WALL COVERING	166,000	0%	1.22
097733 SANITARY WALL PANELS	21,772	0%	0.16
098100 ACOUSTICAL INSULATION	0	0%	0.00
098400 ACOUSTIC ROOM COMPONENTS	387,392	1%	2.84
098415 WOOD FIBER ACOUSTICAL PANELS	106,134	0%	0.78
<b>DIVISION 10 - SPECIALTIES</b>			
101100 MARKERBOARDS & TACKBOARDS	14,800	0%	0.11
101400 SIGNAGE	88,144	0%	0.65
102113 TOILET COMPARTMENTS	55,590	0%	0.41
102600 WALL AND DOOR PROTECTION	10,000	0%	0.07
102813 TOILET ACCESSORIES	35,127	0%	0.26
104000 SAFETY SPECIALTIES	22,800	0%	0.17
107113 EXTERIOR SUN CONTOL DEVICES	75,000	0%	0.55
109000 MISCELLANEOUS SPECIALTIES	635,944	1%	4.66
<b>DIVISION 11 - EQUIPMENT</b>			
113100 RESIDENTIAL APPLIANCES	10,350	0%	0.08
114000 FOOD SERVICE EQUIPMENT	415,270	1%	3.04
115213 PROJECTION SCREENS	65,000	0%	0.48
116143 THEATRICAL EQUIPMENT(No Spec)	866,921	2%	6.35
116600 ATHLETIC & SPORTS EQUIPMENT	157,871	0%	1.16
119000 MISC. EQUIPMENT	100,550	0%	0.74
	DIVISION TOTAL	PERCENT OF PROJECT	COST PER SF

<b>DIVISION 12 - FURNISHINGS</b>			
122400 WINDOW SHADES	92,976	0%	0.68
122414 MOTORIZED WINDOW SHADES	0	0%	0.00
123553 CASEWORK	1,577,937	4%	11.55
124813 FLOOR MATS	7,920	0%	0.06
124816 ENTRANCE GRILLES & FRAMES	0	0%	0.00
126613 TELESCOPING BLEACHERS	0	0%	0.00
129000 MISCELLANEOUS FURNISHING	106,445	0%	0.78
<b>DIVISION 13 - SPECIAL CONSTRUCTION</b>			
130000 SPECIAL CONSTRUCTION	0	0%	0.00
<b>DIVISION 14 - CONVEYING EQUIPMENT</b>			
140001 ELEVATORS*	212,000	0%	1.55
<b>DIVISION 21 - FIRE SUPPRESSION</b>			
210001 FIRE SUPPRESSION*	853,485	2%	6.25
<b>DIVISION 22 - PLUMBING</b>			
220001 PLUMBING*	2,148,401	5%	15.73
<b>DIVISION 23 - HVAC</b>			
230001 HVAC*	8,281,591	18%	60.63
<b>DIVISION 26 - ELECTRICAL</b>			
260001 ELECTRICAL*	5,947,549	13%	43.54
<b>DIVISION 31 - EARTHWORK</b>			
310000 EARTHWORK	464,732	1%	3.40
311000 SITE PREPARATION & CLEARING	0	0%	0.00
<b>DIVISION 32 - EXTERIOR IMPROVEMENTS</b>			
321000 PAVEMENT, CURBING & EDGING	4,380	0%	0.03
323100 SITE IMPROVEMENTS	289,992	1%	2.12
328000 IRRIGATION	165,792	0%	1.21
329000 LANDSCAPING	457,903	1%	3.35
<b>DIVISION 33 - UTILITIES</b>			
330000 UTILITIES	291,650	1%	2.14
	-----		
DIRECT COST	44,929,288	100%	328.91

\*DENOTES FILED SUB-BID

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

DIVISION 02 - EXISTING CONDITIONS

024117 BUILDING DEMOLITION	SEE SUMMARY			----- 0
----------------------------	-------------	--	--	------------

024180 ASBESTOS ABATEMENT	SEE SUMMARY			----- 0
---------------------------	-------------	--	--	------------

DIVISION 03 - CONCRETE

033000 CAST IN PLACE CONCRETE	SEE BID PACKAGE #2			----- 0
-------------------------------	--------------------	--	--	------------

DIVISION 04 - MASONRY

042000 UNIT MASONRY\*

Exterior Walls:

Backup :

Gym 12" CMU Back-up - Exposed	7,497	SF	25.50	191,174
Aud 12" CMU Back-up - Exposed	7,342	SF	25.50	187,221
Int GF finish premium	14,839	deleted		

\*A462 GF is not noted

Masonry Veneer Building ( QTY Noted):

4x4x12 Scored brick veneer	6,252	SF	31.00	193,812
4x8x8 Scored brick veneer	6,722	SF	33.75	226,868
4x8x16 Scored ground face CMU	21,025	SF	28.00	588,700
4x4x12 Scored ground face CMU	3,512	SF	30.25	106,238
Insulation		W/072000		

SS Masonry flashing	1	LS	35,000.00	35,000
Staging		inc. w/ unit		

A501 Premium:

Sill brick		w/Unit Cost		
Lip brick		w/Unit Cost		

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Precast Concrete:				
Precast Planter - on grade	26	LF	750.00	19,500
Precast Planter - on roof	24	LF	750.00	18,000
Misc. BLDG precast veneer		N/A		
*Site planters are included w/ site improvements				
2nd Floor Main Entry Terrace:				
(3/ A316)3'6"H Brick Partial HT wall-comj	26	LF	440.00	11,440
(3/ A316) Wall Cap	26	LF	175.00	4,550
Partitions:				
Interior 12" CMU Partition:				
Gym - 28'	4,480	SF	26.00	116,480
Auditorium - 28'	2,660	SF	26.00	69,160
Auditorium - 14'	420	SF	26.00	10,920
GF CMU - Aud. Only	2,660	SF	4.50	11,970
Acoustical Block - Premium		deleted		
Stage front CMU pier (5 loc)	22.5	SF	55.00	1,238
CMU Partition (Gym & Aud):				
Bond beam	37	LF	48.00	1,776
				-----
				1,794,046

DIVISION 05 - METALS

051200 STRUCTURAL STEEL FRAMING

SEE BID PACKAGE #2

-----  
0

053000 METAL DECKING

SEE BID PACKAGE #2

-----  
0

054000 COLD FORMED METAL FRAMING

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
*w/ gypsum drywall				----- 0
<b>055000 METAL FABRICATIONS*</b>				
<b>Elevators:</b>				
Elev. framing	1	EA	3,000.00	3,000
Elev. pit ladder	1	EA	1,537.00	1,537
Elev. sump grate	1	EA	1,500.00	1,500
<b>Exterior Walls:</b>				
<b>42" Perf Metal Guardrail:</b>				
LVL 2 entry	11	LF	350.00	3,850
LVL 2 emerg. egress	42	LF	350.00	14,700
LVL 2 emerg. egress stair wall rail	8	LF	145.00	1,160
Galv, loose lintel (per 5600-604)	133	LF	36.00	4,788
Misc metals @ ext wall - allow	1	LS	25,000.00	25,000
Reliving angle		W /Structural		
Bolted galv. sill angle @ fnd		W /Structural		
Support clip @ skylight curb (spec)	567	LF	125.00	70,875
<b>Exterior Doors:</b>				
<b>OH door frame @:</b>				
Tech-Makerspace	1	EA	500.00	500
<b>Special Doors:</b>				
LVL 1 Corridor Security Gate- sgl ( 7' x7'1	2	EA	7,000.00	14,000
<b>Partitions:</b>				
<b>Folding Panel partition Support (18/A620):</b>				
Typ classroom (13 EA)	208	LF	165.00	34,320
Music classroom (DBL panel 1 EA)	19	LF	330.00	6,270
SPED suite (3 EA)	120	LF	165.00	19,800
<b>Folding Grille Support @:</b>				
Learning common	46	LF	200.00	9,200
Sgl custom security gate (7'w)	2	EA	4,000.00	8,000
<b>Coiling Grille Support @:</b>				
Servery	35	LF	100.00	3,500
Main office(1 EA)	21	LF	100.00	2,100
<b>CMU Partition (Gym &amp; Aud):</b>				
CMU clip @ 4' oc	70	EA	115.00	8,050

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Misc Metals @ Corridor Locker Enclosure (nic mtl locker) - allow (7/A650):				
1st Floor (307 LF)		N/A		
Upper floors	724	LF	425.00	307,700
Misc. metals	136,600	GSF	1.00	136,600
Fittings:				
Auditorium:				
Stage front access stair rails (9/A602)	32	LF	145.00	4,640
Aisle access stair rails (11/A602)	34	LF	145.00	4,930
Auditorium equip. supports	1	LS	15,000.00	15,000
Interior Metals:				
1st Flr guard rail (5.39)	20	LF	350.00	7,000
2nd & 3rd Flr Lobby guard rail (6/A650)	327	LF	450.00	147,150
Cohort # 2059 2nd Flr Lobby guard rail (6	19	LF	450.00	8,550
OT/PT equip support-allow	1	RM	2,500.00	2,500
Gym equip supports	1	LS	10,000.00	10,000
Concealed stl angle @ corr built-in bench		W/ Unit Cost		
Concealed stl angle @ casework ctr		W/ Unit Cost		
Ships ladder @ gym storage	1	EA	15,000.00	15,000
Interior:				
4/ A601 Curved perf arch grille - classroom	1,536	SF	50.00	76,800
Support atrium vert duct encl.	4	LOC	10,000.00	40,000
Exterior Rails:				
Roof ladder (3 EA)	30	VLF	425.00	12,750
Loading dock stair/ramp guardrail	15	LF	265.00	3,975
Loading dock stair/ramp wall rail	15	LF	150.00	2,250
2nd flr entry terrace guardrail	30	LF	500.00	15,000
High roof safety rail - allow	150	LF	125.00	18,750
Stair Construction:				
5' 6"W Metal Pan Stair #3 @ Learning Commons 1st- 2nd (1 FLT):				
Metal pan stair treads/risers	132	LFR	95.00	12,540
Metal pan landing	33	SF	75.00	2,475
Guardrail	66	LF	400.00	26,400
Cane rail	1	EA	1,350.00	1,350
8'6" W Metal Pan Stair #14 @ Learning Commons 1st- 2nd ( 1 FLT):				
Metal pan stair treads/risers	204	LFR	95.00	19,380
Metal pan landing	51	SF	75.00	3,825
Guardrail	66	LF	400.00	26,400
Cane rail	1	EA	1,350.00	1,350



DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
<b>5'10" W Metal Pan Stair #6 @ Learning Commons 2nd - 3rd( 1 FLT):</b>				
Metal pan stair treads/risers	138	LFR	95.00	13,110
Metal pan landing	33	SF	75.00	2,475
Guardrail	66	LF	400.00	26,400
<b>8' 6"W Metal Pan Stair #5 @ Learning Commons 2nd - 3rd(1 FLT):</b>				
Metal pan stair treads/risers	204	LFR	95.00	19,380
Metal pan landing	55	SF	75.00	4,125
Guardrail	66	LF	400.00	26,400
<b>5' W Metal Pan Stair Hall 1 &amp; 2 ( 2 loc 1st - 3rd 4 FLT):</b>				
Metal pan stair treads/risers	480	LFR	95.00	45,600
Metal pan landing	240	SF	75.00	18,000
Wall rail	128	LF	165.00	21,120
Guardrail	128	LF	400.00	51,200
Guardrail flr open	12	LF	400.00	4,800
Cane rail	2	EA	1,350.00	2,700
<b>5' W Metal Pan Stair @ #1 Penthouse ( 1 FLT):</b>				
Metal pan stair treads/risers	120	LFR	95.00	11,400
Metal pan landing	60	SF	75.00	4,500
Wall rail	32	LF	165.00	5,280
Guardrail	32	LF	400.00	12,800
Access gate	1	EA	1,800.00	1,800
<b>* Typ, perforated steel panel guardrail sys</b>				
Aud Rails & Stairs		W/ C1030		
Lobby rails		W/ C1030		
<b>Ceiling Finishes:</b>				
<b>Note #5.55 Perf Arch Grille:</b>				
3rd Flr clg -12"W	210	SF	200.00	42,000
<b>Site Development:</b>				
<b>Ramp and Planter Walls:</b>				
Railings	146	LF	250.00	36,500
<b>Site Stair:</b>				
Site stair railing	33	LF	250.00	8,250
Site decorative bollard	103	EA	2,200.00	226,600
<b>Stage Plenum (7/A602):</b>				
Perf. arch grille - stage front	120	SF	225.00	27,000
				-----

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

1,765,905

## DIVISION 06 - WOOD, PLASTICS &amp; COMPOSITES

## 061000 ROUGH CARPENTRY

## Exterior Windows:

P.T. - perm blocking	9,009	LF	8.65	77,928
----------------------	-------	----	------	--------

## Exterior Doors:

P.T. - perm blocking HM open	316	LF	8.00	2,528
------------------------------	-----	----	------	-------

## Partitions:

Interior blocking	136,600	GSF	0.50	68,300
-------------------	---------	-----	------	--------

Misc. rough carpentry	136,600	GSF	0.50	68,300
-----------------------	---------	-----	------	--------

(5/A601) Frame AV monitor box	65	EA	250.00	16,250
-------------------------------	----	----	--------	--------

-----  
233,306

## 062000 FINISH CARPENTRY

## Exterior Walls:

## Main Entry LVL 2:

Wd bench @ precast planter	24	LF	550.00	13,200
----------------------------	----	----	--------	--------

Phenolic bench @ col. M	7	LF	500.00	3,500
-------------------------	---	----	--------	-------

## Partitions:

## Interior Borrowed Light Window /Sidelight-A620 (NIC Break out Area):

PTD MDF sill 9"	866	LF	32.00	27,712
-----------------	-----	----	-------	--------

PTD MDF head 9"	866	LF	25.00	21,650
-----------------	-----	----	-------	--------

PTD MDF jamb 9"		N/A		
-----------------	--	-----	--	--

## Fittings:

## Finish Carpentry:

A312 Int window panel grilles (Rulon)	450	LF	150.00	67,500
---------------------------------------	-----	----	--------	--------

\*casework is included w/ E2010

## Wall Finishes:

## (16/A621) 18" PTD MDF Bumper w/HD Bamboo Wd Marker Tray:

Bumper Rail	3,480	LF	45.00	156,600
-------------	-------	----	-------	---------

Bumper Top	3,480	LF	30.00	104,400
------------	-------	----	-------	---------

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Wall Finish:				
P.lam Wall Panel:				
11/A600 Drinking Fountain Alcove (7 loc	245	SF	55.00	13,475
P.Lam wall panel @ class entry controls	59	LOC	550.00	32,450
Auditorium vestibule	393	SF	48.00	18,864
Stage full ht	2,880	SF	48.00	138,240
Ceiling Finishes:				
Auditorium/Stage-(A461 & A691):				
Clouds - allow	2,076	SF	120.00	249,120
*Clouds 3/4" Veneer w/wood trim - includes hardware and hangers				-----
				846,711

## DIVISION 07 - THERMAL &amp; MOISTURE PROTECTION

## 071000 DAMPPROOF., WATERPROOF. &amp; CAULKING\*

Foundations:				
Foundation dampproofing	6,884	SF	1.90	13,080
Retaining wall waterproofing	1,360	SF	6.85	9,316
Elev. pit waterproofing	1	LOC	4,300.00	4,300
Exterior Walls:				
Fluid Applied air & vapor barrier:				
Exterior Wall - CMU & Sheathing	59,125	SF	8.00	473,000
Bay covered entry	1,119	SF	8.00	8,952
Exterior Windows:				
Flex flashing - perm	9,009	LF	8.00	72,072
Exterior Doors:				
Perm. Ext HM & OH opening:				
Flex flashing - perm	348	LF	8.00	2,784
Exterior sealants - perm.	348	LF	7.50	2,610
Partitions:				
Joint sealants	136,600	GSF	0.85	116,110
				-----
				702,224

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
<b>070002 ROOFING AND FLASHING*</b>				
Exterior Walls:				
(1/A543) Raised Common Exterior Wall:				
5'6"H Rigid Insul. W/ PVC Membrane( sa 1	2,486	SF	15.00	37,290
Flat Roof Blocking @:				
Base flashing	1,620	LF	12.50	20,250
Typ roof fascia	3,182	LF	12.50	39,775
Expansion joint	86	LF	40.00	3,440
Gable skylight curb ( 4 EA)	567	LF	45.00	25,515
Flash Pre Fab Roof Top Mech curb block	618	LF	35.00	21,630
Misc Equip blocking	1	LS	7,500.00	7,500
Roof hatch	1	EA	750.00	750
Atrium vent	4	EA	750.00	3,000
Roofing (A502):				
White 60 mil PVC Roofing w/R-36 (6" Insul ) :				
Typ Flat roof	64,092	SF	16.50	1,057,518
1/2 " glass mat cover bd -100%	64,092	SF	1.45	92,933
1/2" glass mat protection bd(nic conc deck	23,302	SF	1.45	33,788
1/2" glass mat protection 2 lysr aud	7,563	SF	5.20	39,328
Poly vapor retarder-100%	64,092	SF	0.42	26,919
3' High Rubber Walkway Pad	765	SF	7.00	5,355
Membrane flashing	64,092	SF	0.50	32,046
Base flashing	1,620	LF	32.00	51,840
Alum Typ roof fascia	3,182	LF	22.00	70,004
Expansion joint - allow	86	LF	185.00	15,910
Flash gable skylight curb ( 4 EA)	567	LF	32.00	18,144
Flash Pre Fab Roof Top Mech encl curb	618	LF	32.00	19,776
Scupper - allow	4	EA	750.00	3,000
Flash roof drain - allow	32	EA	135.00	4,320
Entry pier/chimney cap flashing -complete	55	SF	100.00	5,500
Misc roof flashing	1	LS	25,000.00	25,000
Premium Terrace Paver Sys (1/A316):				
Main entrance #2000	730	SF	45.00	32,850
*Includes Sections 075419, 076200, 077236 & 086300				
Roof Openings:				
Roof hatch	1	EA	4,200.00	4,200
Stage vent-allow	2	EA	13,500.00	27,000

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

1,724,581

## 072100 THERMAL INSULATION

Slab on Grade:

2" Rigid Slab Insul.- 4' @ perm. SEE BID PACKAGE #1

Exterior Walls:

Exterior Wall A501:

3" Mineral fiber insul @ masonry	43,331	SF	3.72	161,191
4" Mineral fiber insul @ panel wall	11,380	SF	4.15	47,227
Spray foam at perm openings	9,299	LF	8.25	76,717

Aud Roof Deck:

Insulate aud deck flutes 7,563 SF 2.00 15,126

6/A323 Exterior Wall - Raised Commons:

4" Mineral fiber insul 2,486 SF 2.65 6,588

Exterior Ceiling Insulation @ :

Bay / covered entry 1,119 SF 5.00 5,595

-----  
312,444

## 072600 VAPOR RETARDERS

\*Excludes under slab waterproofing system

-----  
0

## 074214 EXTERIOR WALL PANELS

Exterior Walls:

Exterior Wall Panel System:

Corrugated metal panel	5,500	SF	48.00	264,000
Composite metal panel	2,662	SF	55.00	146,410
Phenolic panel	8,518	SF	76.00	647,368

Exterior Ceiling Stucco System:

Bay/covered entry 1,119 SF 32.00 35,808

8'H Mech roof screen(NIC Struct Frame - 8/A325):

8' Corrugated Perf Mtl wall panel-complete 1,112 SF 42.00 46,704

Screen wall cap - allow 139 LF 30.00 4,170

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
(2 sided) Phenolic fin - complete: 3' Fin 12'4"H (5 loc) *Includes Sections 074214 & 074224	200	SF	120.00	24,000
				----- 1,168,460
078100 FIREPROOFING				
Floor Construction:				
Allow:				
Spray fireproofing	68,431	SF	3.00	205,293
Roof Construction:				
Allow:				
Spray fireproofing	36,041	SF	2.80	100,915
				----- 306,208
078400 FIRESTOPPING				
Partitions:				
Firestopping	136,600	GSF	0.65	88,790
				----- 88,790
079513 EXPANSION JOINTS (NO SPEC)				
Exterior Walls:				
Control and expansion joints	1	LS	30,000.00	30,000
Partitions:				
Int Wall Expansion joints	1	LS	10,000.00	10,000
				----- 40,000

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
DIVISION 08 - OPENINGS				
080001 METAL WINDOWS*				
Exterior Doors:				
Alum. Doors (Incl. Glass, Glazing):				
7' 1st Flr Entry - sgl	2	EA	4,100.00	8,200
7' 1st Flr Entry - dbl	3	PR	8,200.00	24,600
7' 2nd Flr Entry - sgl	1	EA	4,100.00	4,100
7' 2nd Flr Entry - dbl	1	PR	8,200.00	8,200
7' Main office egress - sgl	1	EA	4,100.00	4,100
7' Stair egress - sgl	2	EA	4,100.00	8,200
7' Staff lunch rm	1	EA	4,100.00	4,100
8' Media ctr - sgl	1	EA	4,100.00	4,100
Premium :				
Auto opener	2	EA	4,500.00	9,000
Ext. School Guard (6 lvs ) - Factory glazing	90	SF	36.00	3,240
Interior Doors:				
Aluminum ( Frame, Door, Glass, Glazing and Hdw):				
7' 1st Flr Entry Vestibule - sgl	1	EA	4,000.00	4,000
7' 1st Flr Entry Vestibule - dbl	2	PR	8,150.00	16,300
8' 2nd Flr Entry Vestibule- sgl	1	EA	4,400.00	4,400
8' 2nd Flr Entry Vestibule - dbl	1	PR	8,600.00	8,600
Premium:				
Int. School Guard ( 9 lvs ) - Factory glazing	135	SF	36.00	4,860
Exterior Windows - Allow:				
Storefront	14,204	SF	110.00	1,562,440
Exterior sealants - perm.	9,009	LF	7.50	67,568
ALLOW:				
Security Glazing Film 2nd flr entry	125	SF	36.00	4,500
Exterior Wall Mock-up	1	LS	35,000.00	35,000
Partitions:				
Aluminum Storefront Frame, Glass & Glazing-Allow:				
1st Floor Vestibule (11A/A221)		w/B2010		
Office/ vestibule security window (6/A403)				
2nd Flr Main office	1	EA	5,000.00	5,000
				-----
				1,790,508

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
080002 GLASS AND GLAZING*				
Fittings:				
Multi User Toilet & Locker Rm (16 ea):				
5'H mirror @ lav ctr	1,215	SF	38.00	46,170
Dressing Rm (2 ea):				
5'H mirror @ ctr	90	SF	38.00	3,420
Site Development:				
Band Shell (A500):				
9/16 " Temp. lam glazing - roof	132	SF	175.00	23,100
9/16 " Temp. lam glazing - wall	254	SF	175.00	44,450
Partitions:				
Interior Window /Sidelight-A620 (NIC Break out Area):				
SGL Alum channel ,glass & glazing	5,071	SF	62.00	314,402
DBL Alum channel ,glass & glazing	930	SF	88.00	81,840
GL-Graduated pattern film premium	3,094	SF	10.00	30,940
3m Safety Glazing	4,332	SF	15.00	64,980
Interior Doors:				
Glass & Glazing @ Interior Wood Door:				
Sgl C1 7'H ( 6 EA )	60	SF	48.00	2,880
Sgl C1 8'H ( 105 EA )	1,260	SF	48.00	60,480
Dbl C2 8'H ( 9 EA )	216	SF	48.00	10,368
Dbl C3 8'H ( 1 EA )	4	SF	48.00	192
Breakout Space:				
Breakout A( 2 story):				
Glass wall w/ perim trim	381	SF	75.00	28,575
Glass wall w/ perim trim	646	SF	75.00	48,450
Breakout D( 1 story):				
Glass wall w/ perim trim	202	SF	75.00	15,150
Breakout E ( 1 story):				
Glass wall w/ perim trim	250	SF	75.00	18,750
				-----
				794,147

## 081113 HOLLOW METAL DOORS &amp; FRAMES



DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
<b>Interior Doors:</b>				
<b>Int. HM Door Frame:</b>				
Single Door 7'H	22	EA	285.00	6,270
Double Door 7'H	1	EA	305.00	305
Single Door 8' H	251	EA	320.00	80,320
Double door 8'H	26	EA	345.00	8,970
<b>Int. HM Door:</b>				
Sgl B1 7'H	15	EA	495.00	7,425
90 Min Sgl B1 7'H	1	EA	530.00	530
Dbl B2 7'H	1	EA	990.00	990
Sgl B1 8'H	25	EA	540.00	13,500
90 Min Sgl B1 8'H	1	EA	565.00	565
90 Min Dbl B2 8'H	3	EA	1,130.00	3,390
<b>Exterior Doors:</b>				
<b>Ext Insulated HM Doors and Frame:</b>				
Sgl B1 7'H	4	EA	585.00	2,340
Dbl B2 7'H	1	EA	1,170.00	1,170
Sgl B1 8'H	1	EA	630.00	630
Dbl B2 8'H	8	EA	1,260.00	10,080
<b>Partitions:</b>				
Interior HM Frame Glass & Glazing:		N/A		
				-----
				136,485

081416 FLUSH WOOD DOORS

<b>Interior Doors:</b>				
<b>Int. Prefinished Wood Door (Glass):</b>				
Sgl B1 2'x 8'H	35	EA	490.00	17,150
Sgl B1 3'x 8'H	77	EA	530.00	40,810
90 Min Sgl B1 3'x 8'H	8	EA	560.00	4,480
Dbl B2 8'H	13	EA	1,060.00	13,780
Sgl C1 7'H	6	EA	610.00	3,660
Sgl C1 8'H	105	EA	635.00	66,675
Dbl C2 8'H	9	EA	1,270.00	11,430
Dbl C3 8'H	1	EA	1,240.00	1,240
				-----
				159,225

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

## 083100 ACCESS DOORS AND PANELS

## Partitions:

Access panels	1	LS	30,000.00	30,000
				-----
				30,000

## 083323 SPECIAL DOORS

## Interior Doors:

## Café/Learning Common:

Coiling Security Mesh Drape ( 21'x 8' -2EA	336	SF	95.00	31,920
--	-----	----	-------	--------

## Serving :

Coiling Security Mesh Drape ( 40'x 8' -1EA	320	SF	95.00	30,400
--	-----	----	-------	--------

## Main office:

Coiling Security Mesh Drape ( 21' x 5' 6"-1	116	SF	95.00	10,973
---	-----	----	-------	--------

## Exterior Doors:

## Motor Operated Insulated OH Door:

Tech-Makerspace (10'x10'6" )	1	EA	7,500.00	7,500
------------------------------	---	----	----------	-------

-----  
80,793

## 084513 STRUCT-POLYCARBONATE PNL ASSEMB. &amp; SKYLIGHTS

## Roof Coverings:

## Main Entrance Canopy -Complete:

Clear Polycarb glazing w/ alum struct -7'w	416	SF	175.00	72,800
--	-----	----	--------	--------

## Roof Openings:

Gable Skylight ( 4 loc)	4,261	SF	140.00	596,540
-------------------------	-------	----	--------	---------

Gable Skylight End wall ( 8 loc)	427	SF	140.00	59,780
----------------------------------	-----	----	--------	--------

\*Includes Section 086300

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
				-----
				729,120

## 087100 DOOR HARDWARE

## Exterior Doors

## Hardware Set @ Ext. Alum Door:

1	1	EA	750.00	750
2	1	EA	825.00	825
3	3	EA	2,250.00	6,750
4	2	EA	2,300.00	4,600
5	1	EA	3,850.00	3,850
SGL -allow	2	EA	2,500.00	5,000
9	1	EA	1,425.00	1,425
11	1	EA	5,900.00	5,900
12	1	EA	6,300.00	6,300
Terrace - sgl	-1	EA	2,000.00	-2,000
Terrace - dbl	-1	EA	4,000.00	-4,000
Entry - sgl	1	EA	4,000.00	4,000

## Hardware Set # Ext HM Door:

6	1	EA	1,150.00	1,150
8	3	EA	2,925.00	8,775
10	2	EA	4,500.00	9,000
13	1	EA	2,475.00	2,475
14	3	EA	2,325.00	6,975
16	1	EA	750.00	750
17	1	EA	3,350.00	3,350
18	1	EA	1,400.00	1,400
19	1	EA	5,100.00	5,100

\*Hardware also included with 080001

## Interior Doors:

## Hardware Set @ Int. Alum Door:

15	5	EA	5,425.00	27,125
----	---	----	----------	--------

## Hardware Set @ Typ Int. Doors ( per Spec ):

20	1	EA	1,500.00	1,500
22	2	EA	785.00	1,570
23	1	EA	805.00	805
24	13	EA	695.00	9,035
25	2	EA	485.00	970
26	1	EA	460.00	460

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
27	2	EA	590.00	1,180
28	23	EA	670.00	15,410
29	10	EA	510.00	5,100
30	44	EA	585.00	25,740
31	1	EA	480.00	480
32	39	EA	680.00	26,520
33	1	EA	510.00	510
34	1	EA	510.00	510
35	1	EA	810.00	810
36	12	EA	810.00	9,720
37	1	EA	910.00	910
38	2	EA	835.00	1,670
39	1	EA	835.00	835
40	49	EA	985.00	48,265
41	18	EA	835.00	15,030
42	2	EA	1,785.00	3,570
43	5	EA	785.00	3,925
44	1	EA	805.00	805
45	1	EA	1,835.00	1,835
46	6	EA	2,005.00	12,030
47	1	EA	3,085.00	3,085
48	2	EA	1,470.00	2,940
49	1	EA	885.00	885
50	1	EA	1,045.00	1,045
51	3	EA	1,345.00	4,035
52	1	EA	1,415.00	1,415
53	5	EA	1,665.00	8,325
54	3	EA	1,485.00	4,455
55	2	EA	1,135.00	2,270
56	3	EA	2,790.00	8,370
57	2	EA	1,945.00	3,890
58	1	EA	4,270.00	4,270
59	1	EA	4,465.00	4,465
60	1	EA	4,445.00	4,445
61	2	EA	4,610.00	9,220
62 - Coiling dr		w/Unit Cost		
Toilet rm - multi user	12	EA	1,200.00	14,400
Storage rm - sgl	1	EA	550.00	550
				-----
				366,760

089000 LOUVERS & VENTS

Exterior Windows:

Vert Alum louver w/damper (RFI #17)	660	SF	125.00	82,500
-------------------------------------	-----	----	--------	--------

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

Roof Openings:				
Elevator vent	1	EA	1,500.00	1,500
				-----
				84,000

## DIVISION 09 - FINISHES

## 090003 TILE\*

\*Noted 5'6" on A441

## Wall Finishes:

## Drinking Fountain Alcove (7 loc):

Ceramic wall tile 6'h	405	SF	35.00	14,175
-----------------------	-----	----	-------	--------

## Multi User Toilet Rm (16 EA)

Ceramic wall tile 6'h	1,355	SF	23.00	31,165
-----------------------	-------	----	-------	--------

## Sgl User Toilet Rm (15 EA):

Ceramic wet wall tile 6'h	835	SF	23.00	19,205
---------------------------	-----	----	-------	--------

## 1/4" Stl plate @ tile - 6" w (10/A620)

*Tile includes alum trim	1	LS	30,000.00	30,000
--------------------------	---	----	-----------	--------

Tile Backer Bd Premium	2,595	SF	1.85	4,801
------------------------	-------	----	------	-------

## Floor Finishes:

## Café/Learning Commons:

Porcelain tile	5,583	SF	24.00	133,992
----------------	-------	----	-------	---------

Anti-fracture membrane	5,583	SF	6.00	33,498
------------------------	-------	----	------	--------

## Quarry Tile:

Kitchen / servery	1,654	SF	17.25	28,532
-------------------	-------	----	-------	--------

Wall base	290	LF	9.75	2,828
-----------	-----	----	------	-------

Anti-fracture membrane	1,654	SF	6.00	9,924
------------------------	-------	----	------	-------

-----  
308,119

## 090006 RESILIENT FLOORING\*

## Floor Finishes:

Moisture mitigation -spec	46,242	SF	1.00	46,242
---------------------------	--------	----	------	--------

LT-linoleum tile TYP	59,665	SF	5.00	298,325
----------------------	--------	----	------	---------

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
LP - linoleum plank Corridor	28,786	SF	6.50	187,109
LP - linoleum plank breakout area		w/ corr.		
Acoustical Mat - nr 99 (2nd & 3rd flr)	40,000	SF	2.50	100,000
*Includes sections 0965000 & 096513				
Wall Finishes:				
Wall base 12" VCT tile w/ Schluter top edg	28,500	LF	6.50	185,250
Wall base 6" @ locker box	1,050	LF	5.00	5,250
Typ resilient wall base - allow	1	LS	7,500.00	7,500
Stair Finishes:				
Metal Pan Stair Learning Commons Stair ( 4 FLT):				
VCT tile landing	172	SF	8.00	1,376
VCT treads & risers w/rub nosing	678	LFR	14.25	9,662
Aud Stair Finish		W/ C1030		
				-----
				840,714

## 090009 PAINTING\*

## Exterior Walls:

Misc exterior painting -allow	1	LS	10,000.00	10,000
-------------------------------	---	----	-----------	--------

## Exterior Doors:

Paint HM door & Frame - sgl	5	EA	120.00	600
Paint HM door & Frame - dbl	9	EA	225.00	2,025

## Interior Doors:

## Paint Int HM door frame:

Single Door 7'H	22	EA	125.00	2,750
Double Door 7'H	1	EA	145.00	145
Single Door 8' H	251	EA	140.00	35,140
Double door 8'H	26	EA	160.00	4,160

## Paint Int HM door:

Sgl B1 7'H	15	EA	150.00	2,250
90 Min Sgl B1 7'H	1	EA	150.00	150
Dbl B2 7'H	1	EA	300.00	300
Sgl B1 8'H	25	EA	175.00	4,375
90 Min Sgl B1 8'H	1	EA	175.00	175
90 Min Dbl B2 8'H	3	EA	300.00	900

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Roof Construction:				
Intumescent paint - roof struct.	1	LS	75,000.00	75,000
*Exposed structure @ atrium noted				
*Includes Section 099646				
Stair Finishes:				
Paint Metal Pan Stair & Rail:				
5' W @ Learning Commons 1st- 3rd	2	FLTS	2,500.00	5,000
8' W @ Learning Commons 1st- 2nd	2	FLTS	2,750.00	5,500
5' W @ Stair Hall	5	FLTS	2,500.00	12,500
Seal Concrete Finish:				
5' W @ Stair Hall	5	FLTS	2,000.00	10,000
Wall Finishes:				
Interior painting- walls	136,600	GSF	1.90	259,540
Floor Finishes:				
SC Sealed Concrete Floor Finish (030513):				
Storage, mech, elec & receiving	5,561	SF	2.00	11,122
Ceiling Finishes:				
Paint gyp ceiling	45,000	SF	1.00	45,000
Paint gyp soffits	1	LS	25,000.00	25,000
Paint exposed structure- 100%:				
Class Small Closet( 34 loc)	408	SF	2.00	816
Typ mech, elec & storage rm	5,759	SF	2.00	11,518
Auditorium & stage	5,996	SF	2.50	14,990
Main gym deck	8,268	SF	4.00	33,072
Typ, Sci, Art, Music, & Media - exp deck	23,986	SF	2.00	47,972
Stair hall	1,203	SF	2.00	2,406
				-----
				622,406

## 092116 GYPSUM WALLBOARD ASSEMBLIES

Exterior Walls:				
1 lyr 5/8" gyp @ stud	43,553	SF	3.25	141,547
Exterior Walls:				
Exterior wall Backup:				
10" x 16 Ga. stud @ Typ 14'	41,075	SF	11.70	480,578
10" x 16 Ga. stud @ raised common 5-6'h	2,486	SF	11.70	29,086
Entry pier/chimney framing-14'H	668	SF	9.85	6,580
1/2" Dens glass sheathing	44,229	SF	3.30	145,956

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
* Mech Penthouse Unit - Complete		W / HVAC		
Ext Ceiling Framing @ :				
Canopy & covered entry	1,056	SF	6.50	6,864
1/2" Dens glass sheathing	1,056	SF	3.50	3,696
Partitions:				
H6 Elevator shaft - 56'6"H	2,095	SF	18.00	37,710
C4 Auditorium - 28'H	952	SF	18.00	17,136
C7 Auditorium - 28'H	4,755	SF	18.00	85,590
Stage front	120	SF	9.00	1,080
F1 gym storage - 28'H	695	SF	18.00	12,510
F1 gym storage chase 1 side - 28'H	105	SF	16.00	1,680
1 side class radial mech chase 14'H	7,318	SF	12.00	87,816
Chase @ fnd wall 14'H	996	SF	10.00	9,960
Drinking fountain chase wing wall 14'H	689	SF	10.00	6,890
D6 & D6 Bulkhead @ dbl op part - 6'H	114	SF	15.00	1,710
Curb 1'H @ glazed part	866	SF	15.00	12,990
Bulkhead 6'H @ glazed part	5,196	SF	12.00	62,352
F6 Bulkhead @ op part - 6'H	1,248	SF	12.00	14,976
B1 Atrium shaft 2nd - high roof	4,107	SF	16.50	67,766
TYP -14' Drywall Partitions:				
B1	1,621	SF	9.15	14,832
B3	417	SF	10.15	4,233
B4	4,116	SF	12.15	50,009
C2	5,578	SF	14.65	81,718
C3	9,149	SF	14.65	134,033
C4	2,589	SF	14.65	37,929
C6	3,620	SF	16.90	61,178
C7	1,112	SF	14.65	16,291
C8	181	SF	19.40	3,511
C10	229	SF	16.90	3,870
D3	1,429	SF	12.65	18,077
D6	455	SF	14.90	6,780
E3	10,614	SF	17.15	182,030
E4	580	SF	17.15	9,947
E6	1,181	SF	19.40	22,911
E7	894	SF	24.15	21,590
E8	18,658	SF	21.90	408,610
E9	2,588	SF	21.90	56,677
F1	4,933	SF	19.65	96,933
F2	2,142	SF	21.90	46,910
F6	4,592	SF	19.65	90,233
F8	775	SF	24.40	18,910
H4	1,232	SF	14.65	18,049
J1	7,734	SF	19.30	149,266



DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
J2	596	SF	16.40	9,774
K1	7,317	SF	23.80	174,145
K2	1,724	SF	23.80	41,031
GWB @ Corridor Locker Enclosure (nic mtl locker) & Rails - allow:				
Freestanding locker box - 1st flr	307	LF	60.00	18,420
Freestanding - locker box upper flr w/ soffit	724	LF	120.00	86,880
Upper flr guardrail w/ soffit (6/A650)	327	LF	55.00	17,985
Cohort # 2059 2nd flr guard rail w/soffit(6/	19	LF	55.00	1,045
Additional framing @ sloped AWP (A601)	10,700	SF	7.50	80,250
(5/A601) frame AV monitor box	65	EA	100.00	6,500
Tile Backer Bd Premium		W / TILE FSB		
Impact resis. Gwb premium	1	LS	50,000.00	50,000
Misc. GWB assemblies (inc extruded alum	136,600	GSF	0.50	68,300
Load, Distribute and Misc.	136,600	GSF	0.50	68,300
*Partitions include sound attenuation, tape & joint compound finish				
Ceiling Finishes:				
Acoustical Gypsum Plaster (092313):				
Clg spray sys - allow	1	LS	TBD	
Typ, Sci, Art, Music, SPED & ELL Classroom CLG & Soffits:				
Summer Beam bottom 3'W (1/A690)	3,530	SF	20.00	70,600
Summer Beam light cove & vert framing (1	2,354	LF	150.00	353,100
Typ. gyp clg bay	1,161	SF	15.00	17,415
Complete soffit @ gyp bay	326	LF	48.00	15,648
Complete beam box 11'6" bot	998	LF	80.00	79,840
Sloped ACT clg - metal deck transition sol	1,365	LF	32.00	43,680
Complete soffit @ OP partition class (6/A601)		N/A		
Central Corridor CLG & Soffits:				
Horiz gyp clg 8'AFF	6,049	SF	14.00	84,686
Horiz gyp clg 12'AFF	2,735	SF	14.00	38,290
(9/A690) Soffit @ bot of sloped ACT	1,852	LF	35.00	64,820
(8/A690) Soffit @ top of sloped ACT	1,852	LF	45.00	83,340
(7/A650) Cap @ locker box	565	LF	50.00	28,250
(6/A650) Soffit @ guardrail	367	LF	50.00	18,350
Misc. Soffits @:				
Toilet rm light cove (7/A690)	570	LF	65.00	37,050
ACT - GWB transition 8" AFF	75	LF	32.00	2,400
Pyramid Skylight 2'H	1,134	SF	45.00	51,030
Gyp Ceiling System :				
Atrium 3rd flr sloped gyp clg	4,700	SF	30.00	141,000
Typ gyp ceiling	1,917	SF	15.00	28,755

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Emergency shw gyp clg	54	SF	15.00	810
1 Hr gyp mech/elec	474	SF	15.00	7,110
2Hr gyp mech/elec	169	SF	22.00	3,718
A651 Underside monumental Stair w/ retur	800	SF	21.00	16,800
Underside proj rm/bridge	600	SF	21.00	12,600
Sub acoustical clg (2/A690)	5,296	SF	24.00	127,104
Breakout rm sloped gyp clg 50%	2,000	SF	16.00	32,000
Toilet/shw rm (3 loc)	438	SF	12.00	5,256
Partitions:				
<b>Breakout 3,400 GSF</b>				
Breakout Floor Framing -Allow:				
Light gauge floor	1,600	SF	20.00	32,000
9/16" Metal Deck	1,600	SF	4.00	6,400
Concrete Deck fill			w/ package #2	
Breakout A( 2 story):				
P lam wall finish -allow	54	SF	55.00	2,970
Typ GWB wall -sgl stud	900	SF	25.00	22,500
GWB chase wall-complete	978	SF	25.00	24,450
GWB roof	260	SF	25.00	6,500
Breakout B( 3 story):				
P lam wall finish -allow	74	SF	55.00	4,070
GWB chase wall-complete	2,688	SF	25.00	67,200
GWB roof	300	SF	25.00	7,500
Breakout C( 2 story w/ guard rail 3rd flr):				
P lam wall finish -allow	150	SF	55.00	8,250
Typ GWB wall -sgl stud	1,034	SF	25.00	25,850
GWB chase wall-complete	1,038	SF	25.00	25,950
Typ GWB knee wall -sgl stud	42	SF	25.00	1,050
GWB chase knee wall-complete	107	SF	25.00	2,675
Cap @ knee wall walls	44	LF	25.00	1,100
Breakout D( 1 story):				
P lam wall finish -allow	50	SF	55.00	2,750
Typ GWB wall -sgl stud	771	SF	25.00	19,275
GWB roof	205	SF	25.00	5,125
Breakout E ( 1 story):				
P lam wall finish -allow	47	SF	55.00	2,585
Typ GWB wall -sgl stud	611	SF	25.00	15,275
GWB chase wall-complete	286	SF	25.00	7,150
GWB roof	292	SF	25.00	7,300

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
				-----
				5,073,206
095100 ACOUSTICAL CEILING*				
A1 2'x2'and 4' x 3/4" ACT Ceiling System @ :				
A1 Typ ACT	2,525	SF	9.00	22,725
A1 Splayed ACT (20%)	1,870	SF	8.25	15,428
A2 2'x2'and 4' x 5/8" ACT Ceiling System @ :				
A2 Typ ACT	6,546	SF	8.25	54,005
A2 Splayed ACT (20%)	20,732	SF	8.25	171,039
A2 Breakout rooms (50%)	1,715	SF	10.00	17,150
A 3 ACT 2 x 2		N/A		
A 4 Kitchen / servery	1,688	SF	6.75	11,394
Random Size Ultima:				
Corridor 8'w	13,564	SF	10.00	135,640
Exterior Soffit panel		W /Ext Wall		
*Includes Sections 095100 & 095133				-----
				427,380
096446 WOOD & ATHLETIC FLOORING				
Floor Finishes:				
Main Gym:				
Moisture mitigation -(vapor retarder)	8,276	SF	4.75	39,311
Wood Maple Gym flooring	8,276	SF	19.00	157,244
Vented wall base	365	LF	9.85	3,595
Auditorium (8/A602) - Finish Carp Spec:				
Stage flooring - 4" assembly	1,540	SF	14.00	21,560
Stage nosing	59	LF	38.00	2,242
Stage wall base /transition	113	LF	9.85	1,113
*Includes Sections 096429 & 096466				-----
				225,065
096712 RESINOUS FLOORING				

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

Floor Finishes:

SGL User Toilet Room (15 EA) :

Epoxy flr w/int base	997	SF	18.00	17,946
Shw receptor 3x3	1	EA	550.00	550
Shw receptor 5x3	2	EA	700.00	1,400
Threshold/transition	15	EA	200.00	3,000

Multi User Toilet & Locker Room( 18 EA):

Epoxy flr w/int base	4,601	SF	18.00	82,818
Threshold/transition	18	EA	200.00	3,600

-----  
109,314

096800 CARPET

Floor prep	1,033	SF	0.25	258
------------	-------	----	------	-----

Floor Finishes:

Auditorium:

Carpet aisle	1,033	SF	6.00	6,198
Carpet aisle stair/stage (4 riser)	4	FLT	500.00	2,000

-----  
8,456

097217 DIGITAL IMAGE WALL COVERINGS

Wall Finish:

Mural - Digital image wall covering - install only w/ 1/2" GWB Back up:

Media center	1,400	SF	15.00	21,000
Main office	50	SF	50.00	2,500

-----  
23,500

097233 DRY-ERASE WALL COVERING

Wall Finish:

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Dry Erase Wall Finish	6,640	SF	25.00	166,000
				----- 166,000
 097733 SANITARY WALL PANELS				
Wall Finish:				
8' FRP Wall Panel -allow:				
Main kitchen	2,233	SF	9.75	21,772
				----- 21,772
 098100 ACOUSTICAL INSULATION				
		w/092116		----- 0
 098400 ACOUSTIC ROOM COMPONENTS				
Wall Finish:				
Fabric Wrapped Acoustical Panels 1":				
Media ctr	1,260	SF	32.00	40,320
Science Lab Classroom (260 SF /6 EA)	1,560	SF	32.00	49,920
Makerspace ( 1 EA)	224	SF	32.00	7,168
Fab-lab ( 1 EA)	250	SF	32.00	8,000
Art Class Room ( 1 EA)	300	SF	32.00	9,600
Teacher Prep Room ( 24 EA)		N/A		
Typ, SPED & ELL Classroom 206SF / 32	6,592	SF	32.00	210,944
Drama Classroom ( 1 EA)	300	SF	32.00	9,600
Band Rm ( 1 EA)	912	SF	32.00	29,184
Chorus Classroom ( 1 EA)	309	SF	32.00	9,888
Guidance Suite (133 SF /3 Loc)	399	SF	32.00	12,768
Break out areas		NIC		
Auditorium		NIC		
				----- 387,392

098415 WOOD FIBER ACOUSTICAL PANELS

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Wall Finish:				
Cementitious Wood Fiber Wall Panel:				
Music practice rm ( 3 EA)	409	SF	19.00	7,771
Band Rm ( 1 EA)	833	SF	19.00	15,827
Gymnasium	4,344	SF	19.00	82,536
				-----
				106,134

## DIVISION 10 - SPECIALTIES

## 101100 MARKERBOARDS &amp; TACKBOARDS

## Fittings:

## Allow:

Media center tack surfaces	100	SF	28.00	2,800
4'H Tack Board	30	EA	400.00	12,000

\*Dry-erase magnetic wall covering is included in C3010

-----  
14,800

## 101400 SIGNAGE

## Exterior Walls:

## Ext. Signage:

18" Cast bronze letter (1 loc) - chimney	6	EA	650.00	3,900
Cast lettering @ entry ramp	18	EA	500.00	9,000
Misc. bldg mtd signage -allow	1	LS	20,000.00	20,000

## Fittings

## Allow:

Building directory	1	EA	5,000.00	5,000
Dedication plaque	1	EA	3,800.00	3,800
Room ID sign	136,600	GSF	0.22	30,052
Misc Int. ADA signage	136,600	GSF	0.12	16,392

-----  
88,144

## 102113 TOILET COMPARTMENTS

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Fittings:				
HDPE Toilet Partitions:				
Std. partition	23	EA	1,220.00	28,060
HC partition	16	EA	1,430.00	22,880
Urinal screen	15	EA	310.00	4,650
				-----
				55,590

## 102600 WALL AND DOOR PROTECTION

Fittings:				
Vinyl/Acrylic Composite:				
Corner guard	1	LS	5,000.00	5,000
Crash rail	1	LS	5,000.00	5,000
				-----
				10,000

## 102813 TOILET ACCESSORIES

Fittings:				
SGL User Toilet Rm Accessories ( 15 ea):				
Tilt mirror @ wall hung lav	15	EA	220.00	3,300
Soap dispenser (owner furnish & installed)		NIC		
Toilet tissue dispenser	15	EA	48.00	720
San. prod. disposal	15	EA	60.00	900
Toilet grab bars	30	EA	85.00	2,550
Paper towel dispenser-allow	15	EA	135.00	2,025
Waste receptacle	15	EA	150.00	2,250
Elec hand dryer - allow		NIC		
Coat hook	15	EA	25.00	375
Fixed diaper changing sta - allow	3	EA	550.00	1,650
3' ADA SHW accessories -allow	1	EA	550.00	550
Multi User Toilet & Locker Rm Accessories (16 ea):				
Soap dispenser (owner furnish & installed)		NIC		
Toilet tissue dispenser	39	EA	48.00	1,872
San. prod. disposal	27	EA	60.00	1,620
Toilet grab bars	32	EA	85.00	2,720
Paper towel dispenser- 2/rm	32	EA	135.00	4,320
Waste receptacle - 2/rm	32	EA	150.00	4,800

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Elec hand dryer - allow		NIC		
Coat hook	39	EA	25.00	975
5' ADA shw accessories - allow	2	EA	550.00	1,100
Dressing Rm Accessories (2 ea):				
Soap dispenser (owner furnish & installed)		NIC		
Allow:				
Misc. locker rm accessories	2	EA	1,000.00	2,000
Janitor shelf/mop holder	7	EA	200.00	1,400
*Excludes classroom and workroom accessories				
				-----
				35,127

104000 SAFETY SPECIALTIES

Fittings:				
Safety Specialties :				
Hose connection cabinet	16	EA	350.00	5,600
First aid kit (nic sci rm)	6	EA	450.00	2,700
Fire Dept key cab	2	EA	1,000.00	2,000
Fire extinguisher and cab (nic sci rm)	20	EA	475.00	9,500
AED & cabinets	4	EA	750.00	3,000
*See also science equipment				
				-----
				22,800

107113 EXTERIOR SUN CONTROL DEVICES

Allow (per Spec)	1	LS	75,000.00	75,000
				-----
				75,000

109000 MISCELLANEOUS SPECIALTIES

Exterior Walls:



DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
LVL 2 entry flagpole 34' H	1	EA	9,000.00	9,000
Fittings:				
Phenolic Locker-Allow:				
15" wx12"dx36"H corridor (nic enclosure)	660	EA	415.00	273,900
Metal Locker:				
15"w x 15"d x 30"H PE student 2 tiered	40	EA	215.00	8,600
15"w x 15"d - Custodian/kitchen staff db	6	EA	265.00	1,590
12" Kitchen staff dbl tier	3	EA	265.00	795
Locker base @ :				
Student corridor		W /Enclosure		
PE student	50	LF	36.00	1,800
PE staff	9	LF	36.00	324
Free Standing Wood Bench:				
PE locker rm (2 EA)	12	LF	125.00	1,500
Health office cubicle track w/ curtain	3	EA	1,325.00	3,975
Safety Specialties (104000):				
Hose connection cabinet	16	EA	350.00	5,600
First aid kit (nic sci rm)	6	EA	450.00	2,700
Fire Dept key cab	2	EA	1,000.00	2,000
Fire extinguisher and cab (nic sci rm)	20	EA	475.00	9,500
AED & cabinets	4	EA	750.00	3,000
*See also science equipment				
Secure wall panels-Allow:				
OT/PT rm (1 ea)	320	SF	15.00	4,800
Padded athletic flr tiles - allow:				
OT/PT rm (1 ea)	100	SF	15.00	1,500
Partitions:				
Folding Panel partition:				
16' x 8' H Typ classroom (13 EA)	1,664	SF	110.00	183,040
(22/A620)Dbl 19' x 8'H Music rm acoustic	152	SF	110.00	16,720
8' H SPED suite (3 LOC)	960	SF	110.00	105,600
*Includes pass dr & white bd finish				
*Includes Sections 102123, 102239, 105113, 105123 & 107113				
				-----
				635,944

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
DIVISION 11 - EQUIPMENT				
113100 RESIDENTIAL APPLIANCES				
Custodian Storage Rm #1216:				
Stack washer/dryer	1	EA	2,500.00	2,500
Custodian Office/Break Rm (1 EA):				
Refrigerator -full size	1	EA	1,400.00	1,400
Staff Dinning Rm ( 1 ea):				
Refrigerator -full size	1	EA	1,400.00	1,400
Medical Suite:				
Refrigerator -full size	1	EA	1,400.00	1,400
SPED Classroom 1260 (12/A410):				
Range	1	EA	750.00	750
Refrigerator	1	EA	1,400.00	1,400
Washer	1	EA	1,500.00	1,500
Range hood		NIC		
Dryer		NIC		
Dishwasher		NIC		
Kitchen washer and dryer		W / Kitchen Equipment		
Science rm appliance		W / Science Equipment		
				-----
				10,350
114000 FOOD SERVICE EQUIPMENT				
Kitchen equipment & casework	1	LS	415,270.00	415,270
*Kitchen equipment & casework Quote 7/19/2019				
				-----
				415,270
115213 PROJECTION SCREENS				
Projection Screen - Elec Op. - Allow:				
18' auditorium (spec)	1	EA	15,000.00	15,000
18' Café/Learning commons (clg plan)	1	EA	15,000.00	15,000
18' Gym - allow	1	EA	15,000.00	15,000
Media center (spec)	2	EA	10,000.00	20,000

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

-----  
65,000

## 116143 THEATRICAL EQUIPMENT(No Spec)

Auditorium (6/28/2019 Quote 420 Seat)- Allow:

Theatrical Rigging	1	LS	158,300.00	158,300
Theatrical Draperies	1	LS	33,854.00	33,854
Theatrical Lighting Instruments & Access.	1	LS	129,018.00	129,018
Theatrical Lighting Control System	1	LS	95,749.00	95,749

Technology and Local Sound:

Gym	1	EA	120,000.00	120,000
Café	1	LS	50,000.00	50,000
Aud Audio Visual System	1	LS	200,000.00	200,000
Band and Chorus Class	1	LS	60,000.00	60,000
Drama Class	1	LS	20,000.00	20,000

-----  
866,921

## 116600 ATHLETIC &amp; SPORTS EQUIPMENT

Main Gym:

Basketball backstops - electric	6	EA	9,500.00	57,000
Wall padding	861	SF	17.00	14,637
Motor op divider curtain (51'x24')-allow	1,224	SF	16.00	19,584
Volley ball court equip.	2	PR	700.00	1,400
Scoreboard (2 EA Spec 116643)		W / Electrical		
Wall Mtd Motor op Bleacher (qty noted)	650	SEAT	85.00	55,250
Batting cage (not shown)	1	EA	10,000.00	10,000

\*Includes Sections 116623 - 116653

-----  
157,871

## 119000 MISC. EQUIPMENT

Allow -Science Lab Classroom Equipment ( 6 EA):

Safety glasses monitor case	6	EA	1,000.00	6,000
Glassware pegboards ( 1/RM) - allow	6	EA	350.00	2,100
Sgl sided fume hood #2210	1	EA	7,200.00	7,200

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Dbl sided fume hood #2214	1	EA	9,500.00	9,500
First aid kit - allow	6	EA	300.00	1,800
OH track - equip support - allow		NIC		
Safety SHW		w/ plumbing		
Fire blanket	6	EA	500.00	3,000
Fire ext & cab ( 1/RM)	6	EA	425.00	2,550
Misc equipment	6	RM	500.00	3,000
Science Shared Prep Room Equipment ( 3 EA):				
Refrigerator - full size	3	EA	750.00	2,250
Dishwasher under counter	3	EA	1,100.00	3,300
Glassware pegboards (1 RM) - allow	1	EA	350.00	350
Misc equipment	3	RM	500.00	1,500
Chem storage/fume unit	3	EA	8,500.00	25,500
*Includes Sections 115300 - 115313				
Allow:				
Loading dock bumpers	1	LS	3,500.00	3,500
Kiln (11.38)	1	EA	4,000.00	4,000
Metal storage shelving		NIC		
Library equipment		NIC		
Power op changing table- Hoyer lift		NIC		
Vocational shop equipment(spec 115700)	1	LS	25,000.00	25,000
A420 Exhaust hood Tech Lab		W/Vocational allowance		
*Includes Section 115300, 115313 & 115700				
				-----
				100,550

## DIVISION 12 - FURNISHINGS

## 122400 WINDOW SHADES

Exterior Manual op Window Shade	8,000	SF	8.00	64,000
Interior Roller Shade (4/A690):				
Int borrowed light	3,304	SF	6.50	21,476
Door Manual Shade				
Single Door	50	EA	150.00	7,500
A312 Int panel grilles (Rulon)		W / Finish Carpentry		

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
				----- 92,976
122414 MOTORIZED WINDOW SHADES				
Motorized skylight shade (122414)		NIC		----- 0
123553 CASEWORK				
Utility & closet shelving	1	LS	10,000.00	10,000
Solid surface lav ctr	243	LF	265.00	64,395
Display Case ( 6/A401)	18	LF	1,000.00	18,000
Art recess corridor #2000	1	LS	15,000.00	15,000
Classroom Entry:				
Corridor built-in bench A621 4'w	212	LF	400.00	84,800
Framing and Blocking:				
Corridor Locker Enclosure (nic mtl locker) - allow (7/A650):				
Freestanding - 1st flr	307	LF	320.00	98,240
Freestanding - upper flr	724	LF	320.00	231,680
Main Office 2nd Floor:				
P. lam Radial Reception counters	20	LF	650.00	13,000
Radial work island /work table	38	SF	165.00	6,270
Reception work ctr	10	LF	325.00	3,250
Tall storage unit 4'	3	EA	1,650.00	4,950
Mail unit wall cab	16	LF	750.00	12,000
Mail area work ctr	16	LF	250.00	4,000
Mobile storage cab (36"x27"h)	4	EA	1,200.00	4,800
Copier area work ctr	16	LF	250.00	4,000
Large conf base cab w/ctr	15	LF	450.00	6,750
Work space work ctr	16	LF	250.00	4,000
Library / Media Center (1 EA):				
P. lam circulation desk - radial	11	LF	1,200.00	13,200
Book shelving sys - free standing		NIC		
8'6" Book shelving sys-perm fixed unit	39	LF	500.00	19,500
P. lam work ctr	27	LF	175.00	4,725
Mobile storage cab (36"x27"h)	6	EA	1,200.00	7,200
30" P. lam work ctr	33	LF	220.00	7,260

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Science Lab Classroom ( 6 EA):				
Sink			w/ plumbing	
24" Epoxy ctr (no base cab (48.5LF/RM)	291	LF	295.00	85,845
24"H Epoxy backsplash ( 48.5 LF/RM)	582	SF	95.00	55,290
Mobile storage cab (36"wx27"h 8/RM)	48	EA	1,200.00	57,600
P lam Wall cab (10 LF/RM)	60	LF	210.00	12,600
Teachers demo table		NIC		
Student table		NIC		
Science Shared Prep Room ( 3 EA):				
Sink			w/ plumbing	
24" Epoxy ctr (no base cab )	54	LF	295.00	15,930
24"H Epoxy backsplash	109	SF	95.00	10,355
P lam Wall cab	30	LF	210.00	6,300
Mobile storage cab (36"wx27"h)	8	EA	1,200.00	9,600
Tech-Makerspace ( 1 EA):				
30" P. lam counter w/backsplash(no base c	10.5	LF	230.00	2,415
Mobile storage cab (36"x27"h)	1	EA	1,200.00	1,200
24" P. lam back splash	21	SF	25.00	525
4 Tier shelving unit	3	LF	400.00	1,200
(6.81) Shadow relief	2	EA	450.00	900
Fab-lab ( 1 EA):				
P.lam Counter	13.5	LF	230.00	3,105
Mobile storage cab (36"x27"h)	1	EA	1,200.00	1,200
24" P. lam back splash	27	SF	25.00	675
4 Tier shelving unit	3	LF	400.00	1,200
(6.81) Shadow relief 3D mdo	2	EA	450.00	900
Art Class Room (1 EA):				
3' Tall storage cab	4	EA	1,550.00	6,200
Epoxy ctr (no base cab)	20.5	LF	295.00	6,048
24"H Epoxy backsplash	41	SF	95.00	3,895
Class Closet ( 34 EA):				
12" MDO lowest Shelf w/ framing (4'6"/LC	153	LF	45.00	6,885
12" Shelving (4 tier- 18'/loc)	612	LF	42.00	25,704
Teacher Prep Room (24 EA):				
P Lam ctr w/ wd edge ( 11'/loc)		N/A		
12" MDO lowest Shelf w/ framing (9' LOC	216	LF	45.00	9,720
12" Shelving (4 tier- 36'/loc)	864	LF	42.00	36,288
Typ, SPED & ELL Classroom (32 EA - A410):				
30" P Lam ctr w/ wd edge ( 12' 6"/loc)	400	LF	275.00	110,000
30" P Lam flip top ctr w/ wd edge ( 3'/loc)	96	LF	325.00	31,200

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Mobile storage cab (36"wx27"h 3/RM)	96	EA	1,200.00	115,200
4 tier shelving unit (10' /loc)	320	LF	400.00	128,000
(6.81) Shadow relief 3D mdo (3/rm)	96	EA	450.00	43,200
Music Classroom ( 2 EA):				
30" P Lam ctr w/ wd edge	26	LF	275.00	7,150
Mobile storage cab (36"wx27"h 2/RM)	4	EA	1,200.00	4,800
Ext wall 4 tier shelving unit 8'6" - (1/loc)	17	LF	400.00	6,800
(6.81) Shadow relief 3D mdo (2/rm)	4	EA	450.00	1,800
Drama Classroom ( 1 EA):				
30" P Lam ctr w/ wd edge	16	LF	275.00	4,400
24" P.lam backsplash	32	SF	25.00	800
Mobile storage cab (36"wx27"h)	2	EA	1,200.00	2,400
SPED Classroom #1260 ( Additional casework 1 EA):				
Sink ctr w/skirt	6	LF	300.00	1,800
24" P.lam backsplash	17	SF	25.00	425
SPED Classroom #2260 ( Additional casework 1 EA):				
42" Wall cab	15	LF	225.00	3,375
Sink ctr w/skirt	15	LF	300.00	4,500
20" P.lam backsplash	25	SF	25.00	625
Staff Lunch Room ( 1 EA):				
Base cab w/p.lam ctr	7.5	LF	425.00	3,188
Custodian Office (1 EA):				
Work ctr	9	LF	165.00	1,485
Medical Suite (A425):				
Work ctr	15	LF	165.00	2,475
Wall cab	8	LF	200.00	1,600
Open wall cab	7	LF	225.00	1,575
Microwave shelf	3	LF	225.00	675
Aud Dressing room (2 EA):				
P.lam counter w/ backsplash(no base cab)	38	LF	225.00	8,550
Auditorium:				
P.lam AV ctr	9	LF	165.00	1,485
P.lam projector support	1	LOC	1,500.00	1,500
P lam low wall @ seating complete	89	LF	475.00	42,275
Guidance Suite (3 Loc):				
Base cab w/ctr	8	LF	350.00	2,625
Wall cab	15	LF	210.00	3,150

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

Misc. Casework Allowance:

Misc Display Cases (19/A621)	1	LS	20,000.00	20,000
Trash/ recycle ctr - allow	1	EA	10,000.00	10,000
Custom P lam radial bench - Corr #2000	38	SF	100.00	3,800
Kit. serving ctr (4/603)	32	LF	265.00	8,480

\*Counter tops include manufactures wall brackets

\*Includes Section 123653

-----  
1,577,937

124813 FLOOR MATS

Floor Finishes:

Recessed mtl vest. grille (2 loc)	360	SF	22.00	7,920
-----------------------------------	-----	----	-------	-------

-----  
7,920

124816 ENTRANCE GRILLES & FRAMES

w/124813

-----  
0

126613 TELESCOPING BLEACHERS

w/116000

-----  
0

129000 MISCELLANEOUS FURNISHING

Auditorium fixed seat	321	EA	295.00	94,695
Removable auditorium seat	46	EA	125.00	5,750
Stackable auditorium seat	48	EA	125.00	6,000

\*Includes Section 126100

Choral classroom risers

W/FFE



DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Band classroom risers		W/FFE		
Stage risers		W/FFE		
*Includes Section 126100				-----
				106,445
DIVISION 13 - SPECIAL CONSTRUCTION				
130000 SPECIAL CONSTRUCTION		N/A		
				-----
				0
DIVISION 14 - CONVEYING EQUIPMENT				
140001 ELEVATORS*				
Passenger elevator ( 1 door - 4,500 lb)	4	STOP	53,000.00	212,000
*Includes roof level stop				-----
				212,000
DIVISION 21 - FIRE SUPPRESSION				
210001 FIRE SUPPRESSION*				
6" BF Preventer	1	EA	7,450.00	7,450
Wet valve assembly	1	LS	3,500.00	3,500
Elec. bell	1	LS	1,500.00	1,500
Siamese fire dept connection	1	LS	1,350.00	1,350
Fire Dept. Connection:				
2 1/2" w/cabinet	9	EA	1,850.00	16,650
Siamese FD Connection	2	EA	1,235.00	2,470
FCVA - 4"	9	EA	1,050.00	9,450
Tamper sw	30	EA	225.00	6,750
Heads and Branch:				
Semi Recess head - typ.	946	EA	315.00	297,990
Concealed head - aud.	41	EA	750.00	30,750

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Upright head	315	EA	329.00	103,635
Upright w/ cage	71	EA	360.00	25,560
Sidewall	144	EA	285.00	41,040
Window wash	12	EA	385.00	4,620
3" drain	220	LF	31.50	6,930
2 1/2" - 6"	5,100	LF	39.00	198,900
4" Shut off	4	EA	1,025.00	4,100
6" Shut off	4	EA	1,185.00	4,740
Misc. Valve	1	LS	10,000.00	10,000
Underground Fire Prot. Service:				
6"	10	LF	110.00	1,100
Coring and firesafing	1	LS	5,000.00	5,000
Staging and Lifts	1	LS	30,000.00	30,000
Test, as built	1	LS	40,000.00	40,000
				-----
				853,485

## DIVISION 22 - PLUMBING

## 220001 PLUMBING\*

## Plumbing Fixtures ( Per Plumbing):

P-1 water closet	20	EA	1,850.00	37,000
P-1A water closet	31	EA	1,850.00	57,350
P-2 Urinal	18	EA	1,575.00	28,350
P-2A Urinal	8	EA	1,575.00	12,600
P-3 Lav ctr mtd	47	EA	1,100.00	51,700
P-3A Lav wall hung	31	EA	1,375.00	42,625
P-4 Drinking Fountain (high/low)	11	EA	3,150.00	34,650
P-5 Mop Receptor	5	EA	1,425.00	7,125
P-6 Shower 3x3	1	EA	2,850.00	2,850
P-6 Shower 5x3	2	EA	3,000.00	6,000
P-7 Science	40	EA	2,200.00	88,000
P-7A	2	EA	2,200.00	4,400
P - 8	4	EA	1,500.00	6,000
P - 9 Art Sink w/ Plaster Trap	4	EA	2,150.00	8,600
P - 10 Eye Wash Station	5	EA	2,800.00	14,000
Sink - Aud. dressing rm	4	EA	1,500.00	6,000
Sink - health office	1	EA	1,500.00	1,500
Sink - SPED	1	EA	1,500.00	1,500
Sink - Tech Lab	2	EA	1,500.00	3,000
Sensor Faucet ( spec only)	78	EA	525.00	40,950

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Sensor Flush ( spec not indicated)	77	EA	485.00	37,345
FPSC wall hydrant	8	EA	450.00	3,600
HB hose bibb	18	EA	350.00	6,300
IMB Conn	5	EA	500.00	2,500
Fix Connection	237	EA	300.00	71,100
Misc. Specialties:				
MV-1	1	EA	7,500.00	7,500
MV-2 - science room	5	EA	1,250.00	6,250
1" Mech BFP	3	EA	950.00	2,850
Misc. Mix valve	4	EA	450.00	1,800
P - 11 Fume Hood Connection	3	EA	2,500.00	7,500
Heat Trace non potable water ( spec )	1	LS	5,000.00	5,000
Fire sealing penetration	1	LS	45,000.00	45,000
Elevator Sump pump	1	EA	3,500.00	3,500
Pumps:				
RP-1 & RP-2	2	EA	15,000.00	30,000
RP-3	1	EA	4,500.00	4,500
RP-4	1	EA	4,500.00	4,500
Gas Fire Hot Water Supply Boiler:				
BLR-1, 2(Lochinvar - Armor AWN501P )	2	LS	19,500.00	39,000
HW Storage Tank	1	EA	18,000.00	18,000
Mech Rm Neutralization	1	EA	4,000.00	4,000
Boiler Valve and Trim	1	LS	30,000.00	30,000
Heat Trace	1	LS	7,500.00	7,500
Interior Grease Interceptor:				
GI-1 & GI-2	2	EA	8,500.00	17,000
Roof/Storm Drain System				
Underground D/W/V Pipe:				
4"	61	LF	46.00	2,806
6"	75	LF	61.00	4,575
8"	75	LF	96.00	7,200
10"	93	LF	110.00	10,230
12"	19	LF	132.00	2,508
FCO	8	LF	425.00	3,400
Above Ground D/W/V Pipe:				
4"	230	LF	48.00	11,040
6"	932	LF	63.00	58,716
8"	486	LF	99.50	48,357
10"	150	LF	112.00	16,800
CO	20	EA	400.00	8,000
RD - 4"	7	EA	1,275.00	8,925

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
RD - 5"	3	EA	1,320.00	3,960
RD - 6"	9	EA	1,460.00	13,140
RD - 8"	2	EA	1,545.00	3,090
Insulate leader	1,000	LF	13.00	13,000
Footing drain	100	LF	36.50	3,650
Acid Waster System:				
Underground D/W/V Pipe:				
2"	43	LF	41.00	1,763
4"	587	LF	62.00	36,394
FCO	6	EA	485.00	2,910
FD	5	EA	725.00	3,625
Above Ground Sanitary D/W/V Pipe:				
4"	447	LF	67.00	29,949
Acid Neutralization Precast Structure	1	EA	15,000.00	15,000
Neutralization Tank and Alarm	1	EA	35,000.00	35,000
Precast Pump Chamber	1	EA	25,000.00	25,000
Domestic Piping:				
1 1/2"	339	LF	33.90	11,492
1 1/4"	754	LF	27.80	20,961
1"	2,900	LF	23.65	68,585
1/2"	1,245	LF	18.10	22,535
2 1/2"	533	LF	66.00	35,178
2"	735	LF	48.20	35,427
3"	50	LF	89.00	4,450
3/4"	1,590	LF	20.60	32,754
6"	100	LF	162.00	16,200
Kitchen conn	1	LS	30,000.00	30,000
Water Hammer arrestors	1	LS	5,000.00	5,000
1" Pipe Insulation:				
1 1/2"	339	LF	8.00	2,712
1 1/4"	754	LF	7.90	5,957
1"	2,900	LF	7.50	21,750
1/2"	1,245	LF	7.10	8,840
2 1/2"	533	LF	9.00	4,797
2"	735	LF	8.45	6,211
3"	50	LF	9.50	475
3/4"	1,590	LF	7.40	11,766
6"	100	LF	14.45	1,445
Sanitary System				
Underground D/W/V Pipe:				
2"	79	LF	32.00	2,528
3"	392	LF	38.00	14,896

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
4"	971	LF	49.00	47,579
5"	284	LF	56.00	15,904
6"	14	LF	63.00	882
8"	31	LF	99.50	3,085
Floor Drain	17	EA	580.00	9,860
Gas and Sand separator	1	EA	15,000.00	15,000
5,000 gal. Grease Trap	1	EA	22,000.00	22,000
Sewer manhole	1	EA	4,000.00	4,000
Floor Sink	8	EA	2,200.00	17,600
FCO	25	EA	425.00	10,625
Above Ground D/W/V Pipe:				
2"	1,600	LF	32.00	51,200
3"	600	LF	38.00	22,800
4"	1,249	LF	49.00	61,201
FD	18	EA	800.00	14,400
CO	20	EA	495.00	9,900
Trap primer Pipe	1	LS	5,000.00	5,000
Roof Vent Term.	8	EA	1,100.00	8,800
Gas Pipe:				
1" - Science hw conn?	300	LF	36.00	10,800
2" - main	135	LF	75.00	10,125
3/4" - kitchen	50	LF	30.00	1,500
1" - 1/2' lab connection	1	RM	30,000.00	30,000
Kitchen Connection	1	LS	5,000.00	5,000
Boiler Room Connections	1	LS	5,000.00	5,000
Kitchen Master Shut off	1	LS	4,000.00	4,000
Gas sub metering	3	EA	3,000.00	9,000
Flues:				
6" HW Flue	60	LF	95.00	5,700
Generator:				
Gas Connection	1	LS	25,000.00	25,000
Exhaust Breeching		NIC		
Underground Water Service:				
6"	10	LF	150.00	1,500
Meter Install Only	1	EA	2,500.00	2,500
Sub-meter	3	EA	3,000.00	9,000
6" BFP	1	EA	12,500.00	12,500
Staging and Lifts	1	LS	30,000.00	30,000
Commissioning Coordination	200	HRS	125.00	25,000
Sanitize system	1	LS	25,000.00	25,000
Test , permit misc gc	1	LS	75,000.00	75,000

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
				-----
				2,148,401

## DIVISION 23 - HVAC

## 230001 HVAC\*

## Rooftop Units:

RTU-1 (22,000 cfm)	20,000	CFM	15.00	300,000
RTU-2 (22,000 cfm)	20,000	CFM	15.00	300,000
RTU-3 (22,000 cfm)	20,000	CFM	15.00	300,000
RTU-4 (22,000 cfm)	20,000	CFM	15.00	300,000
RTU-5 (15,000 cfm)	15,000	CFM	15.00	225,000
RTU-6 (12,000 cfm)	12,000	CFM	15.00	180,000
RTU-7 (2,000 cfm)	2,000	CFM	13.50	27,000

## Make Up Air Units:

MAU-1 (5,000 cfm)	4,170	CFM	12.00	50,040
Sound Attenuators ( 17 ea )	218,000	CFM	0.55	119,900

## Exhaust Fans:

EF-1 G-VG - roof	1	EA	3,150.00	3,150
EF-2 G-VG - roof	1	EA	3,150.00	3,150
EF-3 G-VG - roof	1	EA	3,150.00	3,150
EF-4 G-VG - roof	1	EA	3,150.00	3,150
EF-5 SQ-VG - kiln	1	EA	2,850.00	2,850
SEF-1 QEI - roof	1	EA	22,000.00	22,000
SEF-2 QEI - roof	1	EA	22,000.00	22,000
SEF-3 QEI - roof	1	EA	22,000.00	22,000
SEF-4 QEI - roof	1	EA	22,000.00	22,000
KEF-1 Cube - roof	1	EA	5,500.00	5,500
KEF-2 Cube - roof	1	EA	5,500.00	5,500
FEF-1 Vektor - roof	1	EA	12,250.00	12,250
FEF-2 Vektor - roof	1	EA	12,250.00	12,250
FEF-3 Vektor - roof	1	EA	12,250.00	12,250
FEF-4 Vektor - roof	1	EA	12,250.00	12,250
FEF-5 Vektor - roof	1	EA	12,250.00	12,250

## Dust Collection:

DC-1	1	EA	35,000.00	35,000
------	---	----	-----------	--------

## Dust Connection:

Bandsaw	1	EA	2,500.00	2,500
Combo sander	1	EA	2,500.00	2,500
Planer	1	EA	2,500.00	2,500
Table swa	1	EA	2,500.00	2,500

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Jointer	1	EA	2,500.00	2,500
Miter saw	1	EA	2,500.00	2,500
HW System:				
HWB-1 (AR 4,000)	1	EA	52,500.00	52,500
HWB-2 (AR 4,000)	1	EA	52,500.00	52,500
HWP-1,2	2	EA	15,000.00	30,000
BP 1,2	2	EA	2,250.00	4,500
VFD	2	EA	3,200.00	6,400
Chemical feed	1	LS	35,000.00	35,000
Air separator	1	EA	2,800.00	2,800
Expansion tank	1	EA	3,200.00	3,200
8" Feed Manifold	50	LF	350.00	17,500
6" Manifold S&R	100	LF	225.00	22,500
Boiler piping trim and valves	1	LS	26,000.00	26,000
10" Flue	365	LF	185.00	67,525
Flue Roof Term and Mast	4	EA	1,500.00	6,000
PH Tank	1	LS	1,500.00	1,500
Intake Louver and Damper	1	LS	6,000.00	6,000
Exhaust Louver and Damper	1	LS	6,000.00	6,000
10" Boiler flue	275	LF	160.00	44,000
Elec Room Exhaust fan and Louver	1	LS	3,500.00	3,500
Air-Cooled Chiller:				
CH - 1	370	TON	1,050.00	388,500
Chiller rough in, valve and trim	1	LS	20,000.00	20,000
Pump Package	1	LS	175,000.00	175,000
Ductwork:				
Galv Ductwork	136,090	LBS	10.50	1,428,945
Stainless Steel - welded	4,000	LBS	25.00	100,000
Premium for perf atrium ducts	1	LS	25,000.00	25,000
20" Fabric duct soc	402	LF	36.50	14,673
24" Fabric duct soc	302	LF	41.00	12,382
Kitchen hood exhaust duct - welded	2,918	LBS	17.50	51,065
Alum. dishwasher ductwork	750	LBS	12.00	9,000
1" Duct insul	48,376	SF	4.10	198,342
Duct Liner	8,025	SF	6.25	50,156
Matt white Rigid duct insul;	20,000	SF	6.80	136,000
EPDM wrap	9,055	SF	12.00	108,660
2 HR Fire wrap - dbl wrap	849	SF	16.20	13,754
Plenum Air Intake				
Alum Louver	carried w/ exterior			
Motor Op damper	19	EA	4,500.00	85,500

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Ducted Plenum intake	19	EA	3,000.00	57,000
Air Devices:				
DD - 1	39	EA	450.00	17,550
DD - 2	116	EA	575.00	66,700
DD - 3	22	EA	375.00	8,250
DD - 4	7	EA	310.00	2,170
DD - 5	5	EA	875.00	4,375
DD - 6	4	EA	600.00	2,400
DD - 7	40	EA	775.00	31,000
DD - 8	3	EA	825.00	2,475
DD - 9	4	EA	975.00	3,900
E - 1	57	EA	195.00	11,115
R - 1	86	EA	185.00	15,910
R - 2	7	EA	195.00	1,365
SA - 1	14	EA	220.00	3,080
VAV Box	150	EA	1,250.00	187,500
CV Regulator	32	EA	980.00	31,360
Volume Damper	47	EA	245.00	11,515
Auto Damper	16	EA	1,400.00	22,400
Fire damper	30	EA	550.00	16,500
Destratification fan	3	EA	8,500.00	25,500
AC Split System:				
Ductless Cooling Unit Systems:				
DCUe-1	1	EA	7,800.00	7,800
DCUe-2	1	EA	10,500.00	10,500
DCUe-3	1	EA	10,500.00	10,500
DCUe-4	1	EA	9,500.00	9,500
DCUe-5	1	EA	9,500.00	9,500
DCUe-6	1	EA	9,500.00	9,500
DCUe-7	1	EA	9,500.00	9,500
DCUe-8	1	EA	9,500.00	9,500
Condensate Pumps:				
CP-1 & Cond. Piping	8	EA	1,200.00	9,600
Hydraunic Heater:				
Unit Heater	16	EA	1,100.00	17,600
RP - 1	1,341	LF	156.00	209,196
RP - 2	92	LF	156.00	14,352
FTR - 1	602	LF	68.00	40,936
FTR - 2	320	LF	68.00	21,760
FT Cover	934	LF	27.00	25,218
Modulating Valve	135	EA	285.00	38,475
Isolation valve	270	EA	92.00	24,840
Electric Fin Tube Heater	8	EA	950.00	7,600



DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
<b>Domestic Piping:</b>				
1 1/2"	1,031	LF	33.25	34,281
1 1/4"	897	LF	27.30	24,488
1"	2,139	LF	22.00	47,058
2 1/2"	723	LF	66.00	47,718
2"	1,516	LF	44.00	66,704
3"	504	LF	91.00	45,864
3/4"	7,788	LF	19.50	151,866
4"	967	LF	103.00	99,601
6"	1,374	LF	144.50	198,543
8"	243	LF	187.00	45,441
<b>1" Pipe Insulation:</b>				
1 1/2"	1,031	LF	8.00	8,248
1 1/4"	897	LF	7.90	7,086
1"	2,139	LF	7.50	16,043
2 1/2"	723	LF	9.00	6,507
2"	1,516	LF	8.45	12,810
3"	504	LF	9.50	4,788
3/4"	7,788	LF	7.40	57,631
4"	967	LF	11.90	11,507
6"	1,374	LF	14.45	19,854
8"	243	LF	16.25	3,949
<b>Mechanical Piping:</b>				
AHU Valving	8	EA	3,500.00	28,000
Misc. Control Valve	8	EA	2,500.00	20,000
<b>Temperature Control:</b>				
AHU/ERV	8	EA	25,000.00	200,000
Chiller and Cooling Equipment	1	LS	30,000.00	30,000
Boiler and Heating	1	LS	20,000.00	20,000
Pump	6	EA	1,800.00	10,800
VAV	156	EA	1,500.00	234,000
Hydronic point	135	EA	1,000.00	135,000
Exhaust Fan	17	EA	1,500.00	25,500
AC Split	8	EA	750.00	6,000
CO2 Sensor	119	EA	650.00	77,350
T stat	188	EA	485.00	91,180
Misc. temp control	1	LS	50,000.00	50,000
Seismic & vibrator control	1	LS	35,000.00	35,000
Test and balance	136,600	GSF	0.65	88,790
Staging and Lifts	1	LS	30,000.00	30,000
Commission coordination	1	LS	25,000.00	25,000
GC & misc.	1	LS	25,000.00	25,000

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
				-----
				8,281,591

## DIVISION 26 - ELECTRICAL

## 260001 ELECTRICAL\*

## Lighting Fixtures:

Exit	43	EA	324.20	13,941
G\$ - gym	80	EA	837.00	66,960
LC3 - classroom cove	1,927	LF	97.76	188,384
LK24	15	EA	267.00	4,005
LP4	6	EA	452.00	2,712
LP4S - aud	81	EA	775.00	62,775
LP8	6	EA	836.40	5,018
LR2 - typical	763	EA	402.00	306,726
LRD 5 - bathroom	12	EA	1,119.00	13,428
LRS - corridor	104	EA	783.60	81,494
LS2	2	EA	332.00	664
LS4	53	EA	362.00	19,186
LS8	17	EA	526.40	8,949
LWS - bathroom cove	647	LF	84.10	54,413
RC-1	92	EA	267.00	24,564
RSH	1	EA	282.00	282
SC - commons	40	EA	888.00	35,520
SL4 - exterior	19	EA	507.80	9,648
UC (as shown only)	66	LF	50.40	3,326
Branch Wiring	136,000	SF	1.25	170,000
Lighting Control System	136,000	SF	2.00	272,000

## Mechanical:

VAV 20A 1 frac	89	EA	182.20	16,216
WH 20A 1 1a	3	EA	182.20	547
WH 30A-3P-250v	1	EA	344.00	344
GB 30A-3P-250v	2	EA	611.00	1,222
J\$M	3	EA	182.20	547
Meters & flows & solen \$M WP	14	EA	182.20	2,551
MC-14/2 W/G	1,500	LF	1.69	2,529
MC-12/2 W/G	1,900	LF	1.71	3,241
MC-12/3 W/G	1,400	LF	2.14	2,996
MC-12/4 W/G	1,180	LF	2.56	3,026
MC-10/4 W/G	400	LF	4.56	1,825
UH	21	EA	182.20	3,826
EMT 3/4"C-3#12	2,800	LF	5.34	14,952

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
VFD FBO I&W	17	EA	216.00	3,672
25 - 100/100A/3/480v	4	EA	466.00	1,864
EMT-1 1/2"C-4#2 & 1#8	500	LF	15.76	7,880
GFI WP roof	22	EA	97.00	2,134
Roof stonco	10	EA	228.00	2,280
WP roof Switch	10	EA	87.00	870
EMT-3/"C-3#12 (roof)	3,450	LF	5.32	18,354
EMT-3/"C-4#12 (roof)	3,100	LF	5.80	17,980
CP-1	11	EA	182.20	2,004
MC-12/2 W/G	700	LF	1.71	1,194
JB 8x8x4	11	EA	68.20	750
480v 3 30A	11	EA	706.00	7,766
480v 3 40A	2	EA	938.00	1,876
EUH 250v 1 30A/2P	3	EA	416.00	1,248
ECU 208v 1 15A	11	EA	182.20	2,004
DCU J 208v 1 30A	11	EA	436.00	4,796
EMT-3/4"C-4#10	1,200	LF	6.38	7,656
ET 120v 1	8	EA	182.20	1,458
MAU-1 60/40A/3/480v	1	EA	391.00	391
EMT-1"C - 4#8 & 1#10	70	LF	7.14	500
Mechanical (cont):				
Boiler 20A - 1 30A/2P	3	EA	513.00	1,539
Boiler pumps 20A 2P 208v	3	EA	366.00	1,098
Chiller 480v 600/600A/3	2	EA	2,148.00	4,296
EMT-3"C - 3#250 mcm & 1#4	260	LF	32.56	8,466
EMT-3/4"C 4#8 & 1#10	140	LF	8.39	1,175
SEF 100/100A/3/480v	4	EA	650.00	2,600
#2 MI cable	1,600	LF	19.32	30,912
#2 MI terms (quick)	32	EA	116.00	3,712
RTU - 400/250A/3/3R	4	EA	971.00	3,884
RTU - 200/150A/3/3R	2	EA	613.00	1,226
RTU - 100/70A/3/3R	1	EA	486.00	486
RTU - 60/50A/3/3R	1	EA	391.00	391
EMT-3"C-4#250 & 1#4	520	LF	40.38	20,998
EMT-2"C-4#1/0 & 1#6	325	LF	21.96	7,137
EMT-1 1/4"C-4#4 & 1#8	150	LF	12.62	1,893
EMT-1"C-4#6 & 10	150	LF	10.25	1,538
Wiring Devices & Scoreboard Work:				
Duplex	388	EA	58.84	22,830
GFI duplex	109	EA	61.84	6,741
WP GFI	8	EA	94.00	752

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Surf double duplex	37	EA	124.00	4,588
Switched rec w/IO module	24	EA	240.00	5,760
NEMA L14-20R	27	EA	107.00	2,889
LS limit switch	3	EA	107.00	321
CP cont pnl - wire only	8	EA	144.00	1,152
TML mtr conn	8	EA	83.80	670
J 4" sq w/cover	6	EA	41.00	246
ISO grd out shot clock	2	EA	87.00	174
Wire only scoreboard	1	EA	144.00	144
30/20A/3240v	2	EA	269.00	538
EMT-3/4"C-4#12	1,800	LF	5.79	10,422
Double duplex - color	216	EA	101.40	21,902
Tw loc @ tray	11	EA	102.00	1,122
Cable tray 24"c12'0"	6	EA	309.00	1,854
Poke thru	2	EA	666.00	1,332
Key sw	1	EA	64.00	64
MOM conn cw	6	EA	70.00	420
CP bleacher pwr	7	EA	366.00	2,562
MC-12/2 w/G	39,500	LF	1.71	67,387
MC-12/3 w/G	2,000	LF	2.14	4,280
EMT-3/4"C - 3#12	1,900	LF	5.32	10,108
Emergency Generator & ATS:				
300kw 277/480v Natural Gas Generator	1	EA	159,320.00	159,320
Enclosure	1	EA	432.00	432
400A/3P output c/b	1	EA	144.00	144
150A/3P output c/b	1	EA	144.00	144
Interior panel	1	EA	288.00	288
Receive rig & set	1	EA	11,152.00	11,152
Unit mtd EPO	1	EA	638.00	638
Bldg mtd EPO	1	EA	907.00	907
Annunciator	1	EA	576.00	576
ATS-OS 400A 4P	1	EA	432.00	432
ATS-LS 150A 4P	1	EA	576.00	576
PVC-1"C-4#10 & 1#10	150	LF	4.01	602
PVC-1"C-14#13	150	LF	5.60	840
EMT-3/4"C-2#14	280	LF	5.12	1,434
EMT-3/4"C-5#14	120	LF	6.09	731
MI - 4#1/0	140	LF	107.36	15,030
MI - quick terms	8	LF	133.20	1,066
WIC 4#500 & 1#3	130	LF	45.84	5,959
EMT-4"C-4#500 & 1#3	140	LF	67.24	9,414
EMT-2"C-4#10 & 1#6	150	LF	21.96	3,294
Fire Alarm System:				
Material	1	LS	219,942.00	219,942
Bi-directional antenna sys	1	LS	4,752.00	4,752

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Elevator shaft & machine rm fitout	1	LS	3,456.00	3,456
Floor plan under glass	3	LS	144.00	432
Sprinkler bell I&W only	1	LS	216.00	216
DK drill key switch	1	LS	72.00	72
FACP flush control pnl	1	LS	4,608.00	4,608
Red beacon	1	LS	216.00	216
As built cabinet	1	LS	144.00	144
FM flush master box	1	LS	360.00	360
K knox box	1	LS	216.00	216
W white strobe	1	LS	144.00	144
LOC local operator control pnl	1	LS	864.00	864
Smoke exhaust graphic plaque w/LED indicator of statue	1	EA	1,152.00	1,152
FATC term cabinet	3	EA	864.00	2,592
ANN annunciator	3	EA	432.00	1,296
VE voice evac pnl	1	EA	2,304.00	2,304
MNS ??	3	EA	288.00	864
LS limit sw	6	EA	72.00	432
BD beam det xmit/rcur	5	EA	180.00	900
MM monitor module	66	EA	72.00	4,752
CM control module	26	EA	72.00	1,872
IM isolation module	3	EA	72.00	216
CO2 det tie in	1	EA	144.00	144
Security tie in	2	EA	144.00	288
Refuge tie in	1	EA	144.00	144
BDA tie in	5	EA	144.00	720
CO MM CO2 det w/monitor mod	9	EA	144.00	1,296
Smoke w/base	89	EA	72.00	6,408
Smoke to control atrium smoke	115	EA	72.00	8,280
Strobe only	61	EA	108.00	6,588
A/V unit	0	EA	0.00	0
A/V unit w/ amber alert	270	EA	144.00	38,880
FS TS flow & tampers	42	EA	72.00	3,024
Fire Alarm System ( cont):				
F Pull station	29	EA	61.20	1,775
MAG door holders	6	EA	72.00	432
ST1 stopper II 6500	29	EA	36.00	1,044
J 4" oct j-box	218	EA	33.80	7,368
J 4" sq w/device ring	158	EA	42.00	6,636
BB back box	331	EA	53.20	17,609
Programming & pretest	1	EA	1,728.00	1,728
FFD testing & cert	1	EA	1,728.00	1,728
ir & smoke test	1	EA	576.00	576
Water flow testing	1	EA	576.00	576

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
EMT-3/4"C-4#14	1,200	LF	5.42	6,504
AFC-#4901-16/2 14/2	13,160	LF	4.46	58,694
MC-4/C#14 red jacket	13,240	LF	2.64	34,954
Induct smoke	40	EA	288.00	11,520
Rem test sat	40	EA	108.00	4,320
Relay modules	40	EA	72.00	2,880
Monitor modules	40	EA	72.00	2,880
Mass notif UL listed computer	1	LS	50,000.00	50,000
Kitchen Power & Conns:				
S clg speaker	9	EA	381.00	3,429
Wall clock	1	EA	247.00	247
Voice outlet	1	EA	225.00	225
Duplex	36	EA	59.84	2,154
J	36	EA	92.00	3,312
TML-3/4"C-3#12	46	EA	50.24	2,311
TML-3/4"C-4#12	2	EA	61.00	122
TML-3/4"C-5#12	3	EA	69.60	209
TML-3/4"C-4#10	2	EA	81.80	164
TML-1 1/4"C-4#4 & 1#0	2	EA	132.00	264
60/50/3/250v	2	EA	286.00	572
30/20/3/250v	1	EA	228.00	228
30/3P/250v	2	EA	208.00	416
30/2P/250v	4	EA	198.00	792
Ther sw w/OL	9	EA	150.00	1,350
EMT-3/4"C-3#12	2,000	LF	5.32	10,640
EMT-3/4"C-4#12	100	LF	5.78	578
EMT-3/4"C-5#12	160	LF	6.24	998
EMT-3/4"C-4#10	100	LF	6.38	638
EMT-1 1/4"C-4#4 & 1#10	100	LF	13.19	1,319
MC-12/2 w/G	1,500	LF	1.85	2,775
CO2 gas solenoid shutdown	1	LS	3,404.00	3,404
Hood/ansul/EP work	1	LS	6,206.00	6,206
Master Lightning Protector Systems & Theatre:				
Theatrical ltg Rough-in	1	LS	98,780.00	98,780
Heary Bros Lightning Preventer Systems	2	EA	13,820.00	27,640
Window shade installation	1	LS	10,760.00	10,760
Area of refuge system	1	LS	16,676.00	16,676

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Integrated Electronic Security:				
Material - Turnkey:	1	LS	342,000.00	342,000
Includes:				
DSC Main cont pnl	1	EA		
12v 7 AH batteries	2	EA		
Xfmrs	2	EA		
Key lock w/relay mod	1	EA		
8 Zone expansion mod	1	EA		
16 Zone expansion mod	1	EA		
Addr. point modules	12	EA		
Touchscreen keypad	4	EA		
Wireless panic statin	6	EA		
Wireless received mod	1	EA		
Wall motions	35	EA		
Clg motions	38	EA		
Interface printer	1	EA		
Fargo photo badging	1	EA		
Flush door contacts	50	EA		
OHD central contacts	2	EA		
Cellular communicator	1	EA		
8 Reader controller	11	EA		
DSX proximity readers	18	EA		
Bosch rte motions	14	EA		
DSC lan module/software	1	EA		
160 TB Network video recorder	1	EA		
12MP camera	13	EA		
5 MP ext dome camera	2	EA		
Wall arms	2	EA		
5 MP Interior dome	27	EA		
5 MP indoor 360der dome	29	EA		
Rack w/receivers/mx mmtrs	1	EA		
Axis ect 360 deg camera	3	EA		
A1 phone master video	3	EA		
A1 phone IC-DF video door sta	4	EA		
Strong pole split 20'	3	EA		
43" Smart TV	2	EA		
55" Smart TV	2	EA		
Chief TV wall brkt	4	EA		
24 Port poe & sw	3	EA		
28 Port poe & sw	10	EA		
Programming	1	LS		
Accessories	1	LS		
Supervision & final conn	1	LS		
O&M manuals	1	LS		
Auto Cad dwgs	1	LS		
Owner training	1	LS		

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Structured Cabling System:				
Material - turnkey	1	LS	389,939.00	389,939
Includes:				
ACCU tech TS teacher sta	70	EA		
Programming	1	EA		
Supervision & final conn	1	EA		
O&M manuals w/closeout	1	EA		
Auto Cad drawings	1	EA		
Owner training	1	EA		
50 PR 66 blocks	6	EA		
25 PR 66 blocks	6	EA		
50 PR 110 blocks	6	EA		
Belden 2 post rack	8	EA		
Belden rack mt PDU	8	EA		
Belden 4 port face plate	150	EA		
Belden 2 port face plate	250	EA		
Belden F conn insert	70	EA		
Belden CAT6A green insert	400	EA		
Belden CAT6A blue insert	400	EA		
Belden 48 port patch pnl	12	EA		
Belden horiz cable mgr	40	EA		
Belden 10' patch cord	800	EA		
Belden CAT6A plenum blue	100	EA		
Belden CAT6A plenum green	100	EA		
Belden OS2 sm patch cord	100	EA		
Belden OM4 mm patch cord	100	EA		
Belden 4 cassettes hsg	8	EA		
Belden 6 fiber hsg	8	EA		
Belden 18 fiber hsg	8	EA		
Ground bars w/grd cable	1	LS	23,640.00	23,640
Conduit sleeves, cable tray and fiber backbone	1	LS	30,960.00	30,960
Intercom & Clock Systems:				
Material - turnkey	1	LS	119,970.00	119,970
Includes:				
Valcom 9 position back plane	1	EA		
Valcom main power supply	2	EA		
Valcom main VPV	1	EA		
Valcom Rack mount kit	1	EA		
Valcom dual 6A switching	1	EA		
Valcom 2x2 talkback spkr	240	EA		
Valcom call in pushbutton	66	EA		
Valcom GPS master clock	1	EA		



DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Valcom repeater	2	EA		
Valcom 12" round clocks	84	EA		
Valcom administrative teleph	1	EA		
Valcom 16" clocks/repeater	2	EA		
Valcom wire guard	2	EA		
Valcom power supply	1	EA		
Cowell rack equip	1	LS		
Atlas paging horns	21	EA		
Atlas flush enclosures	21	EA		
Atlas grills	21	EA		
Valcom retro blocks	3	EA		
Valcom power amps	3	EA		
Valcom rack mount kit	3	EA		
Valcom 24 pt talk back	3	EA		
Valcom admin gateway	1	EA		
Valcom volume control	21	EA		
Valcom network port/cards	1	EA		
Programming	1	LS		
Supervisions & final conn	1	LS		
O&M manuals & closeout	1	LS		
Auto cad swgs & submit	1	LS		
System testing	1	LS		
System owner training	1	LS		
A/V Systems:				
FSR	1	EA	951.40	951
Clg proj	1	EA	700.00	700
Duplex	41	EA	60.84	2,494
Data drop	43	EA	250.00	10,750
Hardwired AC pwr	2	EA	97.00	194
Chief PAC 526	3	EA	741.00	2,223
VI Wall proj IG deep	41	EA	44.00	1,804
SI Wall spkr 1G deep	82	EA	44.00	3,608
RI Rec pnl 2G deep	42	EA	57.80	2,428
BP ?? 2G deep	42	EA	57.80	2,428
J1 12'x12'x4" flush	2	EA	203.00	406
R2 2 gang deep	4	EA	74.00	296
R3 3 gang deep	4	EA	82.00	328
S2 clg loud spkr - b.box	10	EA	74.00	740
S3 clg loud spkr - b.box	8	EA	74.00	592
EMT-1 1/4"C- w/PS	480	LF	7.66	3,677
EMT-1 "C- w/PS	300	LF	6.19	1,857
EMT-3/4"C- w/PS	2,500	LF	4.63	11,575

Section 274100 A/V

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Includes Systems for:				
Classrooms		NIC		
Auditorium		w/equipment		
Auditorium av Rough-in	1	EA	45,000.00	45,000
Switchgear Panels & Transformers:				
45 KVA xfmr	8	EA	5,232.00	41,856
75 KVA xfmr	6	EA	7,540.00	45,240
Xfmr ground	14	EA	394.00	5,516
100A/3P/480v	3	EA	304.00	912
200A/3P/480v	3	EA	372.00	1,116
SFD 2500A @ 480v	1	EA	1,788.00	1,788
SPD panel mounted	39	EA	422.00	16,458
SPD grounds	40	EA	172.00	6,880
Elev controller	1	EA	144.00	144
100/100A/3P/480v	1	EA	339.00	339
30/20A/3P/208v	1	EA	218.00	218
TML 40	1	EA	204.00	204
100A/3/250v	1	EA	274.00	274
UPS system 24 kw	1	EA	24,880.00	24,880
Rigging for UPS	1	EA	2,432.00	2,432
EPO power off setup	1	EA	274.00	274
ST1 6500 guard	1	EA	127.00	127
Main service grounding	1	EA	822.00	822
Meter socket	1	EA	544.00	544
Main swbrd 3000A @ 480v	1	EA	40,896.00	40,896
Feeders	136,000	EA	1.95	265,200
Dist pnl 4DP1B-800A @ 480v	1	EA	7,248.00	7,248
Dist pnl 2DP1C-400A @ 208v	1	EA	5,160.00	5,160
Double tub pnl @ 120/208v	10	EA	3,890.00	38,900
Single tub pnl @ 120/208v	12	EA	2,752.00	33,024
400A-480v pnl	3	EA	5,072.00	15,216
225A-480v pnl	3	EA	3,052.00	9,156
100A-480v pnl	8	EA	2,688.00	21,504
DENIS VERIFY SECONDARY FEED				
60% CD Adders/Deletes:				
Integrated Electronic Security - 60% Adders/Deducts:				
Turnkey - Includes:	1	EA	27,000.00	27,000
Reader controller - add	1	EA		
Elevator controller - add	3	EA		
CR REX DC DC PS - add	1	EA		
CR DC REX PS - add	3	EA		
Wall motions - add	9	EA		
Ext. wall camera - add	1	EA		
Int. dome camera - add	1	EA		

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Int. 180 deg - add	30	EA		
Ext. 180 deg - add	14	EA		
Int. 360 deg - deduct	-29	EA		
Ext. 360 deg - deduct	-9	EA		
VES - add	1	EA		
VMS - deduct	-2	EA		
OHD - DC - add	2	EA		
Structured Cabling - 60% Adders/Deducts:				
Turnkey - Includes:	1	LS	97,000.00	97,000
IDE closets - reduced	-1	EA		
Teachers station - add	1	EA		
TVE - add	4	EA		
AN - add	115	EA		
N2D - delete	-7	EA		
2 Data - add	39	EA		
TVS-48	3	EA		
TVC-96	1	EA		
CAT 6A ports	1,135	EA		
48 Port patch pnl's	15	EA		
P.A. & Intercom - 60% CD Adders:				
Turnkey - Includes:	1	LS	20,000.00	20,000
Speakers - add	41	EA		
Volume control - add	6	EA		
12" Clocks - add	8	EA		
Ext. flush horn spkrs - add	2	EA		
#of classrooms - reduced	-9	EA		
IDF closets - reduced	-1	EA		
Fire Alarm & Gear - 60% Adders/Deducts:				
FA - A/V w/ amber alert	7	EA	419.00	2,933
S - smoke w/base	3	EA	162.00	486
W WP - A/V - WP	1	EA	271.00	271
BB backbox	7	EA	53.20	372
BB WP backbox WP	1	EA	63.40	63
J - 4" oct	3	EA	33.80	101
AFC - #4901 cable	300	LF	4.46	1,338
MC - 14/4C red jacket	50	LF	2.64	132
Dist. pnl 2 DP1A - 600A @ 480	1	EA	7,248.00	7,248
Dist. pnl 2 DP1B - 600A @ 480	1	EA	7,248.00	7,248
Upsize ATS-LS from 150 to 200A	1	EA	1,144.00	1,144
Upsize ATS-OS from 400 to 600A	1	EA	3,216.00	3,216
Upsize G/S from 250kw to 300 kw	1	EA	5,500.00	5,500
Upsize G/S output d/b from 400 to 600A	1	EA	2,000.00	2,000

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
ESL storm sw w/feeder tie	1	EA	6,830.00	6,830
Power Wiring Devices - 60% Adders/Deducts:				
Duplex	105	EA	58.84	6,178
GFI duplex	23	EA	62.84	1,445
WP GFI duplex	18	EA	94.00	1,692
NEMA CIS 3OR	1	EA	107.00	107
20A GFI - color	28	EA	71.84	2,012
Double duplex	42	EA	113.20	4,754
MC-10/3	60	LF	2.83	170
\$MC	2	EA	70.00	140
\$DW disc sw - DW	1	EA	82.00	82
J - dishwasher	1	EA	96.20	96
J - fume hood	1	EA	117.00	117
EF	2	EA	182.20	364
SEF	2	EA	182.20	364
KEF	1	EA	344.00	344
FEF	1	EA	344.00	344
DCU	2	EA	436.00	872
CPJ - bleacher power	1	EA	366.00	366
Scoreboard power & cont.	1	EA	463.00	463
Turnkey - area of refuge AKA				
2 way communication	1	LS	14,953.00	14,953
90% CD Adders/Deducts:				
Service, Fire Alarm - 90% CD Adders/Deducts:				
24 kw UPS	1	EA	24,380.00	24,380
EPO em. pwr off	1	EA	491.00	491
Disc sw.	1	EA	344.00	344
TEP2B - add section 2	1	EA	938.00	938
MP1A - add section 2	1	EA	938.00	938
Pnl ELIID - F&I new	1	EA	3,296.00	3,296
SPD - pnl mtd	2	EA	539.00	1,078
PNI - MHP-LR-F&I new	1	EA	3,640.00	3,640
ATS - LR-400A 4P	1	EA	7,448.00	7,448
Increase gen/set to 350 kw	1	EA	7,000.00	7,000
Add output c/b	1	EA	144.00	144
Misc. additional feeders	1	LS	27,960.00	27,960
MI cable #2 w/terms	1	LS	13,320.00	13,320
TS tamper or flow	23	EA	84.00	1,932
MM monitor module	23	EA	147.00	3,381
F pull station	5	EA	126.20	631
F - strobe	4	EA	233.00	932
S - smoke	6	EA	162.00	972

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
J	6	EA	30.20	181
J square	51	EA	36.24	1,848
BB	4	EA	46.00	184
4901 cable	500	LF	4.46	2,230
14/4C cable	2,800	LF	2.64	7,392
Security & Misc. Wiring Devices - 90% CD Adders/Deducts:				
WP - ext. camera	2	EA	1,125.00	2,250
Int. camera	3	EA	975.00	2,925
CR WP	3	EA	1,295.00	3,885
IC WP	1	EA	978.00	978
Door setups - box & conduit	4	EA	800.00	3,200
CR - interior	5	EA	1,295.00	6,475
DC	8	EA	275.00	2,200
Welder	1	EA	184.00	184
Duplex	79	EA	58.84	4,648
Duplex - double	34	EA	124.00	4,216
CR - clg for cord reel	8	EA	128.00	1,024
GFI	40	EA	61.84	2,474
Mech conn w/j.box	1	EA	83.80	84
G - sw. rec. w/ IL mod.	15	EA	240.00	3,600
USB - duplex w/USB outlet	7	EA	133.00	931
WP GFI	1	EA	94.00	94
Backboard gym setups	2	EA	391.00	782
MC-12/2 wG	10,740	LF	1.72	18,430
MC-6/3 wG	100	LF	4.16	416
Lighting, Controls, Mechanical - 90% CD Adders/Deducts:				
LR5D - deleted	-10	EA	95.00	-950
LS4B - deleted	-15	EA	375.00	-5,625
L - LV switch - add	10	EA	230.00	2,300
PC1 - add	16	EA	480.00	7,680
PC2 - add	9	EA	480.00	4,320
LR4 - deleted	-8	EA	450.00	-3,600
JB wall fixt. - add	8	EA	280.00	2,240
LS4 - add	3	EA	362.00	1,086
LP8 - add	3	EA	526.00	1,578
OS clg occ - add	4	EA	420.00	1,680
LR2 - add	499	EA	385.00	192,115
LC3 - add	980	LF	97.76	95,805
J - 4" oct j-box	46	EA	30.20	1,389
Mtg hdwre	530	EA	8.20	4,346
MC-12/2 w/ground	2,000	LF	1.72	3,432
CH-1 - control conn/heat tape	2	EA	591.00	1,182
DCV-8-208v 1 30A	2	EA	713.00	1,426

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
EFT - elec BB 2 kw 208v	8	EA	571.00	4,568
FEF - F.H. ex fan 480v 3	2	EA	942.00	1,884
KEF-2 - ex. fan 120v 1	1	EA	541.00	541
UH - unit heater 120v 1	3	EA	541.00	1,623
Technology Drawings - 90% CD Adders/Deducts:				
AN - wifi	8	EA	275.00	2,200
2 Data	24	EA	300.00	7,200
W - wall voice	21	EA	215.00	4,515
S clg spkr	11	EA	129.00	1,419
S clg spkr	52	EA	189.00	9,828
?	3	EA	295.00	885
S	10	EA	129.00	1,290
T	1	EA	500.00	500
IV/2D	5	EA	385.00	1,925
OH&P - 10%	1	LS	500,295.85	500,296
DJE	1	LS	150,000.00	150,000
Site Electrical Work:				
Utilities:				
PRI manhole dressing	1	EA	1,576.00	1,576
Utility pole PRI & FA dressing	1	EA	1,364.00	1,364
Utility pole commun. dressing	1	EA	1,076.00	1,076
Gen/set pad grndg	1	EA	982.00	982
Xfmr pad grndg	1	EA	1,376.00	1,376
Gen/set pad 90 deg. & sleeves	1	EA	566.00	566
Xfmr pad 90 deg. & sleeves	1	EA	688.00	688
Duct Bank CC:				
PVC-4"C - w/PS (120')	600	LF	4.38	2,628
PVC-1"C- w/4#12	480	LF	3.62	1,738
Duct Bank AA:				
PVC-4"C - w/PS (270')	540	LF	4.38	2,365
Duct Bank BB:				
PVC-4"C - w/PS (110')	770	LF	4.38	3,373
Duct Bank FF:				
PVC-4"C - w/PS (120')	240	LF	4.38	1,051
Duct Bank Fire Alarm:				

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
PVC-2"C - w/PS (300')	300	LF	2.06	618
IMSA 20-5 cable	350	LF	3.44	1,204
Duct Bank DD (230'):				
PVC-4"C - w/PS	920	LF	4.38	4,030
Inner duct 1 1/4"C- w/PS	690	LF	2.64	1,822
Ext camera on 20' pole	3	EA	5,470.00	16,410
Fiber optic w/PVC	1,000	LF	5.88	5,880
Pole foundation	3	EA	1,326.00	3,978
Electrical Manhole	2	EA	8,500.00	17,000
OH&P - 10%	1	LS	6,972.38	6,972
DJE	1	LS	20,000.00	20,000
Site Lighting:				
Lighting Fixtures:				
SL1 - 20' pole	37	EA	2,676.00	99,012
SL3 - poulsen bollard	9	EA	1,812.00	16,308
SL4 - egress perimeter lgt	21	EA	616.00	12,936
SL5 - in ground bega	16	EA	791.00	12,656
SL6 - bega flood w/remote driver	0	EA	0.00	0
SL10 - mini flood	0	EA	0.00	0
SL1A - 20' pole	4	EA	2,676.00	10,704
SL3 - wall mtd area lt - MV	4	EA	544.00	2,176
HH 12x12x12"d in gr p.box	3	EA	638.00	1,914
PB 17"x30"x12"d	12	EA	648.00	7,776
PB-24"x36"x24"d w/divider	2	EA	788.00	1,576
EV charging station - level 2	3	EA	3,754.00	11,262
J 8x8x4 inter j-box	3	EA	74.00	222
T/C 7 dy w/batt pack	1	EA	666.00	666
Pipe into & wire to exist pnl	1	EA	144.00	144
Demo exist pole w/fixt	4	EA	576.00	2,304
Penetrate m bay gym	1	EA	338.00	338
Relocated emer call box	2	EA	926.00	1,852
Call box base setup	2	EA	241.00	482
MC-12/2 w/G-fished	540	EA	1.99	1,077
PVC-1"C-3#8	9,320	EA	3.99	37,187
Pole base anchor bolts	48	EA	54.00	2,592
Pole base grounding	48	EA	162.00	7,776
Pole base sleeves & 90 deg	48	EA	137.00	6,576
Bollard base setups	42	EA	122.00	5,124
In ground hsg setups	16	EA	112.00	1,792
PVC-2 1/2"C-w/PS	1,500	EA	3.33	4,989
PVC-2"C-w/PS	620	EA	2.77	1,717
WP pedestal mtd Wayne Tyler CB box	5	EA	1,926.00	9,630

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Site - 60% Deducts:				
SL5 - Bega - in ground - delete	-11	EA	791.00	-8,701
SL4 - ext. pak - delete	-6	EA	616.00	-3,696
J WP - wall back box -WP- delete	-6	EA	43.00	-258
SL3 - poulson (bollard ) - delete	-18	EA	1,812.00	-32,616
PVC-1"C-3#8 - delete	-1,080	EA	3.99	-4,309
Bollard base setups - delete	-18	EA	122.00	-2,196
SL10 - in grade tree ltg - add	12	EA	816.00	9,792
Exist. ltg pole to demo - delete	-4	EA	576.00	-2,304
SL1 - 20' pole - delete	-10	EA	2,676.00	-26,760
SL1A - 20' pole - delete	-4	EA	2,676.00	-10,704
SL3 - wall mtd area lt- delete	-4	EA	616.00	-2,464
MC-12/2 - fished - delete	-540	EA	1.99	-1,077
8"x8"x4" interior j.box - delete	-3	EA	74.00	-222
T/C - 7 day w/batt pak - delete	-1	EA	666.00	-666
Penetrate M bay gym - delete	-1	EA	338.00	-338
PVC-1"C-3#8 - delete	-1,400	EA	3.99	-5,586
Pole base anchor bolts - delete	-14	EA	54.00	-756
Pole base grounding - delete	-14	EA	162.00	-2,268
Pole base sleeves & 90 degs - delete	-14	EA	137.00	-1,918
Site - 90% CD Adders/Deducts:				
Early Site Plan - Phase 1 Dwg				
E-PH-1 back in		w package #1		
HH handhole for P.V. sys	3	EA	591.00	1,773
PVC-4"C w/p.s	600	EA	4.58	2,748
PVC-2"C w/p.s	400	EA	2.14	856
PVC-2 1/2"C w/p.s	760	EA	3.16	2,402
OH&P - 10%	1	LS	26,078.80	26,079
				-----
				5,947,549

DIVISION 31 - EARTHWORK

310000 EARTHWORK

Site Earthwork:

12" Soil @ plant bed ( 8,122 sf)	301	CY	62.00	18,662
3" Planting bed mulch	76	CY	60.00	4,560
6" Loam - Lawn ( 288,987 sf)	5,351	CY	55.00	294,305
8" Loam - Athletic Field ( 260,744 sf)	6,431	CY	55.00	353,705
Credit to amend existing soil	-5,900	CY	35.00	-206,500



DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

-----  
464,732

## 311000 SITE PREPARATION &amp; CLEARING

-----  
0

## DIVISION 32 - EXTERIOR IMPROVEMENTS

## 321000 PAVEMENT, CURBING &amp; EDGING

## Pedestrian Paving:

## Site Pavement:

HC tactile paver	12	EA	365.00	4,380
------------------	----	----	--------	-------

-----  
4,380

## 323100 SITE IMPROVEMENTS

## Basketball Court:

Bit pavement	1,750	SF	3.00	5,250
--------------	-------	----	------	-------

Color seal coat	1,750	SF	6.00	10,500
-----------------	-------	----	------	--------

8" Gravel	44	CY	38.00	1,672
-----------	----	----	-------	-------

## Site Development:

## Site Improvements:

Gateway and Bandstand	carried w/ building cost			
-----------------------	--------------------------	--	--	--

## Amphitheater Seating:

Amphitheater earthwork	1	LS	15,000.00	15,000
------------------------	---	----	-----------	--------

## Site Benches:

Precast bench - wood top	20	LF	550.00	11,000
--------------------------	----	----	--------	--------

Bike loop	20	EA	675.00	13,500
-----------	----	----	--------	--------

8" Gravel Base	11	CY	45.00	495
----------------	----	----	-------	-----

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Versa loc Block - avg 10' high	3,200	SF	48.00	153,600
Filter Fabric	8,750	SF	1.10	9,625
Allowance:				
Trash/recycle receptacle	10	EA	2,000.00	20,000
Entry sign	1	LS	30,000.00	30,000
Electronic school zone signals		NIC		
Flag pole w/base	1	EA	7,200.00	7,200
Parking/traffic signage (C-7-5)	27	EA	450.00	12,150
*site bollard carried with misc metals				
				-----
				289,992

## 328000 IRRIGATION

Irrigate sod	41,496	SF	2.00	82,992
Irrigation System- Repair/Replace	82,800	SF	1.00	82,800
				-----
				165,792

## 329000 LANDSCAPING

## Plantings:

## Trees:

## Sheet L2.0:

AC Shadblow Serviceberry (2.5-3" cal)	1	EA	775.00	775
AL Allegheny Serviceberry (2.5-3" cal)	12	EA	775.00	9,300
CK American Yellowwood (3-3.5" cal)	17	EA	900.00	15,300
FG American Beech (3-3.5" cal)	11	EA	900.00	9,900
NS Black Tupelo (3-3.5" cal)	8	EA	900.00	7,200
OA Sourwood (2.5-3" cal)	3	EA	775.00	2,325
PA London Plane Tree (3-3.5" cal)	24	EA	900.00	21,600
QP Pin Oak (3-3.5" cal)	7	EA	900.00	6,300
QR Red Oak (3-3.5" cal)	7	EA	900.00	6,300

## Sheet L2.1:

AR Red Maple (3-3.5" cal)	6	EA	900.00	5,400
CK American Yellowwood (3-3.5" cal)	7	EA	900.00	6,300
LT Tulip Tree (3-3.5" cal)	8	EA	900.00	7,200
NS Black Tupelo (3-3.5" cal)	7	EA	900.00	6,300

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
<b>Shrubs:</b>				
CA Sweet Pepperbush (3.5-4' ht)	28	EA	215.00	6,020
HQ Oak Leaf Hydrangea (3-3.5' ht)	49	EA	200.00	9,800
HV Witch Hazel (7-8' B&B)	3	EA	450.00	1,350
IG Inkberry (4-4.5' ht)	33	EA	265.00	8,745
IV Winterberry (2.2.5' ht)	61	EA	185.00	11,285
JH Creeping Juniper (15-24" spd)	68	EA	50.00	3,400
JV Easter Red Cedar (7-8' ht)	26	EA	450.00	11,700
MG Sweetgale (3.5-4' ht)	38	EA	215.00	8,170
PF Pink Beauty Potentilla (24" spd)	22	EA	65.00	1,430
RA Grow Low Sumac (2-2.5' spd)	47	EA	80.00	3,760
RT Staghorn Sumac (3 gal)	13	EA	135.00	1,755
VA Lowbush Blueberry (15-24" spd)	53	EA	50.00	2,650
VD Arrowwood (4-4.5' ht)	31	EA	265.00	8,215
VT Dwarf Cranberry Bush (3-3.5' ht)	12	EA	265.00	3,180
<b>Groundcover:</b>				
Sheet L2.0:				
CP Sweet Fern (1 gal)	1,436	EA	36.00	51,696
Sheet L2.1:				
CP Sweet Fern (1 gal)	530	EA	36.00	19,080
Plant Maintance	1	LS	10,000.00	10,000
<b>Sod:</b>				
Sod at Amphitheater	25,334	SF	1.10	27,867
<b>Rake , Seed, Fertilize New Lawns:</b>				
Lawn	119,912	SF	0.26	31,177
Meadow Mix	143,741	SF	0.28	40,247
Pea Stone drip edge	996	SF	12.00	11,952
Sports field	260,744	SF	0.30	78,223
Stone Dust - mech yard	500	SF	4.00	2,000
				----- 457,903

DIVISION 33 - UTILITIES

330000 UTILITIES

Fuel Distribution:

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
BASE COST ESTIMATE				
Electrical Utilities:				
Generator Pad	200	SF	25.00	5,000
Transformer pad	200	SF	25.00	5,000
Site Lighting:				
Site light trenching	10,500	LF	18.50	194,250
Trench, Backfill and Concrete:				
Electric Ductbank	1,150	LF	76.00	87,400
				-----
				291,650

PROJECT: Fuller Middle School  
 LOCATION: Framingham, MA  
 CLIENT: SMMA Architects  
 DATE: 26-Sep-19

NO. OF SQ. FT.: 136,600  
 COST PER SQ. FT.: 63.76

No.: 18020

**EARLY SITE PACKAGE #1**

SUMMARY	DIVISION TOTAL	PERCENT OF PROJECT	COST PER SF
<b>DIVISION 02 - EXISTING CONDITIONS</b>			
<b>DIVISION 31 - EARTHWORK</b>			
310000 EARTHWORK	5,387,568	62%	39.44
311000 SITE CLEARING	756,447	9%	5.54
<b>DIVISION 32 - EXTERIOR IMPROVEMENTS</b>			
321000 BASES, BALLASTS AND PAVING	64,350	1%	0.47
323000 SITE IMPROVEMENTS	1,486,262	17%	10.88
<b>DIVISION 33 - UTILITIES</b>			
330000 UTILITIES	1,015,510	12%	7.43
	-----		
DIRECT COST	8,710,136	100%	63.76

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
DIVISION 31 - EARTHWORK				
310000 EARTHWORK				
Foundations:				
Ground Improvements:				
Geopiers	74,000	FTP	10.50	777,000
Rigid Inclusion towards RB - 1 and RB -	1	LS	50,000.00	50,000
Foundation Earthwork:				
Surcharge Bldg Footprint	1	LS	300,000.00	300,000
Excavate Footings	3,000	CY	15.00	45,000
Backfill Foundation	1,400	CY	15.00	21,000
Slab Fill	2,000	CY	28.00	56,000
Dewatering	1	LS	25,000.00	25,000
Foundation drain (1/S300)	120	LF	38.00	4,560
Slab on Grade:				
12" Gravel base - SOG	2,372	CY	34.00	80,648
Site Earthwork:				
Phase 1/2:				
Site Cut	2,847	CY	12.00	34,164
Stockpile cut	2,847	CY	10.00	28,470
Site Fill - supply	15,810	CY	18.00	284,580
Phase 3:				
Site Cut	21,721	CY	10.25	222,640
Site Fill - reuse mat'l	21,721	CY	11.00	238,931
Site Fill - supply	18,000	CY	18.00	324,000
Site Rough Grading	101,781	SY	2.30	234,096
Layout, Mobilization, Supervision	1	LS	250,000.00	250,000
Temp Drainage				
Dust Control	1	LS	10,000.00	10,000
Street Sweeping	1	LS	10,000.00	10,000
Surcharge Ampitheater	1	LS	200,000.00	200,000
Soils	1	LS	2,118,778.00	2,118,778
Soil Management:				
Dispose of contaminated soil - less than F	2,550	TONS	14.00	35,700
Dispose of contaminated soil - unlined	850	TONS	40.00	34,000
Add New Site Fill	4,000	CY	0.75	3,000

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
				----- 5,387,568
311000 SITE CLEARING				
Site Preparation:				
Phase One:				
Jersey barriers	1,533	LF	75.00	114,975
Temp pavement	98,683	SF	1.50	148,025
Phase 1 - Grading & Drainage				
Erosion control	701	LF	7.50	5,258
Site prep	101,316	SF	0.20	20,263
Phase 2 - Grading & Drainage:				
Temp erosion basin Eroison control	307	LF	15.00	4,605
Construction entrance	1	EA	7,500.00	7,500
Construction fence	3,200	LF	12.00	38,400
Erosion control	2,500	LF	6.00	15,000
Drain inlet protection	25	EA	50.00	1,250
Erosion control maintenance	1	LS	15,000.00	15,000
Strip & stack top soil - 6"	5,900	CY	9.25	54,575
Selective Clear and Grub	1	LS	20,000.00	20,000
Saw cut walk	25	LF	5.00	125
Saw cut drive	25	LF	5.00	125
Site - Remove Existing:				
Cut and Cap	1	LS	5,000.00	5,000
Sanitary and Drain pipe	1,435	LF	35.00	50,225
Water Line	900	LF	31.00	27,900
Utility structures	10	EA	425.00	4,250
Wood guardrail	300	LF	15.00	4,500
Bit walk	201,786	SF	0.85	171,518
Conc. walk	14,967	SF	1.00	14,967
Bit Walkway	8,874	SF	0.90	7,987
Misc. site demolition	1	LS	25,000.00	25,000
				----- 756,447

## DIVISION 32 - EXTERIOR IMPROVEMENTS

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
<b>321000 BASES, BALLASTS AND PAVING</b>				
Pedestrian Paving:				
Bit sidewalk	1,862	SY	27.00	50,274
8" Gravel Base	414	CY	34.00	14,076
				-----
				64,350
<b>323000 SITE IMPROVEMENTS</b>				
Roadways:				
Phase 1:				
Bit pavement - parking and drive	8,147	SY	27.50	224,043
Raised Road Pavement w/ stamped finish	10,500	SF	15.00	157,500
12" Gravel base	2,715	SY	32.00	86,880
PCC- RAD	320	LF	32.00	10,240
PCC - straight	1,130	LF	26.00	29,380
SGC - straight	189	LF	39.50	7,466
VGC - RAD	79	LF	46.00	3,634
VGC - straight	365	LF	42.00	15,330
Line Painting	1	LS	5,000.00	5,000
Phase 2:				
Bit pavement	182	SF	30.00	5,460
12" Gravel base	61	SY	35.00	2,135
Base:				
Bit firelane pavement	1,685	SY	27.00	45,495
Bit pavement	14,204	SY	27.00	383,508
12" Gravel base	5,296	CY	32.00	169,472
VGC radial	1,646	LF	46.00	75,716
VGC straight	2,297	LF	42.00	96,474
Line Painting	1	LS	7,500.00	7,500
Street Patch at New Curb	1,154	LF	50.00	57,700
Pavement patch @ utilities	1	LS	15,000.00	15,000
Site Development:				
Manual vehicle gate 20'w	1	EA	4,800.00	4,800
Vehicular guardrail - wood	952	LF	65.00	61,880
Utility Bollard	13	EA	1,050.00	13,650
Basketball hoop	2	EA	4,000.00	8,000



DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
				-----
				1,486,262

DIVISION 33 - UTILITIES

330000 UTILITIES

Water:

Phase 1 - Grading & Drainage

2" Water	21	LF	70.00	1,470
6" Water	168	LF	92.00	15,456
CTE water	5	EA	3,000.00	15,000
Fire hydrant	3	EA	2,250.00	6,750
6" Gate Valve	4	EA	1,400.00	5,600
Misc Valves	4	EA	1,400.00	5,600

Phase 2 - Grading & Drainage:

2" Water line	147	LF	62.50	9,188
6" Water line	717	LF	88.00	63,096
Fire hydrant	1	EA	2,250.00	2,250
6" Gate Valve	1	EA	1,400.00	1,400
Misc Valves	2	EA	1,400.00	2,800
Site Connection	1	LOC	7,500.00	7,500

Sanitary Sewer:

Phase 2 - Grading & Drainage:

8" PVC san	606	LF	80.00	48,480
Sewer manhole	3	EA	4,100.00	12,300
EGI-1	1	EA	12,500.00	12,500
Acid Waste tank	1	LS	15,000.00	15,000
Exist. sanitary manhole - site conn.	1	EA	7,500.00	7,500

Storm Sewer:

Phase 1 - Grading & Drainage

12" HDPE	33	LF	76.00	2,508
18" HDPE	531	LF	94.00	49,914
24" HDPE	63	LF	145.00	9,135
30" HDPE	10	LF	210.00	2,100
6" PVC	45	LF	62.50	2,813
Catch Basin	6	EA	2,100.00	12,600
CTE drainage	1	EA	4,000.00	4,000
Cut & patch existing parking lot	431	LF	50.00	21,550
Drain man hole	3	EA	4,100.00	12,300
Head wall	1	LS	6,500.00	6,500
STC 6000	1	EA	60,000.00	60,000

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
STC 3600	1	EA	30,000.00	30,000
STC 450i	2	EA	11,500.00	23,000
Phase 2 - Grading & Drainage:				
12" HDPE	154	LF	76.00	11,704
Catch Basin	2	EA	4,100.00	8,200
Temp drain line	282	LF	100.00	28,200
Phase 3 ( per revised plane 4 /17/19):				
12" HDPE	262	LF	76.00	19,912
15" HDPE	665	LF	84.00	55,860
18" HDPE	152	LF	94.00	14,288
24" HDPE	305	LF	145.00	44,225
30" HDPE	537	LF	182.00	97,734
Catch Basin	10	EA	4,100.00	41,000
CB Conversion	1	EA	1,200.00	1,200
Drain Manhole	9	EA	4,100.00	36,900
Head Wall	1	EA	7,500.00	7,500
Outfall wier construction	1	LS	5,000.00	5,000
Infiltration field	1,292	SF	25.00	32,300
*EXCLUDES WORK SOUTH OF FLAGG DRIVE				
Fuel Distribution:				
Phase 2 - Grading & Drainage:				
Gas trench	311	LF	48.00	14,928
Gas Pipe		By utility		
Service Meter Pad	1	EA	2,500.00	2,500
Electrical Distribution:				
Light Pole base - 12' Precast	37	EA	1,350.00	49,950
Temporary Electrical Service	1	LS	75,800.00	75,800
				-----
				1,015,510

PROJECT: Fuller Middle School  
 LOCATION: Framingham, MA  
 CLIENT: SMMA Architects  
 DATE: 26-Sep-19

NO. OF SQ. FT.: 136,600  
 COST PER SQ. FT.: 53.73

No.: 18020

**EARLY SITE PACKAGE #2**

SUMMARY	DIVISION TOTAL	PERCENT OF PROJECT	COST PER SF
<b>DIVISION 03 - CONCRETE</b>			
033000 CAST IN PLACE CONCRETE	#####	46%	24.48
<b>DIVISION 05 - METALS</b>			
051000 STRUCTURAL METAL FRAMING	#####	54%	29.06
<b>DIVISION 07 - THERMAL &amp; MOISTURE PROTECTION</b>			
071000 DAMPPROOFING & WATERPROOFING	26,170	0%	0.19
	-----		
DIRECT COST	#####	100%	53.73

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
DIVISION 03 - CONCRETE				
033000 CAST IN PLACE CONCRETE				
Foundations:				
Column Footing - (F 3 thru F 12 @ 135 ea):				
4000 psi, NW, (incl. placement)	454	CY	205.00	93,070
Formwork	6,300	SFCA	9.50	59,850
Rebar	45,400	LBS	1.22	55,388
<i>*unit cost \$458.83</i>				
Perim Wall Footing 1' x 3/4' ( 1,578 LF ):				
4000 psi, NW, (incl. placement)	180	CY	208.00	37,440
Formwork	3,200	SFCA	8.10	25,920
Rebar	9,000	LBS	1.22	10,980
<i>*unit cost \$413.00</i>				
Foundation Wall 16" thick x height varies ( 1,962 lf):				
4000 psi, NW, (incl. placement)	442	CY	215.00	95,030
Formwork - 4' or less	8,808	SFCA	14.00	123,312
Formwork - 4' Aud/Gym	4,960	SFCA	14.00	69,440
Formwork - 15'	3,120	SFCA	20.00	62,400
Brick Shelf	1,962	LF	14.50	28,449
Reinforcing steel	66,300	LBS	1.22	80,886
<i>*unit cost \$1,039.63</i>				
Auditorium Interior Foundations - Stage front:				
Wall footing	32	CY	350.00	11,200
12" Knee wall	27	CY	850.00	22,950
Loading Dock:				
Wall footing		inc. above		
Foundation wall	36	CY	975.00	35,100
Misc. Foundations:				
CMU Footing - aud/gym	28	CY	385.00	10,780
#1 - #5 Grade Beam	42	CY	675.00	28,350
12" Elevator mat	6	CY	650.00	3,900
Elev sump pit	1	EA	900.00	900
12" Elevator pit wall -5'D	7	CY	900.00	6,300
Interior Mechanical pads - allow	1	LS	5,000.00	5,000
Concrete Pilaster	28	CY	1,100.00	30,800
Setting Anchor Bolts and Grout	132	EA	310.00	40,920
<i>*Includes Section 031000 - 033500</i>				

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
<b>Band Shell Foundation:</b>				
Wall Footing 1' x 5'	6	CY	800.00	4,800
16" Radial Found wall	9	CY	1,300.00	11,700
<b>Slab on Grade:</b>				
5" Slab on Grade - Typ:				
3,500 psi, NW, (incl. placement)	988	CY	228.00	225,264
6x6 W2.9 X W2.9	64,048	SF	1.80	115,286
Control Joint	4,300	LF	2.60	11,180
15 Mil poly vapor barrier (2/A100)		w/072600		
Trowel Finish	64,048	SF	2.10	134,501
*unit cost \$7.59				
<b>Misc. Slabs and Concrete:</b>				
Premium Stepped/sloped slab	3,460	SF	8.00	27,680
Ext. 5" Loading Dock	1,125	SF	9.00	10,125
Ext. Loading Dock Stair Structure	1	FLT	7,500.00	7,500
Gyp cement underlayment(spec 035413)		w/C3020		
<b>Floor Construction:</b>				
3 1/4" LW Deck fill - typ floor	68,431	SF	9.80	670,624
3 1/4" LW Deck fill - stage plenum (7/A)	570	SF	10.00	5,700
<b>Roof Construction:</b>				
3 1/4" LW Deck fill :				
R 6.25 3" x 18 Ga. Comp Deck- Typ	3,641	SF	8.70	31,677
3 1/4" LW Deck fill :				
R 5.5 3" x 18 Ga. Comp Deck- Typ	29,586	SF	8.70	257,398
<b>Roof top 1'W x 2'H Concrete Curb @:</b>				
Mech RTU unit	618	LF	92.00	56,856
Misc Equip curbs	1	LS	9,998.00	9,998
<b>Stair Construction:</b>				
Conc stair pan fill :				
Metal pan stair treads and risers	1,278	LFR	22.00	28,116
Metal pan landing	472	SF	18.00	8,496
Aud cast stair @ grade (4 ft)	48	LFT	145.00	6,960
<b>Floor Finishes:</b>				
PC Power Troweled Concrete Floor Finish::				
Auditorium	3,788	SF	5.00	18,940
Makerspace ( 1 EA)	1,972	SF	5.00	9,860

SITWORK:

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Pedestrian Paving:				
Site Pavement:				
Entry Stoop	200	SF	22.00	4,400
Concrete sidewalk	21,127	SF	11.00	232,397
Plaza Paving	1,760	SF	20.00	35,200
Site Development:				
Pavilion Amphitheater Step:				
Amphitheater stair foundation	5	CY	1,100.00	5,500
Amphitheater stair tread (radial)	385	LF	190.00	73,150
Ramp and Planter Walls:				
Wall Footing	25	CY	475.00	11,875
12" Foundation Wall	82	CY	1,600.00	131,200
Ramp Slab	510	SF	15.00	7,650
Sandblast finish	1	LS	10,000.00	10,000
Site Stair:				
Site stair foundation	38	CY	1,100.00	41,800
Site stair tread	251	LF	110.00	27,610
Main stair tread	193	LF	110.00	21,230
Bike Conc Pad	426	SF	25.93	11,046
Foundations:				
2" Rigid found. insul w/ 1/2" drain bed -	1,360	SF	6.00	8,160
2" Rigid found. insul - frost wall	6,884	SF	3.20	22,029
Slab on Grade:				
Stegro vapor barrier (15 mil)	64,048	SF	1.71	109,522
				-----
				3,343,795

DIVISION 05 - METALS

051000 STRUCTURAL METAL FRAMING

Floor Construction:				
Wide Flange - beam	210.52	TONS	3,800.00	799,976
HSS Beam	36.2	TONS	3,900.00	141,180
HSS Brace Frame	46.7	TONS	4,200.00	196,140
Wide Flange- Column	10.7	TONS	3,550.00	37,985
HSS Column	88.3	TONS	3,900.00	344,370
Bolted Ledger Angle	1.5	TONS	3,550.00	5,325
Relieving angle (S500)	1,043	LF	185.00	192,955

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
Wide flange - stage front	0.5	TON	3,700.00	1,850
4" x 4" x 1/8" Bolted angle at found - all	250	LF	65.00	16,250
Hilti bolt conn	74	EA	128.00	9,472
Moment Connection	194	EA	1,300.00	252,200
Shear stud ( 10/100sf)	16,200	EA	5.25	85,050
Atrium coped Beam Detailing #4/S500	1	LS	49,402.00	49,402
Roof Construction:				
Wide Flange - beam	200.8	TONS	3,800.00	763,040
HSS Beam	61.0	TONS	4,100.00	250,100
DLH Bar Joist	47.84	TONS	3,657.00	174,951
HD Galv pipe/ HSS Roof Screen	4.70	TONS	5,200.00	24,440
HD Galv HSS Entrance Canopy	2.60	TONS	6,000.00	15,600
HSS Brace Frame	w/ floor construction			
Wide Flange- Column	w/ floor construction			
HSS Column	w/ floor construction			
Bolted Ledger Angle	3	TONS	3,550.00	10,650
Hilti bolt conn	140	EA	128.00	17,920
Moment connection	38	EA	750.00	28,500
Galv Roof Dunnage:				
CH/WF	9	TONS	4,500.00	40,500
HSS post	1	TONS	4,500.00	4,140
Angle brace	500	LBS	4.00	2,000
Site Development:				
HD Color Galv HSS/ C Channel Band Sh	3.40	TONS	10,000.00	34,000
Floor Construction:				
3" x 18 Ga. Comp Deck- Typ	68,431	SF	3.40	232,665
3" x 18 Ga. Comp Deck- stage	570	SF	3.60	2,052
Roof Construction:				
R 1.5 1 1/2" x 20Ga Roof deck	765	SF	2.80	2,142
R3 3" X 18 Ga. Typical Roof Deck	13,702	SF	3.00	41,106
R 6.25 3" x 18 Ga. Comp Deck- Typ	3,641	SF	3.18	11,578
R 5.5 3" x 18 Ga. Comp Deck- Typ	29,586	SF	3.18	94,083
R 1.5A 1 1/2" Acoustical Roof Deck - gy	8,835	SF	7.25	64,054
R3C 3" Roof Deck - aud (acoustical dele	7,563	SF	3.15	23,823
				-----
				3,969,500

DESCRIPTION	QUANTITY	UNIT	UNIT COST	TOTAL
-------------	----------	------	-----------	-------

DIVISION 07 - THERMAL & MOISTURE PROTECTION

071000 DAMPPROOFING & WATERPROOFING

Bid Page #2 Foundation Waterproofing	1	LS	26,170.00	26,170
				----- 26,170