

Addendum No. 1

April 25, 2016 Replacement of Existing HVAC Units at Crescenta Valley High School Bid Number 125-15/16

This addendum supercedes, supplements and has precedence over all portions of the bidding documents with which it differs. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

Changes to Bid Specifications:

All Installers of I-vue system must be Sigler – Carrier certified installers.

In Rooms 1108: add a return air with a grill with a filter for the return air on side wall of the room and add a 2 inch filter rack on the door louver for filter. Place new sheet metal ducting in room utilizing existing opening with a larger size registers

In Rooms 1208: add a return air with a grill with a filter for the return air on side wall of the room and add a 2 inch filter rack on the door louver for filter (per Unit total of 2). Place new sheet metal ducting in room utilizing existing opening with a larger size registers

In Rooms 1306: add 2 return air with a grill with a filter for the return air on side wall of the room and add a 2 inch filter rack on the door louver for filter. Place 2 sets of new sheet metal ducting in room utilizing existing opening with a larger size registers and opening new registers.

Please see below for the model and serial numbers for the units to be installed at CVHS.

| ROOM NUMBER | INDOOR COIL MODEL | NUMBER OF INDOOR UNITS | OUTDOOR CONDNSOR MODEL | NUMBER OF OUTDOOR UNITS |
|----------------|-------------------------|------------------------------|---------------------------|-------------------------------|
| 1108 | FB4CNF060000 | 1 | 25HCE560A003 | 1 |
| | 208/230v (single phase) | | 208/230v (single phase) | |

CVHS HVAC PROJECT MODEL NUMBERS

| | Heat Pump | | Heat Pump | |
|------|-------------------------|---|-------------------------|---|
| 1208 | FB4CNF060000 | 2 | 25HCE560A003 | 2 |
| | 208/230v (single phase) | | 208/230v (single phase) | |
| | Heat Pump | | Heat Pump | |
| 1306 | FB4CNF060000 | 2 | 25HCE560A003 | 2 |
| | 208/230v (single phase) | | 208/230v (single phase) | |
| | Heat Pump | | Heat Pump | |
| 8201 | MMC-AP0241H2UL | 4 | MMY-MAP0964HT9UL | 1 |
| | 208/230v (single phase) | | 208/230v (3 phase) | |
| | Heat Pump | | Heat Pump | |
| 8202 | MMC-AP0361H2UL | 5 | MMY-MAP0964HT9UL | 2 |
| | 208/230v (single phase) | | 208/230v (3 phase) | |
| | Heat Pump | | Heat Pump | |

For Rooms 1108, 1208, 1306-Please reference the bottom Pictures as to how the district would like the units mounted in the rooms where the fan coils should be installed with stand and a filter Bay to accept a 4 inch filter under the unit. Mount must be secured to the floor with proper hardware.



Fan coil stand with a 4 inch filter bay With filter showing



Fan coil stand with a 4 inch filter bay With filter closed

End of Addendum No. 1