



Addendum No. 1

March 6, 2017

Roofing Project at Crescenta Valley High School

Bid Number 138-16/17

This addendum supercedes, supplements and has precedence over all portions of the bidding documents with which it differs. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

Changes to Scope of Work, Building AB (2000) Lower Roof Section:

Additional Scope of Work:

- A. Contractor to install a new drain and all related piping to the south side of the roof section, area indicated on Job Walk, and extended to the canopy below. Contractor will need to core two holes through the concrete deck and concrete wall to install the drain and related pipes.
- B. Contractor to seal base of new blower units and unistrut on metal pans. Contractor shall unbolt the units and unistrut and apply Solargard Seam Sealer to base and reinstall all bolts. The Contractor shall seal the supports and unistrut with a three course of Solargard Seam Sealer and Membrane.
- C. Contractor shall seal the Hypalon Flashing with Solargard Seam Sealer and Membrane as necessary.
- D. All vertical surfaces shall have SP Primer and ICE Coating.

End of Addendum No. 1