

EXHIBIT "A" ("SCOPE OF WORK")

1. Remove existing instrument cabinets and keep safe for re-installation once raised floor is removed.
2. Remove four (4) roll down doors and associated hardware and dispose of offsite.
3. Remove three (3) existing partition walls and dispose of offsite.
4. Remove existing raised floor and dispose of offsite.
5. Re install existing instrument cabinets at finished floor.
6. Install adjustable shelving standards, shelving brackets, and shelving in identified existing cabinets.
7. Manufacture and install doors for existing cabinets.
8. Manufacture and install cabinets, with doors, above existing instrument cabinets. Install adjustable shelving standards, shelving brackets, and one shelf per cabinet. Cabinet sizes to match depth and width of existing cabinets that they are above with height to be determined by field measurement after existing cabinets are placed on finished floor.
9. Patch and paint walls as necessary to repair any missing or damaged areas caused by the removal and re-installation of the cabinets.
10. Provide and install the necessary trim panels to tie the cabinets in with the existing walls and ceiling.