

F. Rosemont Middle School

- 5. Work must be done during hours with no students occupying the school.
- 6. Must coordinate work hours with project manager to assure school is aware of the work taking place

INTERIOR LIGHTING

- 7. Please remove all T-8 and T-12 bulbs with Ballasts and install all new LED bulbs with provide fluorescent sockets per instructions included per bulb
- 8. Contractor must dispose of all old bulbs and electronic ballasts in proper manner (Recycle) and provide documentation of disposal to the district
- 9. All PCB Ballasts must be properly wrapped turned in to district for proper disposal by the district
- 10. All bulbs will be provided by District
- 11. All of other materials needed must be provided by contractor.
- 12. All area must be cleaned and all furniture returned to its original location for class

Fixture	<u>Rosemont Interior Count</u>		Total Tubes	Total Fixtures
	Type			
8 foot fixtures	Replace existing fixtures with district provided 1x8x2 light fixtures		184	92
			184	92