

SITE IMPROVEMENT PROJECTS

RD White

➤ **Front of School**

Replace approximately 2,300 square foot of dirt with Concrete:

- Protect existing Irrigation Sprinkler System.
- Remove dirt, grind Tree Roots as required and dispose.
- Install 4" Sand, 4" Concrete (min. 3000 psi with 6x6x10x10 wire mesh).
- Install expansion joints at maximum 18' o.c.
- Install control joints at maximum 6' o.c.

➤ **Playground**

- Install additional Plants to match existing in north east planter up to existing curbs;
- Remove dirt, grade and install Turf, as noted
- Install 4" thick concrete in fill curb on the west side of the Playground along side walk/ wrought iron fence approximately 350'.
- Remove existing Turf and pavers at planter areas on the west side of the Playground, grade and install new Turf.
- Remove temporary power posts.

District has right of Salvage.