

PAVING AND STRIPING PROJECT

R.D. White

Per attached Plan provided the attached scope of work:

- Demolish, remove Concrete foundations, rails, ramps, etc. where Relocatable Buildings were removed
- Install compacted Base and Asphalt
- Remove Temporary Power Poles, approximately ten (10).
- Remove and dispose of two (2) Electrical Switchgears, with concrete base.
- Clean and prepare existing Asphalt area for striping.
- Stripe Playground per Plans.
- Demo and install Asphalt to Fire Lane as specified on Plans.
- Provide Irrigation Sleeve under Fire Lane to future Turf area for future Irrigation.
- Demo grade and put in Curb for future Turf area, leave grade 2” below top of Curb.
- Provide missing Signage.
- Rather than “Plexipave” specified per Plans, provide and apply GAF Street Bond 150 Coating.
- Repair Curb 2-3’ in two places along west side (Geneva).
- Clean and dispose of all debris

Additive Alternate

Remove soil and debris on the west side at WI Fence and repair as needed with 2” minimum Asphalt.