



Bid No. 2020-21-02
MILL VALLEY SHADE STRUCTURE PROJECT
Amendment 1

- 1. Does the district want M-C to include painting of RWL's in our scope or leave that to the General Contractor?**

Answer: Please include painting RWL's in the M-C scope of work.

- 2. Should footing sleeves be included for Strawberry given the high water table and proximity of the wetlands?**

Answer: Yes, include footing sleeves for Strawberry Point Elementary site.

- 3. What is the clear height of the walkway covering access to the courtyard where the work is to be performed?**

Answer: As-built drawings for the Strawberry site are included in the [link](#), named - Strawberry Site As-Builts.

- 4. Will locating be by the District, GC, or M-C?**

Answer: M-C, any ground marking needs to be with temporary chalk paint.

- 5. M-C will be providing a Galvanized column due to the proximity to the ocean. Is this acceptable?**

Answer: Galvanized columns are acceptable and provide paint per specifications.

- 6. Will the owner sign the drilling release/notice to proceed after location?**

Answer: This will be reviewed by the District and discussed with the vendor prior to construction.

- 7. Can you please share soil reports for each site to understand the soil conditions?**

Answer: Yes, they are found on this [link](#).

- 8. Are there any changes in the scope of the project?**

Addendum 1

Yes, a breakdown can be found at this [link](#) HY_5 11 21_210511 Addendum 1 MVSD in addition to the project drawings.

9. Is there an opportunity to submit additional questions?

Yes, please submit questions by May 14, 2021, at 1:00 pm to jarroyo@mvschools.org.