

Addendum for the MILL VALLEY MIDDLE SCHOOL roof restoration for Mill Valley School District

General

Bidders shall acknowledge receipt of this addendum on the bid form or as indicated. Failure to do so may render bidders non responsive.

The following changes, additions or deletions shall be made part to the following documents as indicated and shall be part thereof as if originally specified and/or shown. All other conditions shall remain the same.

Mill Valley Middle School

- |            |  |
|------------|--|
| Item No. 1 | Reference: Flashing of drain<br>Scope: See specification: 075600 Section<br>Delete: 3.6 K Drains<br>Add: Remove [e] strainer and set aside for re-installation. Carefully Remove Clamping ring. Inspect bowl and connection and report all Defects.<br>Prime metal surfaces. Run base coat and Perma fab into bowl. Cut and Fit mat so it lays in tight, with no wrinkles or voids. Clean up clamping Ring and set in layer of TF tape. Insure clamping ring sandwiches System. Furnish and install [n] bolts and washers. Secure ring evenly.<br>Re –install strainer and secure. |
| Item No. 2 | Reference: Walkways<br>Scope: See specification: 075600 Section<br>Delete: Letter M completely<br>Add: N/A   |
| Item No. 3 | Reference: Coping plates<br>Scope: See specifications: 075600 Section<br>Delete: Letter O completely<br>Add: N/A   |
| Item No. 4 | Reference: Existing wood blocking – Wood blocking 4” x 4” and larger<br>Scope: See specifications 075600 Section 3.6<br>Add: Letter R. Remove duration application and re –install all [e] 4” x 4” and larger wood blocking after completion of application  |

- Item No. 5      Reference: Existing wood blocking- Wood blocking 2” x 4”  
Scope: See specifications 075600 Section 3.6  
Add: Letter S Furnish and install [n] 2” x 4” pressure treated lumber.
- Item No. 6      Reference: Existing Dura blocks  
Scope: See specifications 075600 Section 3.6  
Add: Letter T – Re use all [e] Dura Blocks and reinstall into original  
After application of fluid applied system
- Item No. 7      Reference: Termination of single ply @ baseflashings  
Scope: See specifications 075600 Section 3.6  
Add: Letter U – Furnish and install [n] single ply over lay @  
Baseflashings in designated locations. Furnish and install [n]  
Flat Aluminum pre slotted termination bar. Fasten twelve [12]  
O.C. with washered fasteners @ the bottom of the interior of the coping.  
Cover bar completely with [n] fluid applied system.
- Item No. 8      Reference: Detail @ end of expansion joints  
Scope: See Specifications 075600 Section 3.6  
Add: Letter V- At the end of the existing expansion joints, neatly trim  
Granulated cap sheet back a minimum of three [3] inches to expose  
end /underlayment. Clean and prime surfaces to include metal. Apply  
Base, reinforcement and top coat to provide a watertight seal at ends  
onto metal cap. Tie system onto metal at areas where they intersect.